# Materials
## in Design Engineering




PHOTOCOPY PROHIBITED

**Materials**
in Design Engineering

MID-NOVEMBER 1960

# MATERIALS SELECTOR ISSUE

This Materials Selector Issue of MATERIALS IN DESIGN ENGINEERING features the latest available data on engineering materials, forms, finishes, and joining and fastening methods. The issue consists of two major sections: a Data Section and a Directory Section. Each of these is subdivided to make it as useful as possible. Contents of the entire issue are listed on these two pages; in addition, a more detailed contents page appears at the beginning of most subsections. All subsections are described briefly on the facing page.

INDEXES, LITERATURE, ETC.

How to Use the Selector . . . 2
What the Data Mean . . . . . 2
Index to Data . . . . . 3
Index to Advertised Products 8
Index to Advertisers . . . . . 9
Sources of Data . . . . . 96
Inquiry Cards . . . . . 585-592
How to Use the Directory 504

**SUPPLIERS' LITERATURE**

Irons & Steels . . . . . 36
Nonferrous Metals . . . . . 98
Plastics & Rubber . . . . . 186
Other Nonmetallics . . . . . 282
Finishes & Coatings . . . . 328
Forms, Shapes & Composites . . . . . 364
Joining & Fastening . . . . 468

## DATA SECTION

The Data Section consists of eight parts. It contains extensive data on the properties of virtually all important engineering materials (including finishes and coatings), the forms in which they are available, and the methods by which they can be joined.

## DIRECTORY SECTION

The Directory Section, consisting of two parts, contains the names of the leading suppliers of engineering materials and their forms and shapes. A full explanation of the organization and use of the Directory is given on page 504.

PAGE TO USE THIS THUMB INDEX

PAGE

## Comparisons of Materials 11

Based on specific end service requirements

Tables comparing the important engineering materials with respect to a particular property (e.g., tensile strength). The major part of this section is a series of data sheets in which materials are ranked in descending order for various properties. The materials are ranked by the highest value of their **typical** properties, the lowest typical value also being given. In some cases the form, temper, heat treatment or other condition of the material is given, particularly where such conditions markedly affect the value. More details on materials and conditions can be found in the other data sections.

Comparisons of Materials

## Properties of Materials 37

Typical properties and uses of the important engineering materials. Most of the information is given in a standard tabular form, making comparison easy, and test conditions are summarized where known. A list of helpful suppliers' bulletins appears at the beginning of each section, and advertisements appear at the end of each section.


| | |
|---|---|
| IRONS AND STEELS | 37 |
| NONFERROUS METALS | 99 |
| PLASTICS AND RUBBER | 187 |
| OTHER NONMETALLICS | 283 |
| FINISHES AND COATINGS | 329 |


Irons & Steels

Nonferrous Metals

Plastics & Rubber

Other Nonmetallics

Finishes & Coatings

## Forms, Shapes & Composites 365

Data on the common forms (castings, moldings, etc.) of engineering materials and on composite materials (clad metals, laminates, etc.). Much of the information is in tabular form. A list of suppliers' bulletins appears at the beginning of the section, and advertisements of suppliers appear at the end.

Forms, Shapes & Composites

## Joining & Fastening of Materials 469

Data on the joining and fastening methods used for engineering materials. A list of helpful bulletins available from suppliers appears at the beginning of the section, and advertisements of suppliers appear at the end.

Joining & Fastening

## Suppliers of Materials 503

An alphabetical index to the important engineering materials and forms of materials, containing under each heading the names of the leading suppliers.

Suppliers of Materials

## Addresses of Suppliers 562

An alphabetical list of the names and addresses of the suppliers of engineering materials and forms mentioned in the Directory.

Addresses of Suppliers

# Materials
## in Design Engineering

**Application of metals, nonmetallics, forms, finishes**

VOL. 52, NO. 6 • MID-NOVEMBER, 1960



WILLIAM P. WINSOR, *Publisher*
H. R. CLAUSER, *Editor*
JOHN B. CAMPBELL, *Managing Editor*

WALTER LUBARS
*Editor, Materials Selector Issue*
ALICIA STRATTON, *Directory Section Editor*

ROBERT J. FABIAN, *Associate Editor*
DONALD PECKNER, *Associate Editor*
MALCOLM W. RILEY, *Associate Editor*
JOHN A. MOCK, *Assistant Editor*
ROBERT B. TRAVIS, *Assistant Editor*
HARRY KOKIS, *Editorial Production Assistant*
*Entire issue designed by* GIL MILLER



PUBLISHED BY
REINHOLD PUBLISHING CORP.
430 PARK AVE., NEW YORK 22, N. Y.



M. RANDOLPH LONG,
*Advertising Sales Manager*
JOHN Y. CUNNINGHAM,
*Research & Promotion Manager*
DAVID N. WHITCOMBE, *Circulation Manager*
SUE FELDMAN, *Subscription Manager*
JOHN A. KOVCHOK, *Production Manager*
WILLIAM SCOLLON,
*Advertising Production Manager*
E. M. WOLFE, *Manager, Reader Service*

RALPH REINHOLD, CHAIRMAN OF THE BOARD
PHILIP H. HUBBARD, PRESIDENT & TREASURER
E. A. STARKE, ASSISTANT TREASURER
F. P. PETERS, VICE PRESIDENT & SECRETARY
H. BURTON LOUIE, VICE PRESIDENT
HERALD LUE, VICE PRESIDENT
H. BRAD WILKIE, VICE PRESIDENT
WILLIAM P. WINSOR, VICE PRESIDENT



PRICE FIFTY CENTS PER COPY, EXCEPT MID-NOVEMBER ISSUE NOT SOLD SEPARATELY. PAYABLE IN ADVANCE, ONE YEAR, $3.00; TWO YEARS, $5.00 IN U.S., U.S. POSSESSIONS AND CANADA, IN ALL LATIN AMERICAN COUNTRIES: ONE YEAR, $10.00; TWO YEARS, $16.00. ALL OTHER COUNTRIES: ONE YEAR, $15.00; TWO YEARS, $25.00 (REMIT BY NEW YORK DRAFT). PUBLISHED MONTHLY, WITH AN ADDITIONAL ISSUE IN MID-NOVEMBER. PRINTED BY PUBLISHERS PRINTING-ROGERS KELLOGG CORP. INDEXED REGULARLY IN ENGINEERING INDEX AND INDUSTRIAL ARTS INDEX. ESTABLISHED IN 1929 AS METALS AND ALLOYS. TITLE CHANGES: MATERIALS & METHODS IN 1945, PRESENT TITLE IN 1957. POSTMASTER: SECOND CLASS MAIL PRIVILEGE AUTHORIZED AT NEW YORK, N.Y. SEND FORM 3579 TO MATERIALS IN DESIGN ENGINEERING, 430 PARK AVE., NEW YORK 22, N.Y. SUBSCRIBERS: SEND SUBSCRIPTION CORRESPONDENCE AND CHANGE OF ADDRESS TO MATERIALS IN DESIGN ENGINEERING, 430 PARK AVE., NEW YORK 22, N.Y., GIVING OLD AS WELL AS NEW ADDRESS, AND INCLUDING CITY POSTAL ZONE NUMBER IF POSSIBLE. ENCLOSE LATEST ADDRESS LABEL. ALLOW TWO MONTHS FOR CHANGE.



COPYRIGHT, 1960, REINHOLD PUBLISHING CORPORATION. ALL RIGHTS RESERVED.


## How to Use the Materials Selector Issue

Naturally, you can use this issue in many different ways, depending upon the nature of your own materials problems. However, this issue is called the *Materials Selector Issue* because it is designed to help you systematically narrow your choice of materials, parts and finishes to meet a specific problem. Here is a logical procedure:

**1. See Comparisons of Materials.**
Look up the critical properties and see which materials warrant further investigation.

**2. See Index to Data.**

**3. See Properties of Materials.***
Look up the pages indicated by the Index. Reduce the number of materials requiring further study by comparing significant properties, available forms, typical uses, and finishing and coating methods.

**4. See Forms and Shapes of Materials.**
Narrow the choice of materials further by comparing the characteristics of competitive forms and shapes.

**5. See Joining and Fastening of Materials.**
If assembly is required, limit choice of materials still further by comparing characteristics of competitive joining materials and processes.

**6. See Suppliers of Materials.**
Look up promising materials and forms to obtain the names of suppliers.

**7. See Addresses of Suppliers.**

**8. Obtain detailed information**
on properties, availability and cost of materials and fabricated forms by:

**a.** Writing to suppliers.

**b.** Consulting the Suppliers' Literature pages in Properties of Materials sections. Note key numbers of promising bulletins and circle them on one of the eight free post cards (pp 585-592).

**c.** Consulting the advertisements. Names of advertisers are bold faced in the Directory, and the pages on which their advertisements appear are indicated.

***WHAT THE DATA MEAN:**

Properties of Materials consists almost entirely of tabular data on the properties, forms and uses of engineering materials.

Tabular data on properties generally represent average test results obtained from many different sources and suppliers. Although the values may have been obtained from standard specified tests, in no case do the values represent minimum or maximum specified limits. A range of values may indicate either the normal variation encountered in that particular test, or the differences attributable to variations in the composition, temper, heat treatment, form, or other condition of the material. Where a value or range applies only to a particular condition of the material, the condition is stated.

Available forms listed in these sections are the most important forms that are readily available commercially. Uses listed in these sections are only typical and are not intended to be exhaustive.

These data have a limited purpose. Space does not permit a complete description of the materials and test conditions to which the data apply; hence, these data cannot be used directly for final designs. They are intended solely to aid in the important job of materials selection.

**Sorry—No Extra Copies**

***This issue is not sold separately and is available only to Materials in Design Engineering subscribers. No extra copies sold to subscribers.***

## Stress-Rupture Strength of High Temperature Alloys

**1000 Hr**

| 1200 F | | 1350 F | | 1500 F | | 1600 F | | 1700 F | | 1800 F | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Alloy | Stress, 1000 psi | Alloy | Stress, 1000 psi | Alloy | Stress, 1000 psi | Alloy | Stress, 1000 psi | Alloy | Stress, 1000 psi | Alloy | Stress, 1000 psi |
| René 41 | 102 | Inconel 713C[a] | 70 | Inconel 713C[a] | 41 | Udimet 700 | 29 | Inconel 713C[a] | 17.5 | Molybdenum[a] | 44 |
| Udimet 700 | 101 | Udimet 500 | 67.5 | 1753 | 34 | Inconel 713C[a] | 28 | X-40[a] | 14.5 | Columbium[a] | 25 |
| 1753 | 98 | Inconel 700 | 59 | Udimet 500 | 32 | 1753 | 22 | 1753 | 12 | X-40[a] | 9.8 |
| Udimet 500 | 94 | Waspaloy | 52 | Inconel 700 | 31 | Udimet 500 | 20.5 | René 41 | 11 | Inconel 713C[a] | 9 |
| U-212 | 88 | W-545 | 50 | GMR-235[a] | 29 | GMR-235[a] | 18 | HS-21[a] | 10 | HS-21[a] | 7 |
| Inconel 700 | 87 | D979 | 47 | René 41 | 29 | X-40[a] | 18 | Inconel 700 | 8.6 | S-816 | 6.5 |
| Waspaloy | 86 | GMR-235[a] | 47 | Waspaloy | 26.5 | René 41 | 17 | HS-25 | 8.4 | 1753 | 6.5 |
| D979 | 79 | M-252 | 43 | X-40[a] | 23.5 | Waspaloy | 16.5 | Hastelloy C[a] | 6.0 | HS-25 | 5 |
| M-252 | 79 | U-212 | 42.5 | M-252 | 22.5 | Inconel 700 | 16 | N-155 | 4.8 | HT[a] | 3.7 |
| Inconel X | 68 | Inconel X | 40 | D979 | 22 | M-252 | 13.5 | HT[a] | 4.7 | Hastelloy X | 3 |
| W-545 | 66 | S-816 | 40 | S-816[a] | 21 | HS-21[a] | 13.4 | HH[a] | 3.9 | HK[a] | 3 |
| Refractaloy 26 | 63 | X-40[a] | 39 | S-816 | 19 | S-816[a] | 13 | HK[a] | 3.8 | Hastelloy X[a] | 2.9 |
| Incoloy 901 | 62 | Refractaloy 26 | 38 | Inconel X | 18 | HS-25 | 12 | Inconel 702[b] | 3.5 | N-155 | 2.6 |
| HS-25 | 54 | HS-25 | 34 | Refractaloy 26 | 18 | Refractaloy 70 | 10 | | | HH[a] | 2.5 |
| S-816 | 51 | Incoloy 901 | 30 | HS-25 | 17 | S-816 | 10 | | | Inconel 702[b] | 2.4 |
| X-40[a] | 51 | S-816[a] | 29 | N-155 | 16 | Hastelloy C[a] | 9.2 | | | | |
| N-155[a] | 47 | Hastelloy B[a] | 25.5 | S-590 | 16 | S-590 | 9.0 | | | | |
| A-286 | 46 | Hastelloy C[a] | 25 | Refractaloy 70 | 15 | N-155 | 7.2 | | | | |
| HS-21[a] | 44.2 | S-590 | 25 | Hastelloy C[a] | 14.5 | Hastelloy X | 7 | | | | |
| S-816[a] | 44 | N-155[a] | 24 | HS-21[a] | 14.2 | Inconel X | 7 | | | | |
| Hastelloy C | 43 | Refractaloy 70 | 24 | N-155[a] | 14 | Inconel 702[b] | 5.1 | | | | |
| N-155 | 43 | Hastelloy C | 23 | Hastelloy B[a] | 12.7 | | | | | | |
| Nivco | 43 | HS-21[a] | 22 | Hastelloy C | 12.5 | | | | | | |
| Hastelloy C[a] | 42.5 | N-155 | 22 | Incoloy 901 | 11 | | | | | | |
| Refractaloy 70 | 42 | A-286 | 21 | Hastelloy X | 10 | | | | | | |
| Discaloy | 41 | 16-25-6 | 21 | V-36[a] | 10 | | | | | | |
| Inconel 702[b] | 41 | Inconel 702[b] | 20 | HT[a] | 9.2 | | | | | | |
| Hastelloy B[a] | 40.5 | 19-9DL | 19 | Hastelloy X[a] | 9.1 | | | | | | |
| S-590 | 38 | Hastelloy X | 18.5 | 16-25-6 | 9 | | | | | | |
| 19-9DL | 37 | V-36[a] | 18 | 19-9DL | 9 | | | | | | |
| Hastelloy B | 36.5 | Hastelloy B | 17 | Inconel 702[b] | 8.8 | | | | | | |
| 16-25-6 | 34 | Hastelloy X[a] | 16 | HH[a] | 8.2 | | | | | | |
| Hastelloy X | 33 | HT[a] | 15.2 | A-286 | 7.7 | | | | | | |
| V-36[a] | 30 | HH[a] | 14.9 | HK[a] | 7 | | | | | | |
| Hastelloy X[a] | 26.5 | HF[a] | 12 | HF[a] | 6.5 | | | | | | |
| HH[a] | 26.5 | HK[a] | 11 | | | | | | | | |
| HT[a] | 25 | | | | | | | | | | |

[a] Cast. [b] Estimated. [c] Sheet. [d] Annealed or recrystallized. [e] Stress relieved.

**10,000 Hr**

| 1200 F | | 1350 F | | 1500 F | | 1600 F | |
|---|---|---|---|---|---|---|---|
| Alloy | Stress, 1000 psi | Alloy | Stress, 1000 psi | Alloy | Stress, 1000 psi | Alloy | Stress, 1000 psi |
| Waspaloy | 67 | U-500 | 46 | U-500 | 24 | Waspaloy | 11 |
| M-252 | 64 | Waspaloy | 39 | Waspaloy | 17.5 | M-252 | 8.2 |
| S-816 | 40 | M-252 | 33 | S-816 | 16 | S-816 | 7.5 |
| N-155 | 35 | S-816 | 24 | M-252 | 14 | HT | 4.9 |
| A-286 | 32 | N-155 | 17 | N-155 | 11.5 | HH | 3.9 |
| 19-9DL | 31 | 19-9DL | 12.5 | HT | 6.9 | HK | 3.8 |
| HH, HT | 20 | HT | 11.5 | HH | 6.0 | | |
| | | | | 19-9DL | 5.6 | | |
| | | | | HK | 4.7 | | |

## Effect of Radiation on Materials

**EFFECT ON TENSILE PROPERTIES OF METALS**

| Metal | Condition of Metal | Irradiation | | Yield Strength | | Tensile Strength | | Elongation | |
|---|---|---|---|---|---|---|---|---|---|
| | | Temp, F | Integrated Fast Neutron Flux, n/sq cm | Unirrad, 1000 psi | Change After Irrad, 1000 psi | Unirrad, 1000 psi | Change After Irrad, 1000 psi | Unirrad, % | Change After Irrad,* % |
| **CARBON STEELS** | | | | | | | | | |
| ASTM A212B | Normalized at 1904 F | 176 | $10^{19}$ | 51 | 14.4 | 75 | 6.8 | 23 | −5 |
| ASTM A212B | Same as Above | 176 | $10^{20}$ | 51 | 42 | 75 | 25 | 23 | −18 |
| ASTM A302B | | 500 | $3.7 \times 10^{18}$ | 65 | 7.1 | 91.5 | 3.8 | 26 | −2 |
| ASTM A302B | | 698 | $3.7 \times 10^{18}$ | 64.2 | 3.3 | 89.8 | 2.8 | 27 | −1 |
| **STAINLESS STEELS** | | | | | | | | | |
| 347 | | | $2.6 \times 10^{22}$ | 61.6 | 39.2 | 95.8 | 11.4 | 63.2 | 19.2 |
| 316 | Annealed | 104 | $5 \times 10^{20}$ | — | — | 79 | 71 | — | — |
| 440 C | Hardened | | $5 \times 10^{19}$ | 185 | 18 | 205 | 35 | — | — |
| 301 | | 176 | $4 \times 10^{19}$ | 38.4 | 48.6 | 98.7 | 14.5 | 56 | −8 |
| 304 ELC | | 176 | $8 \times 10^{19}$ | 24.4 | 51.1 | 86.3 | 17.5 | 63 | −5 |
| 302 | | 176 | $4 \times 10^{19}$ | 33.9 | 50.1 | 95.5 | 15.8 | — | — |
| 302 B | | 176 | $4 \times 10^{19}$ | 33.5 | 48 | 107.8 | 17.2 | — | — |
| 305 | | 176 | $4 \times 10^{19}$ | 32.1 | 39.3 | 98 | 5.6 | — | — |
| 347 | | 176 | $4 \times 10^{19}$ | 37 | 59.5 | 97.6 | 17.2 | 49 | −24 |
| 321 | | 176 | $8 \times 10^{19}$ | 31.2 | 59.4 | 84.8 | 21 | — | — |
| 410 | Annealed | | $10^{20}$ | 147.7 | 35.1 | 177 | 24 | 20 | −5 |
| **ALUMINUM ALLOYS** | | | | | | | | | |
| 1100 | | | $2.6 \times 10^{22}$ | 18.4 | 8.1 | 20.3 | 10.1 | 22.3 | 0.7 |
| 356 | | | $2.6 \times 10^{22}$ | 24.1 | 11.9 | 32.4 | 12.6 | 2.7 | −1.2 |
| 1100-O | | 149 | $10^{20}$ | 6.8 | 10.3 | 13.6 | 12.4 | 38.2 | −17 |
| 1100-H14 | | 149 | $10^{20}$ | 16.6 | 7.4 | 17.3 | 8.7 | 6 | −0.5 |
| 6061-O | | 149 | $10^{20}$ | 9.5 | 16.1 | 18.1 | 19.2 | 28.8 | −6.4 |
| 6061-T6 | | 149 | $10^{20}$ | 38.5 | 5.9 | 45 | 5.6 | 17.5 | −1.3 |
| **NICKEL ALLOYS** | | | | | | | | | |
| Monel | As Received | 104 | $4 \times 10^{19}$ | — | — | 85 | 11 | 33 | −23 |
| K Monel | As Received | 104 | $4 \times 10^{19}$ | — | — | 123 | 11 | 11 | −8 |
| Inconel | As Received | 104 | $4 \times 10^{19}$ | — | — | 106 | 10 | 31 | −2 |
| Inconel X | As Received | 104 | $4 \times 10^{19}$ | — | — | 126 | 7 | 37 | −14 |
| Hastelloy C | Cast | | $4 \times 10^{19}$ | — | — | 80 | 27 | — | — |
| Hastelloy C | Wrought | 104 | $4 \times 10^{19}$ | — | — | 138 | 4 | 20 | −8 |
| Hastelloy X | Annealed | | $5 \times 10^{19}$ | 49.4 | 50.8 | 112.5 | 16.8 | 52 | −2 |
| Inconel 702 | Annealed | | $5 \times 10^{19}$ | 42.6 | 58.5 | 94.9 | 18.2 | 67 | −17 |
| Inconel X | Aged Once | | $2 \times 10^{20}$ | 120.3 | 50.5 | 184.3 | −10.3 | 23 | −10 |
| K Monel | Annealed | | $5 \times 10^{19}$ | 132.4 | 35.2 | 163.4 | 5.3 | 22 | −10 |
| **OTHER METALS** | | | | | | | | | |
| Copper | Annealed | 212 | $5 \times 10^{19}$ | 8.4 | 21.9 | 27.1 | 7.2 | 42.2 | −14.7 |
| Nickel | Annealed | 212 | $5 \times 10^{19}$ | 36.2 | 25.3 | 58.6 | 4.3 | 34.4 | −11 |
| Molybdenum | Stress Relieved | 212 | $5 \times 10^{19}$ | 93.7 | 5.7 | 99.8 | 4.5 | 23.6 | −1.6 |
| Tungsten | Fully Recrystallized | 212 | $5 \times 10^{19}$ | — | — | 137 | 15 | 0 | 0 |
| Titanium | Annealed | 212 | $5 \times 10^{19}$ | 79.8 | 8.9 | 83.4 | 8.8 | 10.4 | −2.1 |
| Zirconium | Heavily Cold Worked | 212 | $5 \times 10^{19}$ | 107 | −1 | 123.5 | 0.8 | 3.5 | 0.7 |
| Tungsten | As Received | | $5 \times 10^{19}$ | — | — | 153 | −36 | 0 | 0 |
| Tantalum | As Received | | $5 \times 10^{19}$ | — | — | 68 | 19 | 21 | −4 |
| Stellite 3 | As Received | | $5 \times 10^{19}$ | — | — | 86 | 8 | — | Low |
| Zircaloy 2 | Annealed | 122 | $10^{21}$ | 44.1 | 25.9 | 68.4 | 11.6 | 23 | −8 |
| Zircaloy 2 | 50% Cold Worked | 122 | $1 \times 10^{21}$ | 79.6 | 24.9 | 98.3 | 16.2 | 19.5 | −10.3 |
| QMV Beryllium | | | $7 \times 10^{21}$ | 24.5 | — | 35.7 | 14.7 | 1.4 | −1.2 |
| Zirconium | Annealed | 158 | $2 \times 10^{20}$ | 34.5 | 21.6 | 64.1 | 7.1 | 33 | −11 |
| Zirconium | 50% Cold Worked | 158 | $2 \times 10^{20}$ | 83.7 | 10.8 | 86.7 | 9 | 11 | −4 |

* All changes are plus unless otherwise indicated.

## EFFECT ON HARDNESS OF METALS

| Metal ↓ | Condition of Metal | Irradiation | | Brinell Hardness | |
|---|---|---|---|---|---|
| | | Temp, F | Integrated Fast Flux, n/sq cm | Unirrad | Change After Irrad[a] |
| **PLAIN CARBON STEELS** | | | | | |
| 1018 | Annealed | 104 | $10^{19}$ | 138 | 23 |
| 1018 | Hardened | 104 | $10^{19}$ | 237 | 6 |
| 1042 | Annealed | 104 | $10^{19}$ | 225 | −38 |
| 1042 | Hardened | 104 | $10^{19}$ | 390 | 36 |
| 1045 | Annealed | 104 | $10^{20}$ | 187 | 0 |
| 1095 | Annealed | 104 | $10^{19}$ | 290 | 25 |
| 1095 | Hardened | 104 | $10^{19}$ | 535 | 0 |
| **STAINLESS STEELS** | | | | | |
| 410 | Annealed | | $3 \times 10^{20}$ | 318 | 10 |
| 16-1 Croloy | Annealed | | $8 \times 10^{19}$ | 159 | 57 |
| 347 C | Annealed | 203 | $10^{20}$ | — | 82 |
| 304 | Surface Nitrided | 104 | $5 \times 10^{20}$ | 654 | 156 |
| 316 | Annealed | 104 | $5 \times 10^{20}$ | 154 | 74 |
| 410 | Surface Nitrided | 104 | $5 \times 10^{20}$ | 656 | 84 |
| 440 C | Hardened | 104 | $5 \times 10^{20}$ | 545 | 0 |
| 440 C | Hardened | | $4 \times 10^{19}$ | 461 | 73 |
| USS "W" | Hardened | 104 | $5 \times 10^{20}$ | 461 | 0 |
| **NICKEL ALLOYS** | | | | | |
| Hastelloy C | Cast | | $5 \times 10^{19}$ | 228 | 132 |
| Hastelloy C | Wrought | 104 | $4 \times 10^{19}$ | 209 | 0 |
| Monel | Annealed | 104 | $4 \times 10^{19}$ | 150 | 59 |
| K Monel | As Received | 104 | $4 \times 10^{19}$ | 260 | 25 |
| Inconel | As Received | 104 | $4 \times 10^{19}$ | 175 | 65 |
| Inconel X | Annealed | 104 | $4 \times 10^{19}$ | 209 | 56 |
| Hastelloy X | Annealed | | $5 \times 10^{19}$ | 172 | 44 |
| Inconel 702 | Annealed | | $5 \times 10^{19}$ | 156 | 60 |
| Inconel X | Aged Twice | | $10^{19}$ | 265 | 21 |
| Inconel X | Aged Once | | $10^{19}$ | 301 | 17 |
| K Monel | Annealed | | $5 \times 10^{19}$ | 271 | 9 |
| **OTHER METALS** | | | | | |
| Copper[b, c] | | 194 | $5 \times 10^{20}$ | 44 | 56 |
| Nickel[b, c] | | 194 | $5 \times 10^{20}$ | 61 | 55 |
| Titanium (75A)[c] | | 194 | $5 \times 10^{20}$ | 177 | 33 |
| Zirconium[b, c] | | 194 | $5 \times 10^{20}$ | 69 | 21 |
| Iron[b, c] | | 194 | $5 \times 10^{20}$ | 53 | 42 |
| Molybdenum[c] | | 194 | $5 \times 10^{20}$ | 204 | 23 |
| 1100 Aluminum | | | $2 \times 10^{21}$ | 38 | 34 |
| 1100 Aluminum | | | $3 \times 10^{22}$ | 38 | 38 |
| 356 Aluminum | | | $2 \times 10^{21}$ | 67 | 29 |
| QMV Beryllium | | | $2 \times 10^{21}$ | 127 | 52 |
| Stellite 3 | | | $5 \times 10^{19}$ | 420 | 55 |
| Tungsten | | | $5 \times 10^{19}$ | — | 0 |
| Tantung G | | | $5 \times 10^{19}$ | — | 0 |
| Tantalum | | | $5 \times 10^{19}$ | 147 | 53 |

[a] All changes are plus unless otherwise indicated.
[b] High purity. [c] Annealed.

## EFFECT ON IMPACT PROPERTIES OF METALS

| Metal ↓ | Irradiation | | Change in Transition Temp, °F[a] |
|---|---|---|---|
| | Temp, F | Integr Fast Neutron Flux, n/sq cm | |
| **FERROUS METALS** | | | |
| Iron | 527 | $10^{20}$ | Increase |
| ASTM A302B Steel[b, c] | 500 | $4 \times 10^{18}$ | 11 |
| Same as Above | 698 | $4 \times 10^{18}$ | 11 |
| ASTM A212B Steel[d] | 176 | $10^{19}$ | 9 |
| Same as Above | 176 | $10^{20}$ | 103 |
| ASTM A212 Steel[f] | 122 | $10^{20}$ | 151 |
| ASTM A212 Steel | 428 | $2 \times 10^{18}$ | 34 |
| ASTM A212 Steel | 572 | $2 \times 10^{18}$ | 45 |
| **NONFERROUS METALS** | | | |
| Tungsten[e] | 212 | $5 \times 10^{19}$ | 14 |
| Molybdenum | 212 | $5 \times 10^{19}$ | 185 |
| Zirconium | 104 | $5 \times 10^{19}$ | Small |
| Aluminum | 527 | $10^{20}$ | Decreases |
| Copper | 527 | $10^{20}$ | Increases |
| Nickel | 527 | $10^{20}$ | Increases |

[a] Numerical changes indicated are positive.
[b] Normalized at 1650 F. [c] Standard V-notch Charpy.
[d] Normalized at 1900 F. [e] Subsize Izod.
[f] Subsize notched cylinders. [g] Subsize tension test.

## EFFECT ON DENSITY OF METALS

| Material ↓ | Irradiation | Density | |
|---|---|---|---|
| | Integr Fast Neutron Flux, n/sq cm[a] | Unirrad, lb/cu in. | Change After Irrad, %[b] |
| 1100 Aluminum | 240 | 0.0978 | −0.004 |
| 356 Aluminum | 240 | 0.0962 | −0.02 |
| QMV Beryllium | 240 | 0.0665 | 0 |
| 347 Stainless Steel | 240 | 0.285 | −0.003 |
| 316 Stainless Steel | 3.5 | 0.288 | −0.06 |
| 347 Stainless Steel | 3.5 | 0.286 | −0.09 |
| 347+Ta Stainless Steel | 3.5 | 0.286 | −0.04 |
| 410 Stainless Steel | 3.5 | 0.277 | −0.05 |
| "A" Nickel | 3.5 | 0.321 | −0.07 |
| Monel | 3.5 | 0.319 | −0.05 |
| Stellite 3 | 3.5 | 0.309 | 0.06 |
| Stellite 6 | 3.5 | 0.301 | 0.11 |
| ASTM A212 Steel | 3.5 | 0.283 | 0 |
| Tantalum | 5 | — | −0.10 |
| Tungsten | 5 | — | −0.15 |
| Tantung G | 5 | — | −0.20 to −0.25 |
| WC-Co, TAC-Co | 8 | — | −0.3 to −0.6 |
| TiC-Ni | 8 | — | −0.3 to −0.6 |

[a] 104 F. [b] All changes are plus unless otherwise indicated.

*continued on page 34*

## Effect of Radiation on Materials

**EFFECT ON CERAMICS AND ALLIED MATERIALS**

| Material ↓ | Exposure | Effects |
|---|---|---|
| **CERAMIC OXIDES** | | |
| $Al_2O_3$[a] | $2 \times 10^{20}$ n/sq cm | No chg in x-ray pattern and ther cond. Some color chg |
| BeO[b] | $2 \times 10^{20}$ n/sq cm | 0.3% exp in $c_o$, none in $a_o$ as det by x-ray pattern. No chg in ther cond |
| MgO[c] | $2 \times 10^{20}$ n/sq cm | No chg in basic lattice. Single crystal broken into reactive small crystals |
| Quartz | $10^{21}$ n/sq cm | Decr in density to 2.25. Chg in axial ratio (c/a) from 4.1 to about 1.06. Signif energy release shown by DTA at 1110 F |
| $SiO_2$ | $10^{21}$ n/sq cm | Decr in density to about 2.25 (17.7% chg). No macroscopic defects or loss of structure. Color chg |
| $SiO_2$[d] | $2 \times 10^{20}$ n/sq cm | Incr in density to 2.25. Heating at red heat removes increase. Color chg to deep violet or dark brown |
| $SiO_2$[d] | $2 \times 10^{10}$ ergs/gm (C), electrons | Highly purified silica shows no discolor. Comm silica appears dark, mottled |
| $TiO_2$[c] | $2 \times 10^{20}$ n/sq cm | No chg in x-ray pattern. Slight decr in ther cond. Color chg |
| $ZrO_2$[c] | $2 \times 10^{20}$ n/sq cm | Rad-induced phase chg, monoclinic to cubic. No chg in cubic lattice. Slight decr in ther cond |
| **MISCELLANEOUS CERAMICS** | | |
| Spinel, Forsterite, Porcelain, Steatite | $2 \times 10^{20}$ n/sq cm | No chg in crystal structure. Decr in ther cond (factor of 2). Color chg |
| Cordierite | $2 \times 10^{20}$ n/sq cm | Loss of crystallinity. Decr in ther cond (factor of 4). Color chg |
| Zircon | $1 \times 10^{20}$ n/sq cm | 1.9% exp. Large loss of crystallinity |
| Zircon | $2 \times 10^{20}$ n/sq cm | Complete loss of crystallinity. Decr of ther cond (factor of 5). Color chg |
| $BaTiO_3$ | $2 \times 10^{20}$ n/sq cm | 2.87% exp in $a_c$. Marked color chg |
| Mica (muscovite) | $10^9$ ergs/gm (C), gamma | No effects noted |

[a] Effects noted on both single crystals and hot pressed materials.
[b] Hot pressed. [c] Single crystal.
[d] Vitreous. [e] Polycrystalline, sintered.

**EFFECT ON GLASS**

| Glass Type | Type of Radiation or Dosage | Property Change |
|---|---|---|
| **PHOSPHATE GLASSES** | | |
| K-Ba-Al Phosphate | Gamma | Colors easily |
| Ca Metaphosphate | Gamma | Abs peak near 4700 A |
| Silver (activated) | Gamma | Abs near UV |
| Lead-Containing (60% w/o PbO) | $10^{14}$ n/sq cm | No discolor, melts |
| **SPECIAL GLASSES** | | |
| Pure $GeO_2$ Glass | Gamma | Insensitive at $10^8$–$10^9$ ergs/gm (C) |
| 1 PbO–1.3 $P_2O_5$ | $2 \times 10^{20}$ n/sq cm | Slight discolor |
| 1 PbO–1.22 $V_2O_5$ | $2 \times 10^{20}$ n/sq cm | No signif chg |
| 1 PbO–1.5 $SiO_2$ | $2 \times 10^{20}$ n/sq cm | Chg from yellowish clear to amber clear; considerable decr in hardness |
| $0.8K_2O$–$0.2CaO$–$2.75$ $SiO_2$ | $2 \times 10^{20}$ n/sq cm | Chg from colorless to gray |
| $Li_2O \cdot 3B_2O_3$, $Na_2O \cdot 2B_2O_3$, $K_2O$–$2B_2O_3$, $Rb_2O \cdot 2B_2O_3$ | $3 \times 10^{10}$ ergs/gm (C), gamma | Abs 10 times greater than for fused $B_2O_3$ |
| **OTHER GLASSES** | | |
| Lead Glass (window) | Gamma | May develop brown color |
| Soft Glass | $5.8 \times 10^{19}$ n/sq cm | Dark color, slight incr in ten str; decr in impact str |
| Optical Glass (crown and flint) | $10^6$–$10^8$ ergs/gm (C) | Develops color at $10^6$ ergs/g (C) or less; useless at $10^8$ ergs/gm |
| Optical Glass (protected; cont 1-2% $CeO_2$) | X-ray or gamma | No color at $10^8$ ergs/g (C); usable at $5 \times 10^{10}$ ergs/gm (C) |
| Soda-Lime-Silica Glass (cont cobalt) | Gamma | Color chg sensitive to dosage; suitable for dosimeter |
| Fused Silica | | |
| General | All types of high-energy rad | Color centers form; abs band at 214 mμ |
| Pure | Fast neutrons | Density may chg from 2.2 to 2.27 |
| | $10^{11}$ ergs/gm (C), gamma | No chg in abs |
| | Reactor, gamma | Intense abs band at 218 mμ |
| With Al Impurity | X-ray, UV | Develops abs bands at 5500, 2950 and 2150 A |
| Borosilicate | $10^{20}$ n/sq cm | Develops large cracks |
| Pyrex (borosilicate) | $5.8 \times 10^{19}$ n/sq cm | Color darkens; slight incr in ten and impact str |

**EFFECT ON PLASTICS LAMINATES**

| Material | Irradiation | | | Tensile Strength, psi | | Flexural Modulus, $10^6$ psi | |
|---|---|---|---|---|---|---|---|
| | Exposure, ergs/gm (C) | Temp, F | Exp Time, hr | Unirrad, 1000 psi | Chg After Irrad, 1000 psi | Unirrad | Chg After Irrad |
| Silicone (flexure test) | $8.5 \times 10^9$ | Room | 200 | 31.7 | −0.3 | 3.06 | −0.12 |
| | $2 \times 10^9$ | 500 | 50 | 12.4 | +1.2 | 1.9 | +0.10 |
| | $4 \times 10^9$ | 500 | 100 | 13.4 | −1.7 | 2.0 | 0 |
| | $8.5 \times 10^9$ | 500 | 200 | 14.1 | −4.2 | 2.0 | −0.1 |
| Heat Resistant Epoxy (compression test) | $8.5 \times 10^9$ | Room | 200 | 46.7 | 0 | — | — |
| | $2 \times 10^9$ | 500 | 50 | 3.7 | +0.1 | — | — |
| | $4 \times 10^9$ | 500 | 100 | 4.1 | +1.3 | — | — |
| | $8.5 \times 10^9$ | 500 | 200 | 4.7 | +1.6 | — | — |
| Phenolic (flexure test) | $8.5 \times 10^9$ | Room | 200 | 84.5 | −0.5 | 4.2 | +0.1 |
| | $2 \times 10^9$ | 500 | 50 | 27.3 | +27.7 | 3.1 | +0.3 |
| | $4 \times 10^9$ | 500 | 100 | 17.7 | +24.3 | 2.6 | +1.0 |
| | $8.5 \times 10^9$ | 500 | 200 | 12.3 | +3.3 | 2.1 | +0.3 |

**EFFECT ON PLASTICS AND RUBBER MATERIALS[a]**

| Material ↓ | Beginning of Moderate Damage, ergs/gm (C)[b] | Beginning of Serious Damage, ergs/gm (C) |
|---|---|---|
| PLASTICS MATERIALS | | |
| Phenolic Laminates | $>10^{12}$ | $>10^{12}$ |
| Polystyrene | $7.5 \times 10^{10}$ | $6.5 \times 10^{11}$ |
| Polyester Laminates | $7.5 \times 10^{10}$ | $5.5 \times 10^{11}$ |
| Phenolics, Mineral-Filled | $5 \times 10^{10}$ | $5 \times 10^{11}$ |
| Silicones, Glass-Reinforced | $5 \times 10^{10}$ | $5 \times 10^{11}$ |
| Epoxy Resins | $10^{10}$ | $9 \times 10^{10}$ |
| Phenolics, Unfilled | $4.5 \times 10^9$ | $3 \times 10^{10}$ |
| Polyvinyl Chloride | $4.5 \times 10^9$ | $5 \times 10^{10}$ |
| Amino Resins | $2 \times 10^9$ | $9 \times 10^9$ |
| Polyethylene | $10^9$ | $9 \times 10^9$ |
| Cellulosics | $8 \times 10^8$ | $5 \times 10^9$ |
| Silicones | $10^8$ | $4.5 \times 10^9$ |
| Polyamides | $10^8$ | $10^9$ |
| Polyesters, Unfilled | $10^8$ | $2.5 \times 10^8$ |
| TFE Fluorocarbon | $5 \times 10^6$ | $2.5 \times 10^7$ |
| RUBBER MATERIALS | | |
| Urethane | $7.5 \times 10^9$ | $4.5 \times 10^{10}$ |
| Natural | $6 \times 10^9$ | $3 \times 10^{10}$ |
| SBR | $3.5 \times 10^9$ | $3 \times 10^{10}$ |
| Nitrile | $2 \times 10^9$ | $9.5 \times 10^9$ |
| Neoprene | $2 \times 10^9$ | $9.5 \times 10^9$ |
| Acrylic | $0.5 \times 10^9$ | $10^{10}$ |
| Silicone | $8 \times 10^8$ | $6 \times 10^9$ |
| Fluoroelastomers | $8 \times 10^8$ | $4 \times 10^9$ |
| Polysulfide | $1.5 \times 10^8$ | $4.5 \times 10^8$ |
| Butyl | $0.5 \times 10^8$ | $4 \times 10^8$ |

[a] Estimated from graph.
[b] Incipient to mild damage at about $10^5 - 10^7$ ergs/gm (C).

# SUPPLIERS' LITERATURE

## Irons and Steels

**Stainless Steel.** Allegheny Ludlum Steel Corp., 18 pp, No. FS57. Information on grades of stainless steel; various forms of corrosive attack; resistance of stainless steel to various corrosive media; comparative physical, mechanical and other properties; fabrication data; available forms; and other information necessary for selecting stainless steels. **1**

**Manganese Steel.** American Manganese Steel Div., American Brake Shoe Co., 16 pp, illus., No. 2. Information on the use of manganese steel for hard facing and for construction equipment. **2**

**Oriented Electrical Steels.** Armco Steel Corp., 4159 Curtis St., Middletown, Ohio, 64 pp, illus. Classification; advantages; physical, mechanical and magnetic properties; surface preparation; and other technical data on a line of oriented electrical steels. Write on company letterhead directly to Armco.

**Tool Steel Selector.** Bethlehem Steel Co., 14 pp, No. 513. General descriptions of the five basic groups of tool steels, typical analyses and properties, and a selection guide consisting of recommended tool steels for typical applications. Included are specifications, sizes, and instructions for ordering. **3**

**Corrosion of Wrought Iron.** A. M. Byers Co., 12 pp. Results of eight-year corrosion tests on wrought iron and 10 structural steels in salt water and lake water environments. Included are comparative corrosion-time curves, weight loss tables and complete details on test materials, conditions, methods and results. **4**

**Stainless Steel Services.** G. O. Carlson, Inc., 12 pp, illus. Information on stainless steel plates, heads, forgings, rings, circles, flanges, bars, and sheets used in the metalworking, chemical process, nuclear, and aircraft and missile industries. **5**

**Specialty Steels.** Carpenter Steel Co., 40 pp, illus. Properties and uses of tool and die steels, stainless steels, high temperature alloys, electronic, magnetic and electrical alloys, special purpose alloy steels, tubing and pipe, and fine wire specialties. **6**

**Stainless Steels.** Cooper Alloy Corp., 10 pp, illus. Composition ranges, mechanical properties, corrosion resistance and high temperature mechanical properties of molybdenum-containing 18-8 type stainless steels. **7**

**Electric Furnace Steels.** Copperweld Steel Co., Artistoloy Steel Div., 48 pp, illus. Facilities for melting, rolling, finishing, heat treating and conditioning electric furnace steels. Rolling limits and chemical analyses are also given. **8**

**Boron Stainless Steel.** Superior Steel Div., Copperweld Steel Co., 8 pp, illus., No. 57. Chemical composition, microstructure, corrosion resistance, machinability and mechanical properties of a boron stainless steel. **9**

**Data on Steel.** Crucible Steel Co. of America, 73 pp, illus. Composition, heat treatment, and weight and conversion tables for tool, stainless, heat resisting, carbon, alloy, and special purpose steels. **10**

**Titanium-Bearing Stainless Steels.** Eastern Stainless Steel Corp., 4 pp, illus., No. 102. Information on a new flux casting method that reduces inclusions in titanium-bearing stainless steels. **11**

**Stainless Steel Specifications.** Peter A. Frasse & Co., Inc., Sec. A, No. 1. Chart provides chemical compositions and nearest SAE and AMS designations for 40 standard AISI grades of stainless steel and 18 special grades, including precipitation hardening stainless steels. **12**

**Tool Steels.** Jessop Steel Co., 14 pp, illus. Information on cast-to-shape air hardening, oil hardening, hot worked, flame hardening, stainless and heat resisting tool steels. **13**

**Stainless Steel Wire.** Jones & Laughlin Steel Corp., Stainless & Strip Div., 22 pp, illus. Technical data and other information on how to use and order stainless steel wire. **14**

**Steel Analyses.** Jones & Laughlin Steel Corp., Stainless & Strip Div., 20 pp. Compositions, and SAE, AISI and AMS numbers for 40 stainless steels, 184 alloy steels and 105 carbon steels. **15**

**High Strength Steel Bar.** LaSalle Steel Co., 10 pp, illus., No. 15. Advantages, characteristics, properties, typical applications and other information on copper-containing high strength steel bar. **16**

**High Strength Steel.** Latrobe Steel Co., 4 pp, illus. Composition, physical and mechanical properties, specifications and applications of a machinable high strength steel. **17**

**Steel Plate Shapes.** Lukens Steel Co., 16 pp, illus., No. 378. Information on facilities for flame cutting, shearing, blanking, punching, pressing, bending, and welding various shapes made from steel plates. **18**

**Zinc-Coated Steel.** Weirton Steel Co., Div. of National Steel Corp., 12 pp, illus. Installation data, specifications, uses and characteristics of zinc-coated steel. **19**

**Coated Steel Strip.** Thomas Strip Div., Pittsburgh Steel Co., 20 pp, illus. Actual samples of strip steel electrolytically coated with zinc, copper, brass, lead alloy, nickel and chromium, in natural and buffed finishes. **20**

**Stainless Steel.** Republic Steel Corp., 12 pp, illus., May-June '60. Advantages, characteristics, properties, and other data on stainless steel. **21**

**Steel Services.** Joseph T. Ryerson & Son, Inc., 256 pp, illus., No. 117. Reference book lists types, shapes and sizes of steel, aluminum, and industrial plastics available for immediate shipment from stock. **22**

**Spring, Strip, Specialty Steels.** Sandvik Steel, Inc., 6 pp, illus. Sizes, materials and chemical composition of spring and specialty strip steels. **23**

**Steel Catalog.** Timken Roller Bearing Co., 16 pp, illus., No. L758. General information, advantages, and other data on alloy steel bars and billets, stainless steel bar, tool steels and seamless steel tubing. **24**

**High Temperature Steels.** United States Steel Corp., 88 pp, illus. Discusses the nature of creep, measurement of flow under stress at elevated temperature, factors affecting high temperature properties, and behavior of steels at elevated temperatures. Includes specifications, heat treatment, composition, tensile properties, creep and rupture properties, and effect of time and temperature on impact strength and hardness of 21 different high temperature steels. **25**

**Steel Strip.** American Steel & Wire Co., Div. of U. S. Steel Corp., 48 pp, illus. Physical properties, dimensions, tempers and finishes of cold rolled stainless and carbon steel strip. **26**

**Stainless Wire.** Universal-Cyclops Steel Corp., 4 pp, illus., No. SS-200. Information on cost, corrosion resistance and cold heading characteristics of commonly used stainless steel cold heading wire. **27**

**Cr-Mo-V Steel.** Vanadium Corp. of America. Chemical composition, creep strength, stress rupture strength, and resistance to graphitization of a chromium-molybdenum-vanadium steel. **28**

**Superalloy Casting Alloy.** WaiMet Alloys Co., 4 pp, illus. Stress rupture properties, mechanical properties, chemical composition, and other technical data on a superalloy casting alloy. **29**

**Stainless Steel.** Washington Steel Corp., 32 pp, illus. Physical properties, composition, fabrication, corrosion and heat resistance, and cleanability of special purpose stainless steel sheet and strip. **30**

**Galvanized Sheet Steel.** Wheeling Steel Corp., 44 pp, illus. Properties and uses for galvanized steel sheet and strip called Softite. **31**

*To get literature, use free post cards on pp 585-592*

PROPERTIES OF MATERIALS

# Irons and Steels




PAGE

38 Gray Irons—Cast
40 Nodular or Ductile Irons—Cast
42 Malleable Irons—Cast
43 Ingot and Wrought Irons
44 Low and Medium Carbon Steels—Wrought
45 Medium and High Carbon Steels—Wrought
46 Free-Cutting Steels—Wrought
47 Nitriding Steels—Wrought
48 Low Alloy and H-Steels—Wrought
52 H-Steels—Wrought
54 Austenitic Stainless Steels—Wrought
57 Ferritic Stainless Steels—Wrought
58 Martensitic Stainless Steels—Wrought
60 High Temperature Steels—Wrought
61 Ultra High Strength Steels—Wrought
62 Age Hardenable Stainless Steels—Cast, Wrought
64 Iron-Base Superalloys (Cr-Ni)—Wrought
66 Iron-Base Superalloys (Cr-Ni-Co)—Cast, Wrought
67 Carbon Steels—Cast
68 Low Alloy Steels—Cast
70 Stainless Steels—Cast
74 Heat Resistant Alloys—Cast
77 Standard Tool Steels—Wrought
78 Advertisements
36 Suppliers' Literature

## Gray Irons—Cast

| Class[a] → | 20 | 25 | 30 |
|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | |
| Density, lb/cu in. | 0.26 | 0.26 | 0.26 |
| Thermal Conductivity (212 F), Btu/hr/sq ft/°F/ft. | 24–34 | 24–34 | 24–34 |
| Coef of Ther Exp (32–212 F), per °F. | $6 \times 10^{-6}$ | $6 \times 10^{-6}$ | $6 \times 10^{-6}$ |
| Magnetic? | Yes | Yes | Yes |
| Electrical Resistivity (68 F), microhm-cm. | Varies from 50 to 200 depending on composition | | |
| **MECHANICAL PROPERTIES[b]** | | | |
| Mod of Elast in Tension, psi[c] | 13, 12, $9 \times 10^6$ | 14, 13, $11.5 \times 10^6$ | 16, 15, $13.5 \times 10^6$ |
| Tensile Strength (as cast), 1000 psi | 24–29, 20–24, 15–19 | 27–33, 25–30, 20–24 | 35–40, 30–34, 20–24 |
| Transverse Strength (as cast), 1000 lb[d] | 1, 2, 5.2 | 1.25, 2.1, 5.5 | 1.4, 2.2, 7.3 |
| Deflection (as cast), in.[d] | 0.14, 0.25, 0.25 | 0.17, 0.27, 0.30 | 0.16, 0.28, 0.31 |
| Modulus of Rupture (as cast), 1000 psi | 50, 53, 40 | 57, 56, 42 | 63, 58, 56 |
| Hardness (Brinell, as cast)[e] | 200, 180, 170 | 205, 190, 175 | 210, 200, 180 |
| Fatigue Strength (endurance limit, as cast), 1000 psi[f] | —, 10, — | —, 12.5, — | —, 14.5, — |
| Compressive Strength (as cast), 1000 psi[g] | 100, 95, 90 | —, 100, — | —, 115, — |
| Shear Strength (as cast), 1000 psi | —, 32, — | —, 37, — | —, 44, — |
| **FABRICATING PROPERTIES** | Gray cast iron, having a ferrite matrix in which graphite flakes are dispersed, has a machinability rating of 110. When a cast iron microstructure shows alloy segregation, free carbides, steadite and free pearlite, machinability is reduced and may be as low as 40. Some castings show several structures due to cooling rate and section size | | |
| **JOINING** | Can be joined by gas welding; shielded metal-arc welding using special electrodes; carbon arc welding. Preheating necessary. Can be brazed with nonferrous filler metal | | |
| **CORROSION RESISTANCE** | More resistant to some types of corrosion than carbon and low alloy steels, possibly because of graphite; cast iron soil pipe usually lasts longer than steel pipe, for example. Gray irons are resistant to strong sulfuric acid, cold concentrated phosphoric and nitric acids; attacked by dilute sulfuric, phosphoric and nitric acids. Resistant to many alkalis, including sodium hydroxide, soda ash and ammonia | | |
| **USES** | Machine bases, grates, housings, ornamental castings, sanitary wear, piston rings, pipe and fittings | Similar to class 20 where higher strength is required | Light brake drums, clutch plates, cylinder blocks, liners, impellers, pipe and fittings, grate bars, machine parts |

[a] Specified min tensile strength, 1000 psi, ASTM A48-48.
[b] Three values are given for light, medium and heavy sections, respectively.
[c] At ¼ max transverse load.
[d] Bar diameters 0.875, 1.2 and 2.0 in., respectively. Distance between supports 12, 18 and 24 in., respectively.
[e] Considerably wider range obtainable by heat treatment.
[f] About 40% of tensile strength appears to be safe level for endurance limit.
[g] In general, compressive strength is three to five times tensile strength.

## Gray Irons—Cast

| Class[a] → | 35 | 40 | 50 | 60 |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Density, lb/cu in. | 0.26 | 0.26 | 0.26 | 0.26 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 24–34 | 24–34 | 24–34 | 24–34 |
| Coef of Ther Exp (32–212 F), per °F | 6 x $10^{-6}$ | 6 x $10^{-6}$ | 6 x $10^{-6}$ | 6 x $10^{-6}$ |
| Magnetic? | Yes | Yes | Yes | Yes |
| Elec Res (68 F), microhm-cm | Varies from 50 to 200 depending on composition | | | |
| **MECHANICAL PROPERTIES[b]** | | | | |
| Mod of Elast in Tension, psi[c] | 17, 16, 14.5 x $10^6$ | 18, 17, 15.5 x $10^6$ | 19, 19, 18 x $10^6$ | 20, 19.5, 19 x $10^6$ |
| Ten Str (as cast), 1000 psi | 38–42, 35–40, 25–33 | 50, 40–48, 33–45 | 60, 50–57, 52 | 70, 60–66, 50–75 |
| Transverse Str (as cast), 1000 lb[d] | 1.5, 2.6, 8 | 1.75, 2.9, 10 | 2, 3.3, 10.7 | 2.5, 3.7, 15 |
| Deflection (as cast), in.[d] | 0.17, 0.28 – | 0.16, 0.28, 0.30 | 0.18, 0.28, 0.30 | 0.13, 0.34, 0.40 |
| Mod of Rupture (as cast), 1000 psi | 70, 69, 63 | 80, 78, 76 | 91, 88, 82 | 114, 98, 115 |
| Hardness (Brinell, as cast)[e] | 220, 210, 190 | 230, 220, 210 | 260, 240, 230 | 300, 290, 275 |
| Fatigue Str (endur limit, as cast), 1000 psi[f] | –, 17.5, – | –, 21, – | –, 25, – | –, –, – |
| Compr Str (as cast), 1000 psi[g] | 150, 125, – | –, 143, – | –, 150, – | –, 170, – |
| Shear Str (as cast), 1000 psi | –, 43, – | –, 57, – | –, –, – | –, –, – |
| **FABRICATING PROPERTIES** | Gray cast iron, having a ferrite matrix in which graphite flakes are dispersed, has a machinability rating of 110. When a cast iron microstructure shows alloy segregation, free carbides, steadite and free pearlite, machinability is reduced and may be as low as 40. Some castings show several structures due to cooling rate and section size | | | |
| **JOINING** | Can be joined by gas welding, shielded metal-arc welding using special electrodes, carbon arc welding. Preheating necessary. Can be brazed with nonferrous filler metal | | | |
| **CORROSION RESISTANCE** | More resistant to some types of corrosion than carbon and low alloy steels, possibly because of graphite; cast iron soil pipe usually lasts longer than steel pipe, for example. Gray irons are resistant to strong sulfuric acid, cold concentrated phosphoric and nitric acids; attacked by dilute sulfuric, phosphoric and nitric acids. Resistant to many alkalis, including sodium hydroxide, soda ash and ammonia | | | |
| **USES** | Clutch plates, crankcases, light brake-drums, liners, sleeves, cylinder blocks, impellers, machine components | Gears, camshafts, heads, liners, valves, pumps, tube supports, dies, wheels | Gears, valves, heads, blocks, steam pressure castings, dies, compressors, pumps, rams | Special brake drums, pressure castings, crusher frames, hot forming dies, heavy duty gears, hydraulic cylinders |

[a] Specified min tensile strength, 1000 psi, ASTM A48-48.
[b] Three values are given for light, medium and heavy sections, respectively.
[c] At ¼ max transverse load.
[d] Bar diameters 0.875, 1.2 and 2.0 in., respectively. Distance between supports 12, 18 and 24 in., respectively.
[e] Considerably wider range obtainable by heat treatment.
[f] About 40% of tensile strength appears to be safe level for endurance limit.
[g] In general, compressive strength is three to five times tensile strength.

## Nodular or Ductile Irons—Cast

| Type → | 80-50-3 | 60-45-10 | 100-75-04[a] |
|---|---|---|---|
| COMPOSITION, % | T.C. 3.3–3.8, Si 2.0–3.0, Mn 0.2–0.5, P 0.06–0.08, Ni 0–1.0, Mg 0.02–0.07 | T.C. 3.4–4.0, Si 2.0–2.75, Mn 0.2–0.6, P 0.06–0.08, Ni 0–1.0, Mg 0.02–0.07 | T.C. 3.4–3.8, Si 2.0–2.75, Mn 0.3–0.6, P 0.08 max, Ni 0–2.5, Mo 0-1.0, Mg 0.02–0.07 |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.257 | 0.257 | 0.257 |
| Melting Temp Range, F | 2050–2150 | 2050–2150 | 2050–2150 |
| Thermal Conductivity (212 F), Btu/hr/sq ft/°F/ft | 18 | 20 | — |
| Coef of Ther Exp (70–400 F), per °F | $6.6 \times 10^{-6}$ | $6.6 \times 10^{-6}$ | $6.6 \times 10^{-6}$ |
| Electrical Resistivity (75 F), microhm-cm | 68[b] | 66[b] | — |
| MECHANICAL PROPERTIES | | | |
| Mod of Elast in Tension, psi | $22–25 \times 10^6$ | $22–25 \times 10^6$ | $22–25 \times 10^6$ |
| Tensile Strength, 1000 psi | 90–110 | 60–80 | 100–120 |
| Yield Strength, 1000 psi | 60–75 | 45–60 | 75–90 |
| Elongation (in 2 in.), % | 3–10 | 10–25 | 6–10 |
| Hardness (Brinell) | 200–270 | 140–190 | 200–240 |
| Impact Strength (Charpy), ft-lb | | | |
| Unnotched | 15–65 | 60–115 | 35–50 |
| Notched | 2–5 | 10–15 | — |
| Fatigue Strength | Endurance ratio follows pattern of other ferrous materials. For soft ferritic materials, notched endurance ratio is about 50-55%; with stronger irons, the ratio drops to 30-40% or lower | | |
| Compressive Strength | Ratio of compressive strength to tensile strength is about 2 to 1 | | |
| Creep Strength (0.0001%/hr), psi | | | |
| 800 F | 19,000 | 14,000 | — |
| 1000 F | 1,750 | 4,000 | — |
| 1200 F | 480 | 550 | — |
| 1400 F | — | — | — |
| THERMAL TREATMENT | | | |
| Ferritic Structure (ferritizing anneal) | Heat in 1600–1650 F range, cool to 1300 F, hold 1-3 hr, furnace cool to 1100 F, air cool | | |
| Pearlitic-Ferritic Structures | Heat to 1600–1650 F, cool rapidly, reheat at 1100–1300 F | | |
| Pearlitic Structures | Normalize by air cooling from 1600–1650 F | | |
| Tempered Structures | Quench from 1400–1650 F (depending on composition), temper at 800–1300 F | | |
| FABRICATING PROPERTIES | | | |
| Machinability | Depends on structure but has excellent machinability in both as-cast and annealed conditions | | |
| Weldability | Can be welded by most fusion welding processes. For maximum ductility, welding should be done on fully annealed material. Composition affects weld quality. A 60 Ni-40% Fe filler wire is best for metal arc welding. Can be brazed with the lower melting BAg filler metals | | |
| CORROSION RESISTANCE | Approx same corrosion resistance as gray irons of similar composition | | |
| USES | Anvils for forging hammers; impellers, levers, cams, crankshafts, dies, jet engine burner support rings | Valve and pump bodies, pipe fittings, clamps, gear housings, tractor and farm machine parts | Track shoes, brake drums, gears, camshafts, pistons |

[a]Obtained by heat treatment involving normalizing or quenching and tempering.
[b]Iron containing 1% silicon.

## Nodular or Ductile Irons—Cast

| Type → | 120-90-02[a] | Heat Resistant | Austenitic |
|---|---|---|---|
| COMPOSITION, % | T.C. 3.4–3.8, Si 2.0–2.75, Mn 0.3–0.6, P 0.08 max, Ni 0–2.5, Mo 0–1.0, Mg 0.02–0.07 | T.C. 2.8–3.8, Si 2.5–6.0, Mn 0.2–0.6, P 0.08 max, Ni 0–1.5, Mg 0.02–0.07 | T.C. 3.0, Si 2.0–3.2, Mn 0.8–1.5, P 0.02 max, Ni 18–22, Cr 0–2.5 |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.257 | 0.25 | 0.268 |
| Melting Temp Range, F | 2050–2150 | 2050–2150 | 2250 |
| Thermal Conductivity (212 F), Btu/hr/sq ft/°F/ft | — | — | — |
| Coef of Ther Exp (70–400 F), per °F | $6.6 \times 10^{-6}$ | — | $10.4 \times 10^{-6}$ |
| Electrical Resistivity (75 F), microhm-cm | — | — | 102 |
| MECHANICAL PROPERTIES | | | |
| Mod of Elast in Tension, psi | $22–25 \times 10^6$ | $22–25 \times 10^6$ | $18.5 \times 10^6$ |
| Tensile Strength, 1000 psi | 120–150 | 60–100 | 58–68 |
| Yield Strength, 1000 psi | 90–125 | 45–75 | 32–38 |
| Elongation (in 2 in.), % | 2–7 | 0–20 | 7–40[c] |
| Hardness (Brinell) | 240–325 | 140–300 | 140–200 |
| Impact Strength (Charpy), ft-lb | | | |
| Unnotched | 25–40 | 5–115 | — |
| Notched | — | — | 10–28 |
| Fatigue Strength | Endurance ratio follows pattern set with other ferrous materials. For soft ferritic materials, notched endurance ratio is 50–55%; with the stronger irons, ratio drops to 30–40% or lower | | |
| Compressive Strength | Ratio of compressive strength to tensile strength is about 2 to 1 | | |
| Creep Strength (0.0001%/hr), psi[d] | | | |
| 800 F | — | — | 18,500 |
| 1000 F | — | — | 13,000 |
| 1200 F | — | — | 5,700 |
| 1400 F | — | — | 2,000 |
| THERMAL TREATMENT | | | |
| Ferritic Structure (ferritizing anneal) | Heat in 1600–1650 F range, cool to 1300 F, hold 1–3 hr, furnace cool to 1100 F, air cool | | — |
| Pearlitic-Ferritic Structures | Heat to 1600–1650 F, cool rapidly, reheat at 1100–1300 F | | — |
| Pearlitic Structures | Normalize by air cooling from 1600–1650 F | | — |
| Tempered Structures | Quench from 1400–1650 F (depending on composition), temper at 800–1300 F | | — |
| FABRICATING PROPERTIES | | | |
| Machinability | Depends on structure but is excellent in both as-cast and annealed conditions | | |
| Weldability | Can be welded by most fusion welding processes. For maximum ductility, welding should be done on fully annealed material. Composition affects weld quality. A 60 Ni-40% Fe filler wire is best for metal arc welding. Can be brazed with the lower melting BAg filler metals | | |
| CORROSION RESISTANCE | Approx same corrosion resistance as gray irons of similar composition; superior to ordinary gray irons | | |
| USES | Machine guides, pinions, gears, cams, dies, track rollers | Grate boxes, sinter pots, lead pots, glass molds, furnace doors | Impellers, grids, paper mill machine parts, pumps, valves |

[a]Obtained by heat treatment involving normalizing or quenching and tempering.
[c]25–40% with 0% chromium.
[d]For 0% chromium.

## Malleable Irons

| Type and Grade → | Standard | | Pearlitic |
|---|---|---|---|
| | 32510 | 35018 | |
| COMPOSITION, % | C 2.3–2.7, Si 1.5–0.8, Mn 0.55 max, P 0.18 max, S 0.20 max | C 2.0–2.45, Si 1.4–0.85, Mn 0.55 max, P 0.18 max, S 0.20 max | Same as standard grades except that Mn can be higher |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.259–0.263 | 0.259–0.263 | 0.260–0.268 |
| Thermal Conductivity, Btu/hr/sq ft/°F/ft | | | |
| 80 F | 29.5 | 29.5 | [b] |
| 700 F | 23.0 | 23.0 | [b] |
| Coef of Ther Exp (68–212 F), per °F | $5.9 \times 10^{-6}$ | $5.9 \times 10^{-6}$ | $7.5 \times 10^{-6}$ |
| Specific Heat (70–750 F), Btu/lb/°F | 0.133 | 0.133 | — |
| Electrical Resistivity (68 F), microhm-cm | 27–34 | 27–34 | 38.19–41.17 |
| Magnetic? | Yes | Yes | Yes |
| MECHANICAL PROPERTIES | | | |
| Mod of Elast in Tension, psi | $25 \times 10^6$ | $25 \times 10^6$ | $28 \times 10^6$ |
| Tensile Strength, 1000 psi | 50–52 | 53–60 | 65–120 |
| Yield Strength, 1000 psi | 32–35 | 35–40 | 45–100 |
| Elongation (in 2 in.), % | 10–18 | 18–25 | 2–16 |
| Reduction of Area, % | 18–23 | 18–23 | — |
| Hardness (Brinell) | 110–156 | 110–156 | 160–285 |
| Impact Strength (Charpy), ft-lb[a] | 16.5 | 16.5 | 12 |
| Fatigue Strength | | | |
| Endurance Limit, 1000 psi | 25 | 31 | 30–32 |
| Endurance Ratio | 0.50 | 0.57 | 0.40 |
| Mod of Elast in Compression, psi | $25 \times 10^6$ | $25 \times 10^6$ | $23 \times 10^6$ |
| Compressive Yield Strength, 1000 psi | | | |
| 1% Permanent Set | 28 | 28 | 43 |
| At Failure | 90+ | 90+ | 197–290 |
| Ultimate Shear Strength, 1000 psi | 45–48 | 48–54 | 65–100 |
| Yield Strength in Shear, 1000 psi | 29–32 | 32–36 | — |
| Mod of Rupture in Torsion, psi | 58,000 | 58,000 | — |
| Poisson's Ratio | 0.17 | 0.17 | — |
| Allowable Working Stress (775 F), psi | 5600 | 5600 | — |
| THERMAL TREATMENT | | | |
| Hardening Temp, F | 1500[c] | 1500[c] | 1500 |
| Tempering Temp, F | — | — | About 600 |
| FABRICATING PROPERTIES | | | |
| Casting Temperature Range, F | 2600–2800 | 2600–2850 | 2600–2850 |
| Shrinkage Allowance (contraction minus expansion during anneal), in. | 11/64–1/32 | 11/64–1/32 | 11/64–1/32 |
| Machinability Index (AISI B1112 steel=100) | 120 | 120 | 80–90 |
| Weldability | Not fusion welded. Can be soldered and brazed | | |
| CORROSION RESISTANCE | Resistant to atmospheric corrosion in rural, industrial and marine atmospheres; fresh and salt waters | | |
| USES | Gear cases, brake supports, journal boxes, pipe fittings, pole line hardware, ordnance parts, marine deck fittings, anchors, parts for domestic appliances and business machines | | Rocker arms, camshafts, gears, sprockets, tractor parts, agricultural machinery parts |

[a] V-notch 0.079 in. deep, 0.394-in. sq bar.
[b] Estimated to be somewhat higher than for standard grades.
[c] Must first be heated to 1700 F to dissolve massive carbides.

## Ingot and Wrought Irons

| Type → | Ingot Iron | Wrought Iron | |
|---|---|---|---|
| COMPOSITION, % | C<0.02, Mn<0.02, Si trace, P 0.005, S 0.02 | C 0.02, Mn 0.06, Si 0.13, P 0.13, S 0.01, slag 2.5 | |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.28 | 0.278 | |
| Melting Point, F | 2794 | 2750 | |
| Thermal Conductivity (212 F), Btu/hr/sq ft/°F/ft | 38 | 34.5 | |
| Coef of Ther Exp (68–212 F), per °F | $6.8 \times 10^{-6}$ | $7.4 \times 10^{-6}$ | |
| Specific Heat, Btu/lb/°F | 0.11 | 0.11 | |
| Electrical Resistivity (68 F), microhm-cm | 9.7 | 11.97 | |
| Magnetic? | Yes | Yes | |
| MECHANICAL PROPERTIES | | | |
| Mod of Elast in Tension, psi | $29.8 \times 10^6$ | $29.5 \times 10^6$ | |
| | | Longitudinal[a] | Transverse[a] |
| Tensile Strength, 1000 psi | | | |
| Annealed | 42 | — | — |
| Hot Rolled | 44 | 48 (min) | 39 |
| Cold Drawn | 73 | — | — |
| Yield Point, 1000 psi | | | |
| Annealed | 19 | — | — |
| Hot Rolled | 23 | 27 (min) | 27 |
| Cold Drawn | 69 | — | — |
| Elongation (in 2 in.), % | | | |
| Annealed | 48 | — | — |
| Hot Rolled | 47 | 14[b] | 2[b] |
| Cold Drawn | 12 | — | — |
| Reduction of Area, % | | | |
| Annealed | 76 | — | — |
| Hot Rolled | 75 | 52 | — |
| Cold Drawn | 63 | — | — |
| Hardness (Brinell) | | | |
| Annealed | 69 | — | — |
| Hot Rolled | 83 | 97–105 | 97–105 |
| Cold Drawn | 142 | — | — |
| Impact Strength (Charpy), ft-lb | | | |
| Annealed | 19 | — | — |
| Hot Rolled | — | 24–28 | — |
| Cold Drawn | — | — | — |
| Fatigue Strength (endurance limit), 1000 psi | | | |
| Annealed | 26 | — | — |
| Hot Rolled | 28 | 23 | 19 |
| Cold Drawn | 33 | — | — |
| FABRICATING PROPERTIES | | | |
| Annealing Temperature, F | 1700–1800 | 1300–1400 | |
| Forging Temperature Range, F | — | 2100–2400 | |
| Bending Temperature Range, F | — | 1300–1400 | |
| Machinability Index (AISI B1112 steel=100) | 50 | 50 | |
| Weldability | Readily joined by resistance, arc and gas methods | | |
| CORROSION RESISTANCE | In spite of its purity, ingot iron has corrosion rates much the same as plain carbon steel | Current improved wrought iron has at least 25% greater corrosion resistance than former grade. Shows its greatest advantage over carbon steels in heat transfer equipment handling brines, industrial cooling waters and flue gases. Also used in steam condensate and drainage systems and other elevated temperature equipment | |
| AVAILABLE FORMS | Sheet and strip, wire, rail sections | Tubular products, plate, sheet, bars, structural shapes, wire, chain | |
| USES | Deep drawn parts, enameling stock, third rails, wire for electrical apparatus | Condensers and heat exchangers; piping for steam condensates, fresh and salt water, coolants, caustics; processing equipment; plates used for tanks, stacks, exhausts and breechings; bars for curing racks, manhole ladder steps, etc. | |

[a] As rolled. [b] In 8 in.

## Low and Medium Carbon Steels—Wrought

| AISI Type → | C1010, C1015 | C1018 | C1020, C1025 | C1030, C1035 |
|---|---|---|---|---|
| COMPOSITION, % | C 0.08–0.18, Mn 0.30–0.60, P 0.040 max, S 0.050 max | C 0.15–0.20, Mn 0.60–0.90, P 0.040 max, S 0.050 max | C 0.18–0.28, Mn 0.30–0.60, P 0.040 max, S 0.050 max | C 0.28–0.38, Mn 0.60–0.90, P 0.040 max, S 0.050 max |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.283 | 0.283 | 0.283 | 0.283 |
| Melting Temp Range, F | 2750–2775 | 2750–2775 | 2750–2775 | 2700–2750 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 27 | 27 | 27 | 27 |
| Coef of Ther Exp (70–1200 F), per °F | $8.4 \times 10^{-6}$ | $8.4 \times 10^{-6}$ | $8.4 \times 10^{-6}$ | $8.3 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 |
| Elec Res (68 F), microhm-cm | 14.3 | 14.3 | 14.3 | 19 |
| Magnetic? | Yes | Yes | Yes | Yes |
| MECHANICAL PROPERTIES[a] | | | | |
| Mod of Elast in Tension, psi | $29–30 \times 10^6$ | $29–30 \times 10^6$ | $29–30 \times 10^6$ | $29–30 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Hot Rolled | 51, 61 | 69 | 65, 67 | 80, 85 |
| Cold Worked | 56, 74 | 82 | 78, 80 | 85, 92 |
| Yld Str, 1000 psi | | | | |
| Hot Rolled | 29, 46 | 48 | 43, 45 | 50, 54 |
| Cold Worked | 33, 62 | 70 | 66, 68 | 72, 79 |
| Elong (in 2 in.), % | | | | |
| Hot Rolled | 38, 39 | 38 | 36, 36 | 30, 30 |
| Cold Worked | 35, 24 | 20 | 20, 20 | 26, 25 |
| Red. of Area, % | | | | |
| Hot Rolled | 70, 61 | 62 | 59, 58 | 56, 53 |
| Cold Worked | 65, 57 | 57 | 55, 55 | 51, 50 |
| Hardness (Brinell) | | | | |
| Hot Rolled | 101, 126 | 143 | 143, 143 | 163, 183 |
| Cold Worked | 113, 143 | 163 | 156, 163 | 179, 201 |
| Impact Str | Markedly dependent on section size and processing details, such as deoxidation practice, rolling practice, etc.—more so than other mechanical properties | | | |
| Fatigue Str | Dependent on thermal and mechanical history, though not to the extent that impact strengths are. Conservative estimate of fatigue strength is 40–50% of tensile strength | | | |
| THERMAL TREATMENT[a] | | | | |
| Annealing Temp, F | 1650–1750 | 1650–1750 | 1650–1750, 1600–1700 | 1550–1700, 1500–1650 |
| Hardening Temp, F | 1650–1700[c] | 1650–1700[c] | 1600–1675[d] | 1575–1650, 1525–1600[c] |
| Tempering Temp, F | 300–1350 | 300–1350 | 300–1350 | 300–1350 |
| FABRICATING PROPERTIES[a] | | | | |
| Machinability Index[b] | | | | |
| Hot Rolled | 40, 50 | 52 | 50, 50 | —, — |
| Cold Worked | 45, 58 | 65 | 60, 60 | 67, 67 |
| Weldability | Easily welded by all commercial welding procedures, including gas, arc, bronze, thermit, oxy-acetylene and submerged-melt processes. Preheat and postheat treatments sometimes necessary | | | |
| CORROSION RESISTANCE | Rusted by oxygen and water at room temperature, rate of attack increasing sharply as pH goes above 4 and decreasing below pH of 8. Dilute salt solutions increase corrosion rate. Attacked by acids, in general, but satisfactorily resistant to alkalis at normal temperatures. Corrosion rate in ordinary rusting not appreciably affected by carbon or alloy content or by cold working | | | |
| AVAILABLE FORMS | Can be obtained in all standard mill forms | | | |
| USES | Automobile spiders, gears, clutch disks, bolts, bearing races, camshafts, crankshafts, piston pins, cams, pneumatic tool cylinders, gun blocks, bushings, stud and collar bolts, shifter shoes, draw bars, pivot pins, cap screws, precision shafting, scythe blade heels, flanges, shackles, tie rods, drag links, steering gear connecting rods, thrust washers, wrenches | | | Brake shoe parts, gears, tie rods, clutch pedals, pitman arms, flywheel rings, crankshafts, camshafts, wheel hubs, tools, springs |

[a] Where two values are given, they are for the two grades in that column.
[b] Based on AISI B1112 steel = 100.
[c] Quench in water, brine or caustic frequently used.
[d] Soluble oil solution used for hardening bolts; mineral oil used when quenching for machinability.
[e] Quenched in oil, water, or brine or caustic solutions.

## Medium and High Carbon Steels—Wrought

| AISI Type → | C1040, C1045 | C1055, C1060 | C1070, C1080 | C1095 |
|---|---|---|---|---|
| COMPOSITION, % | C 0.37–0.50, Mn 0.60–0.90, P 0.040 max, S 0.050 max | C 0.50–0.65, Mn 0.60–0.90, P 0.040 max, S 0.050 max | C 0.65–0.88, Mn 0.60–0.90, P 0.040 max, S 0.050 max | C 0.90–1.05, Mn 0.30–0.50, P 0.040 max, S 0.050 max |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.283 | 0.283 | 0.283 | 0.283 |
| Melting Temp Range, F | 2700–2750 | — | — | — |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 27 | 27 | 27 | 27 |
| Coef of Ther Exp (70–1200 F), per °F | $8.3 \times 10^{-6}$ | $8.1 \times 10^{-6}$ | $8.1 \times 10^{-6}$ | $8.1 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 |
| Elec Res (68 F), microhm-cm | 19 | 18 | 18 | 18 |
| Magnetic? | Yes | Yes | Yes | Yes |
| MECHANICAL PROPERTIES[a] | | | | |
| Mod of Elast in Tension, psi | $29–30 \times 10^6$ | $29–30 \times 10^6$ | $29–30 \times 10^6$ | $29–30 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Annealed (1450 F) | 100, 103[i] | 97, 105 | 112, 119 | 100 |
| Hot Rolled | 91, 98 | 109, 116 | 128, 141 | 142 |
| Hard. & Temp | 113[c], 120[d] | 150[e], 160[e] | 174[f], 189[f] | 180[g] |
| Yld Str, 1000 psi | | | | |
| Annealed | 88, 90[i] | 52, 54 | 60, 66 | 53 |
| Hot Rolled | 58, 59 | 65, 70 | 77, 84 | 84 |
| Hard. & Temp | 86[c], 90[e] | 105, 112 | 127, 142 | 118 |
| Elong (in 2 in.), % | | | | |
| Annealed | 17, 14[i] | 24, 20 | 17, 15 | 21 |
| Hot Rolled | 27, 24 | 19, 17 | 15, 12 | 9 |
| Hard. & Temp | 23[c], 18[e] | 14, 12 | 13, 14 | 11 |
| Red. of Area, % | | | | |
| Annealed | 42, 40[i] | 47, 44 | 34, 22 | 42 |
| Hot Rolled | 50, 45 | 38, 36 | 27, 17 | 18 |
| Hard. & Temp | 62[c], 52[d] | 45, 40 | 37, 34 | 30 |
| Hardness (Brinell) | | | | |
| Annealed | 207, 217[i] | 185, 192 | 207, 223 | 197 |
| Hot Rolled | 201, 212 | 235, 241 | 267, 293 | 293 |
| Hard. & Temp | 235[c], 277[d] | 307, 321 | 354, 388 | 375 |
| Impact Str (Izod), ft-lb | | | | |
| Annealed | Markedly dependent on section size and processing details | 22, 15 | 11, 6 | 5 |
| Hot Rolled | | 18, 13 | 9, 5 | 3 |
| Hard. & Temp | | 22, 15 | 13, 10 | 5 |
| THERMAL TREATMENT[a] | | | | |
| Normalizing Temp, F | — | 1525–1650 | 1525–1650 | 1525–1650 |
| Annealing Temp, F | 1450–1600 | 1500–1575 | 1500–1575 | 1500–1575 |
| Hardening Temp, F | 1475–1575[h] | 1450–1550 | 1450–1525 | 1430–1500 |
| Tempering Temp, F | 300–1350 | 400–1300 | 400–1300 | 400–1300 |
| FABRICATING PROPERTIES[a] | | | | |
| Hot Working Temp Range, F | — | 1550–1650 | 1550–1650 | 1550–1650 |
| Machinability Index (annealed)[b] | 65, 60[i] | 55, 53 | 45, 44 | 43 |
| Weldability | Easily welded; preheat and postheat treatments necessary | High carbon content introduces difficulties in welding. Thermit process satisfactory; gas and arc methods difficult | | |
| CORROSION RESISTANCE | Rust when brought into contact with moisture and air at room temperature; rates not appreciably affected by carbon content. If salts are present, corrosion rate increases. Attacked readily by acids; resistant to alkalis at ordinary temperatures | | | |
| AVAILABLE FORMS | All mill forms | Cold rolled strip, hot rolled strip, flat bars, forgings | | |
| USES | Brake shoe parts, gears, tie rods, clutch pedals, crankshafts, camshafts | Heavy machine parts such as shafts, braces and control rods; hand tools such as wrenches, hammers, pliers, screwdrivers, hatchets and axes; agricultural machinery parts such as plowshares, disks for harrows and mower knives; and flat and helical springs | | |

[a] Where two values are given, they correspond to the two alloys listed in that column. [b] Based on AISI B1112 steel = 100.
[c] 1-in. round, water quenched 1525 F, drawn at 1000 F. [d] 1-in. round, water quenched 1550 F, tempered at 1000 F.
[e] 1-in. round, normalized 1650 F, reheated to 1550 F, oil quenched, tempered 700 F.
[f] 1-in. round, normalized 1650 F, reheated to 1525 F, oil quenched, tempered 700 F.
[g] 1-in. round, normalized 1650 F, reheated to 1475 F, oil quenched, tempered 700 F.
[h] Quenched in oil, water, or brine or caustic solutions. [i] Cold worked.

## Free-Cutting Steels—Wrought

| AISI Type[a] → | B1111, C1211 | B1112, C1212 | B1113, C1213 |
|---|---|---|---|
| COMPOSITION, % | C 0.13 max, Mn 0.60–0.90, P 0.07–0.12, S 0.08–0.15 | C 0.13 max, Mn 0.70–1.00, P 0.07–0.12, S 0.16–0.23 | C 0.13 max, Mn 0.70–1.00, P 0.07–0.12, S 0.24–0.33 |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.283 | 0.283 | 0.283 |
| Thermal Conductivity (212 F), Btu/hr/sq ft/°F/ft | 27 | 27 | 27 |
| Coef of Ther Exp (70–1200 F), per °F | $8.4 \times 10^{-6}$ | $8.4 \times 10^{-6}$ | $8.4 \times 10^{-6}$ |
| Specific Heat, Btu/lb/°F | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 |
| Electrical Resistivity (68 F), microhm-cm | 14.3 | 14.3 | 14.3 |
| MECHANICAL PROPERTIES | | | |
| Mod of Elast in Tension, psi | $29 \times 10^6$ | $29 \times 10^6$ | $29 \times 10^6$ |
| Tensile Strength, 1000 psi[c] | | | |
| 9/16-In. Dia | 85–110 | 85–110 | 85–110 |
| 1-In. Dia | 80–105 | 80–105 | 80–105 |
| 2-In. Dia | 70–90 | 70–90 | 70–90 |
| Yield Strength, 1000 psi[c] | | | |
| 9/16-In. Dia | 75–100 | 75–100 | 75–100 |
| 1-In. Dia | 70–90 | 70–90 | 70–90 |
| 2-In. Dia | 60–85 | 60–85 | 60–85 |
| Elongation (in 2 in.), %[c] | | | |
| 9/16-In. Dia | 10–20 | 10–20 | 10–20 |
| 1-In. Dia | 12–22 | 12–22 | 12–22 |
| 2-In. Dia | 10–20 | 10–20 | 10–20 |
| Reduction of Area, %[c] | | | |
| 9/16-In. Dia | 30–50 | 30–50 | 30–50 |
| 1-In. Dia | 35–55 | 35–55 | 35–55 |
| 2-In. Dia | 30–50 | 30–50 | 30–50 |
| Hardness (Brinell)[c] | | | |
| 9/16-In. Dia | B90–102[b] | B90–102[b] | B90–102[b] |
| 1-In. Dia | 163–229 | 163–229 | 163–229 |
| 2-In. Dia | 149–202 | 149–202 | 149–202 |
| Impact Strength | Relatively low impact strength at low temperatures; should not be used for shock loading applications at subzero temperatures | | |
| Fatigue Strength | Notch sensitive as cold drawn. Polished fatigue specimens will show expected values but poor finishing or processing of parts may cause low and erratic results for finished parts under dynamic or alternating stresses of relatively low intensity | | |
| THERMAL TREATMENT | | | |
| Case Hardening | Case hardened for high surface hardness and good wear resistance where core properties not important. Case hardness Rockwell C60–65 | | |
| Case Hardening Temp, F[d] | 1450–1700 | 1450–1700 | 1450–1700 |
| Tempering Temp, F | 300 | 300 | 300 |
| FABRICATING PROPERTIES | | | |
| Workability | Not recommended for operations involving cold metal movement, such as crimping, forming or bending | | |
| Machinability Index[e] | 90 | 100 | 125 |
| Machining Speed (avg), sfm | 153 | 170 | 213 |
| AVAILABLE FORMS | Cold drawn shapes | | |
| USES | Studs, nuts, fasteners, sleeves, collars, spacers, dowels, rods, handles, levers | | |

[a] B1111, B1112, B1113 are bessemer steels. C1211, C1212, C1213 are basic open hearth steels.
[b] Rockwell hardness.
[c] Cold drawn.
[d] Quench in water or oil
[e] Based on AISI B1112 Steel = 100.

## Nitriding Steels—Wrought

| Type → | 135 | 135, Modified | N | EZ | 5 Ni-2 Al |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.30–0.40, Mn 0.40–0.70, Si 0.20–0.40, Cr 0.90–1.40, Al 0.85–1.20, Mo 0.15–0.25 | C 0.38–0.45, Mn 0.40–0.70, Si 0.20–0.40, Cr 1.40–1.80, Al 0.85–1.20, Mo 0.30–0.45 | C 0.20–0.27, Mn 0.40–0.70, Si 0.20–0.40, Cr 1.00–1.50, Al 0.85–1.20, Mo 0.20–0.30, Ni 3.25–3.75 | C 0.30–0.40, Mn 0.50–1.10, Si 0.20–0.40, Cr 1.00–1.50, Al 0.85–1.20, Mo 0.15–0.25, Se 0.15–0.25 | C 0.20–0.25, Mn 0.25–0.45, Si 0.20–0.30, Ni 4.75–5.25, Cr 0.40–0.60, Mo 0.20–0.30, Al 1.80–2.20, V 0.08–0.15 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.283 | 0.283 | 0.283 | 0.283 | — |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 30 | 30 | 30 | 30 | — |
| Coef of Ther Exp (32–932 F), per °F | $6.5 \times 10^{-6}$ | $6.5 \times 10^{-6}$ | $6.5 \times 10^{-6}$ | $6.5 \times 10^{-6}$ | — |
| Spec Ht, Btu/lb/°F | 0.11–0.12 | 0.11–0.12 | 0.11–0.12 | 0.11–0.12 | — |
| Elec Res (68 F), microhm-cm | 27–29 | 27–29 | 27–29 | 27–29 | — |
| Magnetic? | Yes | Yes | Yes | Yes | — |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $29–30 \times 10^6$ | $29–30 \times 10^6$ | $29–30 \times 10^6$ | $29–30 \times 10^6$ | $29–30 \times 10^6$ |
| Ten Str (hard. & temp), 1000 psi | 138[a], 121[b] | 159[a], 145[b] | 132[c], 190[d] | 126[a] | 206[e] |
| Yld Str (hard. & temp), 1000 psi | 120[a], 103[b] | 141[a], 125[b] | 114[c], 180[d] | 90[a, f] | 202[e] |
| Elong (in 2 in., hard. & temp), % | 20[a], 23[b] | 18[a], 20[b] | 22[c], 15[d] | 17[a] | 15[e] |
| Red. of Area (hard. & temp), % | 58[a], 62[b] | 56[a], 64[b] | 59[c], 43[d] | 44[a] | 46.5[e] |
| Hardness (Brinell, hard. & temp) | 280[a], 230[b] | 320[a], 285[b] | 277[c], 415[d] | 255[a] | 44[e, i] |
| | Cases produced by nitriding these steels will have hardnesses of about Rockwell 15N 94–95, excepting case on Nitralloy N which will be about Rockwell 15N 92–93 | | | | |
| Impact Str (Izod, hard. & temp), ft-lb | 65[a], 80[b] | — | — | — | 14[e, j] |
| Endurance Limit, 1000 psi | — | 45[g1], 24[g2], 90[g3], 80[g4] | — | — | 90[e, k] |
| THERMAL TREATMENT | | | | | |
| Annealing Temp, F | 1650–1700 | 1650–1700 | 1500–1550[b] | 1650–1700 | — |
| Normalizing Temp, F | — | — | — | — | 1700 |
| Quenching Temp, F | 1700–1750 | 1700–1750 | 1625–1675 | 1700–1750 | 1650 |
| Tempering Temp, F | 1100–1300 | 1100–1300 | 1100–1300 | 1100–1300 | — |
| Solution Treating Temp, F | — | — | — | — | 1275 |
| Aging (8 hr min) Temp, F | — | — | — | — | 1050 |
| Nitriding Temp, F | 930–1050 for periods ranging to 100 hr; 24 to 48-hr treatments are most widely used | | | | |
| FABRICATING PROPERTIES | | | | | |
| Hot Working Temp Range, F | 1950–2200 | 1950–2200 | 1950–2200 | 1950–2200 | 1950–2200 |
| Weldability | Can be welded by atomic hydrogen process using Nitralloy welding rod; also flash welding | | | | Can be welded with AWS ER310 stainless welding rod |
| CORROSION RESISTANCE | Provided the outer skin or white layer is not removed, the nitrided case is resistant to alkalis, crude oil, natural gas combustion products, tap water and unagitated salt water. Case is attacked by mineral acids. Removal of white layer greatly reduces resistance to attack | | | | |
| USES | Most uses based on resistance to wear. Cylinder liners and barrels in aircraft engines, bushings, shafts, piston pins, spindles and thread guides, cams and camshafts, rubber and paper mill rolls. 5 Ni–2 Al recommended where highest core strength is required for heavily loaded wear resistant parts such as gears, bearings, shafts | | | | |

[a] Core properties; oil quenched from 1700 F, tempered at 1200 F.
[b] Core properties; oil quenched from 1700 F, tempered at 1300 F.
[c] Core properties; oil quenched from 1650 F, tempered at 1200 F before nitriding.
[d] Core properties; oil quenched from 1650 F, tempered at 1200 F after nitriding.
[e] Core properties; solution treated at 1275 F, aged 8 hr min at 1050 F.
[f] Proportional limit.
[g] Heat treated to 269 Bhn and tested (g1) unnitrided, unnotched; (g2) unnitrided with V notch; (g3) nitrided, unnotched; (g4) nitrided with V notch.
[h] Must be cooled rapidly below 1150 F to avoid precipitation hardening.
[i] Rockwell C. [j] Charpy V notch. [k] Polished.

## Low Alloy Steels and H Steels—Wrought

| AISI Type ↓ | COMPOSITION • C | Mn | Ni | Cr | Mo |
|---|---|---|---|---|---|
| **13XX** | | | | | |
| 1330 | 0.28–0.33, 0.27–0.33 | 1.00–1.90, 1.45–2.05 | —, — | —, — | —, — |
| 1335 | 0.33–0.38, 0.32–0.38 | 1.60–1.90, 1.45–2.05 | —, — | —, — | —, — |
| 1340 | 0.38–0.43, 0.37–0.44 | 1.60–1.90, 1.45–2.05 | —, — | —, — | —, — |
| 1345 | 0.43–0.48, — | 1.60–1.90, — | —, — | —, — | —, — |
| **23XX, 25XX** | | | | | |
| 2317 | 0.15–0.20, — | 0.40–0.60, — | 3.25–3.75, — | —, — | —, — |
| 2515 | 0.12–0.17, 0.12–0.18 | 0.40–0.60, 0.30–0.70 | 4.75–5.25, 4.70–5.30 | —, — | —, — |
| 2517 | —, 0.14–0.20 | —, 0.30–0.70 | —, 4.70–5.30 | —, — | —, — |
| E2517 | 0.15–0.20, — | 0.45–0.60, — | 4.75–5.25, — | —, — | —, — |
| **31XX, 33XX** | | | | | |
| 3120 | 0.17–0.22, 0.17–0.23 | 0.60–0.80, 0.50–0.90 | 1.10–1.40, 1.00–1.45 | 0.55–0.75, 0.45–0.85 | —, — |
| 3130 | 0.28–0.33, 0.27–0.33 | 0.60–0.80, 0.50–0.90 | 1.10–1.40, 1.00–1.45 | 0.55–0.75, 0.45–0.85 | —, — |
| 3135 | 0.33–0.38, 0.32–0.38 | 0.60–0.80, 0.50–0.90 | 1.10–1.40, 1.00–1.45 | 0.55–0.75, 0.45–0.85 | —, — |
| 3140 | 0.38–0.43, 0.37–0.44 | 0.70–0.90, 0.60–1.00 | 1.10–1.40, 1.00–1.45 | 0.55–0.75, 0.45–0.85 | —, — |
| 3310 | —, 0.07–0.13 | —, 0.30–0.70 | —, 3.20–3.80 | —, 1.30–1.80 | —, — |
| E3310 | 0.08–0.13, — | 0.45–0.60, — | 3.25–3.75, — | 1.40–1.75, — | —, — |
| 3316 | —, 0.13–0.19 | —, 0.30–0.70 | —, 3.20–3.80 | —, 1.30–1.80 | —, — |
| E3316 | 0.14–0.19, — | 0.45–0.60, — | 3.25–3.75, — | 1.40–1.75, — | —, — |
| **40XX** | | | | | |
| 4023 | 0.20–0.25, — | 0.70–0.90, — | —, — | —, — | 0.20–0.30, — |
| 4024 | 0.20–0.25, — | 0.70–0.90, — | —, — | —, — | 0.20–0.30, — |
| 4027 | 0.25–0.30, — | 0.70–0.90, — | —, — | —, — | 0.20–0.30, — |
| 4028 | 0.25–0.30, — | 0.70–0.90, — | —, — | —, — | 0.20–0.30, — |
| 4032 | 0.30–0.35, 0.29–0.35 | 0.70–0.90, 0.60–1.00 | —, — | —, — | 0.20–0.30, 0.20–0.30 |
| 4037 | 0.35–0.40, 0.34–0.41 | 0.70–0.90, 0.60–1.00 | —, — | —, — | 0.20–0.30, 0.20–0.30 |
| 4042 | 0.40–0.45, 0.39–0.46 | 0.70–0.90, 0.60–1.00 | —, — | —, — | 0.20–0.30, 0.20–0.30 |
| 4047 | 0.45–0.50, 0.44–0.51 | 0.70–0.90, 0.60–1.00 | —, — | —, — | 0.20–0.30, 0.20–0.30 |
| 4053 | 0.50–0.56, 0.49–0.56 | 0.75–1.00, 0.65–1.10 | —, — | —, — | 0.20–0.30, 0.20–0.30 |
| 4063 | 0.60–0.67, 0.59–0.69 | 0.75–1.00, 0.65–1.10 | —, — | —, — | 0.20–0.30, 0.20–0.30 |
| 4068 | 0.63–0.70, 0.62–0.72 | 0.75–1.00, 0.65–1.10 | —, — | —, — | 0.20–0.30, 0.20–0.30 |
| **41XX** | | | | | |
| 4118 | 0.18–0.23, 0.17–0.23 | 0.70–0.90, 0.60–1.00 | —, — | 0.40–0.60, 0.30–0.70 | 0.08–0.15, 0.08–0.15 |
| 4130 | 0.28–0.33, 0.27–0.33 | 0.40–0.60, 0.30–0.70 | —, — | 0.80–1.10, 0.75–1.20 | 0.15–0.25, 0.15–0.25 |
| 4135 | 0.33–0.38, 0.32–0.38 | 0.70–0.90, 0.60–1.00 | —, — | 0.80–1.10, 0.75–1.20 | 0.15–0.25, 0.15–0.25 |
| 4137 | 0.35–0.40, 0.34–0.41 | 0.70–0.90, 0.60–1.00 | —, — | 0.80–1.10, 0.75–1.20 | 0.15–0.25, 0.15–0.25 |
| 4140 | 0.38–0.43, 0.37–0.44 | 0.75–1.00, 0.65–1.10 | —, — | 0.80–1.10, 0.75–1.20 | 0.15–0.25, 0.15–0.25 |
| 4142 | 0.40–0.45, 0.39–0.46 | 0.75–1.00, 0.65–1.10 | —, — | 0.80–1.10, 0.75–1.20 | 0.15–0.25, 0.15–0.25 |
| 4145 | 0.43–0.48, 0.42–0.49 | 0.75–1.00, 0.65–1.10 | —, — | 0.80–1.10, 0.75–1.20 | 0.15–0.25, 0.15–0.25 |
| 4147 | 0.45–0.50, 0.44–0.51 | 0.75–1.00, 0.65–1.10 | —, — | 0.80–1.10, 0.75–1.20 | 0.15–0.25, 0.15–0.25 |
| 4150 | 0.48–0.53, 0.47–0.54 | 0.75–1.00, 0.65–1.10 | —, — | 0.80–1.10, 0.75–1.20 | 0.15–0.25, 0.15–0.25 |
| **43XX, 46XX** | | | | | |
| 4320 | 0.17–0.22, 0.17–0.23 | 0.45–0.65, 0.40–0.70 | 1.65–2.00, 1.55–2.00 | 0.40–0.60, 0.35–0.65 | 0.20–0.30, 0.20–0.30 |
| 4337 | 0.35–0.40, 0.34–0.41 | 0.60–0.80, 0.55–0.90 | 1.65–2.00, 1.55–2.00 | 0.70–0.90, 0.65–0.95 | 0.20–0.30, 0.20–0.30 |
| E4337 | 0.35–0.40, — | 0.65–0.85, — | 1.65–2.00, — | 0.70–0.90, — | 0.20–0.30, — |
| 4340 | 0.38–0.43, 0.37–0.44 | 0.60–0.80, 0.55–0.90 | 1.65–2.00, 1.55–2.00 | 0.70–0.90, 0.65–0.95 | 0.20–0.30, 0.20–0.30 |
| E4340 | 0.38–0.43, 0.37–0.44 | 0.65–0.85, 0.60–0.95 | 1.65–2.00, 1.55–2.00 | 0.70–0.90, 0.65–0.95 | 0.20–0.30, 0.20–0.30 |
| 4608 | 0.06–0.11, — | 0.25–0.45, — | 1.40–1.75, — | —, — | 0.15–0.25, — |
| 4615 | 0.13–0.18, — | 0.45–0.65, — | 1.65–2.00, — | —, — | 0.20–0.30, — |
| 4617 | 0.15–0.20, — | 0.45–0.65, — | 1.65–2.00, — | —, — | 0.20–0.30, — |
| 4620 | 0.17–0.22, 0.17–0.23 | 0.45–0.65, 0.35–0.75 | 1.65–2.00, 1.55–2.00 | —, — | 0.20–0.30, 0.20–0.30 |
| 4621 | 0.18–0.23, 0.17–0.23 | 0.70–0.90, 0.60–1.00 | 1.65–2.00, 1.55–2.00 | —, — | 0.20–0.30, 0.20–0.30 |
| 4640 | 0.38–0.43, 0.37–0.44 | 0.60–0.80, 0.50–0.90 | 1.65–2.00, 1.55–2.00 | —, — | 0.20–0.30, 0.20–0.30 |
| **47XX, 48XX** | | | | | |
| 4720 | 0.17–0.22, 0.17–0.23 | 0.50–0.70, 0.45–0.75 | 0.90–1.20, 0.85–1.25 | 0.35–0.55, 0.30–0.60 | 0.15–0.25, 0.15–0.25 |
| 4812 | 0.10–0.15, 0.09–0.15 | 0.40–0.60, 0.30–0.70 | 3.25–3.75, 3.20–3.80 | —, — | 0.20–0.30, 0.20–0.30 |
| 4815 | 0.13–0.18, 0.12–0.18 | 0.40–0.60, 0.30–0.70 | 3.25–3.75, 3.20–3.80 | —, — | 0.20–0.30, 0.20–0.30 |
| 4817 | 0.15–0.20, 0.14–0.20 | 0.40–0.60, 0.30–0.70 | 3.25–3.75, 3.20–3.80 | —, — | 0.20–0.30, 0.20–0.30 |
| 4820 | 0.18–0.23, 0.17–0.23 | 0.50–0.70, 0.40–0.80 | 3.25–3.75, 3.20–3.80 | —, — | 0.20–0.30, 0.20–0.30 |

• Phosphorus and sulfur contents usually range between 0.025 and 0.040% for low alloy steels. Silicon content usually ranges between 0.20 and 0.35%. All steels except those prefixed by an "E" are open hearth; "E" steels are electric furnace. The two sets of ranges are for standard low alloy steels and H steels, respectively, and apply to bar, billets and blooms not exceeding 200 sq in. in cross-sectional area.

# Low Alloy Steels and H Steels—Wrought

**COMPOSITION [a] (continued)**

| AISI Type ↓ | C | Mn | Ni | Cr | Mo |
|---|---|---|---|---|---|
| **50XX, 51XX** | | | | | |
| 5015 | 0.12–0.17, — | 0.30–0.50, — | —, — | 0.30–0.50, — | —, — |
| 5046 | 0.43–0.50, 0.43–0.50 | 0.75–1.00, 0.65–1.10 | —, — | 0.20–0.35, 0.13–0.43 | —, — |
| 5117 | 0.15–0.20, — | 0.70–0.90, — | —, — | 0.70–0.90, — | —, — |
| 5120 | 0.17–0.22, 0.17–0.23 | 0.70–0.90, 0.60–1.00 | —, — | 0.70–0.90, 0.60–1.00 | —, — |
| 5130 | 0.28–0.33, 0.27–0.33 | 0.70–0.90, 0.60–1.00 | —, — | 0.80–1.10, 0.75–1.20 | —, — |
| 5132 | 0.30–0.35, 0.29–0.35 | 0.60–0.80, 0.50–0.90 | —, — | 0.75–1.00, 0.65–1.10 | —, — |
| 5135 | 0.33–0.38, 0.32–0.38 | 0.60–0.80, 0.50–0.90 | —, — | 0.80–1.05, 0.70–1.15 | —, — |
| 5140 | 0.38–0.43, 0.37–0.44 | 0.70–0.90, 0.60–1.00 | —, — | 0.70–0.90, 0.60–1.00 | —, — |
| 5145 | 0.43–0.48, 0.42–0.49 | 0.70–0.90, 0.60–1.00 | —, — | 0.70–0.90, 0.60–1.00 | —, — |
| 5147 | 0.45–0.52, 0.45–0.52 | 0.70–0.95, 0.60–1.05 | —, — | 0.85–1.15, 0.80–1.25 | —, — |
| 5150 | 0.48–0.53, 0.47–0.54 | 0.70–0.90, 0.60–1.00 | —, — | 0.70–0.90, 0.60–1.00 | —, — |
| 5152 | 0.48–0.55, 0.48–0.55 | 0.70–0.90, 0.60–1.00 | —, — | 0.90–1.20, 0.85–1.30 | —, — |
| 5155 | 0.50–0.60, — | 0.70–0.90, — | —, — | 0.70–0.90, — | —, — |
| 5160 | 0.55–0.65, 0.55–0.65 | 0.75–1.00, 0.65–1.10 | —, — | 0.70–0.90, 0.60–1.00 | —, — |
| E50100 | 0.95–1.10, — | 0.25–0.45, — | —, — | 0.40–0.60, — | —, — |
| E51100 | 0.95–1.10, — | 0.25–0.45, — | —, — | 0.90–1.15, — | —, — |
| E52100 | 0.95–1.10, — | 0.25–0.45, — | —, — | 1.30–1.60, — | —, — |
| **61XX** [b] | | | | | |
| 6117 | 0.15–0.20, — | 0.70–0.90, — | —, — | 0.70–0.90, — | —, — |
| 6120 | 0.17–0.22, 0.17–0.23 | 0.70–0.90, 0.60–1.00 | —, — | 0.70–0.90, 0.60–1.00 | —, — |
| 6145 | 0.43–0.48, 0.42–0.49 | 0.70–0.90, 0.60–1.00 | —, — | 0.80–1.10, 0.75–1.20 | —, — |
| 6150 | 0.48–0.53, 0.47–0.54 | 0.70–0.90, 0.60–1.00 | —, — | 0.80–1.10, 0.75–1.20 | —, — |
| **86XX** | | | | | |
| 8615 | 0.13–0.18, — | 0.70–0.90, — | 0.40–0.70, — | 0.40–0.60, — | 0.15–0.25, — |
| 8617 | 0.15–0.20, 0.14–0.20 | 0.70–0.90, 0.60–0.95 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8620 | 0.18–0.23, 0.17–0.23 | 0.70–0.90, 0.60–0.95 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8622 | 0.20–0.25, 0.19–0.25 | 0.70–0.90, 0.60–0.95 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8625 | 0.23–0.28, 0.22–0.28 | 0.70–0.90, 0.60–0.95 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8627 | 0.25–0.30, 0.24–0.30 | 0.70–0.90, 0.60–0.95 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8630 | 0.28–0.33, 0.27–0.33 | 0.70–0.90, 0.60–0.95 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8635 | 0.33–0.38, 0.32–0.38 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8637 | 0.35–0.40, 0.34–0.41 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8640 | 0.38–0.43, 0.37–0.44 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8641 [c] | 0.38–0.43, 0.37–0.44 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8642 | 0.40–0.45, 0.39–0.46 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8645 | 0.43–0.48, 0.42–0.49 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8650 | 0.48–0.53, 0.47–0.54 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8653 | 0.50–0.56, 0.49–0.56 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.50–0.80, 0.50–0.85 | 0.15–0.25, 0.15–0.25 |
| 8655 | 0.50–0.60, 0.50–0.60 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| 8660 | 0.55–0.65, 0.55–0.65 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.15–0.25, 0.15–0.25 |
| **87XX, 92XX** | | | | | |
| 8715 | 0.13–0.18, — | 0.70–0.90, — | 0.40–0.70, — | 0.40–0.60, — | 0.20–0.30, — |
| 8717 | 0.15–0.20, — | 0.70–0.90, — | 0.40–0.70, — | 0.40–0.60, — | 0.20–0.30, — |
| 8720 | 0.18–0.23, 0.17–0.23 | 0.70–0.90, 0.60–0.95 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.20–0.30, 0.20–0.30 |
| 8735 | 0.33–0.38, — | 0.75–1.00, — | 0.40–0.70, — | 0.40–0.60, — | 0.20–0.30, — |
| 8740 | 0.38–0.43, 0.37–0.44 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.20–0.30, 0.20–0.30 |
| 8742 | 0.40–0.45, 0.39–0.46 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.20–0.30, 0.20–0.30 |
| 8750 | 0.48–0.53, 0.47–0.54 | 0.75–1.00, 0.70–1.05 | 0.40–0.70, 0.35–0.75 | 0.40–0.60, 0.35–0.65 | 0.20–0.30, 0.20–0.30 |
| 9255 [d] | 0.50–0.60, — | 0.70–0.95, — | —, — | —, — | —, — |
| 9260 [d] | 0.55–0.65, 0.55–0.65 | 0.70–1.00, 0.65–1.10 | —, — | —, — | —, — |
| 9261 [d] | 0.55–0.65, 0.55–0.65 | 0.75–1.00, 0.65–1.10 | —, — | 0.10–0.25, 0.05–0.35 | —, — |
| 9262 [d] | 0.55–0.65, 0.55–0.65 | 0.75–1.00, 0.65–1.10 | —, — | 0.25–0.40, 0.20–0.50 | —, — |
| **93XX, 98XX** | | | | | |
| 9310 | —, 0.07–0.13 | —, 0.40–0.70 | —, 2.95–3.55 | —, 1.00–1.45 | —, 0.08–0.15 |
| E9310 | 0.08–0.13, — | 0.45–0.65, — | 3.00–3.50, — | 1.00–1.40, — | 0.08–0.15, — |
| E9314 | 0.11–0.17, — | 0.40–0.70, — | 3.00–3.50, — | 1.00–1.40, — | 0.08–0.15, — |
| 9840 | 0.38–0.43, 0.37–0.44 | 0.70–0.90, 0.60–0.95 | 0.85–1.15, 0.80–1.20 | 0.70–0.90, 0.65–0.95 | 0.20–0.30, 0.20–0.30 |
| 9845 | 0.43–0.48, — | 0.70–0.90, — | 0.85–1.15, — | 0.70–0.90, — | 0.20–0.30, — |
| 9850 | 0.48–0.53, 0.47–0.54 | 0.70–0.90, 0.60–0.95 | 0.85–1.15, 0.80–1.20 | 0.70–0.90, 0.65–0.95 | 0.20–0.30, 0.20–0.30 |

[a] Phosphorus and sulfur contents usually range between 0.025 and 0.040% for low alloy steels. Silicon content usually ranges between 0.20 and 0.35%. All steels except those prefixed by an "E" are open hearth; "E" steels are electric furnace. The two sets of ranges are for standard low alloy steels and H steels, respectively, and apply to bar, billets and blooms not exceeding 200 sq in. in cross-sectional area.

[b] These types contain the following amounts of vanadium: 6117 0.10 min, 6120 0.10 min, 6145 0.15 min and 6150 0.15% min.

[c] Sulfur content is 0.040–0.060%. [d] Silicon content is 1.80–2.20%.

## Low Alloy Steels—Wrought

**TYPICAL PHYSICAL PROPERTIES** [a]

| AISI Type → | 13XX | 23XX | 25XX | 40XX | 41XX | 43XX |
|---|---|---|---|---|---|---|
| Melting Temperature, F | — | 2600–2620 | 2610–2620 | — | — | 2740–2750 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 27 | 38.3[c] | 34.5–38.5[c] | 27 | 24.7[d] | 21.7[c] |
| Coef of Ther Exp (0–1200 F), per °F | $7.9 \times 10^{-6}$[b] | $8.0 \times 10^{-6}$ | $7.8 \times 10^{-6}$ | $8.3 \times 10^{-6}$[b] | — | $8.1 \times 10^{-6}$ |
| Specific Heat (68–212 F), Btu/lb/°F | 0.10–0.11 | 0.11–0.12 | 0.11–0.12 | 0.10–0.11 | 0.11 | 0.107 |
| Electrical Resistivity (68 F), microhm-cm | 17 | 28.4[c] | — | 19 | 22.3 | 30[c] |

[a] Density for all low alloy steels is approximately 0.28 lb per cu in. [b] 68–1200 F. [c] 120 F. [d] 68 F.

**TYPICAL MECHANICAL PROPERTIES** [a]

| AISI Type ↓ | Ten Str, 1000 psi | Yld Str (0.2% offset), 1000 psi | Elong (in 2 in.), % | Red. of Area, % | Hardness, Brinell | Impact Str (Izod), ft-lb |
|---|---|---|---|---|---|---|
| 1330[b] | 122 | 100 | 19 | 52 | 248 | — |
| 1335[c] | 126 | 105 | 20 | 59 | 262 | — |
| 1340[c] | 137 | 118 | 19 | 55 | 285 | — |
| 2317[c] | 107 | 72 | 27 | 71 | 222 | 84 |
| 2515[c] | 113 | 94 | 25 | 69 | 233 | 85 |
| E2517[c] | 120 | 100 | 22 | 66 | 244 | 80 |
| 4023[d] | 120 | 85 | 20 | 53 | 255 | — |
| 4032[e] | 210 | 182 | 11 | 49 | 415 | — |
| 4042[f] | 235 | 210 | 10 | 42 | 461 | — |
| 4053[g] | 250 | 223 | 12 | 40 | 495 | — |
| 4063[h] | 269 | 231 | 8 | 15 | 534 | — |
| 4130[i] | 200 | 170 | 16 | 49 | 375 | 25 |
| 4140[j] | 200 | 170 | 15 | 48 | 385 | 16 |
| 4150[k] | 230 | 215 | 10 | 40 | 444 | 12 |
| 4320[d] | 180 | 154 | 15 | 50 | 360 | 32 |
| 4337[k] | 210 | 140 | 14 | 50 | 435 | 18 |
| 4340[k] | 220 | 200 | 12 | 48 | 445 | 16 |
| 4615[d] | 100 | 75 | 18 | 52 | — | 42 |
| 4620[d] | 130 | 95 | 21 | 65 | — | 68 |
| 4640[i] | 185 | 160 | 14 | 52 | 390 | 25 |
| 4815[d] | 150 | 125 | 18 | 58 | 325 | 44 |
| 4817[d] | — | — | 15 | 52 | 355 | 36 |
| 4820[j] | — | — | 13 | 47 | 380 | 28 |
| 5120[d] | 143 | 114 | 13 | 45 | 302 | 6 |
| 5130[m] | 189 | 175 | 13 | 51 | 380 | — |
| 5140[m] | 190 | 170 | 13 | 43 | 375 | 16 |
| 5150[m] | 224 | 208 | 10 | 40 | 444 | — |
| 6120[n] | 125 | 94 | 21 | 56 | — | 28 |
| 6145[o] | 176 | 169 | 16 | 52 | 429 | 20 |
| 6150[o] | 187 | 179 | 13 | 42 | 444 | 13 |
| 8620[p] | 122 | 98 | 21 | 63 | 245 | 76 |
| 8630[p] | 162 | 142 | 14 | 54 | 325 | 42 |
| 8640[p] | 208 | 183 | 13 | 43 | 420 | 18 |
| 8650[p] | 214 | 194 | 12 | 41 | 423 | — |
| 8720[p] | 122 | 98 | 21 | 63 | 245 | 76 |
| 8740[p] | 208 | 183 | 13 | 43 | 420 | 18 |
| 8750[p] | 214 | 194 | 12 | 41 | 423 | — |
| 9255[p] | 232[q] | 215 | 9 | 21 | 477 | 6 |
| 9261[p] | 258[r] | 226 | 10 | 30 | 514 | 12 |

[a] Properties are for materials hardened and tempered as follows: [b] water quenched from 1525 F, tempered at 1000 F; [c] oil quenched from 1525 F, tempered at 1000 F; [d] pseudo-carburized 8 hr at 1700 F, oil quenched, tempered 1 hr at 300 F; [e] water quenched from 1525 F, tempered at 600 F; [f] oil quenched from 1500 F, tempered at 600 F; [g] oil quenched from 1475 F, tempered at 600 F; [h] oil quenched from 1450 F, tempered at 600 F; [i] water quenched from 1550–1600 F, tempered at 800 F; [j] oil quenched from 1550 F, tempered at 800 F; [k] oil quenched from 1525 F, tempered at 800 F; [l] normalized at 1650 F, reheated to 1475 F, oil quenched, tempered at 800 F; [m] normalized at 1625 F, reheated to 1550 F, water quenched, tempered at 800 F; [n] carburized 10 hr at 1680 F, pot cooled, oil quenched from 1525 F, tempered at 300 F; [o] normalized at 1600 F, oil quenched from 1575 F, tempered at 1000 F; [p] oil quenched, tempered at 800 F; [q] normalized at 1650 F, reheated to 1625 F, quenched in agitated oil, tempered at 800 F; [r] normalized at 1600 F, reheated to 1575 F, quenched in agitated oil, tempered at 800 F.

**TYPICAL PHYSICAL PROPERTIES [a] (continued)**

| AISI Type → | 46XX | 48XX | 51XX | 61XX | 86, 87XX | 92, 94XX |
|---|---|---|---|---|---|---|
| Melting Temperature, F | — | 2750 | 2720–2760 | — | 2745–2755 | — |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 27[d] | 26.0[f] | 27–34[g] | 27 | 21.7[c] | 27 |
| Coef of Ther Exp (0–1200 F), per °F | 6.3 x $10^{-6}$[c] | 8.6 x $10^{-6}$ | 7.4 x $10^{-6}$[h] | 8.1 x $10^{-6}$[h] | 8.2 x $10^{-6}$ | 8.1 x $10^{-6}$[h] |
| Specific Heat (68–212 F), Btu/lb/°F | 0.10–0.11 | — | 0.10–0.11 | 0.10–0.11 | 0.107 | 0.10–0.12 |
| Electrical Resistivity (68 F), microhm-cm | — | 30 | 21 | 21 | 30[c] | 19–20 |

[a] Density for all steels is approximately 0.28 lb per cu in. [b] 68–1200 F. [c] 120 F. [d] 68 F. [e] 0–200 F. [f] 75 F. [g] 32–212 F. [h] 100–518 F.

**MACHINABILITY, WELDABILITY, AVAILABILITY, USES [a]**

| AISI Type ↓ | Mach Index[b] | Weldability | Available Forms | Uses |
|---|---|---|---|---|
| 1330<br>1335<br>1340 | 62<br>62<br>59 | Mn increases crack sensitivity and care must be taken | Billets, bars, forgings | Automotive, farm implements: axles, shafts, bolts, studs, gears, tie rods |
| 2317 | 55 | Good by most commercial procedures | Bar, forgings | Carburized gears, cams |
| 2515<br>E2517 | 40<br>— | | Bar, forgings, tubing; also mill forms | Heavy duty carburized parts: aircraft gears, piston pins |
| 4023<br>4032<br>4042<br>4053<br>4063 | 73<br>70<br>65<br>56<br>52 | Weldable by procedures used for carbon steels; preheating or postheating sometimes necessary | All standard mill forms | Automotive parts such as countershafts, differential gears, transmission gears and shafts, leaf and coil springs, bolts, axles, steering arms; also hand tools |
| 4130<br>4140<br>4150 | 60<br>62<br>45 | Weldable by all procedures; difficulty increases with carbon content | All standard mill forms | Arbors, gears, shafts, bushings, axles, aircraft fuselage, bolts, clutch parts, machine tool parts |
| 4320<br>4337<br>4340 | 51<br>51<br>51 | Readily weldable by oxyacetylene, inert arc and electrical resistance methods | Bar, forgings, tubing, billets; also mill forms | Heavy duty, high strength parts: gears, bearing races, aircraft tubing, shafts, heavy forgings, churn drills |
| 4615<br>4620 | 58–60<br>58–60 | Weldable by all procedures | All standard mill forms | Arbors, ball bearings, gears, spindles, camshafts, leaf and coil springs, shovels |
| 4815, 4817, 4820 | 45 | Ordinarily not welded | Billets, bar, tubing, forgings, plate | Heavy duty gears, rock bits, pump parts, sucker rods, machine tools |
| 5120<br>5130<br>5140<br>5150 | 65<br>67<br>60<br>55 | Weldable by oxyacetylene, inert arc and electrical resistance methods | Bar, rod, tubing, forgings, castings | Transmission gears, steering knuckles, side gears, shafts, axles, coil and flat springs |
| 6120<br>6145<br>6150 | 46<br>27<br>26 | Weldable by all commercial methods | All standard mill forms | Carburized gears, shafts, pistons; springs, axles, pins, connecting rods |
| 8620, 8720<br>8630<br>8640, 8740<br>8650, 8750 | 57<br>61<br>55<br>45 | Weldable by oxyacetylene, inert arc and electrical resistance methods; preheating desirable for grades with more than 0.30% carbon | Usually supplied as bar, forgings, tubing or billet; sometimes in other mill forms | Medium and heavy duty carburized gears, cams, bearing races; also heavy duty bolts, aircraft tubing, hand tools, shafts, forgings |
| 9255<br>9261 | 38<br>36 | Not normally recommended | Billets, bar, forgings | Coil and flat springs, axles, chisels, bolts |

[a] In general, corrosion resistance of these steels ranges from about the same to slightly better than carbon steels.
[b] Based on AISI B1112 steel = 100.

## H Steels—Wrought

**END QUENCH HARDENABILITY BAND LIMITS** [a]

| AISI Type ↓ | "J" Distance, in. | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 1/8 | 1/4 | 3/8 | 1/2 | 5/8 | 3/4 | 7/8 | 1 | 1 1/8 | 1 1/4 | 1 3/8 | 1 1/2 | 1 5/8 | 1 3/4 | 1 7/8 | 2 |
| **13XX** | | | | | | | | | | | | | | | | |
| 1330 H[b] | 56–47 | 53–40 | 50–31 | 45–26 | 42–23 | 39–21 | 37 max | 35 max | 34 max | 33 max | 32 max | 31 max | 31 max | 31 max | 30 max | 30 max |
| 1335 H[c] | 57–49 | 55–44 | 52–34 | 48–29 | 44–26 | 41–24 | 39–22 | 37–21 | 35–20 | 34 max | 33 max | 32 max | 31 max | 31 max | 30 max | 30 max |
| 1340 H[c] | 60–52 | 58–49 | 56–40 | 54–33 | 51–29 | 48–27 | 44–25 | 41–24 | 39–23 | 38–23 | 37–22 | 36–22 | 35–21 | 35–21 | 34–20 | 34–20 |
| **25XX** | | | | | | | | | | | | | | | | |
| 2515 H[d] | 44–37 | 42–30 | 40–24 | 37–20 | 34 max | 31 max | 29 max | 28 max | 27 max | 26 max | 25 max | 24 max | 24 max | 23 max | 23 max | 22 max |
| 2517 H[d] | 46–38 | 45–31 | 43–25 | 41–21 | 37 max | 34 max | 32 max | 31 max | 30 max | 29 max | 28 max | 27 max | 27 max | 26 max | 26 max | 25 max |
| **31XX** | | | | | | | | | | | | | | | | |
| 3120 H[c] | 47–39 | 42–30 | 35–23 | 30–20 | 28 max | 27 max | 26 max | 25 max | 24 max | 23 max | 23 max | 22 max | 22 max | 21 max | 21 max | 21 max |
| 3130 H[b] | 55–47 | 52–42 | 49–34 | 45–30 | 41–28 | 38–25 | 35–24 | 34–22 | 33–21 | 32–20 | 32 max | 31 max | 31 max | 31 max | 30 max | 30 max |
| 3135 H[c] | 57–50 | 55–47 | 53–41 | 50–35 | 48–33 | 44–30 | 39–28 | 37–26 | 36–25 | 35–23 | 34–22 | 34–20 | 34 max | 34 max | 33 max | 33 max |
| 3140 H[c] | 60–52 | 59–49 | 57–45 | 56–41 | 54–36 | 52–33 | 50–31 | 48–30 | 46–29 | 44–28 | 43–28 | 42–27 | 41–27 | 40–26 | 40–26 | 39–25 |
| **33XX** | | | | | | | | | | | | | | | | |
| 3310 H[d] | 43–36 | 42–35 | 42–33 | 41–31 | 40–30 | 40–29 | 39–28 | 38–27 | 37–26 | 37–26 | 37–26 | 36–26 | 36–25 | 36–25 | 35–25 | 35–25 |
| 3316 H[d] | 47–39 | 46–38 | 46–37 | 45–35 | 45–33 | 45–32 | 44–32 | 44–31 | 44–31 | 43–31 | 43–31 | 43–31 | 42–31 | 42–30 | 42–30 | 41–30 |
| **40XX** | | | | | | | | | | | | | | | | |
| 4032 H[b] | 54–45 | 46–29 | 34–23 | 29–21 | 26 max | 25 max | 24 max | 23 max | 23 max | 22 max | 22 max | 21 max | 21 max | 20 max | — | — |
| 4037 H[c] | 57–49 | 51–35 | 38–26 | 32–22 | 29–20 | 27 max | 26 max | 25 max | 25 max | 25 max | 25 max | 24 max | 24 max | 24 max | 23 max | 23 max |
| 4042 H[c] | 60–52 | 55–40 | 45–29 | 36–26 | 33–24 | 31–23 | 30–23 | 29–22 | 28–22 | 28–21 | 28–20 | 27–20 | 27 max | 27 max | 26 max | 26 max |
| 4047 H[c] | 62–55 | 58–42 | 52–32 | 43–28 | 38–27 | 35–26 | 33–25 | 32–25 | 31–24 | 30–24 | 30–23 | 30–23 | 30–22 | 29–22 | 29–21 | 29–21 |
| 4053 H[c] | 65–59 | 62–53 | 59–38 | 55–32 | 47–30 | 42–29 | 38–28 | 36–28 | 34–27 | 33–27 | 33–27 | 32–26 | 32–26 | 32–26 | 31–25 | 31–25 |
| 4063 H[c] | 60 min | 65–56 | 64–39 | 61–35 | 57–33 | 51–32 | 46–31 | 43–31 | 41–30 | 40–30 | 39–29 | 38–29 | 38–28 | 37–28 | 37–27 | 36–27 |
| 4068 H[c] | 60 min | 59 min | 64–45 | 62–36 | 58–34 | 52–33 | 47–32 | 44–32 | 42–31 | 41–31 | 40–30 | 39–30 | 38–29 | 38–29 | 38–28 | 37–28 |
| **41XX** | | | | | | | | | | | | | | | | |
| 4118 H[c] | 46–36 | 35–23 | 28 max | 25 max | 23 max | 21 max | 20 max | — | — | — | — | — | — | — | — | — |
| 4130 H[b] | 55–46 | 51–38 | 47–31 | 42–27 | 38–26 | 35–25 | 34–24 | 33–23 | 32–22 | 32–21 | 32–20 | 31 max | 31 max | 30 max | 30 max | 29 max |
| 4135 H[c] | 58–50 | 56–48 | 55–45 | 53–40 | 51–36 | 49–33 | 47–31 | 45–30 | 44–29 | 42–28 | 41–27 | 40–27 | 39–27 | 38–26 | 38–26 | 37–26 |
| 4137 H[c] | 59–51 | 58–49 | 57–48 | 55–43 | 54–39 | 52–36 | 50–34 | 48–33 | 46–32 | 45–31 | 44–30 | 43–30 | 42–30 | 42–29 | 41–29 | 41–29 |
| 4140 H[c] | 60–53 | 59–51 | 58–50 | 57–47 | 56–42 | 55–39 | 54–37 | 53–35 | 52–34 | 51–33 | 49–33 | 48–32 | 47–32 | 46–31 | 45–31 | 44–30 |
| 4142 H[c] | 62–55 | 61–53 | 61–52 | 60–50 | 59–47 | 58–44 | 57–41 | 56–39 | 55–37 | 54–36 | 53–35 | 53–34 | 52–34 | 51–34 | 51–33 | 50–33 |
| 4145 H[c] | 63–55 | 62–54 | 61–53 | 61–52 | 60–50 | 59–48 | 59–45 | 58–42 | 57–40 | 57–38 | 56–37 | 55–36 | 55–35 | 55–35 | 55–34 | 54–34 |
| 4147 H[c] | 64–57 | 64–56 | 63–55 | 63–54 | 62–53 | 62–51 | 61–48 | 60–45 | 59–42 | 59–40 | 58–39 | 57–38 | 57–37 | 57–37 | 56–37 | 56–36 |
| 4150 H[c] | 65–59 | 65–58 | 65–57 | 64–56 | 64–55 | 63–53 | 62–50 | 62–47 | 61–45 | 60–43 | 59–41 | 59–40 | 58–39 | 58–38 | 58–38 | 58–38 |
| **43XX** | | | | | | | | | | | | | | | | |
| 4320 H[c] | 47–38 | 43–32 | 38–27 | 34–23 | 31–21 | 29–20 | 27 max | 26 max | 25 max | 25 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max |
| 4337 H[c] | 59–52 | 59–52 | 58–51 | 58–51 | 57–50 | 57–49 | 57–47 | 57–46 | 56–44 | 56–42 | 55–41 | 55–40 | 55–39 | 54–39 | 54–39 | 53–39 |
| 4340 H[c] | 60–53 | 60–53 | 60–53 | 60–52 | 60–52 | 59–51 | 58–49 | 58–48 | 58–47 | 57–46 | 57–45 | 57–44 | 57–43 | 56–42 | 56–41 | 56–40 |
| E4340 H[c] | 60–53 | 60–53 | 60–53 | 60–53 | 60–53 | 60–53 | 59–52 | 59–51 | 58–51 | 58–50 | 58–49 | 57–48 | 57–47 | 57–46 | 57–45 | 57–44 |
| **46XX** | | | | | | | | | | | | | | | | |
| 4620 H[c] | 45–35 | 39–24 | 31 max | 27 max | 25 max | 23 max | 22 max | 21 max | 21 max | 20 max | — | — | — | — | — | — |
| 4621 H[c] | 47–38 | 44–30 | 37–25 | 32–22 | 28 max | 26 max | 25 max | 24 max | 24 max | 23 max | 23 max | 22 max | 22 max | 22 max | 21 max | 21 max |
| 4640 H[c] | 60–52 | 58–50 | 56–44 | 53–37 | 49–32 | 44–29 | 41–27 | 39–27 | 38–26 | 37–26 | 36–26 | 35–25 | 35–25 | 34–25 | 34–24 | 33–24 |
| **47XX,48XX** | | | | | | | | | | | | | | | | |
| 4720 H[c] | 47–39 | 39–27 | 32–21 | 28 max | 26 max | 24 max | 23 max | 22 max | 21 max | 21 max | 21 max | 20 max | — | — | — | — |
| 4812 H[d] | 43–34 | 41–26 | 37–21 | 33 max | 29 max | 27 max | 25 max | 24 max | 24 max | 23 max | 23 max | 22 max | 22 max | 21 max | 21 max | 21 max |
| 4815 H[d] | 44–37 | 42–30 | 39–24 | 35–21 | 31 max | 29 max | 28 max | 27 max | 26 max | 25 max | 24 max | 24 max | 24 max | 23 max | 23 max | 23 max |
| 4817 H[d] | 46–38 | 44–32 | 41–27 | 37–23 | 33–21 | 31–20 | 29 max | 28 max | 27 max | 26 max | 25 max | 25 max | 25 max | 25 max | 24 max | 24 max |
| 4820 H[d] | 48–40 | 46–38 | 43–31 | 40–27 | 37–25 | 35–23 | 33–22 | 31–21 | 29–20 | 28–20 | 28 max | 27 max | 27 max | 26 max | 26 max | 25 max |

[a] Rockwell C hardness value and distance from quenched end of standard end quench hardenability band. Range indicates maximum and minimum values. Steels heat treated as follows: [b] normalized at 1650 F, austenitized at 1600 F; [c] normalized at 1600 F, austenitized at 1550 F; [d] normalized at 1700 F, austenitized at 1550 F; [e] normalized at 1700 F, austenitized at 1700 F.

**END QUENCH HARDENABILITY BAND LIMITS [a] (continued)**

| AISI Type ↓ | "J" Distance, in. | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 1/16 | 1/8 | 3/16 | 1/4 | 5/16 | 3/8 | 7/16 | 1/2 | 5/8 | 3/4 | 7/8 | 1 | 1 1/8 | 1 1/4 | 1 3/8 | 1 1/2 |
| **50XX,51XX** | | | | | | | | | | | | | | | | |
| 5046 H[c] | 62–55 | 56–32 | 46–27 | 35–25 | 33–24 | 32–23 | 31–22 | 30–21 | 29–20 | 28 max | 27 max | 26 max | 25 max | 24 max | 23 max | 23 max |
| 5120 H[c] | 46–34 | 36–23 | 30 max | 27 max | 24 max | 22 max | 21 max | — | — | — | — | — | — | — | — | — |
| 5130 H[b] | 55–46 | 51–39 | 47–32 | 42–28 | 38–25 | 36–22 | 34–20 | 33 max | 32 max | 31 max | 30 max | 29 max | 27 max | 26 max | 25 max | 24 max |
| 5132 H[b] | 56–47 | 52–40 | 48–32 | 42–27 | 38–24 | 36–22 | 34–20 | 33 max | 32 max | 31 max | 30 max | 29 max | 28 max | 27 max | 26 max | 25 max |
| 5135 H[c] | 57–49 | 55–43 | 52–35 | 47–30 | 43–27 | 40–24 | 38–22 | 37–21 | 36–20 | 35 max | 34 max | 33 max | 32 max | 32 max | 31 max | 30 max |
| 5140 H[c] | 59–52 | 57–48 | 54–38 | 50–33 | 46–30 | 43–28 | 40–27 | 38–25 | 37–24 | 36–23 | 35–21 | 34–20 | 34 max | 33 max | 33 max | 32 max |
| 5145 H[c] | 62–55 | 60–51 | 58–42 | 56–35 | 53–32 | 50–30 | 47–29 | 44–28 | 42–26 | 41–25 | 39–24 | 38–23 | 37–22 | 37–21 | 36 max | 35 max |
| 5147 H[c] | 64–56 | 62–54 | 61–52 | 60–45 | 59–37 | 58–34 | 57–32 | 56–31 | 55–30 | 54–29 | 53–27 | 52–26 | 51–25 | 50–24 | 49–22 | 48–21 |
| 5150 H[c] | 65–58 | 63–56 | 61–49 | 59–38 | 56–34 | 53–32 | 50–31 | 47–30 | 45–29 | 43–28 | 42–27 | 41–26 | 40–25 | 39–24 | 39–23 | 38–22 |
| 5152 H[c] | 65–58 | 64–57 | 63–55 | 62–51 | 60–45 | 59–39 | 58–37 | 57–35 | 56–34 | 55–32 | 53–31 | 51–30 | 50–29 | 48–27 | 47–26 | 45–25 |
| 5160 H[c] | 60 min | 65–59 | 64–56 | 63–47 | 61–39 | 59–36 | 56–35 | 52–34 | 48–33 | 47–32 | 46–31 | 45–30 | 44–29 | 43–28 | 43–28 | 42–27 |
| **61XX** | | | | | | | | | | | | | | | | |
| 6120 H[c] | 47–38 | 42–29 | 36–24 | 33–22 | 31–21 | 31–20 | 30 max | 29 max | 28 max | 28 max | 27 max | 26 max | 25 max | 25 max | 24 max | 23 max |
| 6145 H[b] | 63–55 | 62–54 | 61–49 | 59–42 | 57–38 | 55–36 | 52–35 | 50–33 | 49–32 | 48–31 | 47–30 | 46–29 | 45–27 | 44–26 | 43–25 | 42–24 |
| 6150 H[b] | 65–58 | 64–56 | 63–53 | 61–47 | 60–41 | 58–38 | 55–36 | 52–35 | 50–34 | 48–32 | 47–31 | 46–30 | 45–29 | 44–27 | 43–26 | 42–25 |
| **86XX** | | | | | | | | | | | | | | | | |
| 8617 H[c] | 44–33 | 38–24 | 31 max | 27 max | 25 max | 23 max | 22 max | 21 max | 21 max | 20 max | — | — | — | — | — | — |
| 8620 H[c] | 47–37 | 41–27 | 34–21 | 30 max | 28 max | 26 max | 25 max | 24 max | 23 max | 23 max | 23 max | 23 max | 23 max | 22 max | 22 max | 22 max |
| 8622 H[c] | 49–39 | 44–30 | 37–24 | 32–20 | 30 max | 28 max | 26 max | 25 max | 25 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max |
| 8625 H[b] | 51–41 | 46–32 | 40–27 | 35–23 | 32–21 | 30 max | 28 max | 27 max | 27 max | 26 max | 26 max | 26 max | 26 max | 25 max | 25 max | 25 max |
| 8627 H[b] | 52–43 | 48–35 | 43–29 | 38–26 | 34–24 | 32–22 | 30–21 | 29–20 | 28 max | 28 max | 28 max | 27 max | 27 max | 27 max | 27 max | 27 max |
| 8630 H[b] | 55–46 | 52–39 | 47–32 | 41–28 | 37–26 | 34–24 | 33–22 | 31–21 | 30–21 | 30–20 | 29–20 | 29 max | 29 max | 29 max | 29 max | 29 max |
| 8635 H[c] | 57–49 | 55–45 | 53–39 | 50–33 | 46–30 | 43–28 | 40–26 | 37–25 | 36–24 | 35–23 | 34–23 | 33–23 | 33–23 | 33–22 | 32–22 | 32–22 |
| 8637 H[c] | 58–51 | 57–48 | 55–42 | 53–36 | 49–32 | 46–30 | 43–28 | 40–26 | 39–25 | 37–25 | 36–24 | 36–24 | 35–24 | 35–24 | 35–23 | 35–23 |
| 8640 H, 8641 H[c] | 60–53 | 59–51 | 58–46 | 55–39 | 52–34 | 49–31 | 45–29 | 42–28 | 41–26 | 39–26 | 38–25 | 38–25 | 37–24 | 37–24 | 37–24 | 37–24 |
| 8642 H[c] | 62–54 | 61–52 | 60–48 | 58–42 | 55–37 | 52–33 | 49–31 | 46–29 | 44–28 | 42–28 | 41–27 | 40–27 | 40–26 | 39–26 | 39–26 | 39–26 |
| 8645 H[c] | 63–56 | 63–54 | 61–50 | 60–45 | 58–39 | 55–35 | 52–33 | 49–31 | 47–30 | 45–29 | 43–28 | 42–28 | 42–27 | 41–27 | 41–27 | 41–27 |
| 8650 H[c] | 65–58 | 64–57 | 63–54 | 62–50 | 60–44 | 59–39 | 58–36 | 56–34 | 55–33 | 53–32 | 52–31 | 50–31 | 49–30 | 47–30 | 46–29 | 45–29 |
| 8653 H[c] | 65–59 | 65–58 | 64–57 | 64–56 | 63–53 | 62–47 | 62–44 | 61–42 | 61–40 | 60–39 | 59–38 | 59–37 | 59–36 | 59–35 | 58–35 | 58–34 |
| 8655 H[c] | 59 min | 58 min | 56 min | 54 min | 65–49 | 64–43 | 63–40 | 62–38 | 61–37 | 60–35 | 59–34 | 58–34 | 57–33 | 56–33 | 55–32 | 53–32 |
| 8660 H[c] | 60 min | 60 min | 59 min | 57 min | 53 min | 47 min | 44 min | 65–42 | 64–40 | 64–39 | 63–38 | 62–37 | 62–36 | 61–36 | 60–35 | 60–35 |
| **87XX** | | | | | | | | | | | | | | | | |
| 8720 H[c] | 47–38 | 42–30 | 35–24 | 31–21 | 29 max | 27 max | 26 max | 25 max | 24 max | 24 max | 23 max | 23 max | 23 max | 23 max | 22 max | 22 max |
| 8740 H[c] | 60–53 | 60–51 | 58–46 | 56–40 | 53–35 | 50–32 | 48–31 | 45–29 | 43–28 | 42–28 | 41–27 | 40–27 | 39–27 | 39–27 | 38–26 | 38–26 |
| 8742 H[c] | 62–55 | 61–53 | 60–49 | 58–44 | 56–39 | 53–35 | 51–33 | 48–31 | 46–30 | 45–29 | 43–29 | 42–28 | 42–28 | 41–28 | 41–28 | 40–27 |
| 8750 H[c] | 65–59 | 64–57 | 63–56 | 62–53 | 61–49 | 60–45 | 59–42 | 58–39 | 57–37 | 55–35 | 53–34 | 52–33 | 51–33 | 50–32 | 49–32 | 48–32 |
| **92XX** | | | | | | | | | | | | | | | | |
| 9260 H[b] | 60 min | 64–53 | 62–41 | 58–36 | 52–35 | 47–34 | 43–33 | 40–32 | 38–31 | 37–31 | 36–30 | 36–30 | 35–29 | 35–29 | 35–28 | 34–28 |
| 9261 H[b] | 60 min | 65–59 | 64–52 | 63–42 | 60–37 | 54–36 | 45–35 | 42–34 | 39–33 | 38–32 | 37–31 | 37–31 | 36–30 | 36–30 | 35–29 | 35–29 |
| 9262 H[b] | 60 min | 60 min | 65–56 | 64–48 | 62–39 | 59–37 | 55–36 | 48–35 | 45–34 | 43–33 | 41–33 | 39–32 | 38–31 | 37–31 | 36–30 | 36–30 |
| **93XX,98XX** | | | | | | | | | | | | | | | | |
| 9310 H[d] | 43–35 | 42–34 | 42–31 | 41–29 | 40–27 | 38–26 | 36–26 | 35–26 | 35–26 | 35–25 | 34–25 | 34–25 | 34–25 | 34–25 | 33–24 | 33–24 |
| 9840 H[c] | 60–53 | 60–53 | 60–53 | 60–52 | 59–51 | 58–48 | 58–45 | 57–43 | 56–41 | 55–39 | 55–38 | 55–36 | 54–36 | 54–35 | 53–34 | 53–34 |
| 9850 H[c] | 65–59 | 65–59 | 65–59 | 65–58 | 65–58 | 65–58 | 64–57 | 64–56 | 63–54 | 62–52 | 62–50 | 61–49 | 61–48 | 61–47 | 60–47 | 60–47 |

| AISI Type ↓ | "J" Distance, in. | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 1 5/8 | 1 3/4 | 1 7/8 | 2 | 2 1/8 | 2 1/4 | 2 3/8 | 2 1/2 | 2 5/8 | 2 3/4 | 2 7/8 | 3 | 3 1/8 | 3 1/4 | 3 3/8 | 3 1/2 |
| **50XX,51XX** | | | | | | | | | | | | | | | | |
| 5046 H[c] | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max |
| 5120 H[c] | — | — | — | — | — | — | — | — | — | — | — | — | — | — | — | — |
| 5130 H[b] | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max |
| 5132 H[b] | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max |
| 5135 H[c] | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max | 30 max |
| 5140 H[c] | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max | 32 max |
| 5145 H[c] | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max | 35 max |
| 5147 H[c] | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 | 48–21 |
| 5150 H[c] | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 | 38–22 |
| 5152 H[c] | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 | 45–25 |
| 5160 H[c] | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 | 42–27 |
| **61XX** | | | | | | | | | | | | | | | | |
| 6120 H[c] | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max | 23 max |
| 6145 H[b] | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 | 42–24 |
| 6150 H[b] | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 | 42–25 |
| **86XX** | | | | | | | | | | | | | | | | |
| 8617 H[c] | — | — | — | — | — | — | — | — | — | — | — | — | — | — | — | — |
| 8620 H[c] | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max |
| 8622 H[c] | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max | 24 max |
| 8625 H[b] | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max | 25 max |
| 8627 H[b] | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max | 27 max |
| 8630 H[b] | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max | 29 max |
| 8635 H[c] | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 | 32–22 |
| 8637 H[c] | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 | 35–23 |
| 8640 H, 8641 H[c] | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 | 37–24 |
| 8642 H[c] | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 | 39–26 |
| 8645 H[c] | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 | 41–27 |
| 8650 H[c] | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 | 45–29 |
| 8653 H[c] | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 | 58–34 |
| 8655 H[c] | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 | 53–32 |
| 8660 H[c] | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 | 60–35 |
| **87XX** | | | | | | | | | | | | | | | | |
| 8720 H[c] | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max | 22 max |
| 8740 H[c] | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 | 38–26 |
| 8742 H[c] | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 | 41–28 |
| 8750 H[c] | 49–32 | 49–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 | 48–32 |
| **92XX** | | | | | | | | | | | | | | | | |
| 9260 H[b] | 35–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 | 34–28 |
| 9261 H[b] | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 | 35–29 |
| 9262 H[b] | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 | 36–30 |
| **93XX,98XX** | | | | | | | | | | | | | | | | |
| 9310 H[d] | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 | 33–24 |
| 9840 H[c] | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 | 53–34 |
| 9850 H[c] | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 | 60–47 |

[a] Rockwell C hardness value and distance from quenched end of standard end quench hardenability band. Range indicates maximum and minimum values. Steels heat treated as follows: [b] normalized at 1650 F, austenitized at 1600 F; [c] normalized at 1600 F, austenitized at 1550 F; [d] normalized at 1700 F, austenitized at 1550 F; [e] normalized at 1700 F, austenitized at 1700 F.

## Austenitic Stainless Steels—Wrought

| AISI Type → | 201 | 202 |
|---|---|---|
| COMPOSITION, % | C 0.15 max, Mn 5.5–7.5, Cr 16.0–18.0, Ni 3.5–5.5, N 0.25 max | C 0.15 max, Mn 7.5–10.0, Cr 17.0–19.0, Ni 4.0–6.0, N 0.25 max |
| PHYSICAL PROPERTIES | | |
| Density, lb/cu in. | 0.28 | 0.28 |
| Ther Cond (68–212 F), Btu/hr/sq ft/°F/ft | 9.4 | 9.4 |
| Coef of Ther Exp, per °F | | |
| 32 to 200 F | 8.78 x $10^{-6}$ | — |
| 32 to 600 F | 9.7 x $10^{-6}$ | 10.2 x $10^{-6}$ |
| 32 to 900 F | 10.1 x $10^{-6}$ | 10.6 x $10^{-6}$ |
| 32 to 1400 F | — | 11.3 x $10^{-6}$ |
| Specific Heat, Btu/lb/°F | 0.12 | 0.12 |
| Electrical Resistivity (68 F), microhm-cm | 69 | 69 |
| Magnetic? | No | No |
| Magnetic Permeability (max) | 1.02 | 1.02 |
| MECHANICAL PROPERTIES | | |
| Mod of Elast in Tension, psi | 28.6 x $10^6$ | 28 x $10^6$ |
| Tensile Strength, 1000 psi | | |
| Annealed[a] | | |
| Tested at Rm Temp | 115, 114, 95[b] | 105, — |
| Tested at 1200 F | —, 50 | — |
| Tested at 1400 F | —, 37 | — |
| Cold Worked[c] | | |
| Quarter Hard | 125 | — |
| Half Hard | 150 | — |
| Yield Strength, 1000 psi | | |
| Annealed[a] | | |
| Tested at Rm Temp | 55, 53 47[b] | 55, — |
| Tested at 1200 F | —, 21 | — |
| Tested at 1400 F | —, 19 | — |
| Cold Worked[c] | | |
| Quarter Hard | 75 | — |
| Half Hard | 110 | — |
| Elongation (in 2 in.), % | | |
| Annealed[a] | | |
| Tested at Rm Temp | 55, 57, 60[b] | 55, — |
| Tested at 1200 F | —, 36 | — |
| Tested at 1400 F | —, 38 | — |
| Cold Worked[c] | | |
| Quarter Hard | 25 | — |
| Half Hard | 15 | — |
| Hardness (Rockwell, annealed) | B90 | B90 |
| Rupture Stress (annealed, 1000 hr), 1000 psi | | |
| Tested at 1200 F | 22.0 | — |
| Tested at 1400 F | 7.0 | — |
| THERMAL TREATMENT | | |
| Annealing Temp, F | 1850–2050 | 1850–2050 |
| FABRICATING PROPERTIES | | |
| Hot Working Temp Range, F | 2100–2250 | 2100–2250 |
| Formability | Moderate; similar to type 301 | Good; similar to type 302 |
| Machinability | Good | Good |
| Weldability | Similar to type 301; normally spot welded | Similar to type 302 |
| CORROSION RESISTANCE | Good; similar to type 301 | Good; similar to types 302, 304 |
| AVAILABLE FORMS | Sheet, strip, some bar | Rod, bar, sheet, strip, plate |
| USES | Alternate for type 301, but tests should be made if severe corrosion conditions exist | Alternate for type 302, but tests should be made if severe corrosion conditions exist |

[a] Where two values are given, they represent sheet and bar respectively.
[b] Welded and annealed.
[c] Minimum value for sheet tested at room temperature.

## Austenitic Stainless Steels—Wrought

| AISI Type → | 301 | 302 | 303 | 304, 304L |
|---|---|---|---|---|
| COMPOSITION, % | C 0.08–0.20, Mn 2 max, Si 1 max, P 0.04 max, S 0.03 max, Cr 16–18, Ni 6–8 | C 0.08–0.20, Mn 2 max, Si 1 max, P 0.04 max, S 0.03 max, Cr 17–19, Ni 8–10 | C 0.15 max, Mn 2 max, P, S or Se 0.07 min, Si 1 max, Cr 17–19, Ni 8–10, Mo or Zr 0.60 max | C 0.08 max (304) or 0.03 max (304L), Mn 2 max, Si 1 max, P 0.04 max, S 0.030 max, Cr 18–20, Ni 8–11 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.29 | 0.29 | 0.29 | 0.29 |
| Melting Point Range, F | 2550–2590 | 2550–2590 | 2550–2590 | 2550–2650 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 9.4 | 9.4 | 9.4 | 9.4 |
| Coef of Ther Exp (32–212 F), per °F | 9.5 x 10⁻⁶[a] | 9.9 x 10⁻⁶ | 9.9 x 10⁻⁶ | 9.9 x 10⁻⁶ |
| Spec Ht (32–212 F), Btu/lb/°F | 0.12 | 0.12 | 0.12 | 0.12 |
| Elec Res (68 F), microhm-cm | 72 | 72 | 72 | 72 |
| MECHANICAL PROPERTIES[b] | | | | |
| Mod of Elast in Tension, psi | 28.0 x 10⁶ | 28.0 x 10⁶ | 28.0 x 10⁶ | 28.0 x 10⁶ |
| Ten Str, 1000 psi | | | | |
| Annealed | 110, 105, — | 90, 90, 85 | —, —, 90 | 85, 85, 85 |
| Cold Worked[d] | 185, —, — | —, —, 110[c] | —, —, 110[c] | —, —, 110[c] |
| Yld Str, 1000 psi | | | | |
| Annealed | 40, 40, — | 40, 35, 35 | —, —, 35 | 35, 30, 35 |
| Cold Worked[d] | 140, —, — | —, —, 75[c] | —, —, 75[c] | —, —, 75[c] |
| Elong (in 2 in.), % | | | | |
| Annealed | 60, 55, — | 50, 60, 60 | —, —, 50 | 50, 60, 60 |
| Cold Worked[d] | 8–9, —, — | —, —, 35[c] | —, —, 30[c] | —, —, 60 |
| Red. of Area, % | | | | |
| Annealed | —, 70, — | —, 70, 70 | —, —, 55 | —, 70, 70 |
| Cold Worked | — | —, —, 60[c] | —, —, 50[c] | — |
| Hardness[e] | | | | |
| Annealed | $R_B$85, —, — | $R_B$85, $R_B$80, 150 | —, —, 160 | $R_B$80, 150, 150 |
| Cold Worked | $R_B$41, —, — | —, —, 240[c] | —, —, 240[c] | —, —, 240[c] |
| Impact Str (Izod), ft-lb | | | | |
| Annealed | —, 165, — | —, 110, 110 | —, —, 80 | —, 110, 110 |
| Cold Worked | — | — | — | —, —, 90[c] |
| Endurance Limit, 1000 psi | | | | |
| Annealed | 35, 39, — | —, —, 34 | —, —, 35 | 35, 35, 34 |
| Cold Worked | 80, —, — | — | — | — |
| Creep Str (1% ext in 1000 hr), psi | | | | |
| 1000 F | — | 17,000 | — | 17,000 |
| 1300 F | — | 4,000 | — | 4,000 |
| 1500 F | — | 1,200 | — | 1,200 |
| FABRICATING PROPERTIES | | | | |
| Annealing Temp, F[f] | 1850–2050 | 1900–2050 | 1850–2050 | 1900–2050 |
| Forging Temp (start), F[g] | 2200 | 2100 | 2100 | 2200 |
| Machinability | — | Fair; tough | Good; about 65% of screw stock | Fair; tough |
| Weldability | Very good | Not recommended; may crack | | Very good |
| CORROSION RESISTANCE | Very good atmosphere resistance; slightly less than type 302 | Excellent atmosphere resistance; also resists food products, acids and other chemicals | Very good atmosphere resistance; some resistance sacrificed for better machinability | Excellent atmosphere resistance; slightly better than type 302 |
| AVAILABLE FORMS | Sheet, strip, wire | Sheet, strip, plate, bar, wire | Bar, wire | Sheet, strip, plate, bar, wire |
| USES | Lightweight, high strength applications; transportation equipment, roof drainage and trim | General purpose | General purpose, but where better machinability (than type 302) is required | Light welded construction where corrosive conditions are not too severe |

[a]For 32-600 F range. [b]Where three values are given, they represent sheet, plate and bar in that order.
[c]Cold drawn, high tensile 1½-in. dia bar. [d]Minimum value at full hard temper.
[e]Values are Brinell except where Rockwell scale is noted. [f]Cool rapidly after anneal.
[g]Finish forging all grades at 1700 F or above.

*continued on next page*

## Austenitic Stainless Steels—Wrought

| AISI Type → | 309, 309S | 310, 310S | 316, 316L | 321 |
|---|---|---|---|---|
| COMPOSITION, % | C 0.20 max (309), C 0.08 max (309S), Mn 2 max, P 0.04 max, S 0.03 max, Si 1 max, Cr 22–24, Ni 12–15 | C 0.25 max (310), C 0.08 max (310S), Mn 2 max, P 0.04 max, S 0.03 max, Si 1.5 max, Cr 24–26, Ni 19–22 | C 0.10 max (316), C 0.03 max (316L), Mn 2 max, Si 1 max, P 0.04 max, S 0.03 max, Cr 16–18, Ni 10–14, Mo 2–3 | C 0.08 max, Mn 2 max, Si 1 max, P 0.04 max S 0.03 max, Cr 17–19, Ni 8–11, Ti 5 x C |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.29 | 0.29 | 0.29 | 0.29 |
| Melting Point Range, F | 2550–2650 | 2550–2650 | 2500–2550 | 2550–2600 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 8 | 8 | 9.4 | 9.3 |
| Coef of Ther Exp (32–600 F), per °F | $9.3 \times 10^{-6}$ | $9.0 \times 10^{-6}$ | $9.0 \times 10^{-6}$ | $9.5 \times 10^{-6}$ |
| Spec Heat (32–212 F), Btu/lb/°F | 0.12 | 0.12 | 0.12 | 0.12 |
| Elec Res (68 F), microhm-cm | 78 | 78 | 74 | 72 |
| MECHANICAL PROPERTIES[b] | | | | |
| Mod of Elast in Tension, psi | $29.0 \times 10^6$ | $2.9 \times 10^6$ | $28.0 \times 10^6$ | $28.0 \times 10^6$ |
| Ten Str (ann.), 1000 psi | 90, 95, 95 | 95, 95, 95 | 90, 85, 80 | 90, 85, 85 |
| Yld Str (ann.), 1000 psi | 45, 40, 40 | 45, 45, 45 | 40, 35, 30 | 35, 30, 35 |
| Elong (in 2 in., ann.), % | 45, 45, 45 | 45, 50, 50 | 50, 55, 60 | 50, 55, 55 |
| Red. of Area (ann.), % | —, —, 65 | —, —, — | —, —, 70 | —, —, 65 |
| Hardness (ann.)[c] | $R_B$85, 170, 160 | $R_B$85, —, $R_B$89 | $R_B$85, 150, 150 | $R_B$80, 160, 150 |
| Impact Str (Izod, ann.), ft-lb | —, —, 110 | —, —, 85 | —, —, 110 | —, —, 110 |
| Endurance Limit (ann.), 1000 psi | — | —, —, — | 39, 39, 38 | —, —, 38 |
| Creep Str (1% ext in 10,000 hr), psi | | | | |
| 1000 F | 15,900 | 17,000 | 25,000 | 18,000 |
| 1300 F | 4,500 | 5,000 | 7,900 | 4,500 |
| 1500 F | 1,000 | 1,000 | 2,800 | 850 |
| FABRICATING PROPERTIES | | | | |
| Annealing Temp, F | 1900–2050 | 1900–2100 | 1850–2050 | 1900–2050 |
| Forging Temp (start), F[d] | 2150 | 2000–2250 | 2200 | 2250 |
| Machinability | Fair; tough | Fair; tough | Fair; tough | Fair; tough |
| Weldability | Good | Good | Very good | Very good |
| CORROSION RESISTANCE | Excellent atmosphere resistance; better than type 302. Resists destructive heat scaling up to 2000 F | Excellent atmospheric resistance; better than type 309. Resists scaling to 2100 F | Best of any standard stainless steel. Greater resistance than type 302 to reducing acids, sea water and other corrosive media causing pitting type of corrosion. Intergranular corrosion due to welding eliminated in 316 ELC | Excellent atmosphere resistance; similar to type 302. Not subject to harmful carbide precipitation |
| AVAILABLE FORMS | Sheet, strip, plate, bar, wire | Sheet, strip, plate, bar | Sheet, strip, plate, bar, wire | Sheet, strip, plate, bar, wire |
| USES | Heat resisting applications | Heat exchangers, petroleum refining and chemical processing equipment, gas turbines | Processing equipment exposed to severe corrosive media. Stressed parts that operate at high temperatures | Welded equipment used in the unannealed condition and exposed to corrosive conditions. Equipment that must operate in the sensitization range (800–1650 F) |

[b] Where three values are given, they represent sheet, plate and bar in that order.
[c] Values are Brinell except where Rockwell scale is noted.
[d] Finish forging in all grades at 1700 F or above.

## Ferritic Stainless Steels—Wrought

| AISI Type → | 405 | 430 | 430F | 446 |
|---|---|---|---|---|
| COMPOSITION, %[a] | C 0.08, Mn 1.00, Si 1.00, P 0.04, S 0.03, Cr 11.5–14.5, Al 0.10–0.30 | C 0.12, Mn 1.00, Si 1.00, P 0.04, S 0.03, Cr 14.0–18.0 | C 0.12, Mn 1.25, P 0.06, S 0.15 min, Cr 14.0–18.0 | C 0.20, Mn 1.50, Si 1.00, P 0.04, S 0.03, Cr 23.0–27.0, N 0.25 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.28 | 0.28 | 0.28 | 0.27 |
| Melting Temp Range, F | 2700–2790 | 2600–2750 | 2600–2750 | 2600–2750 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | — | 15.1 | 15.1 | 12.1 |
| Coef of Ther Exp (32–212 F), per °F | $6.0 \times 10^{-6}$ | $5.8 \times 10^{-6}$ | $5.8 \times 10^{-6}$ | $5.8 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.11 | 0.11 | 0.11 | 0.12 |
| Elec Res (70 F), microhm-cm | 60.0 | 60.0 | 60.0 | 67.0 |
| Magnetic? | Yes | Yes | Yes | Yes |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | $29 \times 10^6$ | $29 \times 10^6$ | $29 \times 10^6$ | $29 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Annealed | 65–70 | 75 | 80 | 80–85 |
| Cold Worked | 85 | 75–90 | 80–90 | 85 |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Annealed | 35–40 | 40–45 | 55 | 50–55 |
| Cold Worked | 70 | 45–80 | 55–80 | 70 |
| Elong (in 2 in.), % | | | | |
| Annealed | 25–30 | 25–30 | 25 | 20–25 |
| Cold Worked | 20 | 15–25 | 15–25 | 20 |
| Red. of Area, % | | | | |
| Annealed | 50–60 | 60–65 | 60–65 | 45 |
| Cold Worked | 60 | 55–65 | 55–65 | 45 |
| Hardness (Rockwell) | | | | |
| Annealed | B75–90 | B80 | B80 | B83–B86 |
| Cold Worked | 185[b] | B95 | B95 | B90 |
| Impact Str (Izod, annealed), ft-lb | 25[c] | — | — | 2 |
| Creep Str (1%, 1000 F), 1000 psi | | | | |
| 10,000 Hr | — | 8.5 | 8.5 | 6.0 |
| 100,000 Hr | — | 7.0 | 7.0 | 4.2 |
| THERMAL TREATMENT | | | | |
| Annealing Temp, F | 1350–1500 | 1400–1500 | 1250–1400 | 1450–1600 |
| FABRICATIN PROPERTIES | | | | |
| Hot Working Temp Range, F | 1950–2050 | 1900–2050 | 1950–2100 | 1950–2050 |
| Machinability | Good | Fair | Excellent | Fair |
| Weldability | Excellent for fusion welding | Fair; welds are brittle | Not recommended | Fair; great care required because of high Cr content |
| CORROSION RESISTANCE | Good resistance to weather, water, some chemicals | Excellent resistance to weather, water; good resistance to most chemicals | Very good resistance to weather, water; some resistance sacrificed for better machinability | High resistance to corrosion and scaling; one of the most oxidation resistant steels commercially available |
| AVAILABLE FORMS | Bar, plate, sheet | Bar, plate, sheet, strip | Bar | Bar, plate, sheet, strip |
| USES | Lining for oil stills; weldments where 12% Cr gives sufficient corrosion resistance | General purpose grade; substitute for type 302; automobile and other trim, kitchen equipment, chemical equipment (430F is free-machining grade) | | High temperature service up to 2150 F. Furnace parts, glass molds, pyrometer tubes, chemical processing equipment |

[a] Maximum values unless otherwise stated. [b] Brinell. [c] Minimum.

## Martensitic Stainless Steels—Wrought

| AISI Type → | 403, 410 | 414 | 416 | 420 | 431 |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.15 max, Cr 11.5–13.5 | C 0.15 max, Cr 11.5–13.0, Ni 1.25–2.5 | C 0.15 max, Cr 12–14, P, S or Se 0.07 min, Mo or Zr 0.06 max | C > 0.15, Cr 12–14 | C 0.20 max, Cr 15–17, Ni 1.25–2.50 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.28 | 0.28 | 0.28 | 0.28 | 0.28 |
| Melting Point, F | 2700–2790 | — | 2700–2790 | 2650–2750 | 2650 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 14.4 | 14.4 | 14.4 | 14.4 | 11.7 |
| Coef of Ther Exp, per °F | | | | | |
| 32–212 F | $5.5 \times 10^{-6}$ | $5.8 \times 10^{-6}$ | $5.5 \times 10^{-6}$ | $5.7 \times 10^{-6}$ | $6.5 \times 10^{-6}$ |
| 32–1200 F | $6.5 \times 10^{-6}$ | — | $6.5 \times 10^{-6}$ | $6.8 \times 10^{-6}$ | — |
| Spec Ht (32–212 F), Btu/lb/°F | 0.11 | 0.11 | 0.11 | 0.11 | 0.11 |
| Elec Res (rm temp), microhm-cm | 57 | 70 | 57 | 55 | 72 |
| Magnetic? | Yes | Yes | Yes | Yes | Yes |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $29.0 \times 10^6$ | $29.0 \times 10^6$ | $29.0 \times 10^6$ | $29.0 \times 10^6$ | $29.0 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed | 65–75 | 115–120 | 75 | 95 | 125 |
| Hard. & Temp. | 90–190 | 120–200 | 90–190 | 230 | 125–205 |
| Yld Str, 1000 psi | | | | | |
| Annealed | 35–50 | 90–105 | 40 | 50 | 95 |
| Hard. & Temp. | 60–145 | 105–150 | 60–145 | 195 | 90–155 |
| Elong (in 2 in.), % | | | | | |
| Annealed | 25–35 | 15–20 | 30 | 25 | 20 |
| Hard. & Temp. | 15–30 | 15–20 | 12–25 | 8 | 15–20 |
| Hardness (Brinell) | | | | | |
| Annealed | 155 | 235 | 155 | 195 | 260 |
| Hard. & Temp. | 180–390 | 250–410 | 180–390 | 500 | 260–415 |
| Impact Str (Izod), ft-lb | | | | | |
| Annealed | 90 | 50 | 70 | — | — |
| Hard. & Temp. | 35–75 | 45–50 | 20–60 | 10 | 30–50 |
| Endurance Limit (annealed), 1000 psi | 40 | 45 | 40 | 40 | 45 |
| Creep Str (1% ext in 10,000 hr, annealed), psi | | | | | |
| 1000 F | 9200 | — | 9200 | — | — |
| 1300 F | 1000 | — | 1000 | — | — |
| THERMAL TREATMENT | | | | | |
| Annealing Temp, F | 1500–1650 | — | 1500–1650 | 1550–1650 | — |
| Hardening Temp, F | 1700–1850 | 1800–1900 | 1700–1850 | 1800–1900 | 1800–1950 |
| Tempering Temp, F | 400–1400 | 400–1300 | 400–1400 | 300–700 | 400–1200 |
| FABRICATING PROPERTIES | | | | | |
| Machinability | Fair | Poor | Good; 80% of screw stock | Fair | Poor |
| Weldability | Fair; small welds can be annealed | Poor | Poor | Fair | Poor |
| Forging Temp (start), F | 2000–2200 | 2100–2200 | 2100–2300 | 2000–2200 | 2100–2250 |
| CORROSION RESISTANCE | Good resistance to weather and water; also good resistance to some chemicals | | | | |
| AVAILABLE FORMS | Plate, sheet, strip, bar, tube, rounds, structural and bar shapes, round and flat wire, tubing | | | | |
| USES | Steam turbine blades, highly stressed parts | Springs, knife blades, tempered rules | Automatic screw machine parts | Cutlery, surgical instruments, ball bearings, magnets | High strength parts |

## Martensitic Stainless Steels—Wrought

| AISI Type → | 440A | 440B | 440C | 501 | 502 |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.60–0.75, Cr 16–18, Mo 0.75 max | C 0.75–0.95, Cr 16–18, Mo 0.75 max | C 0.95–1.20, Cr 16–18, Mo 0.75 max | C > 0.10, Cr 4–6 | C 0.10 max, Cr 4–6 |
| **PHYSICAL PROPERTIES** | | | | | |
| Density, lb/cu in. | 0.28 | 0.28 | 0.28 | 0.28 | 0.28 |
| Melting Point, F | 2500–2750 | 2500–2750 | 2500–2750 | 2700–2800 | 2700–2800 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft. | 14.0 | 14.0 | 14.0 | 21.2 | 21.2 |
| Coef of Ther Exp, per °F | | | | | |
| 32–212 F | $5.6 \times 10^{-6}$ | $5.6 \times 10^{-6}$ | $5.6 \times 10^{-6}$ | $6.2 \times 10^{-6}$ | $6.2 \times 10^{-6}$ |
| 32–1200 F | — | — | — | $7.3 \times 10^{-6}$ | $7.3 \times 10^{-6}$ |
| Spec Ht (32–212 F), Btu/lb/°F | 0.11 | 0.11 | 0.11 | 0.11 | 0.11 |
| Elec Res (rm temp), microhm-cm | 60 | 60 | 60 | 40 | 40 |
| Magnetic? | Yes | Yes | Yes | Yes | Yes |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, psi | $29.0 \times 10^6$ | $29.0 \times 10^6$ | $29.0 \times 10^6$ | $29.0 \times 10^6$ | $29.0 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed | 105 | 107 | 110 | 70 | 65–70 |
| Hard. & Temp. | 260 | 280 | 285 | 115–175 | — |
| Yld Str, 1000 psi | | | | | |
| Annealed | 60 | 62 | 65 | 30 | 25–30 |
| Hard. & Temp. | 240 | 270 | 275 | 90–135 | — |
| Elong (in 2 in.), % | | | | | |
| Annealed | 20 | 18 | 14 | 28 | 30 |
| Hard. & Temp. | 5 | 3 | 2 | 15–20 | — |
| Hardness (Brinell) | | | | | |
| Annealed | 215 | 220 | 230 | 160 | 150 |
| Hard. & Temp. | 510 | 555 | 580 | 240–370 | — |
| Impact Str (Izod), ft-lb | | | | | |
| Annealed | 2 | 2 | 2 | — | 85 |
| Hard. & Temp. | 4 | 3 | 2 | — | — |
| Endurance Limit (annealed), 1000 psi | 40 | 40 | 40 | 35 | 35 |
| Creep Str (1% ext in 10,000 hr, annealed), psi | | | | | |
| 1000 F | Not used in fatigue applications | | | 9500 | 9500 |
| 1300 F | | | | 800 | 800 |
| **THERMAL TREATMENT** | | | | | |
| Annealing Temp, F | 1550–1650 | 1550–1650 | 1550–1650 | 1525–1600 | 1525–1600 |
| Hardening Temp, F | 1850–1950 | 1850–1950 | 1850–1950 | 1600–1700 | —[a] |
| Tempering Temp, F | 300–800 | 300–800 | 300–800 | 400–1400 | —[a] |
| **FABRICATING PROPERTIES** | | | | | |
| Machinability | Fair | Fair | Fair | — | — |
| Weldability | Welding not generally recommended | Welding not generally recommended | Welding not recommended | — | — |
| Forging Temp (start), F | 1900–2200 | 1900–2150 | 1900–2100 | — | — |
| CORROSION RESISTANCE | Good resistance to weather and water; also good resistance to some chemicals | | | | |
| AVAILABLE FORMS | Plate, sheet, strip, bar, tube, rounds, structural and bar shapes, round and flat wire, tubing | | | | |
| USES | Instruments, cutlery, valves | | | Applications requiring heat resistance and good mechanical properties at elevated temperatures | |

[a] Generally used in annealed condition only.

## High Temperature Steels—Wrought

| Type → | Martensitic Stainless | | | Low Alloy | |
|---|---|---|---|---|---|
| | 422, 1420 WM | 1415 NW (Greek Ascoloy) | 1430 MV (Lapelloy) | Chromoloy (14 CMV) | 17-22AS (14 MV) |
| COMPOSITION, % | C 0.20, Mn 0.65, Si 0.55, Cr 13.0, Ni 0.75, Mo 0.95, W 1.0, V 0.35, Fe bal | C 0.17, Mn 0.40, Si 0.30, Cr 12.75, Ni 1.95, Mo 0.15, W 3.0, Cu 0.13, Fe bal | C 0.30, Mn 1.05, Si 0.30, Cr 11.80, Ni 0.25, Mo 2.80, V 0.25, Fe bal | C 0.20, Mn 0.50, Si 0.75, Cr 1.0, Mo 1.0, V 0.10, Fe bal | C 0.30, Mn 0.55, Si 0.70, Cr 1.30, Mo 0.50, V 0.25, Fe bal |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.281 | 0.284 | 0.281 | 0.285 | 0.283 |
| Melting Temp Range, F | 2675–2700 | 2660–2670 | 2700–2750 | — | 2700–2750 |
| Ther Cond (800 F), Btu/hr/sq ft/°F/ft | 15.8 | — | 15.8 | — | 17.3 |
| Coef of Ther Exp (70–1000 F), per °F | $6.5 \times 10^{-6}$ | $6.3 \times 10^{-6}$ | $6.5 \times 10^{-6}$ | $7.9 \times 10^{-6}$ | $7.8 \times 10^{-6}$ |
| MECHANICAL PROPERTIES[a] | | | | | |
| Mod of Elast in Tension, psi | | | | | |
| Room Temp | $30 \times 10^6$ | $29 \times 10^6$ | $30 \times 10^6$ | $31.6 \times 10^6$ | $29.5 \times 10^6$ |
| 1000 F | $21.5 \times 10^6$ | $21.5 \times 10^6$ | $22 \times 10^6$ | $25.4 \times 10^6$ | $20 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Room Temp | 235 | 170 | 157 | 139 | 150 |
| 800 F | 221 | 135 | 123 (900 F) | 119 | 121 |
| 1000 F | — | 103 | 89 (1100 F) | 103 | 91 |
| Yld Str (0.2% offset), 1000 psi | | | | | |
| Room Temp | 186 | 150 | 125 | 117 | 127 |
| 800 F | 197 | 122 | 94 (900 F) | 96 | 101 |
| 1000 F | — | 98 | 81 (1100 F) | 85 | 78 |
| Elongation (in 2 in.), % | | | | | |
| Room Temp | 10 | 13.3 | 12 | 8 (min) | 16.5 |
| 800 F | 13.5 | 13.3 | 10 (900 F) | — | 18 |
| 1000 F | — | 17.1 | 28 (1100 F) | — | 18 |
| Impact Str (Charpy), ft-lb | | | | | |
| Room Temp | 19.5 | 19.5 | 10.0 | — | 31 |
| 1000 F | 38.5 | — | 15.0 | — | 37 |
| Fatigue Str ($10^7$ cycles), 1000 psi | | | | | |
| 900 F | 45[b] | — | 53[d] | — | — |
| 1100 F | 32[b] | 53 (1000 F) | 36[d] | — | — |
| Rupture Str (1000 F), 1000 psi | | | | | |
| 10 Hr | 71 | 48[c] | 73[e] | 96 | 95 |
| 100 Hr | 63 | 42[c] | 65[e] | 78 | 74 |
| 1000 Hr | 57 | 36[c] | 58[e] | 52 | 55 |
| 10,000 Hr | 49 | 31[c] | 48[e] | 32 | 31 |
| FABRICATING PROPERTIES | | | | | |
| Hot Working Temp, F | 1700–2100 | 1700–2200 | 1700–2200 | 1500–2100 | 1500–2100 |
| Cold Workability | Fair | Fair | Fair | Good | Good |
| Machinability | Fair to good | Poor | Fair to good | Good | Good |
| Weldability | Not recommended | Not recommended | Not recommended | Excellent | Very good |
| CORROSION RESISTANCE | Resist atmospheric corrosion, weak organic acids and oxidizing acids (such as nitric); do not have the superior resistance to pitting by dilute reducing acids which characterizes the 300 series stainless steels. Good oxidation resistance up to 1450 F | | | Poor res compared to other alloys covered here; easily and severely pitted in salt spray test; can be protected with paints. Good oxidation resistance up to 1000 F | |
| AVAILABLE FORMS | Sheet, strip, plate, bar, forgings, tubing | | | Bar, forgings, plate, sheet, strip | Bar, forgings |
| USES | Turbine buckets, jet engine compressor blades, etc., requiring high strength at high temperatures | | | | |

[a] Properties for materials in the following conditions:
422, 1420 WM: austenitized at 1900 F, oil quenched, double tempered 2 hr at 1200 F and 2 hr at 800 F, air cooled.
1415 NW (Greek Ascoloy): austenitized ½ hr at 1800 F, oil quenched, tempered 2 hr at 1050 F, air cooled.
1430 MV (Lapelloy): austenitized at 2000 F, oil quenched, tempered 2 hr at 2000 F, air cooled.
Chromoloy: normalized 1 hr at 1650–1750 F, air cooled, tempered 2 hr at 1200 F, air cooled.
17-22 AS (14 MV): normalized from 1650–1750 F, tempered 6 hr at 1225 F, air cooled.
[b] Austenitized at 1900 F, tempered 4 hr at 1300 F.
[c] Austenitized ½ hr at 1800 F, air cooled, tempered 1½ hr at 1260 F.
[d] Hardened ¾ hr at 2000 F, salt quenched, held ¾ hr at 800 F, air cooled, tempered 4 hr at 1320 F, air cooled.
[e] Austenitized at 2000 F, oil quenched, tempered 2 hr at 1300 F.

## Ultra High Strength Steels—Wrought

| Type → | Unimach I, Vascojet | MX-2, UCX2 | 300-M | D-6A |
|---|---|---|---|---|
| COMPOSITION, % | C 0.40, Mn 0.35, Si 1.0, Cr 5.0, Mo 1.4, V 0.45, Fe bal | C 0.39, Mn 0.70, Si 1.0, Cr 1.10, Mo 0.25, V 0.15, Co 1.0, Fe bal | C 0.40, Mn 0.75, Si 1.60, Ni 1.85, Cr 0.85, Mo 0.40, V 0.08, Fe bal | C 0.46, Mn 0.75, Si 0.22, Ni 0.55, Cr 1.0, Mo 1.0, Fe bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.281 | 0.276 | — | 0.283 |
| Ther Cond (1100 F), Btu/hr/sq ft/°F/ft | 16.6 | — | — | — |
| Coef of Ther Exp, per °F | 7.4 x $10^{-6}$ [b] | 5.68 x $10^{-6}$ [c] | 7.61 x $10^{-6}$ [d] | — |
| MECHANICAL PROPERTIES [a] | | | | |
| Mod of Elast in Tension, psi | | | | |
| Room Temp | 30 x $10^6$ | 29.4 x $10^6$ | — | 30 x $10^6$ |
| 400 F | 27.6 x $10^6$ | — | — | 24.4 x $10^6$ |
| 800 F | 21.9 x $10^6$ | — | — | 23.7 x $10^6$ |
| Ten Str, 1000 psi | | | | |
| Room Temp | 295 | 279 | 289 | 284 |
| 500 F | 270 | — | 270 | 267 |
| 800 F | 252 | — | 232 (700 F) | 185 [e] |
| 1000 F | 220 | — | — | 139 [f] |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Room Temp | 247 | 239 | 242 | 250 |
| 500 F | 220 | — | 200 | 188 |
| 800 F | 199 | — | 178 (700 F) | 159 [e] |
| 1000 F | 172 | — | — | 121 [f] |
| Elongation (in 2 in.), % | | | | |
| Room Temp | 12.0 | 5.5 | 10.0 | 7.5 |
| 500 F | 9.8 | — | 13.3 | 15.2 |
| 800 F | 12.0 | — | 15.0 | 15.2 [e] |
| 1000 F | 15.0 | — | — | 19.8 [f] |
| Red. of Area, % | | | | |
| Room Temp | 39.9 | — | 38 | 26.8 |
| 500 F | 33.0 | — | 35 | 55.0 |
| 800 F | 35.2 | — | 52 (700 F) | 55.0 [e] |
| 1000 F | 43.0 | — | — | 64.5 [f] |
| Impact Str (Charpy), ft-lb | | | | |
| −200 F | 15 (−100 F) | — | 11 | 10 |
| Room Temp | 15 | — | 22 | 14 |
| 500 F | 31 | — | 23 | 26 |
| Fatigue Str ($10^8$ cycles), 1000 psi | 135 | — | 116 | 110 |
| Rupture Str (900 F), 1000 psi | | | | |
| 10 Hr | 240 | — | — | — |
| 100 Hr | 210 | — | — | 144 |
| 1000 Hr | 140 | — | — | 97 |
| FABRICATING PROPERTIES | | | | |
| Hot Working Temp Range, F | 1700–2100 | 1650–1950 | 1700–2250 | 1800–2250 |
| Machinability | Readily machined in annealed condition | | | |
| Weldability | Readily fusion welded with shielded arc; preheat to 1000 F, postheat at 600 F | Excellent by tungsten-arc inert-gas method | Readily welded by all conventional methods | Readily welded by conventional methods; preheat to 450–550 F, postheat at 600 F |
| AVAILABLE FORMS | Bar, billets, forgings, plate, sheet, strip, wire [g] | | | |
| USES | Aircraft and missile turbine housings, engine mounts, landing gear, airframes and other high strength, high temperature components | High strength, thin-wall rocket motor cases, landing gear and other high strength aircraft structural components | Aircraft landing gear and other high strength components | High strength, thin-wall rocket motor cases, landing gear and other high strength aircraft structural components |

[a] Properties for materials in the following conditions:
Unimach I, Vascojet: air cooled from 1850 F and double tempered at 1000 F.
Unimach UCX2: austenitized at 1700 F, oil quenched, double tempered at 500–600 F.
300-M: normalized at 1700 F, austenitized at 1600 F, oil quenched, tempered at 600 F.
D-6A: normalized at 1650 F, oil quenched, tempered at 500–700 F.
[b] 80–1200 F. [c] 80–600 F. [d] 0–600 F. [e] Tempered at 850 F. [f] Tempered at 1050 F. [g] 300-M also available as castings.

## Age Hardenable Stainless Steels—Wrought

| Type → | Stainless W | 17-4 PH | 17-7 PH | PH 15-7 Mo | 17-14 Cu Mo |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.12 max, Mn 1.0 max, Si 1.0 max, Ni 7.0, Cr 17.0, Ti 1.2, Al 0.50, Fe bal | C 0.07 max, Mn 1.0 max, Si 1.0 max, Cr 16.5, Ni 4.0, Cu 4.0, Cb+Ta 0.30 | C 0.09 max, Mn 1.0 max, Si 1.0 max, Cr 17.0, Ni 7.1, Al 1.0, Fe bal | C 0.09 max, Mn 1.0 max, Si 1.0 max, Cr 15.0, Ni 7.0, Mo 2.5, Al 1.0, Fe bal | C 0.12, Mn 0.75, Si 0.50, Cr 15.9, Ni 14.1, Mo 2.50, Cu 3.0, Cb 0.45, Ti 0.25, Fe bal |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.280 | 0.281 | 0.276 | 0.277 | 0.287 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 12.1 | 10.4 | 9.7 | 9.3 | 8.7 |
| Coef of Ther Exp (70–200 F), per °F | $5.5 \times 10^{-6}$ [c] | $6.0 \times 10^{-6}$ | $5.6 \times 10^{-6}$ | $5\text{–}6 \times 10^{-6}$ | $8.2 \times 10^{-6}$ |
| Elec Res (68 F), microhm-cm | 85 | 77 | 82 | 82 | — |
| Magnetic Permeability (max) | 101 | 151 | 82 | 150 | — |
| MECHANICAL PROPERTIES [a, b] | | | | | |
| Mod of Elast in Tension, psi | $28 \times 10^6$ | $28.5 \times 10^6$ | $29 \times 10^6$ | $29 \times 10^6$ | $28 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Room Temp | 195 | 195 | 200, 235 | 210, 240 | 86 |
| 800 F | 146 | 157 | 143, 159 | 160, 182 | 73 (900 F) |
| 1000 F | 94 | 100 | —, 93 | 110, 130 | 72 |
| 1200 F | 41 | 59 | —, — | —, — | 34 (1500 F) |
| Yld Str (0.2% offset), 1000 psi | | | | | |
| Room Temp | 180 | 180 | 185, 220 | 200, 225 | 42 |
| 800 F | 135 | 138 | 129, 137 | 150, 152 | 27 (900 F) |
| 1000 F | 54 | 77 | —, 76 | 105, 105 | 28 |
| 1200 F | 24 | 42 | —, — | —, — | 26 (1500 F) |
| Elongation (in 2 in.), % | | | | | |
| Room Temp | 3–5 | 13 | 9, 6 | 7, 6 | 45 |
| 800 F | 13.5 | 10 | 6.5, 12 | 9.5, 8.5 | 35 (900 F) |
| 1000 F | 22.5 | 15 | —, 26 | 21, 13 | 32 |
| 1200 F | 40 | 15 | —, — | —, — | 29 (1500 F) |
| Impact Str (Charpy), ft-lb | — | 19 | 6, 4 | 4, 4 | 26 |
| Fatigue Str ($10^8$ cycles), 1000 psi | 54–96 | 90 | 75 [f], 106 [f] | — | 35 [e] |
| Compr Yld Str, 1000 psi | 180 | 180 | 200, 225 | 217, 243 | — |
| Shear Str, 1000 psi | 120 | 130 | 136, 150 | 143, 160 | — |
| Creep Str (1000 hr, 800 F), 1000 psi | | | | | |
| 0.1% | — | 50 | 60, 31 | —, 95 | 24 [b] |
| 0.2% | 40 [d] | — | —, 36 | —, 109 | — |
| Rupture Str (800 F), 1000 psi | | | | | |
| 100 Hr | 31 [e] | 130 | 110, 113 | 139, 174 | 43 [b] |
| 1000 Hr | — | 89 | 90, 92 | 137, 171 | 37 [b] |
| FABRICATING PROPERTIES | | | | | |
| Hot Working Temp Range, F | 1700–2300 | 1800–2200 | To 2150 | — | 2200 |
| Machinability | Slightly easier than type 302 | Same as type 410 | Not often machined | Good | Same as types 302 and 304 |
| Weldability | Readily welded by arc and resistance processes applicable to stainless steels | | | | |
| CORROSION RESISTANCE | In general about the same corrosion and oxidation resistance as conventional stainless steels | | | | |
| AVAILABLE FORMS | Bar, billets, extrusions, plate, sheet, strip, wire | Bar, billets, wire | All wrought forms | All wrought forms | All wrought forms |
| USES | Used where high strength-weight ratio, corrosion resistance and good strength at moderate temperatures are required. Specifically, airframe skin and structural parts | | | Used where high strength and corrosion resistance up to 1000 F are required. Specifically, aircraft parts | Used where good creep strength, impact strength and corrosion and oxidation resistance are needed at temperatures up to 1500 F |

[a] Properties for materials in following conditions:
Stainless W: sheet solution annealed at 1850–1950 F, air cooled, aged ½ hr at 950 F, air cooled.
17-4 PH: bar solution annealed at 1900 F, oil or water quenched, aged 1 hr at 900 F, air cooled.
17-7 PH: two conditions: (1) TH 1050—sheet solution annealed at 1950 F, austenitized 90 min at 1400 F, air cooled to 50–60 F, held 30 min, aged 90 min at 1050 F; (2) RH 950—solution annealed at 1950 F, austenitized 10 min at 1750 F, air cooled, treated 8 hr at −100 F, aged 1 hr at 950 F. PH-15-7 Mo: same as 17-7 PH.
17-14 Cu Mo: solution annealed ½ hr at 2250 F, water quenched, aged 5 hr at 1350 F, water quenched.
[b] Where two sets of values are given they represent the TH 1050 and RH 950 conditions as given in the preceding note.
[c] 32–212 F. [d] 500 hr. [e] At 1000 F. [f] Vapor blasted surface. [g] $10^8$ cycles at 1200 F. [h] At 1200 F.

## Age Hardenable Stainless Steels—Wrought, Cast

| Type → | AM-350 | AM-355 | Cast AM-355 | Cast 17-4PH |
|---|---|---|---|---|
| COMPOSITION, % | C 0.10, Mn 0.80, Si 0.25, Cr 16.5, Ni 4.3, Mo 2.75, N 0.10, Fe bal | C 0.13, Mn 0.95, Si 0.25, Cr 15.5, Ni 4.3, Mo 2.75, N 0.10, Fe bal | C 0.10, Mn 0.80, Si 0.60, Cr 15.0, Ni 4.2, Mo 2.3, N 0.09, Fe bal | C 0.07, Mn 1.0, Si 1.0, Cr 15–17, Ni 3–5, Cu 2.3–3.0, Fe bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.282 | 0.282 | 0.282 | 0.280 |
| Melting Temp, F | 2500–2550 | 2500–2550 | 2500–2550 | — |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 8.87 | 9.18 | 9.18 | 10.4 |
| Coef of Ther Exp (68–212 F), per °F | $6.3 \times 10^{-6}$ | $6.4 \times 10^{-6}$ | $6.4 \times 10^{-6}$ | $6.0 \times 10^{-6}$ |
| Elec Res (80 F), microhm-cm | 78.8 | 75.7 | 75.7 | 98 |
| MECHANICAL PROPERTIES[a] | | | | |
| Mod of Elast in Tension, psi | | | | |
| 80 F | $29.4 \times 10^6$ | $29 \times 10^6$ | $29.3 \times 10^6$ | $28.5 \times 10^6$ |
| 600 F | $25.9 \times 10^6$ | $26 \times 10^6$ | — | — |
| 800 F | $24.3 \times 10^6$ | $24.6 \times 10^6$ | — | — |
| Ten Str, 1000 psi | | | | |
| Room Temp | 206 | 219 | 215 | 170 (min) |
| 600 F | 189 | 210 | — | — |
| 800 F | 186 | 198 | — | 158 |
| 1000 F | 106 | 144 | — | — |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Room Temp | 173 | 181 | 165 | 140 (min) |
| 600 F | 136 | 152 | — | — |
| 800 F | 125 | 139 | — | 138 |
| 1000 F | 85 | 97 | — | — |
| Elongation (in 2 in.), % | | | | |
| Room Temp | 13.5 | 12.6 | 15.0 | 6 (min) |
| 600 F | 7.0 | 11.5 | — | — |
| 800 F | 9.5 | 11.0 | — | — |
| 1000 F | 16.0 | 16.0 | — | — |
| Impact Str (Charpy), ft-lb[b] | | | | |
| Room Temp | 14.1 | 17.1 | — | 17 |
| 212 F | 24.5 | 18.5 | — | — |
| Creep Str (1000 hr, 800 F), 1000 psi | | | | |
| 0.1 % | 91 | 100 | — | 120 (700 F) |
| 0.01% | 23 | 27 | — | 80 (700 F) |
| Rupture Str (800 F), 1000 psi | | | | |
| 10 Hr | 188 | 188 | — | — |
| 100 Hr | 186 | 186 | — | — |
| 1000 Hr | 183 | 180 | — | 89 |
| FABRICATING PROPERTIES | | | | |
| Hot Working Temp, F | 1700–2100 | 1700–2100 | 1700–2100 | 1800–1850 |
| Machinability | Similar to conventional stainless steels | | | |
| Weldability | Readily weldable by all methods used on chromium-nickel stainless steels | | | |
| CORROSION RESISTANCE | Superior to other hardenable stainless grades; offer good resistance to boiling 65% nitric, boiling citric, boiling glacial acetic, 10% oxalic (200 F), and boiling 10% phosphoric acids | | | Better than 12% chromium steels and approaches 18–8 stainless |
| AVAILABLE FORMS | Billets, bar, forgings, sheet, strip, foil, wire, welded tubing | Sheet, strip, plate, bar, forgings, tubing, wire and electrodes | Castings | Castings |
| USES | Structural parts requiring high strength-weight ratio, corrosion resistance and good strength at moderate temperatures | Structural parts requiring high strength, good corrosion resistance and ease of fabrication | | Chemical equipment requiring strength and galling resistance |

[a] Properties for materials in the following conditions:
AM-350: sheet solution treated at 1710 F ± 25 F, air cooled or water quenched, hardened 3 hr at − 100 F, hardened 3 hr at 850–1000 F, air cooled.
AM-355: same as AM-350; elevated temperature properties are for bar stock.
Cast AM-355: same as AM-350.
Cast 17-4PH: solution annealed 1 hr at 1900 F, air cooled, hardened 1 hr at 875 F, air cooled.

[b] Bar stock.

## Iron-Base Superalloys (Cr-Ni)—Wrought

| Type → | 19-9DL | Unitemp 212 | W 545 | Discaloy | D-979 |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.32, Mn 1.15, Si 0.55, Cr 18.5, Ni 9.0, Mo 1.40, W 1.35, Cb+Ta 0.40, Ti 0.25, Cu 0.15, Fe bal | C 0.08, Mn 0.05, Si 0.15, Cr 16.0, Ni 25.0, Ti 4.0, Al 0.15, Cb+Ta 0.50, B 0.06, Zr 0.05, Fe bal | C 0.05, Mn 1.50, Si 0.40, Cr 13.5, Ni 26.0, Mo 1.50, Ti 2.85, Al 0.20, B 0.08, Fe bal | C 0.04, Mn 0.9, Si 0.8, Cr 13.5, Ni 26.0, Ti 1.75, Mo 2.75, Al 0.07, Cu 0.05, Fe bal | C 0.05, Mn 0.50, Si 0.50, Cr 15.0, Ni 45.0, Mo 3.75, W 3.75, Ta 3.0, Al 1.0, B 0.01, Fe bal |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.287 | 0.286 | 0.285 | 0.288 | 0.295 |
| Ther Cond (1200 F), Btu/hr/sq ft/°F/ft. | 12.2 | 13.7 | 13.0 | 13.0 | — |
| Melting Temp, F. | 2560–2615 | 2480 | 2460–2500 | 2516–2664 | 2225–2550 |
| Coef of Ther Exp (70–1500 F), per °F. | $10 \times 10^{-6}$ | $10 \times 10^{-6}$ | $9.7 \times 10^{-6}$ | $9.6 \times 10^{-6}$ | $9.5 \times 10^{-6}$ |
| Specific Heat, Btu/lb/°F. | 0.10 | — | — | — | — |
| Elec Res (200 F), microhm-cm. | — | 91[c] | 104 | 104 | — |
| MECHANICAL PROPERTIES[a] | | | | | |
| Mod of Elast in Tension, psi | | | | | |
| Room Temp. | $29.5 \times 10^6$ | $29.0 \times 10^6$ | $28.5 \times 10^6$ | $28.3 \times 10^6$ | $28.0 \times 10^6$ |
| 1000 F. | $23.3 \times 10^6$ | $23.3 \times 10^6$ | $22.3 \times 10^6$ | $22.2 \times 10^6$ | $24.0 \times 10^6$ |
| 1200 F. | $22.0 \times 10^6$ | $22.0 \times 10^6$ | $21.0 \times 10^6$ | $21.0 \times 10^6$ | $21.0 \times 10^6$ |
| 1400 F. | $20.7 \times 10^6$ | $20.5 \times 10^6$ | — | — | $18.0 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Room Temp. | 114 | 187 | 175 | 145 | 196 |
| 1000 F. | 79 | — | 146 | 125 | 186 |
| 1200 F. | 62 | 144 | 134 | 104 | 156 |
| 1400 F. | 50 | 102 | 83 | 82 (1350 F) | 105 |
| Yld Str (0.2% offset), 1000 psi | | | | | |
| Room Temp. | 71 | 134 | 125 | 106 | 142 |
| 1000 F. | 55 | — | 112 | 94 | 130 |
| 1200 F. | 52 | 122 | 105 | 91 | 122 |
| 1400 F. | 40 | 97 | 70 | 74 (1350 F) | 94 |
| Elongation (in 2 in.), % | | | | | |
| Room Temp. | 41 | 23 | 20 | 19 | 16 |
| 1000 F. | 24 | — | 14 | 16 | 15 |
| 1200 F. | 35 | 18 | 18 | 19 | 20 |
| 1400 F. | 35 | 16 | 34 | 14 (1350 F) | 17 |
| Impact Str (Charpy), ft-lb | | | | | |
| Room Temp. | 46 | 24–34 | 30 | 36 | — |
| 1200 F. | 56 | — | 23 | 35 | — |
| Fatigue Str ($10^8$ cycles), 1000 psi | | | | | |
| Room Temp. | 81 | — | — | 55 | — |
| 1200 F. | 52 | 70 | — | 51 | — |
| Rupture Str (1350 F), 1000 psi | | | | | |
| 100 Hr. | 44 (1200 F) | 63 | 60 (1300 F) | 30 | 48[d] |
| 1000 Hr. | 37 (1200 F) | 43 | 50 | 25 (500 hr) | 34[d] |
| FABRICATING PROPERTIES | | | | | |
| Hot Working Temp, F. | 1200–2150 | 1900–1950 | 1700–2100 | 1800–2150 | 1750–2100 |
| Machinability Index[b] | 40 | — | — | 25 | — |
| Weldability | Excellent | Limited data | — | Limited data | — |
| CORROSION RESISTANCE | Excellent res to acids, exhaust gases | Excellent up to 1400 F | Excellent up to 1300 F | Excellent up to 1300 F | Excellent up to 1500 F |
| AVAILABLE FORMS | Billets, bar, wire, sheet, strip, tubing, forgings | Billets, bar, wire, sheet, strip | Billets, bar, strip, plate, sheet, forgings | Billets, bar, strip, plate, sheet, wire, forgings | Billets, bar, sheet, forgings |
| USES | Highly stressed missile and jet engine parts at elevated temperatures | | | | |

[a] Properties for material in the following conditions:
19–9DL: hot rolled bar stress relieved 8 hr at 1350 F, air cooled.
Unitemp 212: bar solution treated 2 hr at 1850 F, air cooled, aged 16 hr at 1325 F, air cooled.
W 545: bar solution treated 3 hr at 2000 F, water quenched, aged 20 hr at 1375 F and 20 hr at 1200 F, air cooled.
Discaloy: forging solution treated 2 hr at 1650 F, water quenched, aged 10 hr at 1350 F and 40 hr at 1200 F, air cooled.
D 979: bar solution treated 1 hr at 1850 F, oil quenched, aged 4 hr at 1550 F and 16 hr at 1300 F, air cooled.

[b] Based on AISI B1112 steel = 100. [c] At 70 F.

[d] Stress rupture values can be increased to 73,000 psi for 100 hr and 57,000 psi for 1000 hr (with a decrease in tensile properties) by solution treating at 2050 F.

## Iron-Base Superalloys (Cr-Ni)—Wrought

| Type → | A-286 | V-57 | 16-25-6 | Incoloy 901 |
|---|---|---|---|---|
| COMPOSITION, % | C 0.08 max, Mn 1.35, Si 0.95, Cr 15.50, Ni 26.0, Mo 1.25, Ti 1.95, V 0.30, Al 0.20, Fe bal | C 0.06, Mn 0.25, Si 0.55, Cr 15.0, Ni 25.5, Mo 1.25, Ti 3.0, Al 0.25, V 0.025, Fe bal | C 0.10 max, Mn 2.0 max, Si 1.0 max, Cr 16.25, Ni 25.5, Mo 6.0, Fe bal | Cr 13.0, Ni 40.0, Ti 2.40, Mo 6.0, Fe bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.286 | — | 0.291 | 0.297 |
| Melting Temp Range, F | 2500–2600 | — | — | — |
| Ther Cond (1100 F), Btu/hr/sq ft/°F/ft | 13.7 | — | 15.0 | — |
| Coef of Ther Exp (80–1400 F), per °F | $10.3 \times 10^{-6}$ | $10.5 \times 10^{-6}$ | $9.4 \times 10^{-6}$ | $9.2 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.10–0.11 | — | — | — |
| MECHANICAL PROPERTIES[a] | | | | |
| Mod of Elast in Tension, psi | | | | |
| Room Temp | $29.1 \times 10^6$ | — | $28.2 \times 10^6$ | $29.9 \times 10^6$ |
| 1000 F | $23.5 \times 10^6$ | — | — | $24.2 \times 10^6$ |
| 1200 F | $22.2 \times 10^6$ | — | $17.9 \times 10^6$ | $22.1 \times 10^6$ |
| 1500 F | $19.8 \times 10^6$ | — | $10.0 \times 10^6$ | — |
| Ten Str, 1000 psi | | | | |
| Room Temp | 150 | 172 | 142 | 175 |
| 1200 F | 104 | 129 | 90 | 138 |
| 1400 F | 64 | 100 (1350 F) | 60 | 90 |
| 1500 F | 37 | 60 | 47 | 70 |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Room Temp | 100 | 119 | 112 | 115 |
| 1200 F | 88 | 108 | 75 | 88 |
| 1400 F | — | 89 (1350 F) | 50 | 77 |
| 1500 F | — | 49 | 37 | 60 |
| Elongation (in 2 in.), % | | | | |
| Room Temp | 25 | 24 | 23 | — |
| 1200 F | 13 | 22 | 12 | — |
| 1400 F | 19 | 23 (1350 F) | 11 | — |
| 1500 F | 69 | 40 | 9 | — |
| Impact Str (Charpy), ft-lb | | | | |
| Room Temp | 60 | — | 15 | — |
| 1000 F | 46 | — | 50 (1500 F) | — |
| Fatigue Str ($10^8$ cycles, 1200 F), 1000 psi | 38 | — | 46 | — |
| Creep Str (0.0001%/hr), 1000 psi | | | | |
| 1200 F | 30 | — | 19 | — |
| 1350 F | 16 | — | 13 | — |
| Rupture Str (1350 F), 1000 psi | | | | |
| 100 Hr | 35 | 40 | 28 | 50 |
| 1000 Hr | 21 | 25 | 21 | 30 |
| FABRICATING PROPERTIES | | | | |
| Hot Working Temp, F | 2000–2150 | 1950–2050 | 2100 (max) | 1850–2200 |
| Forgeability | Excellent | Excellent | — | Good |
| Machinability Index[b] | 27 | 25 | 31 | 20 |
| Weldability | Limited data | Limited data | Limited data | Limited data |
| CORROSION RESISTANCE | Excellent up to 1300 F in all atmospheres encountered in jet engine service | | Good corrosion and oxidation resistance at elevated temperatures | Adequate oxidation resistance in range of 1000–1400 F |
| AVAILABLE FORMS | Billets, bar, sheet, strip, tubing, forgings | Billets, bars, forgings, wire, sheet | Billets, bar, sheet, rod, forgings | Sheet, bar |
| USES | Jet engine turbine wheels, blades, frames, casings, afterburner parts, bolts and miscellaneous hardware | | Gas turbines; jet engine wheels, buckets, rotors | Jet engine wheels and disks |

[a] Properties for materials in the following conditions:
A-286: bar solution treated 1 hr at 1800 F, oil quenched, aged 16 hr at 1325 F, air cooled.
16-25-6: bar solution treated 10 min at 2150 F, water quenched, cold worked 20%, stress relieved 4 hr at 1250 F.
V-57: bar solution treated 2 hr at 1800 F, oil quenched, aged 16 hr at 1350 F, air cooled.
Incoloy 901: data not available.

[b] Based on AISI B1112 steel = 100.

## Iron-Base Superalloys (Cr-Ni-Co)—Cast, Wrought

| Type → | Multimet, N-155 | Refractaloy 26 | Refractaloy 70 | S-590 |
|---|---|---|---|---|
| COMPOSITION, % | C 0.10, Mn 1.50, Si 0.70, Cr 20.75, Ni 19.85, Co 19.50, Mo 2.95, W 2.35, Cb+Ta 1.15, Ca 0.20, Fe bal | C 0.03, Mn 0.8, Si 1.0, Cr 18.0, Ni 38.0, Co 20.0, Mo 3.2, Ti 2.6, Al 0.2, Fe bal | C 0.04, Mn 2.0, Si 0.3, Cr 20.0, Ni 21.0, Co 30.0, Mo 8.0, W 4.2, Fe bal | C 0.4, Mn 1.5, Si 0.6, Cr 20.0, Ni 20.0, Co 20.0, Mo 4.0, W 4.0, Cb 4.0, Fe bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.296 | 0.296 | 0.311 | 0.301 |
| Melting Temp, F | 2350–2470 | 2450 | 2380 | 2400 |
| Coef of Ther Exp (70–1000 F), per °F | $9.1 \times 10^{-6}$ | $8.2 \times 10^{-6}$ | $8.3 \times 10^{-6}$ | $8.0 \times 10^{-6}$ |
| Spec Ht (70–212 F), Btu/lb/°F | 0.104 | 0.108 | — | 0.10 |
| MECHANICAL PROPERTIES[a] | | | | |
| Mod of Elast in Tension, psi | | | | |
| Room Temp | $28.8 \times 10^6$ | $30.0 \times 10^6$ | — | $31.1 \times 10^6$ |
| 1000 F | $24.0 \times 10^6$ | $26.3 \times 10^6$ | — | — |
| 1200 F | $21.7 \times 10^6$ | $25.0 \times 10^6$ | — | $24.6 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Room Temp | 118 | 154 | 132 | 142 |
| 1000 F | 94 | 143 | 113 | 132 |
| 1200 F | 74 | 136 | 112 | 95 |
| 1400 F | 59 | 71 (1500 F) | 69 (1500 F) | 62 |
| 1600 F | 39 | 48 | 48 | — |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Room Temp | 58 | 91 | 87 | 75 |
| 1000 F | 40 | 85 | 77 | 80 |
| 1200 F | 38 | 89 | 72 | 71 |
| 1400 F | 36 | 66 (1500 F) | 47 (1500 F) | 51 |
| 1600 F | 30 | 47 | 41 | — |
| Elongation (in 2 in.), % | | | | |
| Room Temp | 49 | 19 | 3 | 21 |
| 1000 F | 54 | 18 | 9 | 14 |
| 1200 F | 28 | 15 | 11 | 24 |
| 1400 F | 12 | 29 (1500 F) | 30 (1500 F) | 26 |
| 1600 F | 15 | 49 | 33 | — |
| Impact Str (Charpy), ft-lb | | | | |
| Room Temp | 65 | 18 | — | 12 |
| 1200 F | 61[c] | 25 | — | 21–23 |
| Fatigue Str ($10^8$ cycles), 1000 psi | | | | |
| 1200 F | 66[d] | 54 | — | — |
| 1500 F | 33[d] | 37 | 32 | 33 |
| Creep Str (1.0%, 1350 F), 1000 psi | | | | |
| 100 Hr | 20[e] | 46 | 25 | 25 |
| 1000 Hr | 15[e] | 37 | — | 20 |
| Rupture Str (1350 F), 1000 psi | | | | |
| 100 Hr | 28 | 51 | 33 | 30 |
| 1000 Hr | 22 | 42 | 24 | 22 |
| FABRICATING PROPERTIES | | | | |
| Hot Working Temp, F | 1400–1650 | 1600–2200 | 2150 | 2100–2250 |
| Machinability Index[b] | 15 | 20 | 20 | 15–20 |
| Weldability | Good | Similar to stainless steel | | — |
| CORROSION RESISTANCE | Good oxidation and corrosion res up to 2000 F | Excellent res to oxidizing and reducing atmospheres to 1800 F | Excellent res to oxidation up to 2200 F | Similar to stainless steel |
| AVAILABLE FORMS | Bar, sheet, plate, tubing, electrodes, forgings; also sand and investment castings | Bar, springs, strip, forgings | Bar, flat springs, forgings | Plate, sheet, strip, bar forgings |
| USES | Gas turbine blades, vanes, nozzles and other elevated temperature parts | | | |

[a] Properties for material in the following conditions:
Multimet, N-155: solution treated 1 hr at 2200 F, air cooled.
Refractaloy 26: solution treated 1 hr at 1800–2100 F, oil quenched, aged 20–44 hr at 1350–1500 F and 4–20 hr at 1500 F, air cooled.
Refractaloy 70: solution treated 4 hr at 2350 F, oil quenched, aged 240–300 hr at 1500 F, air cooled.
S-590: solution treated 1 hr at 2250 F, water quenched, aged 16 hr at 1400 F, air cooled.
[b] Based on AISI B1112 steel = 100. [c] Reheated 2 hr at 1200 F. [d] Aged 50 hr at 1200 F. [e] Aged 2 hr at 1350 F.

## Carbon Steels—Cast

| Class[a] → | 60,000 | 65,000 | 70,000 | 80,000 | 85,000 | 100,000 |
|---|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | | | |
| Density, lb/cu in. | 0.283 | 0.283 | 0.283 | 0.283 | 0.283 | 0.283 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 27 | 27 | 27 | 27 | 27 | 27 |
| Coef of Ther Exp (70–1200 F), per °F | $8.3 \times 10^{-6}$ | $8.3 \times 10^{-6}$ | $8.3 \times 10^{-6}$ | $8.3 \times 10^{-6}$ | $8.3 \times 10^{-6}$ | $8.3 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 |
| Elec Res (68 F), microhm-cm | 13–16 | 13–16 | 13–16 | 13–16 | 13–16 | 13–16 |
| Magnetic? | Yes | Yes | Yes | Yes | Yes | Yes |
| **MECHANICAL PROPERTIES[b]** | | | | | | |
| Mod of Elast in Tension, psi | $30.1 \times 10^6$ | $30.1 \times 10^6$ | $30 \times 10^6$ | $29.9 \times 10^6$ | $29.9 \times 10^6$ | $29.7 \times 10^6$ |
| Ten Str, 1000 psi | 60[c] | 65[d] | 70[d] | 80[e] | 85[e] | 100[f] |
| Yld Point, 1000 psi | 30[c] | 35[d] | 38[d] | 45[e] | 50[e] | 70[f] |
| Elong (in 2 in.), % | 32[c] | 30[d] | 28[d] | 26[e] | 24[e] | 20[f] |
| Red. of Area, % | 55[c] | 53[d] | 50[d] | 43[e] | 40[e] | 46[f] |
| Hardness (Brinell) | 120[c] | 130[d] | 140[d] | 160[e] | 175[e] | 200[f] |
| Impact Str (Izod), ft-lb | | | | | | |
| 70 F | 30[c] | 30[d] | 30[d] | 25[e] | 20[e] | 30[f] |
| −50 F | 8[c] | 12[d] | 10[d] | 12[e] | 10[e] | 15[f] |
| Endurance Limit, 1000 psi | 25[c] | 28[d] | 31[d] | 35[e] | 38[e] | 47[f] |
| **THERMAL TREATMENT** | | | | | | |
| Annealing Temp, F | About 200 F above critical range | | | | | |
| Quenching Temp, F | About 100 F above critical range | | | | | |
| **FABRICATING PROPERTIES** | | | | | | |
| Machinability Index[g] | 55 | 60 | 65 | 70 | 70 | 65 |
| Weldability | Can be welded by procedures used for welding wrought steels of similar composition | | | | | |
| **CORROSION RESISTANCE** | When brought into contact with moisture and air, carbon steels rust at rates that are not affected by carbon content. If salts are present, corrosion rate is increased. Attacked readily by acids, but resistant to alkalis at ordinary temperatures | | | | | |
| **USES** | Applications requiring low electrical resistivity, good magnetic properties, carburizing and case hardening, weldability | Applications requiring excellent weldability; medium strength with good machinability and high ductility | | Applications requiring high strength with good machinability, toughness and excellent fatigue resistance | | Applications requiring wear resistance and hardness |

[a] Tensile strength, psi.
[b] Normally expected coupon values for steel castings having tensile strength given.
[c] Annealed.
[d] Normalized.
[e] Normalized and tempered.
[f] Quenched and tempered.
[g] High speed tool steels based on AISI B1112-steel = 100.

## Low Alloy Steels—Cast

| Class[b] → | 70,000 | 80,000 | 90,000 | 100,000 | 110,000 |
|---|---|---|---|---|---|
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.283 | 0.283 | 0.283 | 0.283 | 0.283 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 27 | 27 | 27 | 27 | 27 |
| Coef of Ther Exp (70–1200 F), per °F | 8.0–8.3 x $10^{-6}$ | 8.0–8.3 x $10^{-6}$ | 8.0–8.3 x $10^{-6}$ | 8.0–8.3 x $10^{-6}$ | 8.0–8.3 x $10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 |
| Elec Res (68 F), microhm-cm | 15–20 | 15–20 | 15–20 | 15–20 | 15–20 |
| Magnetic? | Yes | Yes | Yes | Yes | Yes |
| MECHANICAL PROPERTIES[c] | | | | | |
| Mod of Elast in Tension, psi | 29–30 x $10^6$ | 29–30 x $10^6$ | 29–30 x $10^6$ | 29–30 x $10^6$ | 29–30 x $10^6$ |
| Ten Str, 1000 psi | 70[e] | 80[e] | 90[e] | 100[e] | 110[f] |
| Yld Point, 1000 psi | 45 | 50 | 60 | 68 | 85 |
| Elong (in 2 in.), % | 26 | 24 | 22 | 20 | 20 |
| Red. of Area, % | 56 | 50 | 46 | 42 | 45 |
| Hardness (Brinell) | 150 | 170 | 190 | 209 | 235 |
| Impact Str (Charpy), ft-lb | | | | | |
| 70 F | 35 | 30 | 26 | 22 | 23 |
| –50 F | 25 | 20 | 15 | 12 | 18 |
| Endurance Limit, 1000 psi | 33 | 38 | 41 | 45 | 49 |
| THERMAL TREATMENT | | | | | |
| Annealing Temp, F | About 200 F above critical range | | | | |
| Quenching Temp, F | About 100 F above critical range | | | | |
| FABRICATING PROPERTIES | | | | | |
| Machinability Index[d] | 65 | 70 | 70 | 65 | 60 |
| Weldability | Can be welded by procedures used for wrought steels of similar composition | | | | |
| CORROSION RESISTANCE | Similar to corrosion resistance of carbon steels | | | | |
| USES | Applications requiring excellent weldability; medium strength with high toughness and good machinability; good high temperature properties | | Applications requiring toughness or excellent high temperature and deep hardening properties | | Applications requiring high resistance to impact; excellent low temperature properties; deep hardening; or excellent combination of strength and toughness |

[a] Below 8% total alloy content.
[b] Tensile strength, psi.
[c] Normally expected coupon values for steel castings having tensile strength given.
[d] High speed tool steels based on AISI B1112 steel = 100.
[e] Normalized and tempered.
[f] Quenched and tempered.

## Low Alloy Steels—Cast

| Class[b] → | 120,000 | 150,000 | 175,000 | 200,000 |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Density, lb/cu in. | 0.283 | 0.283 | 0.283 | 0.283 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 27 | 27 | 27 | 27 |
| Coef of Ther Exp (70–1200 F), per °F | 8.0–8.3 x $10^{-6}$ | 8.0–8.3 x $10^{-6}$ | 8.0–8.3 x $10^{-6}$ | 8.0–8.3 x $10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 |
| Elec Res (68 F), microhm-cm | 15–20 | 15–20 | 15–20 | 15–20 |
| Magnetic? | Yes | Yes | Yes | Yes |
| **MECHANICAL PROPERTIES**[c] | | | | |
| Mod of Elast in Tension, psi | 29–30 x $10^6$ | 29–30 x $10^6$ | 29–30 x $10^6$ | 29–30 x $10^6$ |
| Ten Str, 1000 psi | 120[f] | 150[f] | 175[f] | 200[f] |
| Yld Point, 1000 psi | 95 | 125 | 148 | 170 |
| Elong. (in 2 in.), % | 16 | 12 | 8 | 5 |
| Red. of Area, % | 38 | 25 | 20 | 11 |
| Hardness (Brinell) | 245 | 300 | 340 | 400 |
| Impact Str (Charpy), ft-lb | | | | |
| 70 F | 20 | 14 | 10 | — |
| –50 F | 16 | 10 | 6 | — |
| Endurance Limit, 1000 psi | 55 | 65 | 77 | 85 |
| **THERMAL TREATMENT** | | | | |
| Annealing Temp, F | About 200 F above critical range | | | |
| Quenching Temp, F | About 100 F above critical range | | | |
| **FABRICATING PROPERTIES** | | | | |
| Machinability Index[d] | 50 | 30 | — | — |
| Weldability | Can be welded by procedures used for wrought steels of similar composition | | | |
| **CORROSION RESISTANCE** | Generally similar to carbon steels | | | |
| **USES** | Applications requiring high resistance to impact, excellent low temperature properties, deep hardening; excellent combination of strength and toughness | Applications requiring deep hardening, high strength, wear resistance, fatigue resistance | Applications requiring high strength, wear resistance, high hardness, high fatigue resistance | |

[a] Below 8% total alloy content.
[b] Tensile strength, psi.
[c] Normally expected coupon values for steel castings having tensile strength given.
[d] High speed tool steels based on AISI B1112 steel = 100.
[f] Quenched and tempered.

## Stainless Steels—Cast

| ACI Type → | CA-15 | CA-40 | CB-30 | CC-50 |
|---|---|---|---|---|
| COMPOSITION, % | C 0.15 max, Mn 1.0 max, Si 1.5 max, P 0.04 max, S 0.04 max, Cr 11.5–14.0, Ni 1.0 max, Mo 0.5[a] | C 0.20–0.40, Mn 1.0 max, Si 1.50 max, P 0.04 max, S 0.04 max, Cr 11.5–14.0, Ni 1.0 max, Mo 0.5[a] | C 0.30 max, Mn 1.0 max, Si 1.0 max, P 0.04 max, S 0.04 max, Cr 18–22, Ni 2.0 max | C 0.50 max, Mn 1.0 max, Si 1.0 max, P 0.04 max, S 0.04 max, Cr 26–30, Ni 4.0 max |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.275 | 0.275 | 0.272 | 0.272 |
| Melting Point, F | 2750 | 2725 | 2725 | 2725 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 14.5 | 14.5 | 12.8 | 12.6 |
| Coef of Ther Exp (70–1000 F), per °F | $6.4 \times 10^{-6}$ | $6.4 \times 10^{-6}$ | $6.5 \times 10^{-6}$ | $6.4 \times 10^{-6}$ |
| Spec Ht (70 F), Btu/lb/°F | 0.11 | 0.11 | 0.11 | 0.12 |
| Elec Res (70 F), microhm-cm | 78 | 76 | 76 | 77 |
| Magnetic Permeability | Ferromagnetic | Ferromagnetic | Ferromagnetic | Ferromagnetic |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | $29 \times 10^6$ | $29 \times 10^6$ | $29 \times 10^6$ | $29 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Annealed | — | — | 95[f] | 97[g] |
| As Cast | — | — | — | 70–95 |
| Hard. & Temp | 200[c], 100[d] | 220[c], 110[e] | — | — |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Annealed | — | — | 60[f] | 65[g] |
| As Cast | — | — | — | 60–65 |
| Hard. & Temp | 150[c], 75[d] | 165[c], 67[e] | — | — |
| Elong (in 2 in.), % | | | | |
| Annealed | — | — | 15[f] | 18[g] |
| As Cast | — | — | — | 2–15 |
| Hard. & Temp | 7[c], 30[d] | 1[c], 18[e] | — | — |
| Hardness (Brinell) | | | | |
| Annealed | — | — | 195[f] | 210[g] |
| As Cast | — | — | — | 193–212 |
| Hard. & Temp | 390[c], 185[d] | 470[c], 212[e] | — | — |
| Impact Str (Charpy, keyhole notch), ft-lb | | | | |
| As Cast | — | — | — | 2–45 (Izod V notch) |
| Hard. & Temp | 15[c], 35[d] | 1[c], 3[e] | — | — |
| THERMAL TREATMENT | | | | |
| Annealing Temp, F[b] | 1450–1650 f.c. | 1450–1650 f.c. | 1450 f.c. and 1000 a.c. | 1450 f.c. or a.c. |
| Hardening Temp, F[b] | 1800–1850 a.c. or o.q. | 1800–1850 a.c. or o.q. | Practically nonhardenable by heat treatment | Nonhardenable by heat treatment |
| Tempering Temp, F | <600 or 1100–1500. Highest strength and corrosion resistance by tempering below 600 | | — | — |
| FABRICATING PROPERTIES | | | | |
| Castability | Sections from 3/16 in. up can be cast satisfactorily. Somewhat lighter sections can be cast in some parts. Difficult-to-run thin sections and designs involving appreciable changes in section should be avoided. Normal shrinkage for these alloys is 1/4 in. per ft, except CC-50 which shrinks 3/32 in. per ft | | | |
| Weldability | Can be welded by metal arc, inert-gas arc and oxyacetylene gas methods. Metal arc most frequently used. Oxyacetylene welding not advisable because of possible reduction in corrosion resistance resulting from carbon pickup. Castings should be preheated and postheated | | | |
| CORROSION RESISTANCE | Good atmospheric corrosion resistance. Excellent resistance to many organic media in relatively mild service | | Resists nitric acid, alkaline solutions, many organic chemicals, oxidizing atmospheres up to 1400 F | Excellent resistance to dilute sulfuric acid in mine waters, mixed nitric and sulfuric acids, and oxidizing acids |
| USES | Pump casing, bushings and liners, impellers, shafts, turbine blades, stuffing boxes | Choppers, cutting blades, cylinder liners, pump parts, steam turbine parts, molds and dies | Furnace brackets and hangers, pump parts, rabble arms, tube supports, valve bodies | Bushings, cylinder liners, pump casings and impellers, valve bodies and seats |

[a] Molybdenum not intentionally added.
[b] f.c. = furnace cool, a.c. = air cool, o.q. = oil quench.
[c] Air cooled from 1800 F, tempered at 600 F.
[d] Air cooled from 1800 F, tempered at 1450 F.
[e] Air cooled from 1800 F, tempered at 1400 F.
[f] Annealed at 1450 F, furnace cooled to 1000 F, air cooled.
[g] Air cooled from 1900 F.

## Stainless Steels—Cast

| ACI Type → | CD-4MCu | CE-30 | CF-3 | CF-8 | CF-20 |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.04 max, Mn 1.0 max, Si 1.0 max, Cr 25–27, Ni 4.75–6.0, Mo 1.75–2.25, Cu 2.75–3.25 | C 0.30 max, Mn 1.50, Si 2.0 max, P 0.04 max, S 0.04 max, Cr 26–30, Ni 8–11 | C 0.03 max, Mn 1.50 max, Si 2.0 max, Cr 17–21, Ni 8–12 | C 0.08 max, Mn 1.50 max, Si 2.0 max, P 0.04 max, S 0.04 max, Cr 18–21, Ni 8–11 | C 0.20 max, Mn 1.50 max, Si 2.0 max, P 0.04 max, S 0.04 max, Cr 18–21, Ni 8–11 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.277 | 0.277 | 0.280 | 0.280 | 0.280 |
| Melting Point, F | 2650 | 2650 | 2625 | 2600 | 2575 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | — | — | 9.2 | 9.2 | 9.2 |
| Coef of Ther Exp (70–1000 F), per °F | $6.5 \times 10^{-6}$ | $9.6 \times 10^{-6}$ | $10 \times 10^{-6}$ | $10.0 \times 10^{-6}$ | $10.4 \times 10^{-6}$ |
| Spec Ht (70 F), Btu/lb/°F | 0.12 | 0.14 | 0.12 | 0.12 | 0.12 |
| Elec Res (70 F), microhm-cm | — | 85 | 76 | 76 | 77.9 |
| Magnetic Permeability | Ferromagnetic | >1.5 | 1.0–2.0 | 1.0–1.3[c] | 1.01 |
| MECHANICAL PROPERTIES[b] | | | | | |
| Mod of Elast in Tension, psi | $29 \times 10^6$ | $25 \times 10^6$ | $27 \times 10^6$ | $28 \times 10^6$ | $28 \times 10^6$ |
| Ten Str, 1000 psi | 105, 140[d] | 97 | 77 | 77 | 77 |
| Yld Str (0.2% offset), 1000 psi | 85, 110[d] | 63 | 37 | 37 | 36 |
| Elongation (in 2 in.), % | 25, 15[d] | 18 | 55 | 55 | 50 |
| Hardness (Brinell) | 260, 300[d] | 170 | 140 | 140 | 163 |
| Impact Str (Charpy keyhole notch), ft-lb | 37, 12[d] | — | 75 | 74 | 60 |
| FABRICATING PROPERTIES | | | | | |
| Castability | Sections from 3/16 in. up can be cast satisfactorily. Somewhat lighter sections are also possible in some parts. Good castability of these alloys permits designs involving intricate shapes, but drastic changes in section should be avoided and uniform thickness should be maintained as far as possible | | | | |
| Weldability | Can be welded by metal arc, inert-gas arc and oxyacetylene gas methods. Metal arc most frequently used. Oxyacetylene welding not advisable because of possible reduction in corrosion resistance caused by carbon pickup. Preheating not necessary, but castings should be quenched from the range 1950 to 2100 F to restore maximum corrosion resistance. This heat treatment is not always necessary, however, with CE-30 or CF-3 | | | | |
| CORROSION RESISTANCE | Resists strongly oxidizing media such as boiling nitric acid, sulfuric acid and sulfates, and organic acids | Particularly resistant to sulfurous acid, mixtures of dilute sulfuric and sulfurous acids, sulfuric and nitric acids, and sulfites | Similar to CD-4MCu | | Similar to CD-4MCu but used under less drastic conditions |
| USES | Corrosion-erosion service: pump impellers, valves, digesters, processing equipment requiring higher strength than CF-8 | Process equipment such as digester fittings, fractionating towers, piping, pump bodies and castings, valve bodies and parts | Autoclaves, blast furnaces, bushings, filter press plates, hardware, headers and heating coils, pump parts, spray nozzles, valve parts; CF-3 especially useful where castings cannot be heat treated after welding | | Cylinder liners, pumps, return bends, rolls, circuit breaker parts, valve parts |

[b] Water quenched from 2000 F.
[c] After heat treatment.
[d] Water quenched from 2000 F plus 3 hr at 900 F

*continued on next page*

## Stainless Steels—Cast

| ACI Type → | CF-3M | CF-8M, CF-12M | CF-8C | CF-16F |
|---|---|---|---|---|
| COMPOSITION, % | C 0.03 max, Mn 1.5 max, Si 1.5 max, Cr 17–21, Ni 9–13, Mo 2–3 | C 0.08 max (CF–8M) or 0.12 max (CF–12M), Mn 1.5 max, Si 2.0 max, P 0.04 max, S 0.04 max, Cr 18–21, Ni 9–12, Mo 2–3 | C 0.08 max, Mn 1.5 max, Si 2.0 max, P 0.04 max, S 0.04 max, Cr 18–21, Ni 9–12, Cb 1.0 max[b] | C 0.16 max, Mn 1.5 max, Si 2.0 max, P 0.17 max, S 0.04 max, Cr 18–21, Ni 9–12, Se 0.2–0.35, Mo 1.5 max |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.280 | 0.280 | 0.280 | 0.280 |
| Melting Point, F | 2550 | 2550 | 2600 | 2550 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 9.4 | 9.4 | 9.3 | 9.4 |
| Coef of Ther Exp (70–1000 F), per °F | $9.7 \times 10^{-6}$ | $9.7 \times 10^{-6}$ | $10.3 \times 10^{-6}$ | $9.9 \times 10^{-6}$ |
| Spec Ht (70 F), Btu/lb/°F | 0.12 | 0.12 | 0.12 | 0.12 |
| Elec Res (70 F), microhm-cm | 82 | 82 | 71 | 72 |
| Magnetic Permeability | 1.5–2.5 | 1.50–2.50 | 1.20–1.80 | 1.0–2.0 |
| MECHANICAL PROPERTIES[c] | | | | |
| Mod of Elast in Tension, psi | $27 \times 10^6$ | $28 \times 10^6$ | $28 \times 10^6$ | $28 \times 10^6$ |
| Ten Str, 1000 psi | 80 | 80 | 77 | 77 |
| Yld Str (0.2% offset), 1000 psi | 42 | 42 | 38 | 40 |
| Elongation (in 2 in.), % | 50 | 50 | 39 | 52 |
| Hardness (Brinell) | 156–170 | 156–170 | 149 | 150 |
| Impact Str (Charpy, keyhole notch), ft-lb | 70 | 70 | 30 | 75 |
| FABRICATING PROPERTIES | | | | |
| Castability | Sections from 3/16 in. up can be cast satisfactorily. Somewhat lighter sections are also possible in some parts. Good castability of these alloys permits designs involving intricate shapes, but drastic changes in section should be avoided and uniform thickness should be maintained as far as possible | | | |
| Weldability | Can be welded by metal arc, inert-gas arc and oxyacetylene gas methods. Metal arc most frequently used. Oxyacetylene welding not advisable because of possible reduction in corrosion resistance caused by carbon pickup. Preheating not necessary, but castings should be quenched from the range 1950 to 2100 F to restore maximum corrosion resistance. This heat treatment is not always necessary, however, with CF-3M or CF-8C | | | |
| CORROSION RESISTANCE | Resists reducing media. More resistant to pitting corrosion than CF–8 in contact with chlorides. Not as resistant to boiling nitric acid as CF–8 | | Resists strongly oxidizing media such as boiling nitric acid, sulfuric acid and sulfates, and organic acids | Similar to CF–8C but somewhat inferior |
| USES | Agitators, evaporator parts, jet engine components, spray nozzles, high pressure steam valves; especially useful where castings cannot be heat treated after welding | Agitators, evaporator parts, jet engine components, spray nozzles, high pressure steam valves | Aircraft shroud assemblies, autoclaves, chemical tubing, fittings, jet engine parts, marine fittings | Bearings, bushings, fittings, pump and machinery parts |

[b] Minimum is eight times carbon content. Cb + Ta: 1.35% max; minimum is ten times carbon content.
[c] Water quenched from 2000 F.

## Stainless Steels—Cast

| ACI Type → | CG-8M | CH-20 | CK-20 | CN-7M |
|---|---|---|---|---|
| COMPOSITION, % | C 0.08 max, Mn 1.5 max, Si 1.5 max, Cr 18–21, Ni 9–13, Mo 3–4 | C 0.20 max, Mn 1.5 max, Si 2.0 max, P 0.04 max, S 0.04 max, Cr 22–26, Ni 12–15 | C 0.20 max, Mn 1.5 max, Si 2.0 max, P 0.04 max, S 0.04 max, Cr 23–27, Ni 19–22 | C 0.07 max, Mn 1.5 max, Si 1.5 max, P 0.04 max, S 0.04 max, Cr 19–22, Ni 27.5–30.5, Mo 1.75–2.50, Cu 3.0 min |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.281 | 0.279 | 0.280 | 0.289 |
| Melting Point, F | 2550 | 2600 | 2600 | 2650 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 9.4 | 8.2 | 8.2 | 12.1 |
| Coef of Ther Exp (70–1000 F), per °F | $9.7 \times 10^{-6}$ | $9.6 \times 10^{-6}$ | $9.2 \times 10^{-6}$ | $9.7 \times 10^{-6}$ |
| Spec Ht (70 F), Btu/lb/°F | 0.12 | 0.12 | 0.12 | 0.11 |
| Elec Res (70 F), microhm-cm | 82 | 84 | 90 | 89.6 |
| Magnetic Permeability | 1.5–2.5 | 1.71[c] | 1.02 | 1.01–1.10 |
| MECHANICAL PROPERTIES[b] | | | | |
| Mod of Elast in Tension, psi | $28 \times 10^6$ | $28 \times 10^6$ | $29 \times 10^6$ | $24 \times 10^6$ |
| Ten Str, 1000 psi | 82 | 88 | 76 | 69 |
| Yld Str (0.2% offset), 1000 psi | 43 | 50 | 38 | 31 |
| Elong (in 2 in.), % | 50 | 38 | 37 | 48 |
| Hardness (Brinell) | 170 | 190 | 144 | 130 |
| Impact Str (Charpy, keyhole notch), ft-lb | 70 | 30 | 50 (Izod V notch) | 70 |
| FABRICATING PROPERTIES | | | | |
| Castability | Sections from 3/16 in. up can be cast satisfactorily. Somewhat lighter sections are also possible on some parts. Good castability permits designs involving intricate shapes, but drastic changes in section should be avoided | | | |
| Weldability | Can be welded by metal arc, inert-gas arc, and oxyacetylene gas methods. Metal arc welding most used. Oxyacetylene welding not advisable because of possible reduction in corrosion resistance resulting from carbon pickup | | | |
| | Preheating not necessary, but castings should be quenched from 2000–2100 F to restore maximum corrosion resistance | | | Preheating at 400 F necessary. After welding, castings should be quenched from 2000 F |
| CORROSION RESISTANCE | Similar to CF-8M, but preferred in reducing environments | Resistant to hot dilute sulfuric acid. Superior to CF-8 in certain media | Similar to CH-20, but better resistance at elevated temperatures | Resists sulfuric acid and many reducing chemicals. Good resistance to dilute hydrochloric acid and salt solutions |
| USES | Especially useful for applications in the pulp and paper industry | Digester fittings, roasting equipment, valves, pump parts | Digesters, filter press parts, fittings, jet engine parts, pumps, valves | Filter parts, heat exchanger parts, pickling rolls, hooks, racks and tanks; valve parts |

[b] Water quenched from 2000 F.
[c] After heat treatment.

## Heat Resistant Alloys—Cast

| ACI Type → | HA | HC | HD | HE | HF |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.20 max, Mn 0.35-0.65, Si 1.00 max, P 0.04 max, S 0.04 max, Mo 0.90-1.20, Cr 8-10 | C 0.50 max, Mn 1.00 max, Si 2.00 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 26-30, Ni 4 max | C 0.50 max, Mn 1.50 max, Si 2.00 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 26-30, Ni 4-7 | C 0.20-0.50, Mn 2.00 max, Si 2.00 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 26-30, Ni 8-11 | C 0.20-0.40, Mn 2.00 max, Si 2.00 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 19-23, Ni 9-12 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.279 | 0.272 | 0.274 | 0.277 | 0.280 |
| Melting Point, F | 2750 | 2725 | 2700 | 2650 | 2550 |
| Ther Cond (212 F), Btu/hr/sq ft/ft/°F | 15.2 | 12.6 | 12.6 | 10.0[f] | 9.0 |
| Coef of Ther Exp (70-1200 F), per °F | $7.5 \times 10^{-6}$ | $6.4 \times 10^{-6}$ | $8.0 \times 10^{-6}$ | $9.9 \times 10^{-6}$ | $10.1 \times 10^{-6}$ |
| Spec Ht (70 F), Btu/lb/°F | 0.11 | 0.12 | 0.12 | 0.14 | 0.12 |
| Elec Res (70 F), microhm-cm | 70 | 77 | 81 | 85 | 80 |
| Magnetic Permeability | Ferromagnetic | Ferromagnetic | Ferromagnetic | 1.3-2.5 | 1.0 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $29 \times 10^6$ | $29 \times 10^6$ | $27 \times 10^6$ | $25 \times 10^6$ | $28 \times 10^6$ |
| Ten Str, 1000 psi[b] | 95[c], 107[d] | 70-110, 115[e] | 85, — | 95, 90[e] | 85, 100[e] |
| Yld Str (0.2% offset), 1000 psi[b] | 65[c], 81[d] | 65-75, 80[e] | 48, — | 45, 55[e] | 45, 50[e] |
| Elong (2 in.), %[b] | 23[c], 21[d] | 2-19, 18[e] | 16, — | 20, 10[e] | 35, 25[e] |
| Hardness (Brinell)[b] | 180[c], 220[d] | 190-223, — | 190, — | 200, 270[e] | 165, 190[e] |
| ELEVATED TEMPERATURE PROPERTIES | | | | | |
| Ten Str, 1000 psi | 67 (1000 F), 44 (1100 F) | — | 36 (1400 F), 23 (1600 F), 15 (1800 F) | — | 57 (1200 F), 35 (1400 F), 22 (1600 F) |
| Yld Str (0.2% offset), 1000 psi | 42 (1000 F), 32 (1100 F) | — | — | — | 21 (1400 F) |
| Elong (2 in.), % | 36 (1100 F) | — | 14 (1400 F), 18 (1600 F), 40 (1800 F) | — | 16 (1200 F), 20 (1400 F), 22 (1600 F) |
| Creep Str (0.0001%/hr), 1000 psi | 16 (1000 F), 7.2 (1100 F), 3.1 (1200 F) | 1.3 (1400 F), 0.75 (1600 F), 0.36 (1800 F) | 3.5 (1400 F), 1.9 (1600 F), 0.9 (1800 F) | 4.0 (1400 F), 2.4 (1600 F), 1.4 (1800 F) | 13 (1200 F), 6.0 (1400 F), 3.2 (1600 F) |
| Rupture Str, 1000 psi 10 Hr | 45 (1000 F) | 4.6 (1400 F), 2.0 (1600 F), 1.1 (1800 F) | 14 (1400 F) | — | 37 (1200 F), 20 (1400 F), 10 (1600 F) |
| 100 Hr | 37 (1000 F) | 3.3 (1400 F), 1.7 (1600 F), 0.85 (1800 F) | 10 (1400 F), 5 (1600 F), 2.5 (1800 F) | 11 (1400 F), 5.3 (1600 F), 2.5 (1800 F) | 30 (1200 F), 14 (1400 F), 6.0 (1600 F) |
| 1000 Hr | 27 (1000 F) | 2.3 (1400 F), 1.3 (1600 F), 0.62 (1800 F) | 7 (1400 F) | — | 17 (1200 F), 8.0 (1400 F), 3.8 (1600 F) |
| FABRICATING PROPERTIES | | | | | |
| Annealing Temp, F | 1625 | — | — | — | 1900[g] |
| Machinability | Fair | Good | Good | Good | Good |
| Weldability | Weldable by all common methods. Preheating, postheating desirable | | Weldable by all common methods. Preheating not required | | |
| USES | Fan blades, furnace rollers, lehr rolls, refinery fittings, trunnions | Grate bars, dampers, kiln parts, rabble blades, salt pots, tuyeres | Brazing furnace parts, cracking equipment, furnace blowers, pouring spouts, salt pots, gas burner parts | Billet skids, burner nozzles, furnace conveyors, tube supports, soot blower elements | Electrode arms, burner tips, annealing boxes, wear plates, gas burner rings, conveyor belts, dampers |

[a] Molybdenum not intentionally added. [b] As cast and heat treated values given in that order.
[c] Annealed. [d] Normalized at 1825 F, tempered at 1250 F.
[e] Aged 24 hr at 1400 F, furnace cooled. [f] At 1500 F.
[g] Before cyclic temperature service; 6 hr at 1900 F may improve life.

## Heat Resistant Alloys—Cast

| ACI Type → | HH | | HI | HK | HL |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.20–0.50, Mn 2.00 max, Si 2.00 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 24–28, Ni 11–14, N 0.2 max | | C 0.20-0.50, Mn 2.00 max, Si 2.00 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 26-30, Ni 14-18 | C 0.20-0.60, Mn 2.00 max, Si 2.00 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 24-28, Ni 18-22 | C 0.20-0.60, Mn 2.00 max, Si 2.00 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 28-32, Ni 18-22 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.279 | | 0.279 | 0.280 | 0.279 |
| Melting Point, F | 2500 | | 2550 | 2550 | 2600 |
| Ther Cond (212F), Btu/hr/sq ft/ft/°F | 8.2 | | 10.9 | 8.2 | 8.2 |
| Coef of Ther Exp (70–1800 F), per °F | $10.5 \times 10^{-6}$ | | $10.5 \times 10^{-6}$ | $10.0 \times 10^{-6}$ | $9.9 \times 10^{-6}$ |
| Spec Ht (70 F), Btu/lb/°F | 0.12 | | 0.12 | 0.12 | 0.12 |
| Elec Res (70 F), microhm-cm | 75-85 | | — | 90 | 94 |
| Magnetic Permeability | 1.0-1.9 | | 1.0-1.7 | 1.02 | 1.01 |
| MECHANICAL PROPERTIES | Type I[c] | Type II[c] | | | |
| Mod of Elast in Tension, psi | $27 \times 10^6$ | $27 \times 10^6$ | $27 \times 10^6$ | $29 \times 10^6$ | $29 \times 10^6$ |
| Ten Str, 1000 psi[b] | 80, 86 | 85, 92 | 80, 90 | 75, 85 | 82, — |
| Yld Str, 1000 psi[b] | 50, 55 | 40, 45 | 45, 65 | 50, 50 | 52, — |
| Elong (2 in.), %[b] | 25, 11 | 15, 8 | 12, 6 | 17, 10 | 19, — |
| Hardness (Brinell)[b] | 185, 200 | 180, 200 | 180, 200 | 170, 190 | 192, — |
| ELEVATED TEMPERATURE PROPERTIES | | | | | |
| Ten Str, 1000 psi | | | | | |
| 1400 F | 33 | 35 | 38 | — | 50 |
| 1600 | 18.5 | 22 | 26 | 23 | 30 |
| 1800 F | 9.0 | 11 | — | — | 18.7 |
| Yld Str (0.2% offset), 1000 psi | | | | | |
| 1400 F | 17 | 18 | — | — | — |
| 1600 F | 13.5 | 14 | — | — | — |
| 1800 F | 6.3 | 7.0 | — | — | — |
| Elong (2 in.), % | | | | | |
| 1400 F | 18 | 12 | 6 | — | — |
| 1600 F | 30 | 16 | 12 | 21 | — |
| 1800 F | 45 | 30 | — | — | — |
| Creep Str (0.0001% hr), 1000 psi | | | | | |
| 1400 F | 3.0 | 7.0 | 6.6 | 6.8 | 7.0 |
| 1600 F | 1.7 | 4.0 | 3.6 | 4.2 | 4.3 |
| 2001 F | 0.3 | 0.8 | 0.8 | 1.0 | — |
| 2150 F | — | — | 0.15 | 0.2 | — |
| Rupture Str, 1000 psi | | | | | |
| 10 Hr 1400 F | — | 20 | — | 23 | — |
| 10 Hr 1600 F | — | 10 | — | 11 | — |
| 10 Hr 1800 F | 4.7 | 6.0 | — | 6.5 | — |
| 100 Hr 1400 F | 14 | 14 | 13 | 14.5 | 15 |
| 100 Hr 1600 F | 6.4 | 7.5 | 7.5 | 7.8 | 9.2 |
| 100 Hr 2000 F | 1.5 | 1.8 | 1.9 | 2.5 | — |
| 1000 Hr 1400 F | 6.5 | 10 | 8.5 | 9.0 | — |
| 1000 Hr 1600 F | 3.8 | 4.7 | 4.8 | 5.0 | — |
| 1000 Hr 2000 F | — | 1.2 | 1.2 | — | — |
| FABRICATING PROPERTIES | | | | | |
| Annealing Temp, F | 1900[d] | 1900[d] | — | — | — |
| Machinability | Fair | Fair | Fair | Good | Good |
| Weldability | Weldable by all common methods; no preheat or postheat required | | | | |
| USES | Annealing trays, tube supports, carburizing boxes, exhaust manifolds, radiant tubes, retorts, stoker parts | | Billet skids, brazing fixtures, furnace rails, lead pots, tube spacers, retorts | Heat treating fixtures, rabble arms, retorts, brazing fixtures, skid rails | Carrier fingers, enameling furnace fixtures, furnace skids, stack dampers |

[a] Molybdenum not intentionally added.
[b] As cast and heat treated (aged 24 hr at 1400 F, furnace cooled), values given in that order.
[c] Partially ferritic.
[d] Before cyclic temperature service; 12 hr at 1900 F may improve life. [e] Austenitic.

*continued on next page*

## Heat Resistant Alloys—Cast

| ACI Type → | HN | HT | HU | HW | HX |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.20-0.50, Mn 2.00 max, Si 2.00 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 19-23, Ni 23-27 | C 0.35-0.75, Mn 2.00 max, Si 2.50 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 13-17, Ni 33-37 | C 0.35-0.75, Mn 2.00 max, Si 2.50 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 17-21, Ni 37-41 | C 0.35-0.75, Mn 2.00 max, Si 2.50 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 10-14, Ni 58-62 | C 0.35-0.75, Mn 2.00 max, Si 2.50 max, P 0.04 max, S 0.04 max, Mo 0.5 max[a], Cr 15-19, Ni 64-68 |
| **PHYSICAL PROPERTIES** | | | | | |
| Density, lb/cu in. | 0.283 | 0.286 | 0.290 | 0.294 | 0.294 |
| Melting Point, F | 2500 | 2450 | 2450 | 2350 | 2350 |
| Ther Cond (212F), Btu/hr/sq ft/ft/°F | — | 7.7 | — | 7.7 | — |
| Coef of Ther Exp (70–1800 F), per °F | — | $9.8 \times 10^{-6}$ | $9.6 \times 10^{-6}$ | $8.8 \times 10^{-6}$ | $9.2 \times 10^{-6}$ |
| Spec Ht (70 F), Btu/lb/°F | 0.11 | 0.11 | 0.11 | 0.11 | 0.11 |
| Elec Res (70 F), microhm-cm | — | 100 | 105 | 112 | — |
| Magnetic Permeability | 1.10 | 1.10-2.00 | 1.10-2.00 | 16.0 | 2.0 |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, psi | $27 \times 10^6$ | $27 \times 10^6$ | $27 \times 10^6$ | $25 \times 10^6$ | $25 \times 10^6$ |
| Ten Str, 1000 psi[b] | 68, — | 70, 75[c] | 70, 73[c] | 68, 84[f] | 65, 73[c] |
| Yld Str, 1000 psi[b] | 38, — | 40, 45[c] | 40, 43[c] | 36, 52[f] | 36, 44[c] |
| Elong (2 in.), %[b] | 17, — | 10, 5[c] | 9, 5[c] | 4, 4[f] | 9, 9[c] |
| Hardness (Brinell)[b] | 160, — | 180, 200[c] | 170, 190[c] | 185, 205[f] | 176, 185[c] |
| **ELEVATED TEMPERATURE PROPERTIES** | | | | | |
| Ten Str, 1000 psi | | | | | |
| 1400 F | — | 35 | 40 | 32 | — |
| 1600 F | — | 18.8 | 19.6 | 19 | 20.5 |
| 1800 F | — | 11 | 10.0 | 10 | 10.7 |
| Yld Str (0.2% offset), 1000 psi | | | | | |
| 1400 F | — | 26 | — | 23 | — |
| 1600 F | — | 15 | — | 15 | 17.5 |
| 1800 F | — | 8.0 | 6.2 | 8.0 | 6.9 |
| Elong (2 in.), % | | | | | |
| 1400 F | — | 10 | — | — | — |
| 1600 F | — | 26 | 20 | — | 48 |
| 1800 F | — | 28 | 28 | 40 | 40 |
| Creep Str (0.0001%/hr), 1000 psi | | | | | |
| 1400 F | — | 8.0 | 8.5 | 6.0 | 6.4 |
| 1600 F | 6.3 | 4.5 | 5.0 | 3.0 | 3.2 |
| 2000 F | 0.9 | 0.5 | 0.6 | — | 0.6 |
| 2150 F | — | 0.15 | — | — | — |
| Rupture Str, 1000 psi | | | | | |
| 10 Hr 1400 F | — | — | — | 16 | 18 |
| 10 Hr 1600 F | — | 11 | — | 8.2 | 10 |
| 10 Hr 2000 F | — | — | — | — | 2.5 |
| 100 Hr 1400 F | — | 18 | 15 | 10 | 13 |
| 100 Hr 1600 F | 9.5 | 8.5 | 8.0 | 6.0 | 6.7 |
| 100 Hr 2000 F | 2.5 | 2.5 | — | — | 1.7 |
| 1000 Hr 1400 F | — | 12.5 | — | 7.8 | — |
| 1000 Hr 1600 F | 6.5 | 7.0 | 6.0 | 4.5 | 4.0 |
| 1000 Hr 2000 F | 0.9 | 1.8 | — | — | 0.9 |
| **FABRICATING PROPERTIES** | | | | | |
| Annealing Temp, F | — | 1900[d] | 1900[d] | — | — |
| Machinability | Good | Good | Good | Good | Good |
| Weldability | Weldable by all common methods; no preheat or postheat required | | | | |
| **USES** | Brazing fixtures, chain, nozzles, furnace parts, radiant tubes, tube supports | Air ducts, carburizing boxes, cyanide pots, glass molds, lead pots | Articulated trays, burner tubes, lead pots, cyanide pots, muffles | Cyanide pots, gas retorts, electric heating elements, hearth plates | Autoclaves, calciner tubes, furnace parts, salt bath electrodes, muffles |

[a] Molybdenum not intentionally added. [b] As cast and heat treated values given in that order.
[c] Aged 24 hr at 1400 F, air cooled. [d] Before cyclic temperature service; 6 hr at 1900 F may improve life.
[e] Aged 24 hr at 1800 F, air cooled. [f] Aged 48 hr at 1800 F, furnace cooled.

## Standard Tool Steels—Wrought

| AISI Type → | Water Hardening Tool Steels (W) | | | | | Shock Resisting Tool Steels (S) | | | |
|---|---|---|---|---|---|---|---|---|---|
| | W1, W2 | W3 | W4 | W5 | W6, W7 | S1 | S2 | S3 | S4, S5 |
| COMPOSITION, % | C 0.60–1.40, V 0.25 (W2) | C 1.00, V 0.50 | C 0.60–1.40, Cr 0.25 | C 1.10, Cr 0.50 | C 1.00, Cr 0.25–0.50, V 0.20–0.25 | C 0.50, Cr 1.50, W 2.50 | C 0.50, Si 1.00, Mo 0.50 | C 0.50, Cr 0.75, W 1.00 | C 0.55 Si, 2.00, Mn 0.80, Mo 0.40 (S5) |
| HEAT TREATMENTS | | | | | | | | | |
| Forging Temp, F | 1800–1950 | 1800–1950 | 1800–1950 | 1800–1950 | 1800–1950 | 1850–2050 | 1850–2050 | 1850–2050 | 1850–2050 |
| Anneal Temp, F | 1360–1450 | 1360–1450 | 1360–1450 | 1360–1450 | 1360–1450 | 1450–1500 | 1400–1450 | 1450–1500 | 1400–1450 |
| Hard. Temp, F | 1400–1550 | 1400–1550 | 1400–1550 | 1400–1550 | 1400–1550 | 1650–1800 | 1550–1650 | 1500–1600 | 1600–1750 |
| Quench Medium[a] | B or W | B or W | B or W | B or W | B or W | O | B or W | B or W | O or W |
| Temper Temp, F | 300–650 | 300–650 | 300–650 | 300–650 | 300–650 | 400–1200 | 300–800 | 300–600 | 350–800 |
| Hardness, Rockwell | C65–50 | C65–50 | C65–50 | C65–50 | C65–50 | C58–40 | C60–50 | C59–50 | C60–50 |
| SERVICE PROPERTIES[b] | | | | | | | | | |
| Depth of Hard. | Shallow | Shallow | Shallow | Shallow | Shallow | Medium | Medium | Medium | Medium |
| Nondeformability | Poor | Poor | Poor | Poor | Poor | Fair | Poor | Poor | Poor-fair |
| Safety in Hard. | Fair | Fair | Fair | Fair | Fair | Good | Poor | Poor | Poor-good |
| Toughness | Good | Good | Good | Good | Good | Very good | Best | Good | Best |
| Wear Res | Fair-good | Fair-good | Fair-good | Fair-good | Fair-good | Fair | Fair | Fair | Fair |
| Machinability | Best | Best | Best | Best | Best | Fair | Fair | Fair | Fair |
| Res to Decarb | Best | Best | Best | Best | Best | Fair-good | Poor | Fair | Poor |
| REMARKS | Shallow hardening, hard case, tough core; subject to distortion during heat treatment; do not retain properties above about 350 F | | | | | Better toughness, less wear resistance than W grades; can be carburized for greater hardness and wear resistance; subject to distortion during heat treatment | | | |
| TYPICAL USES | All types of tools and dies for short runs, especially cold heading dies | | | | | Punching, shearing or trimming dies | | | |

[a] B = brine; W = water; O = oil.
[b] Values on this and next four pages are relative to all tool steels covered.

*continued on next page*

## Standard Tool Steels—Wrought

| AISI Type → | Cold Work Tool Steels—Oil Hardening (O) | | | Cold Work Tool Steels—Air Hardening (A) | | | |
|---|---|---|---|---|---|---|---|
| | O1 | O2 | O7 | A2 | A4 | A5 | A6 |
| COMPOSITION, % | C 0.90, Mn 1.00, Cr 0.50, W 0.50 | C 0.90, Mn 1.00 | C 1.20, Cr 0.75, W 1.75 | C 1.00, Cr 5.00, Mo 1.00 | C 1.00, Mn 2.00, Cr 1.00, Mo 1.00 | C 1.00, Mn 3.00, Cr 1.00, Mo 1.00 | C 0.70, Mn 2.00, Cr 1.00, Mo 1.00 |
| HEAT TREATMENTS | | | | | | | |
| Forging Temp, F | 1800–1950 | 1800–1925 | 1800–2000 | 1850–2000 | 1850–2000 | 1850–2000 | 1400–2050 |
| Anneal Temp, F | 1400–1450 | 1375–1425 | 1450–1500 | 1550–1600 | 1360–1400 | 1360–1400 | 1350–1375 |
| Hard Temp, F | 1450–1500 | 1400–1475 | 1450–1625 | 1700–1800 | 1500–1600 | 1450–1550 | 1525–1600 |
| Quench Medium* | O | O | O or W | A | A | A | A |
| Temper Temp, F | 300–500 | 300–500 | 325–550 | 350–1000 | 300–800 | 300–800 | 300–800 |
| Hardness, Rockwell | C62–57 | C62–57 | C64–58 | C62–57 | C62–54 | C60–54 | C60–54 |
| SERVICE PROPERTIES | | | | | | | |
| Depth of Hard | Medium | Medium | Medium | Deep | Deep | Deep | Deep |
| Nondeformability | Very good | Very good | O: Very good W: Poor | Best | Best | Best | Best |
| Safety in Hard | Very good | Very good | O: Very good W: Poor | Best | Best | Best | Best |
| Toughness | Fair | Fair | Fair | Fair | Fair | Fair | Fair |
| Wear Res | Good | Good | Good | Very good | Good | Good | Good |
| Machinability | Good | Good | Good | Fair | Fair-poor | Fair-poor | Fair-poor |
| Res to Decarb | Good | Good | Good | Fair | Good-fair | Good-fair | Good-fair |
| REMARKS AND USES | Better hardenability and less distortion than W types; dies of all types | | | Less distortion, better safety in hardening than O types; dies of all types | | | |

| AISI Type → | Cold Work Tool Steels—High Carbon-High Chromium (D) | | | | | | |
|---|---|---|---|---|---|---|---|
| | D1 | D2 | D3 | D4 | D5 | D6 | D7 |
| COMPOSITION, % | C 1.00, Cr 12.00, Mo 1.00 | C 1.50, Cr 12.00, Mo 1.00 | C 2.25, Cr 12.00 | C 2.25, Cr 12.00, Mo 1.00 | C 1.50, Cr 12.00, Mo 1.00, Co 3.00 | C 2.25, Si 1.00, Cr 12.00, W 1.00 | C 2.35, Cr 12.00, Mo 1.00, V 4.00 |
| HEAT TREATMENTS | | | | | | | |
| Forging Temp, F | 1850–2000 | 1850–2000 | 1850–2000 | 1850–2000 | 1850–2000 | 1850–2000 | 2050–2125 |
| Anneal Temp, F | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 |
| Hard. Temp, F | 1775–1850 | 1800–1875 | 1700–1800 | 1775–1850 | 1800–1875 | 1700–1750 | 1850–1950 |
| Quench Medium* | A | A | O | A | A | O | A |
| Temper Temp, F | 400–1000 | 400–1000 | 400–1000 | 400–1000 | 400–1000 | 400–1000 | 300–1000 |
| Hardness, Rockwell | C61–54 | C61–54 | C61–54 | C61–54 | C61–54 | C61–54 | C65–58 |
| SERVICE PROPERTIES | | | | | | | |
| Depth of Hard | Deep | Deep | Deep | Deep | Deep | Deep | Deep |
| Nondeformability | Best | Best | Very good | Best | Best | Very good | Best |
| Safety in Hard | Best | Best | Good | Best | Best | Good | Best |
| Toughness | Fair | Poor | Poor | Poor | Poor | Poor | Poor |
| Wear Res | Very good | Best | Best | Best | Best | Best | Best |
| Machinability | Poor | Poor | Poor | Poor | Poor | Poor | Poor |
| Res to Decarb | Fair | Fair | Fair | Fair | Fair | Fair | Fair |
| REMARKS AND USES | Very wear resistant, difficult to machine; little distortion during heat treatment; long runs in all types of tools and dies | | | | | | |

* A = air; O = oil; W = water.

## Standard Tool Steels—Wrought

| AISI Type → | Hot Work Tool Steels (H) | | | | | | |
|---|---|---|---|---|---|---|---|
| | Chromium-Base | | | | | | Tungsten-Base |
| | H11 | H12 | H13 | H14 | H15 | H16 | H20, H21 |
| COMPOSITION, % | C 0.35, Cr 5.00, Mo 1.50, V 0.40 | C 0.35, Cr 5.00, Mo 1.50, W 1.50, V 0.40 | C 0.35, Cr 5.00, Mo 1.50, V 1.00 | C 0.40, Cr 5.00, W 5.00 | C 0.40, Cr 5.00, Mo 5.00 | C 0.55, Cr 7.00, W 7.00 | C 0.35, Cr 2.00–3.50, W 9.00 |
| HEAT TREATMENTS | | | | | | | |
| Forging Temp, F | 1950–2100 | 1950–2100 | 1950–2100 | 1950–2100 | 1900–2100 | 1950–2150 | 1950–2150 |
| Anneal Temp, F | 1550–1650 | 1550–1650 | 1550–1650 | 1600–1650 | 1550–1600 | 1600–1650 | 1600–1650 |
| Hard. Temp, F | 1825–1875 | 1825–1875 | 1825–1900 | 1850–1950 | 2100–2300 | 2050–2150 | 2000–2200 |
| Quench Medium[a] | A | A | A | A | A or O | A or O | A or O |
| Temper Temp, F | 1000–1200 | 1000–1200 | 1000–1200 | 1100–1200 | 1100–1200 | 1050–1250 | 1100–1250 |
| Hardness, Rockwell | C54–38 | C55–38 | C53–38 | C47–40 | C49–36 | C60–45 | C54–36 |
| SERVICE PROPERTIES | | | | | | | |
| Depth of Hard | Deep | Deep | Deep | Deep | Deep | Deep | Deep |
| Nondeformability | Very good | Very good | Very good | Good | A: Good<br>O: Fair | Good | A: Good<br>O: Fair |
| Safety in Hard | Best | Best | Best | Best | Fair | Good | Good |
| Toughness | Good | Good | Good | Good | Good | Good | Good |
| Wear Res | Fair | Fair | Fair | Fair | Fair | Fair | Fair-good |
| Machinability | Fair | Fair | Fair | Fair | Fair | Fair | Fair |
| Res to Decarb | Fair | Fair | Fair | Fair | Poor | Fair | Fair |
| REMARKS AND USES | Little distortion in heat treatment; dies for die casting, forging, extrusion, punching, etc. for use at temp up to 900 F | | | | | | Some distortion; dies up to 1100 F |

| AISI Type → | Hot Work Tool Steels (cont'd) | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| | Tungsten-Base (cont'd) | | | | | Molybdenum-Base | | |
| | H22 | H23 | H24 | H25 | H26 | H41 | H42 | H43 |
| COMPOSITION, % | C 0.35, Cr 2.00, W 11.00 | C 0.30, Cr 12.00, W 12.00 | C 0.45, Cr 3.00, W 15.00 | C 0.25, Cr 4.00, W 15.00 | C 0.50, Cr 4.00, W 18.00, V 1.00 | C 0.65, Cr 4.00, Mo 8.00, W 1.50, V 1.00 | C 0.60, Cr 4.00, Mo 5.00, W 6.00, V 2.00 | C 0.55, Cr 4.00, Mo 8.00, V 2.00 |
| HEAT TREATMENTS | | | | | | | | |
| Forging Temp, F | 1950–2150 | 1950–2150 | 1950–2150 | 1950–2150 | 1950–2150 | 1900–2050 | 1900–2050 | 1900–2050 |
| Anneal Temp, F | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 | 1500–1600 | 1550–1650 | 1500–1600 |
| Hard. Temp, F | 2000–2200 | 2200–2325 | 2000–2250 | 2100–2300 | 2150–2300 | 2000–2175 | 2050–2225 | 2000–2175 |
| Quench Medium[a] | A or O | A or O | A or O | A or O | S, O or A | O, A or S | O, A or S | O, A or S |
| Temper Temp, F | 1100–1250 | 1200–1500 | 1050–1200 | 1050–1250 | 1050–1250 | 1050–1200 | 1050–1200 | 1050–1200 |
| Hardness, Rockwell | C52–39 | C47–30 | C55–45 | C44–35 | C58–43 | C60–50 | C60–50 | C58–45 |
| SERVICE PROPERTIES | | | | | | | | |
| Depth of Hard | Deep | Deep | Deep | Deep | Deep | Deep | Deep | Deep |
| Nondeformability | A: Good<br>O: Fair | A: Good<br>O: Fair | A: Good<br>O: Fair | A: Good<br>O: Fair | S, A: Good<br>O: Fair | S, A: Good<br>O: Fair | S, A: Good<br>O: Fair | S, A: Good<br>O: Fair |
| Safety in Hard | Good | Good | Good | Good | Good | Fair | Fair | Fair |
| Toughness | Good | Fair | Fair | Good | Fair | Poor | Poor | Poor |
| Wear Res | Fair-good | Fair-good | Good | Fair | Good | Good | Good | Good |
| Machinability | Fair | Fair | Fair | Fair | Fair | Fair | Fair | Fair |
| Res to Decarb | Fair | Fair | Fair | Fair | Fair | Poor | Fair | Poor |
| REMARKS AND USES | Tendency to distort during heat treatment; more resistant to heat than chromium-base but more susceptible to thermal shock; dies for die casting, forging, extrusion, punching, etc. at temp up to 1100 F. H24, H25 and H26 may be used at temp above 1100 F | | | | | | | |

[a] A = air; O = oil; S = salt.

*continued on next page*

## Standard Tool Steels—Wrought

| AISI Type → | High Speed Tool Steels—Tungsten-Base (T) | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| | T1, T2, T3 | T4 | T5 | T6 | T7 | T8 | T9 | T15 |
| COMPOSITION, % | C 0.70–1.05, Cr 4.00, V 1.00–3.00, W 18.00 | C 0.75, Cr 4.00, W 18.00, V 1.00, Co 5.00 | C 0.80, Cr 4.00, W 18.00, V 2.00, Co 8.00 | C 0.80, Cr 4.50, W 20.00, V 1.50, Co 12.00 | C 0.75, Cr 4.00, W 14.00, V 2.00 | C 0.75, Cr 4.00, W 14.00, V 2.00, Co 5.00 | C 1.20, Cr 4.00, W 18.00, V 4.00 | C 1.50, Cr 4.00, W 12.00, V 5.00, Co 5.00 |
| HEAT TREATMENTS | | | | | | | | |
| Forging Temp, F | 1950–2150 | 1950–2150 | 1950–2150 | 1950–2150 | 1950–2150 | 1950–2150 | 1950–2150 | 1950–2150 |
| Anneal Temp, F | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 | 1600–1650 |
| Hard. Temp, F | 2250–2375 | 2300–2375 | 2325–2400 | 2325–2400 | 2300–2350 | 2300–2375 | 2275–2325 | 2200–2300 |
| Quench Medium[a] | O, A or S | O, A or S | O, A or S | O, A or S | O, A or S | O, A or S | O, A or S | O, A or S |
| Temper Temp, F | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1200 |
| Hardness, Rockwell | C66–60 | C66–62 | C65–60 | C65–60 | C65–60 | C65–60 | C66–61 | C68–63 |
| SERVICE PROPERTIES | | | | | | | | |
| Depth of Hard | Deep | Deep | Deep | Deep | Deep | Deep | Deep | Deep |
| Nondeformability | Good | Good | Good | Good | Good | Good | Good | Good |
| Safety in Hard | Good | Fair | Fair | Fair | Good | Fair | Fair | Fair |
| Toughness | Poor | Poor | Poor | Poor | Poor | Poor | Poor | Poor |
| Wear Res | Very good | Very good | Very good | Very good | Very good | Very good | Best | Best |
| Machinability | Fair | Fair | Fair | Fair | Fair | Fair | Fair | Fair |
| Res to Decarb | Good | Fair | Poor | Poor | Good | Fair | Good | Fair |
| REMARKS AND USES | Difficult to machine and grind; generally used as cutting tools | | | | | | | |

| AISI Type → | High Speed Tool Steels—Molybdenum-Base (M) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | M1 | M2 | M3, M4 | M6 | M7 | M8 | M10 | M15 | M30, M34, M35, M36 |
| COMPOSITION, % | C 0.80, Cr 4.00, Mo 8.00, W 1.50, V 1.00 | C 0.80, Cr 4.00, Mo 5.00, W 6.00, V 2.00 | C 1.00–1.30, Cr 4.00, Mo 4.50–5.00, W 5.50–6.00, V 2.70–4.00 | C 0.80, Cr 4.00, Mo 5.00, W 4.00, V 1.50, Co 12.00 | C 1.00, Cr 4.00, Mo 8.75, W 1.75, V 2.00 | C 0.80, Cr 4.00, Mo 5.00, W 5.00, V 1.50, Cb 1.25 | C 0.85, Cr 4.00, Mo 8.00, V 2.00 | C 1.50, Cr 4.00, Mo 3.50, W 6.50, V 5.00, Co 5.00 | C 0.80–0.90, Cr 4.00, V 1.25–2.00, W 2.00–6.00, Mo 5.00–8.00, Co 5.00–8.00 |
| HEAT TREATMENTS | | | | | | | | | |
| Forging Temp, F | 1900–2100 | 1900–2100 | 1900–2100 | 1900–2100 | 1900–2100 | 1900–2100 | 1900–2100 | 1900–2100 | 1900–2100 |
| Anneal Temp, F | 1500–1600 | 1600–1650 | 1600–1650 | 1600 | 1500–1600 | 1550–1600 | 1500–1600 | 1600–1650 | 1600–1650 |
| Hard. Temp, F | 2150–2225 | 2175–2250 | 2200–2250 | 2150–2200 | 2150–2240 | 2200–2300 | 2150–2225 | 2175–2250 | 2200–2275 |
| Quench Medium[a] | O, A or S | O, A or S | O, A or S | O, A or S | O, A or S | O, A or S | O, A or S | O, A or S | O, A or S |
| Temper Temp, F | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1100 | 1000–1200 | 1000–1100 |
| Hardness, Rockwell | C65–60 | C65–60 | C66–61 | C66–61 | C66–61 | C65–60 | C65–60 | C68–63 | C65–60 |
| SERVICE PROPERTIES | | | | | | | | | |
| Depth of Hard | Deep | Deep | Deep | Deep | Deep | Deep | Deep | Deep | Deep |
| Nondeformability | Good | Good | Good | Good | Good | Good | Good | Good | Good |
| Safety in Hard | Fair | Fair | Fair | Fair | Fair | Fair | Fair | Fair | Fair |
| Toughness | Poor | Poor | Poor | Poor | Poor | Poor | Poor | Poor | Poor |
| Wear Res | Very good | Very good | Very good-best | Very good | Very good | Very good | Very good | Best | Very good |
| Machinability | Fair | Fair | Fair | Fair | Fair | Fair | Fair | Fair | Fair |
| Res to Decarb | Poor | Fair | Fair | Poor | Poor | Fair | Poor | Fair | Poor |
| REMARKS AND USES | Tend to decarburize more readily than tungsten-base tool steels; most common high speed cutting tool materials | | | | | | | | |

[a] O = oil; A = air; S = salt.

## Standard Tool Steels—Wrought

| AISI Type → | Special Purpose Tool Steels—Low Alloy (L) | | | | | Special Purpose—Carbon-Tungsten (F) | | |
|---|---|---|---|---|---|---|---|---|
| | L1, L2 | L3, L4 | L5 | L6 | L7 | F1 | F2 | F3 |
| COMPOSITION, % | C 0.50–1.10, Cr 1.00–1.25, V 0.20 (L2) | C 1.00, Mn 0.60 (L4), Cr 1.50, V 0.20–0.25 | C 1.00, Mn 1.00, Cr 1.00, Mo 0.25 | C 0.70, Cr 0.75, Ni 1.50, Mo 0.25 | C 1.00, Mn 0.35, Cr 1.40, Mo 0.40 | C 1.00, W 1.25 | C 1.25, W 3.50 | C 1.25, Cr 0.75, W 3.50 |
| HEAT TREATMENTS | | | | | | | | |
| Forging Temp, F | 1800–2000 | 1800–2000 | 1800–2000 | 1800–2000 | 1800–2000 | 1800–2000 | 1800–2000 | 1800–2000 |
| Anneal Temp, F | 1400–1475 | 1425–1500 | 1425–1475 | 1400–1450 | 1450–1500 | 1400–1475 | 1450–1500 | 1450–1500 |
| Hard. Temp, F | 1450–1700 | 1425–1600 | 1450–1600 | 1450–1550 | 1500–1600 | 1450–1600 | 1450–1600 | 1450–1600 |
| Quench Medium* | O or W | O or W | O | O | O | W or B | W or B | W, B or O |
| Temper Temp, F | 300–1000 | 300–600 | 300–600 | 300–1000 | 300–600 | 300–500 | 300–500 | 300–500 |
| Hardness, Rockwell | C64–45 | C64–56 | C64–56 | C62–45 | C64–56 | C64–60 | C66–62 | C66–62 |
| SERVICE PROPERTIES | | | | | | | | |
| Depth of Hard. | Medium | Medium | Medium | Medium | Medium | Shallow | Shallow | Shallow |
| Nondeformability | Fair-poor | Fair-poor | Good | Good | Good | Poor | Poor | Poor |
| Safety in Hard. | Fair-poor | Good-poor | Good | Good | Good | Poor | Poor | Poor |
| Toughness | Very good-fair | Fair | Fair | Very good | Fair | Poor | Poor | Poor |
| Wear Res | Good-fair | Fair | Good | Fair | Good | Good | Very good | Very good |
| Machinability | Good | Good | Good | Fair | Good | Good | Fair | Fair |
| Res to Decarb | Good | Good | Good | Good | Good | Good | Good | Good |
| REMARKS AND USES | Deeper hardening characteristics than W grades and about same properties as O1 and O2, but greater tendency to distort; all types of dies | | | | | Very good abrasion resistance with consequent difficulty in grinding; generally limited to wire, bar or tube cold-drawing die and finishing tools | | |

| AISI Type → | Special Purpose Tool Steels—Mold Steels (P) | | | | | | |
|---|---|---|---|---|---|---|---|
| | P1 | P2 | P3 | P4 | P5 | P6 | P20 |
| COMPOSITION, % | C 0.10 | C 0.07, Cr 2.00, Ni 0.50, Mo 0.20 | C 0.10, Cr 0.60, Ni 1.25 | C 0.07, Cr 5.00 | C 0.10, Cr 2.25 | C 0.10, Cr 1.50, Ni 3.50 | C 0.30, Cr 0.75, Mo 0.25 |
| HEAT TREATMENTS | | | | | | | |
| Forging Temp, F | 1450–1550 or 2200–2350 | 1850–2050 | 1850–2050 | 1850–2050 | 1850–2050 | 1950–2150 | 1850–2050 |
| Anneal Temp, F | 1350–1650 | 1350–1500 | 1350–1500 | 1600–1650 | 1550–1600 | 1550 | 1400–1450 |
| Hard. Temp, F | 1450–1475 | 1525–1550 | 1475–1525 | 1775–1825 | 1550–1600 | 1450–1500 | 1500–1600 |
| Quench Medium* | W or B | O | O | A | O or W | O | O |
| Temper Temp, F | 300–500 | 300–500 | 300–500 | 300–500 | 300–500 | 300–450 | 300–500 |
| Hardness, Rockwell | C64–58 | C64–58 | C64–58 | C64–58 | C64–50 | C58–61 | C64–58 |
| SERVICE PROPERTIES | | | | | | | |
| Depth of Hard. | Shallow | Shallow | Shallow | Shallow | Shallow | Deep | Medium |
| Nondeformability | Poor | Good | Good | — | Good | Good | Good |
| Safety in Hard. | Fair | Good | Good | — | Good | Good | Good |
| Toughness | Good | Good | Good | — | Good | Good | Good |
| Wear Res | Good | Good | Good | — | Good | Good | Fair-good |
| Machinability | Poor | Good | Fair | — | Fair | Fair | Good |
| Res to Decarb | Good | Good | Good | — | Good | Good | Good |
| REMARKS AND USES | P1 is easily hubbed, has low cure hardness, is subject to distortion; P4 and P5 more difficult to hub but relatively nondeforming; P2, P3 and P6 very difficult to hub; primarily as plastic mold steels | | | | | | |

* W = water; B = brine; O = oil; A = air.

# WRITE YOUR OWN RELIABILITY INSURANCE HERE...




Wherever metals are being cast, forged, or fabricated, the important factor of reliability can be assured by specifying $R_x$Met brand alloys. Whether we ship shot for making castings, billets for forging, or special welding rod, the $R_x$Met label on the alloy means more consistent performance in the finished product.

At WaiMet, metallurgical reliability and quality control are more than words—they are integral parts of a dedicated approach to making better alloys. We dig a little deeper than most to find out why an alloy behaves as it does, then define new limits of chemistry to guide the production of every heat. Result: alloys with reproducible, consistently better mechanical properties.

In almost every alloy we make there is some WaiMet improvement in processing or heat treatment technology that will mean better reliability insurance for the user.

## HERE ARE TYPICAL REASONS WHY ALLOY USERS SPECIFY $R_x$ MET®

| USER OF: | SPECIFIES IT FOR: | USES $R_x$MET BECAUSE: |
|---|---|---|
| 410 | Aircraft wing hinge | Cleaner melting and tailored chemical composition. |
| WI - 52 | Gas turbine blades and vanes | Greatly improved high temperature strength |
| 17-4PH | Gas turbine compressor blades | Uniformly high level mechanical properties |
| SUPER 3 | Agricultural equipment twine guide | Superior wear resistance at low metal cost. |

WAIMET ALLOYS CO.
5320 OAKMAN BLVD.
DEARBORN 2, MICH.
LUzon 1-7200
TOOL STEELS • STAINLESS STEELS
SUPERALLOYS • VACUUM-MELTED ALLOYS




Put WaiMet's technical team to work for you at the design stage. Specify $R_x$Met whenever reliability is important in stainless, heat resistant alloys, or superalloys. For information on the $R_x$Met alloy line, just drop us a line, or call.

For more information, turn to Reader Service card, circle No. 531

## Careful And Costly Control Grooms

# SANDVIK SPRING STEELS

## *FOR SPECIAL PERFORMANCE*



Smoothness of strip surface is checked with a "Talysurf" surface measuring instrument which registers the profile depth magnified up to 50,000 times.




Checking the flatness of hardened strip steel.





Sandvik laboratories carry out over 200,000 chemical analyses a year.



Strip thickness is checked during rolling and at final inspection with a "Deltameter"

Sandvik spends extra time, money and effort to produce spring steels with the quality to meet difficult performance demands.

From the ore in Sandvik's mines to the finished strip, Sandvik applies constant, rigid quality control to every steel-making step. Special analyses, careful, small-lot processing, modern laboratories equipped with special scientific instruments . . . these are behind Sandvik's record of success in tough spring steel applications.

For special physical properties plus accurate and uniform flatness, straightness, width, gauge and edge finish, specify Sandvik. Wide variety of qualities and sizes in stock plus local Sandvik facilities for custom-processing and finishing to your requirements. Send for free brochure.

## SANDVIK STEEL, INC.

**1702 Nevins Road, Fair Lawn, N. J.**
**Tel. SWarthmore 7-6200 • In N. Y. C. ALgonquin 5-2200**
***Branch Offices:* Cleveland • Detroit • Chicago • Los Angeles**
**SANDVIK CANADIAN LTD. P.O. Drawer 1335, Sta. O. Montreal 9, P. Q.**
***Works:* Sandviken, Sweden**




88-209



# problem-solving products and services

*from Republic Steel*

**ELECTRO PAINTLOK® STEEL SHEETS.** For production of their top line shower cabinets, Vogt Brothers Mfg. Company, Louisville, Ky, needed sheets that would take and hold paint exceptionally well, because the units are subjected to soap, hot and cold water, bumps and knocks. The solution: Republic Electro Paintlok Steel Sheets. Paintlok sheets are zinc coated electrolytically, then chemically treated to provide an inert phosphate surface film. Result: a firm mechanical bonding of paint, lacquer, or enamel to steel. In die forming, brake forming, and piercing operations, Vogt found that Paintlok is easy to fabricate, too.

If getting a good, tight painted finish is your problem, it will pay you to investigate Republic Electro Paintlok. Mail coupon for data.




**CENTURY SERIES COLD FINISHED STEEL BARS.** Having trouble finding cold finished bar stock with the right balance of machinability and toughness? Republic's CENTURY SERIES was made to solve this problem. CENTURY SERIES offers five different grades of high strength, stress-relieved, cold finished bars, each having a minimum yield strength of 100,000 psi. Selecting the grade with just the degree of machinability and toughness you need can mean reduced savings in material costs. For production of highly machined parts, C-1144 is the right choice. For moderately machined parts—C-1141 or C-1151. If machinability is a minor factor, C-1050 or C-1045 would be the best, most economical choice. Smooth, scale-free surfaces require no finishing operations for many applications. Send for free CENTURY SERIES booklet.



**STAINLESS STEEL.** When a difficult stainless forming problem confronted Applied Arts, Inc., Grand Rapids, Michigan, automotive trim manufacturer, fast action from Republic saved time and money. Problem occurred with a piece of window trim for a 1960 car, where a particularly severe draw was causing a bad roping surface. Applied Arts called on Republic Metallurgists, who studied the forming operations and recommended a specification change to vary the physicals of the stainless slightly. The result: roping was eliminated and the rejection rate dropped well below original estimate.

Republic Stainless Metallurgists are at your service, where and when you need them—to help you select, apply, and process the stainless steel best suited to your requirements. Send for complete information.

For more information, circle No. 549



**VACUUM-MELTED METALS**—carbon, alloy, stainless, and titanium—are available from Republic in plates, billets, bars, sheets, strip, and wire. With the most extensive vacuum-melting facilities ever assembled, Republic is producing ingots weighing from 4,000 to 20,000 pounds, in 18- to 32-inch diameters. Mail the coupon for complete information.

# REPUBLIC STEEL

*World's Widest Range of Standard Steels and Steel Products*

**REPUBLIC STEEL CORPORATION**
**DEPT. ME-9835A**
**1441 REPUBLIC BUILDING • CLEVELAND 1, OHIO**

☐ Please send free CENTURY SERIES Booklet
Send more information on:
☐ Electro Paintlok Steel Sheets
☐ Stainless Steel
☐ Vacuum-Melted Metals

Name_____ Title_____

Company_____

Address_____

City_____ Zone____ State_____




**Stainless steel reduces weight!** An exceptionally high strength-weight ratio makes stainless steel an ideal material for thousands of applications. Designers can count on this property with the assurance that there will be no loss of design properties — ever. For stainless resists corrosion, dents, scratches, and heat. Its beauty is *solid* and is as permanent as anything you can name. No wonder designers say "Yes" to stainless. And the best stainless steels of all are made with Vancoram Products! Vanadium Corporation of America, 420 Lexington Avenue, New York 17, N. Y. • Chicago • Cleveland • Detroit • Pittsburgh

VANADIUM
CORPORATION OF AMERICA
Producers of alloys, metals and chemicals

VANCORAM

For more information, turn to Reader Service card, circle No. 483




**Q.** Where are vacuum melted alloys best suited?

**A.** For exacting applications—including materials for rockets, missiles, and jet engines. And other places where expensive machined parts are involved. In highly stressed parts where failure is highly costly. Where increased reliability is vital.

**Q.** What are the advantages of A-L vacuum melted alloys?

**A.** You get parts with optimum quality for critical applications—higher mechanical properties, better fatigue strength, improved toughness, and better transverse ductility. You also get maximum insurance against internal defects through improved cleanliness and decreased gas content. And hot and cold workability are improved, the material is more homogeneous, and properties are better.

**Q.** How are these metals made?

**A.** A-L uses all three of the vacuum melting processes. Consumable electrode vacuum arc remelting is used to produce A-L Consutrode® steels and alloys in ingots up to 20,000 pounds in weight. Induction vacuum melting is used to produce 2,000 pound heats of Allegheny Ludlum Invac materials. And remelting Invac electrode stock by the consumable electrode process produces A-L Invacutrode steels and alloys that have the best possible combination of chemistry control, cleanliness, and homogeneity.

**Q.** Specifically, what metals are available in A-L's premium quality melting?

**A.** Most of the steels and special alloys—low alloy steels, bearing steels, stainless steels, tool and die steels, and high temperature steels and alloys.

**Q.** In what forms are these A-L special steels available?

**A.** In all commercial mill forms—plates, sheet, strip, billet, bar, wire, tubes, and even extrusions.

**Q.** How do these vacuum melted alloys compare in cost with ordinary alloys?

**A.** Naturally vacuum melting costs more. Consutrode alloys are the least expensive, followed by Invac alloys and Invacutrode alloys. Their use is economically justified by the improvement of quality in the finished part, the quality required by the severity of the manufacturing process involved, and the increase in the yield of sound parts.

**Q.** Where can I get more information?

**A.** Ask your A-L representative for your copy of "Modern Melting at Allegheny Ludlum." It gives technical data on the new melting techniques and quality improvements in materials. Or write: ***Allegheny Ludlum Steel Corporation, Oliver Bldg., Pittsburgh 22, Pennsylvania. Address Dept. MI-S.***

**ALLEGHENY LUDLUM**

PIONEERING on the Horizons of Steel

2256

For more information, turn to Reader Service card, circle No. 377


# NEW REINHOLD BOOKS FOR DESIGN ENGINEERS

*The* how *and* why *of developing equipment for specific operations . . .*

## 1 AUTOMATING THE MANUFACTURING PROCESS

by GEORGE F. HAWLEY, *Vice President of Development and Engineering, Automation Engineering Laboratories, Inc.*

1959, 176 pages, $4.95




THE EMINENTLY sound ideas which this book presents merit the attention of all concerned with the use and development of special automatic machinery. It presents in practical terms some of the mechanical problems involved in developing automatic equipment for specific operations, such as assembly of components, packaging of individual products, bottle capping, feeding, etc. Management and production personnel will gain a greater appreciation for the problems encountered in developing successful machines, while designers and development engineers will find a machine development procedure which, if followed, should minimize their failures.

*Orients processors in new methods . . .*

## 2 VACUUM PROCESSING IN METALWORKING

by J. WESLEY CABLE, *Consulting Engineer*

1960, 256 pages, $5.50


THE RELATIVELY new field of vacuum technology receives complete, practical treatment here. The book encompasses the complete range of operations in the metalworking field. The first few chapters cover the general phases of vacuum technology, such as the means of producing low pressures and their measurement. Following these, the author devotes each subsequent chapter to a particular phase of vacuum processing. He also includes the latest developments, among them electron beam heating. In general, the aim of the book is to present vacuum technology in a descriptive manner, rather than in a highly technical form.

*Includes design, materials and fabrication . . .*

## 3 NUCLEAR FUEL ELEMENTS

edited by HENRY H. HAUSNER, *Adjunct Professor, Brooklyn Polytechnic Institute and* JAMES F. SCHUMAR, *Associate Director, Metallurgy Division, Argonne National Laboratory*

1959, 432 pages, $12.50




CONTAINS the papers presented at the First International Symposium on Nuclear Fuel Elements held at Columbia University in January 1959. This book is the first to deal exclusively with the nuclear fuel elements. The twenty chapters include first-hand information from scientists in the U.S. and European countries who have worked on the development, design and fabrication of fuel elements. These scientists describe their own experiences. Among the individual topics presented by each chapter are discussions of the use of the fuel elements for reactors of the future, the standardization of certain types of elements, cost analysis for low-cost fabrication and reprocessing, metallic fuel elements made from uranium, thorium and plutonium, dispersion-type fuel elements, high-temperature fuel elements, and the behavior of fuel elements under reactor operating conditions.

*Complete revision of a standard work . . .*

## 4 MATERIALS AND TECHNIQUES FOR ELECTRON TUBES

by WALTER H. KOHL, *Senior Engineering Staff, Sylvania Electric Products, Inc., a Division of General Telephone & Electronics Corporation, General Telephone & Electronics Corporation Technical Series*

1960, 640 pages, $16.50




HERE IS the completely revised edition of the previous "Materials Technology for Electron Tubes," long known as the standard work on the subject in English. The text has been rewritten and reorganized on the basis of replies to a questionnaire submitted to a large number of competent users of the first edition. As a result, the text has been brought thoroughly up-to-date. The book covers all the material components of electron tubes and the methods of uniting them, such as joining of metals by brazing, glass-to-metal sealing, and ceramic-to-metal sealing. Chapters dealing with specific materials contain extensive tabulations of physical characteristics, chemical reactions with various reagents, and processes used in application.

*Two new additions to the Reinhold Plastics Applications Series . . .*

## 5 ACRYLIC RESINS

by MILTON B. HORN, *Group Leader, Acrylic R & D, Catalin Corp. of America*

1960, 192 pages, $4.50

DESCRIBES the four types of acrylics in respect to their manufacture, fabrication and applications. These types include cast products, molding compounds, emulsion and solution compounds, and this is the first coverage of all types in one book. The author explains raw materials and manufacture of these polymers sufficient to an understanding of the problems involved in fabrication and application. Then he covers the current and future developments in terms of potential use in a great variety of products. All material presented in the book is available in the literature.

## 6 POLYESTER RESINS

by JOHN R. LAWRENCE, *Project Coordinator—Glidpol Resin, The Glidden Company*

1960, 256 pages, $5.75

HERE IS a comprehensive presentation of the unsaturated polyester resin industry. It covers all aspects from historic background, chemistry, curing mechanisms and manufacturing to techniques used in processing the resins for use in reinforced plastics, casting and coating applications. Particular emphasis is given to formulating resins for special properties such as weathering and flame resistance. The chapter on coating applications is the most complete coverage ever published on this relatively new use for polyester resins.

**Free Examination Order Coupon**

**REINHOLD PUBLISHING CORP.**
**Dept. M-680, 430 Park Avenue**
**New York 22, N. Y.**

Send me the book (s) I have encircled below for 10 days' FREE EXAMINATION:

☐ Purchase price enclosed (Reinhold pays shipping costs)
☐ Bill me ☐ Bill company


**1 2 3 4 5 6**

Name _____

Address _____

City & Zone _____ State _____

SAVE MONEY! You save shipping charges by enclosing payment with order. Same return privilege. Please include 3% sales tax on N.Y.C. orders. DO NOT ENCLOSE CASH!



# WHAT'S DIFFERENT ABOUT J&L PRECISION STRIP STEEL?

The big difference in J&L strip steel is controlled uniformity.

When J&L Precision strip is ordered to exacting specifications, you can be sure that your specifications will be met . . . inch after inch, coil after coil, time after time.

The dimensional accuracy of J&L strip steel, consistently maintained, offers many cost-saving advantages. This means fewer rejects; fewer production problems; less down-time for tool adjustment. This means that you are getting the steel you pay for . . . in terms of maximum product yield per ton.

How?

By delivering the steel you order . . . to your specifications . . . J&L helps you to achieve optimum production with control of in-plant fabricating costs.

The experience, facilities, and accumulated know-how of a specialized organization . . . directed exclusively to the processing of low carbon, high carbon, alloy, tempered and stainless strip steels . . . are available to work for you. For assistance in solving your problems, call your J&L Stainless and Strip Division representative; or write to Dept. 233-Y—1114.

**STRIP**

LOW CARBON • HIGH CARBON • ALLOY • STAINLESS
TEMPERED SPRING STEEL • ZINC AND COPPER COATED

**Jones & Laughlin Steel Corporation • STAINLESS and STRIP DIVISION • Youngstown 1, Ohio**

For more information, turn to Reader Service card, circle No. 507


USS Amerstrip—everything about its method of manufacture has the stamp of precision. Just specify what you need in a cold rolled strip, whether it's a precise gauge, finish, edge, tolerance or temper and you get exactly what you specify. USS Amerstrip will keep your product quality high and consistent because of these six distinct advantages:

# USS AMERSTRIP GIVES YOU PRECISELY



**PRECISION FINISH**

With USS Amerstrip we take special pains to give you a finish that is just right for the specific results you require in a finished product. We believe the Amerstrip finish is the finest you can get in the industry.



**PRECISELY PREPARED EDGES**

Because USS Amerstrip is produced in order-sized quantities engineered to your own specifications, we can give you precisely the edge finish you need. Choose your edge—square, standard, round, full round or bevel.



**PRECISE TEMPERS**

Whether your product must go through a deep draw or undergo other stringent forming operations, or if it requires a special temper for rigidity, you'll always get the correct temper for the job when you order USS Amerstrip.

# WHAT YOU NEED IN A COLD ROLLED STRIP



### PRECISE WIDTH TOLERANCES

When your fabricating machines require a special width strip, you can be sure that's the width you'll get with Amerstrip. We can produce USS Amerstrip within required tolerance limits to fit your special requirements.



### PRECISE THICKNESS TOLERANCES

Whatever thickness tolerance your machines demand, you'll get it in Amerstrip. And it'll be precisely the same in every inch of Amerstrip ordered. Amerstrip can be rolled in thickness tolerances of plus or minus .0005 inches.



### PRECISE UNIFORMITY

Regardless of the size of your order, every coil of USS Amerstrip comes off the line uniform in finish, temper, width and thickness. In short, USS Amerstrip's precision production assures a continuous run and high yield.

**American Steel & Wire Representatives** have the training and experience to give you expert guidance in fabrication and application of USS Amerstrip. They can show you how it contributes to a better finished product. To avail yourself of their services, call your nearest AS&W District Office. American Steel & Wire, 614 Superior Ave., N.W., Cleveland 13, Ohio.

USS and Amerstrip are registered trademarks

**American Steel & Wire**
**Division of**
**United States Steel**


Columbia-Geneva Steel Division, San Francisco, Pacific Coast Distributors
Tennessee Coal & Iron Division, Fairfield, Ala., Southern Distributors
United States Steel Export Company, New York

**For more information, turn to Reader Service card, circle No. 386**

*A treasury of valuable information for the plastics industry . . .*

# POLYESTERS

## and their Applications




**1956, 626 pages, $10.00**

**by JOHAN BJORKSTEN**
*President*

**HENRY TOVEY**
*Chief, Literature Division*

**BETTY HARKER**
*Administrative Assistant*

**and JAMES HENNING**
*Administrative Assistant*

**all of Bjorksten Research Laboratories, Inc.**
**Madison, Wisconsin**

This book is the first comprehensive survey of the entire polyester field from raw materials to fabricated product. The text and annotated bibliography of over 3300 references cover most phases of the production and use of polyesters. You will find here a storehouse of valuable information and a tremendous time-saver in seeking background information. Now you can quickly locate any patents or literature bearing on some particular phase of the polyester field. Included are not only the unsaturated polyesters used in molding, casting, coating, impregnating, and laminating, but also the saturated polyesters used in production of fibers, films, elastomers, and foamed plastics.

This fund of information has been painstakingly assembled for many years by the Bjorksten Research Laboratories. Periodic volumes will be published when merited, to make them a basic reference work covering the current status of the field and indicating the problems which must be overcome for further advancement and the directions of future trends.

The remarkable value of this book will be quickly apparent when you glance through it and realize the cost involved in the endless task of amassing the data and keeping it up to date.

***Notice the wide range of information in these 5 big chapters . . .***

1 THEORETICAL CONSIDERATIONS
Introduction; General Concepts; Polyesters

2 UNSATURATED POLYESTERS
Raw Materials; Resin Manufacture; Catalysis and Inhibition; Fillers and Reinforcements; Shaping; Finishing; Commercial Resins; Tailor-Making Polyesters; Final Products

3 SATURATED POLYESTERS
Linear Fiber-Forming Polyesters; Di-Isocyanate-Modified Polyesters

4 TESTING
Introduction; Raw Materials; Resins and Plastics; Equipment for Testing Plastics; Catalysts; Glass Fillers; Design Data and Nondestructive Tests

5 HEALTH HAZARDS
Introduction; Hazards in Manufacture; Hazards in Fabrication; Standards for Control Health Hazards

**Mail this coupon for FREE EXAMINATION**

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-702, 430 Park Avenue, New York 22, N. Y.**
Please rush me a copy of POLYESTERS AND THEIR APPLICATIONS for Free Examination. After 10 days, I will send you $10.00 plus shipping charge, or I will return the book and owe nothing.

NAME .....

ADDRESS .....

.....

CITY & ZONE .....STATE.....

**SAVE MONEY:** Enclose $10.00 with order and Reinhold pays shipping charge. Same return privilege; refund guaranteed. Please add 3% sales tax on N.Y.C. orders.


# SEND FOR THE LATEST DATA ON CRUCIBLE SPECIALTY STEELS AND TITANIUM

Quality specialty steels, (Stainless, tool and high speed, high alloy, permanent magnets and vacuum melted metals, as well as titanium), have been produced by Crucible Steel Company of America for over sixty years. Quality production is based on research, technical know-how, experience and improved production methods.

These references have been prepared by the world's largest producer of specialty steels and metals: Crucible Steel Company of America. Illustrated below are a few of the many publications Crucible has available for distribution to assist the design engineer, metallurgist and production specialist, to get the most from Crucible's quality specialty steel and titanium products.

So why not send for the references you need (or may need) and have them handy? Just check the coupon and mail it today.


**1**




**THE FABRICATOR'S HANDBOOK — *how to fabricate stainless steels* (162 pages)**

This comprehensive manual covers various methods of fabricating stainless steels: forming, machining, cutting, joining, heat treating — pickling, finishing. It also contains details on compositions and properties; data for estimating weights; and conversion, tolerance and temperature tables.


**2**




**PRODUCT AND WAREHOUSE CATALOG (232 pages)**

Crucible's catalog lists the different types and the thousands of items of specialty steels available from Crucible warehouses and mills. Here, you'll find data on tool and high speed steels; plastic mold and die casting die steels; oil-, water-, and air-hardening tool steels, shock resisting steels, hot work steels; hollow tool steels; drill steels; drill rods; stainless; alloy steels; welded tubing; Permanent Magnets and hard facing electrodes.


**3**




**PERMANENT MAGNET HANDBOOK (380 pages) Edited by Earl M. Underhill. Price: $10.00***

This handbook, in loose leaf form, was written for the practicing engineer as a guide to his use of Permanent Magnets for all types of applications. It is the only technical reference of this type available in the U. S. A. Consisting of 12 sections, it covers in detail the theories of Magnet Design and Measurement, Magnetization, Demagnetization, and Ferromagnetism, and serves as a reference work for the important equations of classical electromagnetism.


**4**




**MAKING THE MOST OF TITANIUM IN THE CHEMICAL PROCESS INDUSTRIES**

A 56 page booklet on how to specify titanium for corrosion applications —where and when not to use titanium. Contains extensive tabulated corrosion data and bibliography.


**5**




**ALLOY AND FREE MACHINING STEELS KIT**

Within this kit there is valuable data for the materials selector concerning alloy and free machining steels. Subjects covered are: the typical applications and properties of steels for use in mining, construction, railroad, automotive and maritime equipment, machine tools, and even jails, vaults and safes.

**6**




**TOOL STEEL LITERATURE FILE**

You will find these brochures helpful in choosing tool steels for forging and hot extrusion processes. Included is valuable background information on specific processes, plus extensive technical data on Crucible's Tool and Die steels.

CIRCLE YOUR CHOICE. **NOTE:* For item No. 3, *Permanent Magnet Handbook*, please send coupon and check or money order for $10.00. (If you are located in Pennsylvania, add 40¢ for state sales tax.) This sum also covers the cost of additions to the handbook which are mailed to you as new data become available.

**PLEASE PRINT OR TYPE**

**CRUCIBLE STEEL COMPANY OF AMERICA**
**P.O. Box 2518, Dept. MS, Pittsburgh 30, Pa.**

1 2 3 4 5 6

NAME _____ TITLE _____

COMPANY _____

STREET _____

CITY _____ ZONE _____ STATE _____


**CRUCIBLE STEEL COMPANY OF AMERICA**

**For more information, turn to Reader Service card, circle No. 403**

*Just Published* **The definitive work on a great originator . . .**

by **ROBERT MARKS**

# THE DYMAXION WORLD OF BUCKMINSTER FULLER



The bridge to this world of patterned abundance is what Fuller calls "Comprehensive Design." The book reviews this kind of design and what it means in terms of human advantage.



The book interprets the man responsible for the dymaxion world: his philosophy, background, and significance.




Thoroughly depicts the most famous of Fuller's creations, the dome. Includes those used by concert halls, sports palaces, industry, agriculture, banks, societies, to name just a few.



Includes all building types—their uses, design, materials, methods of construction, etc.



Presents Fuller's prophecies—transparent domes that cover entire cities for climate control; submarine islands; temporary, disposable dwellings.



Provides an incomparable visual record from earliest designs to current projects under construction.



Explains the Fuller vocabulary with pictorial examples: energetic-synergetic, tensegrity, geodesic, dymaxion, dwelling machine, octet truss, and 4D.



Covers the entire gamut of Fuller achievements—buildings, transports, geometry, cartography, deployment units, and many others.

**Provides a complete, visual record of Fuller's work . . .**
**Over 350 photographs and drawings, fully annotated —**
**Here are just a few reduced samples of the exciting illustrations with which the book abounds. Each one is numbered and explained in corresponding paragraphs. These illustrations alone provide an important historical record of Fuller's work.**

HERE IS A FASCINATING study of the life and work of R. Buckminster Fuller—one of the most original and controversial men of our time. Since their first meeting some 18 years ago, Robert Marks has been an enthusiastic advocate and interpreter of Fuller's structural concepts. In this book he explains even the most complex of Fuller's ideas in a way that makes them accessible to all readers.

Way back in 1938 another originator, Frank Lloyd Wright, addressed Fuller as "the most sensible man in New York." In the delineation of his subject's life and philosophy, Mr. Marks reveals a man whose foresight and energy would naturally gain the attention and respect of other great innovators.

When the book's narrative moves from the man to his work, it takes the reader on the most complete tour of the Dymaxion world ever devised. Included are all the provocative Dymaxion projects that were 25 years ahead of their time—4D house, deployment units and transports, as well as Fuller's more recent work on Geodesic domes and space frames. The book also reveals the "total design" principles behind all these highly original concepts.

In addition, the pattern of thinking which evolved a system of geometry—Energetic and Synergetic—and a new system of map-making, is brilliantly analyzed.

The book is splendidly illustrated with over 350 fully captioned photographs and drawings that graphically depict the plans and structures, the today and tomorrow in Mr. Fuller's Dymaxion world.

**A major portion of the illustrations appear in their own sections. Here are the topics of these sections, many of which are several pages each.**

**ILLUSTRATION SECTIONS:** Astor Plane; Stockade System; Multiple-Deck 4D House: Air Ocean World; Dymaxion House; Dymaxion Bathroom; Dymaxion Transport; Mechanical Wing; Dymaxion Deployment Unit; Dymaxion Dwelling Machine; Synergetic-Energetic Geometry; Maps and Charts; Tensegrity; Octet Truss; Minor Inventions; Autonomous Package; Geodesic Invention and Development; Skybreak Dwellings; Ford Dome; Seedpod Foldable Geodesics; U. S. Marine Corps Geodesics; Radomes; Paperboard Domes.




**1960**
**232 pages**
**Over 350 photographs and drawings**
**8¼ x 10¼**
**$12.00**

*Examine It Free for 10 Days*

**MAIL THIS COUPON TODAY**

**REINHOLD PUBLISHING CORPORATION**
**DEPT. M-697, 430 Park Avenue, New York 22, N. Y.**

Send me a copy of THE DYMAXION WORLD OF BUCKMINSTER FULLER for 10 days' Free Examination.


☐ Purchase price enclosed (Reinhold pays postage)
☐ Bill me (plus postage) ☐ Bill company

NAME_____

ADDRESS_____

CITY & ZONE_____ STATE_____

**SAVE MONEY:** Enclose $12.00 with order and Reinhold pays all shipping costs. Same return privilege. Please add 3% sales tax on N.Y.C. orders. DO NOT ENCLOSE CASH!



# DEPENDABLE VAC-ARC® Steels

## . . . for applications requiring high ductility and tensile strength up to 285,000 psi.

*Compare these data . . .*

| TRANSVERSE TENSILE PROPERTIES<br>8" square billet of VAC-ARC DYNAFLEX | | |
|---|---|---|
| *Property* | *Mid-Radius* | *Center Area* |
| Tensile Strength (psi) | 287,000 | 285,000 |
| Yield Strength .2% (psi) | 252,500 | 250,000 |
| Elongation % | 8 | 8 |
| Reduction of Area % | 25 | 24 |

*Literature available on all Vac-Arc grades upon request . . . Send today!*

Where design demands uniform high strength, toughness and ductility at both low and elevated temperatures, Vac-Arc Steels more than meet the requirements. These steels—produced by Latrobe's consumable electrode vacuum melting process—possess superior cleanliness, lower gas content, improved ingot structure and desirable longitudinal and transverse mechanical properties.

The following grades of Latrobe's Vac-Arc steels are available in a range of sizes and shapes: Pandex (Type A-286) for high temperature applications; MV-1 (Type M-50) and Regent (Type 52100) for critical bearing design; Dynaflex (Type H-11) for aircraft and missile components; AGT (SAE 9310) for carburized aircraft gears.

Many grades of Vac-Arc steels are being produced to meet particular application requirements. Send us your specifications or call your nearest Latrobe representative for *experienced* technical assistance.

*Skillfully made in U.S.A. by*

LATROBE
Metalmasters

**LATROBE STEEL COMPANY**

LATROBE, PENNSYLVANIA

**Branch Offices and Steel Service Centers:**

BOSTON • BUFFALO • CHICAGO • CLEVELAND • DAYTON • DETROIT
HARTFORD • LOS ANGELES • MIAMI • MILWAUKEE • NEW YORK
PHILADELPHIA • PITTSBURGH • SAN LEANDRO • TOLEDO

**For more information, turn to Reader Service card, circle No. 534**

## Sources of Data

Many of the compilations in this issue are entirely new. Collecting new data and up-dating old compilations required the aid of many organizations. Although it would be impractical to list all who contributed in one way or another, we acknowledge particularly the assistance of the following:

Al-Fin Div., Fairchild Engine & Airplane Corp.
Allegheny Ludlum Steel Corp.
Allied Chemical Corp.
Alloy Casting Institute
Aluminum Co. of America
American Brass Co.
American Felt Co.
American Foundrymen's Society
American Hard Rubber Co.
American Iron & Steel Institute
Armco Steel Corp.
Battelle Memorial Institute
J. Bishop & Co.
Bridgeport Brass Co.
A. M. Byers Co.
Carborundum Co.
Celanese Plastics Co.
Chase Brass & Copper Co., Inc.
Cobalt Information Center
Continental Diamond Fibre Corp.
Copper & Brass Research Assn.
Corning Glass Works
Crucible Steel Co. of America
Dow Chemical Co.
Dow Corning Corp.
E. I. du Pont de Nemours & Co., Inc.
Eastman Chemical Products, Inc.
Felt Assn.
Fiberfil, Inc.
Frontier Bronze Corp.
General Electric Co.
Gray Iron Founders' Society, Inc.
Haynes Stellite Co., Union Carbide Corp.
Hexcel Products, Inc.
Hooker Chemical Corp.
International Nickel Co.
Kaiser Aluminum & Chemical Corp.
Kelsey-Hayes Co., Metals Div.
Kennametal, Inc.
Ladish Co.
Lead Industries Assn.
Magnesium Assn.
Malayan Tin Bureau
Malleable Founders Society
Manufacturing Chemists Assn., Inc.
Metals & Controls Corp., General Plate Div.
Met-L-Wood Corp.
Minnesota Mining & Mfg. Co.
Monarch Machine Tool Co.
Mycalex Corp. of America
National Carbon Co.
National Vulcanized Fibre Co.
New Jersey Zinc Co.
Nitralloy Corp.
Norton Co.
Polymer Corp.
Porcelain Enamel Institute, Inc.
Pure Carbon Co., Inc.
Raytheon Mfg. Co.
Rubber Manufacturers Assn., Inc.
St. Regis Paper Co., Panelyte Div.
Steel Founders' Society of America
Stone Woodward, Inc.
Taylor Fibre Co.
Arthur Tickle Engineering Works, Inc.
Timken Roller Bearing Co.
Tin Research Institute, Inc.
Titanium Metals Corp. of America
Union Carbide Metals Co.
U. S. Dept. of Agriculture
U. S. Atomic Energy Commission
United States Steel Corp.
Universal Cyclops Steel Corp.
Vanadium Alloys Steel Co.
R. T. Vanderbilt Co.
Westinghouse Electric Corp.
Zirconium Metals Corp. of America

*Corrections and additions: We welcome your corrections and suggested additions for future editions. Please address Selector Editor,* MATERIALS IN DESIGN ENGINEERING, *430 Park Ave., New York 22, N. Y.*


## INFORMATION PLEASE!

Want more data on products advertised in this section?

Each advertisement has a circle number, and all you have to do is circle the same number on one of the Reader Service cards (beginning page 585) to get literature detailing engineering data, properties, applications and other useful information from the manufacturer of the product(s) you are interested in. The card is postpaid.

This useful materials information service can also bring you any of the literature listed on page 36. Review the advertisements and the literature listings, then make use of this free service. A moment of your time is all it takes. The literature you will receive has been prepared especially to help you solve materials application problems.

Reminder: For Reader Service Cards, please see page 585.

**consistency...**

Consistent, *predictable*, results throughout production processes must begin with the consistent quality of materials. J & L consistent quality stainless steel will give predictable results time after time...order after order.

The service offered by your J & L stainless steel distributor is consistent... and predictable, too. He's as near as your telephone. You'll find that he can further reduce the cost of using stainless steel by providing a complete selection of materials. He can save you the capital investment required to maintain long term inventories. He can provide a wide variety of preproduction services, and reduce your overhead for stocking, handling, accounting and obsolescence.

Your J & L distributor can provide you with the consistent quality stainless steel you need, *as you need it, when you need it.* He can serve you better because *J & L serves him better.* J & L's own staff of technical specialists and metallurgists are at the call of your J & L distributor to give you the technical assistance, even advanced research, you may need.

For better production and better service, call your J & L distributor—call Western Union Operator 25, today.

*J&L—a leading producer of stainless steel and precision cold rolled strip steels*

**STAINLESS**
**SHEET • STRIP • BAR • WIRE**

For more information, circle No. 502


consistent quality production depends on consistent quality stainless steel
Jones & Laughlin Steel Corporation · STAINLESS and STRIP DIVISION · DETROIT 34

# SUPPLIERS' LITERATURE

## Nonferrous Metals

**Specifications for Copper.** American Brass Co., 28 pp, No. B-34. Military, ASTM, SAE, AMS, ASME and AWS specifications for copper, brass, phosphor bronze, cupronickels, nickel silvers and leaded brasses. **32**

**Molybdenum Metal.** Climax Molybdenum Co., Div. of American Metal Climax, Inc., 110 pp, illus. Applications, physical and mechanical properties, corrosion resistance, oxidation resistance and protection, fabrication of parts, methods of production, laboratory techniques, weight tables, references, and other data on molybdenum metal. **33**

**High Strength Aluminum Casting Alloy.** Federated Metals Div., American Smelting & Refining Co., 6 pp, illus. Physical and mechanical properties, specifications, composition and foundry characteristics of a high strength aluminum casting alloy that requires no heat treatment. **34**

**Beryllium Copper.** Beryllium Corp., 48 pp, illus. Advantages, properties, composition, typical applications, available forms, and information on how to select various beryllium copper alloys. Included is information on fabricating, heat treating, joining and corrosion resistance. **35**

**Tellurium Copper.** Bridgeport Brass Co. Physical, mechanical and fabrication properties, and applications of tellurium copper. **36**

**Beryllium Heat-Sink.** Brush Beryllium Co., 20 pp, illus. Design and fabrication data on the beryllium heat-sink used in NASA's Project Mercury. **37**

**Low Melting Alloys.** Cerro de Pasco Sales Corp., 8 pp, illus., No. J4. Sixty-three applications of low melting Cerro Alloys in the metalworking field. **39**

**Bronze.** Chase Brass & Copper Co., 8 pp, No. D-1. Corrosion resistance, properties, forms, tempers, electrical and thermal conductivity, and uses of a high copper alloy called Phosnic bronze. **40**

**Electrical Resistance Alloys.** Driver-Harris Co., 4 pp, illus., Vol. 18, No. 4. Use of electrical resistance alloys in appliances, radiant heaters, welding machines and heat treating furnaces. **41**

**Alloys for Electronics.** Wilbur B. Driver Co., 8 pp, illus., No. E102. Compositions, properties, resistance vs temperature curves, and other engineering data on alloys used for electron tubes, indirectly heated cathodes, plate materials, grid wire, and glass sealings alloys. **42**

**Aluminum Sheet, Coils.** Fairmont Aluminum Co., 4 pp. Physical properties, weights, dimensional data and uses of aluminum sheet, coils and circles. **44**

**Refractory Metals.** Fansteel Metallurgical Corp., 2 pp, illus., No. F-1152-1. Chart gives complete properties of tungsten, tantalum, molybdenum and columbium. Included is a temperature conversion chart which covers the range from absolute zero to 6512 F. **45**

**Specifications for Aluminum.** Peter A. Frasse & Co., Inc., 2 pp. Federal and military specifications for aluminum. Information on the bending and forming of aluminum sheet and plate. **46**

**High Strength Aluminum Alloy.** Frontier Bronze Corp., 24 pp, illus. Engineering data and technical information on a high strength aluminum alloy called 40-E that requires no heat treatment. **47**

**Silver and Its Alloys.** Handy & Harman. Characteristics, advantages and availability of silver and its alloys used in printed circuits, wiring, resistors, condensers, contacts, ceramics, plastics laminates, etc. **48**

**Nickel-Chromium Resistance Alloy.** Hoskins Mfg. Co., 8 pp, illus., No. 110. Composition; physical, mechanical, and electrical properties; temperature-resistance curves; and other technical data on a new modified 80-20 nickel-chromium resistance alloy developed for use as heating elements in controlled atmosphere furnaces. **49**

**Copper and Brass Products.** C. G. Hussey & Co. Div., Copper Range Co., 30 pp, illus. Sizes, specifications, weights, and other information on copper, brass, and bronze sheet, roll, strip, rod, wire, shapes, tubing, pipe, and roofing. **50**

**Indium Alloys.** Indium Corp. of America, 93 pp, graphs. Constitution of indium alloy systems. **51**

**Platinum, Platinum Group Alloys.** Platinum Metals Div., International Nickel Co., Inc. Advantages, characteristics, engineering data, and typical applications of platinum and platinum group metals. **52**

**Cobalt-Chromium Superalloy.** Kelsey-Hayes Co., Metals Div., 8 pp, illus. Chemical composition, physical constants, mechanical properties, isostress curves, heat treatment, finishing and available forms of a cobalt-chromium superalloy used in jet engines, missiles and electronic tubes. **53**

**Uses of Tin.** Malayan Tin Bureau, 20 pp, illus. Detailed descriptions of several uses of tin including tinplate, solder, bronze, babbitt, white metals, tinning, tubes, chemicals, etc. **54**

**Copper and Copper Alloys.** Olin Mathieson Chemical Corp., Western Brass Div., 14 pp, illus. Compositions; available forms; and physical, mechanical, and corrosion properties of wrought copper and copper-base alloys. Included is an extensive list of fabricating properties and joining processes. **55**

**Electronic Alloys.** Riverside-Alloy Metal Div., H. K. Porter Co., Inc., 8 pp, illus. Advantages, characteristics, compositions, and typical uses of phosphor bronze, nickel and nickel alloys, nickel silver, stainless steels, nickel-clad copper wire, and other alloys used for electrical and electronic applications. **56**

**Magnesium Wrought Products.** A. R. Purdy Co., Inc., 4 pp. Dimensions for such magnesium wrought products as sheet, plate, rod, bar, round and square tubing, structural shapes and welding rod. **57**

**Zinc Casting Alloys.** St. Joseph Lead Co., 22 pp, illus. Discusses zinc die casting alloys and commercial finishes for zinc die castings. **58**

**Brass, Aluminum Products.** Scovill Mfg. Co., 12 pp, illus. Information on such products as brass sheet, strip and rod; aluminum sheet and rod; metal stampings; and aircraft fasteners. **59**

**Copper Alloy Strip, Wire, Rod.** Seymour Mfg. Co., 2 pp. Composition, available forms and weights of copper alloy strip, wire and rod. **60**

**Thin Strip.** Somers Brass Co., 4 pp, illus., No. R-1-758. Specifications, available ferrous and nonferrous alloys, and other data on precision rolled thin strip. **61**

**Tantalum-Tungsten Alloy.** Stauffer-Temescal Co. Information on an electron-beam melted tantalum alloy containing 10% tungsten. Properties, fabrication data and typical applications. **62**

**Germanium Ingots, Crystals.** Sylvania Electric Products Inc., Chemical & Metallurgical Div., 4 pp, illus. Discusses purity, forms, types, uses and physical characteristics of germanium ingots and crystals. **63**

**Corrosion Resistant Alloy.** Haynes Stellite Co., Div. of Union Carbide Corp., 16 pp, illus. Corrosion resistance, chemical composition, physical properties, hardness, formability, impact strength and short-time tensile strength for a nickel-base alloy called Hastelloy alloy C. **64**

**Columbium-Base Alloys.** Union Carbide Metals Co., Div. of Union Carbide Corp., 6 pp, illus. Chemical compositions, and comparative data on strength and oxidation resistance of columbium-base alloys. **65**

**Tantalum.** Wah Chang Corp., 2 pp. Fabrication data, uses, and physical, mechanical and chemical properties of tantalum. **66**

*To get literature, use free post cards on pp 585-592*

# Nonferrous Metals


| PAGE | |
|---|---|
| 100 | Aluminum and Its Alloys—Wrought |
| 105 | Aluminum and Its Alloys—Cast |
| 110 | Cobalt and Cobalt-Base Superalloys—Cast, Wrought |
| 112 | Coppers—Wrought |
| 113 | Coppers, Plain Brasses—Wrought |
| 114 | Plain Brasses—Wrought |
| 115 | Tin and Aluminum Brasses—Wrought |
| 116 | Leaded Brasses—Wrought |
| 118 | Phosphor Bronzes—Wrought |
| 119 | Silicon Bronzes—Wrought |
| 120 | Nickel Silvers—Wrought |
| 121 | Cupro-Nickels—Wrought |
| 122 | Leaded Brasses and Bronzes—Cast |
| 124 | Yellow Brasses—Cast |
| 125 | Aluminum Bronzes—Cast |
| 126 | Lead and Its Alloys—Cast, Wrought |
| 128 | Magnesium Alloys—Wrought |
| 130 | Magnesium, Alloys—Cast |
| 133 | Columbium, Tantalum, Tungsten, Molybdenum—Wrought |
| 134 | Nickel and Its Alloys—Wrought |
| 135 | Nickel and Its Alloys—Cast |
| 136 | Low-Expansion Nickel Alloys—Wrought |
| 137 | Nickel-Base Superalloys |
| 140 | Precious Metals—Cast, Wrought |
| 142 | Tin and Its Alloys—Cast, Wrought |
| 143 | Tin-Lead-Antimony Alloys—Cast |
| 146 | Titanium and Its Alloys—Wrought |
| 148 | Zinc Alloys—Cast, Wrought |
| 150 | Hafnium, Thorium, Uranium, Vanadium, Beryllium |
| 151 | Zirconium and Its Alloys—Wrought |
| 152 | Advertisements |
| 98 | Suppliers' Literature |

## Aluminum and Its Alloys—Wrought

| Type → | EC | 1100 | 3003 | 3004 |
|---|---|---|---|---|
| COMPOSITION, % | Al 99.45 min | Al 99.0 min | Mn 1.0–1.5 | Mn 1.0–1.5, Mg 0.8–1.3 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.098 | 0.098 | 0.099 | 0.098 |
| Melting Temp Range, F | 1195–1215 | 1190–1215 | 1190–1210 | 1165–1205 |
| Ther Cond (77 F, ann.), Btu/hr/sq ft/°F/ft | 135 | 128 | 111 | 93.8 |
| Coef of Ther Exp (68 to 212 F), per °F | $13.2 \times 10^{-6}$ | $13.1 \times 10^{-6}$ | $12.9 \times 10^{-6}$ | $12.9 \times 10^{-6}$ |
| Spec Heat (212 F), Btu/lb/°F | — | 0.22 | 0.22 | 0.22 |
| Elec Res (68 F), microhm-cm | | | | |
| Annealed | 2.8 | 2.92 | 3.45 | 4.10 |
| Hard (H18 or H38) | — | 3.02 | 4.31 | 4.10 |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | $10 \times 10^6$ | $10 \times 10^6$ | $10 \times 10^6$ | $10 \times 10^6$ |
| Ten Str (75 F), 1000 psi | | | | |
| Annealed (O) | 12 | 13 | 16 | 26 |
| Half Hard | 16 (H14) | 18 (H14) | 22 (H14) | 35 (H34) |
| Hard | 27 (H19) | 24 (H18) | 29 (H18) | 41 (H38) |
| Yld Str (75 F), 1000 psi | | | | |
| Annealed (O) | 4 | 5 | 6 | 10 |
| Half Hard | 14 (H14) | 17 (H14) | 21 (H14) | 29 (H34) |
| Hard | 24 (H19) | 22 (H18) | 27 (H18) | 36 (H38) |
| Elong (in 2 in., 75 F), %[a] | | | | |
| Annealed (O) | 23[d] | 35, 45 | 30, 40 | 20, 25 |
| Half Hard | — | 9, 20 (H14) | 8, 16 (H14) | 9, 12 (H34) |
| Hard | 1.5[d] (H19) | 5, 15 (H18) | 4, 10 (H18) | 5, 6 (H38) |
| Hardness (Brinell)[b] | | | | |
| Annealed (O) | — | 23 | 28 | 45 |
| Half Hard | — | 32 (H14) | 40 (H14) | 63 (H34) |
| Hard | — | 44 (H18) | 55 (H18) | 77 (H38) |
| Endurance Limit, 1000 psi | | | | |
| Annealed (O) | — | 5 | 7 | 14 |
| Half Hard | — | 7 (H14) | 9 (H14) | 15 (H34) |
| Hard | 7 (H19) | 9 (H18) | 10 (H18) | 16 (H38) |
| Shear Str, 1000 psi | | | | |
| Annealed (O) | 8 | 9 | 11 | 16 |
| Half Hard | 10 (H14) | 11 (H14) | 14 (H14) | 18 (H34) |
| Hard | 15 (H19) | 13 (H18) | 16 (H18) | 21 (H38) |
| FABRICATING PROPERTIES | | | | |
| Annealing Temp, F | 650 | 650 | 775 | 650 |
| Hot Working Temp Range, F | — | 500–950 | 500–950 | 500–950 |
| Machinability | Fair | Good | Good | Good |
| Relative Weldability[c] | | | | |
| Torch | — | A | A | B |
| Inert Arc | A | A | A | A |
| Electrical Resistance | — | A | A | A |
| CORROSION RESISTANCE | High resistance to rural, industrial and marine atmospheres. Good resistance to most neutral or nearly neutral fresh waters; sea water; many foodstuffs; organic acids and anhydrides; alcohols; aldehydes; esters; ketones; oils, gasoline, greases, waxes, and other petroleum derivatives; ammonia and ammonium compounds; nitric acid above 82%; essential oils; amides; nitroparaffins; coal tar derivatives; hydrogen peroxide; and many neutral aqueous inorganic salt solutions | | | |
| AVAILABLE FORMS | Sheet, plate, wire, rod, bar | | | |
| | Foil, extrusions | Rivets, forgings, impact extrusions | Extruded shapes, tubing, forgings | Sheet, plate |
| USES | Electrical conductors | Cooking utensils, heat exchangers, pressure and storage tanks | | Hydraulic tubing for commercial vehicles, storage tanks |
| | | Chemical equipment, reflectors | Ductwork, truck panels, architectural applications, builders' hardware | |

[a] Values given for 1/16-in. sheet and 1/2-in. bar, in that order. [b] 500-kg load, 10-mm ball.
[c] Letter A indicates most favorable, B less favorable, etc. Values relative to aluminum alloys only.
[d] Elongation (in 10 in.) for wire.

## Aluminum and Its Alloys—Wrought

| Type ➡ | 2011 | 2014[a, b] | 2017 | 2024[c] |
|---|---|---|---|---|
| COMPOSITION, % | Cu 5.0–6.0, Pb 0.2–0.6, Bi 0.2–0.6 | Cu 3.9–5.0, Si 0.5–1.2, Mn 0.4–1.2, Mg 0.2–0.8 | Cu 3.5–4.5, Mn 0.4–1.0, Mg 0.2–0.8 | Cu 3.8–4.9, Mn 0.3–0.9, Mg 1.2–1.8 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.102 | 0.101 | 0.101 | 0.100 |
| Melting Temp Range, F | 995–1190 | 950–1180 | 955–1185 | 935–1180 |
| Ther Cond (77 F, annealed), Btu/hr/sq ft/°F/ft | 81.7 | 111.0 | 99.4 | 111.0 |
| Coef of Ther Exp, per °F | | | | |
| 68 to 212 F | $12.8 \times 10^{-6}$ | $12.5 \times 10^{-6}$ | $12.7 \times 10^{-6}$ | $12.6 \times 10^{-6}$ |
| 68 to 572 F | $13.9 \times 10^{-6}$ | $13.6 \times 10^{-6}$ | $13.9 \times 10^{-6}$ | $13.7 \times 10^{-6}$ |
| Spec Heat, Btu/lb/°F | 0.23 | 0.22 | 0.22 | 0.22 |
| Elec Res (68 F), microhm-cm | 4.31 (T3) | 3.45 (O), 4.31 (T6) | 3.83 (O), 5.75 (T4) | 3.45 (O), 5.75 (T4) |
| MECHANICAL PROPERTIES[d] | | | | |
| Mod of Elast in Tension, psi | $10.2 \times 10^6$ | $10.6 \times 10^6$ | $10.5 \times 10^6$ | $10.6 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Annealed (O) | — | 27 | 26 | 27 |
| Heat Treated | 55 (T3), 59 (T8) | 62 (T4), 70 (T6) | 62 (T4) | 70 (T3) |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Annealed (O) | — | 14 | 10 | 11 |
| Heat Treated | 43 (T3), 45 (T8) | 42 (T4), 60 (T6) | 40 (T4) | 50 (T3) |
| Elong (in 2 in.), % | | | | |
| Annealed (O) | — | 18 | 22 | 20[f] |
| Heat Treated | 15 (T3), 12 (T8) | 20 (T4), 13 (T6) | 22 (T4) | 18 (T3)[f] |
| Hardness (Brinell) | | | | |
| Annealed (O) | — | 45 | 45 | 47 |
| Heat Treated | 95 (T3), 100 (T8) | 105 (T4), 135 (T6) | 105 (T4) | 120 (T3) |
| Endurance Limit, 1000 psi | | | | |
| Annealed (O) | | 13 | 13 | 13 |
| Heat Treated | 18 (T3), 18 (T8) | 20 (T4), 18 (T6) | 18 (T4) | 20 (T3) |
| Shear Str, 1000 psi | | | | |
| Annealed (O) | — | 18 | 18 | 18 |
| Heat Treated | 32 (T3), 35 (T8) | 38 (T4), 42 (T6) | 38 (T4) | 41 (T3) |
| FABRICATING PROPERTIES | | | | |
| Annealing Temp, F | 775 | 775 | 775 | 775 |
| Solution Temp, F | 950 | 940 | 940 | 920 |
| Aging Temp, F | 320 | 340 | — | 375 |
| Machinability[e] | A (T3, T8) | A (T6) | A (T4) | A (T3) |
| Relative Weldability[e] | | | | |
| Torch | D | D | D | D |
| Inert Arc | D | B | B | B |
| Electrical Resistance | D | B | A | B |
| CORROSION RESISTANCE | Compared to other aluminum alloys, this group has high resistance to rural atmospheres, fairly good resistance to industrial atmospheres, and poor resistance to marine atmospheres and sea water. More susceptible to corrosive attack than other groups of wrought aluminum alloys. Both degree and nature of the attack are greatly influenced by thermal treatment. Clad sheet alloys generally have high corrosion resistance | | | |
| AVAILABLE FORMS | Rod, hexagon bar, wire | Extruded shapes, rolled shapes, forgings, rod, bar | Rod, bar, wire | Sheet, plate, rod, bar, tubing, wire, rivets, extruded shapes |
| USES | Screw machine products | Heavy duty forgings, power shovel bails, airplane fittings, structural members | Screw machine products | Screw machine products |

[a] 2014 available clad with 6053.
[b] Similar to 2014 is Hardclad 301. Core: 4.0-5.0 Cu, 0.75-1.2 Si, 0.70-1.0 Mn, 0.25-0.55 Mg. Claddings: 0.50-0.90 Si, 0.25-0.75 Mn, 0.80-1.2 Mg.
[c] 2024 available clad with aluminum of 99.3% min purity.
[d] Values given on ½-in. sheet and ½-in. bar, in that order.
[e] Letter A indicates most favorable, B less favorable, etc. Relative to aluminum alloys only.
[f] Elongation (in 10 in.) for wire.

*continued on next page*

## Aluminum and Its Alloys—Wrought

| Type → | 5005 | 5050 | 5052 | 5056 |
|---|---|---|---|---|
| COMPOSITION, % | Mg 0.8 | Mg 1.0–1.8 | Mg 2.2–2.8, Cr 0.15–0.35 | Mn 0.05–0.20, Mg 4.7–5.6, Cr 0.05–0.20 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.097 | 0.097 | 0.097 | 0.095 |
| Melting Temp Range, F | 1160–1205 | 1160–1205 | 1100–1200 | 1055–1180 |
| Ther Cond (77 F, ann.), Btu/hr/sq ft/°F/ft | 111 | 111 | 79.2 | 67.4 |
| Coef of Ther Exp, per °F | | | | |
| 68 to 212 F | $13.3 \times 10^{-6}$ | $13.2 \times 10^{-6}$ | $13.2 \times 10^{-6}$ | $13.4 \times 10^{-6}$ |
| 68 to 572 F | — | $14.2 \times 10^{-6}$ | $14.3 \times 10^{-6}$ | $14.5 \times 10^{-6}$ |
| Spec Heat (212 F), Btu/lb/°F | 0.23 | 0.22 | 0.22 | 0.22 |
| Elec Res (68 F), microhm-cm | | | | |
| Annealed | 3.4 | — | 4.93 | 5.94 |
| Hard (H18 or H38) | — | — | 4.93 | 6.39 |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elasticity in Tension, psi | $10 \times 10^6$ | $10 \times 10^6$ | $10.2 \times 10^6$ | $10.3 \times 10^6$ |
| Ten Str (75 F), 1000 psi | | | | |
| Annealed (O) | 18 | 21 | 28 | 42 |
| Half Hard | 23 (H14) | 28 (H34) | 38 (H34) | — |
| Hard | 29 (H18) | 32 (H38) | 42 (H38) | 60 (H38) |
| Yld Str (75 F), 1000 psi | | | | |
| Annealed (O) | 6 | 8 | 13 | 22 |
| Half Hard | 22 (H14) | 24 (H34) | 31 (H34) | — |
| Hard | 28 (H18) | 29 (H38) | 37 (H38) | 50 (H38) |
| Elong (in 2 in., 75 F), %[a] | | | | |
| Annealed (O) | 30, — | 24 | 25, 30 | —, 35 |
| Half Hard | 6, — (H14) | 8 (H34) | 10, 14 (H34) | — |
| Hard | 4, — (H18) | 6 (H38) | 7, 8 (H38) | —, 15 (H38) |
| Hardness (Brinell)[b] | | | | |
| Annealed (O) | 28 | 36 | 47 | 65 |
| Half Hard | 41 (H14) | 53 (H34) | 68 (H34) | — |
| Hard | 51 (H38) | 63 (H38) | 77 (H38) | 105(H18),100(H38) |
| Endurance Limit, 1000 psi | | | | |
| Annealed (O) | — | 12 | 16 | 20 |
| Half Hard | — | 13 (H34) | 18 (H34) | — |
| Hard | — | 14 (H38) | 20 (H38) | 22 (H38) |
| Shear Str, 1000 psi | | | | |
| Annealed (O) | 11 | 15 | 18 | 26 |
| Half Hard | 14 (H14) | 18 (H34) | 21 (H34) | — |
| Hard | 16 (H18) | 20 (H38) | 24 (H38) | 32 (H38) |
| FABRICATING PROPERTIES | | | | |
| Annealing Temp, F | 650 | 650 | 650 | 650 |
| Hot Working Temp Range, F | — | — | 500–950 | 500–950 |
| Machinability | Good | Good | Good | Good |
| Relative Weldability[c] | | | | |
| Torch | — | B | B | C |
| Inert Arc | — | A | A | A |
| Electrical Resistance | — | A | A | B |
| CORROSION RESISTANCE | High resistance to rural, industrial and marine atmospheres. Good resistance to most neutral or nearly neutral fresh waters; sea water; many foodstuffs; organic acids and anhydrides; alcohols; aldehydes; esters; ketones; oils, gasoline, greases, waxes, and other petroleum derivatives; ammonia and ammonium compounds; nitric acid above 82%; essential oils; amides; nitroparaffins; coal tar derivatives; hydrogen peroxide; and many neutral aqueous inorganic salt solutions | | | |
| AVAILABLE FORMS | Foil, sheet, plate | Sheet, plate, drawn tube | Sheet, plate, wire, rod, bar, drawn tubing | Rod, wire |
| USES | Appliances, cooking utensils, architectural applications | Decorative refrigerator parts, coiled tubes, builders' hardware | Bus and truck bodies, aircraft tubing, milk crates, fan blades, kitchen cabinets | Cable sheathing, rivets for magnesium |

[a] Values given for 1/16-in. sheet and 1/2-in. bar, in that order. [b] 500-kg load, 10-mm ball.
[c] Letter A indicates most favorable, B less favorable, etc. Values relative to aluminum alloys only.

## Aluminum and Its Alloys—Wrought

| Type → | 5083 | 5086 | 5154 | 5456 |
|---|---|---|---|---|
| COMPOSITION, % | Mg 4.0–4.9, Mn 0.5–1.0, Cr 0.25 max | Mg 3.5–4.5, Mn 0.2–0.7, Cr 0.25 max | Mg 3.5, Cr 0.25 | Mg 4.7–5.5, Mn 0.5–1.0, Cr 0.05–0.20 |
| **PHYSICAL PROPERTIES** | | | | |
| Density, lb/cu in. | 0.096 | 0.096 | 0.096 | 0.096 |
| Melting Temp Range, F | 1065–1180 | 1084–1184 | 1100–1190 | — |
| Ther Cond (77 F, ann.), Btu/hr/sq ft/°F/ft | 68 | 73 | 73 | — |
| Coef of Ther Exp (68–212 F), per °F | $13.2 \times 10^{-6}$ | $13.2 \times 10^{-6}$ | $13.3 \times 10^{-6}$ | $13.3 \times 10^{-6}$ |
| Spec Heat (212 F), Btu/lb/°F | 0.23 | 0.23 | 0.23 | 0.23 |
| Elec Res (68 F), microhm-cm | | | | |
| Annealed | 5.9 | 5.5 | 5.3 | 5.9 |
| Hard | — | 5.5 | 5.3 | — |
| **MECHANICAL PROPERTIES** | | | | |
| Mod of Elast in Tension, psi | $10.3 \times 10^6$ | $10.3 \times 10^6$ | $10.2 \times 10^6$ | $10.3 \times 10^6$ |
| Ten Str (75 F), 1000 psi | | | | |
| Annealed (O) | 42 | 38 | 35 | 45 |
| Half Hard | 43 (H113) | 47 (H34) | 42 (H34) | 51 (H321) |
| Hard | — | — | 48 (H38) | — |
| Yld Str (75 F), 1000 psi | | | | |
| Annealed | 21 | 17 | 17 | 23 |
| Half Hard | 33 (H113) | 37 (H34) | 33 (H34) | 37 (H321) |
| Hard | — | — | 39 (H38) | — |
| Elong (in 2 in., 75 F), %[a] | | | | |
| Annealed (O) | 22, — | 22, — | 27, — | 24, — |
| Half Hard | 16 (H113), — | 10 (H34), — | 13 (H34), — | 16 (H321), — |
| Hard | — | — | 10 (H38), — | — |
| Hardness (Brinell)[b] | | | | |
| Annealed (O) | 73 | B16[d] | 58 | 75 |
| Half Hard | — | B44[d] | 78 (H34) | 90 (H321) |
| Hard | — | — | 87 (H38) | — |
| Endurance Limit, 1000 psi | | | | |
| Annealed (O) | — | — | 17 | — |
| Half Hard | 23 (H113) | 16 (H34) | 19 (H34) | — |
| Hard | — | — | 21 (H38) | — |
| Shear Str, 1000 psi | | | | |
| Annealed (O) | 25 | 23 | 22 | 28 |
| Half Hard | — | 27 (H34) | 24 (H34) | 30 (H321) |
| Hard | — | — | 28 (H38) | — |
| **FABRICATING PROPERTIES** | | | | |
| Annealing Temp, F | 650 | 650 | 650 | — |
| Machinability | D | D | D | D |
| Relative Weldability[c] | | | | |
| Torch | D | C | C | D |
| Inert Arc | A | A | A | A |
| Electrical Resistance | B | B | B | B |
| CORROSION RESISTANCE | High resistance to rural, industrial and marine atmospheres. Good resistance to most neutral or nearly neutral fresh waters; sea water; many foodstuffs; organic acids and anhydrides; alcohols; aldehydes; esters; ketones; oils, gasoline, greases, waxes, and other petroleum derivatives; ammonia and ammonium compounds; nitric acid above 82%; essential oils; amides; nitroparaffins; coal tar derivatives; hydrogen peroxide; and many neutral aqueous inorganic salt solutions | | | |
| AVAILABLE FORMS | Plate, extrusions, sheet, structural shapes, bar, rod | Sheet, plate, extrusions, structural shapes | Sheet, plate, welding wire, pipe, rod, bar | Sheet, plate, extrusions, rods, bar, structural shapes |
| USES | Unfired pressure vessels, marine superstructures, decks and hulls, auto frames, aircraft landing gears, TV structural towers, drilling rigs, welded assemblies | Transportation equipment, welded construction, unfired pressure vessels, guided missile containers | Unfired pressure vessels, welded construction, storage tanks, truck and marine applications | Deck housing, heavy duty structures, overhead cranes, gun mounts, pressure vessels, storage tanks |

[a] Values given for ⅛-in. sheet and ½-in. bar in that order. [b] 500-kg load, 10-mm ball.
[c] Letter A indicates most favorable, B less favorable, etc. Values relative to aluminum alloys only.
[d] Rockwell hardness.

*continued on next page*

## Aluminum and Its Alloys—Wrought

| Type → | 6061 | 6063 | 7075 | 7079 |
|---|---|---|---|---|
| COMPOSITION, % | Mg 0.8–1.2, Si 0.4–0.8, Cr 0.15–0.35, Cu 0.15–0.40 | Mg 0.45–0.9, Si 0.2–0.6 | Zn 5.1–6.1, Mg 2.1–2.9, Cu 1.2–2.0, Cr 0.18–0.40 | Zn 3.8–4.8, Mg 2.9–3.7, Cu 0.4–0.8, Mn 0.1–0.3, Cr 0.1–0.25 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.098 | 0.098 | 0.101 | 0.099 |
| Melting Temp Range, F | 1080–1200 | 1140–1205 | 890–1180 | 900–1180 |
| Ther Cond (77 F), Btu/hr/sq ft/°F/ft | 99 | 111 | 70 (T6) | 70 (T6) |
| Coef of Ther Exp, per °F | | | | |
| 68–212 F | $13.0 \times 10^{-6}$ | $13.0 \times 10^{-6}$ | $12.9 \times 10^{-6}$ | $13.1 \times 10^{-6}$ |
| 68–572 F | $14.1 \times 10^{-6}$ | $14.2 \times 10^{-6}$ | $14.4 \times 10^{-6}$ | $14.2 \times 10^{-6}$ |
| Specific Heat, Btu/lb/°F | 0.23 | — | 0.23 | — |
| Elec Res (68 F), microhm-cm | 3.8 (O) | 3.1 (T6) | 5.7 (T6) | 5.5 (T6) |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | $10.0 \times 10^6$ | $10.0 \times 10^6$ | $10.4 \times 10^6$ | $10.3 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Annealed (O) | 18 | 13 | 33 | — |
| Heat Treated | 35 (T4), 45 (T6) | 25 (T4), 35 (T6) | 83 (T6) | 78 (T6) |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Annealed (O) | 8 | 7 | 15 | — |
| Heat Treated | 21 (T4), 40 (T6) | 13 (T4), 31 (T6) | 73 (T6) | 68 (T6) |
| Elong (in 2 in.), % | | | | |
| Annealed (O) | 25 | — | 17 | — |
| Heat Treated | 22 (T4), 12 (T6) | 22 (T4), 12 (T6) | 11 (T6) | 14 (T6) |
| Hardness (Brinell) | | | | |
| Annealed (O) | 30 | 25 | 60 | — |
| Heat Treated | 65 (T4), 95 (T6) | —, 73 (T6) | 150 (T6) | 145 (T6) |
| Endurance Limit, 1000 psi | | | | |
| Annealed (O) | 9 | 8 | — | — |
| Heat Treated | 14 (T4), 14 (T6) | —, 10 (T6) | 23 (T6) | 23 (T6) |
| Shear Str, 1000 psi | | | | |
| Annealed (O) | 12 | 10 | 22 | — |
| Heat Treated | 24 (T4), 30 (T6) | —, 22 (T6) | 48 (T6) | 45 (T6) |
| FABRICATING PROPERTIES | | | | |
| Annealing Temp, F | 775 | 775 | 775 | — |
| Solution Temp, F | 970 | — | 880 | 830 |
| Aging Temp, F | 340 | 350–450 | 250 | 240–250 |
| Machinability* | B (T4, T6) | B (T4, T6) | A (T6) | A (T6) |
| Relative Weldability* | | | | |
| Torch | A | A | D | D |
| Inert Arc | A | A | C | C |
| Elec Res | A | A | C | C |
| CORROSION RESISTANCE | Compared with other aluminum alloys, these alloys have high resistance to rural atmospheres, good resistance to industrial and marine atmospheres. Degree and nature of attack in other environments is greatly influenced by heat treatment. Clad alloys have corrosion resistance of the cladding alloy | | Compared with other aluminum alloys, these alloys have good corrosion resistance to rural atmospheres but are attacked by industrial and marine atmospheres. In other environments, they are generally less corrosion resistant than other wrought aluminum alloys and are frequently clad. Clad alloys have corrosion resistance of the cladding alloy | |
| AVAILABLE FORMS | Sheet, plate, wire, rod, bar, pipe, tubing, rolled and extruded shapes forgings | Extruded shapes, tube, pipe | Sheet, plate, wire, rod, bar, extruded shapes, tube, pipe, forgings | Forgings, extrusions, sheet, plate |
| USES | Transportation equipment, heavy duty structures, marine uses, pipe, furniture | Pipe, railings, hardware, architectural uses | Structural parts for aircraft | |

* Letter A indicates most favorable, B less favorable, etc. Relative to aluminum alloys only.

## Aluminum and Its Alloys—Cast

| Type → | 195 | B195 | 108 | A108 |
|---|---|---|---|---|
| COMPOSITION, % | Cu 4.5, Al bal | Cu 4.5, Si 2.5, Al bal | Cu 4.0, Si 3.0, Al bal | Cu 4.5, Si 5.5, Al bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.101 | 0.100 | 0.100 | 0.100 |
| Solid. Temp Range, F | 1195–910 | 1160–980 | 1160–970 | 1135–970 |
| Ther Cond (as cast, 68 F), Btu/hr/sq ft/°F/ft | 82.5 | 92.5 | 70 | 82 |
| Coef of Ther Exp (68–212 F), per °F | $12.7 \times 10^{-6}$ | $12.2 \times 10^{-6}$ | $12.2 \times 10^{-6}$ | $11.9 \times 10^{-6}$ |
| Elec Cond (as cast), % IACS | 36 | 42.5 | 31 | 37 |
| MECHANICAL PROPERTIES | | | | |
| Ten Str, 1000 psi | | | | |
| As Cast | — | — | 21 | 28 |
| Sol'n Heat Treated | 32 | 37 | — | — |
| Sol'n Treated & Aged | 36 | 40 | — | — |
| Yld Str (0.2% offset), 1000 psi | | | | |
| As Cast | — | — | 14 | 16 |
| Sol'n Heat Treated | 16 | 19 | — | — |
| Sol'n Treated & Aged | 24 | 26 | — | — |
| Elong (in 2 in.), % | | | | |
| As Cast | — | — | 2.5 | 2.0 |
| Sol'n Heat Treated | 8.5 | 9.0 | — | — |
| Sol'n Treated & Aged | 5.0 | 5.0 | — | — |
| Hardness (Brinell) | | | | |
| As Cast | — | — | 55 | 70 |
| Sol'n Heat Treated | 60 | 75 | — | — |
| Sol'n Treated & Aged | 95 | 90 | — | — |
| Endurance Limit, 1000 psi | | | | |
| Sol'n Heat Treated | 7 | 9.5 | 11 | — |
| Sol'n Treated & Aged | 8 | 10.0 | — | — |
| Compr Yld Str, 1000 psi | | | | |
| As Cast | — | — | 14 | 16 |
| Sol'n Heat Treated | 17 | 20 | — | — |
| Sol'n Treated & Aged | 25 | 26 | — | — |
| Shear Str, 1000 psi | | | | |
| As Cast | — | — | 17 | 25 |
| Sol'n Heat Treated | 26 | 30 | — | — |
| Sol'n Treated & Aged | 30 | 32 | — | — |
| THERMAL TREATMENT | | | | |
| Annealing Temp, F | 650 | 650 | 650 | 650 |
| Solution Temp, F | 960 | 950 | 960 | 940 |
| Aging Temp, F | 310 | 310 | 310 | 310 |
| FABRICATING PROPERTIES | | | | |
| Machinability* | AB | AB | C | C |
| Weldability* | | | | |
| Gas | C | C | B | A |
| Arc | B | B | D | A |
| Resistance | B | B | B | A |
| CORROSION RESISTANCE | Good corrosion resistance; alloys containing silicon are superior. In general: Resistant to nitric, chromic and most organic acids; attacked by hydrochloric and sulfuric acids. Resistant to ammonium hydroxide; attacked by sodium, potassium and calcium hydroxides. Resistant to many salts, but attacked by salts of heavy metals. Resistant to attack by industrial and marine atmospheres | | | |
| AVAILABLE FORMS | Sand castings | Permanent mold castings | Sand castings | Permanent mold castings |
| USES | Crankcases, bus wheels, housings, spring hangers, fittings | Aircraft fittings, fuel pump bodies, gear housings, seat frames | Manifolds, valve bodies, pressure-tight parts | Parts requiring pressure tightness |

* General purpose castings. † A = excellent, AB = very good, B = good, C = fair, D = poor.

*continued on next page*

## Aluminum and Its Alloys—Cast

| Type → | 214 | 220 | 43 | 356 |
|---|---|---|---|---|
| COMPOSITION, % | Mg 4.0, Al bal | Mg 4.0, Al bal | Si 5.25, Al bal | Si 7.0, Mg 0.35, Al bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.095 | 0.093 | 0.097 | 0.097 |
| Solid. Temp Range, F | 1185–1075 | 1150–840 | 1170–1065 | 1130–1035 |
| Ther Cond (as cast, 68F), Btu/hr/sq ft/°F/ft | 80 | 51 | 85 | 92 |
| Coef of Ther Exp (68–212 F), per °F | 13.3 x $10^{-6}$ | 13.6 x $10^{-6}$ | 12.2 x $10^{-6}$ | 11.9 x $10^{-6}$ |
| Elec Cond (as cast), % IACS | 35 | 21 | 38 | 41 |
| MECHANICAL PROPERTIES[c] | | | | |
| Ten Str, 1000 psi | | | | |
| As Cast | 25 | — | 19 | — |
| Sol'n Heat Treated | — | 46 | — | — |
| Aged[a] | — | — | — | 25, 40 |
| Yld Str (0.2% offset), 1000 psi | | | | |
| As Cast | 12 | — | 8 | — |
| Sol'n Heat Treated | — | 25 | — | — |
| Aged[a] | — | — | — | 20, 27 |
| Elong (in 2 in.), % | | | | |
| As Cast | 9.0 | — | 8 | — |
| Sol'n Heat Treated | — | 14 | — | — |
| Aged[a] | — | — | — | 2.0, 5.0 |
| Hardness (Brinell) | | | | |
| As Cast | 50 | — | 40 | — |
| Sol'n Heat Treated | — | 75 | — | — |
| Aged[a] | — | — | — | 60, 90 |
| Endurance Limit, 1000 psi | | | | |
| As Cast | 7 | — | 8 | — |
| Sol'n Heat Treated | — | 8 | — | 7.5, 13 |
| Compr Yld Str, 1000 psi | | | | |
| As Cast | 12 | — | 9 | — |
| Sol'n Heat Treated | — | 26 | — | — |
| Aged[a] | — | — | — | 21, 27 |
| Shear Str, 1000 psi | | | | |
| As Cast | 20 | — | 14 | — |
| Sol'n Heat Treated | — | 33 | — | 20, 32 |
| THERMAL TREATMENT | | | | |
| Annealing Temp, F | 650 | 650 | 650 | 650 |
| Solution Temp, F | — | 810 | — | 1000 |
| Aging Temp, F | — | — | — | 310 |
| FABRICATING PROPERTIES | | | | |
| Machinability[b] | A | A | C | A |
| Weldability[b, c] | | | | |
| Gas | B | D | A, — | A, A |
| Arc | A | C | A, — | A, A |
| Resistance | B | B | A, — | A, A |
| CORROSION RESISTANCE | Very good corrosion resistance; alloys containing silicon are superior. In general: Resistant to nitric, chromic and most organic acids; attacked by hydrochloric and sulfuric acids. Resistant to ammonium hydroxide; attacked by sodium, potassium and calcium hydroxides. Resistant to many salts, but attacked by salts of heavy metals. Resistant to attack by industrial and marine atmospheres | | | |
| AVAILABLE FORMS | Sand castings | Sand castings | Sand and perm mold castings | Sand and perm mold castings |
| USES | Dairy and food handling equipment, cooking utensils, chemical fittings, hardware | Aircraft fittings, levers, brackets, parts requiring shock resistance | Sand—marine fittings, food handling equipment, pipe fittings. Permanent mold — refrigerator fittings, carburetor bodies, thin-section general purpose castings | Sand—automotive transmission cases, housings, aircraft fittings |

[a] Corrosion resistant castings. [b] A = excellent, AB = very good, B = good, C = fair, D = poor.
[c] Where two values are given they refer to sand and permanent mold castings, respectively.
[d] First value obtained by artificial aging; second value by solution treating and aging.

## Aluminum and Its Alloys—Cast

| Type → | 122 | 142 | 355 | 40-E |
|---|---|---|---|---|
| COMPOSITION, % | Cu 10.0, Mg 0.25, Al bal | Cu 4.0, Mg 1.5, Ni 2.0, Al bal | Cu 1.25, Si 5.0, Mg 0.5, Al bal | Zn 5.5, Mg 0.6, Cr 0.5, Ti 0.20, Al bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.107 | 0.102 | 0.098 | 0.102 |
| Solid. Temp Range, F | 1160–1005 | 1165–995 | 1160–1070 | 1140–1060 |
| Ther Cond (as cast, 68 F), Btu/hr/sq ft/°F/ft | 77 | 87 | 87 | 80 |
| Coef of Ther Exp (68–212 F), per °F | $12.2 \times 10^{-6}$ | $12.5 \times 10^{-6}$ | $12.4 \times 10^{-6}$ | $13.7 \times 10^{-6}$ |
| Elec Cond (as cast), % IACS | 33 | 38.5 | 39 | 25 |
| MECHANICAL PROPERTIES | | | | |
| Tensile Strength, 1000 psi | | | | |
| Artificially Aged | 37 | 40 | 30 | 35 |
| Sol'n Treated & Aged | 48 | 47 | 42 | — |
| Yield Strength (0.2% offset), 1000 psi | | | | |
| Artificially Aged | 35 | 34 | 24 | 25 |
| Sol'n Treated & Aged | 36 | 42 | 27 | — |
| Elongation (in 2 in.), % | | | | |
| Artificially Aged | 0.5 | 1.0 | 2.0 | 3.0 |
| Sol'n Treated & Aged | 0.5 | 0.5 | 4.0 | — |
| Hardness (Brinell) | | | | |
| Artificially Aged | 115 | 105 | 75 | 60–75 |
| Sol'n Treated & Aged | 140 | 110 | 90 | — |
| Endurance Limit, 1000 psi | | | | |
| Artificially Aged | 8.5 | 10.5 | 7 | 10 |
| Sol'n Treated & Aged | 9 | 9.5 | 10 | — |
| Compressive Yield Strength, 1000 psi | | | | |
| Artificially Aged | 40 | 34 | 24 | 17 |
| Sol'n Treated & Aged | 36 | 44 | 27 | — |
| Shear Strength, 1000 psi | | | | |
| Artificially Aged | 27 | 26 | 24 | 28 |
| Sol'n Treated & Aged | 30 | 31 | 34 | — |
| THERMAL TREATMENT | | | | |
| Annealing Temp, F | 650 | 650 | 650 | — |
| Solution Temp, F | 950 | 960 | 980 | — |
| Aging Temp, F | 310 | 650 | 310 | 356 |
| FABRICATING PROPERTIES | | | | |
| Machinability[c] | AB | AB | B | A |
| Weldability[c,f] | | | | |
| Gas | C, D | C, C | A, A | C |
| Arc | B, C | B, B | A, A | C |
| Resistance | B, B | B, B | A, A | C |
| CORROSION RESISTANCE | Good corrosion resistance; alloy 355 is superior. In general resistant to nitric, chromic and most organic acids; attacked by hydrochloric and sulfuric acids. Resistant to ammonium hydroxide; attacked by sodium, potassium and calcium hydroxides. Resistant to many salts, but attacked by salts of heavy metals. Resistant to attack by industrial and marine atmospheres | | | |
| AVAILABLE FORMS | Sand and permanent mold castings | Sand and permanent mold castings | Sand and permanent mold castings | Sand castings |
| USES | Sand—cylinder heads, bearing caps, bushings, tappet guides. Permanent mold—meter parts, automotive pistons, bushings, bearings | Sand—cylinder heads, diesel engine pistons | Sand—cylinder heads, water jackets, housings, printing press bed plates. Permanent mold—aircraft supercharger impellers, timing gears, meter parts, rotors | Stressed parts of aircraft, turret housings, air compressor pistons, instrument parts, machine parts |

[c] High temperature resistant castings.
[e] A = excellent, AB = very good, B = good, C = fair, D = poor.
[f] The two values refer to sand and permanent mold castings, respectively.

*continued on next page*

## Aluminum and Its Alloys—Cast

| Type → | 218 | 431 | A13 | 380 |
|---|---|---|---|---|
| COMPOSITION, % | Mg 8.0, Al bal | Si 5.25, Al bal | Si 12.0, Fe 1.3 max Al bal | Cu 3.5, Si 8.5 Fe 1.3 max, Al bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.093 | 0.097 | 0.096 | 0.097 |
| Solid. Temp Range, F | 1150–995 | 1175–1070 | 1085–1065 | 1100–1000 |
| Ther Cond (as cast, 68 F), Btu/hr/sq ft/°F/ft | 56 | 84 | 70 | 58 |
| Coef of Ther Exp (68–212 F), per °F | 13.3 x $10^{-6}$ | 12.2 x $10^{-6}$ | 11.4 x $10^{-6}$ | 11.7 x $10^{-6}$ |
| Elec Cond (as cast), % IACS | 24 | 38 | 35 | 25 |
| MECHANICAL PROPERTIES | | | | |
| Ten Str, 1000 psi | 42 | 30 | 35 | 43 |
| Yld Str (0.2% offset), 1000 psi | 23 | 16 | 21 | 26 |
| Elong (in 2 in.), % | 7.0 | 9.0 | 3.5 | 2.0 |
| Endurance Limit, 1000 psi | 18 | 17 | 19 | 20 |
| Compr Yld Str, 1000 psi | 27 | 16 | 21 | 25 |
| Shear Str, 1000 psi | 27 | 19 | 25 | 28 |
| FABRICATING PROPERTIES | | | | |
| Machinability[a] | A | C | A | AB |
| Weldability[a] | | | | |
| Gas | D | B | D | D |
| Arc | D | B | D | D |
| Resistance | D | C | D | D |
| CORROSION RESISTANCE | Good corrosion resistance; alloys containing silicon are superior. In general: Resistant to nitric, chromic and most organic acids; attacked by hydrochloric and sulfuric acids. Resistant to ammonium hydroxide; attacked by sodium, potassium and calcium hydroxides. Resistant to many salts, but attacked by salts of heavy metals. Resistant to attack by industrial and marine atmospheres | | | |
| AVAILABLE FORMS | Die castings | Die castings | Die castings | Die castings |
| USES | Aircraft fittings and brake shoes, marine fittings, hardware | General purpose castings | Dental equipment, outboard motor pistons, typewriter frames | General purpose castings |

[a] Die castings.
[a] A = excellent, AB = very good, B = good, C = fair, D = poor.

## Aluminum and Its Alloys—Cast

| Type → | 319 | C355 | A356 | 327 |
|---|---|---|---|---|
| COMPOSITION, % | Cu 3.8, Si 6.25, Al bal | Cu 1.25, Si 5.0, Mg 0.5, Al bal | Si 7.0, Mg 0.4, Al bal | Cu 1.5, Si 7.8, Mg 0.4, Mn 0.4, Al bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.100 | 0.097 | 0.097 | 0.096 |
| Solid. Temp Range, F | 1120–950 | 1160–1070 | 1130–1075 | 1110–1055 |
| Ther Cond (as cast, 68 F), Btu/hr/sq ft/°F/ft | 66 | 82[b] | 92[b] | 65 |
| Coef of Ther Exp (68–212 F), per °F | $12.0 \times 10^{-6}$ | $12.4 \times 10^{-6}$ | $11.9 \times 10^{-6}$ | $11.9 \times 10^{-6}$ |
| Elec Cond (as cast), % IACS | 28 | 37[b] | 41[b] | 29 |
| MECHANICAL PROPERTIES[a] | | | | |
| Tensile Strength, 1000 psi | | | | |
| As Cast | 27, 34 | — | — | —, — |
| Solution Treated and Aged | 36, 40 | 46 | 41 | 36, 49 |
| Yld Str (0.2% offset), 1000 psi | | | | |
| As Cast | 18, 19 | — | — | —, — |
| Solution Treated and Aged | 24, 27 | 34 | 30 | 20, 40 |
| Elongation (in 2 in.), % | | | | |
| As Cast | 2.0, 2.5 | — | — | —, — |
| Solution Treated and Aged | 2.0, 3.0 | 6.0 | 10.0 | 2.0, 3.0 |
| Hardness, Brinell | | | | |
| As Cast | 70, 85 | — | — | —, — |
| Solution Treated and Aged | 80, 95 | 100 | 90 | 81, 97 |
| Fatigue Str ($5 \times 10^8$ cycles), 1000 psi | | | | |
| As Cast | 10, — | — | — | —, — |
| Solution Treated and Aged | 10, — | 13.0 | 10 | —, — |
| Compr Yld Str (0.2% offset), 1000 psi | | | | |
| As Cast | 18, 19 | — | — | —, — |
| Solution Treated and Aged | 24, 27 | 36 | — | 20, — |
| Shear Str, 1000 psi[b] | — | 33 | 35 | — |
| THERMAL TREATMENT | | | | |
| Annealing Temp, F | 650 | 650 | 650 | 650 |
| Solution Temp, F | 940 | 980 | 1000 | — |
| Aging Temp, F | 310 | 310 | 310 | — |
| FABRICATING PROPERTIES | | | | |
| Machinability | Good | Good | Good | Good |
| Weldability (torch and arc) | Good | Good | Good | Good |
| CORROSION RESISTANCE | Fair | Good | Good | Good |
| AVAILABLE FORMS | Sand and permanent mold castings | Permanent mold castings | Permanent mold castings | Sand and permanent mold castings |
| USES | Engine parts, automotive cylinder heads, piano plates | Aircraft, missile and other structural uses requiring good strength | | |

[a] Where two values are given, they refer to sand and permanent mold castings, respectively. All single values are for permanent mold castings.
[b] Solution treated and aged.

## Cobalt and Cobalt-Base Superalloys

| Type → | Cobalt[a] | S-816 | V-36 | HS-25, L-602 |
|---|---|---|---|---|
| COMPOSITION, % | Co 99.9 | C 0.38, Mn 1.32, Cr 19.88, Ni 20.65, Mo 3.76, W 4.20, Cb 4.13, Fe 3.38, Co bal | C 0.32, Mn 0.99, Cr 25.0, Ni 19.0, Mo 4.48, Cb 2.3, Fe 2.4, Co bal | C 0.05–0.15, Mn 1.0–2.0, Cr 19.0–21.0, Ni 9.0–11.0, W 14.0–16.0, Fe 3.0, Si 1.0, Co bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.32 | 0.31 | 0.30 | 0.33 |
| Melting Temp, F | 2723 | 2350–2450 | 2350–2450 | 2425–2570 |
| Ther Cond (1300 F), Btu/hr/sq ft/°F/ft | — | 13.0 | — | 13 0 |
| Coef of Ther Exp (70–1800 F), per °F | $6.8 \times 10^{-6}$ | $8.3 \times 10^{-6}$ | $9.1 \times 10^{-6}$ | $9.4 \times 10^{-6}$ |
| Spec Ht (77–1300 F), Btu/lb/°F | — | 0.12 | — | 0.09 |
| Elec Res, microhm-cm | — | 93 (Aged) | — | 34.9 |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | | | | |
| Room Temp | $30 \times 10^6$ | $35 \times 10^6$ | $32 \times 10^6$ | $34\ 2 \times 10^6$ |
| 1200 F | — | $28.4 \times 10^6$ | — | $27.4 \times 10^6$ |
| 1500 F | — | $26.2 \times 10^6$ | — | $26.3 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Room Temp | 34.4 | 140 | 146 | 146 |
| 1500 F | — | 73 | 51 | 47 (1600 F) |
| 1800 F | — | 26 | 28 | 25 |
| 2000 F | — | 13 | — | 14 |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Room Temp | 20–43 | 70 | 67 | 67 |
| 1500 F | — | 40 | 38 | 35 (1600 F) |
| 1800 F | — | — | 27 | 25 |
| 2000 F | — | — | — | 12 |
| Elongation (in 2 in.), % | | | | |
| Room Temp | 0.4 | 35 | 55 | 64 |
| 1500 F | — | 22 | 8 | 30 (1600 F) |
| 1800 F | — | 20 | 16 | 35 |
| 2000 F | — | 24 | — | 26 |
| Fatigue Str ($10^8$ cycles), 1000 psi | | | | |
| 1200 F | — | 38 | — | 31 |
| 1800 F | — | — | — | 13 |
| Rupture Str (1500 F), 1000 psi | | | | |
| 10 Hr | — | 28 | 29 | 30 |
| 100 Hr | — | 24 | 23 | 22 |
| 1000 Hr | — | 18 | 18 | 18 |
| THERMAL TREATMENT | | | | |
| Solution Temp, F | — | 2150 (1 hr, w.q.) | 2250–2275 (1 hr, w.q.) | 2250 (a.c.) |
| Aging Temp, F | — | 1400 (12 hr, a.c.) | 1400 (16 hr, a.c.) | — |
| FABRICATING PROPERTIES | | | | |
| Hot Working Temp, F | 930–1100 | 2250–1800 | 2250–1800 | 2250–1850 |
| Machinability | Possible | 9[b] | — | 12[b] |
| Weldability | — | Good | Good | Good |
| CORROSION RESISTANCE | Excellent | Excellent | Excellent | Excellent |
| AVAILABLE FORMS | Rondelles, powders | Sheet, bar, billets, wire | Sheet, bar, billets, forgings, wire | Plate, sheet, bar, wire, tubing |
| USES | Alloy additions to steel cutting tools, magnets, etc.; also a coloring agent drier and catalyst | High temperature applications requiring strength and corrosion resistance | | |

[a] All properties are of as-cast material. [b] Based on AISI B1112 steel = 100.

## Cobalt-Base Superalloys

| Type ➡ | HS-21 | HS-31, X-40 | Nivco |
|---|---|---|---|
| COMPOSITION, % | C 0.20–0.30, Ni 1.75–3.75, Cr 25.5–29.0, Mo 5.0–6.0, Fe 2.0, Mn 1.0, Si 1.0, B 0.007, Co bal | C 0.45–0.55, Ni 9.5–11.5, Cr 24.5–26.5, Fe 2.0, Mn 1.0, Si 1.0, W 7.0–8.0, Co bal | C 0.02–0.05, Ni 21.5–23.5, Fe 1.0, Zr 0.90–1.20, Ti 1.55–1.95, Al 0.15–0.30, Mn 0.20–0.50, Si 0.10–0.25, Co bal |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.30 | 0.31 | 0.31 |
| Melting Temp, F | 2465 | — | 1600–1700 |
| Ther Cond (1100 F), Btu/hr/sq ft/°F/ft | 11.9 | 12.8 | 18.0 |
| Coef of Ther Exp (70–1500 F), per °F | $8.7 \times 10^{-6}$ | $9.2 \times 10^{-6}$ | $8.1 \times 10^{-6}$ |
| Elec Res (70 F), microhm-cm | 87.4 | — | 23.7 |
| MECHANICAL PROPERTIES[a] | | | |
| Mod of Elast in Tension, $10^6$ psi | | | |
| Room Temp | 36, 29 | —, 27 | 30 |
| 1200 F | —, 23 | —, 24 (1350 F) | 21 |
| Ten Str, 1000 psi | | | |
| Room Temp | 101, 125 | 108, 128 | 165 |
| 1000 F | 74, 94 | 80, — | 130 |
| 1200 F | 71, 85 | 76, 76 (1350 F) | 105 |
| 1600 F | 55, 42 | 34 (1700 F), 49 | — |
| Yld Str (0.2% offset), 1000 psi | | | |
| Room Temp | 82, 110 | 76, 113 | 110 |
| 1000 F | 39, 80 | 41, — | 90 |
| 1200 F | —, 71 | —, — | 75 |
| 1600 F | —, 33 | —, 36 | — |
| Elongation (in 1 in.), % | | | |
| Room Temp | 8.2, 1.7 | 9.0, 2.0 | 25 |
| 1000 F | 19.1,[b] 1.3[b] | 17.5, — | 27 |
| 1200 F | 16.0, 2.3[b] | 12.0, — | 20 |
| 1600 F | 23.0, 19.3[b] | 22 (1700 F), 14.3 | — |
| Hardness (room temp), Rockwell | C30, C38 | C34, C42[d] | C32–40 |
| Impact Str (Izod), ft-lb | | | |
| Room Temp | 10, 4[c] | 6, 4[c] | 31 |
| 1500 F | 27, 20[c] | 16, 9[c] | — |
| Fatigue Str ($10^8$ cycles), 1000 psi | | | |
| Room Temp | 35–40, — | —, — | 52 |
| 1200 F | —, — | 56, — | 49 |
| Rupture Str (1200 F), 1000 psi | | | |
| 10 Hr | 70, — | 61, — | 66 |
| 100 Hr | 52, 22 (1500 F) | 56, 29 (1500 F) | 54 |
| 1000 Hr | 42, 14 (1500 F) | 51, 24 (1500 F) | 43 |
| THERMAL TREATMENT | | | |
| Solution Temp, F | — | — | 1700–1900 |
| Aging Temp, F | 1350 (50 hr) | 1350 (50 hr) | 1150–1350 |
| AVAILABLE FORMS | Investment castings | Investment castings | Bars, billets, strip, sheet, plate, wire, forgings |
| USES | Where resistance to thermal shock is required, especially in jet engines | Turbine blades and wheels and other parts subject to high temperatures | Where high damping capacity at high temperature is required, e.g., compression blades, tool supports, precipitron wires, etc. |

[a] For HS-21 and HS-31 (X-40), the two values correspond to as-cast and as-cast and aged (50 hr at 1350 F); values for Nivco are for bar stock.
[b] In 2 in. [c] Aged 24 hr at 1350 F. [d] Aged 50 hr at 1475 F.

## Coppers—Wrought

| Type → | Electrolytic Tough Pitch Copper | Phosphorus Deoxidized Copper | Beryllium Copper | Oxygen-Free Copper | Chromium Copper |
|---|---|---|---|---|---|
| COMPOSITION, % | Cu 99.90 min, O about 0.04 | Cu 99.90 min, P 0.015–0.040 | Be 1.90–2.15, Co 0.20–0.35, Cu bal | Cu 99.92 | Cu 99.05, Cr 0.85, Si 0.10 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.321–0.323 | 0.323 | 0.296–0.298 | 0.323 | 0.321 |
| Melting Temp Range, F | 1949–1981 | 1981 | 1600–1800 | 1981 | 2147 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 226 | 196 | 100–110[a] | 226 | 187[a] |
| Coef of Ther Exp (68–572 F), per °F | $9.8 \times 10^{-6}$ | $9.8 \times 10^{-6}$ | $9.3 \times 10^{-6}$ | $9.8 \times 10^{-6}$ | $9.8 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.092 | 0.092 | 0.10[b] | 0.092 | — |
| Elec Res (68 F, annealed), microhm-cm | 1.71 | 2.03 | 4.82–5.82[a] | 1.71 | — |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $17 \times 10^6$ | $17 \times 10^6$ | $19 \times 10^6$ | $17 \times 10^6$ | — |
| Ten Str, 1000 psi[c] | | | | | |
| Annealed | 32, 35 | 32 | 60–80, 60–80[e] | 32, 35 | 35, 63[j] |
| Hard | 50, 55 | 50 | 165–185, 165–185[f] | 50, 55 | 62, 70[j] |
| Yld Str, 1000 psi[c,d] | | | | | |
| Annealed | 10 | 10 | 25–35, 20–30[e] | 10 | 15, 45[j] |
| Hard | 45 | 45 | 130–150, 150–170[f] | 45 | 55, 60[j] |
| Elong (in 2 in.), %[c] | | | | | |
| Annealed | 45, 35 | 45 | 35–50, 35–50[e] | 45, 35 | 40, 25[j] |
| Hard | 6, 1.5 | 10 | 3–12, 2–5[f] | 6, 1.5 | 12, 20[j] |
| Hardness (Rockwell) | | | | | |
| Annealed | F40 | F40 | B50–65[e] | F40 | F50, B65[j] |
| Hard | B50 | B50 | C36–41[f] | B50 | B60, B84[j] |
| Shear Str, 1000 psi[c] | | | | | |
| Annealed | 22, 24 | 22 | 50–60[e] | 22, 24 | — |
| Hard | 28, 29 | 28 | 90–100[f] | 28, 29 | — |
| Endurance Limit ($10^8$ cycles), 1000 psi[c] | | | | | |
| Annealed | 11 | — | 30–35, 12–20[e,g] | 11 | — |
| Hard | 13 | 19 | 35–40, 120–140[f,g] | 13 | — |
| FABRICATING PROPERTIES | | | | | |
| Cold Workability | Excellent | Excellent | Good | Excellent | Good |
| Hot Workability | Excellent | Excellent | Excellent | Excellent | Good |
| Hot Working Temp, F | 1400–1600 | 1400–1600 | 1050–1475 | 1400–1600 | 1650–1695 |
| Annealing Temp, F | 700–1200 | 700–1200 | 1400–1475 | 700–1200 | — |
| Machinability Index[b] | 20 | 20 | 20 | 20 | 20 |
| Joining | | | | | |
| Soft Soldering | Excellent | Excellent | Excellent | Excellent | Excellent |
| Silver Alloy Brazing | Good | Excellent | Good | Excellent | Excellent |
| Oxyacetylene Welding | Poor | Good | Poor | Good | — |
| Carbon Arc Welding | Fair | Fair | Excellent | Good | — |
| Butt Resistance Welding | Good | Good | Excellent | Good | — |
| CORROSION RESISTANCE | Generally good resistance to industrial, rural and marine atmospheres; also gasolines, fuel oils and lacquers. Generally poor resistance to ammonia, ferric and ammonium compounds, and cyanides. Good resistance to weak acids and bases; some resistance to strong acids and bases | | | | |
| AVAILABLE FORMS | Flat products, rod, wire, tube, pipe, shapes | Flat products, tube, pipe, rod, shapes | Flat products, rod, wire, tube, pipe, shapes | | Flat products, wire, rod, shapes, simple forgings |
| USES | Architectural trim; automobile radiators; electrical contacts, conductors and switches; ball floats; rivets; chemical process equipment | Plumbing and gas lines; heat exchanger tubes; air, water, gasoline and oil lines; rotating bands | Instrument and valve springs, plunger guides, bushings, bearings, cams, diaphragms, bellows, electrical contacts, resistance welding electrodes | Bus bars and connectors, wave guides, copper-to-glass seals in electronic appliances | Resistance welding electrode tips and wheels, circuit breaker parts, cable connectors, parts for electronic devices |

[a] Heat treated.
[b] 86–212 F.
[c] Where two values or ranges appear, second is for wire unless otherwise indicated.
[d] 0.5% extension under load except beryllium copper (0.2% offset).
[e] Solution annealed.
[f] Annealed and heat treated 2–3 hr at 600 F.
[g] Proportional limit.
[h] Based on free-cutting brass = 100.
[j] Heat treated rod: solution annealed ½ hr at 1830 F, quenched, precipitation heat treated 3 hr at 840 F.

## Coppers and Plain Brasses—Wrought

| Type → | Zirconium Copper | Sulfur Copper | Tellurium Copper | Gilding, 95% | Commercial Bronze, 90% |
|---|---|---|---|---|---|
| COMPOSITION, % | Zr 0.12, Cu bal | S 0.30, Cu bal | Te 0.50, Cu bal | Cu 95.0, Zn 5 | Cu 90.0, Zn 10.0 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.323 | 0.323 | 0.323 | 0.320 | 0.318 |
| Melting Temp Range, F | 1976 | 1980 | 1980 | 1920–1950 | 1870–1910 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | — | 216 | 209 | 135 | 109 |
| Coef of Ther Exp (68–572 F), per °F | — | $9.8 \times 10^{-6}$ | $9.8 \times 10^{-6}$ | $10.0 \times 10^{-6}$ | $10.2 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | — | 0.09 | 0.09 | 0.09 | 0.09 |
| Elec Res (68 F, annealed), microhm-cm | 1.99 | 1.78 | 1.91 | 3.1 | 3.9 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | — | — | $16 \times 10^6$ | $17 \times 10^6$ | $17 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed | — | 34 | — | 34 | 37 |
| Hard | 56–80[b] | 50[c] | 48[c] | 56 | 61 |
| Yld Str (0.5% ext), 1000 psi | | | | | |
| Annealed | — | 10 | — | 10 | 10 |
| Hard | 48–75[b] | 48[c] | 44[c] | 50 | 54 |
| Elong (in 2 in.), % | | | | | |
| Annealed | — | 42 | — | 45 | 45 |
| Hard | 25–5[b] | 12[c] | 12[c] | 5 | 5 |
| Hardness (Rockwell) | | | | | |
| Annealed | — | — | — | F46 | F53 |
| Hard | B69–75[b] | B45[c] | B45[c] | B64 | B70 |
| Shear Str, 1000 psi | | | | | |
| Annealed | — | — | — | 26 | 28 |
| Hard | — | — | — | 37 | 38 |
| FABRICATING PROPERTIES | | | | | |
| Cold Workability | Excellent | Excellent | Good | Excellent | Excellent |
| Hot Workability | — | Excellent | Good | Good | Good |
| Hot Working Temp, F | — | 1400–1600 | 1400–1550 | 1400–1600 | 1400–1600 |
| Annealing Temp, F | — | 800–1200 | 800–1200 | 800–1450 | 800–1450 |
| Machinability Index[a] | 20 | 90 | 90 | 20 | 20 |
| Joining | | | | | |
| Soft Soldering | — | Excellent | Good | Excellent | Excellent |
| Silver Alloy Brazing | — | Excellent | Good | Excellent | Excellent |
| Oxyacetylene Welding | — | Fair | Fair | Good | Good |
| Carbon Arc Welding | — | Fair | Fair | Fair | Fair |
| Butt Resistance Welding | — | Good | Good | Good | Good |
| CORROSION RESISTANCE | Generally good resistance to industrial, rural and marine atmospheres; also gasolines, fuel oils and lacquers. Generally poor resistance to ammonia, ferric and ammonium compounds, and cyanides. Good resistance to weak acids and bases; some resistance to strong acids and bases | | | | |
| AVAILABLE FORMS | Rod, wire | Rod | Rod | Rolled strip, wire | Rolled strip, sheet, wire, tube, plate, rod |
| USES | Commutator segments, slip rings, soldering iron tips, rectifier bases, resistance welding wheel electrodes, orifice for reaction motors | Electric and electronic parts, welding torch tips, soldering tips, screw machine parts requiring high conductivity | Torch tips, soldering iron tips, electrical connectors, screw machine products requiring high conductivity | Coins, bullet jackets, fuse caps, primers, jewelry, base for gold plate or vitreous enamel | Grillwork, cosmetic compacts, marine hardware, primer caps, costume jewelry, base for vitreous enamel |

[a] Based on free-cutting brass = 100. [b] Range covers properties obtainable by varying amounts of cold work. [c] Half-hard.

*continued on next page*

## Plain Brasses—Wrought

| Type → | Red Brass, 85% | Low Brass, 80% | Cartridge Brass, 70% | Yellow Brass | Muntz Metal |
|---|---|---|---|---|---|
| COMPOSITION, % | Cu 85, Zn 15 | Cu 80, Zn 20 | Cu 70, Zn 30 | Cu 65, Zn 35 | Cu 60, Zn 40 |
| **PHYSICAL PROPERTIES** | | | | | |
| Density, lb/cu in. | 0.316 | 0.313 | 0.308 | 0.306 | 0.303 |
| Melting Temp Range, F | 1810–1880 | 1770–1830 | 1680–1750 | 1660–1710 | 1650–1660 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 92 | 81 | 70 | 67 | 71 |
| Coef of Ther Exp (68–572 F), per °F | 10.4 x $10^{-6}$ | 10.6 x $10^{-6}$ | 11.1 x $10^{-6}$ | 11.3 x $10^{-6}$ | 11.6 x $10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.09 | 0.09 | 0.09 | 0.09 | 0.09 |
| Elec Res (68 F, annealed), microhm-cm | 4.7 | 5.4 | 6.2 | 6.4 | 6.2 |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, psi | 17 x $10^6$ | 16 x $10^6$ | 16 x $10^6$ | 15 x $10^6$ | 15 x $10^6$ |
| Ten Str, 1000 psi[a] | | | | | |
| Annealed | 39, 41 | 42, 44 | 44, 48 | 46, 50 | 54 |
| Hard | 70, 88 | 74, 107 | 76 | 74, 110 | — |
| Yld Str, 1000 psi[a,d] | | | | | |
| Annealed | 10 | 12 | 11 | 14 | 21 |
| Hard | 57 | 59 | 63 | 60 | — |
| Elong (in 2 in.), %[a] | | | | | |
| Annealed | 48, 48 | 52, 55 | 66, 64 | 65, 60 | 45 |
| Hard | 5, 6 | 7, 5 | 8 | 8, 8 | — |
| Hardness (Rockwell) | | | | | |
| Annealed | F56 | F57 | F54 | F58 | F80 |
| Hard | B77 | B82 | B82 | B80 | — |
| Shear Str, 1000 psi[a] | | | | | |
| Annealed | 31, 31 | 32, 32 | — | 32, 34 | 40 |
| Hard | 42, 48 | 43, 53 | 44 | 43, 55 | — |
| Endur Limit ($10^8$ cycles), 1000 psi[a] | | | | | |
| Annealed | 10.5 | 14 | 13 | 12 | — |
| Hard | 21, 29 | 22, 23 | 21 | 14 | — |
| **FABRICATING PROPERTIES** | | | | | |
| Cold Workability | Excellent | Excellent | Excellent | Excellent | Fair |
| Hot Workability | Good | Fair | Fair | Poor | Excellent |
| Hot Working Temp, F | 1450–1650 | 1500–1650 | 1350–1550 | — | 1150–1450 |
| Annealing Temp, F | 800–1350 | 800–1300 | 800–1400 | 800–1300 | 800–1100 |
| Machinability Index[j] | 30 | 30 | 30 | 30 | 40 |
| Joining | | | | | |
| Soft Soldering | Excellent | Excellent | Excellent | Excellent | Excellent |
| Silver Alloy Brazing | Excellent | Excellent | Excellent | Excellent | Excellent |
| Oxyacetylene Welding | Good | Good | Good | Good | Good |
| Butt Resistance Welding | Good | Good | Good | Good | Good |
| **CORROSION RESISTANCE** | Generally good resistance to industrial, rural and marine atmospheres; also gasolines, fuel oils and lacquers. Generally poor resistance to ammonia, ferric and ammonium compounds, and cyanides | | | | |
| | Good res to weak acids and bases; some res to strong acids and bases. Highly res to dezincification or stress-corrosion cracking | Susceptible to dezincification and stress corrosion cracking | | | |
| | | Good res to weak bases; some res to strong bases and weak acids; poor res to strong acids | Some resistance to weak acids and bases; poor resistance to strong acids and bases. Good resistance to sulfides. Poor resistance to soft and high salinity water | | |
| **AVAILABLE FORMS** | Rolled strip, sheet, wire, tube, pipe | Wire, rolled strip and flat wire | Rolled strip and bar, flat wire, sheet, rod, wire, tube | Rolled strip and flat wire, drawn flat wire, sheet, plate, rod, wire | Rolled strip and bar, sheet, plate, rod, tube |
| **USES** | Weatherstrip, electrical sockets, fasteners, heat exchanger tubes, flexible hose, plumbing, jewelry | Ornamental metal work, battery caps, musical instruments, clock dials, pump lines | Automotive radiator cores and tanks, lamp fixtures, fasteners, springs, ammunition components | Grillwork, reflectors, lamp fixtures, fasteners, stencils, plumbing accessories, springs | Architectural trim, large nuts and bolts, condenser plates, hot forgings, valve stems |

[a]Where two values appear, second is for wire. [d]0.5% extension under load. [j]Based on free-cutting brass = 100.

## Tin and Aluminum Brasses—Wrought

| Type → | Admiralty | Naval Brass | Leaded Naval Brass | Manganese Bronze (A) | Aluminum Brass |
|---|---|---|---|---|---|
| COMPOSITION, % | Cu 71, Sn 1, Zn 28 | Cu 60, Sn 0.75, Zn 39.25 | Cu 60, Pb 1.75, Sn 0.75, Zn 37.5 | Cu 58.5, Fe 1.4, Sn 1, Mn 0.1, Zn 39 | Cu 76, Al 2, Zn 22 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.308 | 0.304 | 0.305 | 0.302 | 0.301 |
| Melting Temp Range, F | 1650–1720 | 1630–1650 | 1630–1650 | 1590–1630 | 1710–1780 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 64 | 67 | 67 | 61 | 58 |
| Coef of Ther Exp (68–572 F), per °F | $11.2 \times 10^{-6}$ | $11.8 \times 10^{-6}$ | $11.8 \times 10^{-6}$ | $11.8 \times 10^{-6}$ | $10.3 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.09 | 0.09 | 0.09 | 0.09 | 0.09 |
| Elec Res (68 F, annealed), microhm-cm | 6.9 | 6.6 | 6.6 | 7.2 | 7.5 |
| MECHANICAL PROPERTIES[a] | | | | | |
| Mod of Elast in Tension, psi | $16 \times 10^6$ | $15 \times 10^6$ | $15 \times 10^6$ | $15 \times 10^6$ | $16 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed[b] | 53 | 57 | 57 | 65 | 60 |
| Quarter Hard | — | 69 | 69 | 77 | — |
| Half Hard | — | 75 | 75 | 84 | — |
| Yld Str, 1000 psi[b] | | | | | |
| Annealed | 22 | 25 | 25 | 30 | 27 |
| Quarter Hard | — | 46 | 46 | 45 | — |
| Half Hard | — | 53 | 53 | 60 | — |
| Elong (in 2 in.), % | | | | | |
| Annealed | 65 | 47 | 40 | 33 | 55 |
| Quarter Hard | — | 27 | 20 | 23 | — |
| Half Hard | — | 20 | 15 | 19 | — |
| Hardness (Rockwell) | | | | | |
| Annealed | F75 | B55 | B55 | B65 | F77 |
| Quarter Hard | — | B78 | B78 | B83 | — |
| Half Hard | — | B82 | B82 | B90 | — |
| Shear Str, 1000 psi | | | | | |
| Annealed | — | 40 | 36 | 42 | — |
| Quarter Hard | — | 43 | 39 | 47 | — |
| Half Hard | — | 44 | 40 | 48 | — |
| FABRICATING PROPERTIES | | | | | |
| Cold Workability | Excellent | Fair | Poor | Poor | Excellent |
| Hot Workability | Fair | Excellent | Good | Excellent | Fair |
| Annealing Temp, F | 800–1100 | 800–1100 | 800–1100 | 800–1100 | 800–1100 |
| Machinability Index[c] | 30 | 30 | 70 | 30 | 30 |
| Joining | | | | | |
| Soft Soldering | Excellent | Excellent | Excellent | Excellent | Fair |
| Silver Alloy Brazing | Excellent | Excellent | Good | Excellent | Good |
| Oxyacetylene Welding | Fair | Good | Fair | Good | Fair |
| Butt Resistance Welding | Good | Good | Fair | Good | Good |
| CORROSION RESISTANCE | Good resistance to industrial, rural and marine atmospheres; petroleum products, alcohols, dry gases and sea water. Fairly good resistance to weak bases. Resistance to some weak bases and weak organic acids, but generally poor resistance to most acids and strong bases. Poor resistance to solutions of cyanides and ammonium compounds. Resistant to dezincification (especially Admiralty and Aluminum Brasses) | | | | |
| AVAILABLE FORMS | Plate, wire, tube | Rolled strip, rolled and drawn bar, plate, rod, tube, shapes | Drawn bar, rod, shapes | Rod, shapes | Tube |
| USES | Condenser, evaporator and heat exchanger tubes; condenser tube plates; distiller tubes; ferrules | Aircraft turnbuckle barrels, balls, bolts, marine hardware, nuts, propeller shafts, rivets, valve stems, condenser plates, welding rods | Marine hardware, screw machine products, valve stems | Clutch disks, pump rods, shafting, balls, valve stems and bodies, welding rods | Condenser, evaporator and heat exchanger tubes, distiller tubes, ferrules |

[a] Mechanical properties are based on 1-in. dia. Values for Admiralty and Aluminum Brasses apply to tube; other values apply to rod.
[b] 0.5% extension under load. [c] Based on free-cutting brass = 100.

## Leaded Brasses—Wrought

| Type → | Leaded Commercial Bronze | Low-Leaded Brass | Medium-Leaded Brass | High-Leaded Brass | Extra-High-Leaded Brass |
|---|---|---|---|---|---|
| COMPOSITION, % | Cu 89.0, Pb 1.75, Zn 9.25 | Cu 65.0, Pb 0.5, Zn 34.5 | Cu 65.0, Pb 1.0, Zn 34.0 | Cu 65.0, Pb 2.0, Zn 33.0 | Cu 63.0, Pb 2.5, Zn 34.5 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.319 | 0.306 | 0.306 | 0.306 | 0.307 |
| Melting Temp Range, F | 1850–1900 | 1650–1700 | 1630–1700 | 1630–1670 | 1630–1660 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 104 | 67 | 67 | 67 | 67 |
| Coef of Ther Exp (68–572 F), per °F | $10.2 \times 10^{-6}$ | $11.3 \times 10^{-6}$ | $11.3 \times 10^{-6}$ | $11.3 \times 10^{-6}$ | $11.4 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.09 | 0.09 | 0.09 | 0.09 | 0.09 |
| Elec Res (68 F, annealed), microhm-cm | 4.1 | 6.6 | 6.6 | 6.6 | 6.6 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $17 \times 10^6$ | $15 \times 10^6$ | $15 \times 10^6$ | $15 \times 10^6$ | $14 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed | — | 51 | 51 | 49 | 49 |
| Hard | 55[b] | 74 | 74 | 74 | 74 |
| Yld Str (0.5% ext), 1000 psi | | | | | |
| Annealed | — | 19 | 19 | 17 | 17 |
| Hard | 50[b] | 60 | 60 | 60 | 60 |
| Elong (in 2 in.), % | | | | | |
| Annealed | — | 55 | 53 | 52 | 50 |
| Hard | 12[b] | 8 | 7 | 7 | 7 |
| Hardness (Rockwell) | | | | | |
| Annealed | — | F72 | F72 | F68 | F68 |
| Hard | B61[b] | B80 | B80 | B80 | B80 |
| Shear Str, 1000 psi | | | | | |
| Annealed | — | 34 | 34 | 34 | — |
| Hard | 31[b] | 43 | 43 | 43 | — |
| FABRICATING PROPERTIES | | | | | |
| Cold Workability | Good | Good | Good | Fair | Poor |
| Hot Workability | Poor | Poor | Poor | Poor | Fair |
| Hot Working Temp, F | — | — | — | — | 1300–1450 |
| Annealing Temp, F | 800–1200 | 800–1300 | 800–1200 | 800–1100 | 800–1100 |
| Machinability Index[a] | 80 | 60 | 70 | 90 | 100 |
| Joining | | | | | |
| Soft Soldering | Excellent | Excellent | Excellent | Excellent | Excellent |
| Silver Alloy Brazing | Good | Good | Good | Good | Good |
| Oxyacetylene Welding | Not Rec | Fair | Not Rec | Not Rec | Not Rec |
| Butt Resistance Welding | Good | Good | Good | Good | Good |
| CORROSION RESISTANCE | Excellent resistance to pure hydrocarbons, lacquers and freon; good resistance to industrial, marine and rural atmospheres, alcohols, fuel oils and dry carbon dioxide; fair resistance to sea water, crude oils, and moist carbon dioxide; attacked by ammonium hydroxide and hydrochloric and sulfuric acids | | | | |
| AVAILABLE FORMS | Bar, rod | Strip, bar, plate[c] | Strip, bar, plate, rod, wire | Strip, bar, plate, rod[d] | Strip, bar, plate, rod |
| USES | Screws, screw machine parts, pickling crates | Butts, hinge brass, watch backs | Butts, gears, nuts, rivets, screws, dials, engravings, instrument plates | Clock plates, nuts, backs, gears, wheels | |

[a] Based on free-cutting brass = 100. [b] Half-hard.
[c] Low-leaded brass tube is also available which has approximately the same properties and is used for plumbing accessories and pumps.
[d] High-leaded brass tube is also available with approximately the same properties and is used for general purpose screw machine parts.

## Leaded Brasses—Wrought

| Type → | Free-Cutting Brass | Leaded Muntz Metal | Free-Cutting Muntz Metal | Forging Brass | Architectural Bronze |
|---|---|---|---|---|---|
| COMPOSITION, % | Cu 61.5, Pb 3.0, Zn 35.5 | Cu 60.0, Pb 0.6, Zn 39.4 | Cu 60.0, Pb 1.0, Zn 39.0 | Cu 59.0, Pb 2.0, Zn 39.0 | Cu 57.0, Pb 3.0, Zn 40.0 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.307 | 0.304 | 0.304 | 0.305 | 0.306 |
| Melting Temp Range, F | 1630–1650 | 1630–1650 | 1630–1650 | 1620–1640 | 1610–1630 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 67 | 71 | 69 | 69 | 71 |
| Coef of Ther Exp (68–572 F), per °F | $11.4 \times 10^{-6}$ | $11.6 \times 10^{-6}$ | $11.6 \times 10^{-6}$ | $11.5 \times 10^{-6}$ | $11.6 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.09 | 0.09 | 0.09 | 0.09 | 0.09 |
| Elec Res (68 F, annealed), microhm-cm | 6.6 | 6.2 | 6.4 | 6.4 | 6.2 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $14 \times 10^6$ | $15 \times 10^6$ | $15 \times 10^6$ | $15 \times 10^6$ | $14 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed | 49 | 54[c] | 54 | 52[d] | 60[d] |
| Hard | 68[b] | — | 80 | — | — |
| Yld Str (0.5% ext), 1000 psi | | | | | |
| Annealed | 18 | 20[c] | 20 | 20[d] | 20[d] |
| Hard | 52[b] | — | 60 | — | — |
| Elong (in 2 in.), % | | | | | |
| Annealed | 53 | 45[c] | 40 | 45[d] | 30[d] |
| Hard | 18[b] | — | 6 | — | — |
| Hardness (Rockwell) | | | | | |
| Annealed | F68 | F80[c] | F80 | F78[d] | B65[d] |
| Hard | B80[b] | — | B85 | — | — |
| Shear Str, 1000 psi | | | | | |
| Annealed | 30 | 40[c] | — | — | 35[d] |
| Hard | 38[b] | — | — | — | — |
| FABRICATING PROPERTIES | | | | | |
| Cold Workability | Poor | Fair | Fair | Poor | Poor |
| Hot Workability | Fair | Excellent | Excellent | Excellent | Excellent |
| Hot Working Temp, F | 1300–1450 | 1150–1450 | 1150–1450 | 1200–1500 | 1150–1350 |
| Annealing Temp, F | 800–1100 | 800–1100 | 800–1100 | 800–1100 | 800–1100 |
| Machinability Index[a] | 100 | 60 | 70 | 80 | 90 |
| Joining | | | | | |
| Soft Soldering | Excellent | Excellent | Excellent | Excellent | Excellent |
| Silver Alloy Brazing | Good | Good | Good | Good | Good |
| Oxyacetylene Welding | Not Rec | Fair | Not Rec | Not Rec | Not Rec |
| Butt Resistance Welding | Good | Good | Good | Good | Good |
| CORROSION RESISTANCE | Excellent resistance to pure hydrocarbons, fluorinated hydrocarbon refrigerants and lacquers; good resistance to industrial, marine and rural atmospheres, alcohols, fuel oils and dry carbon dioxide; fair resistance to sea water, crude oils, and moist carbon dioxide; attacked by ammonium hydroxide and hydrochloric and sulfuric acids | | | | |
| AVAILABLE FORMS | Bar, rod, shapes | Plate | Tube | Rod, shapes | Rod, shapes |
| USES | Gears, pinions, high speed screw machine parts | Condenser tube plates | Automatic screw machine parts | Forgings and pressings of all kinds | Architectural extrusions, store fronts, trim, hinges, lock bodies, forgings |

[a] Based on free-cutting brass = 100. [b] Half-hard. [c] As hot rolled. [d] As extruded.

## Phosphor Bronzes—Wrought

| Type → | Phosphor Bronze, 5% (Grade A) | Phosphor Bronze, 8% (Grade C) | Phosphor Bronze, 10% (Grade D) | Phosphor Bronze, 1.25% (Grade E) | Phosphor Bronze (Free-Cutting) |
|---|---|---|---|---|---|
| COMPOSITION, % | Cu 95, Sn 5 | Cu 92, Sn 8 | Cu 90, Sn 10 | Cu 98.75, Sn 1.25, P trace | Cu 88, Pb 4, Zn 4, Sn 4 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.320 | 0.318 | 0.317 | 0.321 | 0.321 |
| Melting Temp Range, F | 1750–1920 | 1620–1880 | 1550–1830 | 1900–1970 | 1700–1830 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 40 | 36 | 29 | 120 | 50 |
| Coef of Ther Exp (68–572 F), per °F | $9.9 \times 10^{-6}$ | $10.1 \times 10^{-6}$ | $10.2 \times 10^{-6}$ | $9.9 \times 10^{-6}$ | $9.6 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.09 | 0.09 | 0.09 | 0.09 | 0.09 |
| Elec Res (68 F, annealed), microhm-cm | 9.6 | 13 | 16 | 3.6 | 9.1 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $16 \times 10^6$ | $16 \times 10^6$ | $16 \times 10^6$ | $17 \times 10^6$ | $15 \times 10^6$ |
| Ten Str, 1000 psi[a] | | | | | |
| Annealed | 47, 50 | 55, 60 | 66, 66 | 40, — | 44, — |
| Half Hard | 68, 85 | 76, 105 | 83, 118 | 55, — | 58, — |
| Hard | 81, 110 | 93, 130 | 100, 147 | 65, 76 | — |
| Spring | 100, 140 | 112, — | 122, — | 75, — | — |
| Extra Spring | 107, — | 120, — | 128, — | —, — | — |
| Yld Str, 1000 psi[b] | | | | | |
| Annealed | 19, 20 | 24 | 28 | 14 | 19 |
| Half Hard | 55, 80 | 55 | — | — | 40 |
| Hard | 75 | 72 | — | 50 | — |
| Elong (in 2 in.), % | | | | | |
| Annealed | 64, 58 | 70, 65 | 68 | 48 | 50 |
| Half Hard | 28, 8 | 32 | 32 | 16 | 24 |
| Hard | 10 | 10 | 13 | 8 | — |
| Spring | 4 | 3 | 4 | 4 | — |
| Extra Spring | 3 | 2 | 3 | — | — |
| Hardness (Rockwell) | | | | | |
| Annealed | B26 | F75 | B55 | — | F65 |
| Half Hard | B78 | B84 | B92 | B64 | B68 |
| Hard | B87 | B93 | B97 | B75 | — |
| Spring | B95 | B98 | B101 | B79 | — |
| Extra Spring | B97 | B100 | B103 | — | — |
| FABRICATING PROPERTIES | | | | | |
| Cold Workability | Excellent | Good | Good | Excellent | Good |
| Hot Workability | Poor | Poor | Poor | Good (1450–1600 F) | — |
| Annealing Temp, F | 900–1250 | 900–1250 | 900–1250 | 900–1200 | 900–1250 |
| Machinability Index[c] | 20 | 20 | 20 | 20 | 80 |
| Joining | | | | | |
| Soft Soldering | Excellent | Excellent | Excellent | Excellent | Excellent |
| Silver Alloy Brazing | Excellent | Excellent | Good | Excellent | Excellent |
| Oxyacetylene Welding | Fair | Fair | Good | Good | Not rec |
| Butt Resistance Welding | Excellent | Excellent | Excellent | Excellent | Good |
| CORROSION RESISTANCE | Generally good resistance to atmosphere, water and salt water, and salt solutions. Some resistance to alkaline solutions and inorganic acids. Poor resistance to organic acids, cyanides, and ferric and ammonium compounds | | | | |
| AVAILABLE FORMS | Rolled strip, rolled flat wire, rod, wire, tube | Rolled strip, rod, wire | | Rolled strip, wire | Rolled strip, rod, shapes |
| USES | Bridge bearing plates, chemical hardware, perforated sheets, textile machinery, welding rods, beater bars, bellows, clutch disks, cotter pins, diaphragms, fuse clips, fasteners, lock washers, sleeve bushings, springs, switch parts, truss wire, wire brushes | | Heavy bars and plates for severe compression, good wear and corrosion resistance. Bridge and expansion plates | Electrical contacts, flexible hose, pole-line hardware | Bearings, bushings, gears, pinions, shafts, thrust washers, valve parts |

[a] Two values are for flat products and wire, respectively. [b] 0.5% extension under load. [c] Based on free-cutting brass = 100.

## Silicon Bronzes

| Type → | High Silicon Bronze (A) | Low Silicon Bronze (B) | Aluminum Silicon Bronze | Precipitation Hardenable Silicon Bronze [a] |
|---|---|---|---|---|
| COMPOSITION, % | Cu 94.8 min, Si 2.8–3.8, Mn 1.5 max, Zn 1.5 max, Fe 1.6 max, Ni 0.6 max | Cu 96.0 min, Si 0.8–2.0[e], Mn 0.7 max, Fe 0.8 max | Cu 89.0 min, Al 6.5–8.0, Si 1.5–3.0 | Cu 97.5, Ni 1.9, Si 0.6 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.308 | 0.316 | 0.278 | 0.322 |
| Melting Temp Range, F | 1880–1780 | 1940–1890 | 1840[f] | 1990[f] |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 20 | 31 | 26 | — |
| Coef of Ther Exp (68–572 F), per °F | $10.0 \times 10^{-6}$ | $9.9 \times 10^{-6}$ | $10.0 \times 10^{-6}$ | $9.8 \times 10^{-6}$ |
| Specific Heat, Btu/lb/F | 0.09 | 0.09 | 0.09 | — |
| Elec Cond, % IACS | 7 | 12 | 7 | 36[h] |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | $15 \times 10^6$ | $17 \times 10^6$ | $16 \times 10^6$ | $18 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Annealed Strip, Rod[b] | 56–63 | 40[d] | 85–90[d] | 65[d] |
| Hardened Rod | 92 | 70 | 90 | 100 |
| Yield Strength (0.5% ext), 1000 psi | | | | |
| Annealed Strip, Rod[b] | 20–30 | 15[d] | 44–60[d] | 60[d] |
| Hardened Rod | 55 | 55 | 50 | 88[d] |
| Elongation (in 2 in.), % | | | | |
| Annealed Strip, Rod[b] | 55–63 | 50[d] | 20–30[d] | 20[i] |
| Hardened Rod | 22 | 15 | 40 | 22[d] |
| Hardness (Rockwell) | | | | |
| Annealed Strip, Rod[b] | B35–66 | F55–60 | B74–90[d] | — |
| Hardened Rod | B90 | B80 | B92 | B90[d] |
| Impact Strength (Izod, annealed strip, rod), ft-lb[b] | 60–70[d] | 60–70[d] | 17[d] | — |
| Shear Strength (annealed strip, rod), 1000 psi[b] | 42–45 | — | 45[d] | — |
| FABRICATING PROPERTIES | | | | |
| Cold Workability | Excellent | Excellent | Poor | Excellent |
| Hot Workability | Excellent | Excellent | Excellent | Excellent |
| Hot Working Temp Range, F | 1300–1600 | 1300–1600 | 1300–1600 | 1300–1700 |
| Annealing Temp, F | 900–1300 | 900–1250 | 1100–1125 | 850–1450 |
| Machinability Index[c] | 30 | 30 | 60 | 40 |
| Joining | | | | |
| Soft Soldering | Good | Good | Not recommended[g] | Excellent |
| Silver Alloy Brazing | Excellent | Excellent | Fair | Excellent |
| Oxyacetylene Welding | Excellent | Excellent | Poor | Excellent |
| Carbon Arc Welding | Excellent | Excellent | Fair | Excellent |
| Gas Shielded Arc Welding | Excellent | Excellent | Fair | Excellent |
| Resistance Welding | Excellent | Good | Fair | Excellent |
| CORROSION RESISTANCE | Excellent resistance to marine, industrial and rural atmospheres; most types of fresh and sea water; hot and cold dilute sulfuric, cold concentrated sulfuric, cold dilute hydrochloric, and most organic acids; hot and cold dilute alkalis and cold concentrated alkalis; chlorides and sulfates of light metals. Attacked by oxidizing acids and ammonium hydroxide; poor resistance to chlorides and sulfates of heavy metals | | | |
| AVAILABLE FORMS | Sheet, strip, plate, rod, wire, pipe, tube | | Forgings, pressings | Rod, wire, sheet |
| USES | Welded unfired hot water storage heaters, heat exchangers, signs, hot headed fasteners, cast fittings, seamless tube or pipe, clutch disks | Cold headed cap and machine screws, wire and cable connectors, pole line hardware, marine hardware, valve components, tubing | Hot forged or pressed valve components, welding equipment, aircraft compression fittings, gears and pinions, large nuts and bolts | High strength mechanical fasteners; electrical, marine and chemical processing hardware. Sheet used for springs, sockets, etc. requiring high strength |

[a] Properties of hardened material obtained by precipitation hardening 90 min at 700-850 F.
[b] Varies with grain size.
[c] Based on free-cutting brass = 100.
[d] Rod only.
[e] An alloy containing up to 2.6% Si is acceptable if the sum of all elements excepting Cu and Si is less than 0.3%.
[f] Solidus temperature not available.
[g] Can be soldered with special techniques.
[h] In fully heat treated condition.
[i] Elongation in 4D.

## Nickel Silvers—Wrought

| Type → | 65-18 | 65-12 | 65-15 | 65-10 | 55-18 |
|---|---|---|---|---|---|
| COMPOSITION, % | Cu 65, Ni 18, Zn 17 | Cu 65, Ni 12, Zn 23 | Cu 65, Ni 15, Zn 20 | Cu 65, Ni 10, Zn 25 | Cu 55, Ni 18, Zn 27 |
| PHYSICAL PROPERTIES | | | | | |
| Density (68 F), lb/cu in. | 0.316 | 0.314 | 0.314 | 0.313 | 0.314 |
| Melting Temp Range, F | 1960–2030 | 1900 | 1970 | 1870 | 1930 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 19 | 23 | 21 | 26 | 17 |
| Coef of Ther Exp (68–572 F), per °F | $9.0 \times 10^{-6}$ | $9.0 \times 10^{-6}$ | $9.0 \times 10^{-6}$ | $9.1 \times 10^{-6}$ | $9.3 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.09 | 0.09 | 0.09 | 0.09 | 0.09 |
| Elec Cond (68 F), % IACS | 6 | 8 | 7 | 9 | 5.5 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $18 \times 10^6$ | $18 \times 10^6$ | $18 \times 10^6$ | $17.5 \times 10^6$ | $18 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed | 56–60 | 52–61 | 53–61 | 49–63 | 60 |
| Half Hard | 70–86 | 73 | 74 | 73–85 | — |
| Hard | 85–103 | 85 | 85 | 86–105 | 100 |
| Extra Hard | — | 93 | 92 | 95–120 | 108 |
| Yld Str, 1000 psi[a] | | | | | |
| Annealed | 25–30 | 18–28 | 18–28 | 18–28 | 27 |
| Half Hard | 60–80 | 60 | 62 | 60 | — |
| Hard | 74–90 | 75 | 75 | 75 | 85 |
| Extra Hard | — | 79 | 79 | 76 | 90 |
| Elong (in 2 in.), % | | | | | |
| Annealed | 32–45 | 35–48 | 34–43 | 35–50 | 40 |
| Half Hard | 7–20 | 11 | 10 | 7–12 | — |
| Hard | 3 | 4 | 3 | 4–5 | 3 |
| Extra Hard | — | 2 | 2 | 3 | 2.5 |
| Hardness (Rockwell) | | | | | |
| Annealed | B40–55 | B22–55 | B22–55 | B22–52 | B55 |
| Half Hard | B78–83 | B80 | B80 | B80 | — |
| Hard | B87 | B89 | B87 | B89 | B91 |
| Extra Hard | — | B92 | B90 | B92 | B96 |
| Shear Str, 1000 psi | | | | | |
| Annealed | — | 41 | 41 | 41 | — |
| Half Hard | — | 47 | 47 | 50 | — |
| Hard | — | 52 | 52 | 55 | — |
| Extra Hard | — | 56 | 54 | 59 | — |
| FABRICATING PROPERTIES | | | | | |
| Cold Workability | Excellent | Excellent | Excellent | Excellent | Good |
| Hot Workability | Poor | Poor | Poor | Poor | Poor |
| Annealing Temp, F | 1100–1500 | 1100–1500 | 1100–1500 | 1100–1400 | 1100–1500 |
| Machinability Index[b] | 20 | 20 | 20 | 20 | 30 |
| Joining | Soldering, excellent; silver alloy brazing, excellent; carbon arc welding, fair; butt resistance welding, good; oxyacetylene welding, good | | | | |
| CORROSION RESISTANCE | Attacked rapidly by oxidizing acids. Resistant to sodium and potassium hydroxide but attacked rapidly by ammonium hydroxide and moist ammonia. Good resistance to rural and marine atmospheres and to fresh and salt waters. Subject to stress corrosion | | | | |
| AVAILABLE FORMS | Sheet; strip; rods, bars, and shapes; wire; spring. Forging, extruding and casting alloys are also available | | | | |
| USES | Most popular. Hardware, marine and automotive trim, camera parts, lighting fixtures, costume jewelry, screws, springs, slide fasteners | Slide fasteners, nameplates, decorative trim, camera parts | Optical equipment, etching stock, jewelry | Rivets, screws, slide fasteners, optical parts, hollow ware, nameplates | Excellent for springs. Springs and contacts in telephone equipment, electrical controls. Resistance wire, surgical and dental instruments, diaphragms, hardware |

[a] 0.5% extension under load. [b] Based on free-cutting brass = 100.

## Cupro-Nickels—Wrought

| Type → | Cupro-Nickel, 30% | Cupro-Nickel, 20% | Cupro-Nickel, 10% |
|---|---|---|---|
| COMPOSITION, % | Cu 68.9, Ni 30, Fe 0.5, Mn 0.6 | Cu bal, Ni 21, Fe 0.5, Mn 0.6 | Cu 88.35, Ni 10, Fe 1.25, Mn 0.4 |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.323 | 0.323 | 0.323 |
| Melting Temp Range, F | 2260–2140 | 2190–2100 | 2080–2020 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 17 | 21 | 26 |
| Coef of Ther Exp (68–572 F), per °F | $9.0 \times 10^{-6}$ | $9.1 \times 10^{-6}$ | $9.3 \times 10^{-6}$ |
| Specific Heat, Btu/lb/°F | 0.09 | 0.09 | 0.09 |
| Electrical Resistivity (68 F), microhm-cm | 37 | 27 | 15 |
| MECHANICAL PROPERTIES | | | |
| Mod of Elast in Tension, psi | $22 \times 10^6$ | $20 \times 10^6$ | $18 \times 10^6$ |
| Tensile Strength, 1000 psi | | | |
| Annealed[a] | 54–60 | 45–51 | 44 |
| Half Hard[b] | 73 | — | — |
| Hard[b] | 80 | — | — |
| Light Drawn[c] | 75 | 80 | 60 |
| Yield Strength (0.5% ext), 1000 psi | | | |
| Annealed[a] | 20–22 | — | 15 |
| Half Hard[b] | 68 | — | — |
| Hard[b] | 73 | — | — |
| Light Drawn[c] | — | 75 | 57 |
| Elongation (in 2 in.), % | | | |
| Annealed[a] | 40–45 | 27 | 40 |
| Half Hard[b] | 12 | — | — |
| Hard[b] | 6 | — | — |
| Light Drawn[c] | 45 | 40 | 42 |
| Hardness (Rockwell) | | | |
| Annealed[a] | B37–50 | — | B10 |
| Half Hard[b] | B80 | — | — |
| Hard[b] | B85 | — | — |
| Light Drawn[c] | B85 | B81 | B72 |
| Creep Strength (0.001%/1000 hr), 1000 psi | | | |
| At 300 F | 24 | >25 | >30 |
| At 500 F | 16 | 17 | 11 |
| FABRICATING PROPERTIES | | | |
| Cold Workability | Good | Good | Good |
| Hot Workability | Good | Good | Good |
| Hot Working Temp, F | 1700–1900 | 1650–1850 | 1550–1750 |
| Annealing Temp, F | 1200–1500 | 1200–1500 | 1100–1500 |
| Machinability Index[d] | 20 | 20 | 20 |
| Joining | | | |
| Soft Soldering | Excellent | Excellent | Excellent |
| Silver Alloy Brazing | Excellent | Excellent | Excellent |
| Metal Arc Welding | Excellent | Excellent | Good |
| Gas Shielded Arc Welding | Excellent | Excellent | Excellent |
| Resistance Welding | Excellent | Excellent | Good |
| Oxyacetylene Welding | Fair | Fair | Fair |
| Carbon Arc Welding | Not recommended | Not recommended | Not recommended |
| CORROSION RESISTANCE | Resistant to attack by high velocity sea water, fresh water, steam; sulfuric, phosphoric and mild organic acids; ammonia and ammoniacal compounds, chlorides, sulfates, nitrates | | |
| AVAILABLE FORMS | Plate, rod, strip, tube, wire | | |
| USES | Condenser tubes and plates, heat exchanger tubes, salt water piping, evaporator tubes, process equipment, distillation tubes. ASME code permits use of Cupro-Nickel, 30% in heat exchangers and unfired pressure vessels up to 700 F | | |

[a] Properties of annealed materials vary with grain size. [b] Strip. [c] Tube. [d] Based on free-cutting brass –100.

## Leaded Brasses and Bronzes—Cast

| BBII Grade ➡ | Leaded Tin Bronzes[a] | | |
|---|---|---|---|
| | 2A | 2B | 2C |
| COMPOSITION, % | Cu 88, Sn 6, Pb 1.5, Zn 4.5 | Cu 87, Sn 8, Pb 1, Zn 4 | Cu 87, Sn 8, Pb 1, Zn 2 |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.311–0.318 | 0.314–0.320 | 0.314–0.320 |
| Melting Temp Range, F | 1830 | 1830–1570 | 1830–1570 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | — | 28 | 28 |
| Coef of Ther Exp (70–350 F), per °F | $10.3 \times 10^{-6}$ | $10 \times 10^{-6}$ | $10 \times 10^{-6}$ |
| Electrical Conductivity (68 F), % IACS | 14 | 11 | 11 |
| MECHANICAL PROPERTIES[b] | | | |
| Mod of Elast in Tension, psi | $12–16 \times 10^6$ | $10.6–16 \times 10^6$ | $10.6–16 \times 10^6$ |
| Tensile Strength, 1000 psi | 36–48 | 33–43 | 36–46 |
| Yield Strength (0.5% ext), 1000 psi | 16–21 | 16–24 | 18–26 |
| Elongation (in 2 in.), % | 25–40 | 18–30 | 15–25 |
| Reduction of Area, % | 16–33 | 15–30 | 12–26 |
| Hardness (Brinell) | 60–72 | 60–75 | 65–80 |
| Impact Strength (Izod), ft-lb | 11–16 | 12–15 | 7–10 |
| Compr Yld Str (0.001-in. set), 1000 psi | 12–15 | 9–11 | 12–14 |
| FABRICATING PROPERTIES | | | |
| Casting Temp Range, F | | | |
| Light Castings | 2000–2300 | 2100–2300 | 1200–2300 |
| Heavy Castings | 1900–2150 | 1920–2100 | 1920–2100 |
| USES | Oil pumps, gears, bushings, high duty bearings, ornamental bronze | General utility structural bronze, pipe fittings, expansion joints, pressure valves | Bolts, nuts, gears, valves, pump pistons, pressure pipe fittings, expansion joints |

| BBII Grade ➡ | High-Leaded Tin Bronzes[a] | | | |
|---|---|---|---|---|
| | 3A | 3B | 3D | 3E |
| COMPOSITION, % | Cu 80, Sn 10, Pb 10 | Cu 83, Sn 7, Pb 7, Zn 3 | Cu 78, Sn 7, Pb 15 | Cu 71, Sn 5, Pb 24 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.321–0.328 | 0.320–0.322 | 0.329–0.340 | 0.332–0.343 |
| Melting Temp (approx), F | 1770 | 1800 | 1750 | 1700 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 27 | — | — | — |
| Coef of Ther Exp (70–400 F), per °F | $10.2 \times 10^{-6}$ | $10 \times 10^{-6}$ | $10.3 \times 10^{-6}$ | — |
| MECHANICAL PROPERTIES[b] | | | | |
| Mod of Elast in Tension | $8.5–13 \times 10^6$ | — | $8.8–12.6 \times 10^6$ | $9–12 \times 10^6$ |
| Tensile Strength, 1000 psi | 27–37 | 30–38 | 25–33 | 23–30 |
| Yield Strength (0.5% ext), 1000 psi | 15–22 | 17–21 | 14–20 | 11–15 |
| Elongation (in 2 in.), % | 8–12 | 12–20 | 10–18 | 7–16 |
| Reduction of Area, % | 5–11 | 10–22 | 8–15 | 5–12 |
| Hardness (Brinell) | 55–70 | 55–65 | 50–60 | 42–35 |
| Impact Strength (Izod), ft-lb | 2–8 | — | 4–6 | 4–6 |
| Compr Yld Str (0.001-in. set), 1000 psi | 12.5–16 | — | 13–16 | 12–14 |
| FABRICATING PROPERTIES | | | | |
| Casting Temp Range, F | | | | |
| Light Castings | 2000–2250 | 2000–2250 | 2000–2250 | 2000–2200 |
| Heavy Castings | 1850–2100 | 1900–2050 | 1900–2100 | 1850–2000 |
| USES | General purpose bushing and bearing alloy | General purpose bearing alloy, bushings, automobile fittings | Bearing bronze for moderate pressure, mine water pump parts | Bearings operating at high speed and light or medium pressure |

[a] Corrosion resistance generally the same as for nonleaded alloys of similar composition.
[b] Values are given for the as-cast condition.

## Leaded Brasses and Bronzes—Cast

| BBII Grade → | Leaded Red Brass[a] | | Leaded Semi-Red Brass[a] | |
|---|---|---|---|---|
| | 4A | 4B | 5A | 5B |
| COMPOSITION, % | Cu 85, Sn 5, Pb 5, Zn 5 | Cu 83, Sn 4, Pb 6, Zn 7 | Cu 81, Sn 3, Pb 7, Zn 9 | Cu 76, Sn 3, Pb 6, Zn 15 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.314–0.321 | 0.311–0.314 | 0.311–0.318 | 0.309–0.314 |
| Melting Temp Range, F | 1840–1550 | 1800 | 1800 | 1775 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 36 | — | — | — |
| Coef of Ther Exp (70–400 F), per °F | $10.9 \times 10^{-6}$ | — | — | — |
| Elec Cond (68 F), % IACS | 15 | — | 18 | — |
| MECHANICAL PROPERTIES[b] | | | | |
| Mod of Elast in Tension, psi | $9.1–14.8 \times 10^6$ | — | $7.7–14.3 \times 10^6$ | $10–14 \times 10^6$ |
| Ten Str, 1000 psi | 33–46 | 30–38 | 29–39 | 30–40 |
| Yld Str (0.5% ext), 1000 psi | 17–24 | 12–17 | 13–17 | 12–16 |
| Elongation (in 2 in.), % | 20–35 | 15–27 | 18–30 | 20–35 |
| Red. of Area, % | 17–32 | 12–25 | 15–27 | 15–30 |
| Hardness (Brinell) | 55–65 | 50–60 | 50–60 | 50–60 |
| Impact Str (Izod), ft-lb | 6–12 | — | 6–10 | — |
| Compr Yld Str (0.001-in. set), 1000 psi | 10–12 | 11–12 | — | 8–10 |
| FABRICATING PROPERTIES | | | | |
| Casting Temp Range, F | | | | |
| Light Castings | 2100–2350 | 2100–2300 | 2100–2300 | 2100–2300 |
| Heavy Castings | 1950–2150 | 1950–2150 | 1950–2150 | 1950–2150 |
| USES | Low pressure valve bodies, pipe fittings, pump impellers, plumbing goods | Air, gas and water fittings, valves, pump parts, hardware, carburetors | Low pressure valves and fittings, hardware, plumbing fittings | Plumbing fixtures, air and gas fittings, hardware, low pressure valves and fittings |

| BBII Grade → | Leaded Nickel Brass and Bronze[a] | | | |
|---|---|---|---|---|
| | 10A | 10B | 11A | 11B |
| COMPOSITION, % | Cu 57, Sn 2, Pb 9, Zn 20, Ni 12 | Cu 60, Sn 3, Pb 5, Zn 16, Ni 16 | Cu 64, Sn 4, Pb 4, Zn 8, Ni 20 | Cu 66.5, Sn 5, Pb 1.5, Zn 2, Ni 25 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.318–0.322 | 0.318–0.322 | 0.318–0.322 | 0.318–0.322 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 16 | 16 | 14 | 15 |
| Elec Cond (68 F), % IACS | 5–7 | 5–6 | 4.5–5.5 | 4–5 |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | $15–16.5 \times 10^6$ | — | $17–18 \times 10^6$ | $19–22 \times 10^6$ |
| Ten Str, 1000 psi | 30–40 | 35–45 | 40–60 | 50–65 |
| Yld Str (0.5% extn), 1000 psi | 15–20 | 17–24 | 17–30 | 26–40 |
| Elongation (in 2 in.), % | 10–25 | 15–30 | 15–25 | 15–25 |
| Red. of Area, % | 7–20 | 15–30 | 11–22 | 15–30 |
| Hardness (Brinell) | 50–60 | 65–80 | 76–120 | 120–150 |
| FABRICATING PROPERTIES | | | | |
| Casting Temp Range, F | | | | |
| Light Castings | 2200–2400 | 2250–2450 | 2300–2600 | 2400–2600 |
| Heavy Castings | 2000–2200 | 2050–2250 | 2250–2400 | 2300–2400 |
| USES | Hardware fittings, valves and trim, plumbing fittings | Valves and fittings, boat and railroad car fittings, pipe fittings | Marine fittings, furniture trim, building trim, valves, hardware | Dairy and soda fountain parts, valves and seats for elevated temp |

[a] Corrosion resistance generally the same as for nonleaded alloys of similar composition.
[b] Values are given for the as-cast condition.

## Yellow Brasses—Cast

| BBII Grade → | High Strength Yellow Brass* | | |
|---|---|---|---|
| | 7A | 8A | 8C |
| COMPOSITION, % | Cu 56–62, Sn 0.5–1, Pb 0.5–1, Fe 0.75–1.5, Al 0.25–1, Mn 0.1–0.5, Zn bal | Cu 56–59, Sn 1 max, Pb 0.3 max, Fe 0.75–2, Al 0.75–1.5, Mn 0.1–1, Zn bal | Cu 60–68, Fb 0.1 max, Fe 2–4, Al 4–7.5, Mn 3–4.5, Zn bal |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.289–0.303 | 0.289–0.307 | 0.278–0.289 |
| Melting Temp Range, F | 1675–1725 | 1660–1700 | 1650–1700 |
| Coef of Ther Exp (70–400 F), per °F | $11.4 \times 10^{-6}$ | $12 \times 10^{-6}$ | $11 \times 10^{-6}$ |
| Electrical Conductivity (68 F), % IACS | 20–24 | 16–20 | 10–14 |
| MECHANICAL PROPERTIES | | | |
| Mod of Elast in Tension, psi | $12–14 \times 10^6$ | $13–15 \times 10^6$ | $15–16.5 \times 10^6$ |
| Tensile Strength, 1000 psi | 60–78 | 70–88 | 110–120 |
| Yield Strength (0.5% ext), 1000 psi | 25–40 | 28–40 | 65–90 |
| Elongation (in 2 in.), % | 15–30 | 20–35 | 12–18 |
| Red. of Area, % | 15–30 | 20–40 | 5–18 |
| Hardness (Brinell) | 80–95 | 90–120 | 170–225 |
| Impact Strength (Izod), ft-lb | 20–40 | 20–40 | 7–12 |
| Compr Yld Str (0.001-in. set), 1000 psi | 20–26 | 22–26 | 55–65 |
| FABRICATING PROPERTIES | | | |
| Casting Temp Range, F | | | |
| Light Castings | 1900–2050 | 1900–2000 | 1950–2150 |
| Heavy Castings | 1750–1900 | 1750–1900 | 1800–1950 |
| USES | Valve stems, marine castings, pump bodies, gears, brackets | Propeller hubs and blades, valve stems, machine parts, gears | Spur gears, cams, bridge parts, screw down nuts, bearings |

| BBII Grade → | Leaded Yellow Brass* | | |
|---|---|---|---|
| | 6A | 6B | 6C |
| COMPOSITION, % | Cu 71, Zn 25, Pb 3, Sn 1 | Cu 67, Zn 29, Pb 3, Sn 1 | Cu 60, Zn 37.75, Pb 1, Sn 1, Al 0.25 |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.305–0.309 | 0.303–0.307 | 0.300–0.360 |
| Melting Temp Range, F | 1700–1750 | 1700–1725 | 1675–1725 |
| Coef of Ther Exp (70–200 F), per °F | $11.5 \times 10^{-6}$ | $11.2 \times 10^{-6}$ | $12 \times 10^{-6}$ |
| Electrical Conductivity (68 F), % IACS | 15–22 | 18–25 | 20–26 |
| MECHANICAL PROPERTIES | | | |
| Mod of Elast in Tension, psi | $11–14 \times 10^6$ | $12–14 \times 10^6$ | $13–15 \times 10^6$ |
| Tensile Strength, 1000 psi | 35–40 | 30–38 | 40–45 |
| Yield Strength (0.5% ext), 1000 psi | 12–14 | 11–15 | 14–20 |
| Elongation (in 2 in.), % | 25–40 | 20–35 | 15–25 |
| Red. of Area, % | 20–40 | 15–30 | 18–30 |
| Hardness (Brinell) | 40–55 | 40–60 | 50–75 |
| Compr Yld Str (0.001-in. set), 1000 psi | 8–10 | 8–10 | — |
| FABRICATING PROPERTIES | | | |
| Casting Temp Range, F | | | |
| Light Castings | 2000–2100 | 1950–2100 | 1950–2150 |
| Heavy Castings | 1850–2000 | 1850–1950 | 1800–2000 |
| USES | Plumber's fittings and fixtures, ferrules, hardware, andirons | Valves and fittings, spray nozzles, battery clamps, ship fittings | Ship fittings, plumber's flanges, hardware, Navy yellow brass |

* Corrosion resistance generally the same as for nonleaded alloys of similar composition.

## Aluminum Bronzes—Cast

| BBII Grade ➡ | 9A | 9B | 9C | 9D |
|---|---|---|---|---|
| COMPOSITION, % | Cu 87.5, Al 9, Fe 3.5 | Cu 89, Al 10, Fe 1 | Cu 83 min, Al 10–11.5, Fe 3–5, Ni 2.5 max, Mn 0.5 max | Cu 81, Al 11, Fe 4, Ni 4 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.267 | 0.270 | 0.272 | 0.273 |
| Melting Point Range, F | — | — | 1850–1900 | 1937 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | — | 33 | — | 22 |
| Coef of Ther Exp, per °F | 9.5 x 10$^{-6}$[a] | 9.5 x 10$^{-6}$[b] | 9.0 x 10$^{-6}$[b] | — |
| Elec Cond (68 F), % IACS | 13 | 13.5 | 12 | 7.5 |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | 17 x 10$^{6}$ | 15 x 10$^{6}$ | 18 x 10$^{6}$ | 17 x 10$^{6}$ |
| Ten Str, 1000 psi | | | | |
| Sand Cast | 75 | 87 | 75 | 95 |
| Sand Cast & Heat Treated | — | 90[c] | 105[d] | 115[e] |
| Yld Str (0.5% ext), 1000 psi | | | | |
| Sand Cast | 27 | 32 | 35 | 45 |
| Sand Cast & Heat Treated | — | 40[e] | 52[d] | 70[e] |
| Elongation (in 2 in.), % | | | | |
| Sand Cast | 35 | 27 | 18 | 7 |
| Sand Cast & Heat Treated | — | 15[c] | 10[d] | 5[e] |
| Hardness (Brinell) | | | | |
| Sand Cast | 120 | 120 | 155 | 195 |
| Sand Cast & Heat Treated | — | 180[c] | 230[d] | 235[e] |
| THERMAL TREATMENT | | | | |
| Normalizing Temp, F | Heat to 1500, furnace cool to 1000, air cool | | | |
| Quenching Temp, F | 1600–1700 | 1600–1700 | 1600–1700 | 1600–1700 |
| Tempering Temp, F | 700–1200 | 700–1200 | 700–1200 | 700–1200 |
| FABRICATING PROPERTIES | | | | |
| Castability | Because of narrow freezing ranges and high shrinkage, aluminum bronzes are difficult to cast. In addition, they are sensitive to gases. In melting, precautions must be taken to minimize stirring and breaking the oxide skin on the surface of the melt to prevent absorption of gases. In pouring, agitation must be avoided, and castings are generally bottom gated to reduce turbulence. Shrinkage difficulties are overcome by use of large risers (to feed the casting) and chills | | | |
| Machinability Index (free-cutting brass = 100) | 20–30 | 20–30 | 20–30 | 20–30 |
| Weldability | Can be welded by carbon arc, inert-gas arc and resistance methods. Can be brazed with silver brazing alloys, but require special fluxes | | | |
| CORROSION RESISTANCE | Generally good resistance to atmosphere, water and salt water, and salt solutions. Some resistance to alkaline solutions and nonoxidizing inorganic acids. Poor resistance to ammonia compounds, ferric salts and oxidizing inorganic acids | | | |
| USES | Machine parts, pump impellers and castings, gears, rolling mill bearings, segments and washers, bearings, chemical plant equipment, pickling equipment such as chains and hooks, marine propellers, pump casings, fittings | | | |

[a] 70–250 F. [b] 70–500F.
[c] Water quenched from 1625 F, tempered at 1125 F, water quenched.
[d] Water quenched from 1625 F, tempered at 1000 F, water quenched.
[e] Water quenched from 1625 F, tempered at 1150 F, water quenched.

## Lead and Its Alloys—Cast, Wrought[a]

| Type → | Chemical Lead | Common Lead (soft lead) | Tellurium Lead |
|---|---|---|---|
| COMPOSITION, % | Pb 99.90+ | Pb 99.73+ | Te 0.05, Cu 0.06 max |
| PHYSICAL PROPERTIES | | | |
| Density, lb/cu in. | 0.41 | 0.41 | 0.41 |
| Melting Point, F | 618 | 621 | 617 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 19.6 | 19.6 | 19.3 |
| Coef of Ther Exp, per °F | $16.3 \times 10^{-6}$ | $16.3 \times 10^{-6}$ | $16 \times 10^{-6}$ |
| Specific Heat (32 F), Btu/lb/°F | 0.031 | 0.031 | 0.031 |
| Electrical Resistivity (68 F), microhm-cm | — | 20.6 | — |
| MECHANICAL PROPERTIES | | | |
| Mod of Elast in Tension, psi | $2 \times 10^6$ | $2 \times 10^6$ | $1.5 \times 10^6$ |
| Tensile Strength, psi | | | |
| Rolled | 2450 | 2090 | — |
| Extruded | 2200 | 2000 | — |
| Sand Cast | — | 1800 | — |
| Chill Cast | 2200 | 2000 | — |
| Yield Strength, psi | | | |
| Rolled | 1640 | — | — |
| Extruded | — | — | 1500 |
| Sand Cast | — | 800 | — |
| Elongation (in 2 in.), % | | | |
| Rolled | 57 | 43 | 40 |
| Extruded | 48 | — | — |
| Sand Cast | — | 30 | — |
| Chill Cast | 40 | 47 | — |
| Reduction of Area, % | | | |
| Sand Cast | — | 100 | — |
| Chill Cast | — | 100 | — |
| Hardness (Brinell) | | | |
| Extruded | — | — | 6 |
| Sand Cast | — | 3.2–4.5 | — |
| Chill Cast | — | 4.2 | — |
| Impact Strength (Charpy, chill cast), ft-lb | — | 10 | — |
| Endurance Limit ($10^7$ cycles), psi | | | |
| Extruded & Aged | 725 | 470 | 1000 |
| Sand Cast | — | 470 | — |
| Shear Strength, psi | | | |
| Sand Cast | — | 1820 | — |
| Chill Cast | — | 1820 | — |
| Creep Strength (0.1% per yr, rolled, 85 F), psi | 300 | 250 | 300 |
| FABRICATING PROPERTIES | Formed by cold rolling and extrusion | | |
| Casting Temp Range, F | 790–850 | 790–850 | 790–850 |
| Joining | Soft solder with 50-50 or 40-60 solder using rosin or stearic acid flux. Oxyhydrogen welding (lead burning): slightly reducing flame; no flux | | |
| CORROSION RESISTANCE | Resistant to sulfuric, sulfurous, phosphoric and chromic acids. Attacked by acetic, formic and nitric acids. Resistant to atmosphere and fresh and salt water | | |
| AVAILABLE FORMS | Castings, rolled and extruded shapes, sheet | | |
| USES | Nuclear reflectors and shields; anodes for cathodic protection | | |
| | Chemical apparatus | Storage batteries, cable sheath, ammunition, calking, alloying, coatings, liquid baths for heat treating | Chemical apparatus |

[a] See also Tin-Lead-Antimony Alloys.

## Lead and Its Alloys—Wrought

| Type → | 1% Sb-Lead | Hard Lead | Hard Lead | 8% Sb-Lead | Grid Metal (7-12% Sb) |
|---|---|---|---|---|---|
| COMPOSITION, % | Sb 1 | Sb 4 | Sb 6 | Sb 8 | Sb 9 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.406 | 0.398 | 0.393 | 0.388 | 0.385 |
| Melting Temp Range, F | 608–595 | 570–486 | 545–486 | 520–486 | 509–486 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 19 | 18 | 17 | 16 | 16 |
| Coef of Ther Exp (68–212 F), per °F | $16 \times 10^{-6}$ | $15.5 \times 10^{-6}$ | $15.4 \times 10^{-6}$ | $14.5 \times 10^{-6}$ | $14.4 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.031 | 0.032 | 0.032 | 0.032 | 0.032 |
| Elec Res (68 F), microhm-cm | 22 | 24 | 25 | 26.5 | 27.1 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $2 \times 10^6$ | — | — | — | — |
| Ten Str, 1000 psi | | | | | |
| Rolled | 3.0 | 4.0 | 4.1 | 4.6 | 4.7 |
| Extruded | 2.9 | 3.1 | 3.3 | 3.3 | — |
| Extruded & Aged | 3.0 | — | — | — | — |
| Chill Cast | 3.4 | 5.6 | 6.8 | 7.4 | 7.4 |
| Elong (in 2 in.), % | | | | | |
| Rolled | 60 | 48 | 47 | 31 | 17 |
| Extruded | 58 | 58 | 65 | 75 | — |
| Extruded & Aged | 50 | — | — | — | 75 |
| Chill Cast | 16 | 22 | 24 | 19 | — |
| Hardness (Brinell) | | | | | |
| Rolled | 5.9 | 8 | — | 9.5 | 7.8 |
| Extruded | 5.1 | 8.9 | 10.7 | 12.4 | — |
| Extruded & Aged | 7 | — | — | — | — |
| Chill Cast | 7 | 10 | 11.8 | 13.3 | 15.4 |
| Endurance Limit, psi[a] | | | | | |
| Rolled | — | 1500 | 1500 | 1750 | — |
| Extruded | — | — | 1200 | — | — |
| Extruded & Aged | 1150 | — | — | — | — |
| Chill Cast | — | — | 2500 | — | 2700 |
| Creep Str (86 F)[b] | | | | | |
| Rolled | — | 250 | 400 | 425 | 400 |
| Extruded | 350 | 210 | — | — | — |
| FABRICATING PROPERTIES | | | | | |
| Casting Temp Range, F | 750–925 | 750–925 | 750–850 | 750–925 | 750–925 |
| Joining | Soft solder with 50–50 or 40–60 solder using rosin or stearic acid flux. Oxyhydrogen welding (lead burning): no flux, slightly reducing flame | | | | |
| CORROSION RESISTANCE | Similar to soft lead (see opposite page) | | | | |
| USES | Nuclear reflectors and shields; anodes for cathodic protection | | | | |
| | Cable sheathing | Rolled sheet for roofing and flashing; extruded pipe for corrosion resistance applications requiring greater strength than soft lead | | | Battery grids |

[a] $2 \times 10^7$ cycles.
[b] 1% extension in 10,000 hr.

## Magnesium Alloys—Wrought

| ASTM Type → | M1A-F | AZ61A-F | AZ80A-T5 | ZK60A-T5 | (P)ZK60B-T5 | ZK21A-F |
|---|---|---|---|---|---|---|
| COMPOSITION, % | Mn 1.20 min | Al 5.8–7.2, Zn 0.4–1.5, Mn 0.15 min | Al 7.8–9.2, Zn 0.2, Mn 0.15 min | Zn 4.8–6.2, Zr 0.45 min | Zn 4.8–6.8, Zr 0.45 min | Zn 2.0–2.6, Zr 0.45–0.8 |
| PHYSICAL PROPERTIES | | | | | | |
| Density, lb/cu in. | 0.064 | 0.065 | 0.065 | 0.066 | 0.066 | 0.064 |
| Melting Temp Range, F | 1198–1200 | 950–1140 | 900–1115 | 968–1175 | 968–1175 | — |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 80 | 34 | 29 | 68–70 | 70 | — |
| Coef of Ther Exp, per °F | | | | | | |
| 68 F | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ |
| 68 to 750 F | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.245 | 0.245 | 0.245 | 0.245 | 0.245 | 0.245 |
| Elec Res (68 F), microhm-cm | 5.0 | 12.5 | 14.5 | 6.0–5.7 | 5.7 | — |
| MECHANICAL PROPERTIES | | | | | | |
| Mod of Elast in Tension, psi | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ |
| Ten Str, 1000 psi | | | | | | |
| Extruded[a] | 35–38 | 41–46 | 50–55 | 50–53 | 49 | 41–42 |
| Forged | 36 | 43 | 50 | 49 | — | — |
| Yld Str, 1000 psi | | | | | | |
| Extruded[a] | 21–26 | 24–33 | 38–40 | 40–44 | 38 | 33–35 |
| Forged | 23 | 26 | 34 | 38 | — | — |
| Elong (in 2 in.), % | | | | | | |
| Extruded[a] | 5–12 | 14–17 | 6–8 | 11–14 | 17 | 6–10 |
| Forged | 7 | 12 | 6 | 13 | — | — |
| Compr Yld Str, 1000 psi | | | | | | |
| Extruded[a] | 9–12 | 16–21 | 31–34 | 30–36 | 40 | 17–25 |
| Forged | — | 17 | 28 | 28 | — | — |
| Hardness (Brinell) | | | | | | |
| Extruded[a] | 42–44 | 50–60 | 82 | 82 | — | — |
| Forged | 47 | 55 | 72 | — | — | — |
| Shear Str, 1000 psi | | | | | | |
| Extruded | 18 | 20 | 24 | 24–26 | 26 | — |
| Forged | 18 | 20 | 23 | — | — | — |
| Fatigue Strength[b] ($10^8$ cycles), 1000 psi | | | | | | |
| Extruded | 10–13 | 18–23 | 20–24 | 17–23 | 17–23 | — |
| Forged | — | 17–22 | 16–18 | 16–18 | — | — |
| Impact Str (Charpy), ft-lb | | | | | | |
| Extruded | 1.5 | 4.5 | 1.3 | 3 | 2.6 | — |
| Forged | — | — | — | — | — | — |
| FABRICATING PROPERTIES | | | | | | |
| Hot Working Temp Range, F[d] | 550–650 | 450–650 | 350–375 | 300–500 | 300–500 | 300–500 |
| Weldability[c] | | | | | | |
| Inert-Gas Arc | A | B | B | D | D | B |
| Elec Res. | A | A | A | A | A | A |
| Stress Relief Temp, F | — | 500 | 400 | — | — | — |
| Machinability Index (free-cutting brass=100) | 500 | 500 | 500 | 500 | 500 | 500 |
| Hot Formability[c] | A | B | C | A | A | A |
| Cold Formability[c] | B | C | D | C | C | C |
| CORROSION RESISTANCE | Good resistance to atmosphere; attacked by salt water unless finished | | | | | |
| AVAILABLE FORMS | Rod, bar, extruded shapes, tubing (except AZ80A), forgings | | | | Rod, bar, extruded shapes | Rod, bar, extruded shapes, tubing |
| USES | Aircraft and missile parts, ordnance vehicles, automotive and truck parts, electronic equipment, wave guides, office machines, reciprocating machinery parts, drillable oil well casing tools, hand tools, levels, material handling equipment, concrete forms, plastering tools, jigs and fixtures, luggage and furniture, boats, sporting goods, wheels | | | | | |

[a] Generally, strengths and hardness of extruded bar are highest, extruded tubing lowest, and extruded shapes intermediate in the ranges of values given.
[b] Rotating-beam fatigue.
[c] Letter A indicates most favorable, B less favorable, etc. Relative to magnesium alloys only.
[d] Higher working temperatures can be used if they do not require heating aged alloys above the aging temperature.

## Magnesium Alloys—Wrought

| ASTM Type → | ZE10A-H24 [a] | AZ31B-H24 [b] | HK31A-H24 [a] | HM21A-T8 | HM31A-T5 |
|---|---|---|---|---|---|
| COMPOSITION, % | Zn 1.0–1.5, Rare earths 0.12–0.22 | Al 2.5–3.5, Zn 0.7–1.3, Mn 0.20 | Th 2.5–4.0, Zr 0.45–1.0 | Th 1.5–2.5, Mn 0.45–1.1 | Th 2.5–3.5, Mn 1.2 min |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.063 | 0.064 | 0.065 | 0.064 | 0.065 |
| Melting Temp Range, F | 1100–1195 | 1050–1170 | 1092–1195 | 1121–1202 | 1121–1202 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 77 | 44 | 66 | 79 | 60 |
| Coef of Ther Exp (68 to 750 F), per °F | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.245 | 0.245 | 0.245 | 0.245 | 0.245 |
| Elec Res (68 F), microhm-cm | 5.2 | 9.2 | 6.1 | 5.0 | 6.6 |
| MECHANICAL PROPERTIES [c] | | | | | |
| Mod of Elast in Tension, psi | | | | | |
| 75 F | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.4 \times 10^6$ | $6.4 \times 10^6$ | $6.5 \times 10^6$ |
| 500 F | — | — | $5.2 \times 10^6$ | $5.8 \times 10^6$ | $5.7 \times 10^6$ |
| Ten Str, 1000 psi [d] | | | | | |
| 75 F | 34–38 | 42, 38–39 | 37 | 34 | 42 |
| 500 F | — | — | 20 | 15 | 21 |
| Yield Str, 1000 psi [d] | | | | | |
| 75 F | 19–28 | 32, 24–27 | 29 | 21 | 33 |
| 500 F | — | — | 17 | 13 | 19 |
| Elong (in 2 in.), % (75 F) [d] | 8–12 | 15, 18–19 | 8 | 10 | 10 |
| Compr Yld Str, 1000 psi [d] | | | | | |
| 75 F | 16–26 | 24–25, 12–14 | 23 | 15 | 25 |
| 500 F | — | — | 20 | 13 | 19 |
| Shear Str, 1000 psi [d] | | | | | |
| 75 F | — | 23, — | 27 | 19 | 23 |
| 500 F | — | — | 12 | 11 | 11 |
| Fatigue Str, 1000 psi [e] | | | | | |
| 75 F | 20–24 | 20–24 | 18–20 | 16–18 | 12–14 |
| 400 F | — | — | 9–14 | 12–14 | — |
| Creep Str (stress to give 0.5% total ext in 100 hr), 1000 psi | | | | | |
| 300 F | — | 1.5 | 20 | 16 | 21 |
| 500 F | — | — | — | 9 | 13 |
| FABRICATING PROPERTIES | | | | | |
| Hot Working Temp Range, F | 325–425 | 325–425 | 550–700 | 650–800 | 650–800 |
| Weldability [f] | | | | | |
| Inert-Gas Arc | A | A | A | A | A |
| Elec Res | A | A | A | A | A |
| Stress Relief Temp, F | — | 500 | — | — | — |
| Machinability Index (free-cutting brass=100) | 500 | 500 | 500 | 500 | 500 |
| Hot Formability [f] | A | A | A | A | A |
| Cold Formability [f] | B+ | B | C | C | C |
| CORROSION RESISTANCE | Good resistance to atmosphere; attacked by salt water unless finished | | | | |
| AVAILABLE FORMS | Sheet and plate | | | | Extrusions |
| USES | Aircraft and missile parts, ordnance vehicles, truck bodies, electronic cabinets, chassis, covers and reflectors, office machines, appliances, materials handling equipment, concrete forms, jigs and fixtures, templates, foundry pattern plate, deck plate, photoengraving plate, luggage, furniture, sporting goods | | Aircraft and missile components | | |

[a] ZE10A and HK31A also available in -0 temper.

[b] AZ31B sheet and plate also available in -0 temper. AZ31B plate also available in -H26 temper. AZ31B also available as special bending sheet in the -0 temper and 0.040–0.190-in. thickness for cold bending around a mandrel radius of 2-3 or more times the sheet thickness.

[c] HM31A-T5 properties for extrusions (to 4 sq in.) only. ZE10A-H24, HM21A-T8 and HK31A-H24 properties for sheet only. AZ31B-H24 properties for sheet only except as indicated.

[d] AZ31B-H24 values are for sheet and plate, respectively.

[e] Axial load fatigue of ZE10A-H24 and AZ31B-H24 sheet, $10^7$ cycles, R = ⅓. Axial load fatigue of HM21A-T8 and HK31A-H24 sheet, $10^7$ cycles, R = ¼. Rotating beam fatigue of HM31A-T5 extrusions, $10^8$ cycles, R = 1.

[f] Letter A indicates most favorable, B less favorable, etc. Relative to magnesium alloys only.

## Magnesium Alloys—Cast

| ASTM Type → | AZ63A | AZ81A | AZ91A | AZ91C | AZ92A | AM100A |
|---|---|---|---|---|---|---|
| COMPOSITION, % | Al 5.3–6.7, Zn 2.5–3.5, Mn 0.15 min | Al 7.0–8.1, Zn 0.40–1.0, Mn 0.13 min | Al 8.3–9.7, Zn 0.4–1.0, Mn 0.13 min | Al 8.1–9.3, Zn 0.40–1.0, Mn 0.13 min | Al 8.3–9.7, Zn 1.6–2.4, Mn 0.10 min | Al 8.3–9.7, Zn 0.3 max, Mn 0.10 min |
| PHYSICAL PROPERTIES | | | | | | |
| Density, lb/cu in. | 0.066 | 0.065 | 0.065 | 0.065 | 0.066 | 0.065 |
| Melting Temp Range, F | 850–1135 | 1115 | 875–1120 | 875–1105 | 830–1110 | 865–1100 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | 29–39 | 29 | 31 | 27–31 | 27–34 | 24–34 |
| Coef of Ther Exp, per °F | | | | | | |
| 68 F | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ |
| 68–750 F | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.245 | 0.245 | 0.245 | 0.245 | 0.245 | 0.245 |
| Elec Res (68 F), microhm-cm | 11–14 | 15 | 14 | 13–16 | 12–17 | 11–17 |
| MECHANICAL PROPERTIES[a] | | | | | | |
| Mod of Elast in Tension, psi | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ |
| Ten Str, 1000 psi | | | | | | |
| As Cast | 29 | — | 34 | 24 | 24 | 22 |
| Sol'n Treated | 40 | 40 | — | 40 | 40 | 40 |
| Aged[b] | 30, 40 | —, — | —, — | —, 40 | 26, 40 | —, 40 |
| Yld Str, 1000 psi | | | | | | |
| As Cast | 14 | — | 23 | 14 | 14 | 12 |
| Sol'n Treated | 13 | 12 | — | 12 | 14 | 13 |
| Aged[b] | 14, 19 | —, — | —, — | —, 19 | 16, 21 | —, 16 |
| Elong (in 2 in.), % | | | | | | |
| As Cast | 6 | — | 3 | 2 | 2 | 2 |
| Sol'n Treated | 12 | 15 | — | 14 | 9 | 10 |
| Aged[b] | 4, 5 | —, — | —, — | —, 5 | 2, 2 | —, 4 |
| Hardness (Brinell) | | | | | | |
| As Cast | 50 | — | 60 | 52 | 65 | — |
| Sol'n Treated | 55 | 55 | — | 53 | 63 | — |
| Aged[b] | 55, 73 | —, — | —, — | —, 66 | 80, 84 | —, — |
| Shear Str, 1000 psi | | | | | | |
| As Cast | 16 | — | 20 | 16 | 16 | — |
| Sol'n Treated | 17 | 17 | — | 17 | 17 | — |
| Aged[b] | 17, 19 | —, — | —, — | —, 19 | 16, 20 | —, — |
| Fatigue Str ($10^8$ cycles), 1000 psi[c] | | | | | | |
| As Cast | 9–12 | — | 10–14 | 11–14 | 12–14 | — |
| Sol'n Treated | 12–17 | 11–14 | — | 12–15 | 12–15 | — |
| Sol'n Treated and Aged | 11–15 | — | — | 10–13 | 11–15 | — |
| THERMAL TREATMENT | | | | | | |
| Solution Temp, F | 730 | 780 | — | 780 | 770 | 780 |
| Aging Temp, F | 425 | — | — | 420 | 500 | 425 |
| FABRICATING PROPERTIES | | | | | | |
| Weldability[d] | | | | | | |
| Inert-Gas Arc | D | B | — | C | C | A |
| Stress Relief Temp, F | 500 | 500 | — | 500 | 500 | 500 |
| Machinability Index (free-cutting brass=100) | 500 | 500 | 500 | 500 | 500 | 500 |
| CORROSION RESISTANCE | Good resistance to atmosphere; attacked by salt water unless finished | | | | | |
| AVAILABLE FORMS | Sand and permanent mold castings | | Die castings | Sand and permanent mold castings | | Permanent mold castings |
| USES | Wheels, aircraft and missile parts, ordnance equipment, automotive and truck parts, electronic housings, office machines, appliances, reciprocating machinery parts, cameras and optical equipment, hand tools, material handling equipment, sporting goods, griddles | | | | | |

[a] Separately-cast test bars.
[b] First value obtained by artificial aging only; second value by solution treating and artificial aging.
[c] Rotating-beam fatigue.
[d] Letter A indicates most favorable, B less favorable, etc. Relative to magnesium alloys only.

## Magnesium Alloys—Cast

| ASTM Type ➡ | ZE41A-T5 | ZK51A-T5 | ZH62A-T5 | K1-A |
|---|---|---|---|---|
| COMPOSITION, % | Zn 3.5–5.0, rare earths 0.75–1.75, Zr 0.40–1.0 | Zn 3.6–5.5, Zr 0.55–1.0 | Zn 5.2–6.2, Th 1.4–2.2, Zr 0.50–1.0 | Zr 0.7 |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.066 | 0.065 | 0.067 | 0.063 |
| Melting Temp Range, F | — | 1040–1175 | — | 1202[d] |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | — | 48 | 63 | 60 |
| Coef of Ther Exp, per °F | | | | |
| 68 F | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | — |
| 68–750 F | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $15 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.245 | 0.245 | 0.245 | — |
| Elec Res (68 F), microhm-cm | — | 8.4 | 6.5 | 5.7 |
| MECHANICAL PROPERTIES[a] | | | | |
| Mod of Elast in Tension, psi | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ |
| Ten Str, 1000 psi | 30 | 40 | 40 | 26 |
| Yld Str, 1000 psi | 20 | 24 | 25 | 8 |
| Elong (in 2 in.), % | 3.5 | 8 | 6 | 19 |
| Hardness (Brinell) | 62 | 65 | 62 | — |
| Shear Str, 1000 psi | 22 | 22 | 23 | 8 |
| Fatigue Str ($10^8$ cycles), 1000 psi[b] | — | 8–10 | — | — |
| THERMAL TREATMENT | | | | |
| Aging Temp, F | 350 | 350 | 350 | — |
| FABRICATING PROPERTIES | | | | |
| Weldability (inert-gas arc)[c] | B | D | D | B |
| Machinability Index (free-cutting brass = 100) | 500 | 500 | 500 | 500 |
| CORROSION RESISTANCE | Good resistance to atmosphere; attacked by salt water unless finished | | | |
| AVAILABLE FORMS | Sand and permanent mold castings | | | Sand and die castings |
| USES | Aircraft and missile parts, ordnance equipment | | | |

[a] Separately-cast test bars.
[b] Rotating-beam fatigue.
[c] Letter A indicates most favorable, B less favorable, etc. Relative to magnesium alloys only.
[d] Melting point.

*continued on next page*

## Magnesium Alloys—Cast

| ASTM Type → | QE22A-T6 | EZ33A-T5 | HK31A-T6 | HZ32A-T5 | EX31XA-T6 |
|---|---|---|---|---|---|
| COMPOSITION, % | Ag 2.0–3.0, rare earths[d] 1.75–2.25, Zr 0.40–1.0 | Rare earths[e] 2.5–4.0, Zn 2.0–3.1, Zr 0.50–1.0 | Th 2.5–4.0, Zr 0.50–1.0 | Th 2.5–4.0, Zn 1.7–2.5, Zr 0.50–1.0 | Rare earths[d] 2.5–4.0, Zr 0.4–1.0 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.065 | 0.066 | 0.065 | 0.066 | 0.064 |
| Melting Temp Range, F | — | 1110–1189 | 1092–1195 | 1026–1198 | — |
| Ther Cond, Btu/hr/sq ft/°F/ft | | | | | |
| 68 F | — | 58 | 52 | 62 | 36 |
| 600 F | — | 69 | 68 | 74 | 43 |
| Coef of Ther Exp, per °F | | | | | |
| 68 F | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14 \times 10^{-6}$ | $14.5 \times 10^{-6}$ |
| 68–750 F | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $16 \times 10^{-6}$ | $14.5 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.245 | 0.245 | 0.245 | 0.245 | — |
| Elec Res, microhm-cm | | | | | |
| 68 F | — | 7.0 | 7.7 | 6.5 | 7.2 |
| 600 F | — | 12.1 | 12.4 | 11.3 | 12.0 |
| MECHANICAL PROPERTIES[a] | | | | | |
| Mod of Elast in Tension, psi | | | | | |
| 75 F | — | $6.5 \times 10^6$ | $6.5 \times 10^6$ | $6.5 \times 10^6$ | — |
| 300 F | — | $6.0 \times 10^6$ | $6.1 \times 10^6$ | $5.9 \times 10^6$ | — |
| 600 F | — | $5.4 \times 10^6$ | $5.6 \times 10^6$ | $5.6 \times 10^6$ | — |
| Ten Str, 1000 psi | | | | | |
| 75 F | 40 | 23 | 31 | 29 | 35 |
| 400 F | 28 | 21 | 24 | 17 | 29 |
| 700 F | 7 | — | 13 | 10 | 15[f] |
| Yld Str, 1000 psi | | | | | |
| 75 F | 30 | 16 | 16 | 15 | 22 |
| 400 F | 25 | 12 | 14 | 10 | 20 |
| 700 F | 6 | — | 8 | 7 | 13[f] |
| Elong (in 2 in.), %, 75 F | 4 | 3 | 6 | 6 | 5 |
| Hardness (Brinell) | — | 50 | 55 | 57 | 64 |
| Shear Str, 1000 psi | | | | | |
| 75 F | — | 20 | 21 | 20 | 23 |
| 400 F | — | 17 | 16 | 14 | 19 |
| 600 F | — | 10 | 13 | 10 | 11 |
| Fatigue Str, 1000 psi[b] ($10^8$ cycles), 75 F | 15–17 | 9–11 | 9–11 | 9–11 | — |
| Creep Str (stress to give 0.5% total ext in 100 hr), 1000 psi | | | | | |
| 400 F | 14 | 10 | 15 | 10 | 10–13 |
| 500 F | — | 4 | 10 | 8 | 3–4 |
| 600 F | — | 1.5 | 3.5 | 5 | 1.2–1.8 |
| FABRICATING PROPERTIES | | | | | |
| Weldability (inert-gas arc)[c] | — | A | A | A | — |
| Machinability Index (free-cutting brass=100) | 500 | 500 | 500 | 500 | — |
| CORROSION RESISTANCE | Good resistance to atmosphere; attacked by salt water unless finished | | | | |
| AVAILABLE FORMS | Sand and permanent mold castings | | | | Sand castings |
| SERVICE TEMPERATURE, MAXIMUM F | 500 | 500 | 700 | 700 | 550 |
| USES | Aircraft and missile components | | | | Aircraft and missile components up to 550 F; airframe and engine components for 1000 hr at 450 F |

[a] Separately-cast test bars. [b] Rotating-beam fatigue.
[c] Letter A indicates most favorable, B less favorable, etc. Relative to magnesium alloys only.
[d] Rare earths are present as didymium, essentially 85% neodymium and 15% praseodymium.
[e] Rare earths are present as mischmetal. [f] At 600 F.

## Columbium, Tantalum, Tungsten, Molybdenum—Wrought

| Metal → | Columbium | Tantalum | Tungsten | Molybdenum |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Density, lb/cu in. | 0.31 | 0.60 | 0.70 | 0.37 |
| Melting Point, F | 4379 | 5425 | 6152 | 4760 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 31.5 | 31.5 | 96.6 | 84.5 |
| Coef of Ther Exp (70 F), per °F | 3.82 x $10^{-6}$[a] | 3.6 x $10^{-6}$ | 2.2 x $10^{-6}$ | 3.0 x $10^{-6}$ |
| Specific Heat, Btu/lb/°F | 0.065 | 0.036 | 0.034 | 0.065 |
| Elec Res (68 F), microhm-cm | 14.2 | 12.4 | 5.48[b] | 5.17[b] |
| **MECHANICAL PROPERTIES** | | | | |
| Mod of Elast in Tension, psi | — | 27 x $10^6$ | 50 x $10^6$ | 42 x $10^6$ |
| Ten Str, 1000 psi | | | | |
| Annealed | 50 | 50–100 | — | 85–130[c], 88[d] |
| Cold Worked | 100 | 110–180 | 70–300 | 120–175[c] |
| Yld Str, 1000 psi | | | | |
| Annealed | — | — | — | — |
| Cold Worked | — | - | — | — |
| Elong (in 2 in.), % | | | | |
| Annealed | 30 | 11–40 | — | 4–7[c], 42[d] |
| Cold Worked | 5 | 1–1.5 | 0 | 1[c] |
| Hardness (Rockwell) | | | | |
| Annealed | E80 | E60 | — | B95[c] |
| Cold Worked | E100 | E95 | C37–C47 | C22–27[c] |
| **FABRICATING PROPERTIES** | | | | |
| Workability | Easily cold worked | Easily cold worked | Must be hot worked except fine wire | Thin sheet and wire can be cold worked, heavier material hot worked |
| Annealing Temp, F | 1950 in vacuum | 1950 in vacuum | 1830 in protective atm | Anneal to specified mechanical properties |
| Machinability | Like cold rolled steel, with proper lubricants | Like cold rolled steel, with proper lubricants | Difficult, even with special tools and methods; grinding recommended | Like cast iron, but tool life is shorter |
| Joining | Weldable to itself and other metals by resistance or inert arc welding. Special methods necessary | Weldable to itself and other metals by resistance or inert arc welding. Special methods necessary | Weldable to itself by inert arc with special methods; to other metals by brazing or resistance welding | Thin sheet can be resistance welded, heavier sections inert arc welded with special methods. Can be brazed to other metals |
| **CORROSION RESISTANCE** | Res to most acids (except hydrofluoric); res to most liquid metals. Less res to alkalis | More res than columbium to acids (except hydrofluoric); res to most liquid metals, metallic salts and compounds. Less res to alkalis | Res most acids and alkalis to 212 F, attacked by nitric-hydrofluoric mixture at rm temp, by aqua regia at 212 F | Moderately res to acids and alkalis up to 212 F, attacked by nitric-hydrofluoric mixture at rm temp, by aqua regia at 212 F |
| **AVAILABLE FORMS** | Bar, rod, wire, sheet, foil, tubing, powder, fabricated parts | Bar, rod, wire, sheet, foil, tubing, powder, fabricated parts | Bar, rod, wire, sheet, powder, fabricated parts | Bar, rod, wire, sheet, tubing, powder, fabricated parts |
| **USES** | Nuclear reactors, missles, rockets, chemical plant equipment, electronic tubes | Capacitors, chemical plant equipment, electronic tubes, rectifiers, surgical implants, nuclear reactors, missiles, rockets, aircraft | Lamp filaments, electrical contacts, nuclear reactors, rockets, missiles, aircraft, radiation shields, electronic tube parts, x-ray targets | Glass melting electrodes, electronic tube parts, furnace heating elements, electrical contacts, aircraft, missile and rocket structures, guidance systems |

[a] 32–1832 F. [b] 32 F. [c] From powder. [d] Arc melted.

## Nickel and Its Alloys—Wrought

| Type → | A Nickel | Low Carbon Nickel | Duranickel | Monel | K Monel |
|---|---|---|---|---|---|
| COMPOSITION, % | Ni 99.00, Cu 0.10, Fe 0.15, Si 0.05, Mn 0.25, C 0.05, S 0.005 | Ni 99.00, Cu 0.10, Fe 0.15, Si 0.05, Mn 0.25, C 0.01, S 0.005 | Ni 94.00, Cu 0.05, Fe 0.35, Al 4.50, Si 0.50, Ti 0.50, Mn 0.30, C 0.25, S 0.005 | Ni 67.00, Cu 30.00, Fe 1.40, Si 0.10, Mn 1.00, C 0.15, S 0.035 | Ni 66.00, Cu 29.00, Fe 1.00, Al 2.75, Si 0.50, Ti 0.50, Mn 0.75, C 0.15, S 0.005 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.321 | 0.321 | 0.298 | 0.319 | 0.306 |
| Melting Temp Range, F | 2615–2635 | 2615–2635 | 2550–2620 | 2370–2460 | 2400–2460 |
| Ther Cond (80–212 F), Btu/hr/sq ft/°F/ft | 36 | 36 | 10.7–11.2 | 15 | 10.8 |
| Coef of Ther Exp (80–212 F), per °F | $7.4 \times 10^{-6}$ | $7.4 \times 10^{-6}$ | $7.2 \times 10^{-6}$ | $7.8 \times 10^{-6}$ | $7.8 \times 10^{-6}$ |
| Specific Heat (80–212 F), Btu/lb/°F | 0.130 | 0.130 | 0.104 | 0.127[d] | 0.127[d] |
| Elec Res (32 F), microhm-cm | 9.5 | 8.3 | 46.5 (soft) | 48.2[c] | 58.1[c] |
| Magnetic? | Yes | Yes | Yes | Slightly | No to −150 F |
| MECHANICAL PROPERTIES[a] | | | | | |
| Mod of Elast in Tension, psi | $30 \times 10^6$ | $30 \times 10^6$ | $30 \times 10^6$ | $26 \times 10^6$ | $26 \times 10^6$ |
| Tensile Strength, 1000 psi | | | | | |
| Annealed | 55–75 | 50–60 | 90–120 | 70–85 | 90–105 |
| Annealed, Age Hardened | — | — | 160–190 | — | 130–170 |
| Spring | 90–130 | — | 155–190 | 100–140 | 145–165 |
| Spring, Age Hardened | — | — | 180–230 | — | 170–200 |
| Yield Strength, 1000 psi | | | | | |
| Annealed | 15–30 | 12–25 | 35–60 | 25–45 | 40–65 |
| Annealed, Age Hardened | — | — | — | — | 90–120 |
| Spring | 70–115 | — | — | 90–130 | 130–160 |
| Spring, Age Hardened | — | — | — | — | 130–180 |
| Elongation (in 2 in.), % | | | | | |
| Annealed | 55–40 | 60–40 | 50–130 | 50–35 | 45–25 |
| Annealed, Age Hardened | — | — | 25–10 | — | 25–15 |
| Spring | 15–2 | — | 10–2 | 15–2 | 8–3 |
| Spring, Age Hardened | — | — | 15–5 | — | 10–5 |
| Hardness (Rockwell) | | | | | |
| Annealed | B64 (max) | B55 (max) | B90 (max) | B68 (max) | B85 (max) |
| Annealed, Age Hardened | — | — | C30–40 | — | C24 (min) |
| Spring | B95 (min) | — | C30–40 | B98 (min) | C25 (min) |
| Spring, Age Hardened | — | — | C36–46 | — | C34 (min) |
| Endurance Limit ($10^8$ cycles), 1000 psi | | | | | |
| Hot Rolled | 33[c] | 33[c] | 51 | — | — |
| Cold Drawn | 50[c] | 50[c] | 51 | — | — |
| THERMAL TREATMENTS | | | | | |
| Annealing Temperature, F | 1500 (2–5 min) | 1500 (3–6 min) | 1600 (2–5 min) | 1600–1800 (open), 1400–1500 (box) | 1400–1800 (1–5 min) |
| Aging Temperature, F | — | — | 1100 (8–16 hr) | — | 1100 (8–16 hr, f.c.)[f] |
| FABRICATING PROPERTIES | | | | | |
| Hot Working Temp Range, F | | | | | |
| Heavy Forging, Drop Forging | 1600–2300 | 1400–2300 | 1900–2300 | 1700–2150 | 1900–2150 |
| Light Forging | 1200–1600 | 1200–1600 | 1600–1900 | — | — |
| Cutting Speed, fpm[b] | — | — | — | 125–225 | 100–200 |
| Joining | Metallic arc, inert-gas metal arc, oxy-acetylene and resistance welding; silver and copper brazing; soft soldering | | Metallic arc, inert-gas metal arc and resistance welding; silver brazing; soft soldering | Metal arc, inert-gas metal arc, oxy-acetylene and resistance welding; silver and copper brazing; soft soldering | |
| AVAILABLE FORMS | Sheet, strip, rod, bar, shapes, tube, plate, wire | | Strip, rod, bar, shapes, wire | Sheet, strip, rod, bar, shapes, tube, plate | |
| USES | Parts requiring corrosion resistance at high temperatures | Equipment handling molten salts; long time service at 700–1200 F | Parts requiring corrosion resistance and strength at high temperatures | Parts requiring combination of good strength, ductility and corrosion resistance | Parts requiring greater strength and hardness than monel |

[a] Values are for sheet and strip unless otherwise specified.
[b] Surface speed with single point cemented carbide tools.
[c] Rod.
[d] 77–750 F.
[e] 68 F.
[f] Furnace cool.

## Nickel and Its Alloys—Cast

| Type → | Nickel | Inconel | S Inconel | Monel | S Monel |
|---|---|---|---|---|---|
| COMPOSITION, % | Ni 97.00, Cu 0.30, Fe 0.25, Si 1.50, Mn 0.50, C 0.50, S 0.015 | Ni 78.00, Cu 0.25, Cr 13.00, Fe 6.00, Si 2.00, Mn 0.75, C 0.20, S 0.010 | Ni 68.00, Cr 15.00, Fe 7.50, Si 5.50, Mn 0.75, C 0.30 | Ni 67.00, Cu 29.00, Fe 1.25, Si 1.50, Mn 0.75, C 0.15 | Ni 65.00, Cu 28.00, Fe 2.00, Si 4.00, Mn 0.75, C 0.10 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.301 | 0.300 | 0.292 | 0.312 | 0.302 |
| Melting Temp Range, F | 2450–2600 | 2500–2550 | — | 2400–2450 | 2300–2350 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 34.2 | 8.7 | — | 15.5 | 11.3 |
| Coef of Ther Exp (70–1400 F), per °F | $6.8 \times 10^{-6}$ | $8.92 \times 10^{-6}$ | $9.20 \times 10^{-6}$ | $6.8 \times 10^{-6}$ | $6.8 \times 10^{-6}$ |
| Spec Ht (80–750 F), Btu/lb/°F | 0.13 | 0.11 | — | 0.13 | 0.13 |
| Elec Res (32 F), microhm-cm | 20.8 | 11.6 | 12.6 | 53.2 | 65.3 |
| Magnetic Trans Temp, F | 680 | −40 | — | 110–140 | −70 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $21.5 \times 10^6$ | $23 \times 10^6$ | $25 \times 10^6$ | $19 \times 10^6$ | $24.2 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed and Aged | — | — | 75–30 | — | 110–145 |
| As Cast | 45–60 | 70–95 | 90–120 | 65–90 | 110–145 |
| Yld Str (0.5% ext), 1000 psi | | | | | |
| Annealed and Aged | — | — | 55–70 | — | 80–115 |
| As Cast | 20–30 | 30–45 | 80–100 | 32–45 | 80–115 |
| Elong (in 2 in.), % | | | | | |
| Annealed and Aged | — | — | 4–1 | — | 1–4 |
| As Cast | 30–15 | 30–10 | 3–1 | 25–45 | 1–4 |
| Hardness (Brinell) | | | | | |
| Annealed and Aged | — | — | 300–380 | — | 300–380 |
| As Cast | 80–125 | 190 | 300–380 | 125–150 | 275–350 |
| Impact Str (Charpy, rm temp), ft-lb | 60 | 60 | — | 70 | 4 |
| FABRICATING PROPERTIES | | | | | |
| Pouring Temp, F | 2700–2900 | 2800–2950 | 2700–2900 | 2700–2850 | 2650–2800 |
| Pattern Shrinkage, in./ft | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 |
| Weldability | Fabrication or repair by any standard process* | Repair welding by any standard process* | Welding not recommended | Limited amount of repair welding* | Welding not recommended |
| CORROSION RESISTANCE | Good corrosion resistance, especially to hot concentrated caustic soda, and chlorine and fluorine gases | Resistance to nitric acid, ammonium hydroxide and oxidizing conditions superior to that of nickel. Good resistance to oxidation at temperatures up to 2200 F. Good resistance to corrosive vapors above 800 F | | Good resistance to flowing salt water; dilute acids; hydrochloric, hydrofluoric, sulfuric, phosphoric and most organic acids; and strong caustic soda. Not resistant to strongly oxidizing solutions such as nitric acid and ferric chloride | |
| USES | Evaporators, tanks, heating coils, tubular condensers and other processing equipment; magnetostrictive devices; applications in incandescent lamp and radio industries | Dairy equipment, food handling equipment, airplane exhaust manifolds, utensils. Used extensively in oxidizing and carburizing atmospheres at elevated temperatures. Inconel S castings have higher resistance to wear and galling than Inconel | | Valve seats, liners, pump rods, bushings, nozzles, turbine blading, pickling equipment, laundry machines, paper mill and oil refinery equipment, food handling equipment, storage tanks, boilers. Monel S castings have higher resistance to galling and erosion than Monel | |

* For joining by welding, a weldable grade is available.

## Low-Expansion Nickel Alloys—Wrought

| Composition (%)[a] → | Ni 36 | Ni 42 | Ni 47-50 |
|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | |
| Density, lb/cu in. | 0.292 | 0.292 | 0.296 |
| Melting Point, F | 2600 | 2606 | 2600 |
| Ther Cond (68–212 F), Btu/hr/sq ft/°F/ft | 7.8 | 8.9 | 10.3 |
| Coef of Ther Exp, per °F | | | |
| −200 to 0 F | $1.10 \times 10^{-6}$ | $3.42 \times 10^{-6}$ | $5.37 \times 10^{-6}$ |
| 0 to 200 F | $0.70 \times 10^{-6}$ | $3.18 \times 10^{-6}$ | $5.55 \times 10^{-6}$ |
| 200 to 400 F | $1.50 \times 10^{-6}$ | $2.97 \times 10^{-6}$ | $5.55 \times 10^{-6}$ |
| 400 to 600 F | $6.35 \times 10^{-6}$ | $3.15 \times 10^{-6}$ | $5.55 \times 10^{-6}$ |
| 600 to 800 F | $8.61 \times 10^{-6}$ | $5.50 \times 10^{-6}$ | $5.60 \times 10^{-6}$ |
| 800 to 1000 F | $9.48 \times 10^{-6}$ | $8.55 \times 10^{-6}$ | $7.26 \times 10^{-6}$ |
| Specific Heat (77–212 F), Btu/lb/°F | 0.123 | 0.121 | 0.120 |
| Electrical Resistivity (68 F), microhm-cm | 81 | 70 | 48 |
| Poisson's Ratio | 0.290 | 0.290 | 0.290 |
| **MECHANICAL PROPERTIES** | | | |
| Mod of Elast in Tension, psi | $21 \times 10^6$ | $22 \times 10^6$ | $24 \times 10^6$ |
| Tensile Strength, 1000 psi | | | |
| Annealed | 71 | 68 | 77 |
| Cold Worked | 90 | 120 | 140 |
| Yield Point, 1000 psi | | | |
| Annealed | 40 | 39 | 33 |
| Cold Worked | 70 | — | — |
| Elongation (in 2 in.), % | | | |
| Annealed | 43 | 49 | 45 |
| Cold Worked | 20 | — | — |
| Reduction of Area, % | | | |
| Annealed | 75 | 79 | 75 |
| Cold Worked | 60 | — | — |
| Hardness | | | |
| Annealed (Brinell) | 132 | 138 | 144 |
| Cold Worked (Rockwell) | — | B100 | B103 |
| Modulus of Rigidity, psi | $8.1 \times 10^6$ | $8.5 \times 10^6$ | $9.3 \times 10^6$ |
| **FABRICATING PROPERTIES** | | | |
| Annealing Temp, F | Soften progressively in range 1000 to 2300 F | | |
| Hot Working Temp Range, F | To 2300 F | To 2300 F | To 2300 F |
| Machinability | Machine best at a hardness of about Rockwell C20 | | |
| Weldability | Can be welded by acetylene torch, metal arc, carbon arc and resistance methods | | |
| **CORROSION RESISTANCE** | Resistant to atmospheric corrosion and to fresh and salt water | | |
| **AVAILABLE FORMS** | Bar, plate, sheet, strip, wire, tubing, forgings, castings | | |
| **USES** | Length standards, instruments, hypodermic syringes, textile machine parts, thermostatic bimetal — up to 400 F | Higher temperature thermostatic bimetal, instruments, glass sealing — up to 650 F | Higher temperature low expansion applications—up to 1000 F |

[a]Balance Iron.

## Nickel-Base Superalloys

| Type → | Inconel X[a] | Hastelloy B[b] | Hastelloy C[b] | Hastelloy X,[b] Unitemp HX | René-41, R-41[a] |
|---|---|---|---|---|---|
| COMPOSITION, % | Cu 0.05, Cr 15.0, Fe 7.0, Al 0.75, Si 0.40, Ti 2.50, Mn 0.50, C 0.05, S 0.007, Cb 0.90, Ni bal | Co 2.50, Cr 1.0, Mo 26.0–30.0, Fe 4.0–7.0, Si 1.0, Mn 1.0, C 0.05, Ni bal | Co 2.50, Cr 14.5–16.5, Mo 15.0–17.0, W 3.0–4.5, Fe 4.0–7.0, Si 1.0, Mn 1.0, C 0.08, Ni bal | Co 0.5–2.5, Cr 20.5–23.0, Mo 8.0–10.0, W 0.20–1.0, Fe 17.0–20.0, C 0.05–0.15, Si 1.0, Mn 1.0, Ni bal | Cr 18.0–20.0, Co 10.0–12.0, Mo 9.0–10.5, Fe 5.0, C 0.12, Si 0.5, Mn 0.1, Ti 3.0–3.3, Al 1.4–1.6, Ni bal |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.30 | 0.33 | 0.32 | 0.29 | 0.29 |
| Melting Temp Range, F | 2540–2600 | 2408–2462 | 2318–2381 | 2350 | — |
| Ther Cond (1100 F), Btu/hr/sq ft/°F/ft | 13.0 | 9.5 | 9.9 | 15.0 | 11.7 |
| Coef of Ther Exp (70–1600 F), per °F | $9.2 \times 10^{-6}$ | $7.8 \times 10^{-6}$ | $8.2 \times 10^{-6}$ | $9.0 \times 10^{-6}$ | $8.7 \times 10^{-6}$ |
| Specific Ht (70–212 F), Btu/lb/°F | 0.10 | 0.09 | 0.09 | 0.10 | 0.10 |
| Elec Res (75 F), microhm-cm | 122 | 135 | 139 | 118.3 | — |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | | | | | |
| Room Temp | $31 \times 10^6$ | $29.5 \times 10^6$ | $30.9 \times 10^6$ | $28.0 \times 10^6$ | $31.8 \times 10^6$ |
| 1000 F | $25 \times 10^6$ | $32.8 \times 10^6$ | $25.9 \times 10^6$ | $24.3 \times 10^6$ | $27.2 \times 10^6$ |
| 1500 F | $18.5 \times 10^6$ | $22.3 \times 10^6$ | $22.2 \times 10^6$ | — | $24.2 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Room Temp | 162 | 131 | 130 | 114 | 205 |
| 1000 F | 140 | 107 | 106 | 94 | 203 |
| 1500 F | 52 | 53 (1600 F) | 45 (1600 F) | 52 | 135 |
| 1800 F | 9 | — | 26.9 | 21 | 60 (1700 F) |
| Yld Str (0.2% offset), 1000 psi | | | | | |
| Room Temp | 92 | 56.5 | 71.8 | 52.2 | 154 |
| 1000 F | 84 | 41.6 | 53.6 | 41.5 | 147 |
| 1500 F | 44 | 38.7 (1600 F) | 36.5 (1600 F) | 37 | 120 |
| 1800 F | 5.5 | — | — | 17 | 50 (1700 F) |
| Elong (in 2 in.), % | | | | | |
| Room Temp | 24 | 50 | 44 | 43 | 14 |
| 1000 F | 22 | 38 | 27 | 45 | 14 |
| 1500 F | 22 | 11 (1600 F) | 47 (1600 F) | 33.5 | 14 |
| 1800 F | 89 | — | 37.6 | 39 | 26 (1700 F) |
| Hardness, Brinell | | | | | |
| Room Temp | 209 | 209[d] | 218[d] | 187 | — |
| 1000 F | — | 92[d] | 84[d] | — | — |
| Impact Str (Izod), ft-lb | | | | | |
| −320 | 33 | 53[d] | 27[d] | — | — |
| Room Temp | 37 | 58–62[d] | 21–23[d] | — | — |
| Rupture Str (1500 F), 1000 psi | | | | | |
| 10 Hr | 38 | 26[d] | 26[d] | 22[d] | 65[d] |
| 100 Hr | 28 | 16[d] | 18[d] | 14.5[d] | 45[d] |
| 1000 Hr | 18 | 10[d] | 12.5[d] | — | 29[d] |
| THERMAL TREATMENT | | | | | |
| Solution Temp, F | 2100 (2–4 hr, a.c.) | 2150 (a.c.) | 2250 (w.q.) | 2150 (w.q.) | 1950 (4 hr, a.c.) or 2150 (2 hr, a.c.) |
| Aging Temp, F | 1550 (24 hr, a.c.) or 1330 (20 hr, a.c.) | — | — | — | 1650 (4 hr, a.c.) or 1400 (18 hr, a.c.) |
| FABRICATING PROPERTIES | | | | | |
| Hot Working Temp, F | 2225–1900 | 2175–1800 | 2250–1850 | 2200–1800 | 2150–1850 |
| Machinability Index[e] | 15 | 12 | 10 | — | — |
| Weldability | Satisfactory | Good | Good | Excellent | Good |
| AVAILABLE FORMS | Sheet, rod, bar, shapes, tube, plate, wire | Sheet, strip, plate, bar, wire, tubing, electrodes, forgings; sand and investment castings | Sheet, strip, plate, bar, wire, tubing, electrodes, forgings; sand and investment castings | Sheet, plate, bar, wire, electrodes, forgings; sand and investment castings | Sheet, strip, plate, bar, forgings, wire; investment castings |
| USES | Jet engines, missiles, furnaces, etc., where high temperature corrosion resistance is vital | | | | |

[a] Hot rolled bar heat treated as specified unless otherwise indicated.
[b] Sheet 0.109 in. thick heat treated as specified unless otherwise indicated.
[c] Bar solution treated 4 hr at 1950 F, air cooled, aged 16 hr at 1400 F unless otherwise indicated.
[d] Heat treated bar.
[e] Based on AISI B1112 steel = 100.

*continued on next page*

## Nickel-Base Superalloys

| Type → | Udimet 500 | Udimet 700 | Waspaloy | Nicrotung[a] | J-1500 |
|---|---|---|---|---|---|
| COMPOSITION, % | C 0.15 (max), Al 2.5–3.2, Ti 2.5–3.2, Mo 3.0–5.0, Cr 15.0–20.0, Co 13.0–20.0, Fe 4.0, B 0.008 (max), Ni bal | C 0.15 (max), Al 3.75–4.75, Ti 3.0–4.0, Mo 4.5–5.7, Cr 13.0–17.0, Co 17.0–20.0, Fe 1.0, B 0.10 (max), Ni bal | C 0.10 (max), Al 1.3, Ti 3.00, Mo 4.25, Cr 19.50, Co 13.5, Fe 2.0, B 0.005, Zr 0.085, Mn 0.50 (max), Si 0.75 (max), S 0.030 (max), Cu 0.10 (max), Ni bal | C 0.10, B 0.05, Zr 0.05, Cr 12.0, Co 10.0, W 8.0, Al 4.0, Ti 4.0, Ni bal | C 0.15, Cr 20.0, Co 10.0, Mo 10.0, Ti 3.0, Al 1.0, Ni bal |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.29 | 0.28 | 0.29 | 0.30 | 0.29 |
| Ther Cond (1600 F), Btu/hr/sq ft/°F/ft | 14.1 | — | 14.6 | — | 12.4[e] |
| Coef of Ther Exp (1800 F), per °F | $9.8 \times 10^{-6}$ | — | $9.7 \times 10^{-6}$ | $8.8 \times 10^{-6}$ | $7.7 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.10–0.11 | 0.10–0.11 | 0.10–0.11 | — | — |
| Elec Res (70–1800 F), microhm-cm | 121.5–136.5 | 130–148 | — | — | — |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | | | | | |
| Room Temp | $31.2 \times 10^6$ | $32.1 \times 10^6$ | $31.9 \times 10^6$ | $33.5 \times 10^6$ | $29.8 \times 10^6$ |
| 1500 F | $23.3 \times 10^6$ | $23.5 \times 10^6$ | $24.1 \times 10^6$ | $25.7 \times 10^{6b}$ | $21.8 \times 10^6$ |
| 1800 F | $20.6 \times 10^6$ | — | $21.1 \times 10^6$ | — | — |
| Ten Str, 1000 psi | | | | | |
| Room Temp | 175 | 205 | 180 | 130 | 180 |
| 1200 F | 175 | 180 | 165 | 120 | 168 |
| 1500 F | 125 | 130 | 100 | 115 | 106 |
| 1800 F | 40 | 50 | 55 (1700 F) | 67 | 74 (1600 F) |
| Yld Str (0.2% offset), 1000 psi | | | | | |
| Room Temp | 110 | 140 | 120 | 120 | 122 |
| 1200 F | 110 | 125 | 105 | 111 | 108 |
| 1500 F | 90 | 110 | 90 | 102 | 93 |
| 1800 F | 35 | 45 | 50 (1700 F) | 52 | 70 (1600 F) |
| Elong (in 2 in.), % | | | | | |
| Room Temp | 15 | 16 | 29 | 5 | 16 |
| 1200 F | 18 | 15 | 23 | 11 | 11 |
| 1500 F | 22 | 33 | 28 | 4 | 13 |
| 1800 F | 22 | 27 | 36 (1700 F) | 6 | 18 (1600 F) |
| Hardness, Rockwell | | | | | |
| Room Temp | C37 | — | C37 | C38–40 | C38 |
| 800 F | C36 | — | C35 | — | C33 |
| 1000 F | C36 | — | C35 | — | — |
| 1200 F | C32 | — | C35 | — | C33 |
| Fatigue Str ($10^7$ cycles, 1500 F), 1000 psi | 48 | 49 | 40 | 37[c] | 50[f] |
| Rupture Str (1600 F), 1000 psi | | | | | |
| 100 Hr | 32 | 42 | 25 | 48 | 23 |
| 1000 Hr | 21 | 29 | 15 | 36[d] | 14 |
| THERMAL TREATMENT | | | | | |
| Solution Temp, F | 2150 (2 hr, a.c.) or 1975 (4 hr, a.c.) | 2115 (2 hr, a.c.) or 1975 (4 hr, a.c.) | 1975 (4 hr, a.c.) | — | 2100 (4 hr, a.c.) or 1950 (4 hr, a.c.) |
| Aging Temp, F | 1550 (24 hr, a.c.) or 1400 (16 hr, a.c.) | 1550 (24 hr, a.c.) or 1400 (16 hr, a.c.) | 1550 (24 hr, a.c.) or 1400 (16 hr, a.c.) | — | 1400 (16 hr, a.c.) |
| FABRICATING PROPERTIES | | | | | |
| Hot Work Temp, F | 1900–2175 | 1875–2050 | 1850–2150 | Not workable | 1700–2100 |
| Machinability | Satisfactory | Satisfactory | Satisfactory | — | — |
| Weldability | Satisfactory | Satisfactory | Satisfactory | — | Good |
| OXIDATION RESISTANCE | Excellent | Good | Good | Good | Good |
| AVAILABLE FORMS | Bar, wire, billet, plate, sheet, strip | | | Casting alloy | Bar, plate, sheet, wire, forgings |
| USES | Jet engines, missiles, etc., where high temperature corrosion resistance is vital | | | | |

[a] Castings. [b] At 1600 F. [c] $10^6$ cycles at 1700 F. [d] 500 hr. [e] From 70–1500 F. [f] $10^8$ cycles.

## Nickel-Base Superalloys

| Type → | Unitemp 1753 | M-252 | Inconel 700 | Inconel 713C [a] |
|---|---|---|---|---|
| COMPOSITION, % | C 0.24, Mn 0.05, Si 0.10, Cr 16.25, Co 7.20, Mo 1.60, W 8.40, Ti 3.15, Al 1.90, Zr 0.06, B 0.008, Fe 9.50, Ni bal | C 0.16, Mn 0.02, Si 0.08, Cr 19.10, Co 9.95, Mo 9.70, Ti 2.55, Al 1.10, Zr 0.06, B 0.005, Fe 2.10, Ni bal | C 0.16, Mn 0.10, Si 0.25, Cr 15.0, Ti 2.20, Al 3.0, Co 28.0, Mo 3.0, Fe 0.7, Ni bal | C 0.20 max, Mn 1.0 max, Si 1.0 max, Cr 12.5, Mo 4.25, Ti 0.75, Al 6.0, Fe 5.0 max, Cb 2.0, Ni bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.305 | 0.298 | 0.295 | 0.286 |
| Melting Temp Range, F | 2525–2575 | 2470–2500 | — | — |
| Ther Cond (1500 F), Btu/hr/sq ft/°F/ft | — | 12.4 | 10.3 | — |
| Coef of Ther Exp (80–1600 F), °F | $8.6 \times 10^{-6}$ | $7.8 \times 10^{-6}$ [c] | $9.27 \times 10^{-6}$ | $8.3 \times 10^{-6}$ |
| Elec Res, microhm-cm | 132.0 | — | — | — |
| MECHANICAL PROPERTIES [b] | | | | |
| Mod of Elast in Tension, psi | | | | |
| Room Temp | $31.0 \times 10^6$ | $29.8 \times 10^6$ | $32.0 \times 10^6$ | — |
| 1000 F | $26.5 \times 10^6$ | $26.0 \times 10^6$ | $27.7 \times 10^6$ | — |
| 1500 F | $22.8 \times 10^6$ [d] | $21.8 \times 10^6$ | $24.0 \times 10^6$ | — |
| Ten Str, 1000 psi | | | | |
| Room Temp | 177 | 175 | 170 | 117 |
| 1200 F | 161 | 152 | 147 | 118 |
| 1600 F | 79 | 71 | 84 | 98 |
| Yld Str (0.2% offset), 1000 psi | | | | |
| Room Temp | 103 | 98 | 104 | 105 |
| 1200 F | 99 | 92 | 92 | 105 |
| 1600 F | 60 (1650 F) | 71 | 56 | 80 |
| Elongation (in 2 in.), % | | | | |
| Room Temp | 20.5 | 25.0 | 25.0 | 6.0 |
| 1200 F | 24.0 | 35.5 | 23.0 | 5.0 |
| 1600 F | 19.5 | 39.5 | 7.0 | 8.0 |
| Red. of Area, % | | | | |
| Room Temp | 21.5 | — | 27.0 | — |
| 1200 F | 23.2 | 27.0 | 37.0 | — |
| 1600 F | 35.0 | 55.5 | 8.0 | — |
| Fatigue Str ($10^8$ cycles), 1000 psi | | | | |
| 1300 F | 58 (1350 F) | 60 | — | — |
| 1500 F | 48 | 50 | — | — |
| Rupture Str (1500 F), 1000 psi | | | | |
| 10 Hr | 60 | 48 | 55 | 70 |
| 100 Hr | 47 | 38 | 42 | 56 |
| 1000 Hr | 34 | 23 | 31 | 43 |
| FABRICATING PROPERTIES | | | | |
| Hot Working Temp, F | 1850–2150 | 1800–2150 | — | — |
| Machinability [e] | Poor | Poor | 8 | 6 |
| Weldability | Limited data | Limited data | Weldable | Rarely welded |
| CORROSION RESISTANCE | Excellent res to jet engine gases up to 1600 F; very good res to salt spray. Good oxidation res under continuous operation up to 1900 F | | Good corrosion and oxidation resistance up to 1600 F | Excellent res to oxidation at 1700 F |
| AVAILABLE FORMS | Bar, billet, forgings, sheet, wire | | Bar, forgings | Investment castings |
| USES | Jet engine turbine buckets, wheels; high temp bolts and fasteners; airframes | | Aircraft engine blades and other high temp components | Aircraft gas turbine blades and vanes, and other high temp applications |

[a] Casting alloy.

[b] Properties for materials in the following conditions:
Unitemp 1753: Bar solution treated 4 hr at 2150 F, air cooled, aged 16 hr at 1650 F, air cooled.
M-252: solution treated 4 hr at 1950 F, air cooled, aged 15 hr at 1400 F, air cooled.
Inconel 700: rod solution treated 2 hr at 2160 F, air cooled, aged 4 hr at 1600 F, air cooled.
Inconel 713C: as cast bar.

[c] Based on AISI B1112 steel = 100. [d] 1600 F. [e] 70–1500 F.

## Precious Metals—Wrought

| Metal → | Gold[a] | Silver[b] | Platinum[c] | Palladium[b] |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Density, lb/cu in. | 0.698 | 0.379 | 0.775 | 0.434 |
| Melting Point, F | 1945 | 1761 | 3224 | 2829 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 172 | 242 | 42 | 41 |
| Coef of Ther Exp (32-212 F), per °F | $7.9 \times 10^{-6}$ | $10.9 \times 10^{-6}$ | $4.9 \times 10^{-6}$ | $6.5 \times 10^{-6}$[a] |
| Spec Ht, Btu/lb/°F | 0.031 | 0.056 | 0.031 | 0.058 |
| Elec Res (32 F), microhm-cm | 2.35 | 1.59[d] | 14.9 | 10.8[a] |
| **MECHANICAL PROPERTIES** | | | | |
| Mod of Elast in Tension, psi | $12 \times 10^6$ | $11 \times 10^6$ | $21 \times 10^6$ | $17 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Annealed | 19 | 22 | 17-26 | 30 |
| Cold Worked | 32[e] | 54[f] | 34-45 | 47 |
| As Cast | 18 | 15 | — | — |
| Yld Str, 1000 psi | | | | |
| Annealed | Nil | 8 | 2-5.5 | 5 |
| Cold Worked | 30 | 44 | 27 | 30 |
| As Cast | — | 5 | — | — |
| Elong (in 2 in.), % | | | | |
| Annealed | 45 | 48 | 30-40 | 24-40 |
| Cold Worked | 4 | 2.5 | 2.5-3.5 | 1.5 |
| As Cast | 30 | 60 | — | — |
| Red. of Area (as cast), % | — | 67 | — | — |
| Hardness (Brinell) | | | | |
| Annealed | 25 | 25-35 | 38-52 | 46 |
| Cold Worked | 58 | — | 97-13 | 109 |
| As Cast | 33 | 42 | — | — |
| Endurance Limit ($10^7$ cycles, annealed), 1000 psi | 4.6 | — | — | — |
| **FABRICATING PROPERTIES** | | | | |
| Annealing Temp, F | — | 400-600 | 1475-2200 | 1475 |
| Hot Working Temp Range, F | Any to melting point | — | 1475-2300 | 1475-2300 |
| Max Red. Between Anneals, % | Apparently unlimited | — | 99 | 99 |
| Casting Temp Range, F | 2000-2370 | 2000 | 3300 | 3000 |
| Joining | Braze with silver solder, no flux, any flame. Can be resistance welded by any method. Oxyacetylene weld with no flux, any flame | Braze with silver solder. Can be resistance welded | Braze with fine gold or white platinum solder. Hammer weld at 1800 F. Can be resistance or oxyacetylene welded | Braze with oxyacetylene torch using platinum solders. Can be resistance welded |
| **CORROSION RESISTANCE** | Does not oxidize when heated in air. Resists alkalis, salts and most acids. Not attacked by oxygen or sulfur. Rapidly attacked by chlorine and bromine | Does not oxidize when heated in air. Resists most dilute mineral acids and alkalis. Attacked rapidly by nitric and hot sulfuric acids. Attacked rapidly by sulfur-bearing gases | Does not oxidize when heated in air. Resists reducing or oxidizing acids alone but is dissolved by aqua regia | Oxidizes when heated in air. Resists hydrofluoric, acetic and phosphoric acids. Attacked by nitric, sulfuric and hydrochloric acids; and bromine and iodine |
| **AVAILABLE FORMS** | Foil, rod, wire, sheet, tubing | Sheet, strip, rod, wire, tubing | Foil, sheet, wire, tubing | Sheet, foil, wire, tubing |
| **USES** | Lining of chemical equipment, high melting solder, alloys for electrical and chemical purposes, jewelry, dentistry | Electrical contacts, corrosion resisting equipment, bearings, photography supplies; alloying for coinage, brazing alloys, jewelry | Chemical equipment, electrical contacts, catalysts, laboratory equipment, jewelry | Electrical contacts, catalysts, production of pure hydrogen, jewelry, dental alloys |

[a]Gold is generally produced in three grades: proof gold, 99.99% Au; refined gold, 99.95-99.98% Au; and 99.5% Au, which is accepted by the U.S. Mint without penalty.
[b]Usually refined to "the high purity suitable for general use"; in some cases spectographically pure.
[c]Platinum is produced in four grades: type A, 99.99% Pt, sometimes called physically pure; type B, 99.9% Pt, sometimes called chemically pure; type C, 99.5% Pt (crucible grade); and type D, 99% Pt (commercial platinum).
[d]68 F. [e]Cold rolled, 60% reduction. [f]Cold rolled, 50% reduction.

## Precious Metals—Cast, Wrought

| Metal → | Rhodium[b] | Ruthenium[b] | Osmium[b] | Iridium[b] |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Density, lb/cu in. | 0.447 | 0.441 | 0.82 | 0.813 |
| Melting Point, F. | 3571 | 4530 | 4890 | 4450 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft. | 50 | — | — | 34 |
| Coef of Ther Exp (68 F), per °F. | $4.6 \times 10^{-6}$ | $5.1 \times 10^{-6}$ | $3.6 \times 10^{-6}$ | $3.8 \times 10^{-6}$ |
| Specific Heat, Btu/lb/°F. | 0.059 | 0.057 | 0.031 | 0.031 |
| Elec Res (68 F), microhm-cm. | 4.51 | 7.6[a] | 9.5 | 5.3 |
| **MECHANICAL PROPERTIES** | | | | |
| Mod of Elast in Tension, psi. | $42 \times 10^6$ | $60 \times 10^6$ | $80 \times 10^6$ | $74 \times 10^6$ |
| Ten Str, 1000 psi | | | | |
| Annealed. | 73 | — | — | — |
| Cold Worked. | 300 | — | — | — |
| Hardness (Brinell) | | | | |
| Annealed. | 55–156 | — | — | 170 |
| Cold Worked. | 260–390 | — | — | 350 |
| As Cast. | — | 220 | 350 | 163 |
| **FABRICATING PROPERTIES** | | | | |
| Hot Working Temp Range, F. | 1900–2000 | 2700–4300 | Not workable | 2200–2700 |
| Max Red. Between Anneals, % | 30–40 | — | — | — |
| Casting Temp, F. | 3700 | 4700 | 5000 | 4600 |
| Joining. | Can be brazed and resistance welded | Can be brazed and resistance welded | Can be brazed and resistance welded | Can be brazed and resistance welded |
| **CORROSION RESISTANCE** | Oxidizes slowly when heated in air. Resistant to most acids, including aqua regia at room temperature | Oxidizes when heated in air. Unattacked by common acids, including aqua regia up to 212 F. Moderately attacked by solutions of alkaline hypochlorites | Oxidizes rapidly in air at elevated temperatures. Resists common acids at room temperatures, but is attacked by aqua regia | Oxidizes slowly when heated in air. Unattacked by common acids, including aqua regia up to 212 F |
| **AVAILABLE FORMS** | Powder, sheet, wire | Powder | Cast or sintered parts | Sheet, wire, rod, powder |
| **USES** | Mirrors and electrodeposits for a nontarnishing finish; alloys with platinum and palladium for crucibles, glassworking equipment, catalysts, spinnerets | Hardener for platinum and palladium | Alloys used for pen tips, phonograph needles, electrical contacts, instrument pivots | Extrusion dies for glass, alloys with platinum for electrical contacts, fuse wires, hypodermic needles, jewelry |

[b]Usually refined to "the high purity suitable for general use"; in some cases spectrographically pure.
[a]At 32 F.

## Tin and Its Alloys—Cast, Wrought

| Type → | Grade A Tin | Hard Tin | Tin Foil | White Metal | Pewter |
|---|---|---|---|---|---|
| COMPOSITION, % | Sn 99.8 min | Sn 99.6, Cu 0.4 | Sn 92, Zn 8 | Sn 92, Sb 8 | Sn 91, Sb 7, Cu 2 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.264 | — | — | 0.262 | 0.263 |
| Melting Temp Range, F | 449.4 | 441–446 | 390 | 475 | 471–563 |
| Ther Cond (77 F), Btu/hr/sq ft/°F/ft | 37 | — | 34 | — | — |
| Coef of Ther Exp (32–212 F), per °F | $13 \times 10^{-6}$ | — | — | — | — |
| Spec Ht, Btu/lb/°F | 0.054 | — | — | — | — |
| Elec Res (68 F), microhm-cm | 11.5 | — | 12 | 15 | — |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $6–6.5 \times 10^6$ | — | — | — | $7.7 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed Sheet | 2.2 | 3.3 | — | 6.7 | 8.6 |
| Cold Rolled Sheet | 2.8 | 4.0 | 8.7 | 7.4[b] | 7.6 |
| As Cast | 2.1 | — | — | 7.2[c] | — |
| Yld Str, 1000 psi | | | | | |
| Annealed Sheet | 1.3 | — | — | — | — |
| Cold Rolled Sheet | 2.0 | — | 6.0 | — | — |
| As Cast | 1.7 | — | — | — | — |
| Elong (in 2 in.), % | | | | | |
| Annealed Sheet | 45 | — | — | 70 | 40 |
| Cold Rolled Sheet | 35 | — | 40 | 28[b] | 50 |
| As Cast | 55[a] | — | — | — | — |
| Hardness (Brinell) | | | | | |
| Annealed Sheet | 7 | — | — | 17 | 13[d, f] |
| Cold Rolled Sheet | 8 | — | — | — | 18[e, f] |
| As Cast | 5–6 | — | — | 20[c] | 23[d, f] |
| Impact Str (Izod, as cast), ft-lb | 14 | — | — | 22[c] | — |
| Endurance Limit (as cast), 1000 psi | 0.34 | — | — | — | — |
| FABRICATING PROPERTIES | | | | | |
| Casting Temp Range (chill), F | 525–550 | 525–550 | — | 575–600 | 600–625 |
| Joining | Bonds easily by simple melting. Eutectic tin-lead solder or low melting fusible alloys might be used on massive parts such as block tin pipe | | — | Readily soldered | Can be soldered with some of the fusible alloys |
| CORROSION RESISTANCE | Resists distilled, sea and soft tap water. Attacked by strong acids, alkalis and acid salts. Oxygen in solution accelerates rate of attack | | — | — | Tarnishes in soft water; suffers localized attack at water line in hard water. Attacked by dilute hydrochloric and citric acids in presence of air |
| AVAILABLE FORMS | Sheet, pipe, foil, castings, powder | Tubing, foil | Foil | Castings, sheet | Castings, sheet |
| USES | Linings for food cans; pipe for handling water, beer, and carbonated beverages; linings for food processing equipment, food wrappings | Collapsible tubes, foil | Foil for wrapping food, medicines, electrical condensers | Rubber mold castings, cast and wrought costume jewelry | Mountings and ornamental objects such as tea and coffee services, vases and book ends |

[a] In 4 in.
[b] Sheet quenched from 425 F.
[c] Chill cast.
[d] Vickers pyramid hardness.
[e] Vickers pyramid hardness after heat treating 3 hr at 300 F.
[f] Hardenable pewter values are: 13, 28, 29, respectively.

## Tin-Lead-Antimony Alloys—Cast

| Grade[a] → | 1[b] | 2 | 3 | 4 | 5[c] |
|---|---|---|---|---|---|
| COMPOSITION, % | Sn 91, Sb 4.5, Cu 4.5 | Sn 89, Sb 7.5, Cu 3.5 | Sn 84, Sb 8, Cu 8 | Sn 75, Pb 10, Sb 12, Cu 3 | Sn 65, Pb 18, Sb 15, Cu 2 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.265 | 0.267 | 0.269 | 0.272 | 0.280 |
| Melting Temp Range, F | 433–700 | 466–669 | 464–792 | 363–583 | 358–565 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | 7.3 x 10⁶ | 7.6 x 10⁶ | — | — | — |
| Ten Str, 1000 psi | | | | | |
| Chill Cast | 9.3 | 11 | 10–12 | — | — |
| Die Cast | 10.3 | — | — | — | 11.8 |
| Elong (in 2 in., die cast), % | 22 | — | — | — | 4 |
| Hardness (Brinell) | | | | | |
| Chill Cast | 17 | 24 | 27 | 25 | 22 |
| Die Cast | — | — | — | — | 27.7 |
| Impact Str (Izod, chill cast), ft-lb | 2.5 | — | 1 | — | — |
| Endur Limit (chill cast), 1000 psi | 3.8[d] | 4.8[d] | — | — | — |
| Compr Str (chill cast, 25% set), 1000 psi | 13 | 15 | 18 | 16 | 15 |
| Compr Yld Str (chill cast, 0.125% set), 1000 psi | 4.4 | 6.1 | 6.6 | 5.5 | 5.0 |
| FABRICATING PROPERTIES | | | | | |
| Casting Temp Range (chill), F | 750–825 | 795 | 850–915 | 710 | 690–700 |
| CORROSION RESISTANCE | Resists oxidation products of lubricants; food products, beer and carbonated beverages | Resist oxidation products of lubricants | | | |
| AVAILABLE FORMS | Precision inserts of babbitt-lined strip, lined bearing shells, ingots, die castings | | | Ingots | Ingots, die castings |
| USES | Bearings, die castings for dairy machinery, dental appliances, surgical instruments, soda fountain equipment | Most widely used tin-base bearing alloy in automotive field | High load applications, hardest of standard tin babbitts and has greatest load carrying capacity | Limited bearing applications | Limited bearing applications Die cast parts |

[a] ASTM B23–49.
[b] Also die casting Alloy 1, ASTM B102-48.
[c] Also die casting Alloy 3, ASTM B102-48.
[d] 2 x 10⁷ cycles.

**continued on next page**

## Tin-Lead-Antimony Alloys—Cast

| Grade[a] → | 6 | 7 | 8 | 10 | 11 |
|---|---|---|---|---|---|
| COMPOSITION, % | Sn 20, Sb 15, Pb 63.5, Cu 1.5 | Sn 10, Sb 15, Pb 75 | Sn 5, Sb 15, Pb 80 | Sn 2, Sb 15, Pb 83 | Sb 15, Pb 85 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.336 | 0.350 | 0.361 | 0.362 | 0.370 |
| Melting Temp Range, F | 358-531 | 464-514 | 459-522 | 468-507 | 471-504 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | — | 14 | 14 | — | — |
| Coef of Ther Exp (68-212 F), per °F | — | $10.9 \times 10^{-6}$ | $13 \times 10^{-6}$ | — | — |
| Spec Ht, Btu/lb/°F | — | 0.065 | 0.065 | — | — |
| Elec Res (68 F), microhm-cm | — | 28.6 | 28.2 | — | — |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | — | $4.2 \times 10^6$ | $4.2 \times 10^6$ | — | — |
| Ten Str, 1000 psi[a] | — | 10.5 | 10 | — | 6.8 |
| Elong (in 2 in.), %[a] | — | 4 | 5 | — | 8 |
| Hardness (Brinell)[a] | 21 | 22 | 20 | 18 | 15 |
| Endurance Limit, 1000 psi[a] | — | 4[d] | 3.9[d] | — | — |
| Compr Str (25% deformation), 1000 psi[a] | 14.5 | 15.6 | 15.6 | 15.4 | 12.8 |
| Compr Yld Str (0.125% set), 1000 psi[a] | 3.8 | 3.6 | 3.4 | 3.4 | 3.0 |
| FABRICATING PROPERTIES | | | | | |
| Casting Temp (chill), F | 655 | 640 | 645 | 630 | 630 |
| CORROSION RESISTANCE | Resistant to corrosion by the usual lubricants | | | | |
| AVAILABLE FORMS | Small ingots and bars | | | | |
| USES[f] | General purpose bearing applications | General purpose bearings under moderate loads | Bearings for light loads and moderate speeds. Mining machinery, transmission machinery, car journals | Bearings for light loads and speeds. Blowers, pumps, electric motors, machine tools | Bearings for light loads |

[a]ASTM B23-49.
[d]$2 \times 10^7$ cycles.
[e]Chill cast.
[f]Light loads—under 1000 psi; moderate loads—1000 to 2000 psi; heavy loads—over 3000 psi. Surface speeds: low—to 10 fps; moderate—to 20 fps; high—above 30 fps.

## Tin-Lead-Antimony Alloys—Cast

| Grade[a] → | 12 | 15 | 16 | 19 |
|---|---|---|---|---|
| COMPOSITION, % | Sb 10, Pb 90 | Sn 1, Sb 15, Cu 0.5, As 1.0, Pb bal | Sn 10, Sb 12.5, Cu 0.5, Pb bal | Sn 5, Sb 9, Pb bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.384 | 0.362 | 0.355 | 0.378 |
| Melting Temp Range, F | 473-498 | 479-538 | 471-495 | 462-495 |
| Coef of Ther Exp (68-212 F), per °F | $14.6 \times 10^{-6}$ | — | — | — |
| Specific Heat, Btu/lb/°F | 0.065 | — | — | 0.065 |
| Elec Res (68 F), microhm-cm | 25.6 | — | — | 28.7 |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | — | $4.2 \times 10^6$ | — | $4.2 \times 10^6$ |
| Tensile Strength, 1000 psi[c] | — | 10.4 | — | 10 |
| Elongation (in 2 in.), %[c] | — | 2 | — | 5 |
| Hardness (Brinell)[c] | 14 | 21 | 28 | 18 |
| Endurance Limit, 1000 psi[c] | — | 4.3[d] | — | 3.7[f] |
| Compressive Strength (25% deformation), 1000 psi[c] | 12.9 | — | — | 15.6 |
| Compressive Yield Strength (0.125% set), 1000 psi[c] | 2.8 | — | — | — |
| FABRICATING PROPERTIES | | | | |
| Casting Temp (chill), F | 625 | 660 | 620 | 620 |
| CORROSION RESISTANCE | Resistant to corrosion by the usual lubricants | | | |
| AVAILABLE FORMS | Small ingots and bars | | | |
| USES[f] | Bearings for light loads | Bearings for high loads and speeds. Diesel engines, automotive engines, steamships, various types of machines | Bearings for moderate loads and speeds | Bearings for light loads and speeds. Car journal bearings |

[a] ASTM B23-49.
[c] Chill cast.
[f] Light loads—under 1000 psi; moderate loads—1000 to 2000 psi; heavy loads—over 3000 psi. Surface speeds: low—to 10 fps; moderate—to 20 fps; high—above 30 fps. $2 \times 10^7$ cycles.

## Titanium and Its Alloys—Wrought

| Type → | Unalloyed | 5 Al–2.5 Sn | 8 Mn | 3 Mn–1.5 Al | 4 Mn–4 Al |
|---|---|---|---|---|---|
| COMPOSITION, % | Ti 99.0 | Al 5.0, Sn 2.5 | Mn 8.0 | Al 1.5, Mn 3.0 | Al 4.0, Mn 4.0 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.163 | 0.161 | 0.171 | 0.168 | 0.163 |
| Melting Temp Range, F | 3135 | 2822–3002 | 2730–2970 | — | 2822–3002 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 9.8 | 4.85 | 6.7 | — | 4.5 |
| Coef of Ther Exp (68–1650 F), per °F | $5.8 \times 10^{-6}$ | $5.7 \times 10^{-6}$ | $7.1 \times 10^{-6}$ | — | $5.7 \times 10^{-6}$ |
| Spec Ht (68 F), Btu/lb/°F | 0.125 | 0.127 | 0.118 | — | 0.129 |
| Elec Res (68 F), microhm-cm | 55.0 | 157.3 | 90.7 | — | 146.1 |
| Magnetic Permeability (20 oersteds) | 1.00005 | 1.00005 | 1.00005 | — | 1.00005 |
| MECHANICAL PROPERTIES[a] | | | | | |
| Mod of Elast ih Tension, psi | $15–16 \times 10^6$ | $16–17.5 \times 10^6$ | $15.5–17.5 \times 10^6$ | $15 \times 10^6$ | $15.5–17.5 \times 10^6$ |
| Ten Str, 1000 psi | 80–110 | 115–145 | 120–150 | 125 | 140–170 |
| Yld Str, 1000 psi | 70–95 | 110–135 | 110–140 | 116 | 130–160 |
| Elong (in 2 in.), % | 15–25 | 10–20 | 10–20 | 18 | 10–20 |
| Red. of Area, % | 30–45 | 20–40 | 20–40 | — | 20–40 |
| Hardness (Rockwell) | — | C30–35 | C28–34 | C26–32 | C32–38 |
| Impact Str (Charpy), ft-lb | 20–35 | 15–25 | — | 15–20 | 11–15 |
| Endurance Limit, 1000 psi | | | | | |
| Sheet (unnotched) | 60–70 | 95 | 90 | — | — |
| Bar (unnotched) | 60–70 | — | — | — | 85–95 |
| Bar (notched) | 35–45 | — | — | — | 32[f] |
| Compr Yld Str, 1000 psi | 75–100 | 115–140 | 115–145 | — | — |
| Mod of Rigidity, psi | $5.6 \times 10^6$ | — | $6 \times 10^6$ | — | $6.27 \times 10^6$ |
| THERMAL TREATMENT | | | | | |
| Annealing Temp, F | 850–1250 | 1500–1600 | 1300 | 1250 | 1300 |
| Stress Relieving Temp, F | 700–1000 | 1000–1200 | <700 or at 1000 | — | 1000 |
| FABRICATING PROPERTIES | | | | | |
| Hot Working Temp Range, F | 300–800 | 800–1200 | 500–600 | — | — |
| Forging Temp, F | 1300–1600 | 1400–1900 | — | 1300–1700 | 1300–1750 |
| Fusion Weldability[d] | Yes | Yes | No | Marginable | Questionable |
| Formability (sheet, 78 F)[e] | High | Intermediate | Good | Moderate | Bar only |
| Bend Radius (105° V) | 3T | 4.5T | 3.5T | — | — |
| CORROSION RESISTANCE | Superior resistance to nitric acid, moist chlorine, chlorine solutions, chlorinated organic compounds, and inorganic chloride solutions. Excellent resistance to corrosive attack by sea water and most chloride salt solutions—unchallenged by other structural metals. Resists impingement, pitting attack | | | | |
| AVAILABLE FORMS | Sheet, strip, plate, tubing, billets, bar, wire | Sheet, strip, plate, wire, bar | Sheet, strip, plate | Sheet, plate, billets, bar, wire | Billets, bar, forgings, plate, wire |
| USES | Aircraft and missile parts requiring corrosion resistance and high strength-to-weight ratio up to 800 F. Naval and marine applications; chemical, pharmaceutical and food processing and handling equipment; marine diesel engine mufflers; springs (high proportional limit and low modulus of elasticity), rivets, bolts, nuts, screws and fittings; ordnance and sporting equipment; orthopedic and orthodontic equipment; anodes | | | | |

[a] Annealed condition unless otherwise stated.
[d] Some users report difficulty in producing welds without porosity; others do not.
[e] All titanium sheet is formed with considerably less difficulty at elevated temperatures. Forming can be accomplished at temperatures in the 500 to 1000 F range with no need for postforming surface treatment, provided time at temperature is short.
[f] k = 3.9

## Titanium and Its Alloys—Wrought

| Type → | 7 Al–4 Mo | 16 V–2.5 Al | 4 Al–3 Mo–1 V | 13 V–11 Cr–3 Al | 6 Al–4 V |
|---|---|---|---|---|---|
| COMPOSITION, % | Al 7.0, Mo 4.0 | V 16.0, Al 2.5 | Al 4.0, Mo 3.0, V 1.0 | V 13.0, Cr 11.0, Al 3.0 | Al 5.5–6.3, V 3.5–4.5 |
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.162 | 0.168 | 0.161 | 0.175 | 0.160 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | — | — | — | 4.3 | 4.3 |
| Coef of Ther Exp (68–1650 F), per °F | 4.9 x $10^{-6}$ [f] | — | — | 5.2 x $10^{-6}$ [f] | 5.8 x $10^{-6}$ |
| Spec Ht (212 F), Btu/lb/°F | 0.123(68 F) | — | — | 0.128 | 0.135 |
| Elec Res (68 F), microhm-cm | 175 | — | — | — | 176 |
| MECHANICAL PROPERTIES[a] | | | | | |
| Mod of Elast in Tension (200 F), psi | 15.5–17.5 x $10^6$ | 15 x $10^6$ | — | 13–15 x $10^6$ | 15–17 x $10^6$ |
| Ten Str (68 F), 1000 psi | | | | | |
| Annealed | 145–170 | 110–115 | 140 | 125–150 | 130–155 |
| Heat Treated | 160–200 | 175–180 | 190 | 190–240 | 170 |
| Yld Str (68 F), 1000 psi | | | | | |
| Annealed | 135–160 | 40–55 | 90 | 120–145 | 120–150 |
| Heat Treated | 150–190 | 160–165 | 168 | 170–220 | 150 |
| Elong (in 2 in.), % | | | | | |
| Annealed (68 F) | 10–18 | 15–20 | 16 | 10–20 | 10–20 |
| Heat Treated | 5–12 | 6–10 | 8 | 3–10 | 7–12 |
| Red. of Area (68 F), % | | | | | |
| Annealed | 20–40 | 65 | — | 20–40 | 25–40 |
| Heat Treated | 10–25 | 35 | — | — | 20–35 |
| Hardness (Rockwell) | | | | | |
| Annealed | 32–38 | — | — | — | C30–36 |
| Heat Treated | — | — | — | — | — |
| Impact Str (Charpy, 68 F), ft-lb | 10–20 | — | — | — | 15–25 |
| Endurance Limit ($10^8$ cycles), 1000 psi | | | | | |
| Bar (unnotched) | 93 | — | — | — | 75 |
| Bar (notched) | 29 | — | — | — | 30 |
| Sheet (notched) | — | — | — | 34 | — |
| Shear Str, 1000 psi | 104–115 | — | — | — | — |
| THERMAL TREATMENT | | | | | |
| Annealing Temp, F | 1450–1650 | — | 1500–1675 | 1450 | 1350 |
| FABRICATING PROPERTIES | | | | | |
| Hot Working Temp Range, F | — | — | — | 200–400 | — |
| Forging Temp, F | 1400–1850 | — | — | — | 1450–1750 |
| Fusion Weldability[d] | No | — | Limited | Yes | Marginal |
| Formability (sheet, 78 F)[e] | — | High | High | High | Intermediate |
| Bend Radius (105° V) | — | — | 3.5T | 3.5T | 5.0T |
| CORROSION RESISTANCE | Superior resistance to nitric acid, moist chlorine, chlorine solutions, chlorinated organic compounds and inorganic chloride solutions. Excellent resistance to sea water and most chloride salt solutions unchallenged by other structural metals. Resist impingement, pitting attack | | | | |
| AVAILABLE FORMS | Bar, rod, forgings, plate, wire, billet | Sheet, bar | Sheet, strip, plate | Sheet, strip, wire, bar, billet | Bar, sheet, strip, billet, plate, wire |
| USES | Aircraft and missile parts requiring corrosion resistance and high strength-to-weight ratio up to 800 F. Naval and marine applications; chemical, pharmaceutical and food processing and handling equipment; marine diesel engine mufflers; springs (high proportional limit and low modulus of elasticity), rivets, bolts, nuts, screws and fittings; ordnance and sporting equipment; orthopedic and orthodontic equipment; anodes | | | | |

[a] Annealed condition unless otherwise stated. [b] 60-deg notch, 0.010-in. radius, k = 2.7. [c] k = 4.0.
[d] Some users report difficulty in producing welds without porosity; others do not.
[e] All titanium sheet is formed with considerably less difficulty at elevated temperatures. Forming can be accomplished at temperatures in the 500 to 1000 F range with no need for postforming surface treatment, provided time at temperature is short.
[f] 68-200 F.

## Zinc Alloys—Wrought

| Type → | Commercial Rolled Zinc (deep drawing) | Commercial Rolled Zinc | Commercial Rolled Zinc (higher Pb, Cd) | Copper Hardened Rolled Zinc Alloy | Rolled Zinc Alloy (Cu, Mg) | Rolled Zinc Alloy (Cu, Ti) |
|---|---|---|---|---|---|---|
| COMPOSITION, % | Pb 0.10 max, Zn bal | Pb 0.05–0.10, Cd 0.05–0.08, Zn bal | Pb 0.25–0.50, Cd 0.25–0.45, Zn bal | Cu 0.85–1.25, Zn bal | Cu 0.85–1.25, Mg 0.006–0.016, Zn bal | Cu 0.50–1.5, Ti 0.12–0.50, Zn bal |
| PHYSICAL PROPERTIES | | | | | | |
| Density, lb/cu in. | 0.258 | 0.258 | 0.258 | 0.259 | 0.259 | 0.259 |
| Melting Point, F | 786 | 786 | 786 | 792 | 792 | 792 |
| Ther Cond (64 F), Btu/hr/sq ft/°F/ft | 62.2 | 62.2 | — | — | 60.5 | 60.5 |
| Coef of Ther Exp, per °F | | | | | | |
| With Grain | $18.1 \times 10^{-6}$ | $18.1 \times 10^{-6}$ | $18.8 \times 10^{-6}$ | — | $19.3 \times 10^{-6}$ | $13.8 \times 10^{-6}$ |
| Across Grain | $12.8 \times 10^{-6}$ | $12.8 \times 10^{-6}$ | $13.0 \times 10^{-6}$ | — | $11.7 \times 10^{-6}$ | $10.8 \times 10^{-6}$ |
| Spec Ht (68–212 F), Btu/lb/°F | 0.094 | 0.094 | 0.094 | 0.0957 | 0.0957 | 0.0957 |
| Elec Res (68 F), microhm-cm | | | | | | |
| Hot Rolled | 6.06 | — | — | 6.22 | 6.31 | 6.24 |
| Cold Rolled | 6.10 | — | — | — | — | — |
| MECHANICAL PROPERTIES[a] | | | | | | |
| Ten Str, 1000 psi | | | | | | |
| Hot Rolled | 19.5, 23 | 21, 25 | 23, 29 | 24, 30 | 29, 40 | 32, 42 |
| Cold Rolled | 21, 27 | 22, 29 | 25, 31 | 31, 40 | 36, 46 | 29, 37 |
| Elong (in 2 in.), % | | | | | | |
| Hot Rolled | 65, 50 | 52, 30 | 50, 32 | 50, 35 | 20, 10 | 38, 21 |
| Cold Rolled | 50, 40 | 40, 30 | 45, 28 | 44, 30 | 25, 10 | 44, 60 |
| Hardness (Brinell) | | | | | | |
| Hot Rolled | 38 | 43 | 47 | 52 | 61 | — |
| Endurance Limit (hot rolled), 1000 psi | 2.5 | 3.8 | 4.1 | 6.1 | 6.8 | — |
| Creep Rate (12,000 psi, 77 F), days/% | | | | | | |
| Hot Rolled | — | — | — | 0.15 | — | 115.0 |
| FABRICATING PROPERTIES | | | | | | |
| Hot Working Temp Range, F | 248–527 | 248–527 | 248–437 | 447–572 | 447–572 | 382–572 |
| Melting Range, F | 887–977 | 887–977 | 887–977 | 887–977 | 887–977 | 887–977 |
| Ingot Casting Range, F | 815–905 | 815–905 | 815–905 | 815–905 | 815–905 | 815–905 |
| Annealing Temp, F | — | — | 221 | 347 | 347 | 482 |
| Machinability | Good | Good | Good | Good | Good | Good |
| Joining | | | | | | |
| Torch Welding | Poor to fair | Poor to fair | Poor to fair | Poor to fair | Poor to fair | Good |
| Single Impulse Resistance Welding | Poor | Poor | Poor | Poor | Poor | Good |
| Multiple Impulse Resistance Welding | Fair to good | Fair to good | Fair to good | Fair to good | Fair to good | Good |
| Soldering | Good | Good | Good | Good | Good | Good |
| Common Processes | Drawing, bending, roll forming, stamping, swaging, coining, extruding | | | | | |
| | Impact extrusion | | | | | |
| | Spinning | | | | | |
| CORROSION RESISTANCE | Excellent resistance to both metropolitan and rural atmospheric corrosion (penetration in in. per yr is 0.000064 in Palmerton, Pa., and 0.00028 in New York City); also hot soapy water, printing inks, trichloroethylene, carbon tetrachloride, dry illuminating gas, and moisture- and acid-free hydrocarbons. Fair resistance to pure ethyl and methyl alcohols, glycerine, water, petroleum products. Poor resistance to steam, spray insecticides, animal oils, strong acids and bases, and mixtures of glycerine or alcohol and water | | | | | |
| AVAILABLE FORMS | Rolled plate, strip and sheet; extruded rod and shapes; drawn rod and wire | | | | | |
| USES | Dry batteries, eyelets and grommets, address plates, flashing, weatherstrip, laundry tags, novelties, lithoplates, condenser cans, embossing tape, leaders and gutters, corrugated roofing | | | | | |
| | Parts requiring no rigidity | Parts requiring some rigidity | | Parts requiring maximum rigidity | Parts requiring maximum rigidity and some creep resistance | Parts requiring maximum rigidity and creep strength; low thermal expansion; resistance to grain growth |

[a] Two values represent properties parallel to grain and perpendicular to grain, in that order.

## Zinc Alloys—Cast

| Type → | Alloy XXIII[a] | Alloy XXV[a] | Slush Casting Alloy[b] | Slush Casting Alloy (unbreakable metal)[b] |
|---|---|---|---|---|
| COMPOSITION, % | Al 3.5–4.3, Mg 0.03–0.08, Zn[c] bal | Al 3.5–4.3, Cu 0.75–1.25, Mg 0.03–0.08, Zn[c] bal | Al 4.5–5.0, Cu 0.2–0.3, Zn[c] bal | Al 5.25–5.75, Zn[c] bal |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.24 | 0.24 | — | — |
| Melting Point, F | 728 | 727 | 734 | 743 |
| Ther Cond (158–284 F), Btu/hr/sq ft/°F/ft | 65.3 | 62.9 | — | — |
| Coef of Ther Exp (68–212 F), per °F | $15.2 \times 10^{-6}$ | $15.2 \times 10^{-6}$ | — | — |
| Spec Ht (68–212 F), Btu/lb/°F | 0.10 | 0.10 | — | — |
| Elec Res (68 F), microhm-cm | 6.37 | 6.54 | — | — |
| MECHANICAL PROPERTIES[d] | | | | |
| Ten Str, 1000 psi | | | | |
| Die Cast | 41 | 47.6 | — | — |
| Chill Cast | — | — | 28.0 | 25.0 |
| Elong (in 2 in.), % | | | | |
| Die Cast | 10 | 7 | — | — |
| Chill Cast | — | — | — | 1 |
| Hardness (Brinell, die cast) | 82 | 91 | — | — |
| Impact Sfr (Charpy), ft-lb | | | | |
| Die Cast | 43 | 48 | — | — |
| Chill Cast | — | — | 3 | 1 |
| Endurance Limit ($10^8$ cycles, die cast), 1000 psi | 6.9 | 8.2 | — | — |
| Compr Yld Str (die cast), 1000 psi | 60 | 87 | — | — |
| Shear Str (die cast), 1000 psi | 31 | 38 | — | — |
| FABRICATING PROPERTIES | | | | |
| Melting Temp Range, F | 728–932 | 727–932 | — | — |
| Die Casting Temp Range, F | 740–800 | 740–800 | — | — |
| Solidification Shrinkage, % | 1.17 | 1.17 | — | — |
| Machinability | Good | Good | Good | Good |
| Joining | | | | |
| Torch Welding | Poor to fair | Poor to fair | — | — |
| Single Impulse Resistance Welding | Poor | Poor | — | — |
| Multiple Impulse Resistance Welding | Fair to good | Fair to good | — | — |
| Soldering | Poor[e] | Poor[e] | — | — |
| Common Fabrication Processes | Welding, soldering, machining, riveting, spinning, cold swaging | | Welding, soldering, machining | |
| CORROSION RESISTANCE | Excellent resistance to both metropolitan and rural atmospheric corrosion[f]; also hot soapy water, printing inks, trichloroethylene, carbon tetrachloride, dry illuminating gas, and moisture- and acid-free hydrocarbons. Fair resistance to pure ethyl and methyl alcohols, glycerine, water and petroleum products. Poor resistance to steam, spray insecticides, animal oils, strong acids and bases, and mixtures of glycerine or alcohol and water | | | |
| USES | Automotive parts, household utensils, office equipment, building hardware, padlocks, toys, novelties, drop hammer dies (XXV) | | Slush and permanent mold castings, principally for lighting fixtures | |

[a] ASTM B86-57T.
[b] Because of their limited use, few data are available on these alloys.
[c] Special high grade zinc is required.
[d] Based on a ¼-in. section for die cast alloys; a ½-in. section for chill cast alloys.
[e] Cadmium-zinc and lead-tin solders diffuse into the casting, promoting subsurface attack. Castings must be nickel plated to be joined by lead-tin solders.
[f] Penetration in in. per yr in Palmerton, Pa., and New York City, respectively, is $0.78 \times 10^{-4}$ and $2.2 \times 10^{-4}$ for XXIII, and $0.63 \times 10^{-4}$ and $2.8 \times 10^{-4}$ for XXV.

## Hafnium, Thorium, Uranium, Vanadium, Beryllium—Wrought


| Metal → | Hafnium | Thorium | Uranium | Vanadium | Beryllium |
|---|---|---|---|---|---|
| PHYSICAL PROPERTIES | | | | | |
| Density, lb/cu in. | 0.47 | 0.42 | 0.69 | 0.23 | 0 067 |
| Melting Point, F | 3400 | 3180 | 2071 | 3110 | 2341 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | — | 21.4[c] | 14.5[c] | — | 87 |
| Coef of Ther Exp (70 F), per °F | $3.4 \times 10^{-6}$ | $6.2 \times 10^{-6}$ | $12.1 \times 10^{-6}$[c] | $4.8 \times 10^{-6}$ | $6.4 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.035 | 0.03 | 0.03 | 0.12 | 0.45 |
| Elec Res (68 F), microhm-cm | 30[a] | 18 | 25-50 | 25 | 5 |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | $20 \times 10^6$ | $10 \times 10^6$ | $30 \times 10^6$ | $20 \times 10^6$ | $44 \times 10^6$ |
| Ten Str, 1000 psi | | | | | |
| Annealed | 77 | 34 | 90 | 72 | 60-90[f] |
| Cold Worked | 112[b] | 49[d] | — | 11 | — |
| Yld Str, 1000 psi | | | | | |
| Annealed | 32 | 26 | 25 | 64 | 45-55[f] |
| Cold Worked | 96[b] | 45[d] | — | 109 | — |
| Elong (in 2 in.), % | | | | | |
| Annealed | 24 | 51 | 13 | 28 | 2-5[f] |
| Cold Worked | 10[b] | — | — | 3 | — |
| Hardness (Rockwell) | | | | | |
| Annealed | A58 | — | — | B81 | — |
| Cold Worked | A65[b] | — | — | B93 | — |
| FABRICATING PROPERTIES | | | | | |
| Annealing Temperature, F | 1380 in vacuum or inert atm | 1380 in vacuum | — | 1650 in vacuum or inert atm | 1400-2100 in vacuum[g] |
| Workability | Can be hot worked at 1550 F; cold worked 30% between anneals | Can be readily hot or cold worked; fabricated by forging, rolling, swaging, extruding or drawing | Can be forged, rolled, swaged and drawn; heating must be done in a protective atm | Good cold working properties | Hot worked at 750-1800 F |
| Machinability | Similar to stainless steel | Can be machined like mild steel with or without cutting fluids | Moderately difficult to machine | Tools similar to those for cold rolled steel | Difficult because of low ductility |
| Joining | — | Difficult to weld; brazing yields brittle joints | Can be welded or brazed in protective atm or vacuum | Can be welded with heliarc torch under argon | Brazed with aluminum alloy or silver alloy rods |
| CORROSION RESISTANCE | Resistant to oxidizing acids but attacked by hydrofluoric acid | Very poor resistance to atmosphere, water and most reagents | Very poor resistance to atmosphere, water and most reagents | Resists sea water; not affected by moderate strength hydrochloric and sulfuric acids; dissolved by any strength nitric acid | Resists atm at ambient temp; attacked by oxygen and nitrogen at elevated temp; resists sea water; attack in fresh water varies with air content |
| AVAILABLE FORMS | Has been produced in sheet and rod | Has been produced in rod, sheet, thin-walled tube, fine wire, foil | Has been produced in plate, rod, tube, wire and foil | Plate, strip, bar, sheet, wire | Sheet, plate, rod, bar, tube, powder |
| USES | Nuclear reactors | Secondary (breeder) reactor fuel | Fissionable material (fuel) in nuclear reactor | AEC applications | Nuclear reactors, missiles, aircraft |

[a] 32 F. [b] 20% cold work. [c] 70 F. [d] 50% cold work. [e] 70-250 F, parallel to A axis; $0.8 \times 10^{-6}$ parallel to B axis; $12.9 \times 10^{-6}$ parallel to C axis. [f] Warm extruded and annealed at 1400 F. Mechanical properties greatly influenced by method of fabrication. [g] Depends on form.

## Zirconium and Its Alloys

| Metal → | Zirconium | Zircaloy-2 |
|---|---|---|
| COMPOSITION, % | | Sn 1.2–1.7, Fe 0.07–0.17, Cr 0.05–0.15, Ni 0.03–0.08 |
| PHYSICAL PROPERTIES | | |
| Density, lb/cu in. | 0.24 | 0.237 |
| Melting Point, F | 3355 | 3300 |
| Thermal Conductivity (212 F), Btu/hr/sq ft/°F/ft | 9.6 | 8.1 |
| Coefficient of Thermal Expansion (70 F), per °F | $3.1 \times 10^{-6}$ | $3.6 \times 10^{-6}$ |
| Specific Heat, Btu/lb/°F | 0.069 | — |
| Electrical Resistivity (68 F), microhm-cm | 40 | 74 |
| MECHANICAL PROPERTIES | | |
| Modulus of Elasticity in Tension, psi | $14 \times 10^6$ | $13.8 \times 10^6$ |
| Tensile Strength, 1000 psi | | |
| Annealed | 29[a], 59[b] | 67 |
| Cold Worked | 82[a], 90[b] | 108[c] |
| Yield Strength, 1000 psi | | |
| Annealed | 11[a], 38[b] | 45 |
| Cold Worked | 58[a], 84[b] | 98[c] |
| Elongation (in 2 in.), % | | |
| Annealed | 26[a], 27[b] | 22 |
| Cold Worked | 15[a], 10[b] | 6[c] |
| Hardness (Rockwell) | | |
| Annealed | B42[a], B91[b] | B89.5 |
| Cold Worked | B87[a], B98[b] | B96.5[c] |
| FABRICATING PROPERTIES | | |
| Annealing Temperature, F | 1550; heavy sections in air, light sections in vacuum or inert atm | 1550 in vacuum |
| Workability | Similar to titanium | Hot worked at 1500–1800 F |
| Joining | Can be arc or flash-butt welded under inert atm | Can be brazed with special 4–5% Beryllium-Zircaloy 2 rod; can be welded |
| CORROSION RESISTANCE | Excellent resistance to hydrochloric acid in all concentrations. Resists dilute sulfuric acid, nitric acid in all concentrations, and alkalis. Attacked by aqua regia | |
| AVAILABLE FORMS | Sheet, rod, tubing, shapes | Billet bar, sheet, wire, tube |
| USES | Structural parts and fuel cladding in nuclear reactors. Probable future use: corrosion resisting equipment | |

[a] Iodide zirconium; cold worked values are for 90% cold worked.
[b] Kroll zirconium, melted in graphite; cold worked values are for 60% cold worked.
[c] 40% cold work




## The Handy & Harman

# *Silver Supermarket*

## Has every form of silver for your electronics applications

Silver, in many forms and alloys, is a necessity in the electronics and electrical industries. To meet this need on a high quality level, Handy & Harman manufactures powder, flake, paint, paste, sheet, strip, wire, etc., for printed circuits, wiring, resistors, condensers, thermistors, contacts, printed terminal strips on glass, ceramics, plastic laminates, etc.

Another "At Your Service" Division of the Handy & Harman Silver Supermarket is our Research and Engineering Department. Always ready to help you with any problem or project you may have involving silver for *any* application.

**VISIT OUR BOOK DEPARTMENT**

We have five Technical Bulletins giving engineering data on the properties and forms of Handy & Harman Silver Alloys. We would like you to have any or all of those that particularly interest you. Your request, by number, will receive prompt attention.


| | |
|---|---|
| **Fine Silver** | **Bulletin A-1** |
| **Silver-Copper Alloys** | **Bulletin A-2** |
| **Silver-Magnesium-Nickel** | **Bulletin A-3** |
| **Silver Conductive Coatings** | **Bulletin A-4** |
| **Silver Powder and Flake** | **Bulletin A-5** |

**Your No. 1 Source of Supply and Authority on Precious Metal Alloys**

**HANDY & HARMAN**

General Offices: 82 Fulton St., New York 38, N. Y.

**For more information, turn to Reader Service card, circle No. 426**



# Sylvania Tungsten and Molybdenum...

## All forms for better high-temperature alloys

Custom-made Sylvania Tungsten and Molybdenum pellets, powder, ingots and electrodes are helping leading metals producers meet and beat today's tough requirements for high-temperature alloys. Their precise composition and unmatched purity permit the most exacting specifications to be met easily and quickly.

Here are some of the important ways Sylvania Tungsten and Molybdenum are being used in the development of new and better high-temperature metals:

- POWDER FOR CARBIDE MANUFACTURE
- POWDER FOR SLIP CASTING
- PELLETS FOR VACUUM MELTING
- ELECTRODES FOR ARC CASTINGS
- INGOTS FOR FORGING


If any of these forms offer the right solution to your problem, Sylvania can supply the exact purity and composition you need. Contact your Sylvania representative, or the Chemical & Metallurgical Division, Sylvania Electric Products Inc., Towanda, Pennsylvania.

# SYLVANIA

*Subsidiary of* **GENERAL TELEPHONE & ELECTRONICS**

For more information, turn to Reader Service card, circle No. 471

1959, 733 pages, $19.50




# ZINC

## The Science and Technology of the Metal, Its Alloys and Compounds

**Edited by C. H. MATHEWSON**

*Professor Emeritus of Metallurgy and Metallography, Yale University*

**With Chapters by Specialists**

**In Cooperation with THE AMERICAN ZINC INSTITUTE**

ACS Monograph No. 142

This definitive monograph on the metallurgy, chemistry, extraction and uses of zinc is the most complete book ever published on the subject. Forty-five specialists under an outstanding editor-in-chief blanket the field from geology through the end product. Written with the cooperation of the American Zinc Institute, the book's fourteen chapters cover such topics as economics, geology, ore treatment, refining, processing, alloy technology, the use of zinc for extraction of other metals, zinc compounds, the biological significance of zinc, and its use in agriculture. All these subjects are in addition to the basic technology mentioned above. Here is a single source of information for anyone with a general or specific interest in zinc as a major material of modern industry.

CONTENTS

Historical Background
Economics and Statistics
Geology and Zinc Deposits
Chemistry and Physics of Zinc Technology
The Treatment of Ore or Concentrate for Subsequent Processing by Leaching or Pyrometallurgical Methods
Metallurgical Extraction
The Refining of Zinc
The Manufacture of Zinc Oxide
The Processing and Uses of Metallic Zinc and Zinc-Base Alloys
Zinc As An Alloying Agent
Uses of Zinc in Various Forms for the Metallurgical Extraction of Other Metals (Including the Parkes Process)
Industrial Zinc Oxide, Zinc Sulfide and Other Zinc Compounds
The Biological Significance of Zinc
Use of Zinc in Wood Preservation and in Agriculture
Name Index
Subject Index

*Send this coupon today!*

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-682, 430 Park Ave., New York 22, N. Y.**
**Send me a copy of *ZINC* for 10 days' Free Examination.**

☐ Total purchase price enclosed

☐ Bill me ☐ Bill company

NAME .....

ADDRESS .....


CITY & ZONE .....

STATE .....

**SAVE MONEY!** Enclose $19.50 with order and Reinhold pays all shipping costs. Same return privilege. Include 3% sales tax on N.Y.C. orders. Do not enclose cash!

REINHOLD


You'll make better connections with Western Brass, because brass is easily—and firmly—welded, brazed, or soldered. With Western Brass you have the added confidence that comes from working with metallurgical specialists who analyze your blueprints to guarantee that you get sheet or strip in the right alloy, temper, grain size, gauge, and finish. You'll make it better with easy-to-bond brass. And you'll make it best with Western Brass—it's "tailor-made" to your individual requirements.



OLIN MATHIESON · METALS DIVISION · EAST ALTON, ILL., NEW HAVEN, CONN.

Western BRASS

For more information, turn to Reader Service card, circle No. 519




STRAITS TIN

FROM MALAYA... **UNIVERSAL METAL FOR U.S. INDUSTRY**

Tin is nontoxic, malleable, and inert to ordinary corrosive agents. It protects steel; hardens and strengthens copper. Tin imparts antifriction properties to bearing metals, and other desirable characteristics to countless alloys.

There is no substitute for tin . . . and particularly no substitute for Straits Tin from Malaya because of its superior quality and uniformity. Specify Straits—in ready supply and with sizeable reserves.







Write for free monthly letter, TIN NEWS. Keep posted on tin supply, prices, new uses and applications.

THE MALAYAN TIN BUREAU

Dept. 24K, 2000 K St. N.W., Washington 6, D.C.

For more information, turn to Reader Service card, circle No. 442



# JUST A FEW WORDS

# WILL BRING YOU

# *BERYLCO* ALLOYS and SERVICES

Aside from their unique combination of desirable properties, a distinct and important advantage in using BERYLCO beryllium copper alloys is their easy availability. It's the same with service. A phone call or conversation can often help you use BERYLCO advantages better . . . cut waste . . . save time and effort. These three things—product advantages; quick, easy availability; prompt service by highly skilled and experienced men—have made BERYLCO alloys first choice of industry.

**BERYLCO PRODUCTS:** Beryllium Copper and other alloys
Beryllium Metal • Beryllium Oxide

**TECHNICAL SERVICE CENTERS AND DISTRIBUTORS NOW SERVING INDUSTRY THROUGHOUT THE U.S.**

**REGIONAL OFFICES:**
**CHICAGO:** ANdover 3-3353
**CLEVELAND:** ACademy 1-2929
**DAYTON:** BAldwin 8-1496
**DETROIT:** CRestwood 8-9300
**NEW YORK:** MUrray Hill 9-5974
**PHILADELPHIA:** LOcust 8-2071
**SPRINGFIELD:** REpublic 4-7581
**YOUNGSTOWN:** RIverside 6-2214
**GLENDALE, CALIF:** CHapman 5-5684

**DISTRIBUTORS:**
**BALTIMORE** Brass & Copper Supply Co., Inc. BElmont 5-1500
**BOSTON** Eastern Metal Mill Products Co. HIghlands 2-5900
**CHARLOTTE** Brass & Copper Supply of Carolina, Inc. FRanklin 5-5508
**CHICAGO** Guardian Metal Sales Inc. NAtional 2-5800
**CINCINNATI** Williams and Company, Inc. CApital 1-3000
**CLEVELAND** Williams and Company, Inc. UTah 1-5000
**COLUMBUS** Williams and Company, Inc. AXminister 4-1623
**DETROIT** Meier Brass & Aluminum Co. JOrdan 6-3902
**LOS ANGELES** The E. Jordan Brookes Co., Inc. RAymond 3-8431
**LOUISVILLE** Williams and Company, Inc. JUniper 3-7781
**MINNEAPOLIS** Eiler Equip. Co. FEderal 9-9226
**MONTREAL** Peckover's Ltd. WEllington 3-6717
**NEW YORK** New York Brass & Copper Co., Inc. New York City: GRamercy 7-5400 Hillside, N.J.: WAverly 6-5300
**PHILADELPHIA** Brass & Copper Sales, Inc. GLadstone 7-2500
**PITTSBURGH** Williams and Company, Inc. CEdar 1-8600
**ROCHESTER** Ontario Metal Supply Co., Inc. HAmilton 6-1630
**SAN FRANCISCO** The E. Jordan Brookes Co., Inc. YUkon 6-2974
**SEATTLE** James J. Backer Co. ATwater 3-6470
**TORONTO** Peckover's Ltd. ROger 2-8272

**AGENTS:**
**CHARLOTTE 7, N.C.** W. K. Hile P.O. Box 6165, FRanklin 7-5062
**LOS ANGELES 16, CALIFORNIA** The E. Jordan Brookes Co., Inc. 6601 Telegraph Road, RAymond 3-8431
**MINNEAPOLIS 15, MINN.** Eiler Equipment Co. 1107-09 South 2nd Street, FEderal 9-9226
**MONTREAL, CANADA** Peckover's Ltd. 2052 St. Catherine Street West. WEllington 3-6717
**SAN FRANCISCO 5, CALIFORNIA** The E. Jordan Brookes Co., Inc. 571 Howard Street, YUkon 6-2974
**SEATTLE, WASHINGTON** James J. Backer Co. 221 West Galer St., ATwater 3-6470
**ST. LOUIS 15, MISSOURI** Joseph A. Crowe & Associates 1221 Laredo Street, SHerwood 1-6423
**TORONTO, CANADA** Peckover's Ltd. 115 McCormack St., ROger 2-8272

BERYLCO®

## THE BERYLLIUM CORPORATION

P. O. Box 1462, Reading, Pennsylvania • Phone WAlker 9-0781

**For more information, turn to Reader Service card, circle No. 567**

# ECONOTAPE crossbar contacts are most efficient for electrical relays


D. E. MAKEPEACE DIVISION

You can now get ideally efficient crossbar contacts for your electrical relays—with as many contacts as you need, where you need them—with positive assurance of full, contact surface. This has been made possible through the development of Makepeace's new ECONOTAPE, a precision-drawn shaped or rectangular contact wire in either solid precious metal or in laminated metal—in your choice of gold, platinum, palladium, silver and their various alloys.

Econotape crossbar contacts are supplied complete, attached to Makepeace blades... attached to blades supplied by you... or Econotape for your own attaching.

Econotape is cut off and welded to the blade in one operation. It is no longer necessary to handle and attach individual button type contacts. Positioning of Econotape on the blade is done automatically as the tape is cut off and welded. Permanent attachment is assured by a homogenous metallurgical bond that is undisturbed by expansion and contraction caused by temperature changes.

If you are designing a new relay or trying to cut the cost of your present mechanism, send for Econotape literature.



D. E. MAKEPEACE DIVISION • PINE & DUNHAM STREET
ATTLEBORO, MASS.

# a complete range of brush materials for printed circuit applications.

BAKER CONTACT DIVISION

Because the correct choice of contact materials for use on printed circuits is wholly dependent upon such factors as type of circuit, circuit function and mechanical design, the final selection of materials is generally obtained on an empirical basis.

Baker engineers and metallurgists are prepared to offer very broad, specialized experience, together with extensive records of performance data that can be extremely useful to you. They will be pleased to assist in resolving your particular problems in this field.

Baker-developed alloys and powdered metal products meet the full range of brush material requirements for printed circuit applications. Complete facilities are available here for reliable design and manufacture. Send for literature.



BAKER CONTACT DIVISION • 207 GRANT AVE., E. NEWARK
HARRISON P. O., N. J.

DOMESTIC DIVISIONS: AMERICAN PLATINUM & SILVER DIVISION • AMERSIL QUARTZ DIVISION • BAKER CONTACT DIVISION • BAKER DENTAL DIVISION • BAKER PLATINUM DIVISION • BAKER SETTING DIVISION • CHEMICAL DIVISION • HANOVIA LIQUID GOLD DIVISION • INSTRUMENTS & SYSTEMS DIVISION • IRVINGTON-BAKER REFINING DIVISION • D. E. MAKEPEACE DIVISION • RESEARCH & DEVELOPMENT DIVISION • H. A. WILSON DIVISION. COMPANIES ABROAD: ENGELHARD INDUSTRIES OF CANADA, LTD., TORONTO • ENGELHARD INDUSTRIES LTD., BAKER PLATINUM DIVISION, HANOVIA PRODUCTS DIVISION, LONDON • SOCIEDAD SURAMERICANA DE METALES PRECIOSOS S.A., BO-

**PROMPT PRECIOUS METAL SCRAP RECOVERY SERVICE • ENGELHARD PROCEDURES RECOVER**

AMERICAN PLATINUM & SILVER DIVISION




## a simplified mirror-bright silver plating process for electrical and electronic components

Here is the most efficient, simple procedure to protect electrical electronic and lamp components with a mirror-bright silver finish—through a complete range from flash to heavy deposit. The procedure is easy, economical and non-critical —with little or no polishing required. Silva-Brite is a clear, water-white solution, enabling the operator to observe work as it is being plated. Uniformly good results are attained with current densities ranging from 10 to 40 amperes per square foot. Normal room temperature operation minimizes fumes and tendency toward bath decomposition. Send for descriptive data together with detailed plating procedures.

AMERICAN PLATINUM & SILVER DIVISION
231 N. J. RAILROAD AVENUE, NEWARK, N. J.

**ENGELHARD**
INDUSTRIES, INC.
EXECUTIVE OFFICES:
113 ASTOR STREET · NEWARK 2, NEW JERSEY

AMERSIL QUARTZ DIVISION



## look to Amersil for all high purity fused quartz requirements.

Amersil manufactures and fabricates high purity fused quartz for ultraviolet transmission applications, laboratory ware and production equipment. These products include standard apparatus, plain tubing in many intricate fabrications, crucibles, trays, cylindrical containers and piping in a full range of sizes up to 25" in diameter. Ingots and plates are available in general commercial quality as well as in special optical grades. Amersil engineers are also prepared to assist in developing fused quartz and silica equipment for special requirements. Send for literature.


AMERSIL QUARTZ DIVISION • 685 RAMSEY AVENUE
HILLSIDE, N. J.

GOTA • ENGELHARD INDUSTRIES S.A.R.L., PARIS • ENGELHARD INDUSTRIES A/S. COPENHAGEN • GLOVER & GOODE PTY., LTD., MELBOURNE • ENGELHARD INDUSTRIES, K.K., TOKYO • ENGELHARD INDUSTRIES, PTY., LTD., MELBOURNE • ENGELHARD INDUSTRIES, LTD., ZURICH • INDUSTRIE ENGELHARD S.P.A., ROME • GUILIANO STACCIOLI-METALLI PREZIOSI S.P.A., ROME • INVERSIONES EN INDUSTRIES NACIONALES, S.A., BOGOTA. ASSOCIATED COMPANIES: KALIE-CHEMIE-ENGELHARD KATALYSATOREN G.M.B.H., HANOVER

**100% OF ASSAYED PRECIOUS METAL CONTENT • IRVINGTON-BAKER REFINING DIVISION**

For more information, turn to Reader Service card, circle No. 522

# UNIFORM TEMPER UNIFORM DIMENSION UNIFORM GRAIN SIZE UNIFORM TENSILE STRENGTH UNIFORM COATING



## The most uniform springs just naturally start with...

# RIVERSIDE-ALLOY SPRING MATERIALS

It's an acknowledged fact in the trade that Riverside-Alloy produces the finest spring materials for corrosion resistant and high temperature applications . . . materials more uniform in *all* the properties that make *good* springs.

But what about the specific alloy and shape you need? Riverside-Alloy is a *single, dependable source* for spring material in Stainless steel (Isoloy), Phosphor bronze, Nickel silver, Monel, Inconel, Inconel "X" and Duranickel . . . in wire, flat wire and strip.

Write today for a copy of the new "Spring Materials Digest" and other specific information. We have the people who can talk *springs. Riverside-Alloy Metal Division, H. K. Porter Company, Inc., Riverside, N. J.*

***RIVERSIDE-ALLOY METAL DIVISION*** PORTER ***H.K. PORTER COMPANY, INC.***

**PORTER SERVES INDUSTRY** with steel, rubber and friction products, asbestos textiles, high voltage electrical equipment, electrical wire and cable, wiring systems, motors, fans, blowers, specialty alloys, paints, refractories, tools, forgings and piping fittings, roll formings and stampings, wire rope and strand.

**For more information, turn to Reader Service card, circle No. 457**

# FAIRMONT

*the aluminum source that gives you* **ALL FOUR**

1 **QUALITY:** Exactly according to your specifications every time. Reason—Fairmont's modern precision equipment and the most rigid quality-control system in the business.

2 **ENGINEERING:** You get practical help, not just sales talk, from Fairmont field men who are qualified engineers with mature experience in aluminum and its applications.

3 **AVAILABILITY:** All Fairmont products are rolled every day. You can depend on getting what you need when you need it, custom-rolled and on the way fast.

4 **DELIVERY:** Your order gets personal attention *all* the way. Fairmont's own truck fleet, operated by specialists in aluminum handling, guarantees prompt, dependable delivery.

# ALUMINUM

*rolled every day by Fairmont in all these categories*

| ALLOY | TEMPER | SHEET | COILS | CIRCLES | FINISHES PLAIN | FINISHES EMBOSSED | TYPICAL ALLOY APPLICATIONS |
|---|---|---|---|---|---|---|---|
| 1100 | O, H-12, H-14, H-16, H-18 | X | X | X | X | X | Refrigerator parts, fins for heating-air conditioning |
| 3003 | O, H-12, H-14, H-16, H-18 | X | X | X | X | X | Cooking utensils, doors, wall tile, awnings |
| 3004 | O, H-32, H-34, H-36, H-38 | X | X | X | X | X | Truck bodies, building panels, electronic application |
| 5005 | O, H-12, H-14, H-16, H-18 | X | X | X | X | X | Small stampings, trays, rolled shapes, weather stripping |
| 5050 | O, H-32, H-34, H-36, H-38 | X | X | X | X | X | Window screens, jalousies, auto trim, TV cabinets |
| 5052 | O, H-32, H-34, H-36, H-38 | X | X | X | X | X | Home freezer liners, display racks, hardware |
| 5357 | O, H-32, H-34, H-36, H-38 | X | X | X | X | X | Decorative applications where anodized finishes are involved |
| 5457 | O, H-32, H-34, H-36, H-38 | X | X | X | X | X | Decorative applications where anodized finishes are involved |
| 5557 | O, H-32, H-34, H-36, H-38 | X | X | X | X | X | Decorative applications where anodized finishes are involved |
| BLDG. SHEET | H-12, H-14, H-16 | X | X | X | X | X | Building specialty products, siding, roofing, panels |




## . . . Get Fairmont's new Aluminum Selector Guide to help you pinpoint specifications

Here's a complete field of aluminum know-how at your fingertips, based upon Fairmont's 34 years of comprehensive experience. Fairmont's new *Selector* and Design Data Guide is an indispensable reference if you use aluminum sheet, coils, circles, in plain, matte or embossed finishes. Enables you—at a glance—to match best combination of aluminum properties to your specific applications. Includes tabulation of chemical and physical properties, application data on aluminum alloys, plus weights, and helpful specification data. For your free copy, write *Vice-President, Sales, Dept. 25-J, Fairmont Aluminum Company, Fairmont, West Virginia.*

**FAIRMONT ALUMINUM COMPANY**

subsidiary of **CERRO** DE PASCO CORPORATION

Sales Offices in Principal Cities. Mill: Fairmont, West Virginia

For more information, turn to Reader Service card, circle No. 414

# THERE IS ONLY ONE THINSTRIP

Somers THIN STRIP

Somers THIN STRIP® is the registered Trade Mark of The Somers Brass Co., Inc. for nickel and alloys from .020 down to .0001 and copper, brass and alloys from .012 to .0001.

## FOR OVER FIFTY YEARS SOMERS HAS LED IN THE DEVELOPMENT AND PRODUCTION OF THIN METAL

This experience, plus the most advanced equipment in the industry, is ready to solve your problem.

Write for Confidential Data Blank — No Obligation

SOMERS BRASS COMPANY, INC • Baldwin Ave., Waterbury, Conn.

## STAUFFER PRODUCTS

**AGRICULTURAL CHEMICALS DIVISION**

Defoliants Fertilizers Fungicides
Grain Fumigants Herbicides
Insecticides and Miticides
Seed Disinfectants Soil Fumigants
Sulfurs, Ground and Refined

**ANDERSON CHEMICAL DIVISION**

Metal-Organics Metal Esters
Research Chemicals Metal Chlorides
Aluminum Acetylsalicylate

**CONSOLIDATED CHEMICAL INDUSTRIES DIVISION**

Sulfuric Acid Alums Bone Charcoal
Bone Meal Muriatic Acid
Hydrogen Chloride Ferric Sulfate

**INDUSTRIAL CHEMICALS DIVISION**

Acids: Boric, Muriatic, Sulfuric and Tartaric Aluminum Sulfate
Bone Charcoal Bone Meal
Boron Oxide Carbon Disulfide
Caustic Soda Carbon Tetrachloride Chlorides of Aluminum, Antimony, Boron, Columbium, Silicon, Tantalum, Titanium and Zirconium Chlorine
Chloroform Cream of Tartar Ferric Sulfate
Greases Hydrogen Animal Glues
Hydrogen Chloride Mesyl Chloride
Methylene Chloride Oleum Perchlorethylene
Potassium Nitrate Rochelle Salt
Sodium Carbonate Sodium Hydrosulfide
Sodium Sulfate Sulfur Chlorides
Sulfurs: Refined, Flowers, Roll, Rubbermakers and Insoluble Crystex®

**INTERNATIONAL DIVISION**

Products of all Divisions

**A. R. MAAS CHEMICAL DIVISION**

Phosphoric Acid Phosphates
Photographic Chemicals Questex®

**MOLDED PRODUCTS DIVISION**

Battery Boxes and Fittings
Plastic Foam Plastic Pipe
Miscellaneous Molded Rubber and Plastic Products

**NYOTEX CHEMICALS DIVISION**

Hydrofluoric Acid, Anhydrous and Aqueous
Aluminum Chloride Aluminum Fluoride

**STAUFFER-TEMESCAL COMPANY**

Electron Beam Furnaces
High-purity refractory Metals and Alloys

**VICTOR CHEMICAL WORKS DIVISION**

Phosphoric Acid Phosphates of Ammonia, Calcium, Iron, Potassium and Sodium
Organophosphorus Compounds Chlorinated Trisodium Phosphate Phosphoric Anhydride
Phosphorus Chlorides Phosphorus Pentasulfide
Formic Acid and Formates Oxalic Acid and Oxalates Phosphatic Fertilizer Solution
Sodium Hypophosphite Methyl Parathion

**WEST END CHEMICAL COMPANY DIVISION**

Borax Lime Products Soda Ash
Sodium Sulfate

**STAUFFER-TEMESCAL COMPANY**
Richmond, California

Kindly send me:

- ☐ Data Sheet on Forgeable Tungsten
- ☐ Data Sheets on other Refractory Metals and Alloys
- ☐ Information on the Stauffer-Temescal electron beam furnace

(Name) _____


(Company) _____

(Street) _____

(City) _____

(Zone) (State) MDE

For more information, turn to Reader Service card, circle No. 559




# WHO EVER HEARD OF FORGEABLE TUNGSTEN?

Nobody...until Stauffer-Temescal Company made it in this ultra-pure form! Hardness and extreme high-temperature strength are typically tungsten. Impact resistance at all temperatures has been greatly increased. Yet because of the new ductility, forging and other fabrication are now successfully done on conventional steel-working equipment. *Forgeable* tungsten is a major breakthrough in refractory metals technology. This is an exclusive development of Stauffer-Temescal Company. Electron beam processing with critical composition control has greatly reduced grain size and created a random, highly uniform crystal structure. This virtually eliminates the lines of crystallographic weakness which induce fracture in ordinary tungsten. *Forgeable* tungsten and molybdenum are products of Stauffer research. Other exciting developments in electron beam processing are alloys of tungsten and tantalum, columbium and other refractory metals. Use the coupon on the opposite page for detailed information.

FORGEABLE TUNGSTEN AND MOLYBDENUM ARE PRODUCED BY STAUFFER-TEMESCAL COMPANY

75 YEARS OF SERVICE TO INDUSTRY AND AGRICULTURE

Stauffer CHEMICALS

**STAUFFER CHEMICAL COMPANY,** 380 MADISON AVENUE, NEW YORK 17, NEW YORK

For more information, turn to Reader Service card, circle No. 577




Columbium ingots up to 16″ diameter weighing up to 5,000 lbs. are available.

Pure Columbium's extremely high melting point of 4379°F is solving incredible temperature problems encountered in hypersonic travel, as well as for nuclear, jet and rocket powered-aircraft.

WCC is also a major producer of Hafnium control rods.

For technical information, write outlining your requirements.

## WAH CHANG CORPORATION

233 Broadway, New York 7, N.Y.


BRINGING TOMORROW CLOSER WITH NEW METALS


Leading Producers and Fabricators of:


| Hf | Zr | Ta | Mo | W |
|---|---|---|---|---|
| HAFNIUM | ZIRCONIUM | TANTALUM | MOLYBDENUM | TUNGSTEN |

For more information, turn to Reader Service card, circle No. 538

For more information, circle No. 539 ➤


when only a **Different Copper** will do.....
AMCO DIVISION
American Metal Climax, Inc.






# OFHC®

## When you need conductivity of 101.5% IACS plus good formability at high strength levels

**DISTINCTIVE CHARACTERISTICS:** Totally free of oxides and residual deoxidizers, OFHC is 99.99% pure copper. For more than 20 years it has been recognized as the *one* copper able to meet all demands for precision electronic and electrical applications. OFHC offers high conductivity . . . excellent hot and cold workability . . . immunity to hydrogen embrittlement . . . soundness and high density to assure total vacuum . . . low volatility under high vacuum . . . adherent oxide scale . . . superior anodic action in electroplating.

**APPLICATIONS:** OFHC is the preferred copper for essential parts of electronic components such as high-frequency oscillators . . . magnetrons . . . triodes . . . tubes requiring glass-to-metal seals. Rotary components of power-generating equipment and other items requiring the highest obtainable electrical and thermal conductivity rely on OFHC.

**IMPACT RESISTANCE OF OFHC AND TOUGH PITCH COPPER**





# AMZIRC®

## When you need tensile strength of up to 52,000 psi at 400°C plus conductivity of 95% IACS

**DISTINCTIVE CHARACTERISTICS:** AMZIRC consists of OFHC Copper and a rigidly controlled addition of high-purity Zirconium. The designer will find in AMZIRC high conductivity . . . retention of strength at elevated temperatures where copper and conventional high-conductivity alloys weaken . . . extreme notch toughness . . . transverse properties equal to longitudinal properties . . . hardness . . . exceptional hot and cold workability.


**APPLICATIONS:** Typical of the many products that have been improved or made possible by AMZIRC's unique combination of characteristics are high-temperature magnet wire . . . commutators and collector rings . . . rotor wedges . . . resistance welding wheels and tips . . . electron tube studs and side rods . . . rectifier bases.


**TENSILE STRENGTH vs TEMPERATURE**




® *Registered U.S. Pat. Off.*

AMCO DIVISION, American Metal Climax, Inc.






# AMSULF®

## When you need machinability rating of 90 and good workability, plus conductivity of 96% IACS

**DISTINCTIVE CHARACTERISTICS:** AMSULF is produced by combining OFHC Copper and a nominal 0.3% sulfur. This alloy provides high conductivity . . . rapid cutting rates . . . short chip formation . . . low power consumption relative to tool bite . . . excellent hot and cold workability . . . freedom from hydrogen embrittlement . . . fine surface finish and corrosion resistance.

**APPLICATIONS:** AMSULF is ideal for machined parts, especially automatic screw machine products. Its hot and cold workability and immunity to hydrogen embrittlement allow fabricating and finishing techniques impossible with conventional free-cutting coppers. Representative of the parts now being produced from AMSULF are flame-cutting nozzles . . . parts for motors and switches . . . electrical connectors, clamps, and clips . . . soldering iron tips . . . studs and terminals.

**RELATIONSHIP OF ELONGATION, REDUCTION OF AREA, AND TENSILE STRENGTH**





# AMPHOS®

## When you need exceptional hot and cold workability plus rapid piercing and drawing rates

**DISTINCTIVE CHARACTERISTICS:** Unlike ordinary phosphorus-*deoxidized* copper, AMPHOS is produced by adding to *oxygen-free* OFHC Copper a rigidly controlled amount of phosphorus. This results in a high-purity copper having uniform distribution of a predetermined phosphorus content. Distinguishing AMPHOS are high density . . . free-scaling properties . . . freedom from hydrogen embrittlement . . . improved cold workability . . . absence of voids . . . high softening temperature.

**APPLICATIONS:** AMPHOS should be specified for all tube, pipe, and related products where exacting specifications or fabricating techniques result in an appreciable number of rejects when ordinary phosphorized copper is used. Its suitability for welding and brazing and immunity to embrittlement make AMPHOS a superior material for condenser tubes . . . heat exchange units . . . coils . . . complex piping.

**SOFTENING TEMPERATURE**




*For Free Technical Literature, Please Turn Page . . .*




## Free Technical Literature on AMCO's Unconventional Coppers

One of AMCO's coppers with unique combinations of characteristics may hold the elusive answer to your design problem. Another may help you hone your product's competitive edge. Starting point in discovering how to put these unusual metals to work for you are these books, booklets, and technical papers. There's no charge or obligation, of course. Also available without cost is metallurgical design service. Just contact the AMCO Technical Service Section.

**AMCO DIVISION**
American Metal Climax, Inc.
1270 Avenue of the Americas
New York 20, N. Y.

- **"TECHNICAL SURVEY OF OFHC COPPER"**
  122 pages, hardbound comprehensive reference text; Pub C-100
- **"OFHC...PREMIUM COPPER FOR PRECISION ELECTRONICS"**
  8 pages, Pub C-13
- **"AMZIRC...HIGH-CONDUCTIVITY ALLOY WITH HIGH STRENGTH AT ELEVATED TEMPERATURES"**
  8 pages, Pub C-16
- **"AMSULF...FREE-MACHINING ALLOY WITH HIGH CONDUCTIVITY AND UNIQUE WORKABILITY"**
  8 pages, Pub C-17

You will find investigation of the other products in the AMCO Copper Line rewarding, too. The publications covering them are also yours for the asking.

*Electrolytic Copper Powders, Copper Alloy Powders, and Pre-Alloyed Filter Powders*

- **"AMCO NON-FERROUS METAL POWDERS"**
  16 pages, Pub C-14

*OFHC Anodes for Superior Electroplating*

- **"THE COPPER IN YOUR PLATING ANODES"**
  8 pages, Pub C-15
- **"IMPROVING YOUR ELECTROPLATING"**
  8 pages, Pub C-10

AMCO DIVISION
American Metal Climax, Inc.
1270 Avenue of the Americas, New York 20, N. Y.

C-10 ☐ C-13 ☐ C-14 ☐ C-15 ☐ C-16 ☐ C-17 ☐ C-100 ☐


NAME .....

POSITION .....

COMPANY .....

ADDRESS .....

AMAX



a miss is as good as a thousand miles

the higher you aim
for new **productivity**
the more you need
Scovill's "count down"
on quality

SCOVILL®


brass
copper
aluminum
MILL PRODUCTS

MADE IN USA

*. . . and made better to bring out the BEST in your products*

**SCOVILL MANUFACTURING COMPANY**
*Mill Products Division, 99 Mill St., Waterbury 20, Conn., Phone Plaza 4-1171*

6SC60



**SCOVILL**

# gives you fault-free metals for **high speed** fabrication

**Advanced mill processes** — Scovill pioneered the CONTINUOUS CASTING of Brass alloys to bring fabricators of Brass Mill Products the new standard of metal soundness and uniformity made possible by this unique process. Other more recent new mill installations at Scovill include precision-controlled Aluminum rolling mills; the advanced Sendzimir Mill for extra-close-tolerance sheet and strip; the World's largest vertical tube extrusion press, with automatic induction billet-heating equipment, as well as one of the Industry's newest and largest specialized tube mills.

**Advanced quality-control procedures** — insure dependable UNIFORMITY in all Scovill Mill Products specifications . . . order to order and lot to lot. They promise more accurately dimensioned, finer quality mill products essential to efficient high speed fabrication. Quality-control is a full-time job at Scovill, and the results are evident to fabricators in their own higher production speeds, minimum tool and machine adjustments and superior quality of finished products.

**Advanced inspection equipment and methods** — There are many inspection stations along each of the Scovill production lines for Brass strip and sheet, rod, wire and tube. In addition, samples of alloy billets and bars, as well as of finished mill products, undergo detailed inspection and test procedures in Scovill's Metals Research laboratories. Brass Mill Products that pass these rigid inspections and tests are considered by many to be the finest in the World.

**Advanced packaging** — Unique Scovill packaging methods protect quality, finish and condition, make it easier for fabricators to warehouse, handle and use Mill Products. Time- and cost-saving innovations such as extra-long-length coils of strip, self-feeding wire "dispenser" drums, special long lengths when required in tube mill products, are available to fabricators who need them.

***Make Scovill a part of your competitive team, let us contribute our wealth of experience and ultra-modern equipment to the success of your NEW products and production plans.***

**SCOVILL MANUFACTURING COMPANY**

*Mill Products Division, 99 Mill Street, Waterbury 20, Conn. Phone PLaza 4-1171*

MADE IN USA

*. . . and made better to bring out the BEST in your products*

7SC60





MILL PRODUCTS

SIGNIFICANT ADVANCES IN BERYLLIUM TECHNOLOGY COME FIRST FROM BRUSH

# HIGH PERFORMANCE BERYLLIUM PRODUCTS

## QMV® BERYLLIUM

**The high temperature light metal with important thermal and nuclear properties.**




QMV beryllium, available in block, sheet, extrusions and forgings, can be machined, fabricated and joined by adaptations of standard techniques. Beryllium is being used extensively in nuclear devices as a moderator or reflector, in guidance devices, and in the design of advanced aircraft, for structural and heatsink applications.

| | BLOCK | SHEET | EXTRUSIONS |
|---|---|---|---|
| ULTIMATE TENSILE (psi) | 40,000 | 75,000 | 90,000 |
| TENSILE YIELD (psi) | 30,000 | 55,000 | 65,000 |
| ELONGATION (%) | 1-4 | 5-10 | 7-15 |
| YOUNGS MODULUS | 44,000,000 psi | | |
| SPECIFIC HEAT | 0.46 BTU/lb./°F | | |
| THERMAL CONDUCTIVITY | 0.3 BTU/ft.²/Sec (°F/in.)⁻¹ | | |
| ELECTRICAL CONDUCTIVITY | 40-45% I.A.C.S | | |
| DENSITY | 1.85 g./cc. | | |
| MELTING POINT | 2345°F | | |
| REFLECTIVITY—WHITE LIGHT | 55% | | |
| NEUTRON SCATTERING CROSS SECTION | 7 BARNS/ATOM | | |
| NEUTRON ABSORPTION CROSS SECTION | 0.01 BARNS/ATOM | | |

## UOX® BERYLLIUM OXIDE

**The sinterable oxide for high performance applications.**




UOX, the high purity, sinterable ceramic oxide, is available as powder, crucibles, and special shapes fabricated to precision tolerances. Applications include nuclear moderators, reflectors and fuel matrices, heatsinks for aircraft and electronic devices, electronic tube components and metallurgical crucibles.

| | ROOM TEMP. | 2200°F. |
|---|---|---|
| COMPRESSIVE STRENGTH (psi) | 114,000 | 28,000 |
| TENSILE STRENGTH (psi) | 18,000 | 4,000 |
| MODULUS OF RUPTURE (psi) | 35,000 | 14,000 |
| MODULUS OF ELASTICITY (psi x 10⁶) | 45 | 20 |
| SPECIFIC HEAT (BTU/lb./°F.) | 0.24 | 0.57 |
| THERMAL CONDUCTIVITY (BTU/hr./ft.²/°F./ft.) | 125 | 9.7 |
| RESISTIVITY OF LOW DENSITY BeO (Ohm-cm. x 10⁶) | 7000 | 4 |
| SPECIFIC GRAVITY | 3.008 | |
| MELTING POINT (°F.) | 4658 | |
| COEFFICIENT OF EXPANSION (in/in/°F. x 10⁻⁶) R.T.-500°F. | 4.4 | |
| COEFFICIENT OF EXPANSION (in/in/°F. x 10⁻⁶) R.T.-2200°F. | 6.2 | |
| THERMAL SHOCK RESISTANCE | Excellent | |
| DIELECTRIC CONSTANT (10⁷ cps) | 5.9 | |
| LOSS FACTOR (10⁷ cps) | 0.0004 | |

## BERYLLIUM COPPER

**High strength, good conductivity, corrosion and wear resistance, and excellent fatigue strength.**



Available as casting alloy, master alloy, billets, forgings, bar, plate, and precision-rolled strip, these versatile alloys fill a wide range of uses including mechanical springs, electrical contacts, diaphragms, bellows, connectors, plastic mold cavities, non-sparking tools, switchgear, welding electrodes and wear surfaces.

TYPICAL MECHANICAL PROPERTIES OF BERYLLIUM COPPER PRECISION STRIP.

| | | BEFORE HEAT TREATMENT | | AFTER HEAT TREATMENT | | |
|---|---|---|---|---|---|---|
| Alloy | Temper | Tensile Strength psi | Elong. % in 2 in. | Tensile Strength psi | Elong. % in 2 in. | Elec. Cond. % IACS |
| 25 | Annealed | 60- 78,000 | 35-60 | 165-190,000 | 4-10 | 22-25 |
| | Hard | 100-120,000 | 2- 8 | 190-215,000 | 1- 4 | 22-25 |
| 165 | Annealed | 60- 78,000 | 35-60 | 150-180,000 | 4-10 | 22-25 |
| | Hard | 100-120,000 | 2- 8 | 180-200,000 | 1- 4 | 22-25 |
| 10 | Annealed | 35- 55,000 | 20-35 | 100-110,000 | 8-12 | 48-55 |
| | Hard | 70- 85,000 | 5-10 | 110-125,000 | 5- 8 | 48-52 |
| 35 | Annealed | 35- 55,000 | 20-35 | 100-110,000 | 8-12 | 48-55 |
| | Hard | 70- 85,000 | 5-10 | 110-125,000 | 5- 8 | 48-52 |
| 25 | XHM | Mill-hardened | | 170-185,000 | 3- 7 | 25-33 |
| 165 | XHM | Mill-hardened | | 160-175,000 | 3- 7 | 25-33 |

## OTHER BRUSH BERYLLIUM PRODUCTS

BERYLLIUM COMPOUNDS: Beryllium Fluoride, Hydroxide, Nitrate, Sulfate.
SYNTHETIC MICA: Powder and Block.
PRECISION-ROLLED STRIP: Phosphor-Bronze, Brass, Nickel-Silver, Stainless Steel.
ALLOYS: Beryllium-Aluminum, Beryllium-Nickel, Special Alloys.


Whether your problem is improving household appliances, or designing for interstellar exploration, beryllium or its oxide and versatile alloys should have a place in your planning. For more data, or application assistance, contact us at 5209 Euclid Avenue or ENdicott 1-5400 in Cleveland, Ohio.

## THE BRUSH BERYLLIUM COMPANY

For more information, circle No. 464

For more information, turn to Reader Service card, circle No. 393

# JUST OFF THE PRESS




## GET YOUR COMPLETELY NEW SOURCE BOOK ON INDIUM

*The MAGICAL 49th Element*

**PARTIAL LIST OF CONTENTS**

- Discovery, Occurrence, Detection, Estimation and Extraction of Indium.
- Physical Properties of Indium
  - Table of Physical Constants
  - Atomic Diameters of Metallic Elements
- Constitution of Indium Alloy Systems
  - Binary Systems
  - Ternary Systems
  - Quaternary Systems
  - Quinary Systems
  - Phase Diagrams
- Low Melting Solders
- Bearing and Brazing Alloys
- Metallography of Alloys
- INDALLOY Intermediate Solders
- Nomographic Charts of Pellets and Spheres
- Chemical Properties and Compounds of Indium
  - Electrochemical Properties
  - Electrochemical Methods of Analysis
  - Physical Constants of Inorganic Compounds
  - Indium Plating, Stripping, Recovery

*Plus . . .*

**ANNOTATED BIBLIOGRAPHY**

reporting concisely on all writings about Indium properly indexed and sectionalized for reference.

This new reference book on Indium will find its place in hundreds of university and technical libraries in many countries. It will be a worthy companion to research-minded engineers . . . everywhere!

- **770 fact-filled pages**
- **91 photos and drawings**
- **3 years of editing**

In 1950, we published the first edition of "Indium" which has been out of print for some time. This is a completely new edition . . . almost 500 more pages than the first! It will make a handy addition to your reference shelf.

**SINCE 1934**

**Pioneers in the Development and Applications of Indium for Industry**

MAIL COUPON TODAY

THE **INDIUM** CORPORATION OF AMERICA
1676 LINCOLN AVENUE • UTICA, NEW YORK

☐ Please send free bulletin and further information on your new book "Indium".
☐ Please send me immediately ..... copy(s) of your new book priced at $10.00 per copy.
☐ CHECK ENCLOSED ☐ BILL MY FIRM ☐ SEND C.O.D.

Name .....
Title .....
Address .....
City and State .....

For more information, turn to Reader Service card, circle No. 430

*Covers constitution, applications and properties . . .*

# HOT ORGANIC COATINGS


*Just Published!*

by **RAYMOND B. SEYMOUR**
President, Alcylite Plastics and Chemical Corporation
with a special chapter by **GEORGE B. McCOMB**
Consultant to Leading Suppliers of Pipe Line Coatings

**1959, 225 pages, $7.50**

The constitution, applications and properties of hot organic protective coatings are concisely presented here. The book contains chapters on widely used hot organic materials such as asphalt, coal tar pitch, petroleum waxes and cellulose derivatives. Specific information on formulations of proprietary products is included. Additional chapters deal with hot melt applications without solvent such as peel coatings, protective linings, flame spraying and the fluidized bed process. One chapter on hot applied coal tar pitch base coatings is supplied by George B. McComb, consultant to the leading suppliers of pipe line coatings. Hot spray techniques and the many advantages of this application are also covered. This book will be helpful to everyone using these coatings in any form.

**CONTENTS:** Coating Fundamentals; General Discussion of Hot Coatings; Asphalt and Related Products; Coal Tar Pitch; Petroleum Waxes; Synthetic Hydrocarbons Resins; Cellulose Derivatives; Animal, Vegetable & Insect Waxes; Miscellaneous Products; Applications in the Absence of Solvent; Hot Applied Coal Tar Pitch Base Coatings; Hot Solution Applications; Tests; Trends and Potentials of Hot Coatings; Glossary—Trade Names; Index.




*Examine It Free for 10 Days*
MAIL THIS COUPON NOW!

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-707, 430 Park Avenue**
**New York 22, N. Y.**

Send me a copy of HOT ORGANIC COATINGS for 10 days' Free Examination. After 10 days, I will send you $7.50 plus postage or I will return the book and owe nothing.

NAME .....
ADDRESS .....
CITY AND ZONE ..... STATE .....

SAVE MONEY: Enclose payment, and Reinhold pays the shipping costs. Same return privilege; refund guaranteed. Do not enclose cash!



For high strength without excessive weight, the designer of this heavy truck chose Tenzaloy for the front engine supporting frame.

# *Why TENZALOY is the most widely used high-strength aluminum casting alloy*

Among high-strength, self-aging aluminum casting alloys, Tenzaloy has won greatest acceptance and widest use by designers because of its unique all-round combination of properties. Outstanding among these special qualities are:

- High yield and tensile strength, combined with adequate ductility
- Exceptional machinability
- Remarkable dimensional stability
- High impact, shock resistance

When Tenzaloy is specified, one big problem is eliminated: heat treatment. Without any artificial thermal treatment, Tenzaloy castings will precipitation-harden at room temperature to give properties normally obtainable only by the expensive solution treating, quenching, and artificial aging of the heat-treatable alloys.

*Here are typical properties for Federated Tenzaloy:*

| | |
|---|---|
| Tensile strength | 35,000 psi |
| Yield strength | 25,000 psi |
| Elongation (in 2 in.) | 4-5% |
| Brinell hardness No. | 74 |
| Impact strength (Charpy in ft.-lbs.): | |
| Notched | 3 |
| Un-notched | 14 |
| Electrical conductivity | 35% |

Tenzaloy also is corrosion resistant, has superior ductility, and is easily anodized, dyed and polished to brilliant decorative finishes. Castability is excellent in green sand, plaster, investment, shell, oil-bonded sand and precision molds of all kinds. No special techniques are required for handling Tenzaloy in the foundry. Since Tenzaloy has mechanical properties equivalent to such common heat-treated alloys as 195T6, 355T6, 356T6 and 319T6, it can be substituted in applications where any of these heat-treated alloys are presently used.

It is particularly suited to high-strength designs where load carrying capacity and impact strength are essential. For example: frames, brackets, levers, bases, housings, missile ground handling equipment, jet aircraft turntables, explosion-proof enclosures, heavy-duty wheel hubs and cable drums, to name a representative few.

Tenzaloy can widen your design possibilities, increase production efficiency, improve your products, reduce costs. Get complete facts on its physical and mechanical properties by writing for Bulletin No. 103 R5 to: Federated Metals Division, American Smelting and Refining Company, 120 Broadway, New York 5, N. Y.

TENZALOY

FEDERATED METALS DIVISION **ASARCO**

*American Smelting and Refining Company*
*120 Broadway, New York 5, N. Y.*

For more information, turn to Reader Service card, circle No. 385


call

FANSTEEL for proven workability

in

# TANTALUM
# TUNGSTEN
# MOLYBDENUM
# COLUMBIUM
# Refractory Metal Alloys

INGOTS • BILLETS • SHEET
ROD • WIRE • FOIL





**NEW FANSTEEL WAREHOUSE SERVICE**

Now you can order refractory metals just as you do steel... delivery from stock on over 200 popular sizes.

**TANTALUM** sheet, foil, rod, wire; also acidproof chemical equipment, tubing, screws, bolts, studs.

**TUNGSTEN** sheet, rod, wire.

**MOLYBDENUM** sheet, foil, rod, wire; also crucibles, electrodes, tubing, nickel-plated molybdenum sheet.

**COLUMBIUM** sheet, rod, wire; also alloys—Fansteel "80" Metal, Fansteel "82" Metal.

FANSTEEL®

*Complete warehouse service: cutting, slitting, other processing... plus technical assistance on any problem.*

K605A


FANSTEEL METALLURGICAL CORPORATION North Chicago, Ill., U.S.A.

For more information, turn to Reader Service card, circle No. 415

*Details, ideas, sources for all fastening needs...*

**FASTENERS Handbook**

by JULIUS SOLED, P.E.
*Consulting Engineer*




1957
448 pages
$12.50

NEW! OVER 900 ILLUSTRATIONS!

FASTENERS HANDBOOK provides ready, up-to-date answers to fastening problems in all fields. Its pertinent data, hundreds of illustrations, and full page descriptions supply you with detailed information on currently available fasteners.

Here is a *handbook* in every sense of the word. You can *select* the fastener you want because this comprehensive book includes standard and proprietary fasteners from all manufacturers.

*Abounds in Profitable Features*

**FASTENERS HANDBOOK**

- Brings to your attention the many cost-saving features of available, less-known fasteners.
- Presents complete fastener lines in particular fields and applications. Enables you to look at what's available before closing up.
- Makes possible the immediate location of every fastener described with name and address of supply source.
- Relates actual uses of fasteners in one industry to those of another, resulting in concrete examples of money-saving applications.

FASTENERS HANDBOOK greatly facilitates the review of available information, the making of a valid selection, and contacting the sources of supply. It can be used by design engineers, patent attorneys, sales personnel, fastener distributors and jobbers—in fact, anyone who needs solid information on fasteners available for mechanical assembly.

*Everything in fasteners*

**Rivets, Inserts, Screws, Bolts, Studs, Nuts, Washers, Retaining Rings, Pins, Nails, Metal Stitching, Quick Release Fasteners, Masonry Anchoring Devices, Hose Clamps, Manufacturers Directory.**

*Send now for your* ON-APPROVAL *copy*

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-710, 430 Park Ave., New York 22, N. Y.**

## THERE'S A GIRL IN OUR OFFICE

And her sole responsibility is to make sure that you get further information on any of the products advertised in **Materials in Design Engineering.**

Each advertisement has a circle number, and all you have to do is circle the same number on one of the Reader Service cards (beginning page 585) to get literature detailing engineering data, properties, applications and other useful information from the manufacturer of the product(s) you are interested in. The card is postpaid.

This useful materials information service can also bring you any of the literature listed on page 98. Review the advertisements and the literature listings, then make use of this free service. A moment of your time is all it takes. The literature you will receive has been prepared especially to help you solve materials application problems.

Reminder: For Reader Service Cards, please see page 585. The girl in our office (her name is Eleanor), will take care of the rest.


call FANSTEEL for proven workmanship in

# TANTALUM
# TUNGSTEN
# MOLYBDENUM
# COLUMBIUM
# Refractory Metal Alloys

**FABRICATED PRODUCTS**




When you turn over to Fansteel the responsibility for fabricating your refractory metal parts, every piece benefits from the expert attention and experience of Fansteel's team of scientists, engineers and craftsmen—men who know how to make the metal as well as machine and fabricate it.

It costs nothing to get all the facts . . . send prints and specifications or ask Fansteel representative to call.

FANSTEEL HIGH TEMPERATURE METALS

K597A

FANSTEEL METALLURGICAL CORPORATION North Chicago, Ill., U.S.A.

For more information, turn to Reader Service card, circle No. 416

# FREE TECHNICAL PUBLICATIONS SHOW HOW BRIDGEPORT METALS CAN HELP YOU MAKE BETTER PRODUCTS



**1. Brass & Copper Handbook**—230 pages. Sections on Metallurgy, Corrosion, Metalworking, Sheet, Strip, Rod, Wire, Tube, Pipe. Fully illustrated, with property specifications, application data.




**2. Aluminum Extrusions Handbook**—130 pages. Basic guide to use of strong, light, inexpensive aluminum extrusions. Covers design, application data, standard shapes available, and our facilities to custom design and produce extrusions you need.




**3. Brass & Copper Mill Products, Weights and Data**—56 pages. Need to know specific weights of mill products... in any form? These easy-to-read tables and charts simplify the process.

**4. Condenser & Heat Exchanger Tube Handbook**—162 pages. Covers installation or replacement of Condenser or Heat Exchanger Tubes, helps you select the best alloys for efficient, economical, low maintenance operation.




**5. Bridgeport Special Metals Development Plan**—12 pages. See how Bridgeport is transforming Zirconium, Titanium, Columbium, or Tantalum from costly rarities to readily available materials in tube, rod, sheet, extruded or forged shapes.



**6. Bridgeport Alloys**—Copper, Brass, Bronze—8 pages. Complete chemical, physical, mechanical properties, uses and specifications. Easy-to-read charts allow comparison of metals without confusion.







**7. Bridgeport Tubes**—Aluminum, Brass, Copper, Special Metals, Duplex—4 pages. Gives corrosion-control data on both single wall and duplex tubes, properties and applications.




**8. Grain Size**—The 4th Dimension of Brass—6 pages. Tells how selecting correct grain size of a metal may lower your production and finishing costs.




**9. Bridgeport Plumbing, Heating and Air-Conditioning Products**—4 pages. Complete type, size, weight and strength data on brass and copper pipe and tube.




**10. Index of Bridgeport Products, Alloys, Forms**—4 pages. Lists over 250 metal alloys, forms and shapes readily available from Bridgeport.

**11. Bridgeport Duplex Tubes**—24 pages. Describes advantages of dual metal tubes and tube sheets in solving difficult corrosion problems involving two corrosive media in heat transfer equipment. Includes design, installation data, table of typical applications.



**12. Bridgeport Forgings**—12 pages. Explains die forging and unique cored forging process in detail. Illustrates specific advantages and engineering possibilities of each.




**13. Bronze Welding**—Clearly describes Bridgeport's wide selection of rods for gas and arc welding. Gives characteristics, recommended methods of use for each alloy.




## BRIDGEPORT BRASS COMPANY

Bridgeport 2, Connecticut • Sales Offices in Principal Cities

*Specialists in Metals from Aluminum to Zirconium*

*Clip one of these coupons, circle literature wanted, mail with your letterhead.*

| | | | | |
|---|---|---|---|---|
| 1 2 3 4 5<br>6 7 8 9 10<br>11 12 13 | 1 2 3 4 5<br>6 7 8 9 10<br>11 12 13 | 1 2 3 4 5<br>6 7 8 9 10<br>11 12 13 | 1 2 3 4 5<br>6 7 8 9 10<br>11 12 13 | 1 2 3 4 5<br>6 7 8 9 10<br>11 12 13 |

For more information, turn to Reader Service card, circle No. 392

**Chromel-R**—A modified 80-20 nickel-chromium alloy for use in potentiometers and precision wire wound resistors. Possesses resistivity of 800 ohms/cmf at 20° C., temperature coefficient controlled within 0 ± 10 ppm/°C., exceptional linearity and stability from —65° to +150° C.

**Chromel-P/Alumel**—The world's standard base metal thermocouple combination for measuring operating temperatures in laboratory and heat treat furnaces—jet engines, nuclear reactors. Accuracy is guaranteed to close specified limits over the entire range from —300° to +2300° F.

**Chromel-A**—The original 80-20 nickel-chromium resistance alloy that first made electric heating practical. Widely used in major appliances, industrial furnaces and many other devices requiring heating elements capable of operating up to 2150° F. under adverse conditions.

**Alloy 815-R**—A lower density, higher resistivity iron-chromium-aluminum resistor material that gives you 14% more ohms per pound. Noted for strength, ductility, resistance to wear and corrosion. Resistivity: 815 ohms/cmf at 20° C. Temp. Coeff.: 0 ± 10 ppm/° C. from —65° to +150° C.

**Chromel-P/Copel-XM**—A basic thermo-electric alloy combination used primarily as thermopiles to actuate and control operating temperatures of domestic furnaces, hot water heaters, stoves, ranges and other types of heating equipment. Noted for accuracy and reliability in service.

**Chromel-AA**—A new modified 80-20 type nickel-chromium resistance alloy developed especially for use in controlled atmosphere furnaces. It is highly resistant to corrosion, carburization, oxidation and "green rot" over the entire range of operating temperatures up to 2150° F.

**Copel**—A 55-45 copper-nickel alloy for use in edge-wound resistors, rheostats, motor starters and many other types of devices where operating Temperatures do not exceed 1000° F. Has resistivity of 294 ohms/cmf at 68° F., low temperature coefficient and exceptional mechanical stability.

**Hoskins Cunife**—A new improved copper-nickel-iron ductile permanent magnet alloy. Possesses high coercive force and energy product values, greater uniformity. Readily stamped, machined or otherwise formed by conventional methods for economical production of close tolerance parts.

**Chromel-C**—A 60-16 nickel-chromium-iron alloy used primarily as heating elements in small domestic appliances and other devices that require high resistance in limited space for operating temperatures up to 1700° F. Also used as cold resistor alloy in current-temperature controls.

*Unsurpassed for uniformity, performance, reliability*

# HOSKINS Custom Quality ALLOYS

**Chromel-D**—A time proven low nickel heating element alloy developed for use in controlled atmosphere furnaces required to operate in the critical temperature range between 1500° and 1800° F. It is highly resistant to corrosion, possesses exceptional mechanical stability.

**Alloys 815, 835 and 875**—Three superior iron-chromium-aluminum resistance alloys for use at operating temperatures up to 2150°, 2250° and 2350° F. respectively. Suitable for certain types of appliances, industrial furnaces and kilns where proper supports can be provided.

**DETAILED TECHNICAL DATA** on these and other Hoskins Custom Quality Alloys are yours for the asking. Hoskins metallurgical research, development and customer engineering services are also available to help you solve special design and application problems. Write or call today!

**For Electrical Resistance, Resistor, Thermo-Electric and Magnetic Applications**



Developing and producing custom quality alloys is a specialty at Hoskins—and has been for over 50 years. Some, like Chromel-A, have been responsible for the birth and growth of entire industries. Others have made possible many technological advancements in the design and performance of countless different end-products.

Regardless of their application, however, of this you can be sure: Each in its particular field is unsurpassed for uniformity, durability and reliability in service—developed and produced especially to help make your products better!



**HOSKINS MANUFACTURING COMPANY**

4461 Lawton Avenue • Detroit 8, Michigan • TYler 5-2860

In Canada: Hoskins Alloys of Canada, Ltd., 45 Racine Rd., Rexdale P.O., Toronto, Ontario

*Producers of Custom Quality Alloys for Industry since 1908*

**For more information, turn to Reader Service card, circle No. 429**

# FOR INVESTMENT CASTINGS

## with HIGH STRENGTH and UNIFORM QUALITY



"Wave Guide" is a complicated radar fitting, produced as an investment casting by ARWOOD CORPORATION of New York, N. Y. Material is FRONTIER 40-E Aluminum Alloy, chosen for high strength after dip brazing assembly.

ARWOOD knows from experience the many plus features of Frontier 40-E — its Shock Resistance, Corrosion Resistance and High Tensile and Yield Strength — physical properties obtained by natural aging at room temperatures.

## arwood uses FRONTIER "40-E"

***The Original*** High Strength Natural Aging Aluminum Alloy

***HIGH STRENGTH*** — Initially and Regained without Heat Treatment.

***DEPENDABILITY*** — The Utmost in Uniform Quality. All Prime Metal.

FRONTIER 40-E is a primary alloy ingot made from virgin metals. It is the *proven*, high strength, natural aging alloy that is widely copied, yet today, the same as more than twenty years ago, gives the highest properties and uniformity.

FRONTIER does not make investment castings. We can supply your needs in sand castings to 2500 lbs in 40-E and other high strength alloys.

*Write for complete information.*

**FRONTIER BRONZE CORP.**
**4874 PACKARD ROAD • NIAGARA FALLS, N. Y.**

For more information, turn to Reader Service card, circle No. 515

---

Take no chances

## Specify SEYMOUR

**for NICKEL SILVER**
**PHOSPHOR BRONZE**
**Stainless Steel**
**BRASS • COPPER**
**Anodes • Bright Nickel**

*Write for Seymour's Alloy Selection Chart*


**The SEYMOUR Manufacturing Co.**
**21 Franklin St., Seymour, Conn.**

For more information, turn to Reader Service card, circle No. 473

---

## CERROTECHNICS saves TIME • LABOR • MONEY

**in machining turbine rotors**



**(CERROTECHNICS is the practice of using low-temperature-melting CERRO* ALLOYS to expedite many industrial operations).**

Here we show how an aircraft manufacturer supports the thin blades of a turbine rotor in CERROBEND® ALLOY to prevent distortion in machining. After machining, the matrix alloy is melted away at 158°F.

CERRO

Send for bulletin listing the 63 CERRO ALLOY applications.


*T.M. Cerro de Pasco Corporation

**CERRO DE PASCO SALES CORPORATION**
Room R, 312 Park Avenue, New York 22, N. Y.

For more information, turn to Reader Service card, circle No. 397

# ALUMINUM

in stock at
**FRASSE**



Regardless of grade, shape or size ...it's likely the aluminum you want can be shipped *immediately from stock by Frasse*. Frasse aluminum inventories are at an all-time peak —every pound of dependable quality... produced to rigid standards by Reynolds.

And, if you wish—Frasse aluminum specialists will gladly help with grade selection... or prescribe the most economical method of fabrication. You'll like the *fast delivery*... the *uniform quality*... and the *careful handling* your aluminum orders receive at Frasse. Call us whenever you need aluminum.


*FRASSE for* ALUMINUM

Rod • Bar • Wire • Sheet • Plate • Structurals • Extrusions
Tubing • Holobar • Pipe • Valves • Fittings • Tool and Jig Plate

Peter A. Frasse & Co., Inc.

| NEW YORK 13, N.Y. | PHILADELPHIA 29, PA. | BUFFALO 5, N.Y. | SYRACUSE 1, N.Y. | HARTFORD, 1 CONN. |
|---|---|---|---|---|
| 17 Grand St. | 3911 Wissahickon Ave. | P.O. Box 102 | P.O. Box 1267 | P.O. Box 1949 |
| WAlker 5-2200 | BAldwin 9-9900 | BEdford 4700 | HOward 3-8655 | JAckson 9-6861 |

For more information, turn to Reader Service card, circle No. 518




## No need to substitute for

# HUSSEY COPPER

Hussey

**COPPER • BRASS • BRONZE**

**PHOSPHOR BRONZE**


**NICKEL SILVER**

**SHEET, ROD, WIRE, SHAPES**
**in all degrees of finish**

**TUBING • PIPE**

***WRITE***
for Hussey Copper Stock List
of products, sizes, grades.




MADE IN U.S.A.
TO THE STANDARDS
OF AMERICAN INDUSTRY

The price is right . . . to permit the use of genuine Hussey Copper in every application where copper's lasting qualities and functional advantages are known to serve best. Better still, Hussey Copper is truly representative of that well-known American Quality Standard that is unmatched by copper from any other source. Substitute metals can now be a thing of the past and your products can enjoy the full effectiveness of copper for electrical and thermal conductivity, corrosion-resistance, durability, ease of forming and joining, and all its other inherent advantages. Complete mill or warehouse service is ready to meet your needs.

**C. G. HUSSEY & COMPANY**
*(Division of Copper Range Co.)*
Rolling Mills and General Offices
2840 Second Ave.
**PITTSBURGH 19, PENNSYLVANIA**

For more information, turn to Reader Service card, circle No. 496

# *New Frontiers for Refractory Metals*

Space-age metallurgists are mapping whole new worlds. Exploring the rich fields of refractory metals, they have toppled heat barriers, reached new heights of strength, and penetrated the nature of corrosion behavior. Their discoveries are helping to chart not only the course of rocketry, but also of electronics, atomic energy, and chemical processing. Union Carbide Metals Company has pioneered the development of many of these metals, some of which are briefly described here for you.



**Cr Chromium**—The pure metal has been successfully hot-extruded into tubes, rods, and flat stock. Highly resistant to corrosion and oxidation, it shows u.t.s. of 80,000 psi up to 1000 deg. F. and alloy research may lead to higher strengths. Available as powder and flakes.

**Cb Columbium**—Growing in popularity with space-age designers as a structural material for space craft, alloys of this metal provide excellent strength and a high degree of oxidation and shock resistance up to 2600 deg. F. Superconductive near absolute zero, columbium has been used successfully in cryogenics. Certain nuclear reactor designs take advantage of its low thermal neutron capture cross-section, and its corrosion resistance has placed it in chemical processing service. Available as melting stock.

**Ta Tantalum**—Capacitors and power tube components utilize this metal's superior electrical characteristics. Tantalum clad is also being used in nuclear reactors. As an alloy or pure metal, its top-flight resistance to oxidizing and reducing chemical media has led to increased uses in chemical and pharmaceutical fields as well as in surgical equipment. Melting stock is available.

**V Vanadium**—Recent advances in vanadium technology have resulted in higher purity metal. The pure metal is ductile, "works" like steel, and can be welded. It is now available as melting stock and in a variety of mill forms: wire, rod, sheet, foil, and plate. One of its newest uses is as an interlayer for bonding titanium to steel. It can withstand the corrosive action of reducing acids, and it retains good strength up to 1500 deg. F. In the atomic energy field, vanadium reactor tubing does not form brittle phases with uranium fuel alloys, and it resists the corrosion of liquid-sodium coolant.

***Get technical information about any or all of these modern metals. Simply mail the coupon at right.***

UNION CARBIDE METALS

**Union Carbide Metals Company, Division of Union Carbide Corporation, Box 330, Niagara Falls, New York**

*Please send me the latest data on*

☐ CHROMIUM ☐ TANTALUM
☐ COLUMBIUM ☐ VANADIUM

Name_____ Title_____

Address_____

City_____ Zone____ State_____

"Union Carbide" is a registered trade mark of Union Carbide Corporation.

**Platinum does it for less.** An important supplier of platinum catalysts for The Pure Oil Company and other refiners is Engelhard Industries, Inc., Newark, N. J., leading suppliers and fabricators of platinum metals, including catalysts...

# Where any metal but Platinum would cost too much...

Why do The Pure Oil Company and other refiners use precious platinum in the processing of high octane gasoline?

The answer is simple economy. Their use of platinum catalyst is the means of getting the quality desired...at low cost.

The fact that the platinum in the "spent" catalyst is recoverable is another important advantage.

The superior activity of platinum metals catalysts has led to the essential roles they play in the processing of vitamins, pharmaceuticals, agricultural and other chemicals.

## It could pay you to use a platinum metal.

Many reactions you are interested in might be more efficiently performed with one of the platinum metals...where peak catalytic efficiency is required as in the refining of high octane gasoline...where underwater hull protection is a problem...where a combination of severe corrosion and erosion must be met, as in the case of spinnerettes for rayon production...where wear-resisting, non-tarnishing surfaces are required, such as for printed electrical circuits... or where product purity must be retained despite high temperatures, as in the case of lens glasses...the platinum metals have proved to be the most economical for certain critical equipment.

Industry is going to higher temperatures and higher pressures. Perhaps your own progress has been blocked by the limitations of materials to withstand such severe conditions. The platinum metals have removed many barriers. Have you considered them for your problem?

Platinum, palladium, rhodium, ruthenium and iridium have unique potentials, well worth your attention. Specialists are prepared to work closely with you in evaluating these metals for new commercial and scientific uses.

As a first step, write us for additional data on the outstanding characteristics and successful applications of the six platinum metals and their alloys — indicating your field of interest or how we might be of assistance.

| CAN THESE PROPERTIES OF THE PLATINUM METALS HELP YOU? |
|---|
| Peak Catalytic Activity |
| Exceptional Chemical Inertness |
| Superior Wear Resistance |
| High Temperature Stability |
| Low Vapor Pressure |

*The six platinum metals are:*
PLATINUM • PALLADIUM • RHODIUM • RUTHENIUM • IRIDIUM • OSMIUM


**PLATINUM METALS DIVISION**
The International Nickel Company, Inc., 67 Wall Street, New York 5, N.Y.

**For more information, circle No. 433**



THE WALL STREET JOURNAL,

OGRESS IN REFINING



Loading catalyst (see circle) into catalytic reforming unit at o P

# How platinum - 3/4 of a ton of it - helps put more go in PURE Gaso

**(Another advanced refining process we use—so that you can be sure with PURE)**

To meet the requirements of today's high-compression auto engines, PURE and a number of other oil companies go so far as to use a precious metal—platinum—in their refining operations.

If you saw it, you wouldn't recognize PURE's platinum. We use three-quarters of a ton of it, mixed with tons of other material in the form of small pellets. It's plenty valuable—worth well over $1 million. But it's worth more than that in what it means to Pure Oil customers: better gasoline and improved engine performance.

Platinum is the working ingredient in the catalytic reformers at our refineries. Remaining unchanged itself, the catalyst rearranges and reforms the molecules in naphtha vapor, originally low in quality rating, to make a high-quality blending component for gasoline. PURE has built giant reformers like the one above as part of our program of improving our facilities to meet the never-ending demand for better petroleum products. Another reason why you can be sure—at nearly 16,000 Pure Oil dealers in 24 states.

THE PURE OIL COMPANY, 35 E. Wacker Dr., Chicago 1

PURE

Materials Technology Series . . .

# VACUUM METALLURGY

*Contents and Contributors:*

**PART I—Vacuum Equipment**
- Vacuum Pumping Systems—*H. A. Steinherz*
- Vacuum Gauges, Leak Detection and Trouble Shooting—*William Maher*

**PART II—Thermodynamics & Kinetics**
- Thermodynamics & Kinetics in Vacuum Metallurgy—*Thomas B. King*
- Thermodynamics & Kinetics in Vacuum Induction Melting—*A. M. Aksoy*
- Thermodynamics & Kinetics in Vacuum Arc Melting—*P. C. Rossin*

**PART III—Arcs and Arc Melting Processes**
- Arc Phenomena—Basic and Applied —*E. W. Johnson*
- Selection of Power Supply and Methods of Arc Electrode Motion Control—*E. J. Barreboch*
- Survey of European Arc Melting—*H. Gruber*
- Consumable Electrode Arc Melting of Non-Refractory Metals—*S. J. Noesen and R. M. Parke*
- Skull and Permanent Electrode Melting —*John L. Ham*

**PART IV—Induction Melting Processes**
- Induction Melting of Ingot Products —*W. E. Jones*
- Induction Melting of Cast Shapes —*P. W. Beamer*

**PART V—Electron Bombardment Melting Techniques**
- *Hugh R. Smith, Jr.*

**PART VI—Degassing in the Liquid and Solid States**
- Degassing in the Liquid State—*Max Auwarter*
- Deoxidation of Steel in Vacuum —*A. M. Samarin*
- Effect of Liquid Steel Treatment in Vacuum on the Composition and Properties of Some Steels—*A. M. Samarin*
- Degassing and Heat Treatment in the Solid State—*R. F. Gunow*

**PART VII—Distillation of Metals**
- Distillation of Metals Under Reduced Pressures —*H. W. St. Clair*

**PART VIII—Metallurgical Application of Vacuum Processing**
- Ferrous Base Alloys—*A. M. Aksoy*
- High Temperature Alloys—*M. E. Cieslicki*
- Refractory Metals—*Ivor E. Campbell*
- Nuclear Power Plant Materials—*Arthur P. Beard*
- Electronic Materials—*C. W. Horsting*
- Powder Metallurgical Products—*M. H. Hausner*
- Vacuum Coatings for Metals—*Philip J. Clough*

**PART IX—Analytical Techniques**
- Analytical Techniques for Vacuum Processed Metals and Alloys—*Frank C. Benner*

**PART X—Future Trends**
- Future Trends in Vacuum Metallurgy —*James H. Moore*


**Bibliography**

*Edited by*

**R. F. BUNSHAH**

*Department of Metallurgical Engineering*

*College of Engineering*
*New York University*




**1958, 490 pages, $12.50**

The aim of this book is to provide the engineering field with a complete, up-to-date reference on vacuum metallurgy. It is the result of a course on the subject held for engineers and research workers at New York University in 1957.

The book encompasses virtually the entire field—production and measurement of vacuum; vacuum melting techniques (including the new electron bombardment); degassing of metals; and the metallurgical applications of vacuum processing to powdered and electronic materials, coatings, and high temperature alloys. Much new material resulting from basic research as well as that based on practical engineering data is included. There is also a treatment of the specific applications of the concepts of thermodynamics and kinetics to vacuum metallurgy and a discussion of future trends.

The book has particular importance to the missile, aircraft, atomic energy and electronics industries, or wherever the high quality material produced by vacuum processing is needed.

*Free Examination Order Form*

**MAIL THIS COUPON TODAY!**

**REINHOLD PUBLISHING CORPORATION**

**Dept. M-704, 430 Park Ave., New York 22, N. Y.**

Please send me VACUUM METALLURGY to read and examine. In 10 days I will return the book and owe nothing, or I will remit $12.50, plus postage.


NAME_____

ADDRESS_____

CITY_____ ZONE_____ STATE_____

SAVE MONEY! Enclose payment with order and Reinhold pays all shipping costs. Same return privilege, refund guaranteed. Please add 3% sales tax on N. Y. C. orders. DO NOT ENCLOSE CASH!


RELIABLE ALWAYS ...ALWAYS AVAILABLE!




Specify **WBD** ...unexcelled

# Precision Alloys

## engineering/production facilities



Wilbur B. Driver Company's Sendzimir Mills produce high accuracy in rolling




The WBD vacuum melting installation is the largest in the industry



This entire building is devoted to research and engineering at WBD

## ...plus fast service nation-wide



The Newark plant incorporates executive and general offices



Cleveland warehouse is a typical WBD regional headquarters



West coast manufacturing plant located in Santa Maria, California

Specifying WBD precision alloys means quality alloys delivered quickly, in the quantities you require. Backing up the WILBUR B. DRIVER reputation for reliable performance are two complete manufacturing plants, a fully-equipped research and engineering facility, sales offices and warehouses strategically located across the nation, and in Canada. When you need alloys — in wire, rod, ribbon or strip — check with WBD for *complete* dependability!

**WILBUR B. DRIVER CO.**

NEWARK 4, NEW JERSEY
Telephone: HUmboldt 2-5550

Branch Offices and Warehouses in Principal Cities. Manufacturing Plants: 1875 McCarter H'way, Newark 4, N. J. 2734 Industrial Way, Santa Maria, California. Canadian Wilbur B. Driver Co., Ltd., Rexdale (Toronto), Canada.

**Precision Electrical, Electronic, Mechanical and Chemical Alloys for All Requirements**

For more information, turn to Reader Service card, circle No. 406

# SUPPLIERS' LITERATURE

## Plastics and Rubber

**Plastics Molding Compounds.** Allied Chemical Corp., Plastics & Coal Chemicals Div., 10 pp. Briefly outlines characteristics and applications of melamine, urea, alkyd and nylon molding compounds, and polyester and phenolic resins. **67**

**Urea and Melamine.** American Cyanamid Co., Plastics and Resins Div., 4 pp. Charts give properties, tests and conditioning procedures, and typical applications of urea and melamine molding compounds. **68**

**Molded Polyester.** Atlas Powder Co., Chemicals Div., 4 pp, illus. Characteristics, costs and advantages of molded reinforced polyester parts used in a centrifugal pump. **69**

**Polypropylene.** Avisun Corp., No. 35935P. Electrical, chemical, physical and mechanical properties of general purpose extrusion and injection molding polypropylene polymer. **70**

**ABS Resins.** Marbon Chemical Div., Borg-Warner Corp., 12 pp, illus. Advantages, characteristics, typical applications, available types, and mechanical, physical, thermal, and electrical properties of ABS. **71**

**Plastics Molding Compounds.** Catalin Corp. of America, 4 pp, illus. General information, and typical uses of polypropylene, polyethylene, polystyrene, styrene copolymers, and nylon injection molding, blow molding, and extrusion compounds. **72**

**Plastics Materials.** Celanese Corp. of America, Plastics Div., 8 pp, illus. General descriptions; physical, chemical, electrical and mechanical properties; and typical applications of high density polyethylene, cellulose propionate, cellulose acetate, and polyester resins. **73**

**Selecting Molded Plastics.** Chicago Molded Products Corp., 8 pp, illus. Several case histories describe design and selection of molded plastics parts. **74**

**Hardener for Epoxy Resins.** Ciba Products Corp., 10 pp, illus., No. 25. Typical properties, applications, pot life and curing cycles of a safety hardener for epoxy resins. **75**

**Polyester-Glass Laminates.** Continental-Diamond Fibre Corp., 4 pp, illus. Physical, mechanical and electrical properties of polyester-glass laminates. **76**

**Coated Fabrics.** Cordo Chemical Corp., 5 pp. Properties, uses and prices for a line of lead powder-filled vinyl-coated cotton duck and glass fabrics. **77**

**Synthetic Rubber.** E. I. du Pont de Nemours & Co., Inc., Elastomer Chemicals Dept., 8 pp, illus., No. 93. Series of short articles describe neoprene industrial V belts; Viton heavy duty shock mounts; adiprene pallet wheels; Hypalon hose for sulfuric acid; and urethane foam helicopter seats. **78**

**Nylon, Acetal Resins.** E. I. du Pont de Nemours & Co., Inc., Polychemicals Dept., 8 pp, illus., No. A-13039. Discussion of properties and costs of nylon and acetal resins for application in the metal field. **79**

**Plastics-Impregnated Materials.** Fabricon Products Div., Eagle-Picher Co., 20 pp, illus. Information on phenolic-impregnated papers and fabrics; polyester, epoxy, silicone and phenolic-impregnated glass cloth; and custom impregnated materials. **80**

**Low Density Polyethylene.** Eastman Chemical Products, Inc., 3 pp. General information, advantages, characteristics, and physical properties of three new low density polyethylenes. **81**

**Plastics Laminates.** Farley & Loetscher Mfg. Co., Plastics Div., 4 pp. Uses and properties of paper and fabric-base high pressure plastics laminates. **82**

**High Temperature Insulation.** Fiberite Corp., 16 pp, illus. Characteristics, properties, moulding techniques and uses of a line of variously reinforced plastic compounds for high temperature insulation. **110**

**Nylon Insulation.** Firestone Plastics Co., Chemical Sales Div., 20 pp, illus. Advantages, characteristics, properties and other technical information on several types of nylon used for electrical insulation. **83**

**Epoxy Resins.** Food Machinery & Chemical Corp., Chemicals & Plastics Div., 24 pp, No. 1. Properties, characteristics, formulations, curing systems, costs and applications of three new epoxy resins. **84**

**Laminated Plastics.** General Electric Co., Laminated Products Dept., 16 pp, illus., No. L-CDL-494. Applications, available sizes, grades and properties of laminated plastics sheet, tube and rod. **85**

**Plastics Laminates.** Glastic Corp., 1 p, illus. Properties, prices and track resistance of reinforced plastics laminates for use as insulation in humid, contaminated atmospheres. **86**

**Polyester Resins.** Glidden Co., Paint & Varnish Div. Information on the advantages and applications of polyester resins. **87**

**Synthetic Rubber.** B. F. Goodrich Chemical Co., 12 pp, illus. Corrosion resistance, uses, general characteristics, and properties of nitrile, polyacrylic, butyl and styrene synthetic rubbers. **88**

**Plastics Resins.** Durez Plastics Div., Hooker Chemical Corp., 8 pp, illus., No. D400. Properties and uses of phenolic and diallyl phthalate molding compounds, fire retardant polyester resins for reinforced plastics, and phenolic resins for bonding and coating. **89**

**Butyl Rubber.** Enjay Chemical Co., Div. of Humble Oil & Refining Co., 12 pp, illus., No. 2d/En. Weather, sunlight, chemical, solvent and heat resistance, electrical properties and uses of butyl rubber. **90**

**Liquid Epoxy Resin.** Koppers Co., Inc., 20 pp, No. K-2967. Chemical and physical properties, compatibility with other resins, applications, curing systems and casting compositions of a liquid epoxy resin. **91**

**Electrical Resins.** Minnesota Mining & Mfg. Co., Electrical Products Div., Scotchcast, 28 pp, illus. Typical properties, specifications, outstanding characteristics, uses and information on how to select resins to insulate, seal and protect electrical equipment. **92**

**Plastics Materials.** Monsanto Chemical Co., 12 pp, illus. Properties and uses of polystyrene, polyethylene and vinyl chloride molding compounds. Information also on fabricating, extruding, calendering and laminating materials and adhesives. **93**

**Plastics Extrusions.** National Vulcanized Fibre Co., 4 pp, illus. Facilities for making extruded shapes and fabricated parts from nylon, acetal and chlorinated polyether resins. Advantages, uses and limitations of the three plastics materials. **94**

**Plastics Laminates.** New England Laminates Co., Inc., illus. Properties, prices and design information on epoxy-glass, epoxy-paper and phenolic-paper laminated plastics sheets. **95**

**Phenolics.** Plastics Engineering Co., 16 pp, illus. General information on phenolic molding compounds, including available colors, range of properties and typical advantages and applications. **96**

**TFE Fluorocarbon.** Polymer Corp. of Pa., 8 pp, illus., No. DR-4. Characteristics and advantages of TFE fluorocarbon stock shapes and fabricated parts. Included are complete property tables and descriptions of typical applications for rod, tubing, tape and sheet. **97**

**Plastics Products.** Raybestos-Manhattan, Inc., Plastics Products Div., 32 pp, illus. Properties, uses and spe-

*more literature on p 260*

*To get literature, use free post cards on pp 585-592*

PROPERTIES OF MATERIALS

# Plastics and Rubber


PAGE

186 Suppliers' Literature
188 Acrylics—Cast, Molded, Extruded
189 Alkyds—Molded
190 Cellulose Acetate—Molded, Extruded
191 Cellulose Acetate Butyrate, Cellulose Propionate—Molded, Extruded
192 Cellulose Nitrate, Ethyl Cellulose—Molded, Extruded
193 Diallyl Phthalate—Molded
194 Epoxies—Cast, Molded
195 Fluorocarbons—Molded, Extruded
196 Melamines—Molded
198 Polyamides (Nylons)—Molded, Extruded
200 Phenolics—Molded
203 Phenolics—Cast
204 Polyesters—Cast
205 Silicones—Molded
206 Polystyrenes, Modified Polystyrenes—Molded, Extruded
207 ABS Resins, Methylstyrenes—Molded Extruded
208 Polyethylenes—Molded, Extruded
210 Polyvinyl Chloride and Copolymers—Molded, Extruded
211 Polyvinyl Alcohol, Butyral and Formal—Molded, Extruded
212 Acetal, Polycarbonate, Polypropylene, Chlorinated Polyether—Molded, Extruded
213 Ureas—Molded
214 Plastics Films
218 High Pressure Laminates (General Purpose)—Sheet, Rod, Tube
220 High Pressure Laminates (Mechanical)—Sheet, Rod, Tube
222 High Pressure Laminates (Electrical)—Sheet, Rod, Tube
224 Glass-Reinforced Plastics (Low Pressure)—Molded Laminates
225 Plastics and Rubber Foams—Flexible
226 Plastics Foams—Rigid
227 Hard Rubber—Molded, Extruded
228 Rubber—Molded, Extruded
230 Advertisements

## Acrylics—Cast, Molded, Extruded

| Type → | | Cast Resin Sheets, Rods | | Moldings | |
|---|---|---|---|---|---|
| | | General Purpose Type I[a] | General Purpose Type II[a] | Grades 5, 6, 8[b] | High Impact Grade |
| **PHYSICAL PROPERTIES** | ASTM | | | | |
| Specific Gravity | D792 | 1.18-1.19 | 1.18-1.19 | 1.18-1.19 | 1.12-1.16 |
| Ther Cond, Btu/hr/sq ft/°F/ft | [c] | 0.10-0.15 | 0.10-0.15 | 0.12 | 0.12 |
| Coef of Ther Exp, $10^{-5}$ per °F | D696 | 5 | 5 | 3-4 | 3 |
| Spec Ht, Btu/lb/°F | | 0.35 | 0.35 | 0.35 | 0.34 |
| Refractive Index | D542 | 1.485-1.500 | 1.485-1.495 | 1.489-1.493 | — |
| Transmittance (luminous, 0.125 in.), % | D791 | 91-92 | 91-92 | >92 | — |
| Haze, % | D672 | 1-2 | 1-2 | <3 | — |
| Water Absorption (24 hr), % | D570 | 0.3-0.4 | 0.2-0.4 | 0.3-0.4 | 0.3 |
| Flammability (0.125 in.), ipm | D635 | 0.5-2.5 | 0.5-2.5 | 0.9-1.2 | — |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638 | 3.5-4.5 | 4.0-5.0 | 3.5-5.0 | 2.3-3.0 |
| Ten Str, 1000 psi | D638 | 6-8 | 8-10 | 9.5-10.5 | 5.5-7.3 |
| Elong (in 2 in.), % | D638 | 2-7 | 2-7 | 3-5 | >25 |
| Hardness (Rockwell) | D785 | M90-100 | M96-102 | M80-103 | L58-89 |
| Impact Str (Izod notched), ft-lb/in. | D256 | 0.5 | 0.4 | 0.2-0.4 | 0.8-2.0 |
| Mod of Elast in Flex, $10^5$ psi | D790 | 3.5-4.5 | 4.0-5.0 | 3.5-5.0 | 2.8-3.6 |
| Flex Str, 1000 psi | D790 | 12-14 | 15-17 | 15-16 | 8.7-11.5 |
| Compr Yld Str (0.1% offset), 1000 psi | D695 | 10-12 | 12-14 | 14.5-17 | — |
| **ELECTRICAL PROPERTIES** | | | | | |
| Vol Res, ohm-cm | D257 | $>10^{15}$ | $>10^{15}$ | $>10^{14}$ | $2.0 \times 10^{16}$ |
| Dielec Str (short time), v/mil | D149 | 450-500 | 450-500 | 400 | 400-500 |
| Dielec Const | | | | | |
| 60 Cycles | D150 | 3.5-4.5 | 3.5-4.5 | 3.5-3.9 | 3.0-4.0 |
| $10^6$ Cycles | D150 | 2.7-3.2 | 2.7-3.2 | 2.7-2.9 | 2.0-3.0 |
| Dissip Factor | | | | | |
| 60 Cycles | D150 | 0.05-0.06 | 0.05-0.06 | 0.04-0.06 | 0.03-0.04 |
| $10^6$ Cycles | D150 | 0.02-0.03 | 0.02-0.03 | 0.02-0.03 | 0.01-0.02 |
| Arc Resistance, sec | | No track | No track | No track | No track |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | | — | — | 1.8-2.2 | — |
| Injection Molding | | | | | |
| Pressure, 1000 psi | | — | — | 10-20 | 10-20 |
| Temperature, F | | — | — | 320-500 | 400-490 |
| Hot Forming Temp, F | | 250-320 | 280-340 | 240-350 | — |
| Extruding Temp, F | | — | — | 350-450 | — |
| **HEAT RESISTANCE** | | | | | |
| Max Rec Svc Temp, F | | 140-160 | 180-200 | 155-190 | — |
| Heat Dist Temp, F | | 150-170 | 190-210 | 166-202[d] | 169-174 |
| **CHEMICAL RESISTANCE** | | Resist weak alkalis, acids and aliphatic hydrocarbons. Attacked by esters, ketones, aromatic hydrocarbons, chlorinated hydrocarbons and concentrated acids | | | |
| **USES** | | Transparent aircraft enclosures, radio and television parts, lighting, drafting equipment, signs | | Decorative and functional automotive parts, reflectors, protective goggle lenses, radio and television parts, household appliance parts | Shoe heels, control knobs, business machine and piano keys, pump parts, sprinkler heads, tool handles |

[a] ASTM D702-46.
[b] Range includes typical values for Grades 5, 6, and 8, and may be superior to minimum or maximum requirements for these grades as detailed in ASTM D788-56T.
[c] Cenco-Fitch. [d] D788 specified values for Grades 5, 6 and 8: 149 F, 162 F, 183 F respectively.

## Alkyds—Molded

| Type → | | Granular (general purpose) | Putty (electrical) | Glass-Reinforced (impact) |
|---|---|---|---|---|
| PHYSICAL PROPERTIES | ASTM | | | |
| Specific Gravity | D792 | 2.22–2.24 | 2.05–2.15 | 2.00–2.08 |
| Ther Cond, Btu/hr/sq ft/°F/ft | | 0.35–0.60 | 0.35–0.60 | 0.20–0.30 |
| Coef of Ther Exp, per °F | D696 | 1–3 x $10^{-5}$ | 1–3 x $10^{-5}$ | 1–3 x $10^{-5}$ |
| Water Absorption (24 hr), % | D570 | 0.08–0.10 | 0.05–0.08 | 0.07–0.10 |
| Flammability, ipm | D635 | Self-extinguishing | Self-extinguishing | Self-extinguishing |
| MECHANICAL PROPERTIES | | | | |
| Tensile Strength, 1000 psi | D651 | 3–4 | 3–4 | 6–10 |
| Impact Strength (Izod notched), ft-lb/in. | D256 | 0.30–0.35 | 0.30–0.35 | 8–12 |
| Mod of Elast in Flexure, psi | D790 | 22–27 x $10^5$ | 22–27 x $10^5$ | 22–28 x $10^5$ |
| Flexural Strength, 1000 psi | D790 | 7–10 | 7–10 | 14–17 |
| Compressive Strength, 1000 psi | D695 | 16–20 | 18–20 | 24–28 |
| ELECTRICAL PROPERTIES | | | | |
| Volume Resistivity, ohm-cm | D257 | $10^{14}$ | $10^{14}$ | $10^{14}$ |
| Dielectric Strength (step by step), v/mil | D149 | 300–350 | 300–350 | 300–350 |
| Dielectric Constant | | | | |
| 60 Cycles | D150 | 6.0–6.5 | 6.0–6.5 | 5.2–6.0 |
| $10^6$ Cycles | D150 | 4.8–5.0 | 4.2–4.5 | 4.0–4.5 |
| Dissipation Factor | | | | |
| 60 Cycles | D150 | 0.050–0.060 | 0.035–0.040 | 0.02–0.03 |
| $10^6$ Cycles | D150 | 0.016–0.018 | 0.014–0.015 | 0.017–0.022 |
| FABRICATING PROPERTIES | | | | |
| Bulk Factor | D954 | 1.95–2.15 | 1.1–1.2 | 9–11 |
| Compression Molding | | | | |
| Pressure, 1000 psi | | 1.0–1.5 | 0.8–1.0 | 1.5–2.0 |
| Temperature, F | | 270–330 | 270–330 | 270–330 |
| HEAT RESISTANCE | | | | |
| Max Rec Svc Temp (limited periods), F | | 350 | 300 | 350 |
| Heat Dist Temp (264 psi), F | D648 | 350–400 | 350–400 | >400 |
| CHEMICAL RESISTANCE | | Resistant to weak acids; attacked by alkalis; practically unattacked by organic liquids such as alcohols, hydrocarbons and fatty acids | | |
| USES | | Ignition parts, fuse blocks, switch and circuit breaker covers and bases, molded resistors and capacitors, television tuner segments | | |

## Cellulose Acetate—Molded, Extruded

| Type → | | Type I —Medium[a] | Type II—Hard[a] | | | Type III —Soft[a] |
|---|---|---|---|---|---|---|
| | | | H6 | H4 | H2 | |
| PHYSICAL PROPERTIES | ASTM | | | | | |
| Specific Gravity | D792... | 1.23–1.34 | 1.29–1.34 | 1.28–1.34 | 1.27–1.34 | 1.27–1.34 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177... | 0.10–0.19 | 0.10–0.19 | 0.10–0.19 | 0.10–0.19 | 0.10–0.19 |
| Coef of Ther Exp, $10^{-5}$ per °F | D696... | 4.4–9.0 | 4.4–9.0 | 4.4–9.0 | 4.4–9.0 | 4.4–9.0 |
| Refractive Index | D542... | 1.46–1.50 | 1.46–1.50 | 1.46–1.50 | 1.46–1.50 | 1.46–1.50 |
| Spec Ht, Btu/lb/°F | ..... | 0.3–0.42 | 0.3–0.42 | 0.3–0.42 | 0.3–0.42 | 0.3–0.42 |
| Transmittance (luminous), % | D791... | 80–90 | 75–90 | 75–90 | 80–90 | 80–95 |
| Haze, % | D672... | 2–10 | 2–15 | 2–15 | 2–10 | 2–8 |
| Water Absorption (24 hr), % | D570... | 1.7–5.7 | 1.5–3.5 | 1.7–3.6 | 1.7–5.3 | 2.3–6.5 |
| Flammability, ipm[b] | D635... | 0.5–2.0 | 0.5–2.0 | 0.5–2.0 | 0.5–2.0 | — |
| MECHANICAL PROPERTIES | | | | | | |
| Ten Str, 1000 psi | D638... | 2.7–6.5 | 6–8.5 | 5.4–8.2 | 4.6–7.5 | 1.9–4.7 |
| Elong (in 2 in.), % | D638... | 18–54 | 6–31 | 10–35 | 17–40 | 32–70 |
| Hardness (Rockwell) | D785... | R68–115 | R112–123 | R106–121 | R95–119 | R39–103 |
| Impact Str (Izod notched), ft-lb/in. | D256... | 1.1–4.0 | 0.4–1.9 | 0.6–2.3 | 0.7–2.7 | 1.7–5.2 |
| Mod of Elast in Flex, $10^3$ psi | ..... | 1.1–3.5 | 2.6–4.0 | 1.9–3.4 | 1.6–3.3 | 0.5–2.5 |
| Compr Str, 1000 psi | D695... | 14.5–25 | 25–36 | 22–33 | 19–28 | 13–20 |
| ELECTRICAL PROPERTIES | | | | | | |
| Vol Res, ohm-cm | D257... | $10^{10}$–$10^{13}$ | $10^{10}$–$10^{13}$ | $10^{10}$–$10^{13}$ | $10^{10}$–$10^{13}$ | $10^{10}$–$10^{13}$ |
| Dielec Str (short time), v/mil | D149... | 250–600 | 250–600 | 250–600 | 250–600 | 250–600 |
| Dielec Const | | | | | | |
| 60 Cycles | D150... | 3.5–7.5 | 3.5–7.5 | 3.5–7.5 | 3.5–7.5 | 3.5–7.5 |
| $10^6$ Cycles | D150... | 3.2–7.0 | 3.2–7.0 | 3.2–7.0 | 3.2–7.0 | 3.2–7.0 |
| Dissipation Factor | | | | | | |
| 60 Cycles | D150... | 0.03–0.38 | 0.03–0.38 | 0.03–0.38 | 0.03–0.08 | 0.03–0.08 |
| $10^6$ Cycles | D150... | 0.03–0.33 | 0.03–0.33 | 0.03–0.33 | 0.03–0.33 | 0.03–0.33 |
| FABRICATING PROPERTIES | | | | | | |
| Bulk Factor | | 2.0–2.6 | 2.0–2.6 | 2.0–2.6 | 2.0–2.6 | 2.0–2.6 |
| Compression Molding | | | | | | |
| Pressure, psi | | 500–5000 | 500–5000 | 500–5000 | 500–5000 | 500–5000 |
| Temperature, F | | 300–400 | 390–475 | 375–450 | 350–425 | 290–330 |
| Injection Molding | | | | | | |
| Pressure, 1000 psi | | 8–32 | 8–32 | 8–32 | 8–32 | 8–32 |
| Temperature, F | | 355–450 | 420–490 | 410–480 | 390–460 | 335–395 |
| Extruding Temp, F | | 335–450 | 420–450 | 405–455 | 390–420 | 335–365 |
| HEAT RESISTANCE | | As these are thermoplastic materials, they gradually become softer as the temperature rises. Maximum service temperature depends on such factors as formula, design of part, humidity and service conditions | | | | |
| CHEMICAL RESISTANCE | | Unattacked by water, salt water solutions, white gasoline, oleic acid, 5% acetic acid and dilute sulfuric acid. Decomposed by 30% sulfuric, 10% nitric and 10% hydrochloric acids; sodium hydroxide; and 10% ammonium hydroxide. Dissolved by acetone and ethyl acetate | | | | |
| USES | | Automotive and radio knobs, tool handles, business machine keys. Electrical items such as fluorescent lamp supports, coil spools and contact bases. Toys and novelties, sunglass goggles and frames, spectacle frames, buttons and tags, appliance housings, shoe heels | | | | |

[a] ASTM D706-55T.
[b] Self-extinguishing compositions are available.

# Cellulose Acetate Butyrate and Cellulose Propionate—Molded, Extruded

| Type → | | Cellulose Acetate Butyrate | | | Cellulose Propionate[b] |
|---|---|---|---|---|---|
| | | Type I[a] (Medium) | Type II[a] (Hard) | Type III[a] (Soft) | |
| **PHYSICAL PROPERTIES** | ASTM | | | | |
| Specific Gravity | D792 | 1.16-1.24 | 1.19-1.25 | 1.15-1.22 | 1.18-1.24 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177 | 0.10-0.19 | 0.10-0.19 | 0.10-0.19 | 0.10-0.19 |
| Coef of Ther Exp (max), per °F | D696 | 6-9 x $10^{-5}$ | 6-9 x $10^{-5}$ | 6-9 x $10^{-5}$ | 7-9 x $10^{-5}$ |
| Refractive Index | D542 | 1.46-1.49 | 1.46-1.49 | 1.46-1.49 | 1.46-1.48 |
| Spec Ht, Btu/lb/°F | | 0.3-0.4 | 0.3-0.4 | 0.3-0.4 | 0.3-0.4 |
| Transmittance (luminous), % | D791 | 80-92 | 75-92 | 85-95 | 80-92 |
| Haze, % | D672 | 2-5 | 2-5 | 2-5 | 2-5 |
| Water Absorption (24 hr), % | D570 | 1.3-2.1 | 1.5-2.2 | 1.1-2.1 | 1.2-2.0 |
| Flammability, ipm[c] | D635 | 0.5-1.5 | 0.5-1.5 | 0.5-1.5 | 1.0-1.5 |
| **MECHANICAL PROPERTIES** | | | | | |
| Ten Str, 1000 psi | D638 | 2.9-5.7 | 5.0-6.8 | 1.9-3.8 | 1.5-7.5 |
| Elong, % | | 47-66 | 38-54 | 60-74 | 50-60 |
| Hardness (Rockwell) | | R79-112 | R108-114 | R59-95 | R20-120 |
| Impact Str (Izod notched), ft-lb/in. | D256 | 1.0-4.3 | 0.6-2.4 | 2.5-5.4 | 0.8-11.0 |
| Mod of Elast in Flex, psi | | 0.93–1.7 x $10^5$ | 1.5–2.0 x $10^5$ | 0.74–1.3 x $10^5$ | 1.6–3.3 x $10^5$ |
| Flex Str, 1000 psi | | No break | No break | No break | No break |
| **ELECTRICAL PROPERTIES** | | | | | |
| Vol Res, ohm-cm | D257 | $10^{10}$-$10^{12}$ | $10^{10}$-$10^{12}$ | $10^{10}$-$10^{12}$ | $10^{12}$-$10^{15}$ |
| Dielec Str (short time), v/mil | D149 | 250-400 | 250-400 | 250-400 | 300-450 |
| Dielec Const | | | | | |
| 60 Cycles | D150 | 3.5-6.4 | 3.5-6.4 | 3.5-6.4 | — |
| $10^6$ Cycles | D150 | 3.2-6.2 | 3.2-6.2 | 3.2-6.2 | 3.4-3.6 |
| Dissip Factor | | | | | |
| 60-Cycles | D150 | 0.01-0.04 | 0.01-0.04 | 0.01-0.04 | — |
| $10^6$ Cycles | D150 | 0.01-0.04 | 0.01-0.04 | 0.01-0.04 | 0.02-0.03 |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | | 2.0-2.4 | 2.0-2.4 | 2.0-2.4 | 1.6-2.0 |
| Compression Molding | | | | | |
| Pressure, 1000 psi | | 18 | 18 | 0.5-5 | — |
| Temperature, F | | 285-340 | 320-390 | 265-305 | — |
| Injection Molding | | | | | |
| Pressure, 1000 psi | | 8-32 | 8-32 | 8-32 | 8-32 |
| Temperature, F | | 355-440 | 390-480 | 335-395 | 335-480 |
| Mold Shrinkage, in./in. | | 0.001-0.008 | 0.001-0.009 | 0.001-0.006 | 0.002-0.006 |
| **HEAT RESISTANCE** | | | | | |
| Heat Dist Temp, F | | | | | |
| 66 Psi | D648 | 156-197 | 188-233 | 139-164 | 130-200 |
| 264 Psi | D648 | 130-172 | 158-210 | 121-137 | 100-190 |
| **CHEMICAL RESISTANCE** | | Unaffected by 3% sulfuric, 5% acetic, 10% hydrochloric and oleic acids; discolored by 10% nitric acid. Unaffected by 1% sodium hydroxide and 2% sodium carbonate; slightly softened by 10% sodium hydroxide and discolored by 10% ammonium hydroxide. Unaffected by white gasoline, but swollen or dissolved by ethyl alcohol, acetone, ethyl acetate, ethylene dichloride, carbon tetrachloride and toluene. Unaffected by water, salt water and 3% hydrogen peroxide | | | |
| **USES** | | Telephone handsets, steering wheels, automobile white-wall disks, film spools, irrigation tubing, radio housings. Electrical items such as fluorescent light supports, coil spools and contact bases. | | | Pen and pencil parts, telephone handsets. Other uses similar to those of butyrate |

[a] ASTM D707-55T.
[b] Values given are for compounds having different plasticizer contents.
[c] Self-extinguishing cellulose acetate butyrate compounds are available.

## Cellulose Nitrate and Ethyl Cellulose—Molded, Extruded

| Type → | | Cellulose Nitrate Sheet | Ethyl Cellulose Moldings | | |
|---|---|---|---|---|---|
| | | | General Purpose | High Impact | |
| | | | | A | B |
| **PHYSICAL PROPERTIES** | ASTM | | | | |
| Specific Gravity | D792 | 1.35-1.40 | 1.10-1.16 | 1.10-1.16 | 1.10-1.16 |
| Ther Cond, Btu/hr/sq ft/°F/ft | Cenco-Fitch | 0.133 | 0.092-0.167 | 0.092-0.167 | 0.092-0.167 |
| Coef of Ther Exp, $10^{-5}$ per °F | D696 | 4.4-6.6 | 5.5-11 | 5.5-11 | 5.5-11 |
| Refractive Index | D542 | 1.49-1.51 | 1.47 | 1.47 | 1.47 |
| Transmittance (luminous), % | D791 | 89-92[a] | — | — | — |
| Haze, % | D672 | 2.0-4.0[a] | — | — | — |
| Water Absorption (24 hr), % | D570 | 1.0-2.0 | 1.2-2.0 | 0.8-2.0 | 1.0-2.0 |
| Flammability (>0.050 in.), ipm | D635 | [b] | 0.5-1.5 | 0.5-1.5 | 0.5-1.5 |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638 | 1.9-2.2 | 0.5-3.5 | 1.0-3.0 | 1.0-3.0 |
| Ten Str, 1000 psi | D638 | 7-8 | 3-7 | 4-6.5 | 3-5 |
| Strain at Fracture, % | D638 | 40-50 | — | — | — |
| Hardness (Rockwell) | D785 | R95-115 | R80-120 | R80-90 | R70-80 |
| Impact Str (Izod notched), ft-lb/in. | D758 | 5-7 | 1.7-6.0 | 3.5-6.0 | 4.0-7.0 |
| Mod of Elast in Flex, $10^5$ psi | D790 | 2.3-2.5 | — | — | — |
| Flex Str, 1000 psi | D790 | 9-11[c] | 4-10 | 6 | 4 |
| Compr Str, 1000 psi | D695 | 22-35 | — | — | — |
| **ELECTRICAL PROPERTIES** | | | | | |
| Vol Res, ohm-cm | D257 | 10-15 x $10^{10}$ | $10^{12}$-$10^{14}$ | $10^{12}$-$10^{14}$ | $10^{12}$-$10^{14}$ |
| Dielec Str (short time), v/mil | D149 | 300-600 | 350-500 | 350-500 | 350-500 |
| Dielec Const | | | | | |
| 60 Cycles | D150 | 7.0-7.5 | — | — | — |
| $10^6$ Cycles | D150 | 6.4 | 2.8-3.5 | 2.8-3.3 | 3.0-3.6 |
| Dissip Factor | | | | | |
| 60 Cycles | D150 | 0.09-0.12 | — | — | — |
| $10^6$ Cycles | D150 | 0.06-0.09 | 0.010-0.060 | 0.010-0.030 | 0.018-0.035 |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | | — | 1.8-2.4 | 1.8-2.4 | 1.8-2.4 |
| Compression Molding | | | | | |
| Pressure, 1000 psi | | — | 0.5-5 | 0.5-5 | 0.5-5 |
| Temperature, F | | — | 250-390 | 250-390 | 250-390 |
| Injection Molding | | | | | |
| Pressure, 1000 psi | | — | 6-32 | 8-32 | 8-32 |
| Temperature, F | | — | 350-500 | 350-500 | 350-500 |
| Hot Forming Temperature, F | | 135-250 | — | — | — |
| Extruding Temperature, F | | 180-200 | 300-450 | 350-450 | 350-450 |
| **HEAT RESISTANCE** | | | | | |
| Max Rec Svc Temp, F | | 120-140 | — | — | — |
| Heat Dist Temp, F | | | | | |
| 66 Psi | | 200-220 | — | — | — |
| 264 Psi | | 140-160 | 120-160 | 130-145 | 125-140 |
| **CHEMICAL RESISTANCE** | | Resistant to 30% sulfuric acid, carbon tetrachloride, 10% sodium chloride, 10% nitric acid, 10% hydrochloric acid, 5% acetic acid, 2% sodium tetrachloride, distilled water, aliphatic and aromatic hydrocarbons, and < 1% sodium hydroxide. Soluble in ketones, esters, lower alcohols and glycol ethers. Attacked by concentrated sodium hydroxide, ethylene dichloride and 50% ethanol | | Unaffected by 3 sulfuric, 5 acetic and 10% hydrochloric acids; 10% sodium hydroxide, 2% sodium carbonate and water. Slightly affected by 30 sulfuric and 10% nitric acids; and 10% ammonium hydroxide. Attacked by 95% ethyl alcohol, acetone, toluene and gasoline | |
| **USES** | | Fountain pens, spectacle frames, drawing instruments, ping-pong and billiard balls | | Radio housings, toothbrushes, pen and pencil barrels, tool handles | |

[a] ⅛-in. sheet containing no color.
[b] Cellulose nitrate under 0.050 in. thick burns very rapidly (D568).
[c] No break; specimen failed by slipping through supports.

## Diallyl Phthalate—Molded

| Type → | | Orlon-Filled | Dacron-Filled | Asbestos-Filled | Glass Fiber-Filled |
|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | ASTM | | | | |
| Specific Gravity | D792... | 1.31–1.34 | 1.40 | 1.65–1.70 | 1.55–1.59 |
| Coef of Ther Exp, per °F | D696... | $1.5 \times 10^{-5}$ | $2.0 \times 10^{-5}$ | $3.5 \times 10^{-6}$ | $2.2–2.6 \times 10^{-5}$ |
| Water Abs (122 F, 48 hr), % | ..... | 0.2–0.5 | 0.2–0.5 | 0.4–0.5 | 0.2–0.4 |
| Flammability (ignition time), sec | ..... | 68 | 84–90 | 70 | 70–400 |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, psi[a] | D638... | $6 \times 10^5$ | — | $12 \times 10^5$ | — |
| Ten Str, psi | D638... | 4500–6000 | 4600–6000 | 4000–5500 | 5500–7000 |
| Hardness (Rockwell) | D785... | M108 | — | M107 | M108 |
| Impact Str (Izod notched), ft-lb/in. | D256... | 0.5–1.2 | 1.7–4.5 | 0.30–0.45 | 0.5–6.0 |
| Flex Str, 1000 psi | D790... | 10–10.5 | 9–11.5 | 8–10 | 10–18 |
| Compr Str, 1000 psi | D695... | 20–30 | 20–30 | 18–25 | 25 |
| **ELECTRICAL PROPERTIES** | | | | | |
| Dielec Str, v/mil | | | | | |
| Short Time (dry) | D149... | 400 | 376–390 | 450 | 350–430 |
| Short Time (wet[b]) | D149... | 375 | 360–391 | 400 | 300–420 |
| Step by Step (dry) | D149... | 350 | 350–374 | 400 | 300–420 |
| Step by Step (wet[b]) | D149... | 325 | 350–361 | 350 | 275–420 |
| Dielec Breakdown, kv | | | | | |
| Short Time (dry) | ..... | 65–75 | 70–80 | 55–80 | 63–70 |
| Short Time (wet[b]) | ..... | 60–65 | 66–70 | 55 | 45–65 |
| Step by Step (dry) | ..... | 55–60 | 60–65 | 38–70 | 60–65 |
| Step by Step (wet[b]) | ..... | 46–60 | 50–60 | 39–60 | 49–65 |
| Dissip Factor[c] | | | | | |
| Dry | D150... | 0.023, 0.015 | 0.008, 0.015 | 0.05, 0.03 | 0.01, 0.015 |
| Wet[d] | D150... | 0.026, 0.020 | 0.009, 0.017 | 0.042, 0.154 | 0.012, 0.020 |
| Dielec Const[c] | | | | | |
| Dry | D150... | 3.9, 3.3 | 3.8, 3.4 | 5.2, 4.5 | 4.5, 4.2 |
| Wet[d] | D150... | 4.1, 3.4 | 3.9, 3.6 | 4.8, 4.2 | 4.6, 4.4 |
| Vol Res, megohm-cm[d] | D257... | 60,000 | 100–25,000 | 6000 | 40,000 |
| Surface Res, megohms[d] | D257... | 25,000 | 500–25,000 | 6000 | 25,000 |
| Arc Resistance, sec | D495... | 85–115 | 105–125 | 125–140 | 125 |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | D392... | 3.5–5.2 | 3.5–5.2 | 1.9–2.4 | 1.9–5.0 |
| Compression Molding | | | | | |
| Pressure, psi | ..... | 500–2000 | 500–2000 | 500–2000 | 500–2000 |
| Temperature, F | ..... | 270–290 | 270–290 | 270–320 | 270–320 |
| Transfer Molding | | | | | |
| Pressure, psi | ..... | 1000–5000 | 1000–5000 | 1000–5000 | 1000–5000 |
| Temperature, F | ..... | 270–290 | 270–290 | 270–310 | 270–310 |
| Mold Shrinkage, in./in. | ..... | 0.009 | 0.010 | 0.004–0.007 | 0.001–0.004 |
| Post-Mold Shrinkage (480 hr, 257 F), in./in. | ..... | 0.001 | 0.0006 | 0.0005 | 0.0005–0.0007 |
| **HEAT RESISTANCE** | | | | | |
| Max Rec Svc Temp, F | ..... | 300 | 300–370 | 350–450 | 400–450 |
| Heat Dist Temp, F | D648... | 240–266 | 270–290 | 300–350 | 400–500 |
| **CHEMICAL RESISTANCE** | | Unaffected by weak acids and alkalis and organic solvents. Slightly affected by strong acids and alkalis | | | |

[a] Conditioned 48 hr at 122 F.
[b] Tested after 48-hr immersion in water at 122 F.
[c] Values given for frequencies of 1 kc and 1 mc, in that order.
[d] Conditioned 30 days at 100% RH and 158 F.

## Epoxies—Cast, Molded

| Type → | | Cast | | | Molded [b] |
|---|---|---|---|---|---|
| | | General Purpose | Resilient | Heat Resistant | |
| PHYSICAL PROPERTIES | ASTM | | | | |
| Specific Gravity | D792... | 1.12–2.4 | 1.0–1.25 | 1.15–3.2 | 1.8–1.85 |
| Ther Cond, Btu/hr/sq ft/°F/ft | D325... | 0.1–0.8 | 0.1 | 0.1–0.8 | — |
| Coef of Ther Exp, per °F | D696... | $1.7–5.0 \times 10^{-5}$ | $2.8–4.4 \times 10^{-5}$ | $2.8–3.3 \times 10^{-5}$ | $1.4 \times 10^{-5}$ [c] |
| Water Absorption (24 hr), % | D570... | 0.1–0.5 | 0.4 | 0.01–0.2 | 0.06 |
| Linear Mold Shrinkage, in./in. | ..... | 0.001–0.01 | — | 0.01 | 0.004–0.006 |
| Flammability, ipm | D635... | 0.3 to self-exting | — | 0.3 to self-exting | Self-exting |
| MECHANICAL PROPERTIES | | | | | |
| Ten Str, 1000 psi | D651... | 2–12 | 0.1–4.0 | 5–14 | 8–10 |
| Elongation, % | D651... | 2–6 | 150–10 | 2–5 | — |
| Hardness (Rockwell) | D785... | M75–110 | [a] | M90–110 | M110 |
| Impact Str (Izod), ft lb/in. notch | D256... | 0.2–0.7 | 0.5–7.0 | 0.2–1.5 | 0.3–0.8 |
| Mod of Elast in Flex, $10^5$ psi | D790... | 0.4–1.5 | Up to 0.2 | 0.4–1.5 | 1.3–2.2 |
| Flex Str, 1000 psi | D790... | 8–20 | Up to 15 | 8–20 | 11–15.7 [d] |
| Compr Str, 1000 psi | D695... | 20–40 | 3–20 | 25–40 | 25–26 |
| ELECTRICAL PROPERTIES | | | | | |
| Vol Res, ohm-cm | D257... | $10^{13}–10^{14}$ | $10^{11}–10^{13}$ | $10^{13}–10^{14}$ | $0.1–9 \times 10^{15}$ |
| Dielec Str (⅛ in.), v/mil | | | | | |
| Short Time | D149... | 350–550 | 350–550 | 350–550 | 372–468 |
| Step-by-Step | D149... | 350–550 | 350–550 | 350–550 | 334–450 |
| Surface Res, ohms | D257... | $10^{13}–10^{14}$ | $10^{13}–10^{13}$ | $10^{13}–10^{14}$ | $64 \times 10^{13}$ |
| Dielectric Constant | | | | | |
| 60 Cycles | D150... | 3.5–5.0 | 3.5–4.5 | 4.0–4.5 | 4.4–5.4 |
| 1000 Cycles | D150... | 3.5–5.0 | 3.3 | 3.8–4.1 | — |
| $10^6$ Cycles | D150... | 3.4–4.4 | 2.6–2.8 | 3.5–4.0 | 4.1–4.6 |
| Dissipation Factor | | | | | |
| 60 Cycles | D150... | 0.001–0.015 | 0.05 | 0.005–0.013 | — |
| 1000 Cycles | D150... | 0.002–0.017 | 0.04 | 0.012–0.015 | — |
| $10^6$ Cycles | D150... | 0.015–0.035 | 0.04 | 0.012–0.032 | — |
| Loss Factor | | | | | |
| 60 Cycles | D150... | 0.02–0.07 | — | 0.022 | 0.119–0.207 |
| 1000 Cycles | D150... | 0.02–0.09 | — | 0.053 | — |
| $10^6$ Cycles | D150... | 0.09–0.13 | — | 0.12 | 0.111 |
| Arc Resistance, sec | D495... | 65–100 | — | 65–120 | 148–180 |
| HEAT RESISTANCE | | | | | |
| Max Rec Svc Temp, F | ..... | 175 | 122 | 400 | — |
| Heat Dist Temp (264 psi), F | D648... | Up to 250 | — | Up to 500 | 210–320 |
| USES | | Potting and encapsulation of electrical and electronic components, precision castings, tools and dies, patching compounds | | | New materials; primary uses probably electrical moldings of all types, such as condensers, switch plates, connector plugs, resistor bobbins and wirewound resistors, molded coils, relay assemblies |

[a] Shore A up to 100.
[b] Values cover range obtainable with mineral filler or mineral and glass fiber filler. Compounds designed for compression or transfer molding without release agents. Data, in some cases are preliminary.
[c] 77–140 F. [d] After post-cure.

## Fluorocarbons—Molded, Extruded

| Type → | | Polytrifluorochloroethylene | Polytetrafluoroethylene | Fluorinated Ethylene Propylene |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | ASTM | | | |
| Specific Gravity | D792... | 2.10–2.15 | 2.1–2.3 | 2.14–2.17 |
| Ther Cond, Btu/hr/sq ft/°F/ft | [a] | 0.145 | 0.14 | 0.11 |
| Coef of Ther Exp, per °F | D696... | $3.88 \times 10^{-5}$ | $5.5 \times 10^{-5}$ | $8.3–10.5 \times 10^{-5}$ |
| Refractive Index | D542... | 1.43 | 1.35 | 1.34 |
| Specific Heat, Btu/lb/°F | ..... | 0.22 | 0.25 | 0.28 |
| Transmittance (luminous), % | D791... | 80–92 | — | — |
| Water Absorption (24 hr), % | D570... | 0.00 | 0.00 | 0.00 |
| Flammability | ..... | Noninflammable | Noninflammable | Noninflammable |
| **MECHANICAL PROPERTIES** | | | | |
| Mod of Elast in Compression, psi | D638... | $1.8 \times 10^5$ | $0.70–0.90 \times 10^5$ | $0.6–0.8 \times 10^5$ |
| Mod of Elast in Tension, psi | D638... | $1.9–3.0 \times 10^5$ | $0.38–0.65 \times 10^5$ | $0.5–0.7 \times 10^5$ |
| Tensile Strength, 1000 psi | D638... | 4.6–5.7 | 2.5–3.5 | 2.5–3.5 |
| Elongation (in 2 in.), % | D638... | 125–175 | 250–350 | 300–900 |
| Hardness (Rockwell) | D785... | R110–115 | J75–95 | D55 |
| Abrasion Resistance, gm/cycle | [b] | 0.0080 | — | — |
| Impact Strength (Izod notched), ft-lb/in. | D256... | 3.50–3.62 | 2.5–4.0 | No break |
| Mod of Elast in Flexure, psi | D747... | $2.0–2.5 \times 10^5$ | $0.6 \times 10^5$ | $0.8 \times 10^5$ |
| Flexural Strength (0.1% offset), 1000 psi | D790... | 3.5 | 1.6 | — |
| Compressive Strength (0.1% offset), 1000 psi | D695... | 2.0 | 0.7–1.8 | 1.6 |
| **ELECTRICAL PROPERTIES** | | | | |
| Volume Resistivity, ohm-cm | D257... | $10^{16}$ | $10^{19}$ | $10^{19}$ |
| Dielectric Strength (short time), v/mil | D149... | 530–600 | 400–500 | 500–600 |
| Dielectric Constant | | | | |
| 60 Cycles | D150... | 2.6–2.7 | 2.0 | 2.1 |
| $10^6$ Cycles | D150... | 2.30–2.37 | 2.0 | 2.1 |
| Dissipation Factor | | | | |
| 60 Cycles | D150... | 0.02 | 0.0002 | 0.0003 |
| $10^6$ Cycles | D150... | 0.007–0.010 | 0.0002 | 0.0006 |
| Arc Resistance, sec | ..... | >360 | >200 | >165 |
| **FABRICATING PROPERTIES** | | | | |
| Injection Molding | | | | |
| Pressure, 1000 psi | ..... | 5–30 | — | 5–20 |
| Temperature, F | ..... | 420–620 | — | 625–760 |
| Compression Molding | | | | |
| Pressure, 1000 psi | ..... | 0.1–15 | — | 1–2 |
| Temperature, F | ..... | 445–525 | — | 600–750 |
| Bulk Factor | ..... | 2.5 | — | — |
| Mold Shrinkage, in./in. | ..... | 0.005–0.010 | — | 0.03–0.06 |
| **HEAT RESISTANCE** | | | | |
| Max Rec Svc Temp, F | ..... | 380 | 500 | 400 |
| Heat Dist Temp, F | | | | |
| 66 Psi | D648... | 196–291 | — | — |
| 264 Psi | D648... | 151–178 | — | — |
| **CHEMICAL RESISTANCE** | | Impervious to corrosive chemicals; highly resistant to most organic solvents. Swelling may occur with some highly halogenated and aromatic compounds | Inert to most chemicals and solvents with the exception of alkali metals. Halogenated solvents at high temperatures and pressure have some effect | |
| **USES** | | Chemical pipes, gaskets, pump parts, electrical cables, tank linings, connectors, coil forms, connector inserts, valve diaphragms, electrical insulation | Chemical pipes, valves and valve liners, gaskets and packings, pump bearings and impellers, electrical and electronic equipment, anti-adhesive coatings | Molded electronic and instrument components, valve linings, laminates, corrosion resistant and non-adhesive coatings |

[a] Cenco-Fitch.
[b] Federal Spec. L-P-406A, No. 1092.1.

## Melamines—Molded

| Filler and Type → | ASTM | Alpha Cellulose—General Purpose | Mineral—Electrical | Fabric—Low to Intermediate Shock Resistant | Fabric—Intermediate Resistance |
|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | | |
| Specific Gravity | D792... | 1.47–1.52 | 1.7–2.0 | 1.5 | 1.5 |
| Ther Cond, Btu/hr/sq ft/°F/ft | ..... | 0.17–0.24 | 0.32–0.41 | 0.257 | 0.25–0.26 |
| Coef of Ther Exp per °F | D696... | $1.11–3.17 \times 10^{-5}$ | $1.06–2.50 \times 10^{-5}$ | $1.55 \times 10^{-5}$ | $1.55 \times 10^{-5}$ |
| Transmittance (luminous), % | ..... | 14.5 | Opaque | Low | — |
| Water Absorption (24 hr), % | D570... | 0.1–0.6 | 0.08–0.14 | 0.3–0.6 | 0.2–1.3 |
| Flammability | ..... | Self-extinguishing | Self-extinguishing | Self-extinguishing | Self-extinguishing |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, psi | D638... | $13–16 \times 10^5$ | $16–19.5 \times 10^5$ | $16 \times 10^5$ | $16 \times 10^5$ |
| Ten Str, 1000 psi | D638... | 7–10 | 5.5–7.0 | 8–9.5 | 5.7–9 |
| Elong (in 2 in.), % | D638... | — | 0.30–0.45 | 0.6–0.8 | 0.6 |
| Hardness (Rockwell) | D785... | M118–124, E110 | M110 | M120 | M115 |
| Impact Str (Izod notched), ft-lb/in. | D256... | 0.24–0.35 | 0.28–0.40 | 0.5–0.9 | 1.0–1.5 |
| Mod of Elast in Flex, psi | D790... | $15 \times 10^5$ | $16 \times 10^5$ | $18.5 \times 10^5$ | $19 \times 10^5$ |
| Compr Str, 1000 psi | D695... | 40–45 | 25–30 | 30–35 | 25–32 |
| Flex Str, 1000 psi | D790... | 10–16 | 8.7–11 | 12–15 | 13–17 |
| **ELECTRICAL PROPERTIES** | | | | | |
| Vol Res, ohm-cm | D257... | $10^{12}–10^{14}$ | $10^{11}–10^{13}$ | $10^{9}–10^{12}$ | — |
| Dielec Str (short time), v/mil | D149... | 310–330 | 350–430 | 250–350 | 130–370 |
| Dielec Const | | | | | |
| 60 Cycles | D150... | 8.4–9.4 | 6.4–10.2 | 7.6–8.6 | 10.5–15.5 |
| $10^6$ Cycles | D150... | 5.6–5.8 | 6.1–6.7 | 6.5–6.9 | 6.1–6.7 |
| Dissip Factor | | | | | |
| 60 Cycles | ..... | 0.05–0.08 | 0.07–0.17 | 0.07–0.11 | 0.10–0.32 |
| $10^6$ Cycles | ..... | 0.03–0.04 | 0.04–0.05 | 0.036 | 0.050–0.065 |
| Arc Resistance, sec | D495... | 122–128 | 120–170 | 115–128 | 5–8 |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | D392... | 2.1–3.1 | 2.1–2.5 | 5–10 | 5–10 |
| Compression Molding | | | | | |
| Pressure, 1000 psi | ..... | 1.5–8 | 1–7 | 4–8 | 4–8 |
| Temperature, F | ..... | 280–370 | 275–340 | 275–330 | 300–380 |
| Transfer Molding | | | | | |
| Pressure, 1000 psi | ..... | 4–12 | 4–20 | — | — |
| Temperature, F | ..... | 300–320 | 270–340 | — | — |
| Mold Shrinkage, in./in. | ..... | 0.006–0.015 | 0.003–0.007 | 0.003–0.004 | 0.004–0.005 |
| **HEAT RESISTANCE** | | | | | |
| Max Rec Svc Temp, F | ..... | 210 | 250–400 | 250 | 250 |
| Heat Dist Temp (264 psi), F | D648... | 350–410 | 265 | 310 | 375 |
| **CHEMICAL RESISTANCE** | | Resistant to weak acids, weak alkalis, organic solvents, greases and oils. Attacked by strong acids and strong alkalis | | | |
| **USES** | | General purpose electrical and mechanical applications such as kitchenware, tableware, lighting fixtures, reflectors | Elevated temperature and electrical applications such as ignition parts, circuit breakers, terminal blocks, electronic parts | Applications requiring improved impact strength, such as insulation, circuit breakers, food trays, medical equipment | Applications requiring medium impact strength, such as nozzles, insulation |

## Melamines—Molded

| Filler and Type → | | Unfilled | Cellulose Electrical | Glass Fiber | Alpha Cellulose and Mineral |
|---|---|---|---|---|---|
| PHYSICAL PROPERTIES | ASTM | | | | |
| Specific Gravity | D792... | 1.48 | 1.43–1.50 | 1.9–2.0 | 1.49 |
| Ther Cond, Btu/hr/sq ft/°F/ft | ..... | — | 0.17–0.20 | 0.28 | — |
| Coef of Ther Exp, per °F | D696... | — | $1.11–2.78 \times 10^{-5}$ | $0.82 \times 10^{-5}$ | — |
| Transmittance (luminous), % | ..... | Good | Opaque | — | — |
| Water Absorption (24 hr), % | D570... | 0.3–0.5 | 0.27–0.80 | 0.10–0.60 | 0.5 |
| Flammability | ..... | Self-extinguishing | Self-extinguishing | Self-extinguishing | Self-extinguishing |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | D638... | — | $10–11 \times 10^5$ | — | — |
| Ten Str, 1000 psi | D638... | — | 5–9 | 6–10 | 5 |
| Elong (in 2 in.), % | D638... | — | 0.6 | — | — |
| Hardness (Rockwell) | D785... | — | M115–125 | — | — |
| Impact Str (Izod notched), ft-lb/in. | D256... | — | 0.27–0.36 | 4.0–12.0 | 0.30 |
| Mod of Elast in Flex, psi | D790... | $13 \times 10^5$ | $1.0–1.3 \times 10^5$ | — | — |
| Compr Str, 1000 psi | D695... | 40–45 | 25–33.6 | 26–32 | — |
| Flex Str, 1000 psi | D790... | 11–14 | 9–10 | 10–23 | 8 |
| ELECTRICAL PROPERTIES | | | | | |
| Vol Res, ohm-cm | D257... | — | $10^{12}–10^{13}$ | $1–7 \times 10^{11}$ | $10^{12}$ |
| Dielec Str (short time), v/mil | D149... | — | 350–400 | 250–300 | 375 |
| Dielec Const | | | | | |
| 60 Cycles | D150... | — | 6.2–7.6 | 9.7–11.1 | — |
| $10^6$ Cycles | D150... | — | 4.7–7.0 | 6.9–7.2 | 6.4 |
| Dissip Factor | | | | | |
| 60 Cycles | ..... | — | 0.019–0.033 | 0.14–0.23 | — |
| $10^6$ Cycles | ..... | — | 0.032–0.06 | 0.02–0.03 | 0.031 |
| Arc Resistance, sec | D495... | 100–145 | 95–135 | 180–186 | 125 |
| FABRICATING PROPERTIES | | | | | |
| Bulk Factor | D392... | 2.0 | 2.2–2.6 | 5–7 | 2.4 |
| Compression Molding | | | | | |
| Pressure, 1000 psi | ..... | 2–5 | 1.5–3 | 2–8 | 2–5 |
| Temperature, F | ..... | 300–340 | 290–360 | 280–340 | 280–350 |
| Transfer Molding | | | | | |
| Pressure, 1000 psi | ..... | — | 6–20 | 8–20 | 2–10 |
| Temperature, F | ..... | — | 300–330 | 290–310 | 285–350 |
| Mold Shrinkage, in./in. | ..... | 0.011–0.012 | 0.006–0.008 | 0.001–0.004 | 0.006–0.007 |
| HEAT RESISTANCE | | | | | |
| Max Rec Svc Temp, F | ..... | 210 | 250–280 | 300–400 | 275–325 |
| Heat Dist Temp (264 psi), F | D648... | 293–298 | 265 | 400 | 300 |
| CHEMICAL RESISTANCE | | Resistant to weak acids, weak alkalis, organic solvents, greases and oils. Attacked by strong acids and strong alkalis | | | |
| USES | | Pearlescent buttons, moldings ornamental applications | General mechanical and electrical applications, particularly at elevated temperatures. Applications requiring improved holding power for metallic inserts such as electrical and electronic parts | Applications requiring high shock resistance, good electrical properties, and high resistance to burning. Switchgear, terminal strips, stand-off insulators, coil forms | Primarily electrical applications requiring low after-shrinkage, good dimensional stability and excellent molding characteristics |

## Polyamides (Nylons)—Molded, Extruded

| Type → | | 66 Nylon | | | 610 Nylon | |
|---|---|---|---|---|---|---|
| | | General Purpose Injection Molding | | Extrusion and Injection Molding | Extrusion and Injection Molding | |
| | | 0.2% Water | 2.5% Water | | 0.2% Water | 1.5% Water |
| **PHYSICAL PROPERTIES** | ASTM | | | | | |
| Specific Gravity | D792... | 1.14 | — | 1.14 | 1.09 | — |
| Ther Cond, Btu/hr/sq ft/°F/ft | a | 0.14 | — | 0.142 | 0.12 | — |
| Coef of Ther Exp, $10^{-5}$ per °F | D696... | 5.5 | — | 5.5 | 5.5 | — |
| Spec Ht, Btu/lb/°F | ..... | 0.3–0.5 | — | 0.4 | 0.3–0.5 | — |
| Refractive Index | D542... | 1.53 | — | — | 1.53 | — |
| Water Absorption (24 hr), % | D570... | 1.5 | — | 1.5 | 0.4 | — |
| Flammability | D757... | Self-extinguishing | Self-extinguishing | Self-extinguishing | Self-extinguishing | Self-extinguishing |
| **MECHANICAL PROPERTIES** | | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638... | 4.1 | 1.75 | 4.0 | 2.8 | 1.6 |
| Ten Str, 1000 psi | D638... | 11.8 | 11.2 | 11.2–12.6 | 8.5 | 7.1 |
| Elong (in 2 in.), % | D638... | 60 | 300 | 100–200 | 85 | 320 |
| Hardness (Rockwell) | D785... | M79, R118 | M59, R108 | R118 | R111 | — |
| Impact Str (Izod notched), ft-lb/in. | D256... | 0.9 | 2.0 | 1.1–1.5 | 0.6 | 1.6 |
| Mod of Elast in Flex, $10^5$ psi | D790... | 4.1 | 1.75 | — | 2.8 | 1.6 |
| Flex Yld Str, 1000 psi | D790... | 13.8 | — | 13.8 | 8 | — |
| Compr Yld Str, 1000 psi | D695... | 13 | — | — | 7.2 | — |
| Compr Yld Str (1% def), 1000 psi | D695... | — | — | 4.9 | — | — |
| **ELECTRICAL PROPERTIES** | | | | | | |
| Vol Res, ohm-cm | D257... | — | — | $4.5 \times 10^{13}$ | — | — |
| Dielec Str (short time), v/mil | D149... | 385 | — | 385 | 470 | — |
| Dielec Const | | | | | | |
| 60 Cycles | D150... | 4.0 | 7.6 | 4.1 | 3.9 | — |
| $10^6$ Cycles | D150... | 3.6 | 3.6 | 3.4 | — | — |
| Dissip Factor | | | | | | |
| 60 Cycles | D150... | 0.01 | 0.09 | 0.014 | — | — |
| $10^6$ Cycles | D150... | 0.02 | 0.08 | 0.04 | 0.02 | — |
| Arc Resistance, sec | D495... | — | — | — | — | — |
| **FABRICATING PROPERTIES** | | | | | | |
| Bulk Factor | D392... | 2.1 | — | 2.14 | 2.2 | — |
| Injection Molding | | | | | | |
| Pressure, 1000 psi | ..... | 10–20 | — | — | 10–20 | — |
| Temperature, F | ..... | 520–650 | — | — | 450–600 | — |
| Joining | ..... | Can be cemented with aqueous phenol or various proprietary adhesives. Spin welding, extrusion lamination and other techniques can be used in special cases | | | | |
| **HEAT RESISTANCE** | | | | | | |
| Max Rec Svc Temp, F | ..... | 275–300 | — | — | 225 | — |
| Heat Dist Temp, F | | | | | | |
| 66 Psi | D648... | — | — | 360 | — | — |
| 264 Psi | D648... | — | — | 150 | — | — |
| **CHEMICAL RESISTANCE** | | Inert to most organic chemicals such as esters, ketones, alcohols and hydrocarbons. Resist alkalis and salt solutions, but attacked by phenols, formic acid, strong mineral acids and strong oxidizing agents | | | | |
| **USES** | | Gears, bearings, automatic washing machine valves, rollers and slides, combs and brush backs, aerosol bottles, coil forms, and mechanical parts where lubrication is undesirable or difficult | | Tubing, rods, pipe, sheeting, laminations | Jacketing for wire and cable; special molded parts | |

[a]Cenco-Fitch.

## Polyamides (Nylons)—Molded, Extruded

| Type → | | 6 Nylon | | 11 Nylon | Soluble Resin (solution, injection, extrusion) | Glass Fiber-Filled[d] |
|---|---|---|---|---|---|---|
| | | General Purpose Injection Molding | Extrusion and Injection Molding | | | |
| PHYSICAL PROPERTIES | ASTM | | | | | |
| Specific Gravity | D792... | 1.13-1.14 | 1.14 | 1.1 | 1.12-1.13 | 1.30-1.51 |
| Ther Cond, Btu/hr/sq ft/°F/ft | [a] | 0.10-0.14 | 0.11-0.12 | — | 0.16 | 0.12 |
| Coef of Ther Exp, $10^{-5}$ per °F | D696... | 4.6-5.4 | 4.6-7.1 | 5.5 | 8.2 | 1.25-1.7 |
| Spec Ht, Btu/lb/°F | ..... | 0.4 | — | 0.58 | 0.4 | 0.3-0.35 |
| Water Absorption (24 hr), % | D570... | 1.6-2.0 | 2.1-3.3 | 0.4 | 2.0-5.5 | 0.2-1.4 |
| Flammability | D757... | Self-exting | Self-exting | Self-exting | Self-exting | Self-exting |
| MECHANICAL PROPERTIES | | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638... | 2.5-3.4 | 1.5-3.6 | 1.8-1.9 | 0.38 | 1.2-8.6 |
| Ten Str, 1000 psi | D638... | 10.2-12 | 10.2-11.3 | 8.5 | 3.8-7.4 | 19-31 |
| Elong (in 2 in.), % | D638... | 300 | 300 | 100-120 | 300-600 | 1.5-2.3 |
| Hardness (Rockwell) | D785... | R105-118 | R103-111 | A50-55 | R45-83 | E64-79 |
| Impact Str (Izod notched), ft-lb/in. | D256... | 1.2-3.0 | 1.5-3.5 | 3.3-3.6 | >16 | 2.5-5.0 |
| Flex Yld Str, 1000 psi | D790... | 15.5 | — | — | 1-2 | 21-40 |
| Compr Yld Str (1% def), 1000 psi | D695... | 7.1-9.7 | 6.7-8.8 | — | 0.8 | 15-25 |
| ELECTRICAL PROPERTIES | | | | | | |
| Vol Res, ohm-cm | D257... | $10^{13}$-$10^{15}$ | $10^{13}$-$10^{15}$ | 2 x $10^{13}$ | 5 x $10^{13}$ | 1.5-5.5 x $10^{15}$ |
| Dielec Str (short time), v/mil | D149... | 420-485 | 440-500 | 425 | 420 | 400-500 |
| Dielec Const | | | | | | |
| 60 Cycles | D150... | 4.5-11.5 | 5.1-14.0 | 3.3[c] | 10.7 | 4.0-4.6 |
| $10^6$ Cycles | D150... | 3.6-4.3 | 3.5-4.5 | — | 4.5 | 3.4-3.9 |
| Dissip Factor | | | | | | |
| 60 Cycles | D150... | 0.03-0.07 | 0.06-0.10 | 0.03 | 0.19 | 0.018-0.026 |
| $10^6$ Cycles | D150... | 0.03-0.13 | 0.03-0.11 | 0.02 | 0.14 | 0.17-0.22 |
| Arc Resistance, sec | D495... | — | — | — | — | 90-150 |
| FABRICATING PROPERTIES | | | | | | |
| Bulk Factor | D392... | 1.60-1.68 | 1.72-1.82 | 2.2 | 2.5 | 2.0 |
| Compression Molding | | | | | | |
| Pressure, 1000 psi | ..... | — | — | — | 1-2 | — |
| Temperature, F | ..... | — | — | — | 325-380 | — |
| Injection Molding | | | | | | |
| Pressure, 1000 psi | ..... | 10-25 | — | — | 10-25 | 10-25 |
| Temperature, F | ..... | 440-550 | — | — | 300-500 | 500-650 |
| Extruding Temp, F | ..... | 450-550 | 430-550 | — | 500-550 | — |
| Joining | ..... | Nylon adhesive or aqueous phenol | | — | [b] | Same as nylon |
| HEAT RESISTANCE | | | | | | |
| Max Rec Svc Temp, F | ..... | 225-250 | 200-250 | 212-250 | 140 | 300-400 |
| Heat Dist Temp, F | | | | | | |
| 66 Psi | D648... | 340 | — | — | 100 | 430-540 |
| 264 Psi | D648... | 145 | — | — | — | 425-530 |
| CHEMICAL RESISTANCE | | Resists esters, ketones, alkalis, weak acids, alcohols and common solvents. Not resistant to conc mineral acids | Resists petroleum oils and greases, alkalis, esters, ketones, alcohols and common solvents. Not resistant to mineral acids | Similar to other nylons | Resists ketones, alkalis and esters. Not resistant to alcohols, phenols, formic acid, and mineral acids | Attacked by strong acids. Fairly resistant to strong alkalis. Resists common solvents |
| USES | | Bearings, gears, bushings, coil forms, brush backs, rod, tubing, tape | Abrasion resistant shielding oninsulated wire and mechanical cable. Pipe, tubing | Electrical insulation and other nylon uses where low moisture absorption is needed | Jacketing for wire and cable, seals, packings, sheeting, adhesives, abrasion-resistant finishes | Gears, business machine parts, bearing cages, mechanical components |

[a] Cenco-Fitch.
[b] Can be bonded with 70-30 methanol-water as cement, or 10% solution of resin in methanol-water as solvent.
[c] At 1000 cps.
[d] Covers range obtainable in 10 grades.

## Phenolics—Molded

| Type and Filler → | ASTM | General—Woodflour and Flock | Shock—Paper, Flock or Pulp | High Shock—Chopped Fabric or Cord | Very High Shock—Glass Fiber |
|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | | |
| Specific Gravity | D792 | 1.32–1.55 | 1.34–1.46 | 1.36–1.43 | 1.75–1.90 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177 | 0.097–0.3[a] | 0.1–0.16 | 0.097–0.170 | 0.20[a] |
| Coef of Ther Exp, $10^{-5}$ per °F | D696 | 1.66–2.50 | 1.6–2.3 | 1.60–2.22 | 0.88 |
| Spec Ht, Btu/lb/°F | | 0.35–0.40 | — | 0.30–0.35 | 0.28–0.32 |
| Water Absorption (24 hr), % | D570 | 0.3–0.8 | 0.4–1.5 | 0.4–1.75 | 0.1–1.0 |
| Flammability | D635 | Self-extinguishing | Self-extinguishing | Self-extinguishing | Self-extinguishing |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638 | 8–13 | 8–12 | 9–14 | 30–33 |
| Ten Str, 1000 psi | D638, D651 | 5.0–8.5 | 5.0–8.5 | 5–9 | 5–10 |
| Elong (in 2 in.), % | D638 | 0.4–0.8 | — | 0.37–0.57 | 0.2 |
| Hardness (Rockwell) | D785 | M108–120 | — | M93–120 | M95–106 |
| Impact Str (Izod notched), ft-lb/in. | D256 | 0.24–0.50 | — | 0.6–8.0 | 10–33 |
| Mod of Elast in Flex, $10^5$ psi | D790 | 8–12 | — | 9–13 | — |
| Flex Str, 1000 psi | D790 | 8.5–12 | 8.0–11.5 | 8–15 | 10–45 |
| Compr Str, 1000 psi | D695 | 22–36 | 24–35 | 15–30 | 17–30 |
| **ELECTRICAL PROPERTIES** | | | | | |
| Vol Res, ohm-cm | D257 | $10^9$–$10^{13}$ | 1–50 x $10^{11}$ | >$10^{10}$ | 7–10 x $10^{12}$ |
| Dielec Str (short time), v/mil | D149 | 200–425 | 250–350 | 200–350 | 200–370 |
| Dielec Const | | | | | |
| 60 Cycles | D150 | 5.0–9.0 | 5.6–11.0 | 6.5–15.0 | 7.1–7.2 |
| $10^6$ Cycles | D150 | 4.0–7.0 | 4.5– 7.0 | 4.5– 7.0 | 4.6–6.6 |
| Dissip Factor | | | | | |
| 60 Cycles | D150 | 0.05–0.30 | 0.08–0.35 | 0.08–0.45 | 0.02–0.03 |
| $10^6$ Cycles | D150 | 0.03–0.07 | 0.03–0.07 | 0.03–0.09 | 0.02 |
| Arc Resistance, sec | D495 | 5–60 | 5–60 | 5–60 | 60 |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | | 2.1–4.4 | 2.3–5.7 | 3.0–18.0 | 6.1–6.3 |
| Compression Molding | | | | | |
| Pressure, 1000 psi | | 1.5–5.0 | 2–5 | 2–6.5 | 1–5 |
| Temperature, F | | 290–380 | 290–380 | 280–380 | 500–5000 |
| Transfer Molding | | | | | |
| Pressure, 1000 psi | | 2–10 | 2–10 | 2–12 | — |
| Temperature, F | | 275–340 | 275–340 | 275–340 | — |
| Mold Shrinkage, in./in. | | 0.005–0.008 | 0.004–0.009 | 0.002–0.009 | 0.0 |
| **HEAT RESISTANCE** | | | | | |
| Max Rec Svc Temp, F | | 300–350 | 300 | 250–275 | 350–450 |
| Heat Dist Temp, F | D648 | 260–340 | 290–340 | 250–340 | 600 |
| **CHEMICAL RESISTANCE** | | Severely attacked by strong acids and strong alkalis. Effects of dilute acids, alkalis and organic solvents vary with the reagent. Chemical resistance varies with the particular formulation and not all materials of a type are equally resistant | | | |
| **USES** | | Mechanical applications include pulleys, wheels, motor housings, handles. Electrical uses include coil forms, ignition parts, condenser housings, fuse blocks, instrument panels. Thermal applications include handles, appliance connector plugs. Chemical uses include photographic development tanks, rayon spinning buckets and parts, milking machine cups. Decorative uses include radio and television cabinets, handles, knobs, buttons | | | |

[a] Cenco-Fitch.

## Phenolics—Molded

| Type and Filler → | ASTM | High Frequency—Mineral | Shock & Heat—Mineral, Flour and Yarn | Heat—Mineral | Chemical (no filler) |
|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | | |
| Specific Gravity | D792... | 1.75–1.92 | 1.68–2.00 | 1.54–1.75 | 1.24–1.90 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177... | 0.24–0.34 | 0.19–0.39 | 0.19–0.39 | — |
| Coef of Ther Exp, $10^{-5}$ per °F | D696... | 1.05–1.44 | 0.83–1.17 | 1.17 | 2.4 |
| Spec Ht, Btu/lb/°F | ..... | 0.28–0.32 | 0.28–0.32 | 0.28–0.32 | — |
| Water Absorption (24 hr), % | D570... | 0.01–0.07 | 0.1–0.5 | 0.2–0.5 | 0.15–0.60 |
| Flammability | D635... | Self-extinguishing | Self-extinguishing | Self-extinguishing | Self-extinguishing |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638... | 30–50 | 15–25 | 10–20 | 7–15 |
| Ten Str, 1000 psi | D638, D651... | 5–7 | 4–9 | 4–6.5 | 4.5–7.5 |
| Elong (in 2 in.), % | D638... | 0.10–0.53 | — | — | — |
| Hardness (Rockwell) | D785... | M100–110 | M100–110 | M98–115 | M105–120 |
| Impact Str (Izod notched), ft-lb/in. | D256... | 0.30–0.38 | 0.27–3.50 | 0.24–0.40 | 0.2–0.6 |
| Mod of Elast in Flex, $10^5$ psi | D790... | 30–40 | 10–25 | 10–20 | 7–15 |
| Flex Str, 1000 psi | D790... | 8–12 | 7–15 | 3–10.5 | 7–12 |
| Compr Str, 1000 psi | D695... | 15–25 | 15–25 | 15–35 | 18–32 |
| **ELECTRICAL PROPERTIES** | | | | | |
| Vol Res, ohm-cm | D257... | $10^{13}$ | $10^{10}$–$10^{12}$ | $10^{11}$–$10^{12}$ | $10^{11}$ - $10^{12}$ |
| Dielec Str (short time), v/mil | D149... | 300–375 | 100–250 | 150–350 | 225–275 |
| Dielec Const | | | | | |
| 60 Cycles | D150... | 4.7–5.5 | 30–150 | 5.8–40.0 | 9–19 |
| $10^6$ Cycles | D150... | 4.4–5.1 | 5–7 | 4.8– 8.0 | 5.5–7.0 |
| Dissip Factor | | | | | |
| 60 Cycles | D150... | 0.01–0.07 | 0.25–0.50 | 0.10–0.35 | 0.15–0.25 |
| $10^6$ Cycles | D150... | 0.005–0.02 | 0.10–0.50 | 0.04–0.15 | 0.04–0.09 |
| Arc Resistance, sec | D495... | 16 | 6–180 | 5–180 | — |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | ..... | 2.1–2.7 | 3–14 | 2.0–2.8 | 1.9–3.0 |
| Compression Molding | | | | | |
| Pressure, 1000 psi | ..... | 2.0–5.5 | 2–6 | 2–6 | 2–6 |
| Temperature, F | ..... | 300–350 | 290–380 | 290–380 | 300–360 |
| Transfer Molding | | | | | |
| Pressure, 1000 psi | ..... | 2–10 | 2–12. | 2–9 | 2–10 |
| Temperature, F | ..... | 275–325 | 275–325 | 275–325 | 275–340 |
| Mold Shrinkage, in./in. | ..... | 0.003 | 0.0005–0.005 | 0.002–0.006 | 0.002–0.01 |
| **HEAT RESISTANCE** | | | | | |
| Max Rec Svc Temp, F | ..... | 250–300 | 350–400 | 375–425 | 300–425 |
| Heat Dist Temp, F | D648... | 230–325 | 290–375 | 350–400 | 300–350 |
| **CHEMICAL RESISTANCE** | | Severely attacked by strong acids and strong alkalis. Effects of dilute acids, alkalis and organic solvents vary with the reagent. Chemical resistance varies with the particular formulation and not all materials of a type are equally resistant | | | |
| **USES** | | Mechanical applications include pulleys, wheels, motor housings, handles. Electrical uses include coil forms, ignition parts, condenser housings, fuse blocks, instrument panels. Thermal applications include handles, appliance connector plugs. Chemical uses include photographic development tanks, rayon spinning buckets and parts, milking machine cups. Decorative uses include radio and television cabinets, handles, knobs, buttons | | | |

*continued on next page*

## Phenolics—Molded

| Type and Filler → | | Arc Resistant—Mineral | Rubber Phenolic—Woodflour or Flock | Rubber Phenolic—Chopped Fabric | Rubber Phenolic—Asbestos |
|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | ASTM | | | | |
| Specific Gravity | D792... | 1.8–3.0 | 1.24–1.35 | 1.30–1.35 | 1.60–1.65 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177... | 0.24–0.34 | 0.12 | 0.05 | 0.04 |
| Coef of Ther Exp, $10^{-5}$ per °F | D696... | — | 0.83–2.20 | 1.7 | 2.2 |
| Spec Ht, Btu/lb/°F | ..... | 0.28–0.32 | 0.33 | — | — |
| Water Absorption (24 hr), % | D570... | 0.2 | 0.5–2.0 | 0.5–2.0 | 0.10–0.50 |
| Flammability | D635... | Self-extinguishing | Self-extinguishing | Self-extinguishing | Self-extinguishing |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638... | — | 4–6 | 3.5–6 | 5–9 |
| Ten Str, 1000 psi | D638, D651... | 6 | 4.5–9 | 3.5 | 4 |
| Elong (in 2 in.), % | D638... | — | 0.75–2.25 | — | — |
| Hardness (Rockwell) | D785... | — | M40–90 | M57 | M50 |
| Impact Str (Izod notched), ft-lb/in. | D256... | 0.32 | 0.34–1.0 | 2.0–2.3 | 0.3–0.4 |
| Mod of Elast in Flex, $10^5$ psi | D790... | — | 4–6 | 3.5 | 5.0 |
| Flex Str, 1000 psi | D790... | 10 | 7–12 | 7 | 7 |
| Compr Str, 1000 psi | D695... | 20 | 12–20 | 10–15 | 10–20 |
| **ELECTRICAL PROPERTIES** | | | | | |
| Vol Res, ohm-cm | D257... | $6 \times 10^{12}$ | $10^{8}$–$10^{11}$ | $10^{11}$ | $10^{11}$ |
| Dielec Str (short time), v/mil | D149... | 380 | 250–375 | 250 | 350 |
| Dielec Const | | | | | |
| 60 Cycles | D150... | 7.4 | 5–16 | 15 | 15 |
| $10^6$ Cycles | D150... | — | 5 | 5 | 5 |
| Dissip Factor | | | | | |
| 60 Cycles | D150... | — | 0.15–0.60 | 0.5 | 0.15 |
| $10^6$ Cycles | D150... | 0.10 | 0.1–0.2 | 0.09 | 0.13 |
| Arc Resistance, sec | D495... | 180 | 7–20 | 10–20 | 5–20 |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | ..... | 2.4 | 2.5–4.0 | 4.6–8.0 | 2.5 |
| Compression Molding | | | | | |
| Pressure, 1000 psi | ..... | 2–5 | 2–6 | 2–6 | 2–6 |
| Temperature, F | ..... | 285–350 | 300–360 | 300–350 | 300–350 |
| Transfer Molding | | | | | |
| Pressure, 1000 psi | ..... | 2–10 | 2–12 | 2–12 | 2–12 |
| Temperature, F | ..... | 285–350 | 300–350 | 300–350 | 300–350 |
| Mold Shrinkage, in./in. | ..... | 0.004 | 0.005–0.010 | 0.003–0.006 | 0.005–0.008 |
| **HEAT RESISTANCE** | | | | | |
| Max Rec Svc Temp, F | ..... | 400 | 212–300 | 212–225 | 225–260 |
| Heat Dist Temp, F | D648... | 335 | 220–270 | 220–280 | 250–300 |
| **CHEMICAL RESISTANCE** | | Severely attacked by strong acids and strong alkalis. Effects of dilute acids, alkalis and organic solvents vary with the reagent. Chemical resistance varies with the particular formulation and not all materials of a type are equally resistant | | | |
| **USES** | | Mechanical applications include pulleys, wheels, motor housings, handles. Electrical uses include coil forms, ignition parts, condenser housings, fuse blocks, instrument panels. Thermal applications include handles, appliance connector plugs. Chemical uses include photographic development tanks, rayon spinning buckets and parts, milking machine cups. Decorative uses include radio and television cabinets, handles, knobs, buttons | | | |

## Phenolics—Cast

| Type → | | Type I—Mechanical and Chemical | Type II—General Purpose Decorative | Type III—General Purpose Transparent |
|---|---|---|---|---|
| PHYSICAL PROPERTIES | ASTM | | | |
| Specific Gravity | D792... | 1.31 | 1.32 | 1.33 |
| Coef of Ther Exp, per °F | D696... | $3.3–4.4 \times 10^{-5}$ | $3.3–5.5 \times 10^{-5}$ | $4.7–6.6 \times 10^{-5}$ |
| Water Absorption (24 hr), % | D570... | 0.35–0.40 | 0.32–0.35 | 0.3–2.0 |
| Flammability (>0.050 in.) | D635... | Self-extinguishing | Self-extinguishing | Self-extinguishing |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | D638... | $4–5 \times 10^5$ | $3–4.5 \times 10^5$ | $1–3 \times 10^5$ |
| Tensile Strength, 1000 psi | D638... | 6–9 | 5–7.2 | 2.5–4.5 |
| Hardness (Rockwell) | D785... | M93–120 | M90–105 | R98–120 |
| Impact Strength (Izod notched), ft-lb/in | D256... | 0.25–0.40 | 0.30–0.45 | 0.23–0.35 |
| Mod of Elast in Flexure, psi | D790... | $3–5 \times 10^5$ | $3–5 \times 10^5$ | $1–3 \times 10^5$ |
| Flexural Strength, 1000 psi | D790... | 11–17 | 10–15 | 4–7 |
| Compressive Yield Strength (1% offset), 1000 psi | D695... | 14–18 | 12.8–15.8 | 4.5–6.5 |
| ELECTRICAL PROPERTIES | | | | |
| Volume Resistivity, ohm-cm | D257... | $1–7 \times 10^{12}$ | $1–3 \times 10^{12}$ | $3 \times 10^{11}$ |
| Dielectric Strength (short time), v/mil | D149... | 350–400 | 300–450 | 75–250 |
| Dielectric Constant | | | | |
| 60 Cycles | D150... | 6.5–7.5 | 15–20 | 20–30 |
| $10^6$ Cycles | D150... | 4.0–5.5 | 5.0–11.0 | 7–8 |
| Loss Factor | | | | |
| 60 Cycles | D150... | 0.05–0.9 | 0.4–4.0 | 5.0–17.0 |
| $10^6$ Cycles | D150... | 0.15–0.35 | 0.05–1.10 | 0.6–0.8 |
| FABRICATING PROPERTIES | — | Castings produced by pouring resins into molds (generally made of lead). Resins converted to solid by heating several days at atmospheric pressure and temperatures below 212 F. After oven baking, casting is removed from mold and is ready for machining and polishing | | |
| HEAT RESISTANCE | | | | |
| Heat Dist Temp, F | | | | |
| 66 Psi | D648... | — | 150–160 | 125–135 |
| 264 Psi | D648... | 165–175 | 130–140 | 100–125 |
| CHEMICAL RESISTANCE | | Unless specially formulated, do not resist strong alkalis or strong acids. Dilute alkalis: slight to marked attack depending on alkali. Dilute acids: no effect or slight decomposition depending on acid. Continuous immersion in acetone, Cellosolve, methyl alcohol or ethyl alcohol results in noticeable attack, depending on time, temperature and hardness of cast resin | | |
| USES | | Drill and saw jigs, stretch press molds and dies for fabricating aircraft parts, furniture hardware, instrument casings, sporting goods, costume and ornamental jewelry | | |

## Polyesters—Cast

| Type → | | Allyl Type | Rigid Styrene Type | Nonrigid Styrene Type |
|---|---|---|---|---|
| PHYSICAL PROPERTIES | ASTM | | | |
| Specific Gravity | D792... | 1.30–1.45 | 1.12–1.46 | 1.06–1.25 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177... | 0.116–0.121 | 0.10–0.12 | — |
| Coef of Ther Exp, per °F | D696... | $2.8–5.6 \times 10^{-5}$ | $3.9–5.6 \times 10^{-5}$ | — |
| Refractive Index | D542... | 1.50–1.58 | 1.53–1.58 | 1.50–1.57 |
| Specific Heat, Btu/lb/°F | ..... | 0.26–0.55 | 0.30–0.55 | — |
| Water Absorption (24 hr), % | D570... | 0.03–1.0 | 0.15–0.60 | 0.40–2.5 |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | D638... | $2–3 \times 10^5$ | $1.5–6.5 \times 10^5$ | — |
| Tensile Strength, 1000 psi | D638... | 4.5–7 | 4–10 | 0.9–1.9 |
| Elongation (in 2 in.), % | D638... | — | <5 | 40–310 |
| Hardness (Rockwell) | D785... | M92–118 | M65–115 | — |
| Impact Strength (Izod notched), ft-lb/in. | D256... | 0.18–0.32 | 0.18–0.40 | >7.0 |
| Mod of Elast in Flexure, psi | ..... | $3–8 \times 10^5$ | $3–9 \times 10^5$ | $0.001–0.1 \times 10^5$ |
| Flexural Strength, 1000 psi | D790... | 6–14 | 7–19 | — |
| Compressive Strength, 1000 psi | D695... | 20–26 | 12–37 | — |
| ELECTRICAL PROPERTIES | | | | |
| Volume Resistivity, ohm-cm | D257... | $>10^{13}$ | $>10^{13}$ | $>10^{12}$ |
| Dielectric Strength (short time), v/mil | D149... | 330–500 | 340–570 | 220–400 |
| Dielectric Constant | | | | |
| 60 Cycles | D150... | 3.2–5.2 | 2.8–4.4 | 4.2–7.0 |
| $10^6$ Cycles | D150... | 3.3–4.8 | 2.8–4.0 | 3.7–6.1 |
| Dissipation Factor | | | | |
| 60 Cycles | D150... | 0.006–0.02 | 0.003–0.04 | 0.02–0.18 |
| $10^6$ Cycles | D150... | 0.024–0.045 | 0.006–0.04 | 0.02–0.06 |
| Arc Resistance, sec | D495... | 120–150 | 115–135 | 125–145 |
| HEAT RESISTANCE | | | | |
| Max Rec Svc Temp, F | D648... | 300 | 250–300 | 200–250 |
| Heat Dist Temp, F | ..... | 120–320 | 120–420 | 250 |
| CHEMICAL RESISTANCE | | Attacked by oxidizing acids. Slightly attacked by strong alkalis. Resistant to organic solvents | Slightly to heavily attacked by strong acids. Attacked by strong alkalis, ketones and chlorinated solvents | |
| USES | | Castings used for aircraft glazing, electrical components, decorative applications. Resins used for premix and prepreg molding materials, matched metal molding and hand lay-up molding | | |

## Silicones—Molded

| Type and Filler → | ASTM | General—Mineral | Improved Impact—Glass Fiber | High Impact—Glass Fiber |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Specific Gravity | D792 | 1.8–2.0 | 1.8–2.0 | 1.65–2.00 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177 | 0.089–0.097 | 0.089–0.097 | 0.089–0.097 |
| Coef of Ther Exp, per °F | D696 | 2.78–3.23 x $10^{-5}$ | 3.17–3.23 x $10^{-5}$ | 0.45 x $10^{-5}$ |
| Water Absorption (24 hr), % | D570 | 0.1–0.15 | 0.1–0.15 | 0.1–0.15 |
| Flammability, ipm | D635 | 0–78 | 0–60 | 25–100 |
| **MECHANICAL PROPERTIES** | | | | |
| Tensile Strength, 1000 psi | D651 | 4–4.3 | 4–4.3 | 4.4–5 |
| Hardness (Rockwell) | D785 | M89 | M89 | M85 |
| Impact Strength (Izod notched), ft-lb/in. | D256 | 0.25–0.30 | 0.33–0.38 | 15.0–20.0 |
| Mod of Elast in Flexure, psi | D790 | 10–13 x $10^5$ | 9–11 x $10^5$ | 15–19 x $10^5$ |
| Flexural Strength, 1000 psi | D790 | 6.8–7.5 | 10–14 | 10–14 |
| Compressive Strength, 1000 psi | D695 | 16–20 | 12–16 | 10–15 |
| **ELECTRICAL PROPERTIES** | | | | |
| Volume Resistivity, ohm-cm | D257 | >3.4 x $10^{13}$ | >3.4 x $10^{13}$ | >5 x $10^{13}$ |
| Dielectric Strength (short time), v/mil | D149 | 350–400 | 300–400 | 250–400 |
| Dielectric Constant | | | | |
| 60 Cycles | D150 | 4.1–4.5 | 4–5 | 4–5 |
| $10^6$ Cycles | D150 | 3.8–4.3 | 4–5 | 3.6–5.1 |
| Dissipation Factor | | | | |
| 60 Cycles | D150 | 0.010–0.014 | 0.008–0.011 | 0.006–0.030 |
| $10^6$ Cycles | D150 | 0.006–0.010 | 0.007–0.011 | 0.005–0.020 |
| Arc Resistance, sec | D495 | 250–420 | 100–350 | 100–350 |
| Loss Factor | | | | |
| 60 Cycles | D150 | 0.041–0.063 | 0.041–0.058 | 0.029–0.035 |
| $10^6$ Cycles | D150 | 0.023–0.043 | 0.034–0.056 | 0.025–0.077 |
| **FABRICATING PROPERTIES** | | | | |
| Bulk Factor | | 2.1–2.6 | 2.3–2.8 | 6–9 |
| Compression Molding | | | | |
| Pressure, 1000 psi | | 2–4 | 2–4 | 1–5 |
| Temperature, F | | 300–350 | 300–350 | 300–350 |
| Transfer Molding | | | | |
| Pressure, 1000 psi | | 3.5–15 | 3.5–15 | 4.5–15 |
| Temperature, F | | 300–350 | 300–350 | 300–350 |
| Mold Shrinkage, in./in. | | 0.006–0.010 | 0.005–0.008 | 0.003–0.005 |
| **HEAT RESISTANCE** | | | | |
| Max Res Svc Temp, F | | > 700 | > 600 | > 600 |
| Heat Dist Temp, F | D648 | > 900 | > 900 | > 900 |
| **CHEMICAL RESISTANCE** | | Resistant to aviation gasoline, lubricating oil, and sulfuric and hydrochloric acids. Slightly softened and pitted by sodium hydroxide, except some of the mineral-filled materials. Should be tested if resistance to ketones, toluene, ethylenes, etc., is required | | |
| **USES** | | Motor slot wedges, terminal boards, connector plugs, switches and insulators, aircraft brake assemblies, jet engine parts, aircraft ignition systems, guided missile parts, tube bases and caps | | |

## Polystyrenes and Modified Polystyrenes—Molded, Extruded

| Type → | | Polystyrene | | Modified Polystyrene | | |
|---|---|---|---|---|---|---|
| | | General Purpose | Glass Fiber-Filled | Heat & Chemical Resistant | Medium-High Impact[a] | Extra High Impact |
| PHYSICAL PROPERTIES | ASTM | | | | | |
| Specific Gravity | D792... | 1.04–1.07 | 1.25–1.32 | 1.05–1.11 | 1.04–1.08 | 1.0–1.10 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177... | 0.058–0.080 | — | 0.046–0.072 | 0.024–0.072 | 0.024–0.073 |
| Coef of Ther Exp, $10^{-5}$ per °F | D696 .. | 3.3–4.4 | 2.2–2.4 | 3.8 | 3.3–4.7 | 2.2–5.6 |
| Spec Ht, Btu/lb/°F | ..... | 0.32–0.35 | 0.24–0.27 | 0.32–0.35 | 0.30–0.35 | 0.30–0.35 |
| Refractive Index | D542... | 1.58–1.60 | — | 1.58–1.60 | — | — |
| Transmittance (luminous), % | ..... | 0–93 | — | — | — | — |
| Water Absorption (24 hr), % | D570... | 0.03–0.05 | 0.05–0.07 | 0.1–0.3 | 0.03–0.08 | 0.05–0.20 |
| Flammability, ipm | D635... | 1.0–1.5 | — | 0.4–0.7 | 0.5–2.0 | 0.5–2.0 |
| MECHANICAL PROPERTIES | | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638... | 4–5 | 11–13 | 4–6 | 3.0–4.5 | 2.5–4.0 |
| Ten Str, 1000 psi | D638... | 5–8 | 11–17 | 10–11 | 3.5–6.8 | 3.0–5.5 |
| Elong (in 2 in.), % | D638... | 1.5–2.4 | 1.1–1.3 | 1–3 | 5–35 | 15–45 |
| Hardness (Rockwell) | D785... | M68–80 | M90–100 | M78–88 | M15–80 | M15–60 |
| Impact Str (Izod), ft-lb/in. notch | D256... | 0.25–0.35 | 1.4–6.1 | 0.25–0.50 | 0.6–3.0 | 6–11 |
| Mod of Elast in Flex, $10^5$ psi | ..... | 4–5 | 11–13 | 4–6 | 3–5 | 2.3–4.0 |
| Flex Str, 1000 psi | D790... | 8–15 | 15–24 | 11–17 | No failure | No failure |
| Compr Str, 1000 psi | D695... | 11.5–16 | 14–20 | 12–17 | — | — |
| ELECTRICAL PROPERTIES | | | | | | |
| Vol Res, ohm-cm | D257... | $10^{18}$–$10^{19}$ | $3.5 \times 10^{16}$ | $10^{13}$–$10^{17}$ | $10^{14}$–$10^{16}$ | $10^{12}$–$10^{17}$ |
| Dielec Str (short time), v/mil | D149... | >500 | 320–425 | 400–600 | >450 | 300–650 |
| Dielec Const | | | | | | |
| 60 Cycles | D150... | — | 2.95–3.50 | 2.7–3.4 | 2.45–2.70[d] | 2.5–4.0 |
| $10^6$ Cycles | D150... | 2.45–2.65 | 2.74–3.41 | 2.7–3.1 | — | 2.5–4.0 |
| Dissip Factor | | | | | | |
| 60 Cycles | D150... | — | 0.005–0.014 | 0.001–0.008 | 0.0004–0.01[d] | — |
| $10^6$ Cycles | D150... | 0.0001–0.0005 | 0.00125–0.0028 | 0.001–0.008 | — | — |
| FABRICATING PROPERTIES | | | | | | |
| Bulk Factor | ..... | 1.6–2.3 | — | 1.6–2.3 | 1.6–2.3 | 1.6–2.3 |
| Compression Molding | | | | | | |
| Pressure, 1000 psi | ..... | 1–7.5 | 2–5 | 1–5 | 1–8 | 1–8 |
| Temperature, F | ..... | 275–400 | 275–350 | 325–450 | 325–475 | 300–450 |
| Injection Molding | | | | | | |
| Pressure, 1000 psi | ..... | 10–24 | 15–20 | 10–24 | 10–24 | 10–30 |
| Temperature, F | ..... | 325–650 | 450–600 | 400–700 | 300–600 | 375–55) |
| Mold Shrinkage, in./in. | ..... | 0.002–0.008 | 0.001–0.003 | 0.002–0.008 | 0.002–0.008 | 0.002–0.0 |
| HEAT RESISTANCE | | | | | | |
| Max Rec Svc Temp, F | ..... | 140–160[a] | 190–200 | 175–190 | 125–165 | 120–160 |
| Heat Dist Temp (264 psi), F | D648... | 165–190[b] | 145–220 | 200–220 | 155–180 | 185–190 |
| CHEMICAL RESISTANCE | | Good resistance to alkalis, salts, lower alcohols, glycols, water. Fair resistance to mineral and vegetable oils. Soluble in aromatic and chlorinated hydrocarbons. Softened or attacked by higher alcohols, gasoline, strong oxidizing acids, chlorine | | More resistant to attack by solvents, oils and other organic liquids than other polystyrenes | Similar to general purpose polystyrene | |
| USES | | Electrical parts, incl storage battery cases, insulators, coil forms. Fluorescent light fixtures, rigid containers, instrument panels, nameplates, refrigerator parts, housewares, toys | Magnetic tape reels, housings and covers, yarn bobbins, structural support members, instrument panels, storage battery cases | Battery cases, coil forms, drafting instruments, sight glasses on pressure lubricating systems, thermostat housings | Coat hangers; toilet seats; refrigerator door panels, drawers and crispers; knobs; toys; vacuum formed sheet | Freezer lids, action toys, children's furniture |

[a] 160–180 F for heat resistant grades.
[b] 180–205 F for heat resistant grades.
[c] Covers values obtainable in both Medium and High Impact grades.
[d] Average for wide frequency range.

# ABS Resins and Methylstyrenes—Molded, Extruded

| Type → | | ABS Resins | | | Methylstyrene[b] | |
|---|---|---|---|---|---|---|
| | | Medium–High Impact[a] | Extra–High Impact | Low Temp Impact | Polymethyl-styrene | Methylstyrene–Acrylonitrile |
| **PHYSICAL PROPERTIES** | ASTM | | | | | |
| Specific Gravity | D792... | 1.04–1.06 | 1.01–1.06 | 1.02 | 1.01–1.03 | 1.06 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177... | 0.08–0.12 | 0.08–0.12 | 0.08–0.12 | — | — |
| Coef of Ther Exp, $10^{-6}$ per °F | D696... | 4.7 | 4.7–5.6 | 4.7–5.6 | — | — |
| Spec Ht, Btu/lb/°F | ..... | 0.35–0.38 | 0.35–0.38 | 0.35–0.38 | — | — |
| Refractive Index | D542... | — | — | — | 1.581 | 1.559 |
| Transmittance (luminous), % | ..... | — | — | — | Transparent | Transparent |
| Water Absorption (24 hr), % | D570... | 0.2 | 0.3 | 0.2 | 0.05 | 0.31 |
| Flammability, ipm | D635... | 1.3 | 1.3 | 1.3 | Slow | Slow |
| **MECHANICAL PROPERTIES** | | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638... | 2.6–2.9 | 2.1–2.6 | 1.0 | — | — |
| Ten Str, 1000 psi | D638... | 4.5–8.5 | 5–8 | 3–4 | 6.6–8.9 | 9.3 |
| Elong (in 2 in.), % | D638... | 5–100 | 20–50 | 30–200 | 2.2–5.0 | 2.5 |
| Hardness (Rockwell) | D785... | R85–118 | R85–100 | R30–65 | M76–83 | M83 |
| Impact Str (Izod), ft-lb/in. notch | D256... | 0.5–6.0 | 5–9 | 6–10 | 0.33 | 0.40 |
| Mod of Elast in Flex, $10^5$ psi | ..... | 37–45 | — | — | 4.0 | 4.6 |
| Flex Str, 1000 psi | D790... | 7.5–11.0 | 6.8–8.0 | 3–4 | 10–13 | 16 |
| Compr Str, 1000 psi | D695... | — | — | — | — | — |
| **ELECTRICAL PROPERTIES** | | | | | | |
| Vol Res, ohm-cm | D257... | $>8 \times 10^{15}$ | $1.8 \times 10^{15}$ | $8.2–0.5 \times 10^{15}$ | $2.6–5000 \times 10^{16}$ | $2.65 \times 10^{11}$ |
| Dielec Str (short time), v/mil | D149... | 350–416 | 312 | 340–416 | 890–1950 | 610 |
| Dielec Const | | | | | | |
| 60 Cycles | D150... | 2.7–4.2 | 2.7–4.76 | 2.7–4.0 | — | — |
| $10^6$ Cycles | D150... | 2.8–3.6 | 3.78 | 2.8–4.1 | 2.48 | 2.81 |
| Dissip Factor | | | | | | |
| 60 Cycles | D150... | 0.009–0.015 | 0.021 | 0.01 | — | — |
| $10^6$ Cycles | D150... | 0.017–0.026 | 0.026 | 0.02 | 0.0006 | 0.0078 |
| **FABRICATING PROPERTIES** | | | | | | |
| Bulk Factor | ..... | 2.25–2.27 | 2.29 | 2.27 | — | — |
| Compression Molding | | | | | | |
| Pressure, 1000 psi | ..... | >1 | >1 | >1 | 1–8 | 1–8 |
| Temperature, F | ..... | 325–375 | 325–375 | 325–375 | 300–375 | 300–375 |
| Injection Molding | | | | | | |
| Pressure, 1000 psi | ..... | 6–30 | 6–30 | 6–30 | 10–30 | 10–30 |
| Temperature, F | ..... | 350–600 | 375–600 | 350–600 | 400–550 | 400–550 |
| Mold Shrinkage, in./in. | ..... | 0.001–0.010 | 0.001–0.010 | 0.001–0.010 | 0.0046 | 0.0035 |
| **HEAT RESISTANCE** | | | | | | |
| Max Rec Svc Temp, F | ..... | — | — | — | 210 | 212 |
| Heat Dist Temp (264 psi), F | D648... | 185–215 | 185 | 175–185 | 213–216 | 215 |
| **CHEMICAL RESISTANCE** | | Highly resistant to aqueous acids, alkalis, salts. Resistant to concentrated phosphoric and hydrochloric acids, alcohols, and animal, vegetable and mineral oils. Disintegrated by concentrated sulfuric and nitric acids. Soluble in esters, ketones, ethylene dichloride | | | Same as polystyrenes | Resists aliphatic hydrocarbons, gasoline, essential oils, vegetable and mineral oils |
| **USES** | | Pipe, appliance housings and wheels, protective sportswear, housewares, howitzer cartridges | | | Radio cabinets, housewares and household utility parts, refrigerator parts, decorative lighting, packaging, electronic components | Same as polymethylstyrene. Also metering sight glasses, fan blades, combs, automotive interior parts, machine housings |

[a] Range covers values obtainable in both Medium and High Impact grades.
[b] Recently withdrawn from commercial production.

## Polyethylenes—Molded, Extruded

| Type → | | Type I—Lower Density (0.910–0.925) | | | Type II—Medium Density (0.926–0.940) | |
|---|---|---|---|---|---|---|
| | | Melt Index 0.3-3.6 | Melt Index 6-26 | Melt Index 200 | Melt Index 12.0 | Melt Index 1.0-1.9 |
| **PHYSICAL PROPERTIES** | ASTM | | | | | |
| Specific Gravity | D792 | 0.910–0.925 | 0.918–0.925 | 0.910 | 0.930 | 0.930–0.940 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177 | 0.19 | 0.19 | 0.19 | 0.19 | 0.19 |
| Coef of Ther Exp, $10^{-5}$ per °F | D696 | 8.9–11.0 | 8.9–11.0 | 11.0 | 8.3–16.7 | 8.3–16.7 |
| Refractive Index | D542 | 1.51 | 1.51 | 1.51 | 1.51 | 1.51 |
| Spec Ht, Btu/lb/°F | | 0.53–0.55 | 0.53–0.55 | 0.53–0.55 | 0.53–0.55 | 0.53–0.55 |
| Water Absorption (24 hr), % | D570 | <0.01 | <0.01 | <0.01 | <0.01 | <0.01 |
| Flammability, ipm | D635 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 |
| **MECHANICAL PROPERTIES** | | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638 | 0.21–0.27 | 0.20–0.24 | — | — | — |
| Ten Str, 1000 psi | D412 | 1.4–2.5 | 1.4–2.0 | 0.9–1.1 | 2.0 | 2.3–2.4 |
| Elong (in 2 in.), % | D412 | 500–725 | 125–675 | 80–100 | 200 | 200–425 |
| Hardness (Shore) | D785 | C73, D50–52 | C73, D47–53 | D45 | D55 | D55–D56 |
| Impact Str (Izod), ft-lb/in. notch | D256 | — | — | — | — | — |
| Brittleness Temp, F | | <−94 | <−4 | <14 | <−148 | <−148 |
| Mod of Elast in Flex, $10^5$ psi | D747 | 13–27 | 12–30 | 10 | 43 | 35–50 |
| Shear Str, 1000 psi | | 1.6–1.85 | 1.4–1.7 | 1 | — | — |
| **ELECTRICAL PROPERTIES** | | | | | | |
| Vol Res, ohm-cm | D257 | $10^{17}$–$10^{19}$ | $10^{17}$–$10^{19}$ | $10^{17}$–$10^{19}$ | $>10^{16}$ | $>10^{16}$ |
| Dielec Str (short time), v/mil | D149 | 480 | 480 | 480 | 480 | 480 |
| Dielec Const | D150 | 2.3 | 2.3 | 2.3 | 2.3 | 2.3 |
| Dissip Factor | D150 | <0.0005 | <0.0005 | <0.0005 | <0.0005 | <0.0005 |
| **FABRICATING PROPERTIES** | | | | | | |
| Bulk Factor | | 1.6–2.2 | 1.6–2.2 | 1.6–2.2 | 1.6–2.2 | 1.6–2.2 |
| Injection Molding | | | | | | |
| Pressure, 1000 psi | | 5–22 | 5–15 | 2–10 | 10–15 | 10–15 |
| Temperature, F | | 275–650 | 275–650 | 250–350 | 300–500 | 300–500 |
| Mold Shrinkage, in./in. | | 0.02–0.05 | 0.01–0.04 | 0.01–0.02 | 0.02–0.05 | 0.02–0.05 |
| **HEAT RESISTANCE** | | | | | | |
| Vicat Softening Point, F | | 176–201 | 176–201 | — | 215 | 220–235 |
| **CHEMICAL RESISTANCE** | | Excellent resistance to acids and alkalis at normal temperature, except oxidizing acids such as nitric, chlorosulfonic and fuming sulfuric. Below 122 F, insoluble in organic solvents; at higher temperatures, soluble to varying degrees in hydrocarbons and halogenated hydrocarbons, but insoluble in more polar liquids. Generally, a higher melt index material has greater solubility | | | | |
| **USES** | | Injection moldings: kitchen utilityware, toys, process tank liners, closures, packages, sealing rings, battery parts. Blow moldings: squeeze bottles for packaging, containers for drugs. Film: wrapping materials for food, clothes, other items. Wire and cable: high frequency insulation, jacketing. Pipe: chemicals handling, irrigation systems, natural gas transmission | | | | |

## Polyethylenes—Molded, Extruded

| Type → | ASTM | Type III—Higher Density (0.942–0.960) | | | |
|---|---|---|---|---|---|
| | | Melt Index 0.2-0.6 | Melt Index 0.1-12.0 | Melt Index 1.5-5.0 | Melt Index 0.2-0.9 |
| **PHYSICAL PROPERTIES** | | | | | |
| Specific Gravity | D792 | 0.942–0.947 | 0.950–0.955 | 0.96 | 0.96 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177 | 0.19 | 0.19 | 0.19 | 0.19 |
| Coef of Ther Exp, $10^{-5}$ per °F | D696 | 8.3–16.7 | 8.3–16.7 | 8.3–16.7 | 8.3–16.7 |
| Refractive Index | D542 | 1.54 | 1.54 | 1.54 | 1.54 |
| Spec Ht, Btu/lb/°F | | 0.46–0.55 | 0.46–0.55 | 0.46–0.55 | 0.46–0.55 |
| Water Absorption (24 hr), % | D570 | <0.01 | <0.01 | <0.01 | <0.01 |
| Flammability, ipm | D635 | 1.0 | 1.0 | 1.0 | 1.0 |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D638 | — | — | — | — |
| Ten Str, 1000 psi | D412 | — | 2.9–4.0 | 4.4 | 4.4 |
| Elongation, % | D412 | — | 25–400 | 12–20 | 25–30 |
| Hardness (Shore) | D785 | D65–66 | D60–70 | D68–70 | D68–70 |
| Impact Str (Izod), ft-lb/in. notch | D256 | 1.5–6 | 0.4–6.0 | 1.2–2.5 | 4.0–14 |
| Brittleness Temp, F | | <−76 | <−76 to <−170 | −100 to −180 | −106 to −180 |
| Mod of Elast in Flex, $10^5$ psi | D747 | 85–120 | 90–125 | 150 | 130–150 |
| Shear Str, 1000 psi | | — | — | — | — |
| **ELECTRICAL PROPERTIES** | | | | | |
| Vol Res, ohm-cm | D257 | $>10^{16}$ | $>10^{16}$ | $>10^{16}$ | $>10^{16}$ |
| Dielec Str (short time), v/mil | D149 | 480 | 480 | 480 | 480 |
| Dielec Const | D150 | 2.3 | 2.3 | 2.3 | 2.3 |
| Dissip Factor | D150 | <0.0005 | <0.0005 | <0.0005 | <0.0005 |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | | 1.6–2.2 | 1.6–2.2 | 1.6–2.2 | 1.6–2.2 |
| Injection Molding | | | | | |
| Pressure, 1000 psi | | 10–15 | 10–15 | 10–15 | 10–15 |
| Temperature, F | | 330–530 | 330–530 | 330–530 | 330–530 |
| Mold Shrinkage, in./in. | | 0.02–0.05 | 0.02–0.05 | 0.02–0.05 | 0.02–0.05 |
| **HEAT RESISTANCE** | | | | | |
| Vicat Softening Point, F | | 250 | 250–260 | 260* | 260* |
| **CHEMICAL RESISTANCE** | | Same basic chemical resistance as Types I and II, but better resistance to some specific chemicals | | | |
| **USES** | | Refrigerator parts, packaging, structural housing panels, pipe, defroster and heater ducts, sterilizable housewares and hospital equipment, hoops, battery parts, blow molded containers and parts, film wrapping materials, wire and cable insulation, and chemical resistant pipe | | | |

* Adapted from method of Karrer, Davis and Dieterich, *Ind. & Engrg. Chem.*, Vol. 2, No. 30, '30.

## Polyvinyl Chloride and Copolymers—Molded, Extruded

| Type → | | Polyvinyl Chloride, Polyvinyl Chloride-Acetate | | | Vinylidene Chloride[a] |
|---|---|---|---|---|---|
| | | Nonrigid—General | Nonrigid—Electrical | Rigid—Normal Impact | |
| **PHYSICAL PROPERTIES** | ASTM | | | | |
| Specific Gravity | D792 | 1.20–1.55 | 1.16–1.40 | 1.32–1.44 | 1.68–1.75 |
| Ther Cond, Btu/hr/sq ft/°F/ft | D325 | 0.07–0.10 | 0.07–0.10 | 0.07–0.10 | 0.053 |
| Coef of Ther Exp, $10^{-5}$ per °F | D696 | — | — | 2.8–3.3 | 8.78 |
| Refractive Index | D542 | — | — | — | 1.60–1.63 |
| Spec Ht, Btu/lb/°F | D570 | — | — | — | 0.32 |
| Water Absorption (24 hr), % | D635 | 0.2–1.0 | 0.40–0.75 | 0.03–0.40 | >0.1 |
| Flammability | | Self-extinguishing | Self-extinguishing | Self-extinguishing | Self-extinguishing |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, $10^5$ psi | D412 | 0.004–0.03 | 0.01–0.03 | 3.5–4.0[b] | 0.7–2.0 |
| Ten Str, 1000 psi | D412 | 1–3.5 | 2–3.2 | 5.5–9 | 4–8, 15–40 |
| Elong (in 2 in.), % | D638 | 200–450 | 220–360 | 5–25 | 15–25, 20–30 |
| Hardness (Rockwell) | D785 | — | — | R117–120 | M50–65 |
| Hardness (Shore) | D676 | A50–100 | A78–100 | D70–85 | >A95 |
| Impact Str (Izod notched), ft-lb/in. | D256 | Variable | Variable | 0.25–1.2 | 2–8, 0.053 |
| Mod of Elast in Flex, psi | D790 | — | — | $3.8–5.4 \times 10^5$ | — |
| 100% Modulus, psi | | 1300–1750 | 1200–2800 | — | — |
| Flex Str, 1000 psi | D790 | — | — | 12.5–16 | 15–17, flexible |
| Compr Str, 1000 psi | D695 | — | — | 11–12 | — |
| Compr Yld Str, 1000 psi | D695 | — | — | 10–11 | 75–85 |
| Cold Flex Temp, F | D1043 | −70 to 0 | −7 to +55 | — | — |
| Cold Bend Temp, F | | −40 to −4 | −49 to −4 | — | — |
| **ELECTRICAL PROPERTIES** | | | | | |
| Vol Res, ohm-cm | D257 | $1–700 \times 10^{12}$ | $4–300 \times 10^{11}$ | $10^{14}–>10^{16}$ | $10^{14}–10^{16}$ |
| Dielec Str (short time), v/mil | D149 | — | 24–500 | 725–1400 | — |
| Dielec Const (60 cycles) | D150 | 5.5–9.1 | 6.0–8.0 | 2.3–3.7 | 3–5 |
| Dissip Factor (60 cycles) | D150 | 0.05–0.15 | 0.08–0.11 | 0.020–0.03 | 0.03–0.15 |
| Loss Factor (60 cycles) | D150 | — | 1.0–1.2 | 0.030–0.072 | — |
| **FABRICATING PROPERTIES** | | | | | |
| Bulk Factor | | 2.4–2.6 | 2.4–2.6 | 2.0–2.4 | — |
| Compression Molding | | | | | |
| Pressure, 1000 psi | | 0.5–2 | 0.5–2 | >1 | 0.5–5 |
| Temperature, F | | 285–350 | 285–350 | 275–400 | 250–350 |
| Injection Molding | | | | | |
| Pressure, 1000 psi | | 7–15 | 12–20 | >20 | 10–30 |
| Temperature, F | | 320–350 | 325–375 | 300–375 | 300–400 |
| Mold Shrinkage, in./in. | | 0.02–0.05 | 0.02–0.06 | 0.001–0.004 | 0.008–0.012 |
| Extrusion Temp, F | | 325–400 | 350–385 | — | <375 |
| **HEAT RESISTANCE** | | | | | |
| Max Rec Svc Temp, F | | 150–220 | 140–220 | 150–165 | 170–212 |
| Heat Dist Temp, F | | | | | |
| 66 Psi | D648 | — | — | 170–185 | 190–210 |
| 264 Psi | D648 | — | — | 140–170 | 130–150 |
| Softening Point, F | | — | — | — | 240–280 |
| **CHEMICAL RESISTANCE** | | Generally resistant to alkalis and weak acids. Moderately to not resistant to strong acids. Not resistant to ketones and esters; aromatic hydrocarbons produce swelling | | | Excellent to all acids and most common alkalis[c] |
| **USES** | | Parts made by molding, high speed extrusion, calendering. Blown extruded film. Vacuum cleaner parts, handlebar grips, doll parts, hair curlers, safety goggle cups, grommets, toy tires, garden hose, and protective garments | Parts made by calendering, extrusion. Insulation and jacketing for: communication and low tension power wire and cable, building wiring, appliance and machine tool cords, and switchboard cable | Parts made by calendering, laminating, molding, extrusion. Fume hoods and ducts, storage tanks, chemical piping, plating tanks, phonograph records. Sheets and shapes for decorative panels, other building uses | Extrusions: gasket rods, valve seats, flexible chemical tubing and pipe, tape for wrapping joints, chemical conveyor belts. Moldings: spray-gun handles, acid dippers, parts for rayon producing equipment |

[a] Where two values or ranges are given, they represent unoriented and oriented forms, respectively.
[b] Modulus of elasticity in compression.
[c] Unaffected by aliphatic and aromatic hydrocarbons, alcohols, esters, etc.

## Polyvinyl Alcohol, Butyral and Formal—Molded, Extruded

| Material → | | Polyvinyl Alcohol | Polyvinyl Butyral | Polyvinyl Formal |
|---|---|---|---|---|
| PHYSICAL PROPERTIES | ASTM | | | |
| Specific Gravity | D792 | 1.21–1.31 | 1.07–1.20 | 1.2–1.4 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177 | 0.46 | — | 0.089 |
| Coef of Ther Exp, per °F | D696 | 3.88–6.65 x $10^{-5}$ | 4.4–12.7 x $10^{-5}$ | 3.55–4.27 x $10^{-5}$ |
| Refractive Index | D542 | 1.49–1.53 | 1.48–1.49 | 1.5 |
| Specific Heat, Btu/lb/°F | | 0.3 | 0.4 | — |
| Transmittance (luminous), % | | [a] | 85–91 | 80–90 |
| Water Absorption (24 hr), % | D570 | >30 | 1.0–3.0 | 0.5–3.0 |
| Flammability | D635 | Slow burning | Slow burning | Slow burning |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension, psi | D638 | — | 3.5–4.0 x $10^5$ | 5–7 x $10^5$ |
| Tensile Strength, 1000 psi | D638 | 1–5 | 4–8.5 | 9–11 |
| Elongation (in 2 in.), % | D638 | 300–600 | 5–60 | 5–20 |
| Hardness (Rockwell) | D785 | — | L95 | M85 |
| Hardness (Shore A) | | 10–100 | — | — |
| Impact Strength (Izod notched), ft-lb/in. | D256 | — | 0.74–1.02 | 0.8–20 |
| Mod of Elast in Flex, psi | | — | — | 5–6 x $10^5$ |
| Flexural Strength, 1000 psi | D790 | — | 10 | 17–18 |
| ELECTRICAL PROPERTIES | | | | |
| Volume Resistivity, ohm-cm | D257 | [b] | >$10^{14}$ | — |
| Dielectric Strength (short time), v/mil | D149 | [b] | 400 | 300–600 |
| Dielectric Constant | | | | |
| 60 Cycles | D150 | [b] | 3.61 | 3.7 |
| $10^6$ Cycles | D150 | [b] | 3.33 | 3.0 |
| Dissipation Factor | | | | |
| 60 Cycles | D150 | [b] | 0.0070 | 0.010 |
| $10^6$ Cycles | D150 | [b] | 0.0065 | 0.023 |
| FABRICATING PROPERTIES | | | | |
| Compression Molding | | | | |
| Pressure, 1000 psi | | 5–15 | 1–2 | 1–10 |
| Temperature, F | | 250–300 | 320–400 | 275–325 |
| Injection Molding | | | | |
| Pressure | | — | 11–15 | 14–32 |
| Temperature, F | | — | 400 | 325–425 |
| Mold Shrinkage, in./in. | | — | — | 0.0015–0.0035 |
| HEAT RESISTANCE | | | | |
| Max Rec Svc Temp, F | | — | 115 | 130–165 |
| Heat Dist Temp, F | D648 | — | 115–140 | 155–185 |
| CHEMICAL RESISTANCE | | Good resistance to organic solvents and petroleum. Attacked by strong acids. Softened or dissolved by weak acids and by alkalis | Resistant to alkalis, aliphatic hydrocarbons, and most oils. Attacked by acids, alcohols, esters and ketones. Butyral used with wider range of solvents than Formal | |
| USES | | Adhesives and binders, textile sizing, coating and sizing for paper, thickening agents. Molded: chemical and oxygen tubing, gaskets and diaphragms. Film: airtight bags, packaging for chemicals | Plasticized form used as interlayer for safety glass. Solution uses: adhesive primer, metal conditioner, cloth waterproofing | Base for electrical insulating enamel with high heat resistance. Metal wire and cable coatings requiring high toughness and adhesion |

[a] Transparent to opaque.
[b] Under atmospheric conditions enough water will be absorbed to make most electrical measurements useless.

## Acetal, Polycarbonate, Polypropylene, Chlorinated Polyether—Molded, Extruded

| Material → | | Acetal | Polycarbonate[a] | Polypropylene | Chlorinated Polyether |
|---|---|---|---|---|---|
| PHYSICAL PROPERTIES | ASTM | | | | |
| Specific Gravity | D792 | 1.425 | 1.20 | 0.90–0.91 | 1.4 |
| Ther Cond, Btu/hr/sq ft/°F/ft | | 0.13 | 0.11 | 0.08 | — |
| Coef of Ther Exp, per °F | D696 | $4.5 \times 10^{-5}$ | $3.9 \times 10^{-5}$ | $6.2 \times 10^{-5}$ | $4.4 \times 10^{-5}$ |
| Specific Heat, Btu/lb/°F | | 0.35 | — | 0.46 | — |
| Water Absorption (24 hr), % | D570 | 0.12 | 0.3 | 0.03 | 0.01 |
| Flammability, ipm | D635 | 1.1 | Self-extinguishing | — | Self-extinguishing |
| MECHANICAL PROPERTIES | | | | | |
| Mod of Elast in Tension, psi | D638 | — | $0.33 \times 10^{5}$[b] | $1.55 \times 10^{5}$ | — |
| Tensile Strength, 1000 psi | D638 | 10.0 | 9.0–10.5 | 5.0 | 6 |
| Elongation (total), % | D638 | 15 | 60–100 | 500–700 | 60–160 |
| Hardness (Rockwell) | D785 | M94, R120 | M70, R118 | R85–95 | R100 |
| Impact Strength, ft-lb/in. | | | | | |
| Notched | D256 | 1.4 | 12–16 | 1.02 | 0.4 |
| Unnotched | D256 | — | >60 | >17 | >33 |
| Mod of Elast in Flex, psi | D790 | $4.1 \times 10^{5}$ | $3.8 \times 10^{5}$ | $1.7 \times 10^{5}$[c] | $1.3 \times 10^{5}$ |
| Flexural Strength, 1000 psi | D790 | 14.1 | 11–13 | 8.1[c] | 5 |
| Stiffness in Flex, 1000 psi | D790 | — | — | 114–142 | — |
| Compressive Strength, 1000 psi | D695 | 5.2 | 11 | — | — |
| Shear Strength, 1000 psi | D732 | 9.5 | 9.2 | — | — |
| Yield Strength, 1000 psi | D638 | — | 8.0–9.0 | 4.3–4.9 | — |
| Elongation (at yield), % | D638 | — | 5 | 10–20 | — |
| ELECTRICAL PROPERTIES | | | | | |
| Volume Resistivity, ohm-cm | D257 | $>4 \times 10^{13}$ | $2.1 \times 10^{16}$ | $>10^{16}$ | $5 \times 10^{15}$ |
| Dielectric Strength (short time), v/mil | D149 | 500 | 400 | 769–820 | 400 |
| Dielectric Constant | | | | | |
| 60 Cycles | D150 | 3.7 | 3.17 | — | 3.1 |
| $10^{6}$ Cycles | D150 | 3.7 | 2.96 | 2.0–2.1 | 2.8 |
| Dissipation Factor | | | | | |
| 60 Cycles | D150 | 0.004 | 0.0090 | — | 0.016 |
| $10^{6}$ Cycles | D150 | 0.004 | 0.0100 | 0.0002–0.0003 | 0.01 |
| Arc Resistance, sec | D495 | 129 | 10–11 | — | — |
| FABRICATING PROPERTIES | | | | | |
| Bulk Factor | D1182 | — | 1.74 | 2.25 | — |
| Injection Molding | | | | | |
| Pressure, 1000 psi | | 15–25 | 15–20 | Wide range | 10–20 |
| Temperature, F | | 380–440 | 550–600 | Wide range | 440–465 |
| Extrusion Temp, F | | — | — | 340–430 | 360–450 |
| Mold Shrinkage, in./in. | | 0.01–0.04 | 0.005–0.007 | 0.015–0.030 | 0.004–0.006 |
| HEAT RESISTANCE | | | | | |
| Max Rec Svc Temp, F | | 185 | — | — | — |
| Heat Dist Temp, F | | | | | |
| 66 Psi | D648 | 338 | 283–293 | 221 | 300 |
| 264 Psi | D648 | 212 | 280–290 | — | 185 |
| Melt Pt (crystalline), F | | 347 | 514 | 330 | — |
| CHEMICAL RESISTANCE | | Excellent res to most organic solvents, including aliphatic and aromatic hydrocarbons. Not rec for use with strong acids and alkalis; should be tested for use with dilute acids and weak alkalis. Affected by ultra violet light | Insoluble in aliphatic hydrocarbons, ether and alcohols; partially soluble in aromatic hydrocarbons; soluble in chlorinated hydrocarbons; slowly decomp by alkaline substances. High stability to water and to mineral and organic acids | Res to most acids, alkalis and saline solutions, even at higher temp; res to organic solvents and polar substances. Above 175 F, soluble in such aromatic substances as toluene and xylene, and such chlorinated hydrocarbons as trichloroethylene | Excellent resistance to both inorganic and organic chemicals. Resistant to all inorganic acids except fuming nitric and fuming sulfuric |
| USES | | Appliance parts. Gears, bushings, bearings, and movie projector and typewriter parts | Gears, housings, structural parts, electronic components, telephone accessories | Structural shapes, housewares, electronic equipment, automotive parts | Valves, pump parts, pipe and sheet for high temperature corrosive environments |

[a] A glass-reinforced type is now available. [b] 212 F. [c] Tinius-Olsen.

## Ureas—Molded

| Type[a] → | | 1 (alpha cellulose-filled) | 2 (cellulose-filled) |
|---|---|---|---|
| **PHYSICAL PROPERTIES** | ASTM | | |
| Specific Gravity | D792... | 1.47–1.52 | 1.52 |
| Ther Cond, Btu/hr/sq ft/°F/ft | C177... | 0.17–0.244 | — |
| Coef of Ther Exp, per °F | D696... | 1.22–1.50 x $10^{-5}$ | — |
| Transmittance (luminous), % | ..... | 21.8 | 0 |
| Water Absorption (24 hr), % | D570... | 0.4–0.8 | — |
| Flammability | D635... | Self-extinguishing | Self-extinguishing |
| **MECHANICAL PROPERTIES** | | | |
| Mod of Elast in Tension, psi | D638... | 13–16 x $10^5$ | — |
| Tensile Strength, 1000 psi | D638... | 5–10 | — |
| Elongation (in 2 in.), % | D638... | 1.0 | — |
| Hardness (Rockwell) | D785... | E94–97, M116–120 | — |
| Impact Strength (Izod notched), ft-lb/in. | D256... | 0.24–0.35 | 0.26–0.275 |
| Flexural Strength, 1000 psi | D790... | 10–18 | 10–13 |
| Compressive Strength, 1000 psi | D695... | 25–38 | — |
| Shear Strength, 1000 psi | ..... | 11–12 | — |
| **ELECTRICAL PROPERTIES** | | | |
| Volume Resistivity, ohm-cm | D257... | 0.5–5 x $10^{11}$ | 5–8 x $10^9$ |
| Dielectric Strength (short time), v/mil | D149... | 300–400 | 340–370 |
| Dielectric Constant | | | |
| 60 Cycles | D150... | 7.0–9.5 | 7.2–7.3 |
| $10^6$ Cycles | D150... | 6.4–6.9 | 6.4–6.5 |
| Dissipation Factor | | | |
| 60 Cycles | D150... | 0.035–0.043 | 0.042–0.044 |
| $10^6$ Cycles | D150... | 0.028–0.032 | 0.027–0.029 |
| Loss Factor | | | |
| 60 Cycles | ..... | 0.24–0.38 | 0.30–0.32 |
| $10^6$ Cycles | ..... | 0.18–0.22 | 0.17–0.19 |
| Arc Resistance, sec | D495... | 80–130 | 85–110 |
| **FABRICATING PROPERTIES** | | | |
| Bulk Factor | ..... | 2.4–3.0 | 2.5 |
| Compression Molding | | | |
| Pressure, 1000 psi | ..... | 2–8 | 2–5 |
| Temperature, F | ..... | 275–350 | 275–320 |
| Mold Shrinkage, in./in. | ..... | 0.006–0.014 | 0.007–0.008 |
| **HEAT RESISTANCE** | | | |
| Heat Dist Temp, F | D648... | 266–280 | — |
| **CHEMICAL RESISTANCE** | | High resistance to organic solvents, oils and greases. Poor resistance to acids and alkalis, depending on concentration | |
| **USES** | | Such housings as radio, television, business machines, food equipment. Toilet seats, household electrical switches and plugs, buttons and cosmetic containers | Low cost items. Available only in dark color. Especially suited for electric switch plates, wiring devices and electrical parts requiring high arc resistance |

[a]ASTM D705-55.

## Plastics Films

| Type → | | Nylon 6 | Polypropylene | Polyethylene | | |
|---|---|---|---|---|---|---|
| | | | | Type I | Type II | Type III |
| GENERAL PROPERTIES | ASTM | | | | | |
| Method of Production[a] | | Extr | Extr, calndr | Extr, calndr | Extr, calndr | Extr |
| Forms Available | | Sheets, rolls, tapes | Sheets, rolls, tapes | Sheets, rolls, tapes, tubes | Sheets, rolls, tapes | Sheets, rolls tapes |
| Clarity[c] | | Trp | Trp | Trp, trl, opaque | Trp, trl, opaque | Trp, trl |
| Min Thickness, in. | | 0.0005 | 0.00075 | 0.00075 | 0.00075 | 0.00075 |
| Max Width, in. | | 60 | 60 | 144 | 60 | 60 |
| Area Factor, 1000 sq in./lb/mil[d] | | 24 | 30.7 | 30 | 30 | 29 |
| PHYSICAL PROPERTIES | | | | | | |
| Specific Gravity | D792 | 1.12 | 0.90 | 0.92 | 0.935–0.938 | 0.940–0.945 |
| Ten Str, 1000 psi | D882 | 13.8–17.0 | 5–10 | 1.6–3.0 | 2.5–3.5 | 3.5–8.0 |
| Elong, % | D882 | >200 | >200 | 200–800 | >200 | 50–400 |
| Burst Str (Mullen), psi[e] | D774 | — | — | 48 | — | — |
| Tear Str (Elmendorf), gm/mil | D689 | 50 | 32–1760 | 100–300 | 93–97 | 10–350 |
| Fold Endurance[e] | D643 | Excellent | Excellent | Good | Good | Good |
| Heat Sealing Range, F[f] | | 400–450 | 325–350 | 250–375 | 250–375 | 250–375 |
| Water Absorp (24 hr), % | D570 | 1.0–1.5 | 0.005 Max | Negligible | Negligible | Negligible |
| Water Vapor Perm, gm/100 sq in./24 hr[e] | E96-53T | 0.9–1.0 (1 mil) | 0.06–0.10 (1 mil) | 1.2–1.4 (1 mil)[e] | 0.5–0.7 (1 mil)[e] | 0.3–0.4 (1 mil)[e] |
| Gas Perm, cu cm/100 sq in./24 hr[e] | | | | | | |
| Oxygen | | 6.5 (1 mil) | 140 (1 mil) | 550 (1 mil) | 280 (1 mil) | 200 (1 mil) |
| Nitrogen | | — | — | 180 (1 mil) | — | 42 (1 mil) |
| Carbon Dioxide | | — | — | 2900 (1 mil) | 990 (1 mil) | 580 (1 mil) |
| CHEMICAL RESISTANCE | | | | | | |
| Strong Acids | D543 or D1239 | Poor | Excellent | Excellent[j] | Excellent[j] | Excellent[j] |
| Strong Alkalis | | Excellent | Excellent | Excellent | Excellent | Excellent |
| Greases and Oils | | Excellent | Very good | Fair | Fair | Fair |
| Solvents | | | | | | |
| Ketone and Ester | | Excellent | — | Good | Good | Good |
| Chlorinated | | — | — | Fair | Fair | Fair |
| Hydrocarbon | | Excellent | Very good | Fair | Fair | Fair |
| PERMANENCE | | | | | | |
| Max Cont Svc Temp, F | | 380 | 300 | 200 | 230 | 250 |
| Min Svc Temp, F | | <−100 | — | −68 | <−100 | <−100 |
| Resistance to Sunlight | | Fair | Fair | Fair | Fair | Fair |
| Dimensional Change, % | | Nil | Nil | Nil | Nil | Nil |
| Storage Stability[k] | | Excellent | Excellent | Excellent | Excellent | Excellent |
| Flammability (rate of burning) | | Self-extinguishing | Slow | Slow | Slow | Slow |

[a] Cast = casting; calndr = calendering; extr = extrusion; block = block process.
[b] ASTM D568.
[c] Trp = transparent; trl = translucent.
[d] Figures may vary with resin-plasticizer ratio.
[e] Properties particularly dependent on thickness.
[f] Unsupported film cannot be sealed on all types of heat sealers, since adhesion to metal sealer and distortion of film may be encountered.
[g] ASTM D643, Method A.
[j] Except nitric, fuming sulfuric and chlorosulfonic.
[k] Average warehouse conditions: 400–100 F, dry.
[l] Coating attacked.
[m] ASTM D643, Method B.
[n] At 95 F, 90% RH.

## Plastics Films

| | Type → | Rigid Polyvinyl Chloride (incl copolymers) | Nonrigid Polyvinyl Chloride (incl copolymers) | Polyvinylidene Chloride (Saran) | PVC-Nitrile Rubber Blend | Polyvinyl Alcohol |
|---|---|---|---|---|---|---|
| GENERAL PROPERTIES | ASTM | | | | | |
| Method of Production[a] | | Cast, calndr, extr | Cast, calndr, extr | Extr | Cast, calndr, extr | Cast |
| Forms Available | | Sheet, rolls, tapes | Sheet, rolls, tapes, tubes | Rolls, tubes | Sheet, rolls, tapes, tubes | Rolls |
| Clarity[c] | | Trp, trl, opaque | Trp, trl, opaque | Trp, trl, opaque | Trp, trl, opaque | Trp, trl |
| Min Thickness, in. | | 0.001 | 0.0005 | 0.0005 | 0.001 | 0.001 |
| Max Width, in. | | 54 | 104 | 40 | 84 | 54 |
| Area Factor, 1000 sq in./lb/mil[d] | | 19.5-22.5 | 20-23 | 16.3 | 22.8-23.7 | 21.6 |
| PHYSICAL PROPERTIES | | | | | | |
| Specific Gravity | D792 | 1.36-1.50 | 1.15-1.50 | 1.68 | 1.18-1.35 | 1.21-1.31 |
| Ten Str, 1000 psi | D882 | 6.5-8.5 | 1-5 | 7-15 | 1.5-4.0 | 6-10 |
| Elong, % | D882 | 5-25 | 50-500 | 25-40 | 250-500 | 400-600 |
| Burst Str (Mullen), psi[e] | D774 | — | 9-20 | 30-70 | — | 185-235 |
| Tear Str (Elmendorf), gm/mil | D689 | 20-150 | 30-1400 | 30 | 100-960 | 500-800 |
| Fold Endurance[e] | D643 | Poor | Good | 500,000[g] | Excellent | Good |
| Heat Seal Temp Range, F[f] | | 260-400 | 200-400 | 285 | 220-350 | 300-400 |
| Water Absorp (24 hr), % | D570 | Negligible | Negligible | Negligible | Negligible | > 30 |
| Water Vapor Perm, gm/100 sq in./24 hr[e] | E96-53T | 0.5 (0.005 in.) to 2.5 (0.001 in.) | 0.7 (0.005 in.) to 8.0 (0.001 in.) | 0.20 | 7.0 | > 10 |
| Gas Perm, cu cm/100 sq in./24 hr[c] | | | | | | |
| Oxygen | | 3 (0.005 in.) to 15 (0.001 in.) | 50-300[m] | 0.56[m] | — | — |
| Nitrogen | | — | — | 0.11[m] | — | — |
| Carbon Dioxide | | 11 (0.005 in.) to 55 (0.001 in.) | 250-2000[m] | 2.4[m] | — | — |
| CHEMICAL RESISTANCE | | | | | | |
| Strong Acids | D543 or D1239 | Excellent | Excellent | Excellent[h] | Good | Poor |
| Strong Alkalis | | Excellent | Excellent | Good[i] | Good | Poor |
| Greases and Oils | | Good | Fair | Excellent | Excellent | Excellent |
| Solvents | | | | | | |
| Ketone and Ester | | Poor | Poor | Fair | Poor | Excellent[e] |
| Chlorinated | | Fair | Fair | Fair | Fair | Excellent |
| Hydrocarbon | | Excellent | Good | Excellent | Good | Excellent |
| PERMANENCE | | | | | | |
| Max Cont Svc Temp, F | | 200-220 | 150-180 | 290 | 200 | — |
| Min Svc Temp, F | | -70 | -50 | Good | -40 | — |
| Resistance to Sunlight | | Good | Good | Excellent | Fair | Excellent |
| Dimensional Change, % | | Nil | Nil | Nil | Nil | High |
| Storage Stability[k] | | Excellent | Excellent | Excellent | Excellent | Excellent |
| Flammability (rate of burning) | | Self-extinguishing | Slow to self-extinguishing | Self-extinguishing | Slow to self-extinguishing | Slow |

[a] Cast = casting; calndr = calendering; extr = extrusion; block = block process.
[c] Trp = transparent; trl = translucent.
[d] Figures may vary with resin-plasticizer ratio.
[e] Properties particularly dependent on thickness.
[f] Unsupported film cannot be sealed on all types of heat sealers, since adhesion to metal sealer and distortion of film may be encountered.
[g] ASTM D643, Method A.
[h] Except sulfuric and nitric.
[i] Except ammonium hydroxide.
[k] Average warehouse condition: 40-100 F, dry
[m] 0.001-in. film.

*continued on next page*

## Plastics Films

| Type → | | Polytetra-fluoro-ethylene | Polytri-fluoromono-chloro-ethylene | Polystyrene (oriented) | Polyester (polyethylene terephthalate) | Rubber Hydrochloride | Ethyl Cellulose |
|---|---|---|---|---|---|---|---|
| **GENERAL PROPERTIES** | ASTM | | | | | | |
| Method of Production[a] | | Block | Extr | Extr | Extr | Cast | Cast, block, extr |
| Forms Available | | Sheet, tapes | Sheet, tubes | Sheet, rolls | Sheet, rolls | Sheet, rolls, tapes | Sheet, rolls, tapes |
| Clarity[c] | | Trp | Trp, trl | Trp, trl, opaque | Trp, opaque | Trp, trl, opaque | Trp |
| Min Thickness, in. | | 0.002 | 0.002 | 0.001 | 0.00025 | 0.0004 | 0.003 |
| Max Width, in. | | 12 | 20 | 40 | 55 | 60 | 30 |
| Area Factor, 1000 sq in./lb/mil[d] | | 13 | 12 | 26.1 | 20 | 24 | 24 |
| **PHYSICAL PROPERTIES** | | | | | | | |
| Specific Gravity | D792 | 2.15 | 2.11 | 1.05-1.07 | 1.39 | 1.12-1.15 | 1.14-1.16 |
| Ten Str, 1000 psi | D882 | 2-3 | 6.3-6.6 | 7-12 | 17-28 | 5-6 | 6-10 |
| Elong, % | D882 | 200-250 | 90-200 | 3-10 | 70-130[m] | 350-500 | 20-35 |
| Burst Str (Mullen), psi[e] | D774 | — | 42 | 30-60 | 45[m] | — | 30-86 |
| Tear Str (Elmendorf), gm/mil | D689 | — | 200-350 | 2-8 | 18 | 1000-1500 | 2-15 |
| Fold Endurance[e] | D643 | — | — | — | Excellent | $10^4$-$10^6$ | 2700 |
| Heat Seal Range, F[f] | | Not heat sealable | 415-450 | 220-300 | 490 | 225-350 | — |
| Water Absorp (24 hr), % | D570 | None | None | 0.04-0.06 | Negligible | Negligible | Low |
| Water Vapor Perm, gm/100 sq in./24 hr[e] | E96-53T | — | 0.00 | 6.2 | 1.8[m] | 0.5-15.5 | 10-50 |
| Gas Perm, cu cm/100 sq in./24 hr[e] | | | | | | | |
| Oxygen | | — | 0.76[m] | 213 | 5.7[m] | 2-405 | — |
| Nitrogen | | — | 5.5[m] | 42 | 0.9[m] | — | — |
| Carbon Dioxide | | — | 8.0[m] | 926 | 17.5[m] | 36-2616 | — |
| **CHEMICAL RESISTANCE** | | | | | | | |
| Strong Acids | D543 or D1239 | Excellent | Excellent | Good | Excellent | Good | Poor |
| Strong Alkalis | | Excellent | Excellent | Excellent | Excellent | Good | Excellent |
| Greases and Oils | | Excellent | Excellent | Good | Excellent | Excellent | Good |
| Solvents | | | | | | | |
| Ketone and Ester | | Excellent | Excellent | Poor | Excellent | Fair | Poor |
| Chlorinated | | Excellent | Excellent | Good | Excellent | Fair | Poor |
| Hydrocarbon | | Excellent | Excellent | Good | Excellent | Excellent | Fair |
| **PERMANENCE** | | | | | | | |
| Max Cont Svc Temp, F | | 565-585 | 300-395 | 160-180 | 490 | 205 | 210-275 |
| Min Svc Temp, F | | -90 | -120 | Good | -80 | -20 | -75 |
| Resistance to Sunlight | | Excellent | Excellent | Fair | Fair | Fair | Good |
| Dimensional Change, % | | Nil | Nil | Nil | Nil | Slight | Slight |
| Storage Stability[k] | | Excellent | Excellent | Good | Excellent | Good | Excellent |
| Flammability (rate of burning) | | Nil | Nil | Slow | Self-extinguishing | Self-extinguishing | Slow |

[a]Cast = casting; calndr = calendering; extr = extrusion; block = block process.
[c]Trp = transparent; trl = translucent.
[d]Figures may vary with resin-plasticizer ratio.
[e]Properties particularly dependent on thickness.
[f]Unsupported film cannot be sealed on all types of heat sealers, since adhesion to metal sealer and distortion of film may be encountered.
[k]Average warehouse conditions: 40-100 F, dry.
[m]0.001-in. film.

## Plastics Films

| Type → | | Cellophane | | Cellulose | | | |
|---|---|---|---|---|---|---|---|
| | | Plain | Coated | Acetate[m] | Triacetate (42.5-44% acetyl) | Acetate Butyrate[m] | Nitrate |
| **GENERAL PROPERTIES** | ASTM | | | | | | |
| Method of Production[a] | | Extr | Extr | Extr, cast | Cast | Extr, cast | Cast, block |
| Forms Available | | Sheet, rolls, tapes | Sheet, rolls | Sheet, rolls, tapes, tubes | Sheet, rolls | Sheet, rolls | Sheet, rolls |
| Clarity[c] | | Trp | Trp | Trp, trl, opaque | Trp | Trp, opaque | Trp, trl, opaque |
| Min Thickness, in. | | 0.0009 | 0.0009 | 0.0005 | 0.003 | 0.0009 | 0.0005 |
| Max Width, in. | | 60 | 60 | 60 | 45 | 40 | 50 |
| Area Factor, 1000 sq in./lb/mil[d] | | 21.5 | 19.5 | 22 | 21.7 | 23.3 | 20 |
| **PHYSICAL PROPERTIES** | | | | | | | |
| Specific Gravity | D792 | 1.45 | 1.40-1.55 | 1.25-1.35 | 1.28 | 1.16-1.18 | 1.42-1.46 |
| Ten Str, 1000 psi | D882 | 8-19 | 7-16 | 9-14 | 9-11 | 6-9 | 10-11 |
| Elong, % | D882 | 15-25 | 15-50 | 15-35 | 25-35 | 50-70 | 30-40 |
| Burst Str (Mullen), psi[e] | D774 | — | — | 30-80 | 100-150 | 40-75 | 40-50 |
| Tear Str (Elmendorf), gm/mil | D689 | 2-10 | 2-15 | 2-15 | 10-15 | 4-16 | — |
| Fold Endurance[e] | D643 | 7000-22,000 | — | 1500-2000[n] | 200-300[n] | 900-1300[n] | 50-250[n] |
| Heat Sealing Range, F[f] | | Not heat sealable | 200-350 | 400-500 | — | — | — |
| Water Absorp (24 hr), % | D570 | High | High | Low | Low | Low | Low |
| Water Vapor Perm, gm/100 sq in./24 hr[e] | E96-53T | High | 0.2-1.0 | 10-40 | 10 | 60 | — |
| Gas Perm, cu cm/100 sq in./24 hr[e] | | | | | | | |
| Oxygen | | — | Low | 3-6[m] | — | — | — |
| Nitrogen | | — | Low | —[m] | — | — | — |
| Carbon Dioxide | | — | Low | 12-31[m] | — | — | — |
| **CHEMICAL RESISTANCE** | | | | | | | |
| Strong Acids | D543 or D1239 | Poor | Poor | Poor | Poor | Poor | Good |
| Strong Alkalis | | Poor | Poor | Poor | Poor | Poor | Fair |
| Greases and Oils | | Excellent | Good[l] | Good | Good | Fair | Fair |
| Solvents | | | | | | | |
| Ketone and Ester | | Excellent | Poor[l] | Poor | Poor | Poor | Poor |
| Chlorinated | | Excellent | Excellent | Poor | Poor | Poor | Fair |
| Hydrocarbon | | Excellent | Fair | Good | Good | Good | Fair |
| **PERMANENCE** | | | | | | | |
| Max Cont Svc Temp, F | | 375 | 300-375 | 250-300 | 300-400 | 200-250 | 140 |
| Min Svc Temp, F | | 0 | 0 | -25 | -25 | -25 | — |
| Resistance to Sunlight | | Good | Good | Good | Good | Good | Poor |
| Dimensional Change, % | | 3-5 | 2-5 | 0.2-0.8 | 0.4 | 0.3 | Nil |
| Storage Stability[k] | | Good | Good | Excellent | Excellent | Excellent | Fair |
| Flammability (rate of burning) | | Fast | Fast | Slow, 70-100[b] | Self-extinguishing | Slow, 50-80[b] | Fast |

[a] Cast = casting; calndr = calendering; extr = extrusion; block = block process.
[b] ASTM D 568.
[c] Trp = transparent; trl = translucent.
[d] Figures may vary with resin-plasticizer ratio.
[e] Properties particularly dependent on thickness.
[f] Unsupported film cannot be sealed on all types of heat sealers, since adhesion to metal sealer and distortion of film may be encountered.
[g] ASTM D 643, Method A.
[k] Average warehouse conditions: 40-100 F, dry.
[l] Coating attacked.
[m] 0.001-in. film
[n] ASTM D 643, Method B.

## High Pressure Laminates (General Purpose)—Sheet, Rod, Tube

| Grade → | CE (canvas-phenolic) | A (asbestos paper-phenolic) | AA (asbestos cloth-phenolic) | G-3 (glass cloth-phenolic) |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Density, gm/cu cm | 1.32 | 1.72 | 1.70 | 1.65 |
| Ther Cond, Btu/sq ft/hr/°F/ft | 0.17 | — | — | — |
| Max Rec Svc Temp, F | | | | |
| Short Time | 300 | 400 | 400 | 410 |
| Continuous | 250 | 275 | 275 | 290 |
| Coef of Ther Exp, $10^{-5}$ per °F | | | | |
| Lengthwise | 1.04 | 0.55 | 1.04 | 0.83 |
| Crosswise | 1.22 | 0.89 | 1.04 | 1.04 |
| Water Absorption (24 hr), % | | | | |
| 1/16 In. Thick | 1.3 | 1.3 | 2.5 | 1.8 |
| 1/8 In. Thick | 0.9 | 0.8 | 2.0 | 1.2 |
| 1/2 In. Thick | 0.5 | 0.5 | 1.2 | 0.7 |
| **MECHANICAL PROPERTIES** | | | | |
| Ten Str, 1000 psi | | | | |
| Lengthwise | 11 | 10 | 12 | 23 |
| Crosswise | 9 | 8 | 10 | 20 |
| Flex Str, 1000 psi | | | | |
| Lengthwise | 22 | 20 | 21 | 32 |
| Crosswise | 17 | 18 | 19 | 28 |
| Compr Str (flatwise), 1000 psi | 39 | 40 | 38 | 50 |
| Mod of Elast in Flex, $10^5$ psi | | | | |
| Lengthwise | 9 | 23 | 16 | 15 |
| Crosswise | 8 | 14 | 14 | 12 |
| Impact Str (edgewise), ft-lb/in. | | | | |
| Lengthwise | 1.6 | 1.0 | 4.5 | 7.5 |
| Crosswise | 1.4 | 0.9 | 4.0 | 6.0 |
| Hardness (Rockwell) | M105 | M111 | M103 | M120 |
| Bond Strength, psi | 2200 | 800 | 2000 | 1000 |
| **ELECTRICAL PROPERTIES** | | | | |
| Dielec Str (perp, short time), v/mil | | | | |
| 1/16 In. Thick | 500 | 225 | 85 | 700 |
| 1/8 In. Thick | 360 | 160 | 70 | 600 |
| Dielec Str (par., step by step, 1/8 in. thick), kv | | | | |
| Cond A | 45 | 10 | — | — |
| Cond D48/50 | 5 | — | — | — |
| Dissip Factor ($10^6$ cycles) | | | | |
| Cond A | 0.055 | — | — | 0.030 |
| Cond D24/23 | 0.070 | — | — | — |
| Dielec Const ($10^6$ cycles, cond A) | 5.3 | — | — | 6.5 |
| Insulation Res (cond 35/90), megohms | — | — | — | 200 |
| Arc Resistance, sec | 10 | 10 | 10 | 10 |
| AIEE Insulation Class | A | B | B | B |
| USES | Switchboard panels, circuit breaker and switch arms, terminal blocks, electrode supports for plating tanks, bases for motors, bobbin heads (often in combination with XX) | Mechanical parts in drying ovens, tenter rails | Rotor vanes, water pumping thrust washers, armature slot wedges, caustic resistant applications, electric appliance insulation | Armature slot wedges, structural parts requiring good electrical properties, electrical equipment operating at relatively high temperatures |

## High Pressure Laminates (General Purpose)—Sheet, Rod, Tube

| Grade → | G-5 (glass cloth–melamine) | G-10 (glass cloth–epoxy) | GPO-1 (glass mat–polyester) | Commercial and Trunk Fibre |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Density, gm/cu cm | 1.9 | 1.78 | 1.5–1.9 | 1.15 |
| Ther Cond, Btu/sq ft/hr/°F/ft | 0.29 | — | — | — |
| Max Rec Svc Temp, F | | | | |
| Short Time | 425 | 350 | 350 | — |
| Continuous | 300 | 250 | 250 | — |
| Coef of Ther Exp, $10^{-5}$ per °F | | | | |
| Lengthwise | 0.55 | — | 1.1 | 1.1 |
| Crosswise | 0.61 | — | — | 1.7 |
| Water Absorption (24 hr), % | | | | |
| 1/16 In. Thick | 1.0 | 0.09 | 1.0 | 66 |
| 1/8 In. Thick | 0.6 | 0.06 | 0.70 | 61 |
| 1/2 In. Thick | 0.4 | 0.03 | 0.35 | 36 |
| **MECHANICAL PROPERTIES** | | | | |
| Ten Str, 1000 psi | | | | |
| Lengthwise | 37 | — | 12 | 16 |
| Crosswise | 30 | — | 10 | 9 |
| Flex Str, 1000 psi | | | | |
| Lengthwise | 65 | 72 | 23 | 18 |
| Crosswise | 50 | 63 | 20 | 15 |
| Compr Str (flatwise), 1000 psi | 70 | — | 40 | 30 |
| Mod of Elast in Flex, $10^5$ psi | | | | |
| Lengthwise | 17 | — | 15 | — |
| Crosswise | 15 | — | 13 | — |
| Impact Str (edgewise), ft-lb/in. | | | | |
| Lengthwise | 12.0 | 14.4 | 12 | 2.3 |
| Crosswise | 9.0 | 10.6 | 10 | 2.1 |
| Hardness (Rockwell) | M120 | — | M93 | R80 |
| Bond Strength, psi | 1700 | 2500 | 1000 | — |
| **ELECTRICAL PROPERTIES** | | | | |
| Dielec Str (perp, short time), v/mil | | | | |
| 1/16 In. Thick | 600 | 810 | 650 | 200 |
| 1/8 In. Thick | 500 | 570 | 500 | 195 |
| Dielec Str (par., step by step, 1/8 in. thick), kv | | | | |
| Cond A | 32 | 55 | 60 | — |
| Cond D48/50 | 12 | 60 | 33 | — |
| Dissip Factor ($10^6$ cycles) | | | | |
| Cond A | 0.016 | 0.0119 | 0.03 | — |
| Cond D24/24 | 0.030 | 0.0126 | 0.05 | — |
| Dielec Const ($10^6$ cycles, cond A) | 6.8 | 4.8 | 4.3 | — |
| Insulation Res (cond C96/35/90), megohms | 100 | $1 \times 10^5$ | — | — |
| Arc Resistance, sec | 200 | 100 | 140 | 80 |
| AIEE Insulation Class | B | B | B | A |
| **USES** | Switchboard panels, arc barriers and circuit breaker parts, armature and slot wedges, structural parts, electrical applications requiring high strength and arc resistance, high temperature applications | Printed circuits; other applications where high insulation resistance and dimensional stability, are required. | Panel boards, slot wedges, spacers, coil blocking, layer insulation, core corner protectors, terminal plates, structural applications | Washers, terminal block covers, insulating plates and switch covers, arch supporters, bobbin and coil spool heads, arc barriers, shoe fiber, switch and appliance insulation, knee pads, golf club head plates, deep formed parts, trunks, cases, wastebaskets, mill boxes |

## High Pressure Laminates (Mechanical)—Sheet, Rod, Tube

| Grade → | X (kraft paper–phenolic) | P (paper-plasticized phenolic) | PC (paper-phenolic) | ES 1, 2, 3 (paper base)[a] |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Density, gm/cu cm | 1.35 | 1.33 | 1.34 | — |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.17 | 0.17 | 0.17 | — |
| Max Rec Svc Temp, F | | | | |
| Short Time | 275 | 275 | 250 | — |
| Continuous | 225 | 250 | 200 | — |
| Coef of Ther Exp, $10^{-5}$ per °F | | | | |
| Lengthwise | 1.1 | 0.77 | — | — |
| Crosswise | 1.39 | 1.22 | — | — |
| Water Absorption (24 hr), % | | | | |
| 1/16 In. Thick | 4.0 | 2.2 | 3.2 | 2.5 |
| 1/8 In. Thick | 2.3 | 1.5 | 2.0 | 1.8 |
| 1/2 In. Thick | 0.9 | — | — | — |
| **MECHANICAL PROPERTIES** | | | | |
| Ten Str, 1000 psi | | | | |
| Lengthwise | 20 | 12 | 10.5 | 12-15 |
| Crosswise | 16 | 9 | 8.5 | 8-12 |
| Flex Str, 1000 psi | | | | |
| Lengthwise | 28 | 15 | 14 | 15 |
| Crosswise | 23 | 13 | 11 | 15 |
| Compr Str (flatwise), 1000 psi | 36 | 25 | 22 | — |
| Mod of Elast in Flex, $10^6$ psi | | | | |
| Lengthwise | 18 | 12 | 10 | — |
| Crosswise | 13 | 9 | 8 | — |
| Impact Str (edgewise), ft-lb/in. | | | | |
| Lengthwise | 0.9 | 0.8 | 0.9 | 0.25 |
| Crosswise | 0.7 | 0.6 | 0.8 | 0.22 |
| Hardness (Rockwell) | M110 | M90 | M70 | M118 |
| Bond Strength, psi | 900 | — | — | — |
| **ELECTRICAL PROPERTIES** | | | | |
| Dielec Str (perp, short time), v/mil | | | | |
| 1/16 In. Thick | 700 | 650 | 600 | — |
| 1/8 In. Thick | 500 | 470 | 425 | — |
| Dielec Str (par., step by step, 1/8 in. thick), kv | | | | |
| Cond A | — | 50 | — | — |
| Cond D48/50 | — | 10 | — | — |
| Dissip Factor ($10^6$ cycles) | | | | |
| Cond A | — | — | — | — |
| Cond D24/23 | — | — | — | — |
| Dielec Const ($10^6$ cycles, cond A) | — | — | — | — |
| Insulation Res (cond C96/35/90), megohms | — | — | — | — |
| Arc Resistance, sec | 10 | — | — | — |
| AIEE Insulation Class | A | A | A | A |
| **USES** | Structural parts for radio, aircraft and electrical equipment and switchgear. Terminal boards or panels, insulating washers, bushings, coil forms, brush-holder bushings | Insulating washers, terminal boards, plug and socket bases, switch bases and panels for subassemblies | Motor and generator terminal boards, insulating washers, terminal strips, switch bases and panels, staked terminal boards and strips | Engraved nameplates, signs |

[a]ES-1 is melamine laminate; ES-2 is phenolic laminate; ES-3 has phenolic core, melamine base.

## High Pressure Laminates (Mechanical)—Sheet, Rod, Tube

| Grade → | C (cotton canvas–phenolic) | L (cotton linen–phenolic) | MC (cotton fabric–melamine) | Base Fibre |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Density, gm/cu cm | 1.35 | 1.34 | 1.5 | 1.3 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.17 | 0.17 | 0.17 | 0.17 |
| Max Rec Svc Temp, F | | | | |
| Short Time | 275 | 275 | 275 | — |
| Continuous | 225 | 225 | 225 | — |
| Coef of Ther Exp, $10^{-6}$ per °F | | | | |
| Lengthwise | 1.04 | 0.77 | — | 1.1 |
| Crosswise | 1.22 | 1.04 | — | 1.7 |
| Water Absorption (24 hr), % | | | | |
| 1/16 In. Thick | 4.4 | 1.3 | 2.2 | 55 |
| 1/8 In. Thick | 1.6 | 0.4 | 1.6 | 48 |
| 1/2 In. Thick | 1.0 | 0.5 | 1.0 | 25 |
| **MECHANICAL PROPERTIES** | | | | |
| Ten Str, 1000 psi | | | | |
| Lengthwise | 11 | 14 | 11 | 17 |
| Crosswise | 9 | 10 | 7 | 10 |
| Flex Str, 1000 psi | | | | |
| Lengthwise | 22 | 23 | 23 | 21 |
| Crosswise | 18 | 18 | 18 | 17 |
| Compr Str (flatwise), 1000 psi | 37 | 35 | 45 | 36 |
| Mod of Elast in Flex, $10^6$ psi | | | | |
| Lengthwise | 10 | 11 | — | 10 |
| Crosswise | 9 | 8 | — | 7 |
| Impact Str (edgewise), ft-lb/in. | | | | |
| Lengthwise | 2.3 | 1.3 | 0.9 | 2.3 |
| Crosswise | 2.2 | 1.2 | 0.9 | 2.1 |
| Hardness (Rockwell) | M103 | M105 | M115 | R100 |
| Bond Strength, psi | 2000 | 1700 | 1900 | — |
| **ELECTRICAL PROPERTIES** | | | | |
| Dielec Str (perp, short time), v/mil | | | | |
| 1/16 In. Thick | 500 | 500 | — | 200 |
| 1/8 In. Thick | 360 | 360 | — | 200 |
| Dielec Str (par., step by step, 1/8 in. thick) kv | | | | |
| Cond A | 15 | 15 | — | — |
| Cond D48/50 | — | — | — | — |
| Dissip Factor ($10^6$ cycles) | | | | |
| Cond A | — | 0.055 | — | — |
| Cond D24/23 | — | 0.070 | — | — |
| Dielec Const ($10^6$ cycles, cond A) | 6.0 | 5.8 | — | — |
| Insulation Res (cond C96/35/90), megohms | — | — | — | — |
| Arc Resistance, sec | 10 | 10 | 100 | 100 |
| AIEE Insulation Class | A | A | — | A |
| **USES** | Gears and pinions, cams, pulleys, bobbin heads, chemical piping and fittings, bearings | Small gears and pinions, parts requiring intricate machining, breaker arms, fairleads and knobs | Plating barrel applications; others requiring good resistance to caustics | Gears, cams, fairleads, bushings, grommets, switch handles, terminal blocks, armature slot wedges, threaded and tapped pieces |

## High Pressure Laminates (Electrical)—Sheet, Rod, Tube

| Grade → | XX (paper-phenolic) | XXP (paper-phenolic) | XXX (paper-phenolic) | XXXP (paper-plasticized phenolic) | LE (cotton linen-phenolic) |
|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | | |
| Density, gm/cu cm | 1.34 | 1.32 | 1.32 | 1.29 | 1.32 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.17 | 0.17 | 0.17 | 0.17 | 0.17 |
| Max Rec Svc Temp, F | | | | | |
| Short Time | 300 | 275 | 300 | 275 | 300 |
| Continuous | 250 | 250 | 250 | 250 | 250 |
| Coef of Ther Exp, $10^{-5}$ per °F | | | | | |
| Lengthwise | 0.94 | 1.05 | 0.94 | 1.04 | 1.04 |
| Crosswise | 1.33 | 1.66 | 1.28 | 1.66 | 1.44 |
| Water Absorption (24 hr), % | | | | | |
| 1/16 In. Thick | 1.3 | 1.3 | 0.8 | 0.40 | 1.3 |
| 1/8 In. Thick | 0.9 | 0.9 | 0.5 | — | 0.8 |
| 1/2 In. Thick | 0.5 | — | 0.3 | — | 0.5 |
| **MECHANICAL PROPERTIES** | | | | | |
| Ten Str, 1000 psi | | | | | |
| Lengthwise | 16 | 11 | 15 | 12 | 13.5 |
| Crosswise | 13 | 8.5 | 12 | 9.5 | 9.5 |
| Flex Str, 1000 psi | | | | | |
| Lengthwise | 18 | 18 | 18 | 21 | 18 |
| Crosswise | 14 | 14 | 14 | 15 | 15 |
| Compr Str (flatwise), 1000 psi | 34 | 25 | 32 | 25 | 37 |
| Mod of Elast in Flex, $10^5$ psi | | | | | |
| Lengthwise | 14 | 9 | 13 | 11 | 10 |
| Crosswise | 11 | 7 | 10 | 8 | 8 |
| Impact Str (edgewise), ft-lb/in. | | | | | |
| Lengthwise | 0.55 | 0.55 | 0.5 | 0.5 | 1.3 |
| Crosswise | 0.50 | 0.50 | 0.45 | 0.4 | 1.2 |
| Hardness (Rockwell) | M105 | M100 | M110 | M110 | M105 |
| Bond Strength, psi | 1100 | — | 1200 | — | 1800 |
| **ELECTRICAL PROPERTIES** | | | | | |
| Dielec Str (perp, short time), v/mil | | | | | |
| 1/16 In. Thick | 700 | 700 | 650 | 1000 | 500 |
| 1/8 In. Thick | 500 | 500 | 470 | 700 | 360 |
| Dielec Str (par., step by step, 1/8 in. thick), kv | | | | | |
| Cond A | 50 | 65 | 65 | 65 | 50 |
| Cond D48/50 | 10 | 15 | 15 | 33 | 6 |
| Dissip Factor ($10^6$ cycles) | | | | | |
| Cond A | 0.040 | 0.037 | 0.034 | 0.027 | 0.048 |
| Cond D24/23 | 0.046 | 0.045 | 0.038 | 0.030 | 0.058 |
| Dielec Const ($10^6$ cycles, cond A) | 5.3 | 4.5 | 4.7 | 4.27 | 5.3 |
| Insulation Res (cond C96/35/90), megohms | 60 | 500 | 1000 | 20,000 | 30 |
| Arc Resistance, sec | 10 | 10 | 10 | 10 | 10 |
| AIEE Insulation Class | A | A | A | A | A |
| **USES** | Panels for switchboards and instruments, switch and circuit breaker arms, terminal blocks for motors and transformers, coil forms for radio and television, brush holder bushings, bobbin heads and spools | Condenser stator brackets, wave change switch rotors and stators, plug and socket bases, terminal boards and subpanels, insulating washers | Panels for radio and television equipment; jack spacers, radio coil forms, high voltage switchgear | Condenser stator brackets, wavechange switch rotors and stators, terminal boards and subpanels, coil support bases | Terminal blocks and strips, panels, high humidity applications |

## High Pressure Laminates (Electrical)—Sheet, Rod, Tube

| Grade → | G-2 (glass cloth-phenolic) | G-5 (glass cloth-silicone) | G-7 (glass cloth-silicone) | N-1 (nylon fabric-phenolic) | Electrical Insulation Fibre |
|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | | |
| Density, gm/cu cm | — | 1.65 | 1.68 | 1.15 | 1.20 |
| Ther Cond, Btu/hr/sq ft/°F/ft | — | 0.17 | 0.17 | — | — |
| Max Rec Svc Temp, F | | | | | |
| Short Time | 410 | 500 | 500 | 200 | — |
| Continuous | 290 | 400 | 400 | 165 | — |
| Coef of Ther Exp, $10^{-5}$ per °F | | | | | |
| Lengthwise | — | 0.56 | — | — | 1.1 |
| Crosswise | — | 0.55 | — | — | 1.7 |
| Water Absorption (24 hr), % | | | | | |
| 1/16 In. Thick | 1.50 | 0.3 | 0.3 | 0.3 | 66 |
| 1/8 In. Thick | 0.95 | 0.25 | 0.20 | 0.2 | 61 |
| 1/2 In. Thick | 0.55 | 0.15 | 0.15 | 0.1 | 36 |
| **MECHANICAL PROPERTIES** | | | | | |
| Ten Str, 1000 psi | | | | | |
| Lengthwise | 16 | 13 | 23 | 8.5 | 21 |
| Crosswise | 11 | 10 | 18 | 8 | 10 |
| Flex Str, 1000 psi | | | | | |
| Lengthwise | 30 | 23 | 44 | 18 | 20.5 |
| Crosswise | 20 | 19 | 37 | 15 | 14.5 |
| Compr Str (flatwise), 1000 psi | 38 | 40 | 45 | — | 34 |
| Mod of Elast in Flex, $10^5$ psi | | | | | |
| Lengthwise | 13 | — | 14 | 6 | — |
| Crosswise | 10 | — | 12 | 5 | — |
| Impact Str (edgewise), ft-lb/in. | | | | | |
| Lengthwise | 6.6 | 15.1 | 12.1 | 3.7 | 3 |
| Crosswise | 4.7 | 9.5 | 9.6 | 3.3 | 2.9 |
| Hardness (Rockwell) | M110 | M95 | M100 | M105 | R70 |
| Bond Strength, psi | 1400 | 1000 | 800 | 1200 | — |
| **ELECTRICAL PROPERTIES** | | | | | |
| Dielec Str (perp, short time), v/mil | | | | | |
| 1/16 In. Thick | 500 | 250 | 400 | 600 | 215 |
| 1/8 In. Thick | 425 | 185 | 350 | 450 | 200 |
| Dielec Str (par., step by step, 1/8 in. thick), kv | | | | | |
| Cond A | 30 | 50 | 55 | 62 | — |
| Cond B48/50 | 10 | 45 | 30 | 55 | — |
| Dissip Factor ($10^6$ cycles) | | | | | |
| Cond A | 0.025 | 0.0022 | 0.0015 | 0.024 | — |
| Cond D24/23 | 0.080 | 0.0227 | 0.0150 | 0.030 | — |
| Dielec Const ($10^6$ cycles, cond A) | 5.5 | 4.18 | 3.9 | 3.3 | — |
| Insulation Res (cond C96/35/90), megohms | 5000 | 4000 | 2500 | $5 \times 10^4$ | — |
| Arc Resistance, sec | — | 220 | 220 | — | 125 |
| AIEE Insulation Class | B | H | H | A | A |
| **USES** | Class B insulation; other applications where good temperature resistance is required but mechanical properties are not critical | Insulation applications where high temperature resistance, arc resistance and low losses are needed, such as Class H transformers | Radio transmitter parts; Class H transformers; low loss, high frequency radio and radar insulators; motor slot wedges; slot liners; top sticks | High voltage applications; radio wave change switch stators and rotors, where low losses are critical; electrical insulating parts that must be postformed | Armature slot insulation, armature end laminations; field coil insulation, metal box liners, washers, arc shields, formed slot wedges, gaskets, specialties |

## Glass-Reinforced Plastics (Low Pressure)—Molded Laminates [a]

| Type → | | Polyester (rigid styrene type) | | Silicone–Woven Fabric | Epoxy–Woven Fabric |
|---|---|---|---|---|---|
| | | Mat | Woven Fabric | | |
| PHYSICAL PROPERTIES | ASTM | | | | |
| Specific Gravity | D792 | 1.15–2.2 | 1.6–2.0 | 1.6–1.93 | 1.6–1.85 |
| Coef of Ther Exp, $10^{-6}$ per °F | D325 | 1.0–1.4 | — | — | — |
| Water Absorption (24 hr), % | D570 | 0.1–2.0 | 0.1–0.8 | 0.03–0.1 | 0.04–0.08 |
| Flammability (<0.050 in.), sq in./min. | D635 | 2.0 to self-exting | 1.0 to self-exting | 0–120[c] | — |
| MECHANICAL PROPERTIES | | | | | |
| Ten Str, 1000 psi | D638 | 8–25 | 25–55 | 20–40.6[d] | 40–85 |
| Hardness | | | | | |
| Rockwell | D785 | M80–120 | M100–120 | — | M100–112 |
| Barcol | | 40–55 | 55–65 | 50–75 | 62–66 |
| Impact Str (Izod), ft-lb/in. notch | D256 | 7–15 | 13–18 | — | 12–18 |
| Mod of Elast in Flex, $10^6$ psi | D790 | 10–25 | 20–38 | 18–32[d] | 30–46 |
| Flex Str, 1000 psi | D790 | 20–40 | 40–75 | 23–47[d] | 65–120 |
| Compr Str, 1000 psi | D695 | 15–35 | 25–45 | 9.3–24[d] | 45–52 |
| ELECTRICAL PROPERTIES | | | | | |
| Vol Res, ohm-cm | D257 | $10^{11}$ | $10^{11}$ | $2.4–14 \times 10^{14}$ | $10^{16}$ |
| Dielec Str (short time, ⅛ in.), v/mil | D149 | 300–800 | 350–700 | 100–388 | 450–550 |
| Dielec Const | | | | | |
| 60 Cycles | D150 | 3.4–6.0 | 4.1–6.0 | — | — |
| 1000 Cycles | D150 | 3.4–5.8 | 4.0–5.8 | — | — |
| $10^6$ Cycles | D150 | 3.4–5.6 | 3.8–5.6 | 3.5–3.97 | 4.2–4.9 |
| Dissip Factor ($10^6$ cps) | D150 | 0.01–0.03 | 0.01–0.03 | 0.001–0.003 | — |
| Loss Factor | | | | | |
| 60 Cycles | D150 | 0.1–0.3 | 0.08–0.3 | — | — |
| 1000 Cycles | D150 | 0.07–0.3 | 0.06–0.3 | — | — |
| $10^6$ Cycles | D150 | 0.03–0.2 | 0.03–0.2 | — | 0.05–0.09 |
| Arc Resistance, sec | D495 | 90–130 | 90–180 | 225–250 | 130–185 |
| HEAT RESISTANCE | | | | | |
| Max Rec Svc Temp, F | | 250–400 | 250–400[b] | 450–500 | 250–400 |
| Heat Dist Temp (264 psi), F | D648 | 200–550 | 390–550 | — | — |
| CHEMICAL RESISTANCE | | Slightly to heavily attacked by strong acids. Attacked by strong alkalis, ketones and chlorinated solvents | | Satisfactory resistance to aviation gas, lube oils, 40% sulfuric acid, 5% hydrochloric acid, and Freon 114. Slightly attacked by 5% hydrochloric acid Severely attacked by acetone, methyl ethyl ketone, ethyl alcohol, isopropyl ether, toluene, cellosolve, carbon tetrachloride, ethylene dichloride and trichlorethylene | Excellent resistance to organic liquids, such as alcohols and hydrocarbons. Resistant to weak acids and some strong acids. Slightly affected by some strong alkalis. Relatively poor general resistance to acetone, glacial acetic acid, 30% nitric acid and 30% peroxide |
| USES | | Either mat, cloth or combination of both used, depending on strength and economic requirements. Represents largest volume of all low pressure reinforced plastics. Used for boats, car bodies and parts, aircraft parts, chairs, trays, skis, tote boxes, laundry tubs, machine housings, chemical storage tanks, architectural building panels | | Special high temperature structural or electrical parts, such as aircraft radomes and ductwork, thermal and arc barriers, covers and cases for high frequency equipment | High strength parts, such as laminated tools for metal forming, aircraft structural parts, pipe, leaf or coil springs, high strength electrical or chemical resistant parts |

[a] Range of values is intended only to indicate general order of magnitude. Specific properties vary widely with type and quantity of reinforcement resin formulation and fabricating practice.
[b] A TAC-polyester is now available for continuous use at 500 F.
[c] When tested according to method 2023 of Spec. MIL L–P–406.
[d] A primary attribute of silicones is good strength retention after continuous exposure to 450–500 F.

# Plastics and Rubber Foams—Flexible

### NATURAL RUBBER (LATEX)

| | |
|---|---|
| Density, lb/cu ft | 6.0–7.0 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.021–0.025 |
| Tensile Strength, psi | 10–20 |
| Max Rec Svc Temp, F | 160 |
| Flammability | Burns |
| Tear Strength, lb/in. | 1.2 |
| Resilience, % | 64 |
| Rebound, in. | 2.5 |
| Elongation, % | 380 |
| Compression Loss, % | |
| 50,000 Flexes | 13.0 |
| 300,000 Flexes | 15.0 |
| Compression Set, % | |
| 22 Hr at 158 F | 4.6 |
| 22 Hr at 177 F | 4.1 |
| Hysteresis Loss, % | 23.2 |
| RMA Compression, lb | 30.0 |

### POLYETHYLENE (CELLULAR)[a]

| | |
|---|---|
| Tensile Strength | 670 |
| Elongation, % | 310 |
| Specific Gravity | 0.47 |
| Dielectric Strength, v/mil | |
| Short Time | 220 |
| Long Time | 190 |
| Dissipation Factor | |
| 1000 Cycles | 0.00033 |
| 10,000 Cycles | 0.00038 |
| Dielectric Constant | |
| 1000 Cycles | 1.48 |
| 10,000 Cycles | 1.49 |

[a]Wire insulation for No. 14 AWG (0.250-in. o. d.). Wire insulation is the primary use of cellular polyethylene at present.

### VINYL (OPEN CELL)

| | |
|---|---|
| Density, lb/cu ft | 4 and up |
| Heat Sealability | Excellent |
| Tensile Strength, psi | 10–200 |
| Elongation, % | 75–300 |
| Flammability | Self-extinguishing |
| Indentation Load | |
| Deflection (25% def) | |
| Original, lb/50 sq in. | 3–500 |
| After Aging, % chg[a] | ±20 |
| Compression Set (max, 2 hr at 158 F), % | 15 |
| Set after Dynamic Flexing (max, 250,000 cycles), % | 10 |
| Chemical Resistance[b] | |
| Strong Acids | E |
| Strong Alkalis | E |
| Grease, Oils | G |
| Organic Solvents | P to E |
| Water | E |
| High Humidity | E |
| Sunlight | G |

[a]Air oven aging 22 hr, 212 F.
[b]E = excellent; G = good; P = poor.

### SYNTHETIC RUBBERS

| Type → | Neoprene | Butadiene-Styrene (GR-S) | Butadiene-Acrylonitrile |
|---|---|---|---|
| Density, lb/cu ft | 10–30 | 4.5 | 10–25 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.021–0.029 | 0.018 | 0.021–0.025 |
| Tensile Strength, psi | 20–100 | 80 | 40 |
| Max Rec Svc Temp, F | 180 | 160 | 210 |

### URETHANES

| Density[a] → | 1 | 2-4 | 6-8 | 10-12 | 16-20 |
|---|---|---|---|---|---|
| Yld Str (0.2% offset), psi | 2.5 | 4–20 | 50–75 | 200 | — |
| Compr Str (50% defl), psi | 5 | 9–48 | 78–150 | 200–380 | — |
| Coef of Ther Exp (−22 to 86 F) $10^{-5}$ per °F | — | 1.4 | — | — | 5 |
| Ther Insulation Coef (K) | 0.20 | 0.20–0.21 | 0.22–0.23 | 0.26 | 0.28–0.30 |
| Water Absorption, lb/cu ft | | | | | |
| 25-Day Soak | 28 | 22.8–24 | — | — | 2–4 |
| 120 Hr at 50% RH | 0.005 | 0.006–0.027 | — | — | 0.067–0.084 |
| 120 Hr at 98% RH | 0.38 | 0.38–0.39 | — | — | 0.359–0.560 |
| Dielec Const (1000 cycles) | — | 2.2–2.3 | — | 2.5 | 2.70–2.85 |
| Vol Res, $10^{14}$ ohm-cm | — | 6.8–6.9 | — | 7.2 | 7.7–8.3 |
| Sound Absorption Coef | | | | | |
| 250 Cycles | — | 0.73 | 0.20 | 0.22 | — |
| 500 Cycles | — | 0.33 | 0.22 | 0.21 | — |
| 1000 Cycles | — | 0.37 | 0.20 | 0.31 | — |
| Bond Str, psi | | | | | |
| Aluminum | 6 | 10–27 | — | 56 | 158 |
| Glass | 5 | 9–25 | — | 50 | 142 |
| Steel | 7 | 12–29 | — | 62 | 146 |
| Wood | 8 | 17–29 | — | 62 | 170 |
| Flame Res[b] | | | | | |
| 2 Lb/Cu Ft | Incombustible | | | | |
| 10 Lb/Cu Ft | Self-extinguishing | | | | |
| Max Rec Svc Temp, F | 200 | | | | |
| Heat Dist Temp (5 psi flex, 0.10 in. defl), F | 130 | | | | |
| Chemical Res | Swell slightly in many chemical solutions. Attacked by strong acids and alkalis | | | | |

[a]Density in lb per cu ft.
[b]Federal Bldg Spec SSA118A.

## Plastics Foams—Rigid

**SILICONES**

| Density[a] → | 12[b] | 14[b] | 16[c] |
|---|---|---|---|
| Compr Str (orig), psi | 100 | 200 | 325 |
| Compr Str (after aging), psi[d] | | | |
| 77 F, 200 Hr | 100 | 190 | 210 |
| 500 F, 1/2 Hr | 5 | 25 | 70 |
| 500 F, 200 Hr | 20 | 45 | 80 |
| Weight Loss During Expansion, % | 1.2 | 1.3 | 1.0 |
| Weight Loss After Heating, % | | | |
| 1000 Hr, 500 F | 3.5 | 2.6 | 2.6 |
| 1000 Hr, 570 F | 8.0 | 4.2 | 4.2 |
| 72 Hr, 700 F | 8.5 | 5.2 | 5.2 |
| Water Abs (24 hr), % | 3.2 | 2.3 | 2.1 |
| Heat Dist Temp, F | >700 | >700 | >700 |
| Flammability | No burn | No burn | No burn |
| Dielec Const ($10^6$ cycles) | 1.23 | 1.25 | 1.26 |
| Dissip Factor ($10^6$ cycles) | 0.0004 | 0.00102 | 0.00105 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.025 | 0.025 | 0.025 |

[a] Density in lb per cu ft.
[b] Expanded at 320 F.
[c] Prefoamed; expanded at 320 F. Heat aged at 500 F.

**POLYSTYRENES AND CELLULOSE ACETATE**

| Type, Density[a] → | Polystyrenes | | | | Cellulose Acetate (prefoamed) |
|---|---|---|---|---|---|
| | Prefoamed | | Foam-in-Place | | |
| | 1.3-2.0 | 3.0-4.2 | 2-4 | 6-10 | 4-8 |
| Compr Yld Str, psi | 10–35 | 50–140 | 15–50[d] | 60–100[d] | 128–235 |
| Ten Str, psi | 30–100 | 105–185 | 30–85 | 90–130 | 112–183 |
| Shear Str, psi | 15–45 | 55–95 | — | — | 100–185 |
| Flex Str, psi | >32 | <170 | 40–120 | 130–310 | 73–177 |
| Compr Mod of Elast, 1000 psi | 0.45–1.75 | 1.7–5.3 | — | — | 5.5–13.5 |
| Flex Mod of Elast, 1000 psi | 0.20–1.9 | — | — | — | 3.5–5.5 |
| Impact Str (Izod), ft-lb/in. notch | 0.5–2.7 | — | 2.0–3.0[e] | 3.0–5.5[e] | 0.01–1.15 |
| Flammability, ipm | Available self-ext | | — | — | 4.2–8.5 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.020–0.024 | | 0.018–0.019 | 0.020–0.023 | 0.025–0.027 |
| Coef of Ther Exp, per °F | $2.5 \times 10^{-5}$ | | — | — | $2.0–2.5 \times 10^{-4}$ |
| Spec Ht, Btu/lb/°F | 0.27 | | — | — | — |
| Max Rec Svc Temp, F | 155–175 | | 185 | 185 | 200–350 |
| Water Absorption (vol), % | <6 | | — | — | 0.15, 1.05[b] |
| Water Vapor Transmission[c] | 1.5–3.0 | | — | — | — |
| Dielec Const | <1.07 | | 1.19[f] | — | 1.10–1.12 |
| Dissip Factor | <0.004 | | >0.0005[g] | — | 0.002–0.003 |

[a] Density in lb per cu ft.
[b] Absorption in lb per cu ft at 50 and 100% RH, respectively.
[c] Grains/sq ft/hr/in. Hg.
[d] At 5% offset.
[e] Unnotched, in.-lb/in.
[f] At 4–6 lb/cu ft density.
[g] At 2–10 lb/cu ft density.

**EPOXIES, PHENOLICS AND URETHANES[a]**

| Type, Density[b] → | Epoxy (prefoamed) | | Phenolic (foam-in-place) | | Urethane (foam-in-place) | | | |
|---|---|---|---|---|---|---|---|---|
| | 5-10 | 13-20 | 2-5 | 7-10 | 0.5-5 | 6-9 | 12-15 | 18-25 |
| Compr Str, psi | 90–260 | 440–1080 | 9–31 | 45–130 | 2–120 | 150–250 | 350–800 | 900–1800 |
| Ten Str, psi | 51–180 | 360–650 | 4–35 | 35–75 | 10–150 | 150–300 | 300–600 | 700–1200 |
| Flex Str, psi | 210–420 | 570–940 | 24–40 | 75–230 | — | — | — | — |
| Shear Str, psi | — | — | 8–30 | 40–135 | 2–100 | 120–200 | 180–550 | 7600 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.022 | 0.024 | 0.020 | 0.023 | 0.01–0.03 | 0.012–0.03 | 0.014–0.03 | 0.015–0.03 |
| Coef of Ther Exp, $10^{-6}$ per °F | 2.2 | 1.6 | — | — | 1.5 | 2.0 | 4.4 | 5.0 |
| Water Abs (vol), % | 0.25–1.3 | 0.09–0.1 | — | — | — | 1.6 | 0.6 | 0.2 |
| Max Rec Svc Temp, F | — | — | 300[c] | 300[c] | 250 | 350 | 400 | 400 |
| Flammability | — | — | Noninflammable | | Self-extinguishing | | | |
| Dissip Factor | 0.0001–0.0004 | 0.003–0.009 | — | — | 0.0005 | 0.001 | 0.002 | 0.003 |
| Vol Res, ohm-cm | — | — | — | — | — | — | — | — |
| Dielec Str, v/mil | — | — | — | — | — | — | — | — |
| Dielec Const | 1.19–1.36 | 1.46–1.55 | — | — | 1.05 | 1.15 | 1.25 | 1.40 |

[a] Chemically activated.
[b] Density in lb per cu ft.
[c] For intermittent exposure: 550 F.

## Hard Rubber—Molded, Extruded

| Type → | Molded Parts[a] | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | GP | GP | GP | GP | H Ht | H Ar | Ar Ht Wr, H DQ | H Ht, Ch | Ht Ma |
| **PHYSICAL PROPERTIES[b]** | | | | | | | | | |
| Specific Gravity | 1.21 | 1.21 | 1.28 | 1.54 | 1.65 | 1.95 | 1.71 | 1.24 | 1.80 |
| Water Absorption (24 hr), % | 0.08 | 0.06 | 0.14 | 0.30 | 0.06 | 0.06 | 0.10 | 0.12 | 0.04 |
| Color | Black | Black | Black | Black | Red-brown | Red-brown | Red-brown | Black | Black |
| **MECHANICAL PROPERTIES** | | | | | | | | | |
| Ten Str, 1000 psi | 8.3 | 7.9 | 4.5 | 2 | 6.75 | 4 | 5.8 | 7.17 | 5.4 |
| Elong (in 2 in.), % | 4.00 | 4.00 | 3.40 | 2.00 | 2.60 | 1.00 | 2.60 | 2.70 | 1.80 |
| Hardness (Rockwell) | B108-76 | B107-91 | B129-79 | B103-27 | B83-60 | B65-41 | B82-55 | B115-85 | B82-54 |
| Hardness (durometer) | 81-87 | 81-87 | 78-84 | 76-82 | 85-92 | 87-95 | 86-92 | 84-90 | 84-92 |
| Impact Str (Izod notched), ft-lb/in. | 0.48 | 0.45 | 0.45 | 0.27 | 0.35 | 0.32 | 0.38 | 0.41 | 0.34 |
| Flex Str, 1000 psi | 12.5 | 11.3 | 7.1 | 2.8 | 8.7 | 8.4 | 9.1 | 11.3 | 10 |
| Heat Dist Temp, F | 142 | 145 | 134 | Low | 283 | 300 | 246 | 275 | 295 |
| **ELECTRICAL PROPERTIES** | | | | | | | | | |
| Dielec Str (60 cycles), v/mil | 435 | 496 | 344 | 377 | 393 | 600 | 371 | 400 | 420 |
| Dielec Const[c] | 3.00 | 2.95 | 3.80 | 4.95 | 4.10 | 4.80 | 4.60 | 3.50 | 4.10 |
| Dissip Factor[c] | 0.8 | 0.7 | 1.2 | 2.8 | 1.2 | 2.5 | 1.2 | 1.6 | 1.8 |
| Surface Res (74 F, 86% RH), megohms | $4.8 \times 10^5$ | $>10^8$ | $>10^8$ | $5.08 \times 10^5$ | $5.32 \times 10^5$ | — | $4.46 \times 10^4$ | $2.0 \times 10^3$ | $8.02 \times 10^4$ |

| Type → | Sheets[a] | | | | | Rods and Tubes[a] | | | |
|---|---|---|---|---|---|---|---|---|---|
| | GP | El[d] | H Ht | H Ht, Ch | St Fl, H DQ | GP | El | H Ht, Ch | St Fl, H DQ |
| **PHYSICAL PROPERTIES[b]** | | | | | | | | | |
| Specific Gravity | 1.20 | 1.17 | 1.43 | 1.24 | 1.27 | 1.21 | 1.15 | 1.24 | 1.27 |
| Water Absorption (24 hr), % | 0.06 | 0.22 | 0.15 | 0.12 | 0.08 | 0.06 | 0.12 | 0.12 | 0.07 |
| Color | Black | Black | Black | Black | Yellow-brown | Black | Black | Black | Yellow-brown |
| **MECHANICAL PROPERTIES** | | | | | | | | | |
| Ten Str, 1000 psi | 9.3 | 2.55 | 7.4 | 7.17 | 7.45 | 9.7 | 3.6 | 7.17 | 6.5 |
| Elong (in 2 in.), % | 5.00 | 33.00 | 1.20 | 2.70 | 5.30 | 5.00 | 16.00 | 2.70 | 3.80 |
| Hardness (Rockwell) | 112-79 | — | 86-60 | 115-85 | 112-80 | 107-70 | — | 115-85 | 112-80 |
| Hardness (durometer) | 80-86 | 50-60 | 86-92 | 84-90 | 80-86 | 80-86 | 65-75 | 84-90 | 80-86 |
| Impact Str (Izod notched), ft-lb/in. | 0.48 | 0.51 | 0.53 | 0.41 | 0.50 | 0.48 | 0.48 | 0.41 | 0.52 |
| Flex Str, 1000 psi | 16.6 | — | 9.64 | 11.3 | 14.95 | 11.375 | — | 11.3 | 9.06 |
| Heat Dist Temp, F | 159 | Low | 221 | 275 | 150 | 163 | Low | 275 | 217 |
| **ELECTRICAL PROPERTIES** | | | | | | | | | |
| Dielec Str (60 cycles), v/mil | 487 | 437 | 613 | 400 | 415 | 524 | 512 | 400 | 374 |
| Dielec Const[c] | 2.95 | 3.00 | 3.25 | 3.50 | 3.70 | 2.90 | 3.15 | 3.50 | 3.60 |
| Dissip Factor[c] | 0.5 | 1.3 | 0.6 | 1.6 | 0.6 | 0.5 | 1.4 | 1.6 | 0.9 |
| Surface Res (74 F, 86% RH), megohms | $2.23 \times 10^7$ | $2.66 \times 10^4$ | $>10^8$ | $2.0 \times 10^3$ | $7.98 \times 10^4$ | $>10^8$ | $>10^8$ | $2.0 \times 10^3$ | $6.73 \times 10^4$ |

[a] GP = general purpose, H = high, HT = heat resistance, Ar = arc resistance, Wr = wear resistance, DQ = dielectric quality, Ch = chemical resistance, MA = low moisture absorption, El = elongation, St = strength, Fl = flow resistance. These designations are arbitrary abbreviations of principal properties and are not standard.

[b] Hard rubber in general has a thermal coefficient of linear expansion of 0.00004 per °F.

[c] Frequency: 1 kc-1 mc.

[d] Semihard.

## Rubber—Molded, Extruded

| Type → | Natural Rubber | Butadiene-Styrene (GR-S) | Butadiene-Acrylonitrile (nitrile) | Chloroprene (neoprene) | Butyl (isobutylene-isoprene) |
|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | | |
| Specific Gravity | 0.93 | 0.94 | 1.00 | 1.25 | 0.90 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.082 | 0.143 | 0.143 | 0.112 | 0.053 |
| Coef of Ther Exp (cubical), $10^{-5}$ per °F | 37 | 37 | 39 | 34 | 32 |
| Electrical Insulation | Good | Good | Poor | Fair | Good |
| Flame Resistance | Poor | Poor | Poor | Good | Poor |
| Min Rec Svc Temp. F | -60 | -60 | 0 | -40 | -50 |
| Max Rec Svc Temp, F | 180 | 180 | 250 | 240 | 300 |
| **MECHANICAL PROPERTIES** | | | | | |
| Ten Str, psi | | | | | |
| Pure Gum | 2500-3500 | 200-300 | 500-900 | 3000-4000 | 2500-3000 |
| Black | 3500-4500 | 2500-3500 | 3000-4500 | 3000-4000 | 2500-3000 |
| Elongation, % | | | | | |
| Pure Gum | 750-850 | 400-600 | 450-700 | 800-900 | 750-950 |
| Black | 550-650 | 500-600 | 450-650 | 500-600 | 650-850 |
| Hardness (durometer) | A30-A90 | A40-A90 | A40-A95 | A40-A95 | A40-A90 |
| Rebound | | | | | |
| Cold | Excellent | Good | Good | Very good | Bad |
| Hot | Excellent | Good | Good | Very good | Very good |
| Tear Resistance | Excellent | Fair | Good | Fair to good | Good |
| Abrasion Resistance | Excellent | Good to excellent | Good | Good | Good to excellent |
| **CHEMICAL RESISTANCE** | | | | | |
| Sunlight Aging | Poor | Poor | Poor | Very good | Very good |
| Oxidation | Good | Good | Good | Excellent | Excellent |
| Heat Aging | Good | Very good | Excellent | Excellent | Excellent |
| Solvents | | | | | |
| Aliphatic Hydrocarbons | Poor | Poor | Excellent | Good | Poor |
| Aromatic Hydrocarbons | Poor | Poor | Good | Fair | Poor |
| Oxygenated, Alcohols | Good | Good | Poor | Poor | Very good |
| Oil, Gasoline | Poor | Poor | Excellent | Good | Poor |
| Animal, Vegetable Oils | Poor to good | Poor to good | Excellent | Good | Excellent |
| Acids | | | | | |
| Dilute | Fair to good | Fair to good | Good | Excellent | Excellent |
| Concentrated | Fair to good | Fair to good | Good | Good | Excellent |
| Permeability to Gases | Fair | Fair | Fair | Low | Very low |
| Water Swell Resistance | Fair | Excellent | Excellent | Fair | Excellent |
| **USES** | Pneumatic tires and tubes; power transmission belts and conveyor belts; gaskets; mountings; hose; chemical tank linings; printing press platens; sound or shock absorption; seals against air, moisture, sound and dirt | | Carburetor diaphragms, self-sealing fuel tanks, aircraft hose, gaskets, gasoline and oil hose, cables, machinery mountings, printing rolls | Flexible petroleum tubes and hoses, petroleum and chemical tank linings; electrical insulation in contact with oil, flashlight cases, electrical sockets, special truck tires | Truck and automobile tire inner tubes, airing bags for tire vulcanization and molding, steam hose and diaphragms, flexible electrical insulation |

## Rubber—Molded, Extruded


| Type → | Polysulfide (Thiokol) | Silicone (polysiloxane) | Urethane (diisocyanate polyester) | Fluorinated Acrylic (dihydroperfluoro-butylacrylate) | Viton (vinylidene fluoride-hexafluoropropylene) |
|---|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | | |
| Specific Gravity | 1.35 | 1.25 | 1.25 | 1.5 | — |
| Ther Cond, Btu/hr/sq ft/°F/ft | — | 0.11–0.12 | — | — | — |
| Coef of Ther Exp (cubical), $10^{-6}$ per °F | — | 67 | — | — | — |
| Electrical Insulation | Fair | Excellent | Fair | Good | Excellent |
| Flame Resistance | Poor | Fair | Good | Good | Good |
| Min Rec Svc Temp, F | −60 | −120 | −65 | 0 | −50 |
| Max Rec Svc Temp, F | 250 | 550 | 240 | 450 | 450 |
| **MECHANICAL PROPERTIES** | | | | | |
| Ten Str, psi | | | | | |
| Pure Gum | >1000 | 600–1000 | >5000 | 1200 | >2000 |
| Black | — | — | — | — | — |
| Elongation, % | | | | | |
| Pure Gum | 450–650 | 60–400 | 540–750 | 300 | >350 |
| Black | — | — | — | 300 | — |
| Hardness (durometer) | A40–85 | A40–85 | A35–100 | A55 | A60–90 |
| Rebound | | | | | |
| Cold | Good | Excellent | Bad | — | Good |
| Hot | Good | Excellent | Good | — | Excellent |
| Tear Resistance | Poor | Poor | Good | Poor | Fair |
| Abrasion Resistance | Poor | Poor | Excellent | Poor | — |
| **CHEMICAL RESISTANCE** | | | | | |
| Sunlight Aging | Very good | Excellent | Excellent[a] | Good | Excellent |
| Oxidation | Very good | Very good | Very good | Good | Excellent |
| Heat Aging | Fair | Outstanding | Excellent[a] | Good | Outstanding |
| Solvents | | | | | |
| Aliphatic Hydrocarbons | Excellent | Poor | Excellent | Excellent | Excellent |
| Aromatic Hydrocarbons | Excellent | Poor | Excellent[b] | Excellent | Excellent |
| Oxygenated, Alcohols | Very good | Fair | Poor | Good | Poor |
| Oil, Gasoline | Excellent | Fair | Excellent | Excellent | Excellent |
| Animal, Vegetable Oils | Excellent | Excellent | Excellent | Excellent | Excellent |
| Acids | | | | | |
| Dilute | Good | Excellent | Fair | Excellent[c] | Excellent |
| Concentrated | Good | Fair | Poor | Excellent[d] | Good |
| Permeability to Gases | Extremely low | Fair | Excellent | Fair | — |
| Water Swell Resistance | Excellent | Excellent | Excellent | Poor | Excellent |
| USES | Seals, gaskets, diaphragms, valve seat disks, flexible mountings, hose in contact with solvents, balloons, boats, life vests and rafts | Wire and cable covering, gaskets, tubing, diaphragms, vibration mountings, rollers, insulators, valve seats and closures | Fork lift truck wheels, airplane tail wheels, back-up wheels for turbine blade grinders, spinning cots for glass fiber, hydraulic accumulators, shoe heels | O-rings; V-rings; diaphragms; special applications involving contact with halogenated solvents, organic phosphates and carbon tetrachloride | Critical seals, gaskets, diaphragms, flexible mounts, coated fabrics, etc., for service in chemical and thermal environments |

[a] Discolors, but no change in properties.
[b] For up to 80% aromatics.
[c] To diesters, 450 F.
[d] To fire resistant hydraulic fluids, 450 F.

POLYPENCO®

## . . . where the house-mark is undeviating quality!



Stock Shapes—for rapid, low-cost fabrication
POLYPENCO Nylon and NYLATRON® GS
POLYPENCO Teflon† TFE
POLYPENCO Q-200.5 (cross-linked styrene)
POLYPENCO K-51 Penton‡
POLYPENCO polycarbonates

● When it comes to the really demanding jobs for industrial plastics—where deviation from the highest uniform quality may mean trouble—it pays to specify POLYPENCO. Solve your problems of in-plant production and end-product reliability today with the consistent high quality of POLYPENCO plastics, processed for uniformity in physical, chemical and electrical properties.

And you can get POLYPENCO Nylon, Teflon and other engineering materials in the widest range of stock shapes and sizes available . . . to produce your finished part.

Nationwide warehousing gives you immediate delivery, and the most up-to-date technical data and engineering help are always available to help you get the most practical, economical results. Write for the name of your nearest supplier.




NYLATRON® GS
Nylon Molding Powders



NYLAFLOW® Pressure Tubing and Hose



CORVEL®
Fusion Bond Finishes for the WHIRLCLAD® coating system



Molded Parts—FLUOROSINT® TFE fluorocarbon base composition
NYLASINT® cold pressed and sintered nylon parts

The Polymer Corporation of Penna.
Halex Corporation
Molding Resins Division
Whirlclad Division


*subsidiaries and divisions of*
THE POLYMER CORPORATION
Reading, Pennsylvania
*Export: Polypenco, Inc., Reading, Pa., U.S.A.*

POLYPENCO®

*Trademark of The Polymer Corporation
†DuPont trademark for fluorocarbon resins
‡Hercules Powder Co. trademark for chlorinated polyether resins

For more information, turn to Reader Service card, circle No. 556

# WHEN YOU NEED RESILIENCE PLUS...




**RESISTANCE TO HEAT**

A million tons of hot coke have not harmed this neoprene belt.




**RESISTANCE TO FLAME**

Neoprene coated firewalls for aircraft pass this flame thrower test.




**RESISTANCE TO COLD**

Neoprene remains flexible even at –65° F.



**RESISTANCE TO OIL**

Neoprene retains its properties in contact with oil and grease.




**RESISTANCE TO SUN AND WEATHER**

After 25 years' exposure, neoprene cable (bottom) shows no surface cracking.



**RESISTANCE TO OZONE**

Neoprene tire sidewalls resist ozone cracking.




**RESISTANCE TO ABRASION**

Tough neoprene gives dependable service in severe applications.




**RESISTANCE TO CHEMICALS**

Neoprene assures protection against most acids and chemicals.



**RESISTANCE TO IMPACT**

Neoprene has outstanding resilience, resists permanent distortion.

# SPECIFY VERSATILE DU PONT NEOPRENE

synthetic rubber

A quarter century of industrial service has proven that versatile Du Pont neoprene, with this balanced combination of properties, can meet a range of severe service requirements. Neoprene products are available from rubber goods manufacturers and distributors. For additional information, write E. I. du Pont de Nemours & Co. (Inc.), Elastomer Chemicals Dept. MDE-11, Wilmington 98, Delaware.

DU PONT
REG. U. S. PAT. OFF.

BETTER THINGS FOR BETTER LIVING...*THROUGH CHEMISTRY*

NEOPRENE MAKES TODAY'S PRODUCTS BETTER . . . TOMORROW'S PRODUCTS POSSIBLE

**For more information, turn to Reader Service card, circle No. 407**

DUREZ

PHENOLIC RESINS AND MOLDING COMPOUNDS
DIALLYL PHTHALATE COMPOUNDS
FIRE-RETARDANT POLYESTER RESINS

# For the designer who spells




**LOWER-COST** general-purpose phenolics, proved in all manner of applications for forty years. These workhorses of industry account for thousands of applications—not only because they cost less but because nothing has come along that does things better: housings, cases, large and small parts requiring a balance of such properties as strength, non-conductivity, smooth surface, resistance to heat, cold, chemicals.



**NON-BLEEDING PHENOLICS** that are resistant to alcohol, essential oils, and other solvents and impart no color or flavor to foods, perfumes, cosmetics and other bottled products. For baby-bottle nursing top and caps we offer molding compounds which will stand repeated autoclave sterilization at 275°F, with many combinations of torque strength, surface finish, moisture resistance and other properties. They are formulated for high-speed molding on automatic presses.



**GREATER IMPACT RESISTANCE** for products subject to rough handling. For these Durez can help you choose from a broad range of shock-resistant phenolic compounds for telephone parts, gears, bushings, pulleys and structural components. These range from 0.3 to 17.0 ft.-lb./in. impact. With strength like this, there's no need to run up costs by overengineering or by staying with unsatisfactory materials.



**BONDING, IMPREGNATING,** laminating and coating resins are also available from Durez in hundreds of formulations for use in abrasives, reconstructed wood, friction materials, rubber compounds, and corrosion-resistant mortars. Other types include shell-mold resins that are helping foundries produce better castings. Coating resins contribute important properties to printing inks, and to brushing or spraying finishes.



**LARGE STRUCTURAL SHAPES** such as this outboard motor shroud are stronger and safer when molded with Hetron® polyester resin and fibrous glass. Hetron laminates and molded parts do not support combustion. Fire resistance is inherent—chemically locked in without the use of weakening additives. Corrosion resistance, and the ability to take a baked-on finish without crazing, are other key qualities.


# out tougher specifications...



**DESIRABLE ELECTRICAL PROPERTIES,** combined with light weight and dimensional stability, can be obtained in Durez electrical grade phenolic molding compounds. They find wide use in automotive ignition parts, resistor casings, coil forms, tube bases, and electronic components of many types. Some of these compounds are formulated especially for molding around large inserts. Several are designed to meet military specifications.



**HEAT RESISTANCE** combined with high non-conductivity and other desirable electrical properties is also available in Durez molding compounds. Most compounds in this class are designed to take 72-hour heat-treatment at 392°F. Some will survive 450°F for relatively long periods, and higher temperatures for shorter periods, without serious impairment of physical properties or molded appearance. They find wide use in electrical appliances.



**SPECIAL PROPERTIES** in unusual combinations are available in Durez phenolics. Examples: low modulus of elasticity combined with other wanted properties. Or outstanding chemical and moisture resistance combined with high mechanical strength, as in this sump-pump impeller. By formula variations and the skills of compounding learned over a forty-year period, Durez can give you resins and molding compounds that fit any job.



**SPACE-AGE PERFORMANCE** often requires super-plastics such as Durez diallyl phthalate molding compounds. Reinforced with orlon or glass fiber, these materials are virtually free from cold flow and creep. They retain high electrical insulation values at relative humidities above 90% and over a wide temperature range. Their reliability has led to their wide use in rocket and missile components and in many other electrical and electronic systems.





**FACTS, IDEAS** for your files are available in illustrated bulletins and data sheets. These contain full descriptions of Durez materials, including properties, uses, design suggestions, facts on molding and finishing. For latest application information, ask us to send you **Durez Plastics News,** mailed periodically, and packed with information on new products and uses.

## DUREZ PLASTICS DIVISION

HOOKER CHEMICAL CORPORATION, 1414 WALCK ROAD, NORTH TONAWANDA, N. Y.

HOOKER CHEMICALS PLASTICS

**For more information, turn to Reader Service card, circle No. 410**




# Why "do-it-yourself" fabrication seldom pays

This is a "long length" saw, especially built to cut sheets of Synthane laminated plastics of over 25 feet in length.

It is extremely improbable that you would ever have sufficient work to make the purchase of such a machine profitable. Yet the long length saw is only one of hundreds of unusual machines necessary for fast, accurate, economical fabrication of laminates.

Without the advantage of special machines and tools, and faced with the possibility of errors, waste, delays, mistakes in tolerances or dimensions —at your expense—you may come to the same conclusion as have nearly all of our customers—buy your laminated plastics from us and have us fabricate them for you. Call any of our representatives—located in all principal cities—for a quotation or write to Synthane Corporation, 54 River Road, Oaks, Pa.

*You furnish the print—we'll furnish the part*

**SYNTHANE**
CORPORATION OAKS, PENNA.
Sheets • Rods • Tubes • Fabricated Parts
Molded-laminated • Molded-macerated

For more information, circle No. 444 ➤

For more information, turn to Reader Service card, circle No. 472

# CYCOLAC®



Western Electric's new "Princess" telephone, made of CYCOLAC®

## The **BORG-WARNER** Plastic

### that is **TOUGH, HARD** and **RIGID**

**MARBON CHEMICAL** WASHINGTON — MARBON BW CHEMICAL — Division **BORG-WARNER** WEST VIRGINIA

CYCOLAC OFFERS

# NEW DESIGN

## THE ONLY PLASTIC THAT GIVES YOU ALL THREE OF THESE VITAL REQUIREMENTS!



**TOUGHNESS...**

CYCOLAC has proved its ability to withstand continued rough use, hard knocks and abuse. Football helmets are typical of the gruelling service this ABS material can take without damage.

**HARDNESS...**

CYCOLAC offers unusual hardness and high-gloss finish, and retains its appearance in spite of constant handling and use. Office machines and telephones retain their smooth surface and glossy appearance almost indefinitely.

**RIGIDITY...**

CYCOLAC is resistant to flexure . . . maintains its original shape under load. Furthermore it is chemically resistant and dimensionally stable over a wide temperature range. This makes it suitable for a great variety of appliances, including floor washers.

## CYCOLAC OFFERS YOU ALL OF THESE



**GOOD ELECTRICAL PROPERTIES...**

The low water absorption of CYCOLAC, its uniform dielectric constant and power factor are basic properties needed in many electrical applications, including this automotive spark plug tester.




**RESISTANCE TO CHEMICALS & STAINS**

CYCOLAC is corrosion-resistant, offers protection against alkalies, salt solutions, oils, many acids, most household stains—makes fire extinguisher parts impervious to chemical action.



**DIMENSIONAL STABILITY...**

CYCOLAC contains no plasticizer to leach out. This factor, plus low water absorption, makes it ideal for precision end-use products and parts, such as these accurate coffee mill gears.

# OPPORTUNITIES!

CYCOLAC is the registered trademark for ABS (acrylonitrile-butadiene-styrene) polymers manufactured by the Marbon Chemical Division of Borg-Warner. This lightweight, uniform resin is specially suited for the manufacture of any product requiring superior-impact strength—even at low temperatures—heat resistance, good electrical properties, hard surface, dimensional stability and chemical resistance. CYCOLAC is available in a wide range of colors with a high gloss finish.

Because of the unique balance of mechanical, electrical and chemical properties, CYCOLAC offers manufacturers exceptional opportunities for improving the design, construction and appearance of their products with substantial production economies. This thermoplastic resin is readily injection molded, extruded or vacuum formed. It can be machined, threaded, sawed, milled, drilled, buffed, blanked, punched or sheared. Products of CYCOLAC take lacquering, enameling or printing readily, are easily vacuum metallized, and can be bonded or laminated.

Marbon Chemical is also a major producer of paint and rubber resins and TY-PLY® rubber-to-metal adhesives.

## CYCOLAC® OPENS BROAD NEW VISTAS IN MANUFACTURING ECONOMY BECAUSE IT CAN BE...

### MOLDED

CYCOLAC is an excellent material for injection molding applications. It is readily molded into simple or complex parts and shapes, large and small. The inherent quality and outstanding characteristics of this resin insure greater product uniformity in manufacture and performance, exceedingly fine appearance and increased saleability.

### EXTRUDED

CYCOLAC is extruded into sheet, tubing and profiles and is a major material in the field of rigid pipe. Extrusions of CYCOLAC have unusual durability and strength, dimensional stability, and high gloss. Whatever the need, whatever the specification, designers and engineers find CYCOLAC superior in many ways.

### VACUUM FORMED

The unique properties of CYCOLAC enable designers and engineers to use the economical vacuum forming process to eliminate large, costly metal fabrications. Postforming of extruded or calendered sheet is readily achieved by any conventional vacuum, air-pressure or mechanical method. Gauge control is easy and embossing is retained.

## PRODUCT-IMPROVING ADVANTAGES



**WIDE COLOR RANGE...**
CYCOLAC is available in hundreds of different colors—solids or tints, bright or light—adding instant visual appeal to any end use product, including durable, attractive telephone units.



**HIGH GLOSS FINISH...**
Because of its long-lasting, high-gloss finish and greater sales appeal, CYCOLAC lends itself to quality products, including office equipment, appliances and toys.



**LIGHTWEIGHT...**
CYCOLAC is the lightest of all truly rigid thermoplastics, with a specific gravity as low as 1.02. Lightweight and rigid, despite hot or cold temperature extremes, this material is ideal for products like this airline meal tray carrier.

# CYCOLAC® ...YOUR KEY TO NEW FUNCTIONAL



(A)

### (A) LIGHTER, STRONGER LUGGAGE...

CYCOLAC makes possible the economical production of attractive, durable luggage. This easily-worked plastic permits soft contours and use of unusual and unique patterns in design.

### (B) COMPACT AUTO AIR CONDITIONER...

Because of its strength, rigidity and lightweight, CYCOLAC is ideally suited for use in auto air conditioners. Rapid molding cycles, plus relatively low tooling costs for parts made of CYCOLAC, make it possible to gain substantial economies over other materials.

### (C) CORROSION-RESISTANT SPRINKLER HEADS

Made of CYCOLAC, these sprinkler heads are designed to perform under extremes of climatic conditions without corrosion or major effect from sun or weather.

### (D) BREAK-RESISTANT SHOE HEELS...

Fashionable high heels require maximum resistance to flexural fatigue failure plus resistance to breakage from sudden shocks, even at low temperature. CYCOLAC GS was specifically designed to meet these requirements.

### (E) EASY-TO-CARRY GOLF CADDY...

An interesting application of CYCOLAC is this easy-to-carry golf caddy. CYCOLAC was specified because of its unique combination of toughness and lightweight—a combination of properties essential to all sporting goods equipment.



(B)



(C)



(D)



(E)

# BEAUTY AND SOUND PRODUCT DESIGN!

## *Look at these leading industries now using Cycolac...*

• Automotive • Radio and TV • Footwear

• Air Conditioning • Home Appliance

• Domestic and Commercial Refrigeration

• Office Equipment and Furniture

• Lawn and Garden Equipment

• Telephone • Sporting Goods • Luggage

• Toy • Electrical • Power Mower

• Industrial Pipe and Fitting

• Hardware and Housewares • Photo and Safety Equipment • CYCOLAC also has many Military uses

**APPEALING FLOOR WASHER...**

Fifteen key parts made of CYCOLAC contributed to the economy, appearance and performance of this new, popular home appliance.




**STAIN-RESISTANT BLENDER CONTAINER..**

Even coffee, mustard and grape juice have no staining effect on products made of CYCOLAC.



**DEPENDABLE, PRECISION THERMOSTAT...**

Housing molded of CYCOLAC is dimensionally stable under tension and offers good insulating properties.



**SHOCK, DROP-RESISTANT RADIO...**

Case made of CYCOLAC combines stylish appearance with maximum protection for delicate electrical components.



# CHECK AND COMPARE THESE PROPERTIES OF CYCOLAC

*see why CYCOLAC is better in more ways than any other plastic!*




**CYCOLAC T**

For toughness with maximum hardness and tensile strength. Offers superior flow for injection molding of appearance parts with high surface gloss.



**CYCOLAC H**

For superior impact strength over wide temperature range in injection molded parts. Suitable for extruded sheet which can be readily vacuum formed.



**CYCOLAC L**

For intricate profile extrusions, calendered sheet and blending with PVC to facilitate processing and increase properties.


# 6 TYPES

## GIVE YOU AN UNPARALLELED COMBINATION OF VALUABLE PROPERTIES!



**CYCOLAC C**

For use in Type II ABS rigid plastic pipe. Displays superior long-term fiber stress and excellent high temperature performance.



**CYCOLAC LL**

For use in Type I ABS rigid plastic pipe. Displays a maximum of impact strength, even at low temperatures.



**CYCOLAC GS**

Especially designed for women's shoe heels which require a high resistance to flex fatigue and a good balance of physical properties. Provides excellent tensile strength, rigidity, heat resistance and impact strength at room or low temperatures.

**CHEMICAL PROPERTIES** CYCOLAC resins are almost completely resistant to aqueous acids, alkalies and salts. Concentrated sulfuric and nitric acids produce disintegration but concentrated phosphoric and hydrochloric acids have little effect. Low KB solvents, alcohols, and animal, vegetable and mineral oils produce insignificant changes.

Glacial acetic acid, carbon tetrachloride, aromatic hydrocarbons and high KB solvents cause marked swelling. Esters, ketones, and ethylene dichloride are solvents for CYCOLAC.

(ASTM D543-56T IMMERSION TEST)

# PROPERTIES OF CYCOLAC RESINS

| PROPERTY | TYPE OF RESIN | | | | | | TEST METHOD |
|---|---|---|---|---|---|---|---|
| **MECHANICAL** | **LL** Black Only | **L** | **H** | **GS** | **T** | **C** Black Only | **ASTM** |
| Tensile Strength,[2] psi 160°F | 2,900 | 2,900 | 2,900 | 3,800 | 3,800 | 4,600 | D638-58T |
| 73°F | 5,100 | 5,100 | 5,100 | 6,700 | 6,400 | 7,800 | |
| −40°F | 7,800 | 7,800 | 7,800 | 9,600 | 9,400 | 11,500 | |
| Tensile Modulus,[2] psi 73°F | 210,000 | 210,000 | 210,000 | 310,000 | 280,000 | 340,000 | D638-58T |
| Flexural Strength[1] | | | | | | | |
| 160°F, 73°F, −40°F | No failure | No failure | No failure | No failure | No failure | No failure | D790-59T |
| Flexural Yield 160°F | 5,100 | 4,600 | 4,400 | 5,900 | 5,900 | 6,900 | |
| Strength,[1] psi 73°F | 8,000 | 7,800 | 7,500 | 10,000 | 10,000 | 10,800 | D790-59T |
| ⅛"x1"x4" bar −40°F | 11,800 | 11,800 | 11,800 | 15,000 | 15,000 | 18,500 | |
| Flexural Modulus,[1] psi 160°F | 190,000 | 190,000 | 190,000 | 240,000 | 240,000 | 310,000 | |
| ⅛"x1"x4" bar 73°F | 240,000 | 240,000 | 240,000 | 310,000 | 310,000 | 370,000 | D790-59T |
| −40°F | 260,000 | 260,000 | 260,000 | 360,000 | 360,000 | 420,000 | |
| Rockwell Hardness[1] | R86 | R86 | R87 | R101 M10 | R101 M10 | R108 M35 | D785-51 |
| Specific Gravity[1] | 1.04 | 1.02 | 1.02 | 1.04 | 1.04 | 1.06 | |
| Wear Index, Taber Volume Loss Method CS-17 wheel, 1000g weight 73°F, 50% R.H. | 25.5 | 23.0 | 22.7 | 20.1 | 18.8 | 22.8 | |
| Water Absorption, % increase 24 hours, 73°F | 0.2-0.3 | 0.2-0.3 | 0.2-0.3 | 0.2-0.3 | 0.2-0.3 | 0.2-0.3 | D570-59T |
| **IMPACT STRENGTH** | **LL** Black Only | **L** | **H** | **GS** | **T** | **C** Black Only | **ASTM** |
| Izod Impact Strength ft. lb./inch notch | ⅛" bar[1] | ⅛" bar[2] | ⅛" bar[2] | ⅛" bar[2] | ⅛" bar[2] | ⅛" bar[2] | D256-56 Method A |
| Unnotched 73°F | >40.0 | 38.0 | 34.0 | >40.0 | 30.0 | 29.0 | |
| Notched 73°F | 7.5-9.5 | 6-8 | 5-7 | 4-6 | 3-5 | 4-5 | |
| −20°F | 4.5 | 3.0 | 2.0 | 2.3 | 1.4 | 0.9 | |
| −40°F | 2.5 | 2.0 | 1.5 | 1.5 | 1.0 | 0.7 | |
| Charpy Impact Strength[1] ft. lb./inch notch | ¼" bar[1] | ¼" bar[1] | ¼" bar[1] | ¼" bar[1] | ¼" bar[1] | ¼" bar[1] | D256-56 Method B |
| Unnotched 73°F | >40.0 | >40.0 | >40.0 | 33.0 | 26.5 | >40.0 | |
| Notched 73°F | 7.5 | 6.2 | 4.9 | 4.0 | 3.4 | 3.4 | |
| −20°F | 4.0 | 3.2 | 2.3 | 2.3 | 1.6 | 1.3 | |
| −40°F | 3.2 | 2.7 | 2.0 | 1.5 | 1.5 | 1.0 | |
| **THERMAL** | **LL** Black Only | **L** | **H** | **GS** | **T** | **C** Black Only | **ASTM** |
| Deflection Temperature[1], °F, 264 psi | 196 | 196 | 196 | 198 | 198 | 215 | |
| ½"x½"x5" bar 66 psi | 208 | 208 | 208 | 212 | 212 | 227 | D648-56 |
| (unannealed) Zero Load | 223 | 223 | 220 | 220 | 220 | 238 | |
| Deflection Temperature[1], °F 264 psi | 224 | 224 | 220 | 219 | 219 | 232 | |
| ½"x½"x5" bar 66 psi | 230 | 230 | 225 | 224 | 224 | 236 | |
| (annealed) Zero Load | 241 | 241 | 231 | 229 | 229 | 244 | |
| Coefficient of Linear Thermal Expansion[1], in/in/°C. | $10.1x10^{-5}$ | $10.1x10^{-5}$ | $10.4x10^{-5}$ | | $8.9x10^{-5}$ | $7.8x10^{-5}$ | D696-44 |
| Thermal Conductivity[1] | | | | | | | |
| Btu/hr./ft.²/°F/in. | 1.35 | 1.46 | 1.46 | | 1.54 | 1.80 | C177-45 |
| Cal/sec./cm²/°C/cm | $4.64x10^{-4}$ | $5.05x10^{-4}$ | $5.05x10^{-4}$ | | $5.30x10^{-4}$ | $6.20x10^{-4}$ | |
| Flammability[1], in/min ⅛" thick bar | 1-1.5 | 1-1.5 | 1-1.5 | 1.5-2.0 | 1-1.5 | 1-1.5 | D635-56T |
| Deformation under load[1], % 24 hr./122°F/2000 psi | 1.60 | 1.35 | 1.38 | | 0.81 | 0.41 | D621-59 |
| Mold Shrinkage[2], % | 0.5 | 0.5 | 0.5 | 0.5 | 0.5 | 0.5 | D955-51 |
| **ELECTRICAL** | **LL** Black Only | **L** | **H** | **GS** | **T** | **C** Black Only | **ASTM** |
| Dielectric Constant[1] | | | | | | | |
| 60 cycles | 3.20 | 2.86 | 2.87 | | 2.91 | 3.24 | D150-59T |
| $10^3$ cycles | 3.12 | 2.85 | 2.86 | | 2.91 | 3.21 | |
| $10^6$ cycles | 2.90 | 2.77 | 2.76 | | 2.44 | 3.11 | |
| Power Factor[1] | | | | | | | |
| 60 cycles | .005 | .005 | .005 | | .005 | .005 | D150-59T |
| $10^3$ cycles | .007 | .006 | .006 | | .006 | .006 | |
| $10^6$ cycles | .014 | .008 | .009 | | .008 | .012 | |
| Volume Resistivity[1], ohm-cm | $>3.54x10^{16}$ | $>3.92x10^{16}$ | $>3.80x10^{16}$ | | $>3.96x10^{16}$ | $>3.57x10^{16}$ | D257-58 |
| Arc Resistance[1], Sec | 50 | 71 | 71 | | 82 | 87 | D495-58T |

[1]Compression Molded

[2]Injection Molded

The results given are based upon tests which we believe to be reliable. Due to varying conditions and methods of processing, we cannot guarantee results to be obtained. Nothing contained in this brochure is intended as a recommendation to use our products so as to infringe on any patents.

# CYCOLAC®

## . . . the versatile plastic for use in applications from typewriters to refrigerator car door liners




### REMINGTON RAND FEATURES HOUSINGS OF CYCOLAC FOR STANDARD AND PORTABLE TYPEWRITERS . . .

Remington Rand wanted a superior material for the housing of their new standard and portable typewriters—one as advanced as the machine itself. The material had to be light in weight to make the typewriter easy to carry . . . stain-resistant . . . tough enough to resist cracking under impact . . . durable enough to withstand rough daily use in home or office . . . and economical to meet competitive prices. Remington Rand found what they wanted in CYCOLAC.

### CYCOLAC MAKES HISTORY! WORLD'S LARGEST VACUUM-FORMED PART USED FOR REFRIGERATOR CAR DOOR LINERS . . .

Giant door shells, vacuum-formed of CYCOLAC plastic, are now used on the Pacific Fruit Express mechanical refrigerator cars. The use of CYCOLAC in these cars—developed to transport frozen foods at low temperatures—clearly demonstrates the ability of this versatile plastic to resist the effect of impact at sub-zero temperatures. These doors, supplied by Landis Industrial Company, reduced the weight—another important consideration for the transportation industry. In addition, CYCOLAC provided manufacturing economies and excellent moisture resistance which protects the insulating material. In service, door liners of CYCOLAC stand up under the roughest conditions.




**MARBON CHEMICAL**
WASHINGTON


MARBON B·W CHEMICAL

DIVISION **BORG-WARNER**
WEST VIRGINIA

Printed in U.S.A.











# Data Sheet
# CAMPCO
## Thermoplastic Sheet and Film

Campco Sheet and Film has demonstrated exceptional quality and dependability in thousands of applications. The data which follows indicates the characteristics and qualities of each type, enabling you to match them with the requirements of your product. If further information is desired, we shall be glad to supply it.

### STYRENES

S-540 Styrene—Rubber modified rigid alloy. High impact strength and dimensional stability. Low moisture absorption, good heat resistance. Vacuum form. Gauges .010″ to .187″ stock or custom sheets. Colors, translucent or opaque. For display, toys, trays, packaging, housewares, luggage, housings, cabinets, tote boxes.

S-300 Styrene—Similar to S-540 but with greater rigidity. Good impact strength.

S-1029 Tripolymer Styrene—High impact, tensile and flexural strength at extreme temperatures. Excellent chemical resistance and dimensional stability, low moisture absorption. Forms easily, machines readily. In smooth or Haircell grain finish, gauges .020″ to .125″, many colors. For luggage, housings, chairs, ducts, exhaust hoods, clock cases.

### ACETATE

A-130 Cellulose Acetate—Strong and tough. Vacuum or pressure form. Machines well. In gauges .003″ to .060″ transparent, translucent, opaque, clear and colors. For blister packs, wraps, displays, toys, novelties, indoor signs.

### POLYETHYLENE

PE-200 Linear Polyethylene—Rigid, tough, heat and chemical resistant with good dielectric properties. Forms, machines, welds. Gauges .020″ to .125″ custom sheets and rolls. For housewares, containers, vessels, electrical products, toys, housing, packaging.

PE-100 Low Density Polyethylene—Low melt viscosity, excellent chemical and heat resistance. Stable under humidity changes. Vacuum form. Processes rapidly. In gauges .015″ to .125″ gloss finish custom sheets and rolls. For housewares, packaging, toys, containers, form liners, electronic applications.

### POLYPROPYLENE


PP-300 Polypropylene—Impervious to stress cracking. Excellent dielectric properties, chemical resistance, rigidity, strength. Heat resistant to 300° F. Low specific gravity. Gauges .010″ to .250″ custom sheets and rolls, variety of colors. For chemical ducts and vats, fittings, electrical parts, sterile items.

Campco engineers will gladly work with you on any problem involving the use of these materials. Write or phone today. There is no obligation.

**CAMPCO** division of
CHICAGO MOLDED PRODUCTS CORPORATION
2717-R Normandy Avenue, Chicago 36, Illinois • TUxedo 9-6200

◀ For more information, circle No. 444

▲ For more information, turn to Reader Service card, circle No. 398



Meet AviSun Polypropylene. The structure and molecular weight of this new thermoplastic can be tailored to make a variety of end products, including: hospital and laboratory ware; appliances; automotive and aircraft parts; housewares; toys; containers; closures; electrical items; fibers; rope and packaging film.

**LIGHTEST** of all plastics. Up to 50% more molded parts per pound.

**HIGHLY HEAT RESISTANT** . . . with a melting point of 330° to 340°.

**MOST RIGID** of the polyolefins, plus high surface gloss and abrasion resistance.

**EASY PROCESSING** by various means: injection molding, blow molding, extrusion, vacuum forming and film and sheet extrusion.

AVISUN*

## CHARACTERISTICS

**CHEMICAL** performance is excellent. End products are highly resistant to detergents and other stress cracking agents. The material resists most acids, including hydrochloric and sulphuric, as well as alkalies even at elevated temperatures. Resists gasoline, motor oils, foods, and plating, pickling and salt solutions. At high temperatures Polypropylene will swell in solvents such as toluene, carbon tetrachloride and also oxidizing acids. AviSun certifies that its polypropylene meets the conditions of F.D.A. regulation on the use of polypropylene for food packaging.

**MECHANICAL**—The stiffness modulus of polypropylene is greatest of all polyolefins, and puts polypropylene in the classification of "rigid" plastic materials. Retains strength and stiffness at elevated temperatures better than any competitive thermoplastic. Has high compressive strength and resistance to deformation at high temperatures. Toughness exceeds that of polystyrene at low temperatures. The tensile strength of Polypropylene is the highest of all the polyolefins. At normal test rates, molding grades will show elongations up to 500%.

**ELECTRICAL**—Being a nonpolar material it exhibits very low losses in alternating electrical fields. Its high heat distortion and softening temperature are ideal for many electrical uses. High volume resistivity and ease of extrusion make wire and cable insulation an important potential application. Its low dissipation factor makes it attractive for high frequency insulation. Low moisture absorption makes Polypropylene components electrically stable. Good mechanical and processing properties make the electrical characteristics even more desirable.

**PHYSICAL** — AviSun Polypropylene has a linear, ordered structure which can be highly crystalline. This "tailored" structure is reflected in its many unique properties. In addition, its chemical, mechanical and electrical behavior are generally improved over the known performance of other "isotactic" polyolefin structures. As the material becomes more highly crystalline, the tensile strength and modulus increase, but other qualities change somewhat as well. Therefore, AviSun Polypropylene has been formulated to an optimum balance of end properties.

**TECHNICAL ASSISTANCE**—AviSun Technical Specialists are at your service. They will answer your specific questions about AviSun Polypropylene . . . and help you plan better products at lower cost with this versatile new thermoplastic.

PHONE HUbbard 5-5831 or write

**AVISUN CORPORATION**

379 POST ROAD, MARCUS HOOK, PA.

*a trademark of AviSun Corporation

### SALES REPRESENTATIVES

**A. SCHULMAN, INC.**

**Akron** 9, Ohio, 790 E. Tallmadge Ave. HEmlock 4-4124

**Boston** 16, Mass., 738 Statler Bldg. LIberty 2-2717

**Chicago** 45, Ill., 2947-51 W. Touhy Ave. ROgers Park 1-5615

**East St. Louis,** Ill., P.O. Box 310, 14th & Converse Sts. UPton 5-2800

**Los Angeles** 5, Cal., Rm. 730, Texaco Bldg., 3350 Wilshire Blvd. DUnkirk 5-3018

**New York** 22, N.Y., 460 Park Ave. MUrray Hill 8-4774

For more information, circle No. 500



# Polypropylene

*the new thermoplastic . . . exciting new product opportunities!*

## PROPERTIES OF INJECTION MOLDING AND EXTRUSION GRADES

TABLE 1

**Typical Physical Property Values**

| *Property* | *A.S.T.M. Test Method* | *Units* | *Values* | |
|---|---|---|---|---|
| | | | *Extrusion Grade* | *Injection Molding Grade* |
| Tensile Yield Strength | D-638-58T (0.2 in./min.) | psi | 4700 | 4900 |
| Total Elongation | D-638-58T | % | 300 | 400 |
| Stiffness (flexural) | D-747-50 | $10^5$ psi | 1.8 | 1.8 |
| Izod Impact | D-256-56 | ft. lb./inch of notch | 1.3 | 0.8 |
| Hardness | | | | |
| Shore | D-676-55T | D | 74 | 74 |
| Rockwell | D-785-51 | R | 75 | 80 |
| Deformation under load—2000 psi, 122°F, 24 hrs. | D-621-51 | % | 3.2 | 3.2 |

TABLE 2

**Typical Physical Property Values for Both Grades**

| *Property* | *A.S.T.M. Test Method* | *Units* | *Values* |
|---|---|---|---|
| Form | — | — | ⅛" Pellets |
| Bulk Factor | D-1182-54 | — | 1.8 |
| Specific Gravity | D-792-50 Method A | — | 0.910-0.920 |
| Refractive Index | — | $n_D^{25}$ | 1.510 |
| Water Absorption | D-570-54T (24 hr. at 73°F) | % | nil |
| Heat Distortion | D-648-56 | °F | |
| 66 psi | — | | 240 |
| 264 psi | — | | 150 |
| Flammability | D-635-56T | | slow |
| Coefficient of Linear Thermal Expansion | D-696-44 | $10^{-5}$ in./°F | |
| | | 46 to 154°F | 6.7 |
| | | 97 to 205°F | 8.9 |
| Specific Heat | — | cal./°C/gram | 0.45 |
| Mold Shrinkage | — | in./in. | 0.010-0.025 |
| Environmental Stress Cracking | Bell Laboratory Method 100% Igepal | Years | >2 |

TABLE 3

**Typical Electrical Property Values for Both Grades**

| *Property* | *A.S.T.M. Method* | *Units* | *Values* |
|---|---|---|---|
| Power Factor | D-150-54T | | |
| at $10^2$ cycles | | | <0.0007 |
| at $10^3$ cycles | | | 0.0002 |
| at $10^6$ cycles | | | 0.0002 |
| Dielectric Constant | D-150-54T | | |
| at $10^2$ cycles | | | 2.3 |
| at $10^3$ cycles | | | 2.3 |
| at $10^6$ cycles | | | 2.1 |
| Dielectric Strength | D-149-55T (.032 in. thickness) | | |
| Short Term @ 73°F | | volts/mil | 1040 |
| Step by Step @ 73°F | | volts/mil | 950 |
| Volume Resistivity | D-257-57T | ohm-cm | $>3\times10^{15}$ |
| Surface Resistivity | D-257-49T | ohms | $>3.4\times10^{14}$ |

TABLE 4

**Typical Chemical Properties for Both Grades**

| *Chemical* | *% Weight Change After 30 Days Immersion @ 73°F* |
|---|---|
| Distilled Water | +0.015 |
| Inorganic Acids | |
| Sulfuric Acid 30% | +0.01 |
| Nitric Acid 10% | +0.013 |
| Hydrochloric Acid 10% | +0.013 |
| Organic Acids | |
| Acetic Acid 5% | +0.022 |
| Oleic Acid 93% | +0.04 |
| Citric Acid 10% | +0.02 |
| Alkalies | |
| Sodium Hydroxide 10% | +0.002 |
| Sodium Hydroxide 1% | +0.009 |
| Ammonium Hydroxide 10% | +0.03 |
| Sodium Carbonate 2% | +0.024 |
| Organic Solvents | |
| Ethyl Alcohol 95% | +0.048 |
| Ethyl Alcohol 50% | +0.027 |
| Acetone | +0.68 |
| Ethyl Acetate | +2.84 |
| Ethylene Dichloride | +7.84 |
| Carbon Tetrachloride | +30.0 |
| Toluene | +10.54 |
| Heptane (boiling point) | +11.01 |
| Phenol | +0.041 |
| Other | |
| NaCl Solution 10% | +0.02 |
| Hydrogen Peroxide 3% | +0.03 |

# Taylor Laminated Plastics and Taylorite Vulcanized Fibre

***Basic materials for electrical, electronic and mechanical applications***

***More than 50 grades to meet any requirement***

Take your pick from paper, cotton cloth, nylon, asbestos, glass cloth or other base material impregnated with phenolic, melamine, silicone or epoxy resins and formed into sheets, rods and tubes under heat and pressure.

There is one grade that will fit your exact requirements—whether you need good electrical insulation, great structural strength, resistance to chemical reaction, resistance to heat and flame, ease of fabrication, or a combination of these characteristics.

**Phenolic Laminates.** Thermosetting type. Paper, cotton fabric or mat, asbestos, glass cloth or nylon bases impregnated with phenol formaldehyde type resins. Provide dependable electrical insulation, have high dielectric and mechanical strength. Some grades are excellent basic materials for gears, cams, pinions, bearings and other mechanical applications. Asbestos grades are qualified as Class B insulation; others meet Class A requirements.

**Melamine Laminates.** Thermosetting type. Glass cloth or cotton fabric impregnated with melamine formaldehyde resin. These laminates have superior mechanical strength and are especially desirable for their arc resistant qualities. Good flame and heat resistance and good resistance to the corrosive effects of alkalis and most common solvents are other favorable characteristics. Classified as Class B insulation.

**Silicone Laminates.** Thermosetting type. Continuous filament woven glass fabric impregnated with a silicone resin. These laminates combine high heat resistance (up to 500°F., continuous) with excellent electrical and mechanical properties. Have low power factor and moisture absorption rate; very high insulation resistance and high arc resistance; excellent dimensional stability and high tensile, flexural and impact strength. Classified as Class H insulation.

**Epoxy Laminates.** Thermosetting type. Continuous filament woven glass fabric or paper impregnated with epoxy resin. Combine low moisture absorption with excellent chemical resistance and high mechanical strength. Characterized by good dielectric strength, low dielectric losses, and high insulation resistance even after being subjected to severe humidity conditions. Can be copper clad for production of high fidelity printed circuits.

**Copper-Clad Laminates.** Offer a combination of high-purity copper on superior base materials to produce printed circuits of consistently high quality. Taylor copper-clad laminates are available in several phenolic resin, paper base grades, in epoxy resin, paper or glass cloth base grades, and in specially formulated grades to meet specific requirements. All grades meet or exceed military and NEMA standards. The copper cladding is 99.5% pure and free of pinholes, pits and lead inclusions—has a high-quality finish that accepts all acid resists. All Taylor copper-clad laminates are supplied with 1, 2 or 3-oz. copper on one or both sides.

**Flame-Resistant Laminates.** Flame-retardant paper base laminates made with special phenolic resin. Have excellent moisture resistance, high electrical resistance and good mechanical properties. Offer low dielectric losses. Meet tentative Underwriters' Laboratory requirements for flame retardance.

## TAYLORITE VULCANIZED FIBRE

Taylorite Vulcanized Fibre is a hard, dense material with excellent physical, mechanical and electrical properties. It is tough and resilient; has high resistance to impact, abrasion, wear, organic solvents, oils and gasoline; can be machined, stamped, punched and formed; is attractive in appearance, light in weight. Available in a number of different grades, in sheets, rolls and turned rods: commercial, bone, electrical, trunk, superwhite, built-up, abrasive, flexible, track.

## ADVANCED MATERIALS DEVELOPMENT

Taylor's Advanced Materials Division is organized to research and develop vulcanized fibre and laminated plastics for application in rockets, missiles, jet aircraft, and nuclear reactors, to name a few. It is set up to work on R&D programs for other concerns too, and also for Government agencies. It will develop special materials for particular applications when required.

## ENGINEERING AND FABRICATING SERVICES

New applications for Taylor materials are constantly being developed by design and production engineers in the Taylor plants. These men are available for consultation. Their experience and counsel can help you in the development of your product. Taylor's fabricating division can economically produce parts from any of the above materials. Consult us for complete details on either one or both of these Taylor services. Technical engineering data on all these products available upon request. Write Taylor Fibre Co., Norristown 45, Pa.

**Taylor**

LAMINATED PLASTICS ■ VULCANIZED FIBRE

For more information, turn to Reader Service card, circle No. 478

For more information, circle No. 451 ➤

# Naugatuck PARACRIL OZO

THE OIL-RESISTANT, OZONE-RESISTANT NITRILE RUBBER



## ...tough, oil-proof, weather-proof and **colorful, too!**

The samples above should begin to give you some idea of the endless color possibilities in ozone-resistant rubber products made of new PARACRIL® OZO. Now you can give your product color that *sells*... color that identifies for coding wire and cable jacketing... color that blends or *contrasts*... color that works in a hundred ways. And you can give your product other superior properties, too.

Along with color, new weather-resistant PARACRIL OZO gives you a combination of high abrasion resistance, oil resistance, flex life and other valuable rubber properties far surpassing conventional weather-resistant rubbers.

Cast a new eye on the rubber product you make or buy. See the difference color makes. See your Naugatuck Chemical Representative or write the address below for full information on PARACRIL OZO and the advantages it offers.

**Naugatuck Chemical**

**Division of United States Rubber Company**

Dept. A Elm Street
Naugatuck, Connecticut

US RUBBER

Rubber Chemicals · Synthetic Rubber · Plastics · Agricultural Chemicals · Reclaimed Rubber · Latices · CANADA: Naugatuck Chemicals Division, Dominion Rubber Co., Ltd., Elmira, Ontario · CABLE: Rubexport, N.Y.

QUALITY Glidden PRODUCTS

# GLIDPOL
## POLYESTER RESINS

For Laminating, Impregnating, Molding, Casting and Protective Coating

**GENERAL CHARACTERISTICS**—The Glidpol polyester resins are basically solutions of linear polyester resins, produced by typical alkyd resin production methods, dissolved in solutions of reactive monomers. The linear polyesters are composed of mixtures of difunctional organic acids and alcohols. A certain portion of the acid component is made up of an unsaturated acid capable of reacting with the monomers and cross-linking adjacent polyester groups. Generally a higher concentration of unsaturated acid increases the unsaturation of the resin and gives a more reactive resin which is more rigid and less likely to deform at elevated temperatures.

**Liquid and Cured Properties**—The liquid resin properties vary depending on the process for which a particular product is designed. The principal differences in liquid characteristics are in viscosity—which can vary from a thin, watery consistency to a very thick or thixotropic state—and the particular curing characteristics depending on whether the material is designed to be cured at room temperature or in molds at temperatures as high as 300°F.

In the cured form, the resins differ in rigidity and hot strength and special characteristics which can be built in such as flame resistance, weathering resistance, chemical resistance, etc.

**Compounding**—In the majority of applications, Glidpol resins are compounded with a variety of reinforcing agents, granular fillers, and coloring pigments as required for the particular product being fabricated.

**Curing**—The Glidpol resins are cured by the addition of catalysts which are decomposed by heat or the addition of an accelerator to trigger the conversion of the resin to solid thermoset polymers which vary from flexible, rubber-like materials to rigid, tough solids. The resins are 100% reactive and give off no volatile by-products during cure, thus eliminating the necessity of venting or breathing the material during fabricating operations.

### WHICH GLIDPOL RESIN TO USE

It is usually difficult to select the resin most suitable for any given fabricating requirement on the basis of physical properties alone. Even with considerable experience in what liquid and cured properties are required for a particular fabricating procedure, actual trials are often required to make a final selection from several possible resins and to pin down specific catalysts, curing times, temperatures, etc. The following tabulation can be used as a guide in selecting Glidpol resins for specific applications. This tabulation includes formulations which have proven themselves to be most suitable for current fabricating procedures. Our Plastics Laboratory is continually working on improved formulation which will do a better job for standard and new fabricating procedures. Data sheets on individual resin systems are available.

### GLIDPOL POLYESTERS

| | 1001 | 1001-A | 1001-LS | 1008 | 1012 | 1017 | 1026 | 1027 | 1032 | 2002 |
|---|---|---|---|---|---|---|---|---|---|---|
| Liquid Properties | | | | | | | | | | |
| Styrene | X | X | X | X | X | X | X | X | X | X |
| Viscosity (1) | M | M | M | M | M | M | M | M | | L |
| Thixotropic | | | | | | | | | X | |
| Curing Characteristics | | | | | | | | | | |
| Preaccelerated for Room Temp. Cure | | | | | | | | | X | |
| Air Dry | | | Any with Glidpol 3305 added | | | | | | | |
| Cured Characteristics | | | | | | | | | | |
| Flexible | | | | | | | | | | X |
| Rigid | X | X | X | X | X | X | X | X | X | |
| High H.D.T. | | | | | X | X | | X | | |
| Light Stabilized | | | X | | | | | | | |
| Applications | | | | | | | | | | |
| Casting and Potting | X | X | | X | | | | | | X |
| Contact Molding | X | X | X | | | X | | | X | |
| Matched Die Molding | | | X | | X | X | X | | | |
| Premix Molding | | | | | X | X | X | X | | |
| Laminating | X | X | X | | X | X | | | | |
| MIL-R-7575A | X | | | | X | X | | | | |

(1) L – (low) 100-500 cps; M – (Medium) 500-3000 cps.

RESINS FOR EVERY APPLICATION

The Glidden Company
INDUSTRIAL PAINT DIVISION
900 Union Commerce Building • Cleveland 14, Ohio
In Canada: The Glidden Company, Ltd., Toronto, Ontario

There's a GLIDPOL Polyester Resin system plus Glidden Technical Service, to help you do it better, more economically, whatever your product, process or problem.

REGIONAL SALES OFFICES

Atlanta, Chicago, Cleveland, Los Angeles, Minneapolis, New Orleans, Reading, San Francisco, St. Louis

Canada: Toronto, Montreal

For more information, turn to Reader Service card, circle No. 540

For more information, circle No. 450 ➤

# 116 reasons why we can help you put your finger on the right plastic faster



**85** PHENOLITE® laminates...



**3** different thermoplastics...



**16** grades of Vulcanized Fibre...



**12** grades for printed circuits...

This will give you an idea of how surely National can help you pinpoint exactly the plastic you want. National has the broadest line in the industry, including standard forms, precision-fabricated parts, and a huge stock of many grades ready for immediate shipment. For fast help, samples, or more information, contact your nearby NVF sales office. You'll find the 'phone number in Sweet's Product Design File 2b/Na. Or write NVF, Dept. T, Wilmington, Del. It's a direct line to the one best material per dollar of design performance.

**NATIONAL**
VULCANIZED FIBRE CO.
WILMINGTON 99, DELAWARE
*In Canada:*
NATIONAL FIBRE COMPANY OF CANADA, LTD., Toronto 3, Ontario




# NEW FREE GUIDE TO SPONGE RUBBER

Have 13 different sponge-rubber samples at your fingertips, with full descriptions to aid in the selection of the finest sponge rubber for your next job. Light, flexible, and elastic, Kem-Blo is available in a variety of widths, compressions, thicknesses, shapes, and colors. It can be made to meet your exact specifications. For your free file-sized folder, for information on any sponge-rubber application, write U.S. Kem-Blo Department.

U.S. Kem-Blo® SPONGE

**United States Rubber**
Naugatuck, Connecticut

For more information, turn to Reader Service card, circle No. 572

get your own *SELECTOR* the easy way...

For only $3.00 you can get your own copy of M/DE's annual reference issue—the 1961 MATERIALS SELECTOR—plus 12 monthly issues of MATERIALS in Design Engineering.

• • •

You can see right now that M/DE's annual reference issue, the MATERIALS SELECTOR, is packed with the kind of reference data that makes selecting and specifying the right engineering materials, parts or finishes an easier, more efficient task for you. Remember, too, once you become a subscriber to M/DE you'll receive —every month—fast-reading, factual reports on important innovations and developments in metals, nonmetals, forms and finishes.

• • •

If you do not subscribe to MATERIALS in Design Engineering and want your own personal copy of the MATERIALS SELECTOR . . . fill in and mail the handy order card on page 583. We'll mail the MATERIALS SELECTOR to you, plus 12 monthly issues of MATERIALS in Design Engineering.

For more information, circle No. 382 ▶



# PLASTICS CHARACTERISTICS FROM CYANAMID

## CYMEL®

(THERMOSETTING) MELAMINE FORMALDEHYDE MOLDING COMPOUND

Cymel molding compounds fill a variety of industrial and consumer applications – all have basic properties of surface hardness; non-flammability; resistance to heat, boiling water and attack by solvents; color stability; lack of odor or taste, and good electrical properties – for compression, transfer or plunger molding. *Military and Federal specifications are listed on technical data sheets, available on request.*

**CYMEL 1077-1079** – alpha cellulose-filled – granular or powdered material available in extraordinary surface hardness – rich, lustrous look and feel – excellent chemical resistance – excellent electrical properties, including arc and track resistance . . . *dinnerware, buttons, electric mixer and shaver housings, closures, lighting fixtures.*

**CYMEL 592** – asbestos-filled – granular material, available in brown only – excellent arc resistance and dielectric strength at elevated temperatures – dimensional stability – resistance to atmospheric extremes . . . *electronic equipment, aircraft and automotive ignition parts, circuit breakers, terminal blocks, switch gears.*

**CYMEL 1500** – wood flour-filled – granular material, available in brown only – general purpose arc resistant electrical grade material – excellent dielectric strength . . . *watt-hour meter blocks, connector plug inserts, automotive ignition parts.*

**CYMEL 1502** – cellulose-filled – granular material, available in brown only – particularly good dimensional stability and dielectric strength – excellent insert retention . . . *connector plug inserts, circuit breakers, automotive ignition parts, watt-hour meter blocks.*

**CYMEL 3135** – glass fiber-filled – coarse-chopped material, natural color – electrical grade, high impact resistance – extraordinary flame resistance – arc resistant – low shrinkage and moisture absorption . . . *heavy duty switch gears, terminal strips and stand-off insulators, sockets and coil forms.*

**CYMEL 3136** – glass fiber-filled – granular material, natural color – electric grade material with intermediate strength – excellent arc and insulation resistance – extraordinary flame resistance – low shrinkage and moisture absorption . . . *terminal strips and stand-off insulators, sockets and coil forms.*

**CYMEL 3020** – cotton fabric-filled – chopped cotton, available in black only – electrical grade material with medium impact resistance – very good arc resistance, heat resistance and chemical resistance . . . *terminal strips, circuit breakers.*

**CYMEL 404** – unfilled – highly translucent, may be tinted before molding – high surface luster . . . *decorative moldings including buttons and jewelry findings.*



| | | tests and conditioning procedures[AA] | | Beetle alpha-urea | Cymel 1077-79 apha-mel. |
|---|---|---|---|---|---|
| | compression ratio (bulk factor) | loose-packed | | 2.5 | 2.1 |
| | tabletting | ——— | | excellent | excellent |
| | plasticity range | ——— | | v. soft—hard | soft—med. hard |
| | moldability in compression molds | ——— | | excellent | excellent |
| | compression molding temperature—°F | ——— | | 275—350 | 310—340 |
| | compression molding pressure—psi | ——— | | 2,000—8,000 | 1,500—6,000 |
| | moldability in transfer molds | ——— | | special type | good |
| | transfer molding temperature—°F | ——— | | | 300—320 |
| | transfer molding pressure—psi | ——— | | recommended | 4,000—12,000 |
| physical | shrinkage | D-955 | A | .006—.009 | .007—.009 |
| | additional shrinkage—48 hours at 220°F | D-1299 | A | .006—.012 | .006—.008 |
| | specific gravity | D-792 | A | 1.5 | 1.5 |
| | molded density—grams/cubic inch | | | 24.6 | 24.6 |
| | machining quality | | | good | good |
| | thermal coefficient of expansion—linear/°C | D-696 | A | 22-36x $10^{-6}$ | 20—57 x $10^{-6}$ |
| | thermal conductivity—cals/sq. cm/sec/°C/cm | C-177 | A | 10.1 x $10^{-4}$ | 10.1 x $10^{-4}$ |
| | heat distortion point at 264 psi—°F | D-648 | A | 266 | 410 |
| | heat resistance (¼" section—°F) | | | 170 | 210 |
| | flammability | | | self-exting. | self-exting. |
| | water absorption—24 hours at 25°C—% | D-570 | | 0.4—0.8 | 0.1—0.4 |
| | light—reflectance—% (.050" thick) | D-791 | | 45.8 | 53.6 |
| | transmission—% (.50" thick) | D-791 | | 39.4 | 29.9 |
| | resistance to sunlight | | | pastels grey | pastel yellow |
| | color possibilities | ——— | | unlimited | unlimited |
| | impact strength; 120D, milled—ft. lbs./in | D-256 | A | 0.24—0.28 | 0.25—0.27 |
| | compressive strength—psi | D-695 | A | 30,000—38,000 | 40,000—45,000 |
| | rockwell hardness | D-785 | A | E94—E97 | E110 |
| | shear strength (1" dia. slug)—psi | D-732 | | 11,000—12,000 | 11,000—12,000 |
| | flexural strength (¼" x ½" x 5" bar)—psi | D-790 | A | 11,000—18,000 | 10,000—15,000 |
| | deflection (¼" x ½" x 5" bar)—inches | D-790 | A | 0.103—0.157 | 0.107—0.162 |
| | modulus of elasticity—flexure—psi | D-790 | A | 1.4—1.5 x $10^6$ | 1.3 x $10^6$ |
| | modulus of elasticity—tension—psi | D-638 | A | 1.3 x 1.4 x $10^6$ | 1.35 x $10^6$ |
| | tensile strength—psi | D-638 | A | 5,500—7,000 | 7,000—8,000 |
| electrical | dielectric strength | | | | |
| | short time—volts/mil at 25°C | D-149 | A | 330—370 | 300—340 |
| | —volts/mil at 100°C | | A | 200—270 | 170—210 |
| | step by step—volts/mil at 25°C | D-149 | A | 220—250 | 250—290 |
| | —volts/mil at 100°C | | A | 110—150 | 90—130 |
| | slow rate of rise—volts/mil at 25°C | D-149 | A | 250—260 | 210—240 |
| | —volts/mil at 100°C | | A | 120—170 | 90—120 |
| | volume resistivity—ohms/cm | D-257 | C | 0.5—5.0 x $10^{13}$ | 0.8—2.0 x $10^{12}$ |
| | surface resistivity—ohms | D-257 | C | 0.4—3.0 x $10^{13}$ | 0.8—4.0 x $10^{11}$ |
| | insulation resistance | D-257 | C | 0.2—5.0 x $10^{10}$ | 1.0—4.0 x $10^{10}$ |
| | dielectric constant—60 cycles | D-150 | B | 7.7—7.9 | 8.4—9.4 |
| | —1,000,000 cycles | | B | 6.7—6.9 | 7.6—8.0 |
| | dissipation factor—60 cycles | D-150 | B | 0.034—0.043 | 0.052—0.083 |
| | —1,000,000 cycles | | B | 0.029—0.031 | 0.034—0.043 |
| | dielectric loss factor—60 cycles | D-150 | B | 0.28—0.34 | 0.44—0.78 |
| | —1,000,000 cycles | | B | 0.19—0.21 | 0.20—0.33 |
| | arc resistance—seconds | D-495 | A | 80—100 | 120—128 |
| | surface breakdown ratio | D-495 | A | 0.43—0.51 | 0.15—0.23 |
| chemical | gasoline (hi-oct)—7 days immersion at 25°C | D-543 | | 0 | 0 |
| | lubricating oil (SAE 20)—7 days at 105°C | D-543 | | 0 | 0 |
| | 1% $h_2so_4$—7 days immersion at 25°C | D-543 | | attack | 0 |
| | 1% naoh—7 days immersion at 25°C | D-543 | | discolors | 0 |
| | 1% naoh—8 hours immersion, boiling | D-543 | | attack | discolors |
| | 5% chromic acid—4 hours immersion at 25°C | D-543 | | attack | Sl. attack |
| | 10% citric acid—7 days immersion at 25°C | D-543 | | attack | 0 |
| | acetone—7 days immersion at 25°C | D-543 | | 0 | 0 |

note: the values above are obtained from laboratory prepared test pieces and may not be exactly reproducible in all cases in commercial practice

*water is 16.4 gms/cu. in.

^consult our technical department for details

properties

# BEETLE® and CYMEL®

CYANAMID

Molding Compounds

| Cymel 1500<br>wood fl.-mel. | Cymel 1502<br>alpha-mod. mel. | Cymel 3020<br>rag-mel. | Cymel 404<br>unfilled | Cymel 592<br>mineral-filled | Cymel 3135<br>glass-filled | Cymel 3136<br>glass-filled |
|---|---|---|---|---|---|---|
| 2.4<br>good | 2.7<br>good | 10 (5 packed)<br>hand only | 2.0<br>good | 2.4<br>excellent | 5-7<br>hand only | 3—4.5<br>good |
| 40—100 (extru)<br>excellent | 40—100 (extru)<br>excellent | medium<br>very good | medium<br>good | 50—100 (extru)<br>excellent | medium<br>good | medium<br>good |
| 310—330<br>1,500—6,000 | 300—330<br>1,500—6,000 | 300—340<br>4,000—8,000 | 300—340<br>2,000—5,000 | 270—340<br>1,000—6,000 | 290—310<br>4,000 | 290—320<br>2,000—8,000 |
| excellent<br>300—330 | excellent<br>300—330 | limited<br>——— | limited<br>——— | excellent<br>270—340 | good<br>290—310 | good<br>290—310 |
| 6,000—20,000 | 6,000—20,000 | ——— | ——— | 4,000—20,000 | 8,000—12,000 | 4,000—16,000 |
| .007—.008<br>.004—.007 | .006—.008<br>.001—.002 | .003—.004<br>.004—.008 | .010—.012<br>.007—.012 | .005—.007<br>.002—.003 | .002—.003<br>.002—.004 | .002—.004<br>.003—.005 |
| 1.48—1.52<br>23.8 | 1.43<br>23.5 | 1.5<br>24.6 | 1.48<br>24.3 | 1.78<br>29.2 | 1.94—2.00<br>31.8—32.8 | 1.94—2.00<br>31.8—32.8 |
| good<br>32—50 x $10^{-6}$ | good<br>34—36 x $10^{-6}$ | good<br>25 x $10^{-6}$ | ———<br>——— | fair<br>21—43 x $10^{-6}$ | poor<br>12—20 x $10^{-6}$ | poor<br>17—25 x $10^{-6}$ |
| 8.4 x $10^{-4}$ | ——— | 10.6 x $10^{-4}$ | ——— | 13.1 x $10^{-4}$ | ——— | ——— |
| 266<br>250 | 266<br>250 | 310<br>250 | 293<br>210 | 266<br>300 | 400<br>300 | 400<br>300 |
| self-exting.<br>0.34—0.6 | self-exting.<br>0.3—0.6 | self-exting.<br>0.3—0.6 | self-exting.<br>0.2—0.35 | self-exting.<br>0.13—0.15 | self-exting.<br>0.09—0.21 | self-exting.<br>0.1—0.3 |
| ———<br>——— | ———<br>——— | ———<br>——— | good<br>——— | ———<br>——— | ———<br>——— | ———<br>——— |
| fades<br>brown only | fades<br>brown only | black only<br>0.55—0.90 | good<br>limited | fades<br>brown only | good<br>natural | good<br>natural |
| 0.25—0.38<br>30,000—35,000 | 0.30—0.42<br>24,500—26,000 | 30,000—35,000 | 0.14<br>40,000—45,000 | 0.30—0.40<br>25,000—30,000 | 4.0—6.0<br>20,000—25,000 | 0.5—0.7<br>27,000—29,000[■■] |
| E94<br>10,000—10,500 | ———<br>11,500—12,000 | E100<br>12,000—14,000 | ———<br>——— | E90<br>7,000—8,000 | ———<br>——— | ———<br>——— |
| 6,500—9,000<br>0.081—0.120 | 9,000—12,000<br>0.091—0.103 | 12,000—15,000<br>0.033—0.132 | 9,500—13,000<br>0.105—0.142 | 7,400—10,000<br>0.051—0.067 | 16,400—24,000<br>0.060—0.072 | 13,200—17,400[■■]<br>——— |
| 1.0 x $10^{6}$<br>1.0 x $10^{6}$ | 1.1 x $10^{6}$<br>1.0 x $10^{6}$ | 1.4 x $10^{6}$<br>1.4 x $10^{6}$ | 1.0 x $10^{6}$<br>——— | 1.8 x $10^{6}$<br>1.95 x $10^{6}$ | 2.4 x $10^{6}$<br>——— | ———<br>——— |
| 5,700—6,500 | 5,500—6,500 | 8,000—10,000 | ——— | 5,500—6,500 | 5,800 | 5,000—5,900[■■] |
| 350—370<br>290—330 | 350—390<br>140—190 | 250—340<br>110—130 | 300<br>130 | 410—430<br>280—310 | 170—240<br>90—110 | 320—370 (23°C)[■■]<br>310—350 (50°C)[■■] |
| 200—240<br>190—210 | 200—250<br>90—100 | 220—240<br>60—90 | 240<br>80 | 280—300<br>190—210 | 170—220<br>60—80 | 170—270 (23°C)[■■]<br>150—250 (50°C)[■■] |
| 240—260<br>170—200 | 280—290<br>90 | 210—240<br>70—80 | ———<br>——— | 270—290<br>170—190 | 170—210<br>70—90 | ———<br>——— |
| 6.0—10.0 x $10^{12}$<br>0.3—5.0 x $10^{12}$ | 6 x $10^{10}$<br>1.7 x $10^{12}$ | 1.0—3.0 x $10^{11}$<br>0.7 x 7.0 x $10^{11}$ | ———<br>——— | 1.2 x $10^{12}$<br>1.9 x $10^{13}$ | 2 x $10^{11}$<br>3 x $10^{12}$ | 9.2 x $10^{10}$[■■]<br>4.6 x $10^{12}$[■■] |
| 1.0—3.0 x $10^{11}$ | 2.0—5.0 x $10^{9}$ | 0.1—3.0 x $10^{10}$ | ——— | 1.0—4.0 x $10^{10}$ | 0.2—2.0 x $10^{10}$ | 3—6 x $10^{4}$ |
| 6.4—6.6<br>5.6—5.8 | 7.0—7.7<br>5.2—6.0 | 8.1—12.6<br>6.7—6.9 | 7.9—11.0<br>6.3—7.3 | 10.0—10.2<br>5.3—6.1 | 9.7—11.1<br>6.6—7.5 | 7.2—7.0<br>6.9—7.9[■■] |
| 0.026—0.033<br>0.034—0.035 | 0.192<br>0.044—0.12 | 0.100—0.340<br>0.036—0.041 | 0.048—0.162<br>0.031—0.040 | 0.100<br>0.039—0.048 | 0.14—0.23<br>0.013—0.015 | ———<br>0.014—0.016 |
| 0.17—0.22<br>0.20—0.21 | 0.90—2.4<br>0.19—0.28 | 2.0—5.0<br>0.24—0.26 | ———<br>——— | 0.5—1.0<br>0.21—0.31 | 1.5—2.5<br>0.09—0.19 | ———<br>0.092[■■] |
| 70—106<br>0.15—0.19 | 90—120<br>0.15—0.25 | 122—128<br>0.15—0.23 | 121—123<br>——— | 120—180<br>0.12—0.22 | 180—186<br>0.14—0.22 | 180—186<br>——— |
| 0<br>V. Sl. attack | 0<br>V. Sl. attack | 0<br>0 | ———<br>——— | 0<br>V. Sl. attack | ———<br>——— | ———<br>——— |
| Sl. attack<br>V. Sl. attack | Sl. attack<br>V. Sl. attack | attack<br>0 | ———<br>——— | Sl. attack<br>V. Sl. attack | ———<br>——— | ———<br>——— |
| Sl. attack<br>attack | Sl. attack<br>attack | attack<br>attack | ———<br>——— | Sl. attack<br>attack | ———<br>——— | ———<br>——— |
| attack<br>V. Sl. attack | attack<br>V. Sl. attack | 0<br>0 | ———<br>——— | attack<br>V. Sl. attack | ———<br>——— | ———<br>——— |

[▲▲] tests are ASTM unless otherwise noted. Conditioning procedures follow ASTM D-618-58T
A—40 hours at 23°C, 50% RH. /B—48 hours at 50°C, desiccation at RT. /C—96 hours at 35°C, 90% RH.

[■■] mechanical and electrical properties for Cymel 3136 are determined according to Spec. MIL-M-14F.

# BEETLE®

(THERMOSETTING) UREA-FORMALDEHYDE ALPHA CELLULOSE-FILLED MOLDING COMPOUNDS

Beetle molding compounds produce marproof, lustrous moldings highly resistant to detergents, oils and greases – they are supplied in powder or granular form and various plasticities to meet specific molding needs in compression molding.

**BEETLE** is formulated to meet these specifications: Federal L-P-406b, LC 726-1, ASTM D705-55, Grade 1 (Arc resistance limits are in process of revision by ASTM). Characteristics: unlimited range of lustrous colors, smooth, hard surface, odorless and tasteless, stain-resistant, wear-resistant, arc-resistant, track-resistant, good dielectric strength, durable. Applications: radio cabinets, stove hardware, wiring devices, electric appliance housings, cosmetic containers, closures, buttons.

# LAMINAC®

POLYESTER RESINS

Laminac thermosetting resins vary in viscosity, rate of cure, degree of reactivity and degree of rigidity of the cured product – flexible or rigid laminates can be produced by the proper choice of resins – they are clear, nearly colorless liquids – when cured resist heat and chemicals.

**LAMINAC 4101** – medium viscosity, general purpose rigid resin developed for compression molding of reinforced trays, boxes, housings and similar products.

**LAMINAC 4103** – medium reactivity, resilient resin – ideal for hot-press molding of products required to withstand heavy mechanical abuse – boats, auto bodies and truck cabs.

**LAMINAC 4107** – high reactivity, medium viscosity resin – rigid and chemical resistant – suitable for fast high temperature molding as well as for other fabricating methods.

**LAMINAC 4110** – low viscosity – cures tack free at room temperature – for boats and prototypes.

**LAMINAC 4111** – low viscosity, highly reactive resin – maximum chemical resistance and excellent electrical properties – for storage containers, electric and electronic parts.

**LAMINAC 4116** – low reactive, general purpose resin – recommended for strength, rigidity and water resistance – for fishing rods, mannequins, radomes, castings (Laminac 4134 may be added for improved resilience).

**LAMINAC 4119** – formulated for resistance to mild chemical solutions at temperatures below 120° F – for tanks or storage containers.

**LAMINAC 4120** – fast curing, highly reactive, high viscosity resin – suitable for compounding with fillers and with color pastes for obtaining glossy resin rich surfaces.

**LAMINAC 4123** – intermediate reactivity, general purpose resin – medium viscosity, useful in either high or low temperature applications for suitcases, chairs, safety helmets.

**LAMINAC 4128** – low viscosity, highly reactive resin for hand lay-up or presswork – good hot strength – for aircraft accessories such as junction boxes, fuel tanks.

**LAMINAC 4131** – fast curing, excellent moldability – intended for compounding with fillers and fiber reinforcement for premix molding compounds – good fiber-wetting – low density – molded parts have good hot strength and good resilience.

**LAMINAC 4134** – low viscosity, flexible resin used in combination with rigid resins to improve impact and shock resistance.

**LAMINAC 4146** – for production of self-extinguishing fibrous glass reinforced laminates and moldings – for motor housings under continuous heat, aircraft parts, hot air ducts.

**LAMINAC 4151** – slightly thixotropic, low exotherm resin – for boat builders and other fabricators using hand lay-up techniques – non-sagging, excellent wet-out, fast curing.

**LAMINAC 4152** – slightly thixotropic, low exotherm, excellent wet-out, fast curing – comparable in performance to Laminac 4151 but formulated specifically for use with resin-fiber depositor spray guns.

**LAMINAC 4192** – for maximum resistance to discoloration on exposure to light – used for the production of flat or corrugated sheeting.

**LAMINAC 4202** – high viscosity liquid resin – unusually long catalysed stability – odor free – cures at temperatures above 200°F – for large radomes and aircraft shelters.

**LAMINAC 4232** – exceptionally stable at elevated temperatures when properly cured – for production of critical parts that are required to retain strength at high temperatures.


**LAMINAC 4233** – similar in characteristics to 4232 plus self-extinguishing properties.

CYANAMID

**AMERICAN CYANAMID COMPANY** • PLASTICS AND RESINS DIVISION

SOUTH CHERRY STREET • WALLINGFORD, CONN. OFFICES IN: BOSTON • CHARLOTTE CHICAGO • CINCINNATI • CLEVELAND • DALLAS • DETROIT • LOS ANGELES MINNEAPOLIS • NEW YORK • OAKLAND • PHILADELPHIA • ST. LOUIS • SEATTLE

IN CANADA: CYANAMID OF CANADA LIMITED, MONTREAL AND TORONTO



**A Spaulding before and after**

One Spaulding part replaced 10 individual parts in this assembly. Production and assembly time were reduced, cost and weight were cut by 50%.

## NOW IT'S CALLED VALUE ANALYSIS

As any Spaulding customer can tell you, the only thing new about Value Analysis is the name.

Spaulding has been rendering this service for years with engineers who evaluate a part or assembly, then show how it can be made better, easier and at a lower cost with a Spaulding Material, processed by Spaulding's own Fabricating Department.

The unique characteristics of Spaulding Industrial Plastics and Vulcanized Fibre hold the same advantages for *your* product.

SPAULDING FIBRE COMPANY, INC.

377 Wheeler Street, Tonawanda, New York



free **Value Analysis Brochure.** Send for your copy now.

**SPAULDING FIBRE COMPANY, INC.**
377 Wheeler Street
Tonawanda, New York

Please send a free copy of the brochure, "Spaulding Value Analysis."

Name .....

Firm .....

Address .....

City ..... Zone ..... State .....

◀ For more information, circle No. 382

▲ For more information, turn to Reader Service card, circle No. 468




# Superior Electrical and Mechanical Properties—at Lower Costs!

Glastic fiber glass reinforced polyester offers strength, dimensional stability, arc resistance, flame retardance, low moisture absorption—in the combination of properties you require.

Glastic is engineered for use in equipment operating at 130°-150°C and higher. Full design utilization of its superior physical, thermal and electrical properties will result in substantial savings. Glastic is available in a number of forms:

**LAMINATES.** Glastic flat sheet stock offers improved properties over cellulosic reinforced plastics, generally at lower material and fabrication costs. 14 rigid and flexible grades.

**CUSTOM MOLDED PARTS,** made to your specifications, utilize Glastic's high strength, permitting thinner wall sections. Less material is required; parts are more compact, lighter, frequently less expensive.

**PREMIX MOLDING COMPOUND,** supplied to your molder, offers you the property and cost advantages of Glastic in parts produced by your present supplier.

**STRUCTURAL INSULATING SHAPES,** as illustrated below.

Investigate the ways Glastic can be used to improve your product . . . send for samples and technical data on Glastic products of specific interest.

**THE GLASTIC® CORPORATION**
4321 Glenridge Road • Cleveland 21, Ohio


For more information, turn to Reader Service card, circle No. 423

**CHANNEL/ANGLE STOCK,** in 12 sizes, serves as product-improving replacements for heavier or more expensive forms. Ideal for barrier ends, transformer corners, bus supports, component mountings, raceways, etc. UL-recognized flame retardance.

**INSULATING ROD STOCK,** in 24 round, square and rectangular sizes plus 9 special shapes. Exceptionally strong. Easily fabricated for use in push rods, actuating linkages, clamping blocks, tie bars, spacing sticks, etc.


**INSULATORS,** in 13 low cost models with choice of thread sizes. Dimensional tolerances and impact strength superior to porcelain . . . moisture resistance and arc resistance greater than phenolic. Heights from 1⅛". UL-recognized flame retardance.

**U-WEDGES,** in 11 sizes, for retaining stator windings in motors. Much stronger and easier to drive than wood or fibre wedges, and space-saving design allows greater coil cross-section. Full Class B electrical insulation.



# Know the Design Advantages of these Plastics


***(You'll profit by keeping up to date)***




**POLYETHYLENES:** Light weight with strength. This 100 ft. coil of 2-in. polyethylene pipe is easily supported by one man. Flexible and rigid polyethylenes each have outstanding physical, chemical and electrical properties. Gas permeability and a broad range of colors make polyethylene film ideal for packaging.




**EPOXIES:** With its coils embedded in epoxy, this motor is running under water. The strongest and hardest of plastics, epoxies are ideal for industrial coatings and reinforced laminations, including medium-to-long-run tools and dies. They are extremely tenacious when used as adhesives.



**PHENOLICS:** These electrical parts illustrate one of the long-time uses for phenolic plastics. Strong and durable, phenolics are also molded into washing machine agitators, furniture drawers, bottle caps . . . They are also excellent for chemical-resistant coatings and industrial or decorative laminates.



**STYRENES:** Television masks like these exhibit the superior eye-appeal of styrenes. A range of impact strengths, brilliant colors, and gleaming finish broaden the design applications of these materials. Molded and extruded, styrenes find use as refrigerator door liners, toys, packages, and housewares.



**VINYLS:** This flexible printed circuit has copper conductors laminated between layers of vinyl sheeting. Vinyls combine electrical resistance, formability, color, and elastomeric qualities. Tough, handsome vinyls can be fabricated into flexible or rigid film and sheeting. Inflatables, swimming pool liners, packaging, and wire insulation are important uses.

**Get more detailed information about these design materials now. Mail the coupon for your "1961 Materials and Data Guide" to BAKELITE Brand Plastics. For specific technical assistance just write or call any of our offices, outlining your problem.**



UNION CARBIDE

Dept. DY-85
Union Carbide Plastics Company
270 Park Avenue, New York 17, N.Y.

Please send me the 1961 Materials and Data Guide to BAKELITE Brand Plastics

NAME _____

FIRM NAME _____

ADDRESS _____

CITY _____ STATE _____

"Bakelite" and "Union Carbide" are registered trade-marks of Union Carbide Corporation

**For more information, turn to Reader Service card. circle No. 544**

# SCOTCHPLY®

**BRAND REINFORCED PLASTIC**



***ROTATING STRESS LOADS*** **are constantly changing on the modulus balancing cheek plate (indicated in blue) of this helicopter rotor by Kaman Aircraft. "SCOTCHPLY" is the only structural material tested that satisfied all requirements. Plies are oriented to meet the tension, bending and torsion strains developed in the blades.**

**Modulus of elasticity taken in the lengthwise direction and crosswise direction for several laminate orientations are shown below. Any intermediate ratios may be obtained as "SCOTCHPLY" can be tailored to meet specific stress requirements.**




Cross-hatching indicates filament orientation

# STRENGTH-TO-WEIGHT RATIO TOPS ALL STRUCTURAL MATERIALS

***Strength/weight and other exclusive properties result from customized orientation of continuous, non-woven glass filaments****

What's the big difference between "SCOTCHPLY" and other pre-impregnated reinforced plastics? Only "SCOTCHPLY" BRAND Reinforced Plastic has continuous, non-woven glass filament* reinforcement.

Here are the superior properties that result:

★ ***UNMATCHED INDIVIDUAL PLY STRENGTH***—each ply consists of *continuous straight* filaments in parallel alignment, not crimped or woven.

★ ***HIGHEST DEGREE OF TAILORABILITY***—individual plies may be oriented to meet specific stress requirements; reinforcement (weight and bulk) is not wasted in directions or regions of low stress. This *degree* of tailorability is not possible with other reinforced plastics using woven cloth or short strand reinforcement.

This duo of exclusive advantages combines to give "SCOTCHPLY" an unequalled strength-to-weight ratio and superior fatigue properties.

Sold in uncured rolls or sheets, "SCOTCHPLY" Reinforced Plastic is a moldable, laminated plastic consisting of a mechanically controlled ratio of resin to reinforcement*. Heat and low pressure in matched metal dies, vacuum or pressure-bag molding cure it into rigid form.

For complete information and technical service, write on your letterhead to Dept. XAB-110. Reinforced Plastics Division, 3M Co., 1210 University Ave., St. Paul 4, Minn.


**Other available filaments: nylon, asbestos and other ablation materials. Epoxy, phenolic and other resin systems are available.*


See Sweets Product Design File insert 2a. Mi



***EXTREMELY HIGH TENSILE STRENGTH*** and light weight are essential in this battery case by Prewitt Aircraft for a classified missile. By proper orientation of reinforcing filaments, "SCOTCHPLY" provides maximum strength where strength is needed to withstand tremendous acceleration loads.


**Tensile strength-weight ratios**



***FLEXURAL FATIGUE*** failure of metal Fourdrinier springs resulted in costly breakdowns on this paper machine manufactured by Rice Barton Corporation. Now Fourdrinier springs of "SCOTCHPLY"—tailored to the application—do the job.

**Flexural-fatigue strength @ 2 x 10⁶ cycles**




"SCOTCHPLY" IS A REGISTERED TRADEMARK OF THE 3M CO., ST. PAUL 6, MINN. EXPORT: 99 PARK AVE., NEW YORK 16, N.Y. CANADA: LONDON, ONTARIO

**MINNESOTA MINING AND MANUFACTURING COMPANY**
**...WHERE RESEARCH IS THE KEY TO TOMORROW**

3M COMPANY

For more information, turn to Reader Service card, circle No. 533

Phone
Keystone 7-7754

**Chemfoam®**

TOYAD CORP, LATROBE, PA.

**Cellular Rubber & Plastics**

CUSTOM MOLDING—STOCK SHEETS

★ Neoprene
★ SBR-NBR
★ Polymer-Latex
★ Hypalon
★ Silicone
★ Adhesives—Coatings
★ Polystyrene
★ Polyurethane
★ Polyvinyl Chloride
★ Polyethylene

Phone or Write TOYAD CORP.
Plant Avenue, LATROBE, PA.

For more information, turn to Reader Service card, circle No. 480

*Expert information to solve your corrosion problems!*

**Protective Coatings for Metals**
**SECOND EDITION**

by R. M. BURNS, formerly Director of Chemical and Metallurgical Research, and W. W. BRADLEY, Technical Staff, both of Bell Telephone Laboratories, Murray Hill, New Jersey

*ACS Monograph No. 129* • *1955, 657 pages, $12.50*




Now completely revised, enlarged, and brought up to date, this important new edition contains latest information on the composition, properties and performance of both metallic and organic coatings.

Completely new chapters are devoted to inhibitors, chemical conversion coatings and sprayed metal coatings. Newly experienced troublesome phenomena known as "silver migration" and "metallic whiskers" are fully discussed, and latest practices in metal cleaning, coating application and coating testing are explained.

No other book on the subject so fully meets the needs of corrosion and construction engineers, metallurgists and chemists. Everyone concerned with the use and performance of coatings will find this monograph of utmost value.

• **CONTENTS:** Principles of Corrosion and Corrosion Control; Surface Preparation for Coatings; Types of Metallic Coatings and Methods of Application; Sprayed Metal Coatings; Production and Properties of Zinc Coatings; Protective Value of Zinc Coatings; Cadmium Coatings and Their Protective Value; Tin Coatings; Nickel and Chromium Coatings; Coatings of Copper, Lead, Aluminum, Miscellaneous Metals and Alloys; Coatings of Noble and Rare Metals; Methods of Testing Metallic Coatings; Organic Coatings—Chemistry and Composition; Organic Coatings—Performance and Evaluation; Application and Use of Protective Organic Coatings; Chemical Conversion and Anodized Coatings; Special-Purpose Coatings; Corrosion Inhibitors.

*Send now for your* ON-APPROVAL *copy*

**REINHOLD PUBLISHING CORPORATION**

Dept. M-705 • 430 Park Ave. • New York 22, N. Y.

## SUPPLIERS' LITERATURE

### Plastics and Rubber

*cont'd from p 186*

cifications for sheets, rods, tubes, hose and bearings made from TFE, Raylon, and Kel-F. **98**

**Reinforced TFE.** Rogers Corp., 10 pp. Physical and electrical properties, wear, chemical and heat resistance, and uses for reinforced TFE backup rings, sheets, rods and tubes. **99**

**Laminated Plastics.** Panelyte Div., St. Regis Paper Co., 19 pp, illus., No. 1-d-PA. Industrial, chemical and decorative applications of Panelyte laminated plastics. **100**

**Vulcanized Fibre.** Spaulding Fibre Co., Inc., 40 pp, illus. Available grades, physical and mechanical properties, sizes and typical applications of vulcanized fibre sheet, rod and tubes. Also included is information on copper clad laminates, standard plastics laminates, and other materials. **101**

**Stretched Acrylic.** Swedlow, Inc., Western Contracts Dept., 6 pp, illus., No. Y. General information, technical data, uses, and other information on stretched acrylic glazing material for high speed aircraft. **102**

**High Temperature Laminates.** Synthane Corp., 2 pp. General description, availability and properties of two high temperature industrial plastics laminates. **103**

**Laminated Plastics Selection Guide.** Taylor Fibre Co., 18 pp. Information on what laminates are, how they differ from other plastics, what materials are used, standard thicknesses and tolerances, and other data necessary for specifying and ordering high pressure plastics laminates. Included is a property chart on mechanical, electrical, and general purpose grades. **104**

**Cellular Products.** Toyad Corp. Series of technical bulletins and brochures give general descriptions, properties, characteristics, and typical uses of a line of flexible and rigid cellular products. **105**

**Silicones for Shell Molding.** Union Carbide Corp., Silicones Div., 4 pp, No. SF-1128. Properties of three silicone parting agents used in shell molding. **106**

**Polystyrene Molding Compounds.** Union Carbide Plastics Co., Div. of Union Carbide Corp., 16 pp, illus., Vol. 5, No. 1. Technical data and applications of four impact polystyrene molding compounds. **107**

**Synthetic Rubber.** Naugatuck Chemical Co., Div. of United States Rubber Co., 12 pp, No. 219. Compounding information, physical properties, oil and ozone resistance, and uses of a vinyl modified synthetic rubber called Paracril OZO. **108**

**Mechanical Rubber Goods.** Williams-Bowman Rubber Co., 6 pp, illus. Information on the services and facilities available for the production of mechanical rubber goods. **109**

# ROGERS FIBERLOYS®

**Rogers Fiberloys are fiber-polymer "alloys". The basic grades described below indicate the range of materials available for your requirements.**

## MATERIALS FOR ELECTRICAL INSULATION


| Material | General Description | Outstanding Properties | Fabricating Methods | Application Considerations |
|---|---|---|---|---|
| **ELECTRICAL TRANSFORMER (AND MOTOR) INSULATION** | Cellulose fiber materials produced in 60" x 120" sheets and in rolls, in gauges from .007" to 3". | Exceptionally pure, with uniform dielectric characteristics. Tough, homogeneous — long the standard insulating materials for transformers and motors. | Sheet sizes are standardized for assembly into transformers. Strips can be supplied or cut for blanking into small insulating parts. Rolls for automated operation. | Standard insulation for transformers, electric motors and other electrical equipment. |
| **DUROID 100, 225, 700 SERIES** | Fibrous insulating materials — U. L. recognized — produced in 60" x 66" sheets in gauges .031" to 3". | Arc resistance and dielectric strength equal to XP paper-base laminates. Retains dielectric strength under high humidity. | Parts can be formed or blanked on power presses, using steel rule or compound dies. | General purpose insulating materials. Used frequently in place of paper-base laminates where moisture pick up is not critical. |
| **DUROID 800** | Fibrous insulating material recognized by U. L. for sole support of current carrying parts. 60" x 66" sheets in gauges .031" to 3". | Rigid, springy material, with water absorption of less than 25% per 24-hour immersion. Excellent physical wet strength. | Flat punching, using compound or steel rule dies. Formable before curing. | Recommended for flat punched insulators as replacement for laminated phenolic. |
| **DUROID 5600 SERIES** | Teflon reinforced with ceramic fibers to form homogeneous sheet, rod or tube. | Electrical properties of Teflon but with much greater resistance to cold flow and heat distortion. | Blanking and punching on power presses, using steel rule or compound dies. Machined or molded parts. | Recommended for applications which require Teflon's electrical properties with improved resistance to heat and cold flow. |
| **DUROID 5800 SERIES** | Teflon reinforced by encapsulated glass micro fibers. Available as flat sheets, rods, tubes and copper-clad sheet. | Uniform electrical properties; lower coefficient of expansion than Teflon; no wicking effect. Copper-clad sheet has high bond strength. | Flat sheets readily punched. Rod and tube feature excellent machinability. | Primarily for high temperature dielectric use as circuit base stock, micro-wave strip or plumbing, missile antennae windows. |
| **RX PHENOLIC MOLDING COMPOUNDS** | Wide range of materials in medium to high impact grades. Uniform pellet size and rate of pour. Some formulations also in sheet form. | Low bulk factor, fast rate of cure. Combine impact strength with flexural strength. Clean, dust-free. Quality controlled for high-speed production. | Can be automatically preformed, compression or transfer molded on automatic equipment. | For high strength complex or simple components. (Grades can be supplied to meet special physical, molding or flame-resistant requirements.) |
| **RX DIALLYL PHTHALATE MOLDING COMPOUNDS** | Molding compounds of Diallyl Phthalate reinforced with mineral, glass or synthetic fibers and fillers. | Superior electrical properties even after exposure to humidity. Excellent dimensional stability and chemical resistance. | Conventional compression or transfer molding equipment. Outstanding moldability. | Electronic uses such as connectors, terminal boards, missile components. Also electric power connectors, switch parts. |
| **DUROID 2100 SERIES** | Orlon fibers bonded with acrylic resin. Supplied in 13" wide rolls, in gauges from .010" to .030". | Exceptional electrical properties combined with resistance to freon-oil mixtures. | Blanking and punching on power presses, using steel rule or compound dies. | In hermetic systems for freon-oil resistant motor slot liners, wedges, phase separators. |

**For technical data, please specify materials in which you are interested.**

## ROGERS CORPORATION ROGERS, CONNECTICUT

**PLANTS IN ROGERS, MANCHESTER AND WILLIMANTIC, CONN.**

**For more information, turn to Reader Service card, circle No. 516**




ATLAC 382 is a special bis-phenol polyester which retains a higher percentage of original strength than general purpose polyester and isophthalic resins, under a broad range of corrosive conditions. ATLAC 382 offers superior performance in the construction of corrosion resistant equipment such as storage tanks, processing tanks, fume ducts and hoods. The table shows test data in typical corrosive media.

**CORROSION RESISTANCE: 6 MONTH TESTS OF CAST RESIN**

| Corrosive Agent (210°F.) | % retention of flexural strength | | |
|---|---|---|---|
| | General Purpose Polyester | Isophthalic Resin | ATLAC 382 |
| 15% HCl | Failed | 6% | 64% |
| 5% NaOH | Failed | Failed | 60% |
| 5% Hypochlorite | Failed | 11% | 59% |
| Water | 9% | 13% | 79% |

**LITERATURE AVAILABLE**

We'll be glad to send you the following:

**Detailed test reports** of performance in various corrosive agents.

**Case histories** of use of ATLAC 382 in actual service.

*U.S. Patent No. 2,634,251.

**Thermaflow® High Strength Reinforced Polyester Molding Compounds**

New opportunities for design and fabrication of high strength, light weight molded parts exist with these compounds. All are readily molded on standard compression or transfer presses.

**LITERATURE AVAILABLE**

Write today for:

**Catalog** of the Thermaflow line.

**Case Histories** demonstrating improved performance and cost reductions in switchgear, transformer and other electrical components; pumps and valves; housings; appliance components; and many other molded parts.

Chemicals Division
**ATLAS POWDER COMPANY**
Wilmington 99, Delaware

For more information, turn to Reader Service card, circle No. 388

# Swedlow specializes in heat protection!

*Silicones*
*Phenolics*
*Epoxies*
*Reflective coatings*
*Sheet materials*
*Molded parts*
*Flexible flame-resistant coatings*

### *Swedlow's aluminum-metallized heat reflective laminates* 1650°F



MINIMUM WEIGHT • MINIMUM BULK—By combining the principles of highly efficient reflectivity of aluminum-metallized surfaces with the low thermal conductivity of glass fabric reinforced plastic laminates, Swedlow's "—101" metallized coatings offer protection up to 1650° F. The metallic coating protects the base laminate from thermal degradation.

APPLICATIONS—In flat sheets, or molded into complex contours, these materials are suggested as highly efficient heat blankets for compartment insulation, valve protection, exhaust heat damping, and other applications where there is prolonged high temperature exposure.

### *Swedlow's silicone plastic laminates* 650°F



Swedlow's X5G-138 and X5G-176 silicone base materials are available as flat sheeting or molded parts and offer protection up to 650°F.

Swedlow's X5G-138 provides maximum strength per unit of thickness and weight and is recommended for applications requiring flat sheets or simple contoured molded parts.

The X5G-176 laminate has slightly lower physical properties than X5G-138 but is recommended for applications requiring complex contours.

APPLICATIONS—Missile nose cones, exit cones, fins, stabilizers, adapter rings, closure rings, and similar uses. Applications in airstreams at missile speeds are possible.

### *Dyna-Therm 65—flexible flame-resistant coating* 6000°F



A "major breakthrough"—insulation which can be applied easily in the field for protection of launching equipment from rocket flame and blast. It affords major dollar savings by protecting expensive cables and equipment through successive firings. It promises greatly reduced pad refurbishment time with resultant faster refire capability. It may be sprayed or applied with ordinary paint brush. Cures quickly at ambient temperatures. Intumesces under hot flame to develop full insulating capability, but remains flexible. Charred surface can be scraped away leaving undersurface ready for recoating. Field test indicates serviceability up to 6000°F.

APPLICATIONS—Neoprene cables, electrical connectors, metal and plastic instrumentation housings, piping and general structure, including blast deflectors. Flight applications as well as ground support installations.

### 600°F *Swedlow's high temperature phenolic plastic laminates*



STABLE PHYSICAL PROPERTIES UNDER HIGH TEMPERATURES—Swedlow's X4G-116 is a high-temperature phenolic laminate that offers unusual physical stability at high temperatures up to 600°F. It is available in flat sheets, and can be molded to complex contours.

APPLICATIONS—Fins, stabilizers, missile nose cones, adapter rings, closure rings, and similar applications. May be used in airstreams at missile speeds.

### 450°F *Swedlow's epoxy-plastic laminate*



Swedlow's X6G-141 epoxy-plastic laminate gives the user an electrical insulating material resistant to fracture and warpage in installation, with characteristics of very low moisture absorption and high physical strengths over a prolonged temperature gradient. Approved under MIL-P-18177. Conforms to NEMA standards for type G-3 materials.

APPLICATIONS—Air conditioning and heat distribution ducts. Winding barriers and ducting in transformers. Sheeting for circuitry installations. Dielectric capacitors for condensers. Terminal board and strip applications in electronic equipment. Coil spacers and relay bases in magnetic devices. Mounting plates, contact spacers and shielding for control devices.

**Temperatures shown may be raised appreciably for short periods.**

Swedlow provides the insight to solve challenging problems of design and producibility of advanced materials—in laminates, complex shapes, difficult parts. Write for full information, Dept. Q6


Swedlow

SWEDLOW Inc.
LOS ANGELES 22, CALIFORNIA
YOUNGSTOWN 2, OHIO

**For more information, turn to Reader Service card, circle No. 470**


# heat problems?

# Five reasons why so many designers select



## It's an insulator

The Thermal Conductivity (K Factor) of DYLITE is 0.242 at a 75°F. mean temperature at 2 lb./cu.ft. density. DYLITE resists heat, is unaffected by moisture condensate. Cooler chests molded of DYLITE keep food and beverages cold for days without ice refill. DYLITE is easily molded to fit contours of component parts of refrigerators, air conditioners and freezer cabinets.



## It's waterproof

At 2 lb./cu.ft. density, DYLITE's rate of Water Vapor Transmission is 1.18 perms., and its rate of Water Absorption is 0.54 lbs./cu.ft. after 48 hrs. immersion. DYLITE is ideal for boats, rafts, buoys and other types of buoyant marine equipment. DYLITE remains in the water indefinitely without becoming water logged, and it is mildew-proof.



## It's shock-resistant

DYLITE possesses an Energy Absorption ratio (Maximum Load) of 56.74 in. lbs./cu.in. at a density of 2 lb./cu.ft. For example, Royal electric typewriters are now shipped in shock-absorbent DYLITE packages—a result of performance tests in which DYLITE was proved superior to other materials for this job.







TYPICAL PROPERTIES OF DYLITE EXPANDABLE POLYSTYRENE—DENSITY 2 LB./CU.FT.

• Compressive Strength—30 Psi • Tensile Strength—55 Psi • Water Vapor Transmission—1.18 Perms.
• Water Absorption—0.54 Lbs./Cu.Ft. • Thermal Conductivity (K Factor)—0.242 at a 75°F. Mean Temperature
• Energy Absorption (Maximum Load)—56.74 In.Lbs./Cu.In.

DYLITE is a registered trademark of Koppers Company, Inc.

DYLENE® polystyrene, SUPER DYLAN® polyethylene and DYLAN® polyethylene are other fine plastics produced by Koppers Company, Inc.

Offices in Principal Cities • In Canada: Dominion Anilines and Chemicals Ltd., Toronto, Ontario

# DYLITE® expandable polystyrene



## It's lightweight

DYLITE is lighter than cork—it can be molded in densities of 1 to 10 lb./cu.ft. The advantages of light weight are obvious. In packaging, DYLITE helps reduce shipping costs and makes handling easier. In the construction field, where DYLITE is used as an insulator, its light weight means fast and easy installation.




## It's strong

DYLITE has a Compressive Strength of 30 psi and a Tensile Strength of 55 psi at a 2 lb./cu.ft. density. DYLITE can be used to great advantage in a wide variety of industrial design problems. For instance, sandwich structures that employ DYLITE as the core material offer high strength without sacrificing light weight.





... if you would like more information about versatile DYLITE expandable polystyrene, write for this free booklet.




Koppers Company, Inc.
Plastics Division
Dept. MDE 110,
Pittsburgh 19, Pa.

KOPPERS

For more information, turn to Reader Service card, circle No. 546

# ENJAY BUTYL

## *IS TOPS IN ALL-'ROUND*





### RESISTANCE TO CHEMICALS

Enjay Butyl, because of its unique and extremely low degree of unsaturation, offers excellent resistance to corrosive chemicals. The preferred rubber for tank linings, hose, seals, gaskets and other applications where exacting chemical resistance is required.



### VIVID COLORS

Enjay Butyl requires no additives for quality coloring over a wide range of hues. Famous for colorability and smooth finishes, Butyl has been successfully plastic coated for special applications.

### RESISTANCE TO TEAR AND ABRASION

Enjay Butyl offers the highest aged tear strength of any rubber . . . even after long exposure to ozone and heat! Its inherent toughness resists abrasive wear, in such applications as tires, conveyer belts, hose and other mechanical goods.

### RESISTANCE TO SUN-LIGHT AND WEATHERING

Enjay Butyl has proven its resistance to ultra-violet light, ozone, oxidation, moisture and mildew. Increases life of products such as weatherstrips, garden hose, wading pools and automotive parts.



# RUBBER

## *PERFORMANCE*



### DAMPING PROPERTIES

Enjay Butyl absorbs shock and vibrational energy more completely than any other rubber. Resiliency can be varied in compounding and processing. Butyl is ideal for axle and body bumpers, motor mounts and sound-deadening applications.



### IMPERMEABILITY TO GASES AND MOISTURE

Enjay Butyl is tops in impermeability to gases and moisture . . . retains air pressure 8 times better than natural rubber. Outperforms other rubbers in such application as inner tubes, jar and bottle seals, hoses and inflatable goods.



### ELECTRICAL RESISTANCE

Enjay Butyl tops all vulcanizable rubbers in electrical and dielectric properties . . . in resistance to corona and ozone breakdown and water absorption. Its high dielectric strength insures against electric breakdown under normal or surge voltage. Its heat resistance permits higher current flow for a given conductor size.

The outstanding properties of Butyl Rubber create new horizons for the designer, and offer to manufacturers an opportunity to utilize the qualities of rubber in applications never before possible. The unique properties of Butyl have led to vast improvement in many existing products. Technical skills will open the way to countless new uses.

Butyl is the "idea" rubber with uses stretching as far as the imagination can reach. We'll be glad to tell you all about it. Just contact the nearest Enjay office.

EXCITING NEW PRODUCTS THROUGH PETRO-CHEMISTRY


**ENJAY CHEMICAL COMPANY**

**A DIVISION OF HUMBLE OIL & REFINING COMPANY**

HOME OFFICE: 15 West 51st Street, New York 19, N. Y. OTHER OFFICES: Akron • Boston • Charlotte • Chicago • Detroit • Houston • Los Angeles • New Orleans • Tulsa

ENJAY® BUTYL

For more information, turn to Reader Service card, circle No. 514



# Now you can do even more with TEFLON – made bondable by R/M

Time was, you'd often rule out "Teflon"* where it was sorely needed, simply because you couldn't make anything adhere to it.

But not now. R/M has perfected a process that makes "Teflon" easily bondable to other materials and to itself with commercial adhesives. Now you don't have to design intricate "Teflon" parts in a single piece or devise elaborate and costly fastening methods.

R/M can supply "Teflon" sheets, rods, tubes, and tape with bondable surfaces where you specify them. Thus you can use the high dielectric strength and superior chemical resistance of "Teflon" without worrying about how to make it stay put. In fact, you can take advantage of bondability and non-bondability in the same R/M "Teflon" part.

A lot is happening in "Teflon" daily. To keep up with it, talk "Teflon" with R/M . . . and learn of R/M's *complete "Teflon" service* that can help you cut product costs without cutting corners. Call one of the offices listed below or write Plastic Products Division, Raybestos-Manhattan, Inc., Manheim, Pa.

*Du Pont trademark for its TFE-fluorocarbon resin

R/M

PLASTIC PRODUCTS DIVISION

**RAYBESTOS-MANHATTAN, INC.**

Manheim, Pa.

BIRMINGHAM 1 • CHICAGO 31 • CLEVELAND 16 • DALLAS 26 • DENVER 16 • DETROIT 2
HOUSTON 1 • LOS ANGELES 58 • MINNEAPOLIS 16 • NEW ORLEANS 17 • PASSAIC • PHILADELPHIA 3
PITTSBURGH 22 • SAN FRANCISCO 5 • SEATTLE 4 • PETERBOROUGH, ONTARIO, CANADA

**SPECIALISTS IN ASBESTOS, RUBBER, SINTERED METAL, ENGINEERED PLASTICS**

For more information, turn to Reader Service card, circle No. 460

*Practical facts on uses . . . exactly as you want them!*

# Concise Guide to Plastics

**by HERBERT R. SIMONDS**
*Consulting Engineer*

Every practical question you have about the uses, properties, cost, or sources of all plastics is specifically answered in this truly indispensable book. It describes all known American commercial plastics, including those still in the laboratory stage. It instructs in the selection, use and forms of plastics, and contains discussions of which ones best suit particular products. The information includes basic data on strength, properties, processes, production and prices. All information is presented as accurately and briefly as possible.

**SPECIAL FEATURE:** The "CONCISE GUIDE" also lists the 43 most important plastics producers with their addresses, the names of chief officers, company organization and background, products, trade names, and descriptions of operations.

**1957, 320 pages, Illustrated, $6.95**

*Presenting the first book in Reinhold's*
**Plastics Applications Series . . .**

# POLYETHYLENE




**by THEODORE O. J. KRESSER**
*Technical Service Representative, Spencer Chemical Co.*

**1957**
**229 pages**
**$4.95**
**illustrated**

Covers this exciting new material in respect to its uses and why it is frequently preferable to other materials. Contains discussions of how products are manufactured from polyethylene. The subject is treated in a practical and selective manner; each application described is representative of a group of related applications. Includes recent advances in the field.

**COVERS:** History; General Properties; Basic Chemistry; Manufacture; Processing; Applications: Films, Coatings, Pipe, Coated Wire, Moldings, Blown Bottles, Vacuum Formings, Miscellaneous Extrusions and Processes, Future Prospects.

*Send now for your* ON-APPROVAL *copies*

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-715, 430 Park Ave., New York 22, N. Y.**

# PRE-IMPREGNATED FABRIC and COATED FABRIC PRODUCTS TO SUIT YOUR REQUIREMENTS

**A wide range of thermoplastic and thermosetting resin formulations to suit varied product requirements and molding methods are available from Cordo Chemical Corporation, for many years a leading plastics developer and manufacturer. These superior plastic compounds have excellent flow, high tensile strength and strong adhesion, even at very high temperatures.**

## CORDOGLAS®

### COATED FABRICS

Vinyl, Silicone & Neoprene Coating on Glass, Nylon, Cotton & Laminations.

To customer specifications for industrial and all general purposes, aircraft and military safety, industrial sound/vibration attenuating fields.

### PROPERTIES:

Temperature — 600°F to 65°F.
Breaking Strength — to 500 lb/in.
Flame Resistance — Self-extinguishing to flame resistant
Chemical Resistance — to mild alkalis, acid
Adhesion — to 25#/in.
Joining — Heat sealing and non-heat sealing
Colors — Any color
Weight — 4 to 250 oz./sq. yd.
Widths — to 60 inches

*Plants: Norwalk, Connecticut; Mobile, Alabama; Saugus, California*

**CORDO**
**CHEMICAL CORPORATION**
34 Smith Street
Norwalk, Connecticut

## CORDOPREG,® MOBALOY,® PREPREG

For high temperature and general purpose applications

Pre-Impregnated Fabrics and Roving & Chopped Roving Prepreg using proven

| | |
|---|---|
| POLYESTER RESINS | SILANE RESIN |
| EPOXY RESINS | PHENYL SILANE RESIN |
| PHENOLIC RESINS | MILITARY CERTIFIED RESINS |
| SILICONE RESINS | AND REINFORCEMENTS |

*Flexural Properties of Laminates, Cordopreg, Mobaloy at Elevated Temperatures*

POUNDS PER SQUARE INCH

| | *Polyester* | *Epoxy* | *Phenolic* | *Silane* | *Phenyl Silane* |
|---|---|---|---|---|---|
| 160° | 52,700 | 48,000 | —— | —— | —— |
| 500° | —— | 21,900 | 49,000 | 18,300 | —— |
| 600° | —— | —— | —— | —— | 41,000 |
| 700° | —— | —— | —— | —— | 25,000 |


*Plants: Norwalk, Connecticut; Mobile, Alabama; Saugus, California*

**CORDO**
**MOLDING PRODUCTS, INC.**
230 Park Avenue
New York 17, New York

**CORDO**
**CALIFORNIA CORPORATION**
21444 W. Golden Triangle Road
Saugus, California

**For more information, turn to Reader Service card, circle No. 512**

IF PHENOLICS CAN DO IT, **PLENCO** CAN PROVIDE IT...AND DOES




...AND THE BEST OF COMPANIES PUT IT THERE. From the most delicate of subminiature switches to the toughest of subterannean pipe fittings... *Plenco phenolic molding compounds* are key ingredients in the production plans of major manufacturers across the country. Large or small, industrial or consumer, *your* company and product can benefit from the advantages offered by today's versatile phenolic materials. And from the application of Plenco's creative research and experience to your problem.

You can be sure that, with many years of supplying critical and competitive industry, Plenco has or can *custom-formulate* just the molding compound you need: ready-made or specially-made; general purpose or very special purpose. Our selections are extensive, our facilities ample, our representative always available for consultation. Call on us at any time.

**PLASTICS ENGINEERING COMPANY**
Sheboygan, Wisconsin

PLENCO PHENOLICS
FOR BETTER PLASTIC PRODUCTS

Serving the plastics industry in the manufacture of high grade phenolic molding compounds, industrial resins, and coating resins.

For more information, turn to Reader Service card, circle No. 456

*For more data on*

**FILAMENT WOUND REINFORCED PLASTICS**

**SHEET FORMED PLASTICS PARTS**

**LOW PRESSURE REINFORCED PLASTICS**

Reprints of **MATERIALS IN DESIGN ENGINEERING MANUALS** on these engineering materials are now available at 35¢ per copy. Each Manual is a complete and comprehensive discussion to guide you in materials selection and use. If you would like copies, write today.

**"Filament Wound Reinforced Plastics: State of the Art,"** 20 pp. This popular reprint is a 3-part report that tells you (1) what you can expect from filament wound reinforced plastics parts, (2) how to select and evaluate the materials, and (3) how process variables affect end service properties. Data are supplemented by helpful charts, tables and photographs.

**"Sheet Formed Plastics Parts,"** 16 pp. Parts made from thermoplastic sheet offer wide materials selection, attractive appearance, predecoration, speed of production set-up and economies in manufacture. This manual tells you why to use them, which type of sheet and which material for the job, which forming method to select, and design limitations.

**"Low Pressure Reinforced Plastics,"** 16 pp. High strength-to-weight ratio plus ability to be easily formed into complex curvatures are among the many reasons for the extensive use of low pressure reinforced plastics in structural applications. This manual is an up-to-date run-down on resins and reinforcements, molding methods and design information.

---

*For copies of* M/DE *Manuals at 35¢ each, write to:*

**Reader Service Department**
**MATERIALS IN DESIGN ENGINEERING**
**430 Park Avenue, New York 22, N. Y.**

For more information, circle No. 395 ➤

Celanese

# PLASTICS IN DESIGN

Celanese plastics are reducing time, trouble and cost between design and better finished product. That's true of thousands of consumer and industrial products, where the unique properties of Celanese plastics offer many advantages . . . exceptional moldability . . . color and surface permanence . . . strength and light weight.

## Celanese offers a variety of plastics

The design and function of countless items can be improved by the use of Celanese plastics which include . . .

**FORTIFLEX A**
. . . high density polyethylene

**FLAME RESISTANT FORTIFLEX A**

**FORTIFLEX B**
. . . linear copolymers

**FORTIFLEX C**
. . . . medium density polyethylene

**FORTIFLEX D**
. . . low density polyethylene

**FORTICEL**
. . . cellulose propionate

**ACETATE**
. . . molding compounds

**POLYESTER RESINS**

## Let Celanese help with your Plastic Requirements...

We offer you complete technical service. Competent, experienced Celanese Representatives will gladly assist with any aspect of plastic selection, fabrication or application. And they're backed by one of the industry's most complete, modern plastics laboratories. Celanese warehouses and facilities are located at strategic points throughout the country to assure fast service wherever you are located.

Celanese
POLYMERS

# Celanese MOLDING

## FOR STRONG, RIGID PARTS . . . ELECTRICAL AND

# FORTIFLEX . . . a complete range of polyethylenes from .915 to .96 density

Celanese Fortiflex A and B are a family of linear polyolefins which differ from conventional polyethylene in both physical properties and methods of manufacture. Produced by a low temperature, low pressure method, Fortiflex A and B have the high crystallinity that results in different properties and performance . . . rigidity . . . resistance to high and low temperatures . . . low permeability . . . lustrous, less "waxy" surface . . . excellent tensile strength. What's more, all Fortiflex resins possess good chemical resistance . . . excellent electrical characteristics . . . good impact . . . easy moldability and colorability.

There are four basic Fortiflex groups . . . Series A, B, C and D. Each group is especially adapted to the requirements of specific end uses.

**BLENDS**—For many applications, a combination of Fortiflex of various densities is desirable. Celanese will supply these blends to match customer specifications, or will recommend one for your particular application.

### PROPERTIES OF FORTIFLEX A60 AND B50

| Properties related to Melt Index | Units | ASTM Method | PHYSICAL PROPERTIES A60-20 | A60-70 | A60-250 | A60-500 | A60-800 | B50-20 | B50-80 to B50-500 |
|---|---|---|---|---|---|---|---|---|---|
| Melt Index | — | D1238-52T | 0.2 | 0.7 | 2.5 | 5.0 | 8.0 | 0.2 | 0.8-5.0 |
| Heat Distortion Temp., 66 psi | °F | D648-56 | 185 | 185 | 180 | 180 | 180 | 170-175 | 170-175 |
| Impact Strength (1) | ft. lb./ in. notch | D256-54T | 23 | 18 | 13 | 3 | 0.7 | 7 | 5-1 |
| Notched Izod (2) | | | | | | | | | |
| Tensile Strength, 0.2 in./min. (3) | psi | D638-52T | 3,700 | 3,500 | 3,300 | 3,300 | 3,300 | 3,200 | 3,100 |
| Elongation, 0.2 in./min. (3) | % | D638-52T | 28 | 25 | 18 | 13 | 13 | 30 | 25-18 |
| Environmental Stress Cracking Resistance, F50 Value | hr. | Bell Lab. (4) | 190 | 30 | 6 | 3 | — | 2,000 | (5) |
| **Properties not related to Melt Index** | | | | | | | | | |
| Density | g/cc | D792-50 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.95 | 0.95 |
| Highest Use Temperature (6) | | | | | | | | | |
| Continuous | °F | — | 180 | 180 | 180 | 180 | 180 | — | — |
| Intermittent | °F | — | 225 | 225 | 225 | 225 | 225 | — | — |
| Softening Temperature (7) | °F | — | 260 | 260 | 260 | 260 | 260 | 255 | 255 |
| Stiffness in Flexure | psi | D747-50 | 140000 | 140000 | 140000 | 140000 | 140000 | 100000 | 100000 |
| Hardness | Rockwell R | D785-51 | 40 | 40 | 40 | 40 | 40 | 40 | 40 |
| | Shore D | D676-49 | 65 | 65 | 65 | 65 | 65 | 64 | 64 |
| Mold Shrinkage (8) | | | | | | | | | |
| Length | in./in. | — | .010-.030 | .010-.030 | .010-.030 | .010-.030 | .010-.030 | .010-.030 | .010-.030 |
| Width | in./in. | — | .010-.025 | .010-.025 | .010-.025 | .010-.025 | .010-.025 | .010-.025 | .010-.025 |
| Flammability | in./min. | D635-44 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 |
| Water Absorption | | | | | | | | | |
| 24 hr. at 77°F | % gain | D570-54T | <0.01 | <0.01 | <0.01 | <0.01 | <0.01 | <0.01 | <0.01 |
| Refractive Index | $n_{D25}$ | D542-50 | 1.54 | 1.54 | 1.54 | 1.54 | 1.54 | 1.54 | 1.54 |

### ELECTRICAL PROPERTIES

| | Units | ASTM Method | Frequency (Cycles per Second) | Value |
|---|---|---|---|---|
| Dielectric Strength (Short time) | volts/mil | D149-55T | — | 500 |
| Volume Resistivity | ohm cm. | D257-54T | — | $6 \times 10^{15}$ |
| Dielectric Constant | — | D150-54T | $1 \times 10^{3}$ | 2.35 |
| | | | $1 \times 10^{6}$ | 2.36 |
| Dissipation Factor | — | D150-54T | $1 \times 10^{3}$ | 0.0002 |
| | | | $1 \times 10^{6}$ | 0.0003 |
| Loss Factor | — | D150-54T | $1 \times 10^{3}$ | 0.0007 |
| | | | $1 \times 10^{6}$ | 0.0007 |

### TYPICAL CHEMICAL RESISTANCE

| | Value* |
|---|---|
| Acetic Acid, glacial | 0.7 |
| Sulfuric Acid 98% | 0.0 |
| Sodium Hydroxide 50% | 0.0 |
| Ammonium Hydroxide 28% | 0.0 |
| Carbon Tetrachloride | 14.0 |
| Methyl "Carbitol" | 0.1 |
| Water | 0.0 |
| Gasoline | 6.0 |

*% Increase in wt. after 30 days immersion at 80°F. Sample specimens were 1" x ½" x ⅛".

### FOOTNOTES

(1) Impact values observed on injection molded bars should not be considered indicative of practical impact values for molded items where other factors affect the impact value. While its impact value will be sufficient for most uses, Fortiflex B should be evaluated for each specific application.

(2) Injection molded specimens, ½" x ½" cross section, notch in the ½" face. A60-20, A60-70 and A60-250 specimens did not break. A60-500 and Fortiflex B50 copolymers exhibited partial or hinged breaks.

(3) Injection molded Type I specimens, ⅛" thick. Tensile strength and elongation data recorded at the first yield point.

(4) ASTM Standard on Plastics, Issue of February, 1957. Appendix, Page 831—Proposed Method of Test for Environmental Stress Cracking of Ethylene Plastics.

(5) Fortiflex B50-80 has an environmental stress cracking resistance $F_{50}$ value of 160 hrs.

(6) Highest use temperature depends on part design, molding and service conditions, special formulations are available for continuous use at higher temperatures up to 212°F.

(7) Method of Karrer et al, Ind. Engr. Chem., Anal. Ed. 2, 96 (1930).

(8) Mold shrinkage depends on part design and molding conditions.

# COMPOUNDS AND RESINS . . .

## INDUSTRIAL PRODUCTS . . . HOUSEWARES . . . TOYS . . . PACKAGES

### FORTIFLEX A . . . linear polyolefins

Fortiflex A is available in both natural and colored molding powders. Five formulations provide a wide flow range.

**A60-20** possesses the highest impact strength, stress cracking resistance and low-temperature strength of the A series, and requires somewhat higher process temperatures. It's recommended for extrusion, calendering, blow molding or injection molding of very small parts requiring maximum physical properties.

**A60-70** is a general-purpose resin. It's recommended for injection molding of small parts with limited surface area; for extrusion, calendering, blow molding, and as a rubber compounding additive.

**A60-250** is suggested for intermediate-sized injection molded articles where better moldability and improved surface finish are required.

**A60-500** possesses the best moldability for large-area moldings and applications where maximum processability and high surface gloss are required.

**A60-800** is used primarily as a blending component with Fortiflex D polyethylene. It offers substantially improved flow characteristics with reduced impact strength compared to other resins in the Fortiflex A series. It can be used in blends, single-use containers, or items requiring low impact strength such as certain toys and novelties. It is not recommended where stress cracking is a problem.

**TYPICAL APPLICATIONS:** housewares, appliance, electrical and automotive parts, filaments for textiles and rope, bottles and containers, toys, industrial parts and protective helmets.

**FLAME RESISTANT FORTIFLEX.** Celanese offers specially formulated flame resistant variations of Fortiflex A60-70, A60-250, and A60-500. These formulations are opaque, self-extinguishing, high-density polyethylenes with a specific gravity of 1.04. Their stiffness, hardness and tensile strength are approximately the same as the standard resins', although heat distortion values under 66 psi are slightly lower and impact strength is somewhat reduced. Burning rate or flammability is reduced to the point where they can be classified as non-burning materials under ASTM D-635-44.

### FORTIFLEX B . . . linear copolymers

The Fortiflex B series offers a family of resins with an extremely broad range of properties and special advantages. They make it possible to upgrade many applications now employing other thermoplastics, and open up many new fields of application for plastics.

Fortiflex B is an excellent injection molding plastic and provides outstanding stress crack resistance. Processability of Fortiflex B resins is somewhat improved over the Fortiflex A series resins when compared on a melt index for melt index basis. Thus, cycle time for a given part may be less for these resins compared to Fortiflex A, since their cold point and viscosity are lower.

In tests under a static load, properly oriented filaments of the new polymer show reduced tendency to stretch.

**APPLICATIONS:** filaments for rope and outdoor furniture webbing, wire covering, blown bottles and containers, and pipe.

Applications for injection molding include: containers for stress-active agents, drum plugs, fittings and couplings, thin-walled moldings, large area moldings, insert moldings, bottle caps and closures.

The Fortiflex B series has opened new prospects for the blow molding of bottles and hollow-ware.

### FORTIFLEX C . . . medium density polyethylenes

Fortiflex C is a medium density resin presently offered only in a .934 density and 1.7 melt index. It is midway in stiffness between the softer type low density polyethylenes and the rigid type Fortiflex A and B resins. Fortiflex C is available in three different formulations for film, paper coating and pipe extrusion.

The film formulation is ideal for the extrusion of film for overwraps for stationery and bread and provides excellent clarity in chill roll extrusion. The paper coating formulation gives optimum greaseproofness at ¾ mil thickness, and it passes MIL-B-121B at 12 pounds per ream. The pipe formulation is sold only in black. It is NSF approved, meets the proposed 1960 revision of CS-197 Type II pipe, and has a compounded density of .942.

### FORTIFLEX D . . . low density polyethylenes

The Fortiflex D series of polyethylene resins is available in a range of densities from .915 to .924 and in a variety of melt indices which provide a line of resins ideal for injection and blow molding as well as the extrusion of film, pipe, wire covering and paper coating. These resins range from moderately stiff materials at the top of the density range to the softest low density polyethylenes commonly in use today.

Within this line of resins are materials specially suited to large, medium and small area injection molded toys, housewares, closures and industrial parts; coatings for locker wrapping paper, milk cartons, laminating to aluminum foil and acetate, multi-wall bags, kraft and cellophane. Also available are resins for NSF pipe that meet the proposed 1960 revision of CS-197 Type I, wire coverings for tree and line wire and power cable as well as cable jacketing and primary insulation which meet ASTM D1248-58T, Type I, Grade 4 and Federal Specifications LP-590, Type I, Grade 7. Film resins include materials for blown or chill roll film for freezer bags, produce bags, garment bags, soft goods overwraps, and general purpose films. Blow molding resins cover both general purpose requirements in squeeze bottles and critical packages where superior stress cracking resistance is required.

# Celanese CELLULOSICS AND POLYESTERS

## FORTICEL . . . cellulose propionate

Its excellent *balance* of desirable properties makes Forticel distinctive among thermoplastics. Its combination of toughness and good flexural strength is unique among cellulose ester plastics. And it is free of objectionable odor. The high impact strengths of Forticel occur at moderate plasticizer levels, where its other fine characteristics, such as dimensional stability and stiffness are also optimum. No other cellulose plastic of similar general properties has less humidity expansion. Its low water absorption results in stability against warpage. And Forticel has considerably more resistance to weathering than cellulose acetate, and is very similar to cellulose acetate butyrate in this respect.

Forticel provides an exceptional luster on molded surfaces, obtainable on a fast cycle—in some items the fastest of all the cellulosics. A free flowing plastic, it can be injection molded with great ease, and lends itself to restricted gating and complicated mold layouts. Its superior flow insures practically invisible weld lines where two streams of plastic meet in the die. Forticel eliminates problems of flow around mold pins. Forticel is produced in four series of formulas offering different flow ranges and end-use advantages. It is offered in a range of transparent, translucent and opaque colors.

**TYPICAL APPLICATIONS:** pens, telephone housings, automotive parts, personal items, business machine keys, vacuum cleaner attachments, handles, small equipment housings.

## ACETATE . . . molding compounds

Economical, versatile Celanese Acetate is a widely used cellulosic plastic. In toughness, acetate can seldom be matched by any other plastic in its price bracket. It has high impact strength, rigidity, a hard surface, satisfactory dimensional stability for a wide range of applications. What's more, acetate is free of objectionable odor and has relatively good temperature stability. The XK series is formulated entirely of ingredients considered acceptable for use in contact with foods by the Food & Drug Administration. Dielectric properties are good. The plastic is unharmed by common hydrocarbons such as gasoline, benzene and oils.

Acetate has excellent moldability, and molding temperatures are not critical. The plastic is free-flowing, which minimize the problem of weld lines, and is recommended for applications incorporating metal inserts. With the aid of pre-plasticizing machines, heavy parts can be molded in one cavity, or family molds can be used. Acetate molds with an excellent surface finish, and it is easily fabricated. Parts may be cemented together to give a bond as strong as the original pieces. Formulations can be widely varied in properties by use of various types and amounts of plasticizers.

Acetate is produced in a number of formulations—including flame resistant material in a broad range of flows. It is offered in a practically limitless variety of transparent, translucent and opaque colors, as well as crystal clear. The flame resistant XFA and XFB formulations have achieved wide acceptance in the molding of appliance parts and housings where Underwriters approval may be a problem.

**TYPICAL APPLICATIONS:** toys, shoe heels, appliance housings, toilet seats, jewelry, tool handles, sun glasses, brush backs.

## CELANESE POLYESTER RESINS . . . for boats . . . auto and truck bodies . . . housings . . . tanks and tank linings . . .

Celanese polyester resins are thermosetting liquids; 100 percent polymerizable which do not liberate volatile by-products during cure. The Marco series of base resins are available in blends with styrene, vinyl toluene, methyl methacrylate or diallyl phthalate monomers in a range of varying viscosities. These resins can be readily cured at elevated temperatures employing peroxide type catalysts at moderate to contact pressure. With the addition of accelerators, it is possible to affect rapid cure at room temperature thus eliminating the need for heating equipment.

The simple fabricating techniques required to use Celanese polester resins, combined with the outstanding properties of the end products, such as high strength, light weight, resistance to moisture, excellent weathering, and chemical resistance have led to their use in the production of a broad range of items in the industrial, construction, transportation and decorative fields. Included are such products as auto bodies, aircraft parts, boats, buttons, corrugated and flat sheeting, ducting, fishing rods, furniture, housings, shelters, tanks, trays, tote boxes, trophies and many others.

• To the best of our knowledge the information contained herein is accurate. However, neither Celanese Corporation of America nor any of its affiliates assumes any liability whatsoever for the accuracy or completeness of the information contained herein. Final determination of the suitability of any information or material for the use contemplated, the manner of use and whether there is any infringement of patents is the sole responsibility of the user.

Celanese® Fortiflex® Forticel® Marco®

CELANESE POLYMER COMPANY
744 BROAD STREET, NEWARK, N.J.

Celanese Polymer Company is a Division of Celanese Corporation of America

Canadian Affiliate: Canadian Chemical Company Limited, Montreal, Toronto, Vancouver • Export Sales: Amcel Co., Inc., and Pan Amcel Co. Inc., 180 Madison Ave., N.Y. 16, N.Y.

**MELAMINE IMPREGNATED PAPERS**
in a wide variety of patterns, wood grains, solid colors, and translucent overlay grades for durable decorative laminates. Available in rolls slit to width, sheeted, or die-cut to any shape required.

**PHENOLIC IMPREGNATED PAPERS**
for producing N.E.M.A. industrial grade laminates and molded parts for a wide range of electrical, mechanical, and structural applications. Precisely controlled processing assures uniformity of quality.

**PHENOLIC IMPREGNATED FABRICS**
such as cotton duck, cloth, and sheeting for high or low pressure molding. Available in grades to meet N.E.M.A. standards. Also used in producing gears, bearings, filters, helmets, and many other products.

# FABRICON

## PLASTIC IMPREGNATED MATERIALS


*for Molding and Laminating*

**PHENOLIC IMPREGNATED GLASS CLOTH**
produced in special grades for fabrication of fly rods, aircraft and guided missile parts, plus many other products requiring a strong, light, durable material highly resistant to heat and corrosion.

**POLYESTER IMPREGNATED MATERIALS**
such as glass fabric and mat for low pressure molding of aircraft parts, tools, and other applications where high strength, light weight, ease of forming, and dimensional stability are essential properties.

**SILICONE IMPREGNATED GLASS CLOTH**
in grades having excellent dielectric strength and resistance to distortion at high temperatures, plus other properties required for applications such as radar equipment, printed circuits, motors, etc.

**EPOXY IMPREGNATED MATERIALS**
custom treated to meet the highly specialized requirements of many electrical and electronic devices used for an ever-increasing number of military and industrial applications.



One of several giant impregnating ovens having roll capacities up to 90" in width. All are designed for continuous quality controlled operation.

Whenever you need plastic impregnated and coated materials, you'll do well *always* to think of Fabricon *first!* For regardless of what your requirements may be, you'll find that Fabricon has what it takes to deliver the quality and service that you've been looking for. Years of experience with all types of thermosetting resins and fillers. Complete engineering and laboratory facilities for developing new products and processes. Special production equipment designed for precisely controlled, continuous, economical operation. Facilities, too, for slitting material to width, sheeting, or die-cutting to any shape required.

***Want detailed information*** on the Fabricon Plastic Impregnated Material that's *right* for your particular product? Just outline the nature of your application and send it in today!

**FABRICON PRODUCTS**

*A Division of The EAGLE-PICHER Company*

1721 W. Pleasant Street • River Rouge 18, Michigan

Plastic Impregnated and Coated Materials • Reinforced Plastic Moldings

For more information, circle No. 395

For more information, turn to Reader Service card, circle No. 413




IN SOME WAY-
ALMOST EVERY DAY-
PEOPLE FIND
MORE USES FOR

# FARLITE




## *THE VERY BEST IN HIGH PRESSURE PLASTIC LAMINATES*

■ Need a tough, non-corrosive plastic for gears? A graphite-impregnated, heavy duty stock for bearings? An economical, long-lasting die stock? These and many other applications are being ably handled by the 34 grades and types of Farlite high pressure plastic laminates now available. A Farlite consultant is always ready to assist you in the selection of the proper type for your product application.

**FREE**
**TECHNICAL DATA AND PRODUCT SUGGESTION CHART**



FARLITE

PLASTICS DIVISION
**FARLEY & LOETSCHER MFG. CO.**
DUBUQUE, IOWA

For more information, turn to Reader Service card, circle No. 417

# Wilbow

(Satisfaction . . . Since 1903)

## MECHANICAL RUBBER PARTS

**MOLDED, PUNCHED, EXTRUDED or CUT.....**

*to your order*

**in NATURAL, SYNTHETIC or SILICONE COMPOUNDS**

***We Specialize in producing Rubber Covered Rolls, Silicone Rubber Parts and Bonding Rubber to Metal.***

We also produce... Bushings, Rings, Gaskets and Washers • Slab and Sheet Rubber • Rubber Tubing and Cord • Cylinder Spring Rubber • Rubber Bumpers in bulk.

*Let us know of your requirements*



*Send for* **WILBOW Catalog**

PHONE: BISHOP 2-1640

**The WILLIAMS-BOWMAN RUBBER Co.**
1945 South 54th Avenue • Cicero 50, Illinois (Chicago Suburb)

For more information, turn to Reader Service card, circle No. 485

***Here's latest information on a phenomenal new structural material!***

## FIBERGLAS REINFORCED PLASTICS

**Edited by**
**RALPH H. SONNEBORN**
*Technical Service Dept.,*
*Plastics Reinforcement Division,*
*Owens-Corning Fiberglas Corporation*




**1954, 250 pages, $4.50**


This valuable book offers the first *complete* treatment ever published on the subject of reinforced plastics, the amazing post-war structural material that has found its way into scores of new industries and products.

Written for both design engineers and executives in the materials industries, the book covers in full detail the resins and glass reinforcements used in reinforced plastics, molding techniques, inspection and testing, properties, and design considerations.

This important book will provide all those concerned with reinforced plastics—molders, materials suppliers, government agencies, engineers—with a wealth of information never before available in a single volume.

***Order now for 10 days' FREE EXAMINATION***

**REINHOLD PUBLISHING CORPORATION**
Dept. M-719, 430 Park Avenue, New York 22, N. Y.




# YOUR SILICONES MAN WILL SEND YOU FREE

## THIS NEW IDEA IN CATALOGS TO HELP DESIGN ENGINEERS FIND THE CORRECT SILICONE FOR THE JOB

Want to find out exactly how and where you can use what silicones . . . to cut costs, improve a product? To step up production, save time? This new 16-page, illustrated booklet tells you—for your specific industry—quickly!

Incorporating a 4-page center fold-out showing diagrammatically all UNION CARBIDE Silicone products, it is subdivided into application categories—electrical, electronic, aircraft, automotive, chemical, textile, paint, rubber, building, many others.

You simply turn to your section and find which silicones best serve your needs, how, and the reasons why.

Years of experience of our research chemists, application engineers, and especially of our technically trained Customer Service Representatives familiar with problems of your industry, provide the background for this invaluable catalog. Fill in and mail the coupon *today*. Silicones Division, Union Carbide Corporation, 270 Park Avenue, New York 17, N. Y. *In Canada:* Union Carbide Canada Limited, Bakelite Division, Toronto 12.

**Unlocking the Secrets of Silicones**

**Rubber, Monomers, Resins, Oils and Emulsions**

UNION CARBIDE **SILICONES**

UNION CARBIDE is a registered trademark of Union Carbide Corporation.

Silicones Division, Union Carbide Corporation, Dept. MK-0005. Please send me at once my free copy of your new 16-page UNION CARBIDE Silicones Catalog for Design Engineers.

NAME _____ TITLE _____

COMPANY _____

STREET _____

CITY _____ ZONE _____ STATE _____

**For more information, turn to Reader Service card, circle No. 558**

# CIBA Araldite® Epoxy Resins Properties and Applications

As a leading producer of epoxy resins to meet every application requirement, CIBA has compiled this up-to-date chart summarizing specification data and recommended end uses for your ready reference. CIBA will be pleased to provide detailed information on the use of CIBA Epoxy Resins for specific applications.

| Properties | | Resin | 502 | 506 | 6005 | 6010 | 6020 |
|---|---|---|---|---|---|---|---|
| | | epoxy content | 0.40-0.43 | 0.54-0.58 | 0.53-0.55 | 0.51-0.54 | 0.48-0.51 |
| | | 1. epoxy value (eq. / 100 g.) | 232-250 | 172-185 | 182-189 | 185-196 | 196-208 |
| | | 2. weight per epoxide (WPE) | — | — | — | — | — |
| | | saponification equivalent (av.) | — | — | — | — | — |
| | | weight per gallon (lb.) | 9.3-9.6 | 9.3-9.6 | 9.6-9.8 | 9.6-9.8 | 9.6-9.8 |
| | | color (Gardner) | 3 (max.) | 3 (max.) | 3 (max.) | 3 (max.) | 3 (max.) |
| | | melting point (Durran's) °C. | (liquid) | (liquid) | (liquid) | (liquid) | (liquid) |
| | | viscosity (at 25°C.) Brookfield (cps.) | 2100-3600 | 500-700 | 7000-10000 | 12000-16000 | 16000-20 |
| | | Gardner-Holdt | — | — | — | — | — |
| Structural | | adhesives | ■ | ■ | ■ | ■ | ■ |
| | | body "solders" | ■ | ■ | ■ | ■ | ■ |
| | | casting | ■ | ■ | ■ | ■ | ■ |
| | | caulking and sealants | ■ | ■ | ■ | ■ | ■ |
| | | electrical | ■ | ■ | ■ | ■ | ■ |
| | | impregnating | ■ | ■ | ■ | ■ | ■ |
| | | laminating | ■ | ■ | ■ | ■ | ■ |
| | | tooling | ■ | ■ | ■ | ■ | |
| Coatings | maintenance | equipment finishes | | | | | |
| | | marine finishes | | | | | |
| | | masonry finishes | ■ | | | | |
| | | structural steel coatings | | | | | |
| | | tank coatings | | | | | |
| | product finishing | aircraft finishes | | | | | |
| | | appliance primers | | | | | |
| | | automotive primers | | | | | |
| | | can & drum linings | | | | | |
| | | chemical-resistant finishes | ■ | | | | |
| | | collapsible-tube coatings | | | | | |
| | | furniture finishes | | | | | |
| | | metal decorating finishes | | | | | |
| | | pipe & tank linings | | | | | |
| | trade sales | concrete floor paints | | | | | |
| | | gym and floor varnishes | | | | | |
| | | spar varnishes | | | | | |
| Other Uses | | decorative flooring — Epoxy/Marble Chip (Terrazzo) | ■ | ■ | | | |
| | | floor topping — industrial | ■ | ■ | ■ | | ■ |
| | | printing inks | | | | | |
| | | road toppings | ■ | ■ | | | * |
| | | [illegible] | | ■ | ■ | | |

# CIBA First in Epoxies

* Used primarily in conjunction with fatty acids to produce esters.
** 90% N.V. in xylene
†40% N.V. in butyl "Carbitol"

In U.S.A. and Canada CIBA produces basic resins only, to be formulated for intermediate and end uses.

Further information on these CIBA products and applications may be obtained promptly by addressing:


CIBA Products Corporation
Fair Lawn, New Jersey

For more information, circle No. 399

CIBA

WHERE RESEARCH IS THE TRADITION

| 6030 | 6040 | 6060 | 6071 | 6084* | 6097 | 6099 | 7071 | 7072 | 7097 | RD-1 | RD-2 |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 0.45-0.51 | 0.36-0.43 | 0.20-0.26 | – | – | – | – | – | – | – | 0.70 (av.) | 0.75 (av.) |
| 196-222 | 232-278 | 385-500 | 425-550 | 875-1025 | 2000-2500 | 2500-4000 | 450-530 | 550-700 | 1650-2000 | 143 (av.) | 133 (av.) |
| – | – | – | 145 (av.) | 175 (av.) | 200 (av.) | – | 155 (av.) | 170 (av.) | – | – | – |
| 9.6-9.8 | 9.6-9.9 | 9.9 (av.) | 9.9 (av.) | 9.9 (av.) | 9.8 (av.) | 9.8 (av.) | 9.9 (av.) | 9.9 (av.) | 9.8 (av.) | 7.5 (av.) | 9.2 (av.) |
| 5 (max.) | 5 (max.)† | 4 (max.)† | 4 (max.)† | 4 (max.)† | 5 (max.)† | 5 (max.)† | 4 (max.)† | 4 (max.)† | 4 (max.)† | <1 | 5 (max.) |
| (liquid) | | 60-75 | 65-75 | 95-105 | 125-135 | 145-155 | 65-75 | 75-85 | 113-123 | (liquid) | (liquid) |
| 25000-32000 | – | – | – | – | – | – | – | – | – | 3 | 19 |
| – | Z4-Z6** | – | D-G† | R-U† | Z-Z2† | Z2-Z5† | D-G† | G-K† | X-Z† | – | – |



* **ARALDITE Epoxy Resin Solutions***

| ARALDITE | 471 X | 485 E | 497 C | 540 X | 545 BX | 571 CX | 571 K | 571 KX | 571 T | 597 ET |
|---|---|---|---|---|---|---|---|---|---|---|
| non-volatile ±1.0% | 75 | 50 | 55 | 90 | 60 | 80 | 70 | 75 | 75 | 55 |
| viscosity (G.H.) | Z3-Z5 | X-Z | Z3-Z5 | Z4-Z6 | Y-Z2 | Z5-Z7 | W-Z | Z1-Z4 | Z2-Z4 | Z1-Z4 |
| Room Temperature Systems: | | | | | | | | | | |
| maintenance, marine and floor finishes | | | | | | | | | | |
| specialty maintenance | | | | | | | | | | |
| Baking Finishes: | | | | | | | | | | |
| product finishes, primers, can and drum linings | | | | | | | | | | |

*Solvents code: B = butyl "Cellosolve," C = "Cellosolve," E = "Cellosolve" acetate, K = MIBK, T = toluene, X = xylene

Covers properties, production,

price, use and selection . . .

# Source Book of the NEW PLASTICS

by HERBERT R. SIMONDS

Consulting Engineer,
Editor of the Reinhold Plastics Applications Series,
author of *Concise Guide to Plastics*, etc.

**1959, 365 pages, $10.00**

Here are the new plastics: Their properties, production, price, applications and selection. Sixty plastics producing companies contribute articles describing their own materials. These materials include the seven new primary plastics of 1958. The book also describes the significant recent improvements in established plastics, and the 100 most important patents issued in the plastics field for 1958. An "Introduction to Polypropylene" explains Professor Natta's work and the earlier German development of stereospecific catalysts. The book also gives complete information about polypropylene and polycarbonate. A section on graft copolymers describes the use of that technique in modifying plastics properties. This book is a unique approach to plastics that concerns itself almost exclusively with latest developments. It contains the first and only survey of federal-sponsored research in plastics, and was made by James Kanegis of the Department of Commerce. It continues the practical presentation begun in the author's famous *Concise Guide to Plastics*. Whatever your question, need or interest in new plastic materials, this book should give you specific, accurate and practical answers.

**Includes:**

IMPROVEMENTS IN ESTABLISHED MATERIALS
Graft Copolymers
Resin Improvements
Isocyanates
Urethane Foams
Runnerless Molding

PRODUCERS' NEW MATERIALS
60 Plastics Producers Describe:
Improvements in Established Primary Plastics
New Improved Secondary Materials
Synthetic Rubbers, Synthetic and Vulcanized Fibers, Synthetic Coatings
(This above section occupies pages 36 through 296)

FEDERAL-SPONSORED RESEARCH
Prepared by James Kanegis, U. S. Department of Commerce
For the first time, singles out new plastics developed through government-sponsored research, and polymeric discoveries and formulations which are still in the research stage.

A BRIEF PATENT SURVEY
100 Selected 1958 Patents Relating to Plastics

*Examine It Free for 10 Days*

**MAIL THIS COUPON NOW**

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-700, 430 Park Avenue**
**New York 22, N. Y.**

Send me a copy of SOURCE BOOK OF THE NEW PLASTICS for 10 days' Free Examination.

☐ Total purchase price enclosed
☐ Bill me ☐ Bill company

NAME_____

ADDRESS_____


CITY & STATE_____ STATE_____

SAVE MONEY! Enclose $10.00 with order and Reinhold pays all shipping costs. Same return privilege. Please add 3% sales tax on N.Y.C. orders. DO NOT ENCLOSE CASH!

example...

# FIBERITE

**Reinforced phenolics at work...**



*for* ELECTRIC AUTOLITE distributor bowls

Electric Autolite of Toledo needed a plastic molding compound for ignition distributors in automotive and industrial engines. The molded part must maintain rigid dimensional tolerances under very adverse conditions of temperature and humidity. Autolite specified Fiberite No. X-2414 cotton fiber reinforced phenolic. Here is Autolite's report:

1. Dimensionally stable
2. Impact resistant
3. Heat resistant
4. Corrosion resistant
5. Light weight
6. Easily machined

## EXPLORE FIBERITE

If you need a reliable molding compound with excellent electrical and mechanical properties plus the best in resistance to shock, chemicals and heat, explore Fiberite.

We have formulations to fit a variety of applications. Our research department is at your disposal. Write for the Fiberite catalog.

SALES OFFICES IN PRINCIPAL CITIES

FIBERITE MOLDING COMPOUNDS

THE FIBERITE CORPORATION
Dept. ME-12
510-520 W. 4th St.
Winona, Minnesota

For more information, circle No. 571

# nelco




*...basically best for etched circuitry*

Unclad, or metal-clad on one or both sides, NELCO laminates in thicknesses of 0.005" up — in sheets 36" x 42", 36" x 48", 36" x 60" and 36" x 72" — predictably meet the highest standards of the printed-circuit industry.

NELCO's nationwide engineering representation and aggressive R & D policy facilitate the solution of tough problems. Tell us yours: if the laminate you need is not already listed in our General Catalog (available on request), chances are that we can develop it for you. Write today — Department MS.

**THE FOLLOWING ARE TYPICAL OF NELCO LAMINATES**

| | GRADE | | TYPE OF MATERIAL | | |
|---|---|---|---|---|---|
| NELCO | NEMA | MIL | RESIN | BASE | SALIENT CHARACTERISTICS |
| 100 | G-10 | GE | Epoxy | Glass Fabric | Excellent Mechanicals and Electricals |
| 101/102 | — | — | Epoxy | Glass Fabric | Superior Flushing Grade; Meets MIL Specs |
| 105 | — | GF | Epoxy | Glass Fabric | Flame-Retardant; Good Electricals |
| 110 | G-11 | GB | Epoxy | Glass Fabric | High Temperature; Flame-Retardant |
| 130 | FR-2 | PE | Epoxy | Paper | Good Electricals; Suitable for Flushing |
| 135 | FR-3 | PE | Epoxy | Paper | Flame-Retardant; Punchable; Dimensionally Stable |
| 220 | XXP | — | Phenolic | Paper | Good Electrical & Mechanical Characteristics |
| 230 | XXXP | PP | Phenolic | Paper | Cold-Punching to 3/32"; High Electricals |
| 230-R | XXXP | PP | Phenolic | Glass-Reinforced Paper | Extremely High Impact and Flexural Strengths |

The above Military Grades are per MIL P-13949-B. See also Sweet's Product-Design Catalog File.

nelco *new england laminates co., inc.*
481 CANAL STREET • STAMFORD • CONN.

For more information, turn to Reader Service card, circle No. 528

# SUPPLIERS' LITERATURE

## Nonmetallics
(except Plastics and Rubber)

**Properties of Wool Felts.** American Felt Co., 8 pp, No. 8-60. Lists comparative chemical, physical and mechanical properties of 36 grades of wool felt used for mechanical and industrial applications. Includes information on available forms and fabricating methods. **111**

**Properties of Ceramics.** American Lava Corp., Steatite Div., 8 pp, No. 591. Physical, mechanical and electrical properties of steatite, forsterite, cordierite, lava, alumina and magnesium silicate ceramics. Also gives properties of silicon carbide and zirconium oxide. **112**

**Chrysotile Asbestos.** Lake Asbestos Div., American Smelting & Refining Co., Inc. Advantages, characteristics, properties and applications of chrysotile asbestos. **113**

**Cellophane Film.** American Viscose Corp., Film Div., 24 pp, illus. Characteristics, uses and dimensions of cellophane film. **114**

**High Temperature Materials.** Carborundum Co., Advanced Materials Technology, 8 pp, illus. Properties, uses and general information on 26 materials designed to resist abrasion, corrosion, nuclear radiation and high temperatures. Included are various metals and alloys, and several carbides, nitrides and oxides. **115**

**Felt.** Continental Felt Co. Information on wool, synthetic fiber and colored felts. **116**

**Industrial Ceramics.** Coors Porcelain Co., 4 pp, illus. Series of case histories describe advantages of ceramics for several different applications. Included is a chart giving mechanical and electrical properties of five grades of alumina ceramics. **117**

**Glass Radiant Heaters.** Corning Glass Works, 14 pp, illus., No. Te-70. General description, installation information, maintenance instructions, advantages, characteristics, and typical applications of tubular and panel heaters made of glass. **118**

**Silicones.** Dow Corning Corp., 16 pp, illus., No. 1-115. Forms, properties and applications of silicones used as adhesives, release agents, laminating resins, rubber compounds, electrical insulation, etc. **119**

**Vinyl-Coated Fabrics.** E. I. du Pont de Nemours & Co., Inc., Fabrics Div., Nos. AIA 28-F, AIA 28-C. General information, specifications, advantages, methods of application, materials used, and other information on vinyl-coated fabrics. Included are several dozen samples of various colors and textures available. **120**

**Fused Quartz.** Amersil Quartz Div., Engelhard Industries Inc. Characteristics, properties, advantages, and typical applications of fused quartz. **121**

**Felt in Electric Motors.** Felters Co., 9 pp, illus, No. SE-9-512. Characteristics, advantages, typical applications, properties, and treatments of felts and synthetic nonwoven fabrics used for mechanical parts in electrical motors. **122**

**Glass Reinforcement for Plastics.** Ferro Corp. Advantages, characteristics, and uses of glass cloth, fiber, filaments, etc., for plastics reinforcement. **123**

**High Temperature Insulation.** Fiberite Corp., 16 pp, illus. Characteristics, properties, molding techniques and uses of a line of variously reinforced plastic compounds for high temperature insulation. **124**

**Wood Products.** Gamble Brothers, Inc., 28 pp, illus. Shows wood products manufactured by the company, including industrial wood parts, chair parts and athletic apparatus. **125**

**Graphite.** Graphite Specialties Corp., 4 pp, No. GS-101-1. Chemical and physical properties of an impervious graphite for high temperature parts. **126**

**Thermal Insulation.** Johns-Manville Sales Corp., 54 pp, illus., No. IN-244-A. General description, typical applications, available forms and types, advantages, and specifications of a line of thermal insulation materials. **127**

**Cemented Carbides.** Kennametal, Inc., 24 pp, illus., No. B-666. Outstanding properties and typical uses of tungsten, titanium, tantalum, columbium and cobalt cemented carbides. **128**

**Specialty Papers.** Knowlton Bros., Inc., 12 pp, illus. Information on technical and industrial specialty papers. Shows company research and manufacturing facilities. **129**

**Engineered Glass Parts.** Kopp Glass Inc., 20 pp, No. 760. Services and facilities available for the production of colored and clear glass parts. Included are examples of sizes, colors, designs and custom-engineered glass products. **130**

**Glass Products.** Lancaster Glass Corp., 28 pp, illus. Case histories on the use of glass in television tubes, auto dome lights, desk sets, refrigerator lights and vending machines. **131**

**Industrial Ceramics.** McDanel Refractory Porcelain Co., 4 pp, illus. Briefly describes ceramic pump pistons, combustion tubes, heat reflectors, crucibles and liners. **132**

**Paper Products.** Mosinee Paper Mills Co., 3 pp, illus. Outlines uses and advantages of a flame resistant paper and average physical properties of flat and creped neutral papers. **133**

**Glass-Bonded Mica.** Mycalex Corp. of America, 24 pp, illus. Physical, electrical and thermal properties, and dimensional tolerances of ceramoplastics and glass-bonded micas. **134**

**Carbon and Graphite.** Ohio Carbon Co., 8 pp, illus., No. 1164A. Composition, characteristics, properties and applications of carbon and graphite. **135**

**Glass Fiber Insulation.** Pittsburgh Plate Glass Co., Fiber Glass Div., 4 pp, illus. Advantages of using glass fibers for sound and heat insulation applications. **136**

**Carbon Graphite.** Pure Carbon Co., Inc., 12 pp, illus., No. 55. Catalog on carbon graphite for mechanical applications. **137**

**Coated Fabrics.** Reeves Bros., Inc., 4 pp, illus., No. 107B. Physical properties, dimensions and uses of a neoprene rubber-coated nylon **139**

**Carbon and Graphite.** Speer Carbon Co., 8 pp, illus. General advantages, properties, available grades and other information on a line of carbon and graphite products. **140**

**Carbon and Graphite.** Stackpole Carbon Co., 54 pp, illus., No. 40 C. Properties, and mechanical, chemical, electrical and refractory uses of carbon and graphite. **141**

**Thermal Insulation.** H. I. Thompson Fiber Glass Co., chart. Information on thermal insulations for temperatures from —300 F to 3000 F. **143**

**Synthetic Fiber Felt.** Troy Blanket Mills, 8 pp, illus. Strength, dimensional stability and chemical resistance of a synthetic non-woven material called Troyfelt. **144**

**Carbon, Graphite Products.** National Carbon Co., Div. of Union Carbide Corp., 4 pp, illus., No. 5008. Dimensions and characteristics of carbon, graphite, and impervious carbon and graphite equipment for chemical processing applications. **145**

**Sintered Metallic Oxides.** U. S. Stoneware Co., Alite Div., 8 pp, illus., No. A-7R. Electrical characteristics, size limitations, dimensional tolerances, chemical and heat resistance, and physical properties of sintered metallic oxides. **146**

**Cemented Carbides.** Vascoloy-Ramet Corp., 4 pp, No. 5803. General characteristics, hardness, rupture strength, density and applications of cemented carbides. **147**

**Graphite.** Wickes Corp., U. S. Graphite Co. Div., 8 pp, No. G-12. Properties, applications, and other data on graphite. **148**

*To get literature, use free post cards on pp 585-592*

PROPERTIES OF MATERIALS

# Other Nonmetallics


PAGE

284 Mechanical and Electrical Ceramics—Fired Parts

286 Mica—Sheet, Molded

287 Refractory Ceramics, Cermets—Fired or Sintered Parts

290 Glass (Industrial)—Flat, Pressed, Blown

292 Carbon, Graphite—Molded, Extruded

293 Natural Fibers

294 Synthetic Fibers

298 Inorganic Fibers

299 Woods, Wood-Base Compositions

300 Wool Felts (Mechanical, Filter, Industrial) —Roll

302 Wool Felts (Mechanical, Filter, Industrial) —Sheet

306 Advertisements

282 Suppliers' Literature

## Mechanical and Electrical Ceramics—Fired Parts

| Type → | Polycrystalline Glass (Pyroceram) 9606 | Polycrystalline Glass (Pyroceram) 9608 | Cordierite | Forsterite |
|---|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | | |
| Specific Gravity | 2.60 | 2.50 | 2.29–2.65 | 2.9 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 2.10 | 1.14 | 0.97–2.40 | 1.94–2.40 |
| Coef of Ther Exp, per °F | | | | |
| 68–212 F | $4.0 \times 10^{-6}$ | $0.22–1.1 \times 10^{-6}$ | $2.08 \times 10^{-6}$ | $4.72 \times 10^{-6}$ |
| 68–570 F | $3.16 \times 10^{-6}$ | $0.22–1.1 \times 10^{-6}$ | — | — |
| 68–932 F | $2.7 \times 10^{-6}$ | $0.4–1.1 \times 10^{-6}$ | $1.68 \times 10^{-6}$ | $5.40 \times 10^{-6}$ |
| Thermal Shock Resistance | Good | Good | Good | Moderate |
| Water Absorption, % | 0.00 | 0.00 | 0.02–3.2 | 0.00–0.02 |
| Gas Permeability | Gas-tight | Gas-tight | — | Gas-tight |
| Specific Heat, Btu/lb/°F | 0.185 | 0.190 | — | — |
| **MECHANICAL PROPERTIES** | | | | |
| Mod of Elast in Tension, psi | $17.3 \times 10^6$ | $12.5 \times 10^6$ | $7 \times 10^6$ | — |
| Mod of Rupture, 1000 psi | 20 | 16–23 | 6.8 | 19 |
| Tensile Strength, 1000 psi | — | — | 3.0 | 10 |
| Hardness (Knoop) | 698[d] | 703[d] | 7 | 7.5 |
| Impact Strength (Charpy), in.-lb | | | | |
| ¾ In. Dia | — | — | 7.4 | 7.5 |
| ½ In. Dia | — | — | 4.4 | 2.4–4.0 |
| Compressive Strength, 1000 psi | — | — | 52–95 | 80–85 |
| **ELECTRICAL PROPERTIES** | | | | |
| Volume Resistivity, ohm-cm | | | | |
| 68–77 F | $2 \times 10^{16}$[b] | $6.3 \times 10^{12}$[b] | $>10^{14}$ | $>10^{14}$ |
| 212 F | $1.6 \times 10^{8}$ | $1.3 \times 10^{11}$ | — | $5.0 \times 10^{13}$ |
| 482 F | $10^{10}$ | $1.26 \times 10^{8}$ | — | — |
| 572 F | $2 \times 10^{8}$ | $2 \times 10^{7}$ | — | $7.0 \times 10^{11}$ |
| 662 F | $5 \times 10^{8}$ | $6.31 \times 10^{6}$ | — | — |
| 932 F | $2 \times 10^{7}$ | $3.1 \times 10^{6}$ | — | $1.2 \times 10^{10}$ |
| 1292 F | — | — | — | $1.0 \times 10^{8}$ |
| 1652 F | — | — | — | $3.0 \times 10^{6}$ |
| Dielectric Strength, v/mil | 250–350 | — | 140–230 | 250 |
| Dielectric Constant | | | | |
| 60 Cycles | 5.62[c] | 7.13[c] | — | 6.3 |
| 1 Mc | 5.58 | 6.78 | 4.02–6.23 | 6.2–6.5 |
| 100 Mc | 5.52 | 6.55 | — | 6.1 |
| 10,000 Mc | 5.45 | — | — | 5.8 |
| Dissipation Factor | | | | |
| 60 Cycles | 0.0016[c] | 0.020[c] | — | 0.0014 |
| 1 Mc | 0.0015 | 0.0030 | 0.0010–0.00930 | 0.0002–0.0004 |
| 100 Mc | — | — | — | 0.0003 |
| 10,000 Mc | 0.00033 | 0.0068 | — | 0.0010 |
| Loss Factor | | | | |
| 60 Cycles | 0.009[c] | 0.14[c] | — | 0.009 |
| 1 Mc | 0.009 | 0.026 | 0.0297–0.0579 | 0.001–0.002 |
| 100 Mc | — | — | — | 0.002 |
| 10,000 Mc | 0.002 | 0.045 | — | 0.0058 |
| Te Value, F* | 1400[b] | 815[b] | 1436 | 680–>1832 |
| Temp Coef of Capacitance Chg[f] | — | — | 420 | — |
| **HEAT RESISTANCE** | | | | |
| Max Rec Svc Temp, F | — | — | — | 1832 |
| **USES** | Developed for uniform electrical properties in missile radomes; suitable for high temperature, high frequency applications in electronics | General purpose; line of heatproof cooking-serving ware; telescope mirror blanks | Aircraft firewall connectors, appliance coil supports and terminal blocks, automotive heater cores, hot point insulators, brazing fixture parts, foundry parts, fuel burner tips, thermostat controls | Very low loss insulators, ceramic-to-metal seals (close tolerances obtainable by grinding) |

* Alumina properties are on "Refractories" pages. [b] Extrapolated. [c] 100 cycles. [d] Knoop hardness at 100 gm.
* Te value is the temperature at which a cubic centimeter of the material has a resistance of 1 megohm. [f] 77–185 F, parts per million.

## Mechanical and Electrical Ceramics—Fired Parts

| Type → | Standard Electrical | Steatite | Zircon |
|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | |
| Specific Gravity | 2.37–2.53 | 2.5–2.92 | 3.43–3.86 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.87–1.57 | 1.45–1.94 | 2.88–3.61 |
| Coef of Ther Exp, per °F | | | |
| 68–212 F | $2.00 \times 10^{-6}$ | $3.33–3.99 \times 10^{-6}$ | $1.31–1.84 \times 10^{-6}$ |
| 68–932 F | $2.70 \times 10^{-6}$ | $4.52–5.50 \times 10^{-6}$ | $2.09–2.16 \times 10^{-6}$ |
| Thermal Shock Resistance | Fair | Moderate | Good |
| Water Absorption, % | 0.0–0.1 | 0.0–1.0 | 0.0–9.0 |
| Gas Permeability | Gas-tight | — | — |
| **MECHANICAL PROPERTIES** | | | |
| Mod of Elast in Tension, psi | $10 \times 10^6$ | $13–16 \times 10^6$ | $21 \times 10^6$ |
| Tensile Strength, 1000 psi | 2.5–7.0 | 4.8–15 | 4.5–12 |
| Hardness (Mohs) | 7.0–7.5 | 7.5 | 8 |
| Impact Strength (Charpy), in.-lb | | | |
| ¼ In. Dia | 8.2 | 10.5–14.0 | 8.9–11.4 |
| ½ In. Dia | — | 3.8–5.0 | 5.50–5.64 |
| Flexural Strength, 1000 psi | 5.4–12.0 | 11–20 | 18.5–22.0 |
| Compressive Strength, 1000 psi | 49.1–70.0 | 66–90 | 60–100 |
| **ELECTRICAL PROPERTIES** | | | |
| Volume Resistivity, ohm-cm | | | |
| 68–77 F | $10^{13}–10^{15}$ | $>10^{14}$ | $>10^{14}$ |
| 212 F | $1.2 \times 10^{8}$ [c] | $0.21–>100 \times 10^{13}$ | $2.0 \times 10^{13}$ |
| 570 F | $5.0 \times 10^{6}$ | $0.6–800 \times 10^{8}$ | $5.5 \times 10^{11}$ |
| 930 F | $4.0 \times 10^{5}$ [d] | $0.32–300 \times 10^{6}$ | $5.5 \times 10^{8}$ |
| 1290 F | — | $2.3–500 \times 10^{6}$ | $1.4 \times 10^{7}$ |
| 1650 F | — | $7.0–680 \times 10^{5}$ | $8.2 \times 10^{5}$ |
| Dielectric Strength, v/mil | 55–300 | 145–280 | 60–290 |
| Dielectric Constant | | | |
| 60 Cycles | 5.4–7.0 | 5.9–6.3 | 9.1 |
| 1 Mc | — | 5.5–6.51 | 5.30–9.20 |
| 100 Mc | — | 5.6–6.0 | 8.6 |
| 10,000 Mc | — | 5.3–5.8 | 8.4 |
| Dissipation Factor | | | |
| 60 Cycles | 0.0090–0.0112 | 0.0013–0.0150 | 0.0360 |
| 1 Mc | — | 0.0011–0.0075 | 0.0007–0.0022 |
| 100 Mc | — | 0.0009–0.0028 | 0.0012 |
| 10,000 Mc | — | 0.0014–0.0054 | 0.0027 |
| Loss Factor | | | |
| 60 Cycles | 0.053–0.060 | 0.008–0.090 | 0.327 |
| 1 Mc | — | 0.007–0.0252 | 0.0041–0.0135 |
| 100 Mc | — | 0.005–0.016 | 0.010 |
| 10,000 Mc | — | 0.008–0.030 | 0.023 |
| Te Value, F [a] | 680–842 | 824–1544 | 1292–1598 |
| Temp Coef of Capacitance Chg [b] | 630 | 120 | 175 |
| **HEAT RESISTANCE** | | | |
| Max Rec Svc Temp, F | 1820 | 1832 | 2012 |
| **USES** | Low voltage insulators, vitrified high voltage insulators, wire supports, outlet boxes, lightning arrestors, suspension insulators, x-ray rods and tubes | Aircraft insulators, appliance housings, electric line insulators, tube sockets, electrical instrument spacers and feed-through bushings, fuel igniters, camera and projector rollers, thermostat controls | Aircraft firewall connector plugs and glow plugs; electronic tube sockets, coil forms, spacers, brackets, printed circuits and plates; pump valves, plungers and seats |

[a] Te value is the temperature at which a cubic centimeter of the material has a resistance of 1 megohm.
[b] 77–186 F, parts per million. [c] 392 F [d] 752 F

Other Nonmetallics

## Mica—Sheet, Molded

| Type → | Natural Muscovite | Synthetic Fluor-Phlogopite | Glass-Bonded Synthetic[a] | |
|---|---|---|---|---|
| | | | Insulation | Capacitor |
| **PHYSICAL PROPERTIES** | | | | |
| Specific Gravity | 2.6–3.2 | 2.9 | 3.0, 2.6–3.8 | 3.25, 3.5–3.8 |
| Ther Cond, Btu/hr/sq ft/°F/ft | 0.25–0.36 | 0.3–0.4 | 0.29, 0.23–0.31 | — |
| Coef of Ther Exp, per °F | $1.8 \times 10^{-6}$ | $1.44–2.70 \times 10^{-6}$ | $0.58–0.62 \times 10^{-6}$ | $1.8, 1.8–2.0 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.20 | 0.25 | 0.16, 0.13–0.24 | — |
| Water Absorption | Low | Low | Nil | Nil |
| **MECHANICAL PROPERTIES** | | | | |
| Mod of Elast in Tension, psi | $20–30 \times 10^6$ | $25 \times 10^6$ | $9–12, 7–8 \times 10^6$ | $9–12, 7–8 \times 10^6$ |
| Ten Str, 1000 psi | 40–50 | 45–55 | 6–7, 5–6 | 6, 5 |
| Hardness | | | | |
| Knoop | 90 | 200 | M110–120,[b] M115–130[b] | — |
| Mohs | 3–4 | 3.4 | — | — |
| Impact Str (Izod notched), ft-lb/in. | — | — | 1.8, 0.7 | — |
| Flex Str, 1000 psi | — | — | 15–18, 10–15 | 12–15, 10–15 |
| Compr Str, 1000 psi | >150 | >150 | 35–42, 20–25 | 35–42, 20–25 |
| **ELECTRICAL PROPERTIES** | | | | |
| Vol Res, ohm-cm | $10^{13}–10^{17}$ | $10^{13}–10^{17}$ | $10^{14}–10^{16}, 10^{14}–10^{17}$ | $10^{14}, 10^{14}$ |
| Dielec Str (step by step, ¼ in.), v/mil | 1000–2000 | 1000–2000 | 400–600, 400–500 | 270–400, 300–400 |
| Dielec Const | | | | |
| 60 Cycles | 5.4–8.7 | 6.5 | 7.5–7.6, 7.0–9.5 | — |
| $10^6$ Cycles | 5.4–8.7 | 6.5 | 7.4–7.9, 6.9–9.2 | 10–25, 10–40 |
| Dissip Factor | | | | |
| 60 Cycles | 0.0025 | 0.002–0.004 | 0.0035–0.0070, 0.007–0.050 | 0.0020–0.0040, 0.0025 |
| $10^6$ Cycles | 0.0001–0.0004 | 0.0001–0.0003 | 0.0015–0.0020, 0.0015–0.0120 | 0.0035 |
| Arc Resistance, sec | High | High | 300, 250 | 300, 250 |
| **FABRICATING PROPERTIES** | | | | |
| Machinability | Fair, readily punched | Fair, punches more readily than Natural | Fair to good; poor | Fair to good; poor |
| Moldability | — | — | Fair; good | Fair; good |
| **HEAT RESISTANCE** | | | | |
| Max Rec Svc Temp, F | 1110 | 1400–1800 | 600–1000[c], 500–800[c] | 600–700, 500–600 |
| Heat Dist Temp (264 psi), F | — | — | 850, 700 | 800, 650 |
| Ther Shock Res | — | — | Moderate | Moderate |
| **CHEMICAL RESISTANCE** | Good res to most chemicals and molten materials exc hydrofluoric acid. Oils generally cause delamination | Slightly better chemical res than Natural; high res to oils. High res to high pressure, high temp water | Good res to organic solvents; poor res to strong acids and alkalis | Good res to organic solvents; fair res to strong acids and alkalis |
| **USES** | Furnace peepholes, boiler gage glass; capacitors, tube spacers | Experimental high temp tube spacers and waveguide windows; used to make glass-bonded synthetic mica | Electromechanical devices, high temp (660–900 F) insulators requiring high stability (e.g., computer parts) | Stable capacitors, tuners; high temp uses |

[a] The first value or range in each column refers to glass-bonded mica produced by compression molding, the second to transfer molding.
[b] Rockwell.
[c] A modified type with a max svc temp of 1550 F is called "ceramoplastic" by its producer.

# Refractory Ceramics and Cermets—Fired or Sintered Parts

**HIGH ALUMINA CERAMICS[a]**

| Type (% alumina) → | 85% | 95% | 99+% |
|---|---|---|---|
| **PHYSICAL PROPERTIES** | | | |
| Specific Gravity | 3.45 | 3.65 | 3.85 |
| Ther Cond (200 F), Btu/hr/sq ft/°F/ft | 6.2 | 10.3 | 10.7 |
| Coef of Ther Exp, per °F | | | |
| 77–390 F | $3.1 \times 10^{-6}$ | $3.7 \times 10^{-6}$ | — |
| 77–750 F | $3.7 \times 10^{-6}$ | $4.0 \times 10^{-6}$ | — |
| 77–1100 F | $3.9 \times 10^{-6}$ | $4.3 \times 10^{-6}$ | $4.3 \times 10^{-6}$ |
| 77–1470 F | $4.1 \times 10^{-6}$ | $4.5 \times 10^{-6}$ | — |
| 77–1830 F | $4.3 \times 10^{-6}$ | $4.7 \times 10^{-6}$ | — |
| Water Absorption, % | 0.0 | 0.0 | 0.0 |
| Max Rec Svc Temp, F | 2460 | 3000 | 3540 |
| **ELECTRICAL PROPERTIES** | | | |
| Dielec Str, v/mil | 200 | 250 | 300 |
| Dielec Const (77 F, 1 mc) | 8.2 | 8.9 | 9.6 |
| Power Factor (77 F, 1 mc) | 0.0009 | 0.00035 | 0.00027 |
| Loss Factor (77 F, 1 mc) | 0.007 | 0.003 | 0.003 |
| Te Value, F | 1560 | 1960 | 2012 |
| **MECHANICAL PROPERTIES** | | | |
| Mod of Elast in Tension, psi | $32 \times 10^6$ | $40 \times 10^6$ | $50 \times 10^6$ |
| Ten Str, 1000 psi | 20 | 30 | 39 |
| Flex Str, 1000 psi | 41 | 45 | 47 |
| Compr Str, 1000 psi | 250 | 300 | 400 |
| Hardness | | | |
| Mohs | 9 | 9 | 9 |
| Knoop | 1450 | 1750 | — |
| Impact Str (Charpy), in.-lb | 6.5 | 7.0 | — |

[a] The values given are not maximum values and are dependent upon the minor components or fluxes used as well as a number of other factors.

**ALUMINA CERMETS**

| Type → | Chromium-Alumina | Molybdenum-Chromium-Alumina[a] |
|---|---|---|
| **PHYSICAL PROPERTIES** | | |
| Density, lb/cu in. | 0.21 | 0.22 |
| Porosity, % | <0.25 | <0.25 |
| Melting Point (approx), F | 3362 | — |
| Ther Cond, Btu/hr/sq ft/°F/ft | 29[a] | — |
| Coef of Ther Exp, per °F | $4.7 \times 10^{-6}$[b] | $5.2 \times 10^{-6}$[c] |
| Spec Ht (calc), Btu/lb/°F | 0.16 | 0.14 |
| Poisson's Ratio | 0.22 | 0.25–0.27 |
| **MECHANICAL PROPERTIES** | | |
| Mod of Elast in Tension, $10^6$ psi | $41 \times 10^6$ | $37–39 \times 10^6$ |
| Ult Ten Str, 1000 psi | | |
| Rm Temp | 21 | — |
| 800 F | 20.5 | — |
| 1200 F | 20 | — |
| 1500 F | 19.7 | — |
| 1800 F | 16.8 | — |
| 2000 F | 11.7 | — |
| Hardness (Rockwell) | C37 | C45–55 |
| Mod of Rupture, 1000 psi | | |
| Rm Temp | 45 | 55[d] |
| 1800 F | 27 | 55 |
| 2100 F | 18 | 29 |
| 2400 F | 4.6 | 12 |
| Compr Str, 1000 psi | 110 | 240 |
| Mod of Rigidity, psi | $17 \times 10^6$ | $15 \times 10^6$ |
| Shear Str, 1000 psi | 40 | — |
| Bulk Modulus, psi | $21 \times 10^6$ | $26 \times 10^6$ |

[a] At 500 F. [b] At 32–1832 F. [c] At 68–1472 F.
[d] Addition of tungsten raises room temperature modulus of rupture to about 70,000 psi.

**REFRACTORY OXIDES**

| Type → | Beryllia (BeO) | Calcia (CaO) | Magnesia (MgO) | Thoria ($ThO_2$) | Zirconia (stabilized $ZrO_2$) | Silica (vitreous $SiO_2$) |
|---|---|---|---|---|---|---|
| Melting Point, F | 4620 | 4710 | 5070 | 6000 | 4710 | — |
| Ther Cond (at spec temp and porosity), Btu/hr/sq ft/°F/ft | 9.52 (2190 F, 5–10%) | 4.12 (1830 F, 9%) | 1.47 (2190 F, 22%) | 0.0 (2190 F, 17%) | 0.53 (2190 F, 28%) | 0.80 (0.9%) |
| Coef of Ther Exp, per °F | $52.8 \times 10^{-7}$ (68–2550 F) | $75.5 \times 10^{-7}$ (68–2190 F) | $77.8 \times 10^{-7}$ (68–2550 F) | $52.8 \times 10^{-7}$ (68–2550 F) | $30.6 \times 10^{-7}$[a] (68–2190 F) | $2.8 \times 10^{-7}$ (68–2280 F) |
| Max Use Temp in Oxidizing Atm, F | 4350 | 4350 | 4350 | 4890 | 4530 | — |
| Hardness (Mohs) | 9 | 4.5 | 6 | 7 | 7–8 | — |
| Thermal Shock Resistance | Excellent | Fair | Fair | Poor | Fair | Excellent |
| Stability in — | | | | | | |
| Reducing Atmosphere | Excellent | Poor | Poor | Good | Good | Fair |
| Carbon | Excellent | Poor | Good | Fair | Fair | Good |
| Acid Slags | — | Poor | Poor | Poor | Good | Good |
| Basic Slags | Fair | Fair | Good | Good | Poor | — |
| Metals | Good | Fair | Fair | Excellent | Good | — |

[a] Depends on degree of stabilization.

*continued on next page*

## Refractory Ceramics and Cermets—Fired or Sintered Parts

**CARBIDES**

| Type → | Silicon Carbide | | | Boron Carbide |
|---|---|---|---|---|
| | Silicate-Bonded | Silicon Nitride-Bonded | Densified | |
| PHYSICAL PROPERTIES | | | | |
| Density, lb/cu in. | 0.093 | 0.104 | 0.112 | 0.087[a] |
| Porosity, % | 9–17 | 6–10 | Negligible | Negligible |
| Ther Cond (2200 F), Btu/hr/sq ft/°F/ft | 9 | 10 | 25[b] | 16 |
| Coef of Ther Exp (0–2550 F), per °F | $2.4 \times 10^{-6}$ | $2.4 \times 10^{-6}$ | $2.17 \times 10^{-6}$ | $1.73 \times 10^{-6}$ |
| Specific Heat (0–2550 F), Btu/lb/°F | 0.285 | 0.288 | 0.331 | — |
| Max Service Temperature, F | | | | |
| Inert Atmosphere | 3200 | 3200 | 4000 | 4100 |
| Oxidizing Atmosphere | 2900 | 3000 | 3000 | 1000 |
| MECHANICAL PROPERTIES | | | | |
| Mod of Elast in Tension (77 F), psi | $13.2 \times 10^6$ | $17 \times 10^6$ | $68 \times 10^6$ | $42 \times 10^6$ |
| Tensile Strength (77 F), 1000 psi | Very low | 3 | 25 | 22.5 |
| Compressive Strength (77 F), 1000 psi | 15 | 20 | 150 | 420 |
| Modulus of Rupture (77 F), 1000 psi | 2.2 | 5.5 | 24 | 50 |

[a] Boron carbide is available in densities ranging from 0.069 to 0.091 lb per cu in. [b] 1832 F.

**CARBIDE-BASE CERMETS**

| Type (base) → | Titanium Carbide (TiC)[a] | Tungsten-Titanium Carbide ($WTiC_2$)[b] | Tungsten Carbide (WC) | Chromium Carbide ($Cr_4C$, $Cr_7C_3$, $Cr_3C_2$)[c] |
|---|---|---|---|---|
| Density, lb/cu in. | 0.20–0.26 | 0.38–0.47 | 0.47–0.55 | 0.25–0.29 |
| Ther Cond (68 F), Btu/hr/sq ft/°F/ft | — | 16.5–32.9 | 25.7–50.1 | — |
| Coef of Ther Exp (68–1200 F), per °F | $4.3–7.5 \times 10^{-6}$ | $3.5–4.0 \times 10^{-6}$ | $2.5–3.9 \times 10^{-6}$ | $5.8–6.3 \times 10^{-6}$[f] |
| Electrical Conductivity, % IACS | 1.34–6.0 | 4.3–5.8 | 5.0–10.1 | 2.58–2.78 |
| Mod of Elast in Tension, psi | | | | |
| 70 F | $42–57 \times 10^6$ | $65.5–80.6 \times 10^6$ | $61.6–94.3 \times 10^6$ | — |
| 1600–1800 F | $33–48 \times 10^6$ | — | — | — |
| Tensile Strength, 1000 psi[d] | | | | |
| 75 F | 26–134 (0–61) | 118–145 | 130[e] | 36–37 (0) |
| 1500 F | 45–94 (0–2.7) | — | — | 20–42 (0.2) |
| 1800 F | 35–72 (0–2.4) | — | — | — |
| Hardness (Rockwell) | A73–A91 | A90–A93 | A85–A93 | A86.5–A89 |
| Impact Strength (unnotched Charpy), ft-lb | | | | |
| 75 F | 1.5–16 | 5.3–8.9 | — | — |
| 1800 F | 2.5–16 | — | — | — |
| Transverse Rupture Strength, 1000 psi | 122–236 | 125–350 | 175–460 | 100–120 |
| Stress-Rupture Strength (100 hr, 1800 F), 1000 psi | 8–28 | — | — | — |
| Compressive Strength, 1000 psi | 265–450 | 585–705 | 518–800 | 422–480 |

[a] Property range covers grades ranging from 17.5% to 90% TiC with different binder metal contents.
[b] Property range covers various grades of different carbide-metal proportions.
[c] The type of chromium carbide and the type of binder metal affects properties.
[d] Elongation (%) in parenthesis. [e] Typical of one grade. [f] 68–576 F.

# Refractory Ceramics and Cermets—Fired or Sintered Parts



## OTHER CARBIDES

| Type → | Beryllium Carbide ($Be_2C$) | Titanium Carbide (TiC) | Columbium Carbide (CbC) | Tantalum Carbide (TaC) | Zirconium Carbide (ZrC) |
|---|---|---|---|---|---|
| Ther Cond (68–795 F), Btu/hr/sq ft/°F/ft | 12.1 | 9.9[a] | 8.23[a] | 12.8[a] | 11.9[a] |
| Coef of Ther Exp (77–1472 F), per °F | $5.8 \times 10^{-6}$ | $4.1 \times 10^{-6}$ | — | $4.6 \times 10^{-6}$ | $3.7 \times 10^{-6}$ |
| Electrical Resistivity, ohm-cm[a] | 1.1 | $1.05 \times 10^{-4}$ | $7.4 \times 10^{-5}$ | $2 \times 10^{-5}$ | $6.34 \times 10^{-5}$ |
| Hardness (Mohs') | 9+ | 8–9 | 9–10 | 9+ | 8–9 |
| Compressive Strength, 1000 psi[a] | 105 | 109 | — | — | 238 |
| Mod of Rupture, 1000 psi[a] | 16 | — | — | — | — |
| Ther Shock Res (air quenched), cycles at designated temp range (F) | 4 at 2000–1470 | — | — | — | — |
| Fabrication Methods | Hot pressing, steel die pressing and sintering, hydrostatic pressing and sintering | Hot pressing, steel die pressing and sintering | Hot pressing, steel die pressing and sintering | Hot pressing, steel die pressing and sintering | Hot pressing, steel die pressing and sintering |

[a] Room temperature.

## MOLYBDENUM DISILICIDE ($MoSi_2$)

| Type → | Cold Pressed, Sintered | Hot Pressed |
|---|---|---|
| **PHYSICAL PROPERTIES** | | |
| Density, lb/cu in. | 0.216 | 0.224 |
| Melting Point, F | 3685 ±90 | 3685 ±90 |
| Electrical Resistivity, microhm-cm | | |
| 77 F | — | 21.5–27.2 |
| 2900 F | — | 75–80 |
| Coef of Ther Exp (78–2700 F), per °F | — | $5.1 \times 10^{-6}$ |
| **MECHANICAL PROPERTIES** | | |
| Tensile Strength, 1000 psi | | |
| 1800 F | — | 40 |
| 2000 F | — | 42 |
| 2200 F | — | 43 |
| 2400 F | — | 41 |
| Hardness | | |
| Rockwell | C57[a] | A80–87[b] |
| Knoop (1 kg) | 1065 | 850–870 |
| Compressive Strength, 1000 psi | 100[c] | 350 |
| Modulus of Rupture, 1000 psi | | |
| 77 F | 51 | 36–57 |
| 1800 F | 51–67 | — |
| 2000 F | 51–86 | 72 |
| 2200 F | [d] | 55 |
| Stress-Rupture Strength (100 hr), 1000 psi | | |
| 1600 F | — | 35 |
| 1800 F | — | 29 |
| 1900 F | — | 13.5 |
| 2000 F | — | 8.5 |

[a] Superficial hardness.
[b] Some indentation cracking.
[c] Cast specimens.
[d] Test not applicable because bars showed too much plasticity.

## NITRIDES

| Type → | Boron Nitride | Silicon Nitride[a] |
|---|---|---|
| **PHYSICAL PROPERTIES** | | |
| Density, lb/cu in. | | |
| Theoretical | 0.081 | 0.124 |
| Actual | 0.076 | 0.111 |
| Melting Point, F | >3000[b] | 3452[c] |
| Ther Cond, Btu/hr/sq ft/°F/ft | 16.6, 15.4[d] | 0.90[c] |
| Coef of Ther Exp (70–1800 F), per °F | 4.3 | 1.37 |
| **MECHANICAL PROPERTIES** | | |
| Mod of Elast in Tension, $10^6$ psi | | |
| 75 F | $12.4 \times 10^6$ | — |
| 1300 F | $1.5 \times 10^6$ | — |
| Hardness | | |
| Mohs | 2 | — |
| Rockwell | — | A99 |
| Modulus of Rupture, 1000 psi | | |
| 75 F | 15.9 | 10 |
| 1300 F | 3.8 | — |
| **ELECTRICAL PROPERTIES** | | Not applicable |
| Volume Resistivity, ohm-cm | | |
| 75 F | $1.7 \times 10^{13}$ | |
| 900 F | $2.3 \times 10^{10}$ | |
| 1800 F | $3.1 \times 10^4$ | |
| Dielectric Constant ($10^2$–$10^8$ cps) | 4.15 | |
| Dissipation Factor | | |
| $10^2$ Cycles | 0.00103 | |
| $10^6$ Cycles | 0.00020 | |
| $10^{10}$ Cycles | 0.0003 | |

[a] Mechanical properties are given for direction parallel to direction of forming pressure. Values perpendicular to this direction may be one-half to one-quarter of these values.
[b] May be used continuously at 3000 F, and higher under special conditions.
[c] Sublimes.
[d] Values at 570 F and 1800 F, respectively.
[e] 400–2400 F.

## Glass (Industrial)—Flat, Pressed, Blown

| Type → | Fused Silica | 96% Silica | Soda-Lime Glasses | | Alumino-Silicate |
|---|---|---|---|---|---|
| | | | Plate | General Purpose | |
| **PHYSICAL PROPERTIES** | | | | | |
| Density, lb/cu in. | 0.079 | 0.078 | 0.09 | 0.089 | 0.091 |
| Softening Point, F | 3050 | 2800 | 1330 | 1285 | 1675 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 0.80 | 0.80 | 0.53 | 0.53 | — |
| Coef of Ther Exp (32–570 F), per °F | $0.30 \times 10^{-6}$ | $0.45 \times 10^{-6}$ | $4.8 \times 10^{-6}$ | $5.1 \times 10^{-6}$ | $2.3 \times 10^{-6}$ |
| Spec Ht, Btu/lb/°F | 0.185 | 0.178 | 0.20 | 0.20 | 0.180 |
| Elec Res (212 F), ohm-cm | $>10^{15}$ | $>10^{15}$ | — | $4 \times 10^{9}$ | $>10^{15}$ |
| Power Factor (68 F, 1 mc), % | 0.001 | 0.02–0.04 | 0.80 | 0.90 | 0.16 |
| Dielec Const (68 F, 1 mc) | 3.8 | 3.8 | 7.4 | 7.2 | 6.3 |
| Ther Stress Res, °F[a] | — | 390 | — | 65 | 85 |
| Ther Shock Res, °F[b] | Very high | Very high | 135 | 125 | 240 |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, psi | $10.2 \times 10^{6}$ | $9.7 \times 10^{6}$ | $9–10 \times 10^{6}$ | $9–10 \times 10^{6}$ | $12.7 \times 10^{6}$ |
| Normal Work Stress (annealed), psi | 1000 | 1000 | 1000 | 1000 | 1000 |
| Max Rec Svc Temp, F | | | | | |
| Annealed | 1650 | 1500 | 900 | 840 | 1200 |
| Tempered | — | — | 550 | 480 | 840 |
| **THERMAL TREATMENT** | | | | | |
| Annealing Temp (stress relief), F | 2080 | 1670 | 1010 | 950 | 1315 |
| **FABRICATING PROPERTIES** | | | | | |
| Workability | Glass can be ground or polished without great difficulty. Machining limited to sawing or drilling. Sawing readily accomplished with an impregnated wheel. Drilling is difficult, but is done with special carbide-tipped drills using kerosene as a lubricant | | | | |
| Joining | Glass can be joined by heat sealing using a blast lamp, a gas torch or electric heating. Parts must have closely similar coefficients of expansion; otherwise, intermediate pieces having intermediate coefficients must be used. Glass-to-metal seals are also made by this latter process | | | | |
| **CHEMICAL RESISTANCE** | Glass is attacked by hydrofluoric acid, hot concentrated phosphoric acid and strong alkalis. It is resistant to most other chemicals | | | | |
| **USES** | Ultraviolet energy transmission, chemical apparatus, thermocouple protection tubes, laboratory apparatus | Ultraviolet energy transmission, chemical reaction vessels, thermocouple protection tubes, laboratory apparatus | Sheet and plate glass, molded glassware, bulbs for electric lamps, bottles, vials, fluorescent lamp tubing | | |

[a] Measured by subjecting the two sides of a tube or constrained plate to a temperature differential. Index is the differential that causes a stress of 1000 psi on cooler surface.

[b] Measured by heating squares of annealed glass, 6 by 6 by ¼ in., to a uniform temperature and dropping into cold water. Index is maximum temperature differential at which no breakage occurs.

# Glass (Industrial)—Flat, Pressed, Blown

| Type → | Borosilicate Glasses | | | Lead Silicate Glasses | |
|---|---|---|---|---|---|
| | Low Expansion Chemical Resistant | Baking and Kovar Sealing | Low Electrical Loss | Lamp Tubing | High Lead |
| **PHYSICAL PROPERTIES** | | | | | |
| Density, lb/cu in. | 0.080 | 0.081–0.082 | 0.077 | 0.110 | 0.154 |
| Softening Point, F | 1500 | 1300–1425 | — | 1160 | 1075 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 0.67 | — | 0.67 | 0.50 | 0.45 |
| Coef of Ther Exp (32–570 F), per °F | $1.85 \times 10^{-6}$ | $2.0–2.5 \times 10^{-6}$ | $1.8 \times 10^{-6}$ | $5.0 \times 10^{-6}$ | $5.1 \times 10^{-6}$ |
| Spec Ht, Btu/lb/F | 0.195 | 0.195 | — | 0.17 | 0.16 |
| Elec Res (212 F), ohm-cm | $10^{13}$ | $3 \times 10^{13}$ | $>10^{15}$ | $10^{14}$ | $>10^{15}$ |
| Power Factor (68 F, 1 mc), % | 0.46 | 0.26–0.28 | 0.06 | 0.16 | 0.09 |
| Dielec Const (68 F, 1 mc) | 4.6 | 4.7–5.1 | 4.0 | 6.6 | 9.5 |
| Ther Stress Res, °F[a] | — | — | — | 65 | — |
| Ther Shock Res, °F[b] | 320 | — | — | 120 | — |
| **MECHANICAL PROPERTIES** | | | | | |
| Mod of Elast in Tension, psi | $9.8 \times 10^6$ | — | $6.8 \times 10^6$ | $9.0 \times 10^6$ | $7.6 \times 10^6$ |
| Normal Work Stress (annealed), psi | 1000 | 1000 | 1000 | 1000 | 1000 |
| Max Rec Svc Temp, F | | | | | |
| Annealed | 900 | 900–840 | 810 | 720 | 720 |
| Tempered | 550 | 420–500 | 450 | 380 | 360 |
| **THERMAL TREATMENT** | | | | | |
| Annealing Temp (stress relief), F | 1020 | 890–975 | 910 | 800 | 800 |
| **FABRICATING PROPERTIES** | | | | | |
| Workability | Glass can be ground or polished without great difficulty. Machining limited to sawing or drilling. Sawing readily accomplished with an impregnated wheel. Drilling is difficult, but is done with special carbide-tipped drills using kerosene as a lubricant | | | | |
| Joining | Glass can be joined by heat sealing using a blast lamp, a gas torch or electric heating. Parts must have closely similar coefficients of expansion; otherwise, intermediate pieces having intermediate coefficients must be used. Glass-to-metal seals are also made by this latter process | | | | |
| **CHEMICAL RESISTANCE** | Glass is attacked by hydrofluoric acid, hot concentrated phosphoric acid and strong alkalis. It is resistant to most other chemicals | | | | |
| **USES** | Heat exchanger tubes, chemical apparatus, cooking ware, electrical insulators, sight and gage glasses, containers for chemicals and medicines, metal sealing, industrial piping, industrial glassware requiring thermal resistance, special lighting ware, heat resisting lenses | | | Lamp tubing, electrical and electronic applications, thermometer tubing, metal sealing | Electrical capacitors, x-ray shielding |

[a] Measured by subjecting the two sides of tube or constrained plate to a temperature differential. Index is the differential that causes a stress of 1000 psi on cooler surface.

[b] Measured by heating squares of annealed glass, 6 by 6 by ¼ in., to a uniform temperature and dropping into cold water. Index is maximum temperature differential at which no breakage occurs.

## Carbon and Graphite—Molded, Extruded

| Material → | Carbon (Petroleum coke base) | Graphite |
|---|---|---|
| **PHYSICAL PROPERTIES** | | |
| Density, lb/cu ft | 93.3–102.0 | 90–116 |
| Ther Cond (212 F), Btu/hr/sq ft/°F/ft | 3–5 | 70–120 |
| Coef of Ther Exp (70–212 F), per °F | 1.3–1.5 x $10^{-6}$ | 1.0–1.3 x $10^{-6}$ |
| Specific Heat (100 F), Btu/lb/°F | 0.18 | 0.18 |
| **MECHANICAL PROPERTIES**[d] | | |
| Mod of Elast in Tension, psi | 1.6–2.3 x $10^{6}$ | 0.5–1.8 x $10^{6}$ |
| Tensile Strength, psi | 900–1100 | 440–2000 |
| Compressive Strength, psi | 6300–9000 | 1800–8500 |
| Flexural Strength, psi | 2500–3000 | 800–3300 |
| Hardness (scleroscope) | 30–50 | 8–45 |
| **ELECTRICAL PROPERTIES** | | |
| Electrical Resistivity (68 F), microhm-cm | 3500–4600 | 800–1300 |
| Contact Resistance, ohms/sq in. | | |
| Against Carbon | 0.0058, 0.0026, 0.0017[a] | — |
| Against Copper | 0.0133, 0.0093, 0.0042[a] | 0.000704, 0.000315, 0.000162, 0.0000555[b] |
| Against Brass | 0.038, 0.012, 0.0052[a] | 0.00092, 0.000214, 0.000109[c] |
| Against Aluminum | 0.138, 0.078, 0.015[a] | 0.0448, 0.0067, 0.0020[c] |
| Against Graphite | — | 0.000473, 0.000175, 0.000064, 0.000031[b] |
| Against Steel | — | 0.01309, 0.00438, 0.00177, 0.000737[b] |
| **FABRICATING PROPERTIES** | Powdered material mixed with binder and shaped by molding or extrusion, then baked at approx 1800 F for carbon, 5500 F for graphite | |
| **CHEMICAL RESISTANCE** | Carbon begins to oxidize in air at approximately 630 F and graphite at approximately 810 F, although the rate of oxidation is not rapid even at high temperatures. With a steam or a carbon dioxide atmosphere, temperature can be raised above a red heat before excessive oxidation occurs. Alkalis in solution do not attack these materials but fused hydroxides and carbonates attack them at high temperatures. They are not attacked by dilute acids, including hydrofluoric, but strongly oxidizing chemicals will attack them | |
| **USES**[e] | Mechanical: sealing rings, pump and valve parts, bearings, pistons, and piston rings. Electrical: battery carbons, contacts, welding carbons, anodes, brushes for electrical machines. Refractory: linings, molds, continuous casting dies, furnace boats, brazing jigs. Chemical: pipe, pumps, fittings, heat exchangers, valves, towers and accessories, porous filtering media. Nuclear: neutron moderator, reflector, structural, fuel element matrix | |

[a] Pressures of 5, 25 and 75 psi, respectively.
[b] Pressures of 25, 150, 400 and 1000 psi, respectively.
[c] Pressures of 25, 150 and 400 psi, respectively.
[d] Strength of graphite generally increases with increasing temp.
[e] There are now available 1) special carbon-graphite mixtures for mechanical applications (especially seal rings) and 2) flexible graphitized industrial textiles for a variety of applications requiring the properties of graphite plus flexibility.

## Natural Fibers

| Type → | Cotton | Bast | | | | Hard | | | Animal | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Flax | Jute | Hemp | Ramie | Manila (abaca) | Sisal | Henne-quin | Wool | Horse-hair | Silk |
| NATURE OF FIBER | | | | | | | | | | | |
| Length, in. | ½–2½ | 6–40 | 10–60 | 40–80 | 15–25 | 20–40 | 24 | 20 | 1½–15 | 1–25 | Filament |
| Width, μ | 17 | 16 | 17 | 20 | 47 | 19 | 19 | 20 | 28 | 100 | 11 |
| Cross Section | Flat tube | Tube | Bunched cells | — | Flat tube | Bunched cells | Bunched cells | Bunched cells | Round | Round | Round |
| PHYSICAL AND MECHANICAL PROPERTIES | | | | | | | | | | | |
| Specific Gravity | 1.55 | 1.50 | 1.48 | 1.48 | 1.55 | — | — | — | 1.30 | 1.30 | 1.25–1.35 |
| Breaking Tenacity, gm/den | | | | | | | | | | | |
| 70 F, 65% RH | 3.0–4.9 | 6.3 | 3.0–5.9 | 5.9–6.9 | 6.5 | 6.0–7.5 | 4.1 | 3.0–3.5 | 1.0–1.7 | — | 2.8–5.2 |
| Wet | 3.3–6.37 | — | — | — | — | 6.0–8.5 | — | 2.5–3.0 | 0.76–1.63 | — | 2.1–4.9 |
| Ten Str (70 F, 65% RH), 1000 psi | 44–109 | 115 | 57–112 | 112–132 | 130 | 125 | 100–120 | — | 20–29 | — | 45–83 |
| Breaking Elongation, % | | | | | | | | | | | |
| 70 F, 65% RH | 3–7 | 3 | — | 2–6 | 3–6 | 2–3 | 2–2.5 | — | 25–35 | — | 13–31 |
| Wet | — | — | — | — | — | — | — | — | 25–50 | — | — |
| Stiffness (avg), gm/den[a] | 57–60 | 270 | 185 | 200 | 167 | 175 | 127 | — | 3.9 | — | 18 |
| Strain Recovery (at 2%), %[b] | 74, 45 (5%) | 65 | 74 (1%) | — | 52 | — | — | — | 99, 63 (20%) | 99, 63 (20%) | 92 |
| Toughness (avg), gm-cm/den-cm | 0.15 | 0.09 | 0.03 | — | — | — | — | — | 0.25 | — | 0.44 |
| Moisture Regain (70 F, 65% RH), % | 7 | 12 | 13.75 | 11.75 | 12 | — | — | — | 16 | — | 11 |
| RESISTANCE TO ENVIRONMENTS | | | | | | | | | | | |
| Acids | | | | | | | | | | | |
| Strong | Poor | Poor | Poor | Poor | Poor | Poor | Poor | Poor | Good[d] | — | Poor |
| Weak | Poor (hot) | Poor | — | Poor | — | — | — | — | Good | — | Fair |
| Alkalis | | | | | | | | | | | |
| Strong | Exc | Good | Good | Good | Good | Good | Good | Good | Poor | Poor | Poor |
| Weak | Exc | Good | Good | Good | Good | Good | Good | Good | Attacked | Poor | Poor (hot) |
| Other Chemicals | Show generally good resistance to organic solvents; cotton bleached by hyperchlorites and peroxides; swells and disintegrates in cuprammonium hydroxide | | | | | | | | Bleached by perox-ides or $SO_2$ | Resistant | Resistant |
| Heat | Good to 275 F | Good to 275 F | — | Good to 275 F | Good to 275 F | — | — | — | Good to 212 F | — | Disinte-grates at 340 F |
| Sunlight (prolonged exposure) | Weak-ened | None | None | None | None | None | None | None | Weak-ened | Weak-ened | Weak-ened |
| Microorganisms | Poor | Very good | Good | Good | Exc | Good | Poor | Poor | Fair | Fair | Good |
| Flame[c] | Burns | Burns | Burns | Burns | Burns | Burns | Burns | Burns | Slow burn | Slow burn | Burns |

[a] Ratio of breaking stress to breaking strain (i.e., gm/den to rupture divided by strain in cm/gage cm at breaking stress).
[b] Recovery after 2% strain, except where specific percentage strain is given in parentheses.
[c] Basic flammability of untreated fiber.
[d] Except hot $H_2SO_4$.

## Synthetic Fibers

| Type → | Regenerated Cellulose (rayons) | | | | Cellulose Esters | | Fluorocarbon |
|---|---|---|---|---|---|---|---|
| | Viscose | | Saponified Acetate | | | | |
| | Regular to Medium Tenacity | High Tenacity | Fortisan | Fortisan 36 | Cellulose Acetate | Cellulose Triacetate (Arnel) | TFE (Teflon) |
| **NATURE OF FIBER** | | | | | | | |
| Length, in. | Staple, filament | Filament | Filament | | Staple, filament | Staple, filament | Filament |
| Width, μ | 8.4–4.3 | 10–15 | 3–9 | | 11–46 | — | — |
| Cross Section | Irregular | Irregular | Irregular | | Clover leaf | Clover leaf | Circular |
| **PHYSICAL AND MECHANICAL PROPERTIES** | | | | | | | |
| Specific Gravity | 1.46–1.52 | — | 1.5 | 1.5 | 1.32 | 1.3 | 2.3 |
| Breaking Tenacity, gm/den | | | | | | | |
| 70 F, 65% RH | 1.5–3.2 | 3.0–5.0 | 6–7 | 8 | 1.3–1.5 | 1.2–1.4 | 1.6 |
| Wet | 0.7–1.9 | 1.9–3.6 | 5.1–6.0 | 6.0–6.4 | 0.8–1.2 | 0.8–1.0 | 1.6 |
| Ten Str (70 F, 65% RH), 1000 psi | 29–65 | 65–105 | 136 | 155 | 22–28 | 20–26 | 47 |
| Breaking Elongation, % | | | | | | | |
| 70 F, 65% RH | 15–30 | 9–22 | 6 | 6.2 | 23–34 | 22–28[d] | 13 |
| Wet | 17–40 | 14–30 | 6 | 6 | 30–45 | 30–40 | 13 |
| Stiffness (avg), gm/den[a] | 11.1–16.6 | 25.5–29 | 117 | 135 | 5.5 | 5.2 | 12 |
| Strain Recovery (at 2%), %[b] | 30–97 | 70–100 | 100 (20%), 60 (40%) | 85, 70 (5%) | 48–65 (4%) | 88 (3%), 43 (10%) | — |
| Toughness (avg), gm-cm/den-cm | 0.19–0.21 | 0.22–0.30 | 0.21 | 0.26 | 0.17 | 0.16 | 0.12 |
| Moisture Regain (70 F, 65% RH), % | 13 | 13 | 10.7 | 9.6 | 6 | 3.2 | None |
| **RESISTANCE TO ENVIRONMENTS** | | | | | | | |
| Acids | | | | | | | |
| Strong | Similar to cottons, i.e., disintegrated by hot dilute or cold concentrated acids | | Similar to cotton | | Decomposed | Similar to acetate | Inert |
| Weak | | | | | Good | | |
| Alkalis | | | | | | | |
| Strong | Swell; strength reduced | | | | Saponifies | Saponifies | Inert |
| Weak | Good | | | | Res (cold) | Res (cold) | Inert |
| Other Chemicals | Attacked by strong oxidizing agents; not damaged by hypochlorite or peroxide bleaches | | | | Similar to viscose | Similar to viscose | Only affected by alkali metals and some hot, pressurized halogenated hyd. |
| Heat | Lose strength at 300 F. Decompose at 350–400 F | | | | Sticky at 350–375 F; softens at 400–475 F; melts at 500 F | When heat treated will not stick at 480 F; melts at 575 F | Nondegraded at 400 F; extremely slow sublimation at 55 F |
| Sunlight (prolonged exposure) | Weakened | | Resistant | | Weakened | Weakened | Inert |
| Microorganisms | Attacked | | Attacked | | Resistant | Resistant | Inert |
| Flame[c] | Highly flammable | | Burns | | Burns slowly | Burns slowly | Self-exting |

[a] Ratio of breaking stress to breaking strain (i.e., gm/den to rupture divided by strain in cm/gage cm at breaking stress).
[b] Recovery after 2% strain except where specific percentage strain is given in parentheses.
[c] Basic flammability of untreated fiber. [d] For filament; 35–40% for staple.

## Synthetic Fibers

| Type → | Acrylics | | | | | | |
|---|---|---|---|---|---|---|---|
| | Polyacrylonitrile (Orlon) | Acrylonitrile-Vinyl Derivatives (Acrilan) | Acrylonitrile-Vinyl Chloride (Dynel) | Modified Acrylic (Verel) | Acrylonitrile-Base (Creslan) | Dinitrile [a] (Darvan) | Nitrile [b] Alloy (Zefran) |
| NATURE OF FIBER | | | | | | | |
| Length, in. | Staple | Staple | Staple | Staple | — | — | — |
| Width, μ | 14-27 | 15-30 | — | — | — | — | — |
| Cross Section | Dogbone | — | — | — | — | — | — |
| PHYSICAL AND MECHANICAL PROPERTIES | | | | | | | |
| Specific Gravity | 1.14 | 1.17 | 1.3 | 1.37 | 1.17 | 1.18 | 1.19 |
| Breaking Tenacity, gm/den | | | | | | | |
| 70 F, 65% RH | 2.2-2.6 | 2.5 | 2.5-3.3 | 2.5-2.8 | 3.3 | 1.75 | 3.5 |
| Wet | 1.8-2.1 | 2.0 | 2.5-3.3 | 2.4-2.7 | 3.3 | 1.5 | 3.1 |
| Ten Str (70 F, 65% RH), 1000 psi | 32-39 | 37-40 | 40-57 | 42-47 | 41 | 26 | 53 |
| Breaking Elongation, % | | | | | | | |
| 70 F, 65% RH | 20-28 | 36 | 30-42 | 33-35 | 32 | 30 | 33 |
| Wet | 26-34 | 44 | 30-42 | 32-34 | 32 | 30 | 33 |
| Stiffness (avg), gm/den [c] | 10 | 7 | 8.2 | 8.0 | 10.3 | 6 | 11 |
| Strain Recovery (at 2%), % [d] | — | 99, 89 (5%) | 94 | 88 (4%), 55 (10%) | 90 (1%), 48 (5%) | 100 (3%), 75 (5%) | 99, 72 (10%) |
| Toughness (avg), gm-cm/den-cm | 0.40 | 0.46 | 0.53 | 0.46 | 0.53 | 0.3 | 0.58 |
| Moisture Regain (70 F, 65% RH), % | 1.5 | 1.2 | 0.3-0.4 | 3.5-4 | 1.3 | 2-3 | 2.5 |
| RESISTANCE TO ENVIRONMENTS | | | | | | | |
| Acids | | | | | | | |
| Strong | Good-exc | Good-exc | Good | Exc | Good-exc | Good-exc | Exc |
| Weak | Exc | Exc | Exc | Exc | Exc | Exc | Exc |
| Alkalis | | | | | | | |
| Strong | Poor | Poor | Good | Discolors some, no weakening | Poor | Poor | Fair |
| Weak | Fair-good | Fair-good | Exc | | Fair-good | Fair-good | Good |
| Other Chemicals | Not harmed by solvents, oils, greases and some acid salts | Similar to Orlon | Good; softened by acetone and some ketones | Good; dissolves in warm acetones | Good | Good | Good |
| Heat | No weakening after 32 days at 257 F; sticking temp 455 F [f] | 5% shrinkage at 487 F | Unless heat treated, shrinks at 250 F | Exposure over 300 F causes stiffening | Sticking temp 450 F [f] | Unaffected by 195 days at 300 F; sticking temp 340 F [f] | Sticking temp 490 F [f] |
| Sunlight (prolonged exposure) | Very resistant | Resistant | Weakened | — | — | Resistant | Resistant |
| Microorganisms | Resistant | Resistant | Resistant | — | — | Resistant | Resistant |
| Flame [e] | Burns slowly | Burns slowly | Self-exting | Self-exting | Burns | Burns | Burns |

[a] Though not an acrylic (actually a polymer of vinylidene cyanide), it is grouped here because of similarities of properties.
[b] Nitrile "alloy" based on acrylonitrile.
[c] Ratio of breaking stress to breaking strain (i.e., gm/den to rupture divided by strain in cm/gage cm at breaking stress).
[d] Recovery after 2% strain, except where specific percentage strain is given in parentheses.
[e] Basic flammability of untreated fiber.
[f] Copper block method.

*continued on next page*

## Synthetic Fibers

| Type → | Polyamides | | | | | | Polyesters | | |
|---|---|---|---|---|---|---|---|---|---|
| | Nylon 66 | | | Nylon 6 | | | Polyethylene Terephthalate (Dacron) | | |
| | Regular | High Tenacity | Staple | Regular | High Tenacity | Staple | Regular | High Tenacity | Staple |
| NATURE OF FIBER | | | | | | | | | |
| Length, in | Filament | | Staple | Filament | | Staple | Filament | | Staple |
| Width, μ | 11–43 | 16–43 | 14–43 | — | | — | 11–28 | | 18–25 |
| Cross Section | Round | | Round | Round | | Round | Circular | | — |
| PHYSICAL AND MECHANICAL PROPERTIES | | | | | | | | | |
| Specific Gravity | 1.14 | 1.14 | 1.14 | 1.14 | 1.14 | 1.14 | 1.38 | 1.38 | 1.38 |
| Breaking Tenacity, gm/den | | | | | | | | | |
| 70 F, 65% RH | 4.6–5.9 | 5.9–8.8 | 4.0–4.7 | 4.5–5.8 | 6.8–8.6 | 3.8–5.5 | 4.4–5.0 | 6–7 | 3.8–4 3 |
| Wet | 4.0–5.2 | 5.1–7.6 | 3.5–4.2 | 4.3–5.3 | 5.4–7.5 | — | 4.4–5.0 | 6–7 | 3.8–4.3 |
| Ten Str (70 F, 65% RH), 1000 psi | 67–86 | 86–128 | 58–69 | 73–84 | 109–125 | 70–80 | 77–88 | 106–123 | 67–76 |
| Breaking Elongation, % | | | | | | | | | |
| 70 F, 65% RH | 26–32 | 18–28 | 38–42 | 24–34 | 16–17.5 | 37–40 | 19–25 | 9–11 | 30–36 |
| Wet | 30–37 | 21–32 | 42–46 | 28–38 | 19–24 | 42–46 | 19–25 | 9–11 | 30–36 |
| Stiffness (avg), gm/den[a] | 18 | 32 | 10 | 23 | 48 | 17–20 | 21 | 65 | 12 |
| Strain Recovery (at 2%), %[b] | 100, 100 (8%) | 100 (4%) | — | 100, 100 (8%) | 100 (4%) | 100 | 97, 80 (8%) | 100, 90 (8%) | — |
| Toughness (avg), gm-cm/den-cm | 0.76 | 0.85 | 0.87 | 0.67 | 0.75 | 0.64–0.78 | 0.78 | 0.50 | 1.03 |
| Moisture Regain (70 F, 65% RH), % | 4.5 | 4.5 | 4.5 | 4 0 | 4.0 | 4.0 | 0.4 | 0.4 | 0.4 |
| RESISTANCE TO ENVIRONMENTS | | | | | | | | | |
| Acids | | | | | | | | | |
| Strong | Dissolves in cold HCl, $H_2SO_4$ and $HNO_3$ | | | Degraded by oxidizing agents and mineral acids | | | Dissolves in $H_2SO_4$ | | |
| Weak | Ultimate disintegration in 5% boiling HCl | | | Weakens on prolonged exposure to acids such as benzoic and oxalic | | | Good | | |
| Alkalis | | | | | | | | | |
| Strong | Inert | | | Inert | | | Disintegrates when boiled | | |
| Weak | Inert | | | Inert | | | Good | | |
| Other Chemicals | Good | | | Good | | | Good | | |
| Heat | Yellows slightly after 5 hr at 300 F; melts at 482 F | | | Yellows slightly after 5 hr at 300 F; melts at 420 F | | | Melts at 480 F | | |
| Sunlight (prolonged exposure) | Weakened | | | Weakened | | | Weakened | | |
| Microorganisms | Resistant | | | Resistant | | | Resistant | | |
| Flame[c] | Self-exting | | | Self-exting | | | Burns slowly | | |

[a] Ratio of breaking stress to breaking strain (i.e., gm/den to rupture divided by strain in cm/gage cm at breaking stress).
[b] Recovery after 2% strain, except where specific percentage strain is given in parenthesis.
[c] Basic flammability of untreated fiber.

## Synthetic Fibers

| Type → | Vinyl Derivatives | | | | | Polyolefins | | |
|---|---|---|---|---|---|---|---|---|
| | Vinyl Chloride-Acetate (Vinyon) | Vinylidene Chloride (saran) | | | Polyvinyl Alcohol (Vinylon) | Polyethylene | | Polypropylene |
| | | Monofilament | Filament | Staple | | Type I | Type III | |
| **NATURE OF FIBER** | | | | | | | | |
| Length, in. | Staple | — | — | — | Staple | Monofilament | | Monofilament |
| Width, μ | 16–18 | 1300 | 50 | — | — | 250–1300 | | — |
| Cross Section | Barbell | Circular | Circular | Circular | Peanut | Circular | | Circular |
| **PHYSICAL AND MECHANICAL PROPERTIES** | | | | | | | | |
| Specific Gravity | 1.33–1.35 | 1.7 | 1.7 | 1.7 | 1.26–1.30 | 0.92 | 0.95–0.96 | 0.90–0.91 |
| Breaking Tenacity, gm/den | | | | | | | | |
| 70 F, 65% RH | 0.7–1.0 | 1.2–2.3 | Up to 2 | Up to 1.5 | 4.4–6.0 | 1.0–3.0 | 5.0–7.3 | 5.5–7.0 |
| Wet | 0.7–1.0 | 1.2–2.3 | Up to 2 | Up to 1.5 | 3.7–5.0 | 1.0–3.0 | 5.0–7.3 | 5.5–7.0 |
| Ten Str (70 F, 65% RH), 1000 psi | 12–17 | 15–45 | 44 | 33 | — | 11–35 | 50–90 | — |
| Breaking Elongation, % | | | | | | | | |
| 70 F, 65% RH | 100–120 | 20–30 | 15–25 | 15–25 | 15–17 | 20–80 | 10–40 | 12–25 |
| Wet | 100–120 | 20–30 | 15–25 | 15–25 | — | 20–80 | 10–40 | — |
| Stiffness (avg), gm/den[a] | 1.5 | 7–10 | 8–12 | 8–12 | 24–40 | 2–12 | 20–50 | — |
| Strain Recovery (at 2%), %[b] | — | 95 (10%) | 95 (10%) | 95 (10%) | — | 90–95 (5%) | Slow | — |
| Toughness (avg), gm-cm/den-cm | 1.3 | 0.17–0.27 | 0.125 | 0.125 | 0.79–0.92 | 0.3 | — | — |
| Moisture Regain (70 F, 65% RH), % | Up to 0.5 | None | None | None | 4.5–5.0 | None | None | — |
| **RESISTANCE TO ENVIRONMENTS** | | | | | | | | |
| Acids | | | | | | | | |
| Strong | Exc | Exc; fair to conc $H_2SO_4$ | | | — | Exc to all but oxidizing | | Similar to polyethylene |
| Weak | Exc | Exc | | | — | | | |
| Alkalis | | | | | | | | |
| Strong | Exc | Exc except for ammonium hydroxide | | | — | Exc | Exc | Exc |
| Weak | Exc | Exc | | | — | Exc | Exc | Exc |
| Other Chemicals | Soluble in some chlorinated hydrocarbons | Some effect from esters and others | | | — | Some swelling and weakening in benzene, toluene, etc. | | Similar to polyethylene |
| Heat | Tacky, shrinks at 150 F, softens at 170 F, melts at 260 F | Softens at 240–280 F | | | Melts 420–450 F | Melts at 225 F | Melts at 265–280 F | Melts at 325–335 F |
| Sunlight (prolonged exposure) | Resistant | Tends to yellow | | | — | Resistant if pigmented | | Resistant if pigmented |
| Microorganisms | Resistant | Resistant | | | Resistant | Resistant | | Resistant |
| Flame[c] | Self-exting | Self-exting | | | Burns slowly | Burns slowly | | Burns slowly |

[a] Ratio of breaking stress to breaking strain (i.e., gm/den to rupture divided by strain in cm/gage cm at breaking stress).
[b] Recovery after 2% strain except where specific percentage strain is given in parentheses.
[c] Basic flammability of untreated fiber.

## Inorganic Fibers

| Type → | Glass [a] | Asbestos (chrysotile) | Aluminum Silicate (Fiberfrax) |
|---|---|---|---|
| NATURE OF FIBER | | | |
| Length, in. | Filament, staple | Crude ⅜–2 in. | ¼–10 in. staple |
| Width, μ | 5–16 | 0.1 | 2–20 (mean) |
| Cross Section | Circular | — | — |
| PHYSICAL AND MECHANICAL PROPERTIES | | | |
| Specific Gravity | 2.54 | 2.4–2.6 | 2.73 |
| Breaking Tenacity, gm/den | | | |
| 70 F, 65% RH | 6.0–7.3 | 2.5–3.1 | 1.4–6.5[b] |
| Wet | 3.9–4.7 | — | — |
| Ten Str (70 F, 65% RH), 1000 psi | 200–220 | 80–100 | 50–230 |
| Breaking Elongation, % | | | |
| 70 F, 65% RH | 2.0–3.75 | — | 1.4–2.7[i] |
| Wet | — | — | — |
| Stiffness (avg), gm/den[b] | 322 | — | — |
| Strain Recovery (at 2%), %[c] | 100 (3%) | — | — |
| Toughness (avg), gm-cm/den-cm | 0.07 | — | — |
| Moisture Regain (70 F, 65% RH), % | 0 | — | — |
| RESISTANCE TO ENVIRONMENTS | | | |
| Acids | | | |
| Strong | Attacked only by hydrofluoric and hot phosphoric | Good (cold) to poor (hot) | Seems to have chemical resistance similar to borosilicate glass fibers |
| Weak | Stable | Good (cold) to poor (hot) | |
| Alkalis | | | |
| Strong | Resists most | Good | |
| Weak | Resists most | Good | |
| Other Chemicals | Exc | — | |
| Heat | 600–2000 F[e] | 750–1490 F[g] | 2300 F max use temp; 3300 F melting point |
| Sunlight (prolonged exposure) | Inert[f] | Inert | Inert |
| Microorganisms | Unaffected | Unaffected | Unaffected |
| Flame[d] | Nonflammable | Nonflammable | Nonflammable |

[a] Properties may vary widely depending on glass composition; values here indicative of those of borosilicate.
[b] Ratio of breaking stress to breaking strain (i.e., gm/den to rupture divided by strain in cm/gage cm at breaking stress).
[c] Recovery after 2% strain, except where specific percentage strain is given in parentheses.
[d] Basic flammability of untreated fiber.
[e] Normal glass limited to 600 F; quartz fiber generally useful up to 2000 F, though some shrinkage occurs.
[f] Specific types available with excellent weathering characteristics.
[g] Structure is stable up to 1490 F; at temperatures of 750 F and above, substantial amounts of water of crystallization are lost.
[h] Average is 3.3 gm/den.
[i] Average is 1.7%.

## Woods and Wood-Base Compositions

**AMERICAN AND IMPORTED WOODS**

| Type ↓ | Moisture Content, % | Specific Gravity (oven dry) | Static Bending | | Max Crush Str (par. to grain), 1000 psi | Hardness, lb[a] | | Max Shear Str (par. to grain), psi |
|---|---|---|---|---|---|---|---|---|
| | | | Mod of Rupture, 1000 psi | Mod of Elast, $10^6$ psi | | End | Side | |
| **AMERICAN HARDWOODS**[b] | | | | | | | | |
| Ash (white) | 12 | 0.60 | 15.4 | 1.8 | 7.4 | 1720 | 1320 | 1950 |
| Basswood | 12 | 0.37 | 8.7 | 1.5 | 4.7 | 520 | 410 | 990 |
| Beech | 12 | 0.64 | 14.9 | 1.7 | 7.3 | 1590 | 1300 | 2010 |
| Birch (yellow) | 12 | 0.62 | 16.6 | 2.0 | 8.2 | 1480 | 1260 | 1880 |
| Cottonwood (black) | 12 | 0.35 | 8.3 | 1.3 | 4.4 | 1020 | 540 | 350 |
| Elm (rock) | 12 | 0.63 | 14.8 | 1.5 | 7.1 | 1920 | 1510 | 1320 |
| Hickory (shag bark) | 12 | 0.72 | 20.2 | 2.2 | 9.2 | 2430 | — | — |
| Locust (black) | 12 | 0.69 | 19.4 | 2.1 | 10.2 | 2480 | 1580 | 1700 |
| Maple (sugar) | 12 | 0.63 | 15.8 | 1.8 | 7.8 | 2330 | 1840 | 1450 |
| Oak (red, white) | 12, 12 | 0.63, 0.68 | 14.3, 15.2 | 1.8, 1.8 | 6.8, 7.4 | 1780, 2000 | 1580, 1520 | 1290, 1360 |
| Poplar (yellow) | 12 | 0.42 | 10.1 | 1.6 | 5.5 | 1190 | 670 | 540 |
| Walnut (black) | 12 | 0.55 | 14.6 | 1.7 | 7.6 | 1370 | 1050 | 1010 |
| **AMERICAN SOFTWOODS**[b] | | | | | | | | |
| Cedar (Port Orford) | 12 | 0.42 | 11.3 | 1.3 | 6.5 | 1080 | 730 | 560 |
| Cedar (Eastern red) | 12 | 0.47 | 8.8 | 0.9 | 6.0 | — | 900 | 900 |
| Cypress (Southern bald) | 12 | 0.46 | 10.6 | 1.4 | 6.4 | 1000 | 660 | 510 |
| Douglas Fir (coast type) | 12 | 0.48 | 12.2 | 2.0 | 7.4 | 1160 | 900 | 710 |
| Fir (balsam) | 12 | 0.36 | 7.6 | 1.2 | 4.5 | 710 | 510 | 400 |
| Hemlock (Eastern, Western) | 12, 12 | 0.40, 0.42 | 8.9, 10.1 | 1.2, 1.5 | 5.4, 6.2 | 1060, 1170 | 810, 940 | 500, 580 |
| Pine (Eastern white) | 12 | 0.35 | 8.6 | 1.2 | 4.8 | 900 | 480 | 380 |
| Pine (longleaf, ponderosa) | 12, 12 | 0.58, 0.40 | 14.7, 9.2 | 2.0, 1.3 | 8.4, 5.3 | 1500, 1160 | 920, 550 | 870, 450 |
| Redwood (virgin) | 12 | 0.40 | 10.0 | 1.3 | 6.2 | 940 | 790 | 480 |
| Spruce (sitka) | 12 | 0.40 | 10.2 | 1.6 | 5.6 | 1150 | 760 | 510 |
| **IMPORTED WOODS** | | | | | | | | |
| Balsa (tropical America) | 5 | 0.14 | 2.2 | 0.5 | 1.0 | — | — | — |
| Lignum Vitae (tropical America) | 12 | 1.09 | — | — | 11.4 | 3600 | 4500 | — |
| Ebony (Africa) | 12 | — | 26.0 | 2.7 | 12.9 | 3430 | 3220 | 2480 |
| Teak (Asia) | 52 | — | 11.4 | 1.7 | 5.9 | 915 | 1038 | 1107 |
| Mahogany (tropical America) | 12 | 0.50 | 11.1 | 1.4 | 6.4 | 880 | 760 | 1050 |
| Lemonwood (tropical America) | 14 | 0.78 | 22.3 | 2.3 | 9.7 | 2140 | 1940 | 2120 |

[a] Load required to embed an 0.444-in. ball to half its diameter. [b] Seasoned.

**WOOD COMPOSITION BOARD**

| Material → | Hardboard (fibrous)[a] | | | Particle Board[b] | | Softboard (insulation)[c] | |
|---|---|---|---|---|---|---|---|
| | Untempered | Tempered | Super Hardboard | Medium Density[d] | Hard Pressed | Structural Insulating | Medium Density |
| PHYSICAL PROPERTIES | | | | | | | |
| Specific Gravity | 0.08–1.28 | 0.96–1.28 | 1.36–1.44 | 0.42–0.80 | 0.80–1.28 | 0.16–0.42 | 0.42–0.80 |
| Density, lb/cu ft | 50–80 | 60–80 | 85–90 | 26–50 | 50–80 | 10–26 | 26–50 |
| Ther Cond, Btu/hr/sq ft/°F/in. | 0.80–1.40 | 1.10–1.50 | 1.85 | 0.40–1.0 | 1.10–1.50 | 0.27–0.45 | 0.50–0.60 |
| Water Abs (24 hr), % | 3–30 | 3–20 | 0.3–1.2 | 20–75 | 15–40 | — | 6–150 |
| Max Linear Exp, %[e] | 0.60 | 0.4 | — | 0.6 | 0.85 | 0.50 | 0.2–1.3[f] |
| MECHANICAL PROPERTIES | | | | | | | |
| Ten Str, psi | | | | | | | |
| Par. to Surface | 3000–6000 | 4000–7800 | 7800 | 500–4000 | 1000–5000 | 200–500 | 800–2000 |
| Perp to Surface | — | — | 500 | 40–400 | 275–400 | 10–25 | — |
| Mod of Elast in Bend, 1000 psi | 400–800 | 800–1000 | 1250 | 150–700 | 400–1000 | 25–125 | 90–700 |
| Compr Str (par.), psi | 1800–6000 | 4200–6000 | 26,500 | 1400–2800 | 3500–4000 | — | 500–3400 |
| Mod of Rupture, 1000 psi | 3–7 | 6.5–10 | 10–12.5 | 1.5–8.0 | 3.0–7.5 | 0.2–0.8 | 0.4–4.0 |

[a] Made by felting ligno-cellulosic wood fibers formed by steam exploding or mechanical fiberizing.
[b] Made of flakes, chips, splinters or particles of wood bonded with synthetic resin or other binder.
[c] Made from wood pulp or bagasse (processed sugar cane), bonded by felting properties of fiber.
[d] Does not include extruded board.
[e] Expansion resulting from change in moisture content from equilibrium at 50% RH to equilibrium at 90% RH.
[f] For homogeneous and laminated boards, respectively.

## Wool Felts—Roll[a]

| Grade → | 18R1 | 16R1 | 16R2 | 16R3 | 12R1 | 12R2 |
|---|---|---|---|---|---|---|
| SAE Spec. No. → | — | F-1 | F-2 | F-3 | F-5 | F-6 |
| **GENERAL PROPERTIES** | | | | | | |
| Wool Content (fiber basis), min % | 100 | 100 | 100 | 95 | 100 | 100 |
| Standard Thickness Range, in. | ⅛ to 1 | ⅛ to 1 | ⅛ to 1 | ⅛ to 1 | ⅛ to 1 | ⅛ to 1 |
| Standard Width, in. | 60 | 60 | 60 | 60 | 60 | 60 or 72 |
| Texture | Fine | Fine | Med fine | Medium | Fine | Med fine |
| Color[b] | White | White | Any, except gray or blk | Gray | White | Gray |
| **PHYSICAL PROPERTIES** | | | | | | |
| Specific Gravity | 0.384 | 0.342 | 0.342 | 0.330 | 0.262 | 0.262 |
| Operating Temp Range, F[c] | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 |
| Ther Cond (70 F), Btu/hr/sq ft/°F/in.[d] | 0.39 | 0.36 | 0.36 | 0.35 | 0.30 | 0.30 |
| Coef of Ther Exp, per °F | 0 | 0 | 0 | 0 | 0 | 0 |
| Air Perm (1/16 in.), cfm/sq ft/0.5 in. $H_2O$ | 5–15 | 10–30 | 10–30 | 15–35 | 20–50 | 20–50 |
| Liquid Absorption, % | | | | | | |
| By Weight (1.0 sp gr liquid) | >125 | >175 | >175 | >190 | >250 | >225 |
| By Volume | 71 | 74 | 74 | 76 | 80 | 80 |
| Capillarity (wicking height, 575 SSU, 70 F), in. | 4.5 | 4.0 | 4.0 | 4.0 | 3.0 | 3.0 |
| Coef of Friction[e] | 0.37 | 0.37 | 0.37 | 0.37 | 0.37 | 0.37 |
| Vibration Absorption[f] | | | | | | |
| Static Load Bearing Cap, per Unit Area | High | High | High | High | Medium | Medium |
| Dynamic Stress Endurance | High | High | High | High-med | High | High |
| Coef of Noise Reduction (1 in. thick)[d] | 0.45 | 0.50 | 0.50 | 0.52 | 0.58 | 0.58 |
| **MECHANICAL PROPERTIES** | | | | | | |
| Ten Str (min), psi | 600 | 500 | 500 | 400 | 400 | 275 |
| Elong (at 100 psi), % | 9 | 13 | 14 | 16 | 16 | 18 |
| Mullen Burst Str (⅛ in. thick), psi | 300 | 250 | 225 | 200 | 175 | 150 |
| Split Res (min), lb/2-in. width | 35 | 33 | 28 | 22 | 18 | 16 |
| Hardness Range, Shore A | 40–50 | 30–40 | 30–40 | 30–40 | 20–30 | 20–30 |
| Compressibility (at 10% defl), psi | 37 | 21 | 21 | 13 | 6 | 6 |
| Recovery (within 1 min after 10% defl), % | 99 | 99 | 99 | 99 | 99 | 99 |
| Vibration Disintegration | None | None | None | None | None | None |
| Collapse When Wet | None | None | None | None | None | None |
| Abrasion Resistance[g] | Excellent | Excellent | Excellent | Excellent | Good | Good |
| Flexibility (fold endurance) | ¼-in. thick felt exceeds 3 million 180° flexes | | | | | |
| **CHEMICAL AND ENVIRONMENTAL PROPERTIES[h]** | | | | | | |
| Effect of Sunlight and Oxidation | None | None | None | None | None | None |
| Solvent Res, Stability in Oil | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Acid Resistance | | | | | | |
| Dilute | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Concentrated | Good-fair | Good-fair | Good-fair | Good-fair | Good-fair | Good-fair |
| Alkali Resistance | | | | | | |
| Dilute | Fair | Fair | Fair | Fair | Fair | Fair |
| Concentrated | Poor | Poor | Poor | Poor | Poor | Poor |
| **FABRICATING METHODS** | Can be fabricated by die-cutting, stripping, skiving; laminating, coating, impregnating; stitching, stapling, perforating, cementing; machining, grinding, drilling; and molding and shaping. All grades except 12R1 and 12R2 can be extruded | | | | | |
| **TYPICAL USES** | Bearing seals, ink rolls, polishing, printing, wick lubrication, and precision uses where dense high grade felt with max durability is required | Vibration mounts, precision channels, oil seals, bumpers, gaskets | Automotive, aircraft, machine components. Similar to 16R1 and 16R2, where lower density is acceptable | Lubricators, wipers, shock dampeners, etc., where durable resilient felt is required | Grease retainers, spacer strip seals, vibration mounts, weatherstrip, journal lubricators | |

[a] Industrial, mechanical and filter felts; three dimensional fibrous structure.
[b] Colors available on special order. [c] Felts are flameproofed to meet government and industrial specifications.
[d] For 1-in. felts. Felts blended with kapok fiber have a k factor of 0.21 and a coefficient of sound absorption of 0.80 at 512 cps.
[e] Depends upon condition of contact surface, but can be moderately controlled by altering surface finish of the felt.
[f] Up to 85% under appropriate design conditions. [g] Increases with density. [h] Treated to resist moths, fungus, mildew and vermin.

## Wool Felts—Roll[a]

| Grade → | 12R3 | 9R1 | 9R2 | 9R3 | 9R4 | 9R5 |
|---|---|---|---|---|---|---|
| SAE Spec. No. → | F-7 | F-10 | F-11 | F-12 | F-13 | F-15 |
| **GENERAL PROPERTIES** | | | | | | |
| Wool Content (fiber basis), min % | 85 | 100 | 100 | 90 | 80 | 60 |
| Standard Thickness Range, in. | ⅛ to 1 | ⅛ to 1 | ⅛ to 1 | ⅛ to 1 | ⅛ to 1 | ⅛ to 1 |
| Standard Width, in. | 72 | 72 | 72 | 72 | 72 | 72 |
| Texture | Medium | Fine | Med fine | Med fine | Medium | Medium |
| Color[b] | Gray | White | Gray | Gray | Gray | Gray |
| **PHYSICAL PROPERTIES** | | | | | | |
| Specific Gravity | 0.262 | 0.181 | 0.181 | 0.181 | 0.181 | 0.181 |
| Operating Temp Range, F[c] | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 |
| Ther Cond (70 F), Btu/hr/sq ft/°F/in.[d] | 0.30 | 0.30 | 0.24 | 0.24 | 0.24 | 0.24 |
| Coef of Ther Exp, per °F | 0 | 0 | 0 | 0 | 0 | 0 |
| Air Perm (⅛ in.), cfm/sq ft/0.5 in. $H_2O$ | 20–50 | 75–150 | 75–150 | 75–150 | 75–150 | 75–150 |
| Liquid Absorption, % | | | | | | |
| By Weight (1.0 sp gr liquid) | >225 | >400 | >375 | >350 | >350 | >350 |
| By Volume | 80 | 88 | 88 | 88 | 88 | 88 |
| Capillarity (wicking height, 575 SSU, 70 F), in. | 3.0 | 2.5 | 2.5 | 2.5 | 2.5 | 2.5 |
| Coef of Friction[e] | 0.37 | 0.37 | 0.37 | 0.37 | 0.37 | 0.37 |
| Vibration Absorption[f] | | | | | | |
| Static Load Bearing Cap, per Unit Area | Medium | Low | Low | Low | Low | Low |
| Dynamic Stress Endurance | Medium | High | High-med | Medium | Low | Low |
| Coef of Noise Reduction (1 in. thick) | 0.58 | 0.58 | 0.64 | 0.64 | 0.64 | 0.64 |
| **MECHANICAL PROPERTIES** | | | | | | |
| Ten Str (min), psi | 250 | 225 | 200 | 100 | 75 | 75 |
| Elong (at 100 psi), % | 21 | 33 | 35 | 35 | 37 | 39 |
| Mullen Burst Str (⅛ in. thick), psi | 125 | 75 | 60 | 55 | 50 | 40 |
| Split Res (min), lb/2-in. width | 12 | 8 | 6 | 3 | 2 | 2 |
| Hardness Range, Shore A | 20–30 | 15–25 | 15–25 | 15–25 | 15–25 | 15–25 |
| Compressibility (at 10% defl), psi | 6 | 4 | 4 | 3 | 3 | 3 |
| Recovery (within 1 min after 10% defl), % | 99 | 99 | 99 | 99 | 99 | 99 |
| Vibration Disintegration | None | None | None | None | None | None |
| Collapse When Wet | None | None | None | None | None | None |
| Abrasion Resistance[g] | Good | Fair | Fair | Fair | Fair | Fair |
| Flexibility (fold endurance) | ¼-in. thick felt exceeds 3 million 180° flexes | | | | | |
| **CHEMICAL AND ENVIRONMENTAL PROPERTIES[h]** | | | | | | |
| Effect of Sunlight and Oxidation | None | None | None | None | None | None |
| Solvent Res and Stability in Oil | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Acid Resistance | | | | | | |
| Dilute | Good | Excellent | Excellent | Good | Fair | Fair |
| Concentrated | Fair | Fair-good | Fair-good | Fair-good | Fair | Fair |
| Alkali Resistance | | | | | | |
| Dilute | Fair | Fair | Fair | Fair | Fair | Fair |
| Concentrated | Poor | Poor | Poor | Poor | Poor | Poor |
| **FABRICATING METHODS** | Can be fabricated by die-cutting, stripping, skiving; laminating, coating, impregnating; stitching, stapling, perforating, cementing; and molding and shaping. Grade 12R3 can also be machined, ground and drilled | | | | | |
| **TYPICAL USES** | Dust shields, oil and grease retainers; similar to 12R1 and 12R2 where a lower grade may be used | Fluid storage and delivery, resilient padding, plug filters for gas and air | Dryer drum seals, impregnated packing, insoles, insulation; oil, dust and mud shields | Chassis strips, spacers, dash liners, antisqueak strips and pads, sound deadening | Grease and oil retention, protective lining and insulation for freight cars, trucks, dunnage; uses similar to 9R2 and 9R3 where less durability and lower grade felt is suitable | |

[a] Notes on opposite page.

*continued on next page*

## Wool Felts—Roll and Sheet[a]

| Grade → | 8R5 | 16R1X | 16R3X | 12R3X | 32S1 | 32S2 |
|---|---|---|---|---|---|---|
| SAE Spec. No. → | F-26 | F-50 | F-51 | F-55 | — | — |
| **GENERAL PROPERTIES** | | | | | | |
| Wool Content (fiber basis), min % | 50 | 100 | 100 | 80 | 100 | 100 |
| Standard Thickness Range, in. | ⅛ to 1 | 3/64 to 3/32 | 3/64 to 3/32 | 1/16 to 1/32 | ⅛ to 3 | ⅛ to 3 |
| Standard Width, in. | 72 | 60 or 72 | 60 or 72 | 60 or 72 | 36 x 36 | 36 x 36 |
| Texture | Medium | Fine | Med fine | Medium | Extra fine | Fine |
| Color[b] | Gray | White | Gray | Gray or blk | White | White |
| **PHYSICAL PROPERTIES** | | | | | | |
| Specific Gravity | 0.154 | 0.330 | 0.330 | 0.256 | 0.682 | 0.682 |
| Operating Temp Range, F[c] | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 |
| Ther Cond (70 F), Btu/hr/sq ft/°F/in.[d] | 0.25 | 0.32 | 0.32 | 0.30 | 0.91 | 0.91 |
| Coef of Ther Exp, per °F | 0 | 0 | 0 | 0 | 0 | 0 |
| Air Perm (1/16 in.), cfm/sq ft/0.5 in. $H_2O$ | 100–200 | 15–25 | 15–40 | 20–50 | <1 | <1 |
| Liquid Absorption, % | | | | | | |
| By Weight (1.0 sp gr liquid) | >400 | >180 | >170 | >225 | >90 | >50 |
| By Volume | 92 | 75 | 75 | 81 | 48 | 48 |
| Capillarity (wicking height, 575 SSU, 70 F), in. | — | 4.0 | 4.0 | 3.0 | 5.5 | 5.5 |
| Coef of Friction[e] | 0.37 | 0.37 | 0.37 | 0.37 | 0.42 | 0.42 |
| Vibration Absorption[f] | | | | | | |
| Static Load Bearing Cap, per Unit Area | Very low | — | — | — | Ultra high[g] | Ultra high |
| Dynamic Stress Endurance | Very low | — | — | — | High | High |
| Coef of Noise Reduction (1 in. thick)[d] | 0.65 | 0.55 | 0.55 | 0.58 | 0.05 | 0.05 |
| **MECHANICAL PROPERTIES** | | | | | | |
| Ten Str (min), psi | — | 500 | 200 | 200 | 800 | 800 |
| Elong (at 100 psi), % | — | 8 | 9 | 25 | 2 | 2 |
| Mullen Burst Str (⅛ in. thick), psi | 25 | 225 | 225 | 200 | Over 500 | Over 500 |
| Split Res (min), lb/2-in. width | — | — | — | — | 50 | 48 |
| Hardness Range, Shore A | 5–15 | — | — | — | 75–85 | 75–85 |
| Compressibility (at 10% defl), psi | 1 | — | — | — | 121 | 121 |
| Recovery (within 1 min after 10% defl), % | 99 | 99 | 99 | 99 | 99 | 99 |
| Vibration Disintegration | None | None | None | None | None | None |
| Collapse When Wet | Slight | None | None | None | None | None |
| Abrasion Resistance[e] | Poor | Excellent | Excellent | Good | Excellent | Excellent |
| Flexibility (fold endurance) | ¼-in. thick felt exceeds 3 million 180° flexes | | | | | |
| **CHEMICAL AND ENVIRONMENTAL PROPERTIES[h]** | | | | | | |
| Effect of Sunlight and Oxidation | None | None | None | None | None | None |
| Solvent Res and Stability in Oil | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Acid Resistance | | | | | | |
| Dilute | Fair | Excellent | Excellent | Good | Excellent | Excellent |
| Concentrated | Poor | Fair-good | Fair-good | Fair | Fair-good | Fair-good |
| Alkali Resistance | | | | | | |
| Dilute | Fair | Fair | Fair | Fair | Fair | Fair |
| Concentrated | Poor | Poor | Poor | Poor | Poor | Poor |
| **FABRICATING METHODS** | Can be fabricated by die-cutting, stripping, skiving; laminating, coating, impregnating; stitching, stapling, perforating, cementing; and molding and shaping. Grades 32S1 and 32S2 can also be machined, ground, drilled or extruded | | | | | |
| **TYPICAL USES** | Packing or padding when held between other materials; not recommended for mechanical use | Ball and roller bearing precision seals, strip wicks, industrial filters and uses requiring thin precision felt | Gaskets, liners, bearing seals, where precision tolerances, life and quality are not as exacting | Anti-squeak strips, anti-drumming and insulation lining cemented to metal or other type panels | Extra-hard density polishing wheels and buffs in dental jewelry, glass and lapidary polishing; also hard washers, bumpers and casters | |

[a] Industrial, mechanical and filter felts; three dimensional fibrous structure.
[b] Colors available on special order. [c] Felts are flameproofed to meet government and industrial specifications.
[d] For 1-in. felts. Felts blended with kapok fiber have a k factor of 0.21 and a coefficient of sound absorption of 0.80 at 512 cps.
[e] Depends upon condition of contact surface, but can be moderately controlled by altering surface finish of the felt.
[f] Up to 85% under appropriate design conditions. [g] Increases with density. [h] Treated to resist moths, fungus, mildew and vermin.

## Wool Felts—Sheet[a]

| Grade → | 32S3 | 32S4 | 26S1 | 26S2 | 26S3 | 26S4 |
|---|---|---|---|---|---|---|
| **GENERAL PROPERTIES** | | | | | | |
| Wool Content (fiber basis), min % | 100 | 100 | 100 | 100 | 100 | 100 |
| Standard Thickness Range, in. | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 |
| Standard Width, in. | 36 x 36 | 36 x 36 | 36 x 36 | 36 x 36 | 36 x 36 | 36 x 36 |
| Texture | Medium | Coarse | Extra fine | Fine | Med fine | Coarse |
| Color[b] | White | White | White | White | White | White |
| **PHYSICAL PROPERTIES** | | | | | | |
| Specific Gravity | 0.682 | 0.682 | 0.555 | 0.555 | 0.555 | 0.555 |
| Operating Temp Range, F[c] | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 |
| Ther Cond (70 F), Btu/hr/sq ft/°F/in.[d] | 0.91 | 0.91 | 0.63 | 0.63 | 0.63 | 0.63 |
| Coef of Ther Exp, per °F | 0 | 0 | 0 | 0 | 0 | 0 |
| Air Perm (1/16 in.), cfm/sq ft/0.5 in. $H_2O$ | <1 | <1 | <3 | <3 | <5 | <5 |
| Liquid Absorption, % | | | | | | |
| By Weight (1.0 sp gr liquid) | >50 | >50 | >75 | >75 | >75 | >75 |
| By Volume | 48 | 48 | 58 | 58 | 58 | 58 |
| Capillarity (wicking height, 575 SSU, 70 F), in. | 5.5 | 5.5 | 5.0 | 5.0 | 5.0 | 5.0 |
| Coef of Friction[e] | 0.42 | 0.42 | 0.42 | 0.42 | 0.42 | 0.42 |
| Vibration Absorption[f] | | | | | | |
| Static Load Bearing Cap, per Unit Area | Ultra high | Ultra high | Very high | Very high | Very high | Very high |
| Dynamic Stress Endurance | Med-high | Medium | High | High | Med-high | Medium |
| Coef of Noise Reduction (1 in. thick) | 0.05 | 0.05 | 0.28 | 0.28 | 0.28 | 0.28 |
| **MECHANICAL PROPERTIES** | | | | | | |
| Ten Str (min), psi | 800 | 800 | 700 | 700 | 700 | 700 |
| Elong (at 100 psi), % | 2 | 2 | 4 | 4 | 4 | 4 |
| Mullen Burst Str (⅛ in. thick), psi | >500 | >500 | >400 | >400 | >400 | >400 |
| Split Res (min), lb/2-in. width | 46 | 40 | 48 | 46 | 40 | 30 |
| Hardness Range, Shore A | 75–85 | 75–85 | 55–65 | 55–65 | 55–65 | 55–65 |
| Compressibility (at 10% defl), psi | 121 | 121 | 86 | 86 | 86 | 86 |
| Recovery (within 1 min after 10% defl), % | 99 | 99 | 99 | 99 | 99 | 99 |
| Vibration Disintegration | None | None | None | None | None | None |
| Collapse When Wet | None | None | None | None | None | None |
| Abrasion Resistance[g] | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Flexibility (fold endurance) | ¼-in. thick felt exceeds 3 million 180° flexes | | | | | |
| **CHEMICAL AND ENVIRONMENTAL PROPERTIES[h]** | | | | | | |
| Effect of Sunlight and Oxidation | None | None | None | None | None | None |
| Solvent Res and Stability in Oil | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Acid Resistance | | | | | | |
| Dilute | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Concentrated | Fair-good | Fair-good | Fair-good | Fair-good | Fair-good | Fair-good |
| Alkali Resistance | | | | | | |
| Dilute | Fair | Fair | Fair | Fair | Fair | Fair |
| Concentrated | Poor | Poor | Poor | Poor | Poor | Poor |
| **FABRICATING METHODS** | Die cutting, stripping, skiving; laminating, coating, impregnating; stitching, stapling, perforating, cementing; machining, grinding, drilling; molding and shaping; extruding | | | | | |
| **TYPICAL USES** | Similar to those indicated for 32S1 and 32S2 | | Hard-density wheels for polishing glass sheet, glassware, opthalmic lenses, metal and metallographic samples, wood and furniture; also block cutters, print rolls, cash carrier heads, marking pen nibs, casters, boot and shoe soles, artificial limbs | | | |

[a] Notes on opposite page.

*continued on next page*

## Wool Felts—Sheet[a]

| Grade → | 20S1 | 20S2 | 20S3 | 20S4 | 16S1 | 16S2 |
|---|---|---|---|---|---|---|
| **GENERAL PROPERTIES** | | | | | | |
| Wool Content (fiber basis), min % | 100 | 100 | 100 | 100 | 100 | 100 |
| Standard Thickness Range, in. | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 |
| Standard Width, in. | 36 x 36 | 36 x 36 | 36 x 36 | 36 x 36 | 36 x 36 | 36 x 36 |
| Texture | Extra fine | Fine | Medium | Coarse | Extra fine | Fine |
| Color[b] | White | White | White | White | White | White |
| **PHYSICAL PROPERTIES** | | | | | | |
| Specific Gravity | 0.426 | 0.426 | 0.426 | 0.426 | 0.342 | 0.342 |
| Operating Temp Range, F[c] | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 |
| Ther Cond (70 F), Btu/hr/sq ft/°F/in.[d] | 0.45 | 0.45 | 0.45 | 0.45 | 0.36 | 0.35 |
| Coef of Ther Exp, per °F | 0 | 0 | 0 | 0 | 0 | 0 |
| Air Perm (1/16 in.), cfm/sq ft/0.5 in. $H_2O$ | <10 | <10 | <15 | <15 | <20 | <25 |
| Liquid Absorption, % | | | | | | |
| By Weight (1.0 sp gr liquid) | >100 | >100 | >100 | >100 | >175 | >175 |
| By Volume | 66 | 66 | 66 | 66 | 74 | 74 |
| Capillarity (wicking height, 575 SSU, 70 F), in. | 4.5 | 4.5 | 4.5 | 4.5 | 4.0 | 4.0 |
| Coef of Friction[e] | 0.42 | 0.42 | 0.42 | 0.42 | 0.37 | 0.37 |
| Vibration Absorption[f] | | | | | | |
| Static Load Bearing Cap, per Unit Area | High | High | High | High | High | High |
| Dynamic Stress Endurance | High | High-med | Med-high | Medium | High | High-med |
| Coef of Noise Reduction (1 in. thick)[d] | 0.41 | 0.41 | 0.41 | 0.41 | 0.50 | 0.50 |
| **MECHANICAL PROPERTIES** | | | | | | |
| Ten Str (min), psi | 600 | 600 | 600 | 600 | 500 | 500 |
| Elong (at 100 psi), % | 9 | 9 | 9 | 9 | 12 | 12 |
| Mullen Burst Str (⅛ in. thick), psi | 325 | 325 | 325 | 325 | 250 | 250 |
| Split Res (min), lb/2-in. width | 44 | 40 | 36 | 32 | 32 | 28 |
| Hardness Range, Shore A | 45–55 | 45–55 | 45–55 | 45–55 | 30–40 | 30–40 |
| Compressibility (at 10% defl), psi | 58 | 58 | 58 | 58 | 32 | 32 |
| Recovery (within 1 min after 10% defl), % | 99 | 99 | 99 | 99 | 99 | 99 |
| Vibration Disintegration | None | None | None | None | None | None |
| Collapse When Wet | None | None | None | None | None | None |
| Abrasion Resistance[g] | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Flexibility (fold endurance) | ¼-in. thick felt exceeds 3 million 180° flexes | | | | | |
| **CHEMICAL AND ENVIRONMENTAL PROPERTIES[h]** | | | | | | |
| Effect of Sunlight and Oxidation | None | None | None | None | None | None |
| Solvent Res and Stability in Oil | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Acid Resistance | | | | | | |
| Dilute | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Concentrated | Good-fair | Good-fair | Good-fair | Good-fair | Good-fair | Good-fair |
| Alkali Resistance | | | | | | |
| Dilute | Fair | Fair | Fair | Fair | Fair | Fair |
| Concentrated | Poor | Poor | Poor | Poor | Poor | Poor |
| **FABRICATING METHODS** | Die cutting, stripping, skiving; laminating, coating, impregnating; stitching, stapling, perforating, cementing; machining, grinding, drilling; molding and shaping; extruding | | | | | |
| **TYPICAL USES** | Medium-hard-density polishing wheels and buffs for polishing lenses, mirrors and glass, and marble and granite; fluid transfer rolls, ink rolls, furniture rubbing, rough metal polishing, metal wiping, drilled wicks, bearing seal washers, stamp pads, cushioning under sandpaper | | | | Medium density polishing wheels and buffs for precious metals and plastics, rough optical polishing, metal wiping; drum beaters, drilled wicks, bearing seals, shoe rolls (shank), fluid transfer rolls, oil and fluid wicks, grease and oil retaining washers, ink rollers, vibration mounts, bumpers, plugs, glass channels | |

[a] Industrial, mechanical and filter felts; three dimensional fibrous structure.
[b] Colors available on special order. [c] Felts are flameproofed to meet government and industrial specifications.
[d] For 1-in. felts. Felts blended with kapok fiber have a k factor of 0.21 and a coefficient of sound absorption of 0.80 at 512 cps.
[e] Depends upon condition of contact surface, but can be moderately controlled by altering surface finish of the felt.
[f] Up to 85% under appropriate design conditions. [g] Increases with density. [h] Treated to resist moths, fungus, mildew and vermin.

## Wool Felts—Sheet[a]

| Grade → | 16S3 | 16S4 | 12S1 | 12S2 | 12S3 | 12S4 |
|---|---|---|---|---|---|---|
| **GENERAL PROPERTIES** | | | | | | |
| Wool Content (fiber basis), min % | 100 | 100 | 100 | 100 | 100 | 100 |
| Standard Thickness Range, in. | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 | ⅛ to 3 |
| Standard Width, in. | 36 x 36 | 36 x 36 | 36 x 36 | 36 x 36 | 36 x 36 | 36 x 36 |
| Texture | Medium | Coarse | Extra fine | Fine | Medium | Coarse |
| Color[b] | White | White | White | White | White | White |
| **PHYSICAL PROPERTIES** | | | | | | |
| Specific Gravity | 0.342 | 0.342 | 0.256 | 0.256 | 0.256 | 0.256 |
| Operating Temp Range, F[c] | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 | −80 to +200 |
| Ther Cond (70 F), Btu/hr/sq ft/°F/in.[d] | 0.36 | 0.36 | 0.30 | 0.30 | 0.30 | 0.30 |
| Coef of Ther Exp, per °F | 0 | 0 | 0 | 0 | 0 | 0 |
| Air Perm (⅛ in.), cfm/sq ft/0.5 in. $H_2O$ | <30 | <35 | <30 | <40 | <50 | <60 |
| Liquid Absorption, % | | | | | | |
| By Weight (1.0 sp gr liquid) | >175 | >175 | >250 | >250 | >250 | >250 |
| By Volume | 74 | 74 | 81 | 81 | 81 | 81 |
| Capillarity (wicking height, 575 SSU, 70 F), in. | 4.0 | 4.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| Coef of Friction[e] | 0.37 | 0.37 | 0.37 | 0.37 | 0.37 | 0.37 |
| Vibration Absorption[f] | | | | | | |
| Static Load Bearing Cap, per Unit Area | High | High | Medium | Medium | Medium | Medium |
| Dynamic Stress Endurance | Med-high | Medium | High | High-med | Med-high | Medium |
| Coef of Noise Reduction (1 in. thick) | 0.50 | 0.50 | 0.58 | 0.58 | 0.58 | 0.58 |
| **MECHANICAL PROPERTIES** | | | | | | |
| Ten Str (min), psi | 500 | 500 | 400 | 400 | 400 | 400 |
| Elong (at 100 psi), % | 12 | 12 | 28 | 28 | 28 | 28 |
| Mullen Burst Str (⅛ in. thick), psi | 250 | 250 | 150 | 150 | 150 | 150 |
| Split Res (min), lb/2-in. width | 22 | 20 | 18 | 16 | 12 | 10 |
| Hardness Range, Shore A | 30–40 | 30–40 | 20–30 | 20–30 | 20–30 | 20–30 |
| Compressibility (at 10% defl), psi | 32 | 32 | 18 | 18 | 18 | 18 |
| Recovery (within 1 min after 10% defl), % | 99 | 99 | 99 | 99 | 99 | 99 |
| Vibration Disintegration | None | None | None | None | None | None |
| Collapse When Wet | None | None | None | None | None | None |
| Abrasion Resistance[g] | Excellent | Excellent | Good | Good | Good | Good |
| Flexibility (fold endurance) | ¼-in. thick felt exceeds 3 million 180° flexes | | | | | |
| **CHEMICAL AND ENVIRONMENTAL PROPERTIES[h]** | | | | | | |
| Effect of Sunlight and Oxidation | None | None | None | None | None | None |
| Solvent Res and Stability in Oil | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Acid Resistance | | | | | | |
| Dilute | Excellent | Excellent | Excellent | Excellent | Excellent | Excellent |
| Concentrated | Good-fair | Good-fair | Good-fair | Good-fair | Good-fair | Good-fair |
| Alkali Resistance | | | | | | |
| Dilute | Fair | Fair | Fair | Fair | Fair | Fair |
| Concentrated | Poor | Poor | Poor | Poor | Poor | Poor |
| **FABRICATING METHODS** | Die cutting, stripping, skiving; laminating, coating, impregnating; stitching, stapling, perforating, cementing; machining, grinding, drilling; molding and shaping; extruding | | | | | |
| **TYPICAL USES** | Medium density polishing wheels and buffs for precious metals and plastics, rough optical polishing, metal wiping; also drum beaters, drilled wicks, bearing seals, shoe rolls (shank), fluid transfer rolls, oil and fluid wicks, grease and oil retaining washers, ink rollers, vibration mounts, bumpers, plugs, glass channels | | Soft density polishing wheels and buffs for polishing plastics, and polishing and wiping brass; also piano wedges, surgical pads, punched wicks, dampeners, absorbent pads, oil and fluid retainers, fluid transfer rolls, bearing seals, washers, wicks, shim and spacer pads, shoe insoles, dust shields | | | |

[a] Notes on opposite page.

# KENNAMETAL*

## HARD CARBIDE ALLOYS AND METALLURGICAL PRODUCTS


| PRODUCTS | PROPERTIES | TYPICAL APPLICATIONS |
|---|---|---|
| **Kennametal (tungsten-base carbides)** | YME of 60 to 90 million psi.<br>Compressive strength higher than virtually all melted and cast or forged metals and alloys.<br>Kennametal outwears steel up to 100 to 1.<br>Impact strength in the range of hardened alloy steels of very much lower hardness and compressive strength.<br>Thermal expansion about half that of steel.<br>Compositions to withstand one or various combinations of destructive agents such as abrasion, corrosion, galling, impact, and erosion, or meet specific requirements as to stiffness, strength and weight. | Metalworking and mining tool cutting edges.<br>Die inserts.<br>Seal rings.<br>Integrator discs.<br>Needle valves and cones.<br>Compressor liners.<br>Pulverizing hammers.<br>Abrasion resistant knives, blades, shears.<br>Boring bars.<br>Spray orifices.<br>Balls and seats for oil well pump valves. |
| **Kentanium* (titanium-base carbides)** | Superior strength and abrasion resistance at temperatures 1800°F. and up . . . temperatures that rapidly destroy conventional carbides or high temperature cast alloys.<br>Can be subjected continuously to operating temperatures up to 2200°F., and up to 5000°F. for short periods.<br>Greater resistance to thermal shock than ceramics.<br>Highest stiffness-to-weight ratio of any material . . . approximately ⅔ the weight of steel.<br>YME up to 60 million psi. | Sensing elements for high temperature thermostatic controls.<br>Spinning tools for hot metals.<br>Flash-trimming tools.<br>Turbine components.<br>Balls for pump check valves.<br>Nuclear reactor equipment.<br>Rotary seal rings.<br>Hot rod mill guide inserts.<br>Anvils for spot welding.<br>Balls for hot hardness testing. |
| **Refractory Carbides** | High purity.<br>High melting point—5000°F. to 7000°F. | In powder form as basic materials.<br>Acid resistant parts and crucibles.<br>High temperature furnace parts. |
| **Heavy Tungsten Alloys** | Nominal Density: 16.5 to 18.7 gm/cc.<br>Machinability? Good.<br>Tensile Strength: 40,000 to 90,000 psi.<br>Corrosion Resistance: Excellent.<br>Readily brazed with Easy-Flo No. 3 Compound.<br>Available as bars, rods, rings, discs, special shapes. | Counterweights.<br>Radioactive shielding.<br>Isotope containers.<br>Atomic watch shielding.<br>Shielding—cobalt and X-ray medical equipment.<br>Rotational parts—flywheels, governors, gyroscope components.<br>Electrical contactors for high current, heavy duty applications. |
| **Niobium** | Metal—99.8% grade. Granules, arc melting electrodes, bar, strip.<br>Metal—99.5% and technical grades. Powders, granules, arc melting electrodes.<br>Oxide—99% and 99.5% grades. Fine powder. | Arc melting electrodes:<br>Nominal size 1″ x 2″ x 20″.<br>Niobium-base alloy electrodes also available.<br>Powders: 20 to 80 mesh.<br>Granules: 1/16″ to 40 mesh. |
| **Tantalum** | Metal—99.9% (capacitor) grade.<br>Solid form—strip, bar, wire.<br>Metal—99.5% grade. Granules.<br>Metal Powder—99.8% grade. Fine powder.<br>Oxide—99% grade. Fine powder. | Anodes: Sintered for both liquid and solid electrolytic capacitors, wide range of sizes.<br>Strip: .001″ to .100″ thick, up to 12″ wide.<br>Wire: From .005″ to .030″.<br>Powder: 200 mesh. Other sizes available.<br>Oxides: In analyses and particle sizes to meet specific requirements. |

*Trademark

### FOR DETAILED INFORMATION send for:

1. **Properties of Kennametal**—24-page outline of the company, its history, manufacturing methods and facilities. Plus a detailed description of Kennametal and Kentanium characteristics . . . physical and mechanical properties, with suggestions for design application.
2. **Kentanium**—12-page description of physical characteristics and applications.
3. **Designing with Kennametal**—42 pages of design ideas . . . problems and solutions in designing with carbides, fastening methods, typical applications.
4. **Proven Uses of Kennametal and Kentanium**—28-page case history book illustrating wear, component parts, and other special applications in 26 major industries. Cites customers' savings, Kennametal facilities, and services.

**Write Dept. MDE, KENNAMETAL INC., Latrobe, Pennsylvania.** 33519



INDUSTRY AND
**KENNAMETAL**
*...Partners in Progress*

For more information, turn to Reader Service card, circle No. 434

*Here's why you should consider*


# NATIONAL GRAPHITE
TRADE-MARK

## ...it has a unique combination of properties


| | | | |
|---|---|---|---|
| RESISTS THERMAL SHOCK | GOOD ELECTRICAL CONDUCTIVITY | CORROSION RESISTANCE | STRENGTH INCREASES WITH TEMPERATURE RISE |
| HIGH THERMAL CONDUCTIVITY | LOW THERMAL EXPANSION | NOT WET BY MOST MOLTEN METALS | EASY TO FABRICATE |

## ...it's available in a wide variety of sizes and shapes

"National" graphite is available from minute particles to five ton blocks . . in all sizes of square, round, rectangular and cylindrical shapes. Whatever your needs — whether quantity, purity or size . . . whether machined or unmachined . . call on National Carbon Company, the nation's most experienced graphite producer.



## ...and NATIONAL CARBON can machine it to your specifications



*One of several well equipped NATIONAL CARBON machine shops for fabricating graphite.*

Economically machining graphite at National Carbon Company is a result of years of graphite machining experience teamed with modern equipment located at several strategic locations. Turning out simple or intricate shapes and holding to close tolerances are everyday procedures at these shops. No job is too small or too big, too simple or too complex to receive the required expert consideration and attention.

Whatever your needs, whether simple or complicated parts made from standard or special grades, let National Carbon Company quote on your requirements. For details, contact your National Carbon representative or the nearest sales office.

"National" and "Union Carbide" are registered trade-marks for products of

**NATIONAL CARBON COMPANY**
Division of Union Carbide Corporation . 270 Park Avenue, New York 17, New York
IN CANADA: Union Carbide Canada Limited, Toronto

UNION CARBIDE

For more information, turn to Reader Service card, circle No. 448

# Physical Properties of McDANEL Industrial Ceramics

| FIRED PROPERTIES | Pure Alumina 99% $Al_2O_3$ | Pure Alumina 99% $Al_2O_3$ | Vitreous Alumina 96% $Al_2O_3$ | Vitreous Alumina 85% $Al_2O_3$ | Crushable Alumina | Vitreous Refractory Mullite | Vitreous Refractory Mullite | Vitreous Refractory Mullite |
|---|---|---|---|---|---|---|---|---|
| **BODY NUMBER** | **AP30** | **AP35** | **AV30** | **AV20** | **CA** | **MV33** | **MV30** | **MV20** |
| Water Absorption % | 12.9 | 0.00 | 0.00 | 0.00 | 13.5 | 0.00 | 0.00 | 0.00 |
| Specific Gravity | 2.6 | 3.7 | 3.5 | 3.2 | | 3.3 | 3.2 | 3.0 |
| Gas Permeability R.T.<br>Temperature to which $10^{-5}$ mm Hg will maintain | Porous | Impervious 1500° C 2732° F | Impervious 1450° C 2642° F | Impervious | Porous | Impervious 1500° C 2732° F | Impervious 1450° C 2642° F | Impervious |
| Compressive Strength psi | | 250,000 | 250,000 | 150,000 | | 150,000 | 120,000 | 100,000 |
| Tensile Strength psi | | 35,000 | 35,000 | 20,000 | | 18,000 | 18,000 | 14,000 |
| Transverse Strength psi | | 45,000 | 45,000 | 30,000 | | 22,000 | 20,000 | 20,000 |
| Coefficient of Linear Thermal Expansion /° C<br>/° F | $7.8 \times 10^{-6}$<br>$4.3 \times 10^{-6}$ | $7.8 \times 10^{-6}$<br>$4.3 \times 10^{-6}$ | $7.8 \times 10^{-6}$<br>$4.3 \times 10^{-6}$ | $7.2 \times 10^{-6}$<br>$4.0 \times 10^{-6}$ | | $4.8 \times 10^{-6}$<br>$2.7 \times 10^{-6}$ | $5.4 \times 10^{-6}$<br>$3.0 \times 10^{-6}$ | $5.0 \times 10^{-6}$<br>$2.8 \times 10^{-6}$ |
| Approximate Thermal Conductivity cal/sec/$cm^2$/cm/° C<br>Btu/hr/$ft^2$/in/° F | .040<br>116. | .050<br>145. | .050<br>145. | .040<br>116. | | .006<br>17.4 | .006<br>17.4 | .005<br>14.5 |
| Maximum Service Temperature ° C<br>° F | 1900° C<br>3452° F | 1900° C<br>3452° F | 1650° C<br>3002° F | 1520° C<br>2768° F | 1650° C<br>3002° F | 1760° C<br>3200° F | 1650° C<br>3002° F | 1650° C<br>3002° F |
| Dielectric Constant 1MC | | 9.0 | 8.5 | 8.5 | | 7.0 | 7.0 | 6.5 |
| Dielectric Strength volts/mil ¼" thickness | | 400 | 350 | 300 | | 300 | 300 | 300 |
| Volume Resistivity Room Temp.<br>Ohm cm. 700° C | | $10^{15}$<br>$10^{8}$ | $10^{15}$<br>$10^{8}$ | $10^{15}$<br>$10^{7}$ | $10^{14}$<br>$10^{6}$ | $10^{15}$<br>$10^{6}$ | $10^{15}$<br>$10^{6}$ | $10^{14}$ |
| Te Value ° C<br>° F | 800° C<br>1472° F | 800° C<br>1472° F | 800° C<br>1472° F | 800° C<br>1472° F | 800° C<br>1472° F | 800° C<br>1472° F | 700° C<br>1292° F | 700° C<br>1292° F |
| Hardness (Mohs Scale) | | 9 | 9 | 8½ | Chalky | 8 | 7½-8 | |
| Fabrication Methods | Cast<br>Dry Press<br>Extrusion | Cast<br>Dry Press<br>Extrusion | Cast<br>Dry Press<br>Extrusion | Dry Press<br>Extrusion | Extrusion | Cast<br>Extrusion | Cast | Dry Press<br>Extrusion |
| Comments D660 | Fine grain material. Use above 1650° C will result in additional shrinkage. | Recrystalized Alumina, our most refractory material. Excellent deformation resistance. Superior resistance to reducing atmospheres and chemical reaction at high temperatures. | Recrystalized Alumina. Low loss, high dielectric for normal and high temperatures. High strength with excellent resistance to abrasion, chemical attack and reducing atmosphere. | Good abrasion resistance and electrical properties for lower temperature use. | Soft bonded insulation for swaged thermocouples. Non-hygroscopic. | Stoichiometric Mullite similar to MV30 but with little or no free silica. Exceptional deformation resistance at elevated temperatures. | Good chemical and atmosphere resistance at elevated temps. Excellent thermal shock and sag resistance. | Similar to MV30 but somewhat lower in all physical properties. |

McDANEL Industrial CERAMICS Since 1919

• The modern equipment in our plant puts every ceramic process known to the industry at your service. This provides the best materials for your particular application and the most economical approach to the problem. A phone call or a letter and a sketch of your project will give you specific information on your problem.

McDANEL

REFRACTORY PORCELAIN COMPANY

BEAVER FALLS • PENNSYLVANIA

For more information, turn to Reader Service card, circle No. 445

# Graphite Specialties CORPORATION


Solves difficult problems with GRAPHITE for

FURNACES
CHLORINE HEATERS
MECHANICAL USES
SPACECRAFT
ATOMIC ENERGY
METALLURGICAL PROCESSING

Graphite Specialties
CORPORATION
64th Street and Pine Avenue
Niagara Falls, New York

For more information, circle No. 425

Just published...




NEW BROCHURE
shows how Glass can be engineered to solve specific design problems

Twenty colorful pages describe the Kopp Glass engineering service; showing how the properties of glass are controlled and combined to provide designers and manufacturers with specialized, custom-produced products that meet specific application requirements. This includes analyzing the application, developing the formula, designing the mold and establishing manufacturing procedures.

*A few examples shown in the book* include street and highway traffic control lenses; aviation, marine and railroad signaling lenses; dental and surgical lighting filters; street and interior lighting glassware; floodlight cover glasses; industrial globes and indicator lenses; theatrical and exterior lighting color filters.

Send this coupon for your FREE copy

KOPP GLASS

Kopp Glass, Inc. MDE
Swissvale, Pa.

Please send copy of "This is Kopp Glass"

NAME_____

COMPANY_____ TITLE_____

ADDRESS_____

CITY_____ STATE_____

**Kopp Glass, INC.**
Swissvale, Pennsylvania
MANUFACTURERS OF MOLDED INDUSTRIAL AND SIGNAL GLASSWARE

For more information, turn to Reader Service card, circle No. 545



# Can these **FELT IDEAS** help you?



**FELT GREATLY REDUCES GLAZING COSTS**

over conventional brushing. Fine china manufacturer uses special Felters DuFelt Polishing Belt to reduce glazing costs. Felt coarseness and density can be varied for most effective polishing of metal, glass and ceramics. Can also be coated with abrasives.



**FELT ADHESIVE TAPES AND PADS**

are the most inexpensive material for sealing, padding and cushioning. Felt strips seal out dust, dirt, wind, fumes, moisture, and eliminate squeaks and rattles.



**FELT AS A LOW COST FRICTION MATERIAL**


Used as a braking or friction device, sometimes combined as a seal or washer. High coefficient of friction and extra density provide foolproof clutching and tension action at low cost, like the Lever Puller shown at left.





**To get the most out of Felt,** send for the Felters Design Book — a complete digest on properties and applications. Write, today.




**DuFelt is a laminated combination** of Felters' felt and Hycar; and is recommended for sealing of lighter oils when no head exists. Seals and lubricates at the same time; and offers improvements over other materials.



**Felt is an ideal wicking** and lubricating material which can be designed into special assemblies like this distributor cam shown here. Lubrication is constant, wear reduced, and felt can be shaped to cover all required areas.



**Lifetime bearing lubrication** is now possible by selection of correct SAE grade, and designing into sealed bearing. Felt filters out contamination and works as combined reservoir and wick, directing oil flow to required areas.



**Mechanical felt seals** permit a close seal without undue pressure. Felt can be waterproofed and provides superior grease and oil retaining and dust, dirt and grit exclusion.

*Ask for* **FELT** *from . . .*

## THE FELTERS COMPANY

220 SOUTH STREET, BOSTON 11, MASSACHUSETTS

*Pioneer Producers of Felt and Synthetic Non-Woven Fabrics*

FCO-26

**For more information, turn to Reader Service card, circle No. 419**




**YOU CAN GET better laminated and molded products** three ways with Pittsburgh Fiber Glass. ○ *First*—PPG provides you with a quality, uniform reinforcement of exceptional dimensional stability and dielectric strength; it's fire-resistant, heat-resistant, odorless. ○ *Second*—PPG can supply you with quality YARNS in any twist or ply, in all standard sizes . . . ROVING in a variety of finishes and end counts wound to your requirements; it's static-free, ideal for use in preforming or spraying . . . CHOPPED STRAND in lengths of ¼" and up, packaged for convenient handling; its uniformity helps cut rejects. ○ *Third*—PPG offers you technical help through free trials made in your own plant to show you how Pittsburgh Fiber Glass can help you produce better end products. Call your nearest PPG Sales Office or write Pittsburgh Plate Glass Company, Fiber Glass Division, One Gateway Center, Pittsburgh 22, Pa.

Sales Offices: Atlanta, Boston, Buffalo, Charlotte, Chicago, Cincinnati, Cleveland, Dallas, Denver, Detroit, Fort Wayne, Houston, Jacksonville, Kansas City, Los Angeles, Louisville, Milwaukee, Minneapolis, New Orleans, New York, Philadelphia, Pittsburgh, St. Louis, San Francisco, Seattle and Washington.


FIBER PPG GLASS PITTSBURGH PLATE GLASS COMPANY

For more information, turn to Reader Service card, circle No. 455

WHATEVER MATERIAL ADVANTAGES YOU NEED,
YOU'LL FIND THEM IN A+ FELTS...

AVAILABLE NOW FROM AMERICAN FELT COMPANY

# VALUABLE NEW GUIDE
FOR YOUR REFERENCE



**A+ FELT APPLICATIONS GUIDE**

In the all-important area of materials selection, the "A+ Felt Applications Guide" is an important new tool and source of ideas for engineers and designers.

A+ Felts are engineered in a wide variety of fibers and types, meeting the specifications of numerous industrial and scientific applications.

Our new "A+ Felt Applications Guide" surveys the tremendous range of felt applications including wicking and lubricating, vibration isolation, spacing, surfacing and padding, cushioning, packaging, polishing, sealing, frictional applications, shock absorbing, filtration, thermal insulation, sound absorption, percussion control, and as a fashion and design material.

Send the coupon for your personal copy.

A+ ... *Symbol of your guarantee of unsurpassed excellence in materials ... engineering ... and service.*

AMERICAN FELT COMPANY
902 GLENVILLE ROAD, GLENVILLE, CONN.


*Gentlemen:* Please send me, without obligation, your new booklet "A+ Felt Applications Guide."

NAME.....
COMPANY.....
POSITION.....
STREET.....
CITY.....ZONE.....STATE.....




For more information, turn to Reader Service card, circle No. 383

***An example of Avisco Rayons in Industry***



# Why rayon fibers are rapidly gaining in filtration applications

Avisco rayon fibers have been making giant strides in filters for smoke, air and liquid filtration. Why? Because they can be engineered to meet specific filtration needs . . . plus low cost and filtration control.

Avisco rayon can be produced in accurate diameters resulting in controlled micron ratings economically unapproached by other fibers.

American Viscose makes the fibers, not the filters. If you make or use filters, it will pay you to investigate Avisco fibers for more accurate, more economical filtration. *Just fill in the Quick Reply Coupon.*

**QUICK REPLY COUPON** 1-5

American Viscose Corporation
350 Fifth Avenue, New York 1, N.Y.

Please contact me about Avisco Fibers for filtration use in

_____

Name_____

Company name_____

Address_____

City_____ Zone____ State_____

**AVISCO® RAYON**

AMERICAN VISCOSE CORPORATION, 350 Fifth Avenue, New York 1, N. Y.

For more information, turn to Reader Service card, circle No. 499

# Proper Words in Proper Places . . .

*Covers books, journals, manuals, graphic aids . . .*

## 1 TECHNICAL EDITING

Edited by
**B. H. WEIL**
Chief Editor, Technical Information Division
Esso Research and Engineering Company





Here are the basic concepts and operating practices of internal communications, journal editing, book publishing, and graphic aids presentation for all technical fields. The contributors are leading authorities, and they provide ideal guidance for both the experienced and beginning editor. This book is much more than a copyreading manual; it deals with editing as a primary communications step. It relates the documents of all technical areas to the cardinal purpose of serving the potential reader. There is also emphasis on how to work with authors. This is the first time that every technical editing principle has been brought together in one place. The coverage of subjects and techniques is thoroughly up-to-date. The book serves the experienced technical editor, the management of technical industries and agencies, the fledgling editor, and the technical student who is attracted to editing as a profession.

**1958, 288 pages, $5.75**

*Do it right the first time . . .*

## 2 INFORMATION AND COMMUNICATION PRACTICE IN INDUSTRY

Edited by
**T. E. R. SINGER**
Technical Information Consultant




Immediate answers to every communication question are clearly provided here in the best handbook style. Nineteen chapters cover the entire subject for technical organizations of all kinds. Several leading experts contribute valuable directions for the most efficient handling and transmission of data, information and ideas. Whether you want to design data tables, classify material, edit a report, or abstract articles—this is the one book that shows you how to accomplish the numerous tasks involved with modern communications. By the very nature of its material, it also provides ideas and suggestions for improving company or institutional communications programs.

**1958, 310 pages, $8.75**

*Write what you mean . . .*

## 3 BETTER REPORT WRITING

by **WILLIS H. WALDO**
Technical Editor, Research Dept.
Organic Chemicals Div., Monsanto Chemical Co., St. Louis, Mo.



Here is fingertip help with the chronic problems of scientific expression for all technical report writers. This handy desk guide presents authoritative facts on the important details of effective scientific composition, style, division of reports, tables, illustrations, and use of words. The book is purposely written as a quick reference instead of a classical exposition of technical English. It simplifies the solution of writing problems for all technical authors. Three appendices condense a vast amount of information on abbreviations, symbols and hyphenation. This is the first easily readable guide in book form for the practicing report writer. Whatever field of technical endeavor you're reporting, this handbook contains much profitable information for you.

**1957, 239 pages, $4.75**

*Say what you mean . . .*

## 4 ORAL COMMUNICATION of Technical Information

by **ROBERT S. CASEY**
W. A. Shaeffer Pen Co., Fort Madison, Iowa




Methods of effective speaking for almost all situations are assembled here in "how-to" manner for technical men. Beginning with the bridges and barriers to effective communication, the book then takes up the actual problems involved and how they are solved. It covers organization of material, composition, delivery of formal and impromptu speeches, and the use of mechanical aids such as recordings and slides. How to preside at meetings, talk science to laymen, give technical legal testimony, and converse socially are covered in helpful detail. Emphasis is on the special needs of technical subject matter, but the techniques of organization and delivery apply to all speaking events. One valuable section reviews the most common errors in the speech-writing of chemists and engineers. It is doubtful that a more useful handbook for speakers in the technical field has ever been published.

**1958, 207 pages, $4.50**

*Quick, convenient guide to thousands of difficult technical words . . .*

## 5 HAWLEY'S TECHNICAL SPELLER

by **GESSNER G. HAWLEY**
Executive Editor, Reinhold Book Division
and **ALICE W. HAWLEY**
Consulting Editor




Contained in this handy book is a wide selection of technical words used in the fields of chemistry, physics, electronics, engineering, biology and medicine. Also included are many common words of troublesome spelling which repeatedly occur in technical writing and correspondence. Many of these words, such as names of complex chemicals and proper names, do not appear in desk-size dictionaries. Recommended word divisions are indicated, and easily confused meanings or spellings are explained in footnotes. Writers of technical letters and reports, advertising copy, scientific articles and books will want this quick-reference guide constantly within handy reach. Secretaries who take technical dictation or transcribe manuscripts will find it a wonderful time-saver.

**1955, 160 pages, $2.95**

*Free Examination Order Coupon*

**REINHOLD PUBLISHING CORPORATION**
Dept. M-701, 430 Park Avenue, New York 22, N. Y.

Send me the book(s) I have encircled below for 10 days' **FREE EXAMINATION.** In 10 days, I will either return the book(s) and owe nothing, or will send you full price plus postage.


1 2 3 4 5

NAME.....

ADDRESS.....

CITY & ZONE.....STATE.....

SAVE MONEY! You save shipping charges by enclosing payment with order. Same return privilege; refund guaranteed. Please include 3% sales tax on N. Y. C. orders. Do not enclose cash!




*Upper serviceable limit is the highest temperature at which the material can be folded 180° back upon itself without cracking after 72 hours' exposure. Low limit is the lowest temperature at which the material can be bent around a 1" mandrel after 1 hour's exposure.*

# Temperature effects on the serviceability of Du Pont Fairprene®

Charted above are the serviceable temperature ranges for many of Du Pont's "Fairprene"* coated fabrics. These materials form design materials of amazing versatility with an outstanding range of lubricant, solvent, flex, ozone, age and chemical resistance as well as thermal stability.


Du Pont engineers are eager to help you evaluate "Fairprene" for designing new products or improving old ones. These versatile materials are now being used in hundreds of applications ranging from fire walls to gaskets and diaphragms. For full information and your free copy of Du Pont's coated fabrics manual, mail coupon or write: E. I. du Pont de Nemours & Co. (Inc.), Fabrics Division MD-011, Wilmington 98, Delaware.

**A Du Pont registered trademark.*

**FREE** COATED FABRICS MANUAL

12-page booklet describes in detail all basic specifications, properties, uses and performance characteristics for "Fairprene"* coated fabrics and cements. Mail coupon or write Du Pont . . . there's no obligation.

DU PONT
REG. U. S. PAT. OFF.
Better Things for Better Living . . . through Chemistry



E. I. du Pont de Nemours & Co. (Inc.)
Fabrics Division MD-011, Wilmington 98, Delaware


Please send free information on:
☐ **"Fairprene" coated fabrics** ☐ **Du Pont technical service**
I am interested in using a coated fabric for_____

Name_____ Position_____
Company_____
Address_____
City_____ Zone_____ State_____

**For more information, turn to Reader Service card, circle No. 408**

*Let Your Creative Imagination Go to Work on These*

# NEW DEVELOPMENTS



**Chrysotile asbestos,** one of the most versatile and economical fibrous materials available today, is steadily increasing its value as an engineering material. In addition to being less expensive than other fibrous reinforcing materials and in abundant supply, chrysotile asbestos outperforms all known fibrous materials when the following combination of characteristics is needed:

- HEAT RESISTANCE
- WEATHER RESISTANCE
- MOISTURE RESISTANCE
- ABRASION RESISTANCE
- HIGH TENSILE STRENGTH
- FREEZE AND THAW RESISTANCE

For your information, Lake Asbestos of Quebec reports here two new developments which demonstrate the versatility of chrysotile fiber as a reinforcing design material.

## Cerbestos: For Continuous High Temperature Applications

One of the most promising new products from chrysotile fiber is Cerbestos, a combination of asbestos cloth and ceramic clay with all the advantages of both. Asbestos cloth provides the required strength, heat resistance and flexibility. Kaolin clay adds refractory properties and rigidity. Result: a new material with remarkably high thermal and mechanical stability.

Cerbestos has successfully withstood a temperature of 2500°F continuously for seven days. During a recent oxygen-acetylene burn-through test, a four-layer mat of Cerbestos withstood direct-torch heat 37½ times longer than stainless steel. Cerbestos is being evaluated for a number of missile and space probe applications, such as instrument shielding and rocket discharge tubes.


Cerbestos is an economical material easily formed into desired shapes for the most intricate applications. Explore its design possibilities for your products — old or new.

# IN ASBESTOS

## Asbestos Fiber in Non-Woven Form

The unique properties of chrysotile — fibrous form, tensile strength, fine diameter, flexibility, and resistance to heat, moisture and weathering — are combined in a new non-woven felt which is being used as the basic reinforcement for consumer products — chairs, tables, boats — for defense equipment, missile and space probe nose cones and other high temperature components. Asbestos felt, formed in continuous lengths in widths up to four feet, can be used as replacement for or in combination with glass fiber.

Less expensive than glass fiber and in abundant supply, non-woven asbestos felt means this to designers: A new inorganic fiber for reinforcing applications . . . superior strength, flexibility, abrasion resistance . . . better natural bonding . . . substantially lower production and end-product costs . . . greater design freedom.



**PHYSICAL CONSTANTS of Chrysotile Asbestos**

| | |
|---|---|
| Tensile Strength — psi | 300,000 to 400,000 |
| Modulus of Elasticity — psi | $26.5 \times 10^6$ |
| Fusion Point — °F | 2770 |
| Max. Ignition Loss Temp. — °F | 1800 |
| Specific Heat — BTU/lb./°F | 0.266 |
| pH | 8.6 |
| Surface Area — Sq. meters/gr. | 10 |
| Electrical Charge | Pos. |
| Finite Fiber Diameter — 180 Angstroms = 0.000000706" | |

**CHEMICAL DATA**

Typical Chemical Analysis of ASARCO Asbestos (percent by weight)

| | | | |
|---|---|---|---|
| MgO | 40.5 | $CO_2$ | 0.8 |
| $SiO_2$ | 39.0 | Cu | 0.0004 |
| $Al_2O_3$ | 0.6 | Mn | 0.070 |
| Total Iron as Fe | 3.2 | Cr | 0.09 |
| CaO | <0.1 | Ni | 0.13 |

Ign. loss at 1800°F ....14.2

*For additional information about non-woven asbestos felt* and Cerbestos* and how asbestos can best serve you, write to Sales Department, Lake Asbestos of Quebec, Ltd., 120 Broadway, New York 5, N. Y., or call REctor 2-9500.*

* Not produced by Lake Asbestos

CHRYSOTILE ASBESTOS

LAKE ASBESTOS OF QUEBEC, LTD.

*A subsidiary of American Smelting and Refining Company*

**ASARCO**

For more information, turn to Reader Service card, circle No. 436

# If your design includes a coated fabric... choose



# from over 200 styles of REEVECOTE!

## The most complete source of coated fabrics for industry

When your design calls for diaphragms, seals, gaskets, vapor barriers... any of the hundreds of coated fabric applications... look to the most complete source in the field—the Reevecote line of industrial coated fabrics.

With natural and synthetic rubber coatings, Reevecote is available in over 200 styles—also uncured for molding.

Whether its resistance to oil, acids, abrasion, high temperature ... or flexibility at low temperatures... there's a Reevecote fabric designed and engineered to do the job right.

Continuous research and development enables Reeves to keep pace with *all* your needs for coated fabrics. And our rigid quality control guarantees that Reevecote fabrics will always meet established specifications.

**Make your choice now! Write for new Reevecote catalog today.**

**REEVES VULCAN**

Reeves Brothers, Inc., Vulcan Rubber Products Division
1071 Avenue of the Americas · New York 18, New York

For more information, turn to Reader Service card, circle No. 494

# where contamination must be avoided

# SPECIFY SPEER ULTRA PURE GRAPHITE

You can eliminate undesirable contamination of many metals and crystals by using crucibles, boats and jigs made of SPEER Ultra Pure Graphite. Parts for electronic tubes and mercury-arc rectifiers may also be improved by the higher degree of purity now offered in this material.

**A typical sample of SPEER Ultra Pure Graphite would contain—**

| | |
|---|---|
| B | .25 ppm |
| Fe | 1.0 ppm |
| V | 1.0 ppm |

and—especially important in certain usages such as vacuum tubes—would show gas content of .2 to .5 $cm^3/gm$. This is less gas than is contained in corresponding unpurified grades.

What is your application? SPEER molded and extruded Ultra Pure Graphite is available in many grades and in sizes ranging to more than 16" diameter. We are also prepared to machine parts and equipment expertly to your own close tolerances. *Our engineers will be glad to discuss your specific problems with you.*

**SPEER Carbon Co**

CARBON PRODUCTS DIVISION
ST. MARYS, PENNSYLVANIA

For more information, circle No. 560

*Why it will pay you to*

# CONSIDER GLASS

*before your products reach the blueprint stage*

## WHY GLASS?

It's versatile and basic.

And if it is a *Corning* glass, it offers your products these solid benefits:

*Permanent finish.* Corning glass compositions resist weather, chemical attack, abrasion and high temperatures. Their surfaces stay non-absorbent and non-porous — clean quickly.

*Controlled transparency.* Corning glasses are uniformly transparent—piece after piece, year after year. Colored or clear—they never lose their original clarity.

*Hermetic enclosures* can be made in rugged designs from special glasses developed for glass-to-metal fusion sealing.

*Electrically conductive coatings.* Fired on to glass, they are a very efficient source of radiant energy. They provide uniform heat distribution of a long wave length radiation readily absorbed by most materials.

*Durability.* Glasses with ingenious balances of mechanical, electrical and chemical properties plus correlation of form and shape insure a durable product.

*Heat indifference.* Corning glass keeps strength and finish at high temperatures—in some compositions from 900°F. to 1700°F. Heat indifference is furthered by designs that carefully distribute thermal stress.

*Electrical stability.* Corning glasses have high resistivity, low power losses, low and high dielectric constants, excellent non-tracking properties. They can also be furnished with special characteristics of high dielectric strength.

*Chemical inertness.* Corning glasses resist most atmospheres and chemicals even at relatively high temperatures—do not pit, scale or rust. They keep their chemical, mechanical and electrical properties indefinitely.

## WHICH GLASS?

You can choose from five types of Corning glasses. These fill most needs. But, if you have an unusual application—one that cannot be met by any of the following types—special variations will be suggested.

*Borosilicate glasses* have high thermal endurance, softening points, chemical resistance, and excellent electrical stability.

*High silica glasses* have extreme thermal endurance, very high softening point, high chemical resistance, excellent electrical properties, and exceptional transmittance of the ultraviolet or the infrared.

*Opal glasses* have uniform and well-controlled translucence and good mechanical strength.

*Lime glasses* have controlled mechanical properties and excellent visual qualities.

*Lead glasses* have controlled mechanical and electrical properties and high visual quality.

## WHERE GLASS?

Because you can get Corning glass in almost any shape or form you wish—because you can be sure of the definite and fine balance of properties required for your specific needs, you can use Corning glass in a wide range of applications. Some of these are:

Ovenware
Coffeemakers
Laboratory ware
Electrical insulation
Gauge glasses
Industrial piping
Range burner plates
Crucibles
Ultraviolet lamps
Thermocouple protecting tubes
Induction furnace linings
Electrical insulation
Lighting ware
Food service dishes
Refrigerator storage dishes
Incandescent lamps and stems
Tumblers
Vacuum bottles
Fluorescent lamps
Tableware
Refrigerator trays
Washer windows
Level vials
Fuses
Lampworked novelties
Bowls for food mixers

## FREE BULLETIN

For more complete information on how you can advantageously use glass in your product design, send coupon for Bulletin IZ-1.

It lists specifications of the various types and forms of Corning glasses and tells how our design service can help you.



CORNING MEANS RESEARCH IN GLASS

**CORNING GLASS WORKS** 50-10 Crystal Street, Corning, N.Y.

Please send me a copy of Bulletin IZ-1, entitled "Designing with Glass for Industrial, Commercial and Consumer Applications."

Name_____ Title_____


Company_____

Street_____

City_____ Zone____ State_____

For more information, turn to Reader Service card, circle No. 402

# DON'T OVERLOOK CARBON/GRAPHITE!



## No Other Material Can Do ANY of These:

- ★ Withstand immersion in water from 4,000°F without cracking.
- ★ Resist surface atmospheric action while retaining constant and reproducible contact resistance.
- ★ Be readily processed to provide low friction (graphite) or high friction (carbon) or any desired intermediate value.
- ★ Withstand electric arcing in contacts, lightning arresters and similar applications without appreciable dimensional changes.
- ★ Serve as an electrical conductor which is readily machinable and can operate satisfactorily up to 6,000°F.

## No Other Material Can Do ALL of These:

- ★ Resist corrosive action of most gases and chemicals.
- ★ Serve as a semi-permanent, readily-formed mold for casting metals or glass.
- ★ Act as a seal ring around a moving shaft to retain liquids and gases.
- ★ Operate as a sliding contact on commutators and slip rings.
- ★ Serve as a bearing material for vacuum applications or as an insert in ordinary bearings.
- ★ Operate as a friction unit in constant-speed clutches.
- ★ Serve as a non-welding contact, either by itself or in combination with other metals.

STACKPOLE CARBON COMPANY, St. Marys, Pa.

# STACKPOLE

**"EVERYTHING IN CARBON BUT DIAMONDS"**

SEAL RINGS • BEARINGS • ROCKET NOZZLES • ELECTROCHEMICAL CELL ANODES • FLUXING TUBES • BRAZING BOATS & TRAYS • CATHODIC PROTECTION ANODES • RISER RODS • VOLTAGE REGULATOR DISCS • ELECTRICAL CONTACTS • HEATING ELEMENTS & ELECTRODES • TUBE ANODES • BRAZING TIPS • RUN-OUT TABLE SLABS • MOTOR & GENERATOR BRUSHES • FRICTION SEGMENTS • PUMP VANES • POROUS CARBON . . . and many more.

For more information, turn to Reader Service card, circle No. 477



# CREATIVE IMAGINATION *in Specialty* PAPERS ★




★ *Can it be made of PAPER?*

Western Union thought so. Knowlton Brothers helped prove it could. Although others had failed, Knowlton produced a high-quality base for electro-sensitive paper used in the Western Union Telefax system.

**ONE OF MANY SPECIAL-PURPOSE INDUSTRIAL PAPERS**

Knowlton Brothers have the scientific and technical manpower, the research facilities, the pilot-plant machinery . . . and above all, the *creative imagination* to develop, or make to rigorously maintained specifications, industrial papers for applications where paper was never used before. Chances are, the car you drive, the plane you fly in, has a Knowlton-developed paper in a vital engine part.

***Don't Wonder Any Longer; Ask Knowlton Brothers***

Maybe the relative lightness of paper interests you . . . or the economy . . . the availability . . . the uniformity. But don't wonder. Just ask Knowlton Brothers.

**A Few Conventional Uses of Knowlton Papers:**

*To . . .*

| | | |
|---|---|---|
| Conduct | Dialyze | Cushion |
| Laminate | Shape | Rupture |
| Copy | Insulate | Shield |
| Contain | Record | Synthesize |

**Development Possibilities are Unlimited.**




**WRITE** for free copy of the helpful book, "Creative Imagination in the Development of Technical and Industrial Papers." PHONE or WIRE for a sales engineer to call.


Knowlton Brothers
INCORPORATED

Dept. 311, WATERTOWN, N. Y.


For more information, circle No. 435

# Strong, rugged reinforcement at low cost


Reinforce your plastic products with a fiber glass *woven roving* that's consistently uniform—in weave, sizing and strength. Every roll of UNIROVE is checked against Ferro high-quality standards at every stage of production. This gives you extra value at low woven roving costs. Every roll you receive must conform to the highest "specs". Write for samples, specifications, prices.




CHECK FERRO FIRST... for your complete fiber glass needs!




*Mat* *Fabric* *Woven Roving* *Tape* *Chopped Strand* *Milled Fiber*



**FERRO CORPORATION**
FIBER GLASS DIVISION
Nashville 11, Tenn. . . . Huntington Beach, California
*Other Ferro plants in Argentina, Australia, Brazil, Chile, England, France, Holland, Hong Kong, Japan, Mexico and South Africa. Write for full addresses.*

For more information, circle No. 447

# *Whats' NEW in* INDUSTRIAL* FELT?



**NOW!** Synthetic Fiber Felts and Wool Felts designed for exacting, special applications!

**NOW!** Available CUT to meet your specifications!

**NOW!** Large diversified inventory insures prompt delivery!

*Available in all weights, widths, colors, etc. and made to S.A.E. and Federal Gov't. Specifications.

**FREE** Folder of samples and applications of Industrial Felt. Write for Booklet K-4.



CONTINENTAL **FELT** COMPANY. 1905

22-26 WEST 15th STREET NEW YORK 11 N. Y.

For more information, turn to Reader Service card, circle No. 400

## WANT HEAT DEFIANCE? try KARAK




**4,000—5,000 degree Thermit eats through steel... won't harm KARAK!**

5,000 degrees generated within a fraction of a second, couldn't crack or chip KARAK...exerted no effect other than slight oxidation of the surface.

**This heat-defiance has its uses!**

...Just one quality of KARAK carbon-graphite...a chemically inert material most often used for rings, bearings and seals because of its self-lubricating nature.

*Request new, FREE complete KARAK technical brochure*



The OHIO CARBON COMPANY

12508 Berea Rd., Dept. 286, Cleveland 11, Ohio

For more information, turn to Reader Service card, circle No. 511

Includes processes, properties, design and applications . . .


# WELDING OF PLASTICS

**by J. A. NEUMANN and F. J. BOCKHOFF**

*American Agile Corporation, Bedford, Ohio*

Here is the only comprehensive treatment of all phases of this subject ranging from initial design procedures to final detailed fabrication methods. Various physical and chemical properties of individual plastics presently used for welded construction are completely covered with regard to their use in chemical and allied processing. All presently known techniques of welding are covered in detail and many step-by-step procedures with photographs are included. In addition, the book contains one of the most complete corrosion resistance tables yet published, plus a concise guide for the choice of an appropriate plastic construction material. An entire chapter is devoted solely to design considerations as they specifically affect welded construction. Testing and evaluation are also given separate treatment.

The most recent welding materials, such as linear polyethylene, polypropylene, chlorinated polyethers, and the newer fluorocarbons are covered in detail. In addition, the newest welding techniques are presented in a complete, up-to-date manner.




**CONTENTS**

Introduction
Hot-Gas Welding
Basic Shapes and Forms
Layout, Forming and Machining
Heated-Tool Welding
Friction Welding
Welding Film and Thin Sheet
Design Considerations
Testing Methods
Ducting and Piping
Self-Supporting Vessels
Linings
Special Techniques and Applications
Glossary of Terms
Trade Names of Weldable Plastics
Chemical Resistance of Some Weldable Thermoplastics
Service Ratings and Temperatures
Weldable Plastics

**1959**
**288 pages**
**$7.25**

*Examine It Free for 10 Days*

**MAIL THIS COUPON NOW!**

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-708, 430 Park Avenue, New York 22, N. Y.**

Please send me a copy of WELDING OF PLASTICS for Free Examination. After 10 days, I will send you $7.25 plus shipping costs or I will return the book and owe nothing.

NAME .....

ADDRESS .....

CITY AND ZONE .....

SAVE MONEY! Enclose $7.25 with order and Reinhold pays all shipping costs. Same return privilege. Please add 3% sales tax on N. Y. C. orders. DO NOT ENCLOSE CASH!

For more information, circle No. 525

ceramoplastics and glass-bonded mica

# ENGINEERING COMPARA CHART

*Tear out this valuable COMPARA CHART—for additional copies write to Mycalex Corporation of America*

## ceramoplastics

**SUPRAMICA® 620**
A compression-molded ceramoplastic made with synthetic mica. Has a maximum temperature endurance of 1550°F (unstressed) and a heat distortion temperature** of 1360°F. Machinable to .0001 inch tolerances.

**SUPRAMICA® 500**
A compression-molded ceramoplastic made with synthetic mica, that has a maximum temperature endurance of 700°F (unstressed) and a heat distortion temperature** of 900°F. Readily machinable; not precision moldable.

**SUPRAMICA® 560**
A precision-molded ceramoplastic with a maximum temperature endurance of 932°F (unstressed) and a heat distortion temperature** of 870°F. Inserts may be molded in.

**SUPRAMICA® 555**
A precision-molded ceramoplastic that withstands a maximum temperature endurance of 650°F (unstressed) and a heat distortion temperature** of 700°F. Moldable with or without inserts.

## glass-bonded mica

**MYCALEX® 400**
A standard grade compression-molded, glass-bonded mica that withstands a maximum temperature endurance of 700°F (unstressed) and a heat distortion temperature** of 850°F. Readily machinable, but not moldable. Inserts must be cemented.

**MYCALEX® 410**
Glass-bonded mica, precision-molded with or without inserts, for applications involving a maximum temperature endurance of 650°F (unstressed) and a heat distortion temperature** of 690°F.

**MYCALEX® 410X**
A lightweight, precision-molded glass-bonded mica, with somewhat higher loss factor, having a maximum temperature endurance of 575°F (unstressed) and a heat distortion temperature** of 690°F.

**MYCALEX® 385**
An arc-resistant glass-bonded mica with excellent resistance to thermal shock, that withstands a maximum temperature endurance of 700°F (unstressed) and a heat distortion temperature** of 850°F. Readily machinable, but not moldable.

*SUPRAMICA, MYCALEX, SYNTHAMICA, "400" and "410X" are registered trademarks of Mycalex Corporation of America; "385", "500", "560", and "620" are trademarks of Mycalex Corporation of America.

**ASTM Test Method D648 (modified for glass-bonded mica) at stress of 264 psi—except as noted.

SYNTHAMICA® SYNTHETIC MICA · SINCE 1919 MYCALEX® GLASS-BONDED MICA · SUPRAMICA® CERAMOPLASTIC

**MYCALEX**
CORPORATION OF AMERICA

# The family of the world's most nearly perfect electronic and electrical insulation materials

**MYCALEX CORPORATION OF AMERICA**—world's largest manufacturer of glass-bonded mica, ceramoplastic and synthetic mica products—offers a wide selection of versatile electrical and electronic insulation materials, whose properties are described in these pages.

Each material offers a unique combination of special engineering advantages and is an *exclusive formulation* of the MYCALEX CORPORATION OF AMERICA. The charts on the following pages point up the many gains that can be achieved with MYCALEX® glass-bonded mica and SUPRAMICA® ceramoplastic materials, including their maximum temperature endurance and heat distortion limits.

Long experience enables our engineers to recommend the particular product which most precisely and most economically fits your requirements.

It is desirable, for this reason, to call upon the services of MYCALEX CORPORATION OF AMERICA while components are in the initial design stages. You will find our technical knowledge and our machining and precision molding skills invaluable in creating accurate, reliable components.

**SUPRAMICA** ceramoplastics are advanced formulations of SYNTHAMICA® synthetic mica and high-temperature glass. They are available in precision-molded and machinable types, both of which have *total* dimensional stability. This synthetic mica used exclusively in our formulations confers exceptional heat resistance upon our family of SUPRAMICA ceramoplastics . . . permitting maximum temperature endurances up to 1550°F (unstressed).

**MYCALEX** glass-bonded mica formulations contain high-quality natural mica and electrical grade glasses. They offer high dielectric strength, *total* dimensional stability, high-arc resistance and high-temperature resistance. Depending on formulation, they can be machined or precision-molded to exacting tolerances, and inserts can be molded or cemented in; the thermal expansion of MYCALEX is close to that of stainless steel.

*General Offices and Plant:* 125 Clifton Blvd., Clifton, N. J.
*Executive Offices:* 30 Rockefeller Plaza, New York 20, N.Y.

**World's largest manufacturer of glass-bonded mica, ceramoplastic and synthetic mica products**

# ENGINEERING COMPARA CHART

## A VALUABLE COMPARISON OF

### electrical

### the

| | DISSIPATION FACTOR $10^6$ cycles/sec. | DIELECTRIC CONSTANT $10^6$ cycles/sec. | LOSS FACTOR $10^6$ cycles/sec. | DIELECTRIC STRENGTH ⅛" thick v/mil | ARC RESISTANCE ASTM Seconds | HEAT DISTORTION TEMPERATURE °F ** | MAXIMU TEMPERAT ENDURAN °F |
|---|---|---|---|---|---|---|---|
| **SUPRAMICA 620** ceramoplastic (machinable) | 0.0015 | 7.2 | 0.011 | 250 | 300 | 1360 | 1550 |
| **SUPRAMICA 500** compression-molded ceramoplastic (machinable) | 0.0015 | 7.0 | 0.011 | 500 | 300 | 900 | 700 |
| **MYCALEX 400** compression-molded glass-bonded mica (machinable) | 0.0018 | 7.2 | 0.013 | 500 | 300 | 850 | 700 |
| **SUPRAMICA 555** precision-molded ceramoplastic | 0.0015 | 9.0 | 0.014 | 400 | 250 | 700 | 650 |
| **SUPRAMICA 560** precision-molded ceramoplastic | 0.0020 | 6.7 | 0.013 | 350 | 250 | 870 | 932 |
| **MYCALEX 410** precision-molded glass-bonded mica | 0.0015 | 9.2 | 0.014 | 400 | 250 | 690 | 650 |
| **MYCALEX 410X** precision-molded glass-bonded mica | 0.0025 | 6.3 | 0.016 | 350 | 200 | 690 | 575 |
| Steatite ceramic | 0.0008-0.0035 | 5.2-6.3 | 0.0042-0.0220 | 200-350 | 500 | — | 1800 |
| Mica-filled phenolic | 0.015-0.040 | 4.2-5.2 | 0.021-0.200 | 250-390 | tracks | 230-350 | 250-300 |
| Alkyd polyester molding compound—mineral filled | 0.015-0.040 | 4.6-5.5 | 0.069-0.220 | 300-350 | 75-190 | 350-425 | 300-350 |
| *Melamine asbestos filled | 0.041-0.050 | 6.1-6.7 | 0.250-0.330 | 320 | 120-140 | 265 | 250-400 |
| *General purpose phenolic-wood flour filled | 0.030-0.070 | 4.0-10.0 | 0.120-0.490 | 100-375 | tracks | 260-340 | 300-350 |
| *Polytetrafluoroethylene | 0.0002 | 2.0 | 0.0004 | 430 | 200 | 250 (66 psi) | 500 |
| *Polymonochlorotrifluoroethylene | 0.0036 | 2.5 | 0.009 | 600 | 360 | 160 (66 psi) | 390 |
| *Polystyrene | 0.0001-0.0004 | 2.40-2.65 | 0.0002-0.0011 | 400-600 | 60-80 | 150-195 | 150-170 |
| Electrical glass | 0.0005-0.0100 | 3.8-14.5 | 0.0019-0.145 | 200-480 | 500 | 925-1679 *** | 700-900 |
| Porcelain | 0.0006-0.0200 | 5.4-7.0 | 0.003 0.140 | 40-400 | 500 | — | 2200 |
| *Nylon | 0.030 0.040 | 3.4-3.5 | 0.102 0.140 | 340-410 | 130-140 | 300-360 | 270-300 |
| *Polyester—glass | 0.008-0.030 | 3.5-6.4 | 0.028 0.192 | 275-390 | 60-180 | 400 | 300-350 |
| *Silicone—glass (molding) | 0.0020-0.0200 | 3.2-4.7 | 0.006-0.064 | 125-300 | 20-250 | 570 | 450+ |
| *Silicone—glass (laminate) | 0.0006-0.0035 | 3.7-4.3 | 0.0022-0.0141 | 150-350 | 150-250 | 500 | 400+ |
| *Cold-molded organic | 0.070 | 6.0 | 0.420 | 50-75 | 75-200 | 400+ | 500 |
| *Cold-molded inorganic | — | — | high | 50-80 | 100-600 | — | 900 |

*Tear out this valuable COMPARA CHART—for additional copies write to Mycalex Corporation of America*

SYNTHAMICA® SYNTHETIC MICA · MYCALEX® THE INSULATOR · SUPRAMICA® CERAMOPLASTIC

**MYCALEX**
CORPORATION OF AMERICA

* Data Plastics Properties Chart, courtesy Modern Plastics Encyclopedia

** ASTM Test Method D648 (modified for glass-bonded mica) at stress of 264 psi—except as noted.

*** Not in accordance with ASTM Test Method D648.

World's largest manufacturer of glass-

# F THE PROPERTIES OF INSULATING MATERIALS

| hermal | | | physical | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| MUM RATURE RANCE °F | THERMAL EXPANSION $10^{-6}$/°C | THERMAL CONDUCTIVITY cal/cm²sec.°C/cm | TENSILE STRENGTH psi | COMPRESSIVE STRENGTH psi | FLEXURAL STRENGTH psi | MODULUS OF ELASTICITY $10^6$ psi | IMPACT STRENGTH CHARPY ft. lbs./in. of notch | WATER ABSORPTION 1/8" thick 24 hrs. - % | SPECIFIC GRAVITY | DIMENSIONAL PRECISION AND STABILITY **** |
| 650 | 11.6 | 0.0012 | 5,000 | 35,000 | 10,000 | 12.5 | 0.5 | nil | 3.2 | A |
| 00 | 11.2 | 0.0012 | 6,000 | 40,000 | 15,000 | 12.0 | 1.3 | nil | 3.0 | A |
| 00 | 10.5 | 0.0010 | 6,000 | 45,000 | 15,000 | 11.0 | 1.0 | nil | 3.0 | A |
| 50 | 11.4 | 0.0013 | 4,000 | 40,000 | 12,000 | 8.5 | 0.5 | nil | 3.8 | A |
| 32 | 11.3 | 0.0015 | 4,000 | 25,000 | 12,000 | 8.0 | 0.4 | nil | 2.7 | A |
| 50 | 10.7 | 0.0011 | 5,000 | 40,000 | 14,000 | 7.5 | 0.7 | nil | 3.8 | A |
| 75 | 10.0 | 0.0010 | 5,000 | 25,000 | 12,000 | 8.0 | 0.4 | nil | 2.6 | A |
| 00 | 8.6-10.5 | 0.0015-0.0020 | 8,000-10,000 | 66,000-90,000 | 16,000-24,000 | 13.0-15.0 | 0.3-0.4 | 0.0-0.05 | 2.7 | C |
| 300 | 19-26 | 0.0010-0.0014 | 5,000-7,000 | 15,000-25,000 | 8,000-12,000 | 3.0-5.0 | 0.30-0.38 | 0.01-0.10 | 1.75-1.92 | B |
| 350 | 35-50 | — | 3,000-5,500 | 18,000-25,000 | 7,500-10,000 | 0.5-2.5 | 0.30-0.35 | 0.15-0.80 | 1.60-2.25 | B |
| 400 | 20-45 | 0.0013-0.0017 | 5,500-7,600 | 30,000 | 9,000-11,000 | 1.6 | 0.28-0.40 | 0.08-0.14 | 1.70-2.00 | C |
| 350 | 30-45 | 0.0004-0.0007 | 6,500-8,500 | 22,700-36,000 | 8,500-12,000 | 0.8-1.2 | 0.24-0.60 | 0.3-1.0 | 1.32-1.45 | C |
| 0 | 100 | 0.0006 | 1,500-3,000 | 1,700 | 2,000 | 0.06 | 3.0 | .005 | 2.1-2.2 | C |
| 0 | 45-70 | 0.0006 | 5,700 | 32,000-80,000 | 8,200 | .20-.30 | 3.6 | nil | 2.1 | B |
| 170 | 60-80 | 0.00024-0.00033 | 5,000-9,000 | 11,500-16,000 | 12,000-16,000 | .40-.50 | 0.25-0.40 | 0.03-0.05 | 1.04-1.065 | B |
| 900 | 0.8-13 | 0.001-0.002 | 5,000-10,000 | 50,000-175,000 | 10,000-16,000 | 7.0-13.0 | 0.1-0.3 | nil | 2.2-4.3 | B |
| 0 | 5.0 | 0.0025 | 3,000-15,000 | 25,000-100,000 | 3,500-15,000 | 7.0-14.0 | 0.2-0.3 | 0.0-2.0 | 2.3-2.5 | C |
| 800 | 100-150 | 0.0005 | 7,000-10,900 | 7,200-13,000 | 8,000-13,800 | 0.28-0.40 | 1.0 | 0.4-1.5 | 1.09-1.14 | B |
| 350 | 15-33 | 0.0010-0.0016 | 10,000-50,000 | 15,000-50,000 | 10,000-80,000 | 0.8-4.5 | 1.5-30 | 0.01-0.50 | 1.35-2.3 | B |
| + | 8 | 0.0004 | 4,000-5,000 | 9,000-15,000 | 9,000-14,000 | — | 3.0-15.0 | 0.10-0.20 | 1.68-2.00 | B |
| + | 5-10 | 0.0007 | 10,000-30,000 | 35,000-46,000 | 10,000-38,000 | 1.5-2.0 | 8.0-15.0 | 0.15-0.65 | 1.6-1.9 | B |
| ) | — | — | 1,400-3,000 | 6,000-15,000 | 3,700-10,000 | — | 0.40 | 0.55-2.0 | 1.9-2.2 | B |
| ) | — | — | 1,500-2,200 | 12,000-18,000 | 2,000-7,500 | — | 0.15-0.40 | 0.5-15.0 | 1.6-2.2 | B |

**** "A" No shrinkage during and after molding, and excellent age and dimensional stability under all exposure conditions.
"B" Appreciable molding shrinkage, but good stability under exposure conditions.
"C" Shrinkage during molding, aging or firing and dimensional change under exposure.

ss-bonded mica, ceramoplastic and synthetic mica products

# ENGINEERING COMPARA CHART

## thermal expansion

### Fahrenheit Temperature Limits For Various Materials

| | |
|---|---|
| **SYNTHAMICA 202** synthetic mica melts | 2550 |
| Electrical porcelain—firing temperature | 2400 |
| Glaze for porcelain—firing temperature | 2250 |
| Raw load pottery glazes—firing temperature | 2000-2050 |
| Copper melts | 1981 |
| Furnace temperatures in glass manufacture | 1900-2800 |
| **SYNTHAMICA 202** synthetic mica—maximum heat resistance* | 1832 |
| Silver melts | 1762 |
| Natural phlogopite mica—maximum heat resistance | 1562 |
| **SUPRAMICA 620** ceramoplastic—maximum heat resistance* | 1550 |
| **SUPRAMICA 620** ceramoplastic—heat distortion (264 psi) | 1360 |
| Aluminum melts | 1220 |
| Silver solders melt | 1165-1450 |
| **SUPRAMICA 560** ceramoplastic—maximum heat resistance* | 832 |
| **SUPRAMICA 500** ceramoplastic—heat distortion (264 psi) | 800 |
| Cold-molded refractory and phospho-asbestos—maximum heat resistance | 900-1300 |
| Calcium aluminum silicate—maximum heat resistance | 900 |
| **SUPRAMICA 560** ceramoplastic—heat distortion (264 psi) | 870 |
| **MYCALEX 400** glass-bonded mica—heat distortion (264 psi) | 860 |
| **MYCALEX 385** glass-bonded mica—heat distortion (264 psi) | 850 |
| Aluminum alloy melting points | 850-1225 |
| Muscovite mica—maximum heat resistance | 800-1000 |
| Zinc melts | 785 |
| **SUPRAMICA 555** ceramoplastic—heat distortion (264 psi) | 700 |
| **SUPRAMICA 500** ceramoplastic—maximum heat resistance* | 700 |
| **MYCALEX 400** glass-bonded mica—maximum heat resistance* | 700 |
| **MYCALEX 385** glass-bonded mica—maximum heat resistance* | 700 |
| **MYCALEX 410** glass-bonded mica—heat distortion (264 psi) | 680 |
| **MYCALEX 410X** glass-bonded mica—heat distortion (264 psi) | 680 |
| **MYCALEX 410** glass-bonded mica—maximum heat resistance* | 650 |
| **SUPRAMICA 555** ceramoplastic—maximum heat resistance* | 650 |
| Magnesium alloy melting points | 650-1200 |
| Lead melts | 621 |
| Cadmium melts | 610 |
| **MYCALEX 410X** glass-bonded mica—maximum heat resistance* | 575 |
| Silicone-glass heat distortion | 575 |
| Cold-molded plastic (organic)—sustained service | 500 |
| Polytetrafluoroethylene—sustained service* | 500 |
| Silicone-glass sustained service | 480 |
| Tin melts | 450 |
| Silicone rubber—sustained service | 425 |
| Polyester-glass heat distortion | 400 |
| Cold-molded plastic (organic) heat distortion | 400 |
| Cellulose-filled melamine heat distortion | 400 |
| Polymonochlorotrifluoroethylene—sustained service* | 390 |
| Polyester, mineral-filled, putty—heat distortion | 374-425 |
| Mercury boils | 357 |
| "Hottest spot"—Class H insulation | 356 |
| Diallyl Phthalate glass-filled | 350-400 |
| Alkyd: polyester, mineral-filled, granular—heat distortion | 350-400 |
| Epoxy-glass cloth—maximum temperature | 315 |
| Silicone elastomer—sustained service | 300-500 |
| Nylon (polyamide) heat distortion (66 psi) | 300-360 |
| Casein heat distortion | 300 |
| Urea-formaldehyde heat distortion | 275 |
| Polytetrafluoroethylene heat distortion (66 psi) | 270 |
| "Hottest spot"—Class B insulation | 266 |
| Melamine-formaldehyde (filled) heat distortion | 266-400 |
| Diallyl Phthalate (alpha cellulose filler) heat distortion | 265-310 |
| Phenol-formaldehyde (mica) heat distortion | 260-350 |
| Phenol-formaldehyde (wood flour) heat distortion | 260-340 |
| Hard rubber (mineral-filled) heat distortion | 260 |
| Sulphur (rhombic) melts | 235 |
| "Hottest spot"—Class A insulation | 221 |
| Paper/Phenolic laminate—sustained service | 212-250 |
| Styrene elastomer—upper limit | 212 |
| Epoxy—maximum recommended use | 212 |
| Water boils | 212 |
| Polyvinyl carbazole heat distortion | 210-300 |
| Vulcanized fiber—upper limit | 200 |
| "Hottest spot"—Class O insulation | 194 |
| Polydichlorostyrene heat distortion | 185-230 |
| Polymonochlorotrifluoroethylene heat distortion (66 psi) | 160 |
| Polystyrene heat distortion | 152-210 |
| Methyl methacrylate heat distortion | 150-210 |
| Styrene copolymer heat distortion | 148-235 |
| Vinyl chloride heat distortion | 140-185 |
| Cellulose nitrate heat distortion | 140-160 |
| Hard rubber (no filler) heat distortion | 140 |
| Vinylidene chloride heat distortion | 130-150 |
| Cellulose acetate butyrate heat distortion | 120-210 |
| Cellulose acetate heat distortion | 115-235 |
| Ethyl cellulose heat distortion | 115-190 |
| Vinyl butyral heat distortion | 115-140 |
| Polyethylene heat distortion (66 psi) | 107 |
| Normal room temperature | 72 |
| Water freezes | 32 |
| Mercury freezes | −38 |
| Silicone elastomer loses flexibility | −80 |
| Dry ice ($CO_2$) sublimes | −109 |
| **MYCALEX** glass-bonded mica undamaged | −110 |
| **SUPRAMICA** ceramoplastic undamaged | −110 |

*unstressed

SYNTHAMICA® SYNTHETIC MICA · SUPRAMICA® CERAMOPLASTIC · SINCE 1919 MYCALEX® THE INSULATOR

**MYCALEX**
CORPORATION OF AMERICA

One of the important and most useful characteristics of SUPRAMICA ceramoplastics and MYCALEX glass-bonded mica is the coefficient of thermal expansion, which is very close to that of Type 446 stainless steel. This property gives assurance of permanent anchorage of inserts molded into SUPRAMICA 555 or 560, or MYCALEX 410, eliminating possibilities of differential expansion gaps that introduce corona noise, corona heating and possible loss of the insulator. No bonding agent is necessary when molding inserts into SUPRAMICA 555 or 560 or MYCALEX 410. Inserts must be cemented when used with the machinable materials SUPRAMICA 620 or 500 or MYCALEX 400.

The absolute dimensional stability of both SUPRAMICA and MYCALEX, plus their thermal expansion properties, make these materials ideal for precision applications where even the slightest variation in dimensions would upset delicately balanced equipment. Bonding to and around metallic parts in avionic constructions for effective control of moisture transmission and uniform stress distribution; the manufacture of precision commutator plates; and molding to .0005″ tolerances in other electronic components are some of the applications for which these materials have proved to be unsurpassed.

### THERMAL EXPANSION COEFFICIENTS OF INSERT METALS AND INSULATING MATERIALS

10-6/deg. C.

| | | |
|---|---|---|
| | 0.8-13.0 | ELECTRICAL GLASS |
| INVAR | 1.1 | |
| | 5.0-7.0 | PORCELAIN |
| TITANIUM | 5.9 | |
| | 5.0-10.0 | SILICONE/GLASS LAMINATES |
| | 8.6-10.5 | STEATITE |
| PLATINUM | 8.8 | |
| ILLIUM R | 9.2 | |
| 410 STEEL | 9.9 | |
| | 10.0 | MYCALEX® 385 GLASS-BONDED MICA |
| | 10.0-30.0 | POLYESTER/GLASS |
| 420 STEEL | 10.3 | |
| 446 STEEL | 10.5 | MYCALEX® 400 GLASS-BONDED MICA |
| | 10.7 | MYCALEX® 410 GLASS-BONDED MICA |
| 430 STEEL | 10.8 | |
| 414 STEEL | 11.0 | |
| | 11.3 | SUPRAMICA® 560 CERAMOPLASTIC |
| | 11.3 | SUPRAMICA® 500 CERAMOPLASTIC |
| 330 STEEL | 11.4 | SUPRAMICA® 555 CERAMOPLASTIC |
| INCONEL | 11.5 | |
| | 11.6 | SUPRAMICA® 620 CERAMOPLASTIC |
| PALLADIUM | 11.7 | |
| 431 STEEL | 11.7 | |
| 1010 STEEL | 12.1 | |
| WROUGHT IRON | 12.1 | |
| 1020 STEEL | 12.1 | |
| NICKEL | 13.0 | |
| ILLIUM G | 13.5 | |
| MONEL | 14.0 | |
| DURIMET | 14.1 | |
| 310 STEEL | 14.4 | |
| 309 STEEL | 14.9 | |
| 316 STEEL | 16.0 | |
| NICKEL SILVER | 16.2 | |
| BERYLLIUM COPPER | 16.5 | |
| 321 STEEL | 16.7 | |
| 5% PHOSPHOR BRONZE | 16.8 | |
| 301 STEEL | 16.9 | |
| 304 STEEL | 17.3 | |
| RED BRASS | 17.6 | |
| COPPER | 17.7 | |
| YELLOW BRASS | 18.9 | |
| SILVER | 19.1 | |
| ALUMINUM ALLOYS | 19.8-24.3 | |
| | 20.0-45.0 | MELAMINE-ASBESTOS FILLED |
| NAVAL BRASS | 20.1 | |
| TIN | 21.1 | |
| | 22.0-27.0 | MICA-FILLED PHENOLIC |
| DOWMETAL C | 25.2 | |
| | 30.0-45.0 | GENERAL PURPOSE PHENOLIC |
| | 35.0 | ALKYD-MINERAL FILLED |
| | 45.0-70.0 | POLYMONOCHLORTRIFLUOROETHYLENE |
| | 60.0-80.0 | POLYSTYRENE |
| | 99.0 | POLYTETRAFLUOROETHYLENE |
| | 100.0-150.0 | NYLON |

**DESIGN SERVICES**

**From its inception, Mycalex Corporation of America has maintained a staff of experts in the production and engineering of electrical and electronic insulating materials. Our experience includes both commercial and military projects, and our present activities encompass both applied research and product development. Mechanical and chemical skills are available, to assist customers in the design and evaluation of components for virtually all insulating purposes. You are cordially invited to make use of these and our other materials services, established for your convenience. Inquiries will be answered promptly and in confidence.**

AFFILIATED COMPANIES

**Synthetic Mica Company**—Division of the Mycalex Corporation of America
**Mycalex Electronics Corporation**—Exclusive licensee of Mycalex Corporation of America
**Mycalex Tube Socket Corporation**—Exclusive licensee of Mycalex Corporation of America

COPYRIGHTED MYCALEX CORPORATION OF AMERICA, 1960 PRINTED IN U. S. A.—49-60

*Tear out this valuable COMPARA CHART—for additional copies write to Mycalex Corporation of America*



"THE SOVEREIGN OF THE SEAS" – from the collection of the Seamen's Bank For Savings in the City of New York

# SETTING SAIL INTO THE SEA OF SYNTHETIC FELTS?

## *. . . Let Troyfelt help you plot your course*

TROY'S only business is in the synthetics—Dacron,® Orlon® and combinations. Moreover, TROY specializes in non-woven felts, having pioneered in the development of the non-woven process.

*What is the advantage of* TROYFELT? Simply this: no binder is used. Eliminating chemical and fiber binders results in *far greater design versatility*. We can give you outstanding abrasion, heat and chemical resistance. Higher insulation. Greater filtering ability. Just the thickness, density, permeability or weight you want. You tell us what properties you're looking for – and in most cases we can match your needs precisely.

See how you may improve your present products . . . solve an operating problem . . . or even come up with an entirely new product. Details . . . just drop us a note. We'll send our most recent technical bulletin and sample of various blends of TROYFELT.

**TROYFELT** *. . . by the pioneers in non-woven synthetic felts*

**INDUSTRIAL PRODUCTS DIVISION • TROY BLANKET MILLS**

200 Madison Avenue • New York 16, New York

For more information, circle No. 525

For more information, turn to Reader Service card, circle No. 481

# SUPPLIERS' LITERATURE

## Finishes and Coatings

**Chromium Chemicals.** Solvay Process Div., Allied Chemical Corp., 80 pp, illus. Properties and principal uses of chromium chemicals. Covchromate, potassium chromate and ered are sodium chromate and bibichromate, ammonium bichromate, and chromic acid. Various graphs and charts present such properties as density, solubility, freezing point, viscosity, and pH of solutions. **149**

**Chromate Conversion Coatings.** Allied Research Products, Inc., 28 pp, illus. Discusses chromate conversion coatings for zinc, cadmium, copper, brass, bronze, aluminum, magnesium and silver. Also covers clear protective coatings for all metals. **150**

**Coatings for Metal.** Amchem Products, Inc., 8 pp, No. 1413D. Method of application, purpose of coating and typical applications of a line of chemical conversion coatings for aluminum, copper and copper alloys, iron and steel, zirconium, and other metals. **151**

**Coloring Plastics.** Bee Chemical Co., Logo Div., 16 pp. Information on the advantages of painting thermoplastic parts as opposed to molding-in color. **152**

**Ultrasonic Cleaning System.** Branson Ultrasonic Corp., 6 pp, illus., No. S-610. General information on ultrasonic cleaning; and advantages, characteristics, and specifications of equipment used in an ultrasonic cleaning system. **153**

**Flocked Paper.** Cellusuede Products, Inc., illus. Sample kit containing actual swatches of colored flocked paper. Suggestions for cutting, folding and printing the flocked paper. **154**

**Colored Conversion Coatings.** Chemical Corp., 4 pp. Tells how to produce colored chromate conversion coatings on zinc-plated parts. **155**

**Chromium Diffusion Coatings.** Chromalloy Corp. Advantages, characteristics, properties, typical applications, and other data on a line of chromium diffusion coatings and processes. **156**

**Metallic Coatings for Plastics.** Coating Products, Inc. Information on metallic coatings for plastics. **157**

**TFE-Fluorocarbon Finishes.** E. I. du Pont de Nemours & Co., 12 pp, No. A15272. Description of products, surface preparation, methods of application, fusing operations, curing time, precautions and handling, and other information on a line of TFE-fluorocarbon resin finishes. **158**

**Butyrate Lacquer.** Eastman Chemical Products, Inc., 4 pp, illus., No. 15-M. General information, advantages, characteristics, methods of application, types of pretreatment and typical applications of a clear butyrate lacquer. **159**

**Metal Finishing.** Enthone, Inc., 4 pp. Lists the company's metal finishing processes and electroplating chemicals. Includes a card offering technical data on 77 metal finishing subjects. **160**

**Nickel Alloy Coatings.** Kanigen Div., General American Transportation Corp., 12 pp, illus., No. 258. Frictional properties, abrasion, corrosion and salt spray resistance, uses, ductility and thermal conductivity of Kanigen chemically deposited nickel alloy coatings. **161**

**Plating Services.** Harshaw Chemical Co., 16 pp, illus., No. D-6995. Advantages, characteristics, typical applications, and other data on a line of plating processes, plating chemicals, and plating anodes. **162**

**Coatings for Mirrors.** Libby-Owens-Ford Glass Co., Liberty Mirror Div., 32 pp. Reflectivity, adherence, hardness, durability, water resistance, effect of temperature and other information on a line of coatings for mirrors. **163**

**Multicolor Enamel.** Maas & Waldstein Co., 2 pp, No. 520. Data sheet for industrial multicolor enamels. **164**

**Sprayed Vinyl Finishes.** Metal & Thermit Corp., 4 pp, illus., No. ZF-1. Characteristics, advantages, basic types, methods of application, properties, and uses of sprayed-on textured vinyl finishes. **165**

**Flame Spray Process.** Metallizing Engineering Co., Inc., 16 pp, illus., No. 136B. General information on flame spraying processes, their advantages and uses. Also included is specific information on hardness, tensile strength, bond strength, etc. of various coatings used. **166**

**Silicone Coating.** Midland Industrial Finishes Co., 4 pp, illus. Properties, application data, corrosion resistance and uses of a silicone coating. **167**

**Coatings and Processes.** Neilson Chemical Co., 6 pp, illus., No. 59-170. General information on iron and zinc phosphate coating chemicals and processes for steel and aluminum surfaces; conversion and oxide coatings for aluminum surfaces; rust removers; metal conditioners; metal etchants; alkaline and acidic metal cleaners; spray booth compounds; steam cleaners; and hot or cold paint strippers. **168**

**Refractory Coatings.** Norton Co., Refractories Div., 10 pp, illus., No. CP14.1. Properties, uses and application data for aluminum oxide, zirconia and zirconium silicate refractory coatings. **169**

**Metal Cleaning.** Oakite Products, Inc. Series of technical bulletins give information on metal cleaning and preparation of metals for painting. Covered are: chemistry and techniques of metal cleaning, conversion coatings, rust prevention, paint stripping, ultrasonic cleaning, barrel finishing and many others. **170**

**Conversion Coatings.** Parker Rust Proof Co., 8 pp, illus., No. A-7650. Advantages, characteristics, typical applications, and other information on conversion coatings for aluminum. **171**

**Fusion Bond Finishes.** Polymer Corp., Whirlclad Div., 4 pp, illus. Characteristics, properties and uses of cellulosic, nylon, polyethylene and chlorinated polyether finishes for metal parts. **172**

**Porcelain Enamel.** Porcelain Enamel Institute, 1145 19th St. N. W., Washington 6, D. C. File folder covers general information about porcelain enamel; gives characteristics, properties and corrosion resistance of porcelain enamel. Write on company letterhead directly to Porcelain Enamel Institute.

**Gold Electroplate Thickness.** Sel-Rex Corp., 5 pp, illus. Latest techniques for controlling and measuring thickness and hardness of precious metal electroplates, with particular emphasis on gold. **173**

**Paint Finishing.** Sherwin-Williams Co., General Industrial Div., 12 pp, No. CFP-513. Causes and remedies of common finishing problems. Tells how to estimate paint requirements for coating product surfaces. **174**

**Selective Plating.** Sifco Metachemical Inc., 4 pp, illus. Process of electroplating selected areas without using immersion tanks. For quick precision plating of electronic parts and build-up of parts to exact size without disassembly. **175**

**Dip Coating Process.** Steere Enterprises, Inc., 4 pp, illus. Advantages, uses and characteristics of a low cost dipping process which produces plastics products, plastic-coated metal parts and protective covers for precision machined parts. **176**

**Plastisols, Organisols.** Reynolds Chemical Products Co., Div. of Stubnitz-Green Corp., 8 pp, illus. Information on plastisols and organisols used as coatings for paper, steel, bottles, gloves, rope, wire and plating racks. **177**

**Gold Plating.** Technic, Inc, 6 pp, illus. Complete technical data, properties, uses and costs of a gold electroplating material. **178**

**Plasma Arc Coating.** Linde Co., Div. of Union Carbide Corp., 8 pp, illus. Describes a plasma arc plating process for applying coatings and fabricating shapes. Tells what materials can be applied and where they can be used. **179**

*To get literature, use free post cards on pp 585-592*

PROPERTIES OF MATERIALS

# Finishes and Coatings


PAGE

330 Electrodeposited Coatings
333 Sprayed Metal Coatings
334 Hot Dip Coatings
335 Immersion Coatings
336 Diffusion Coatings
337 Vapor Deposited Coatings
338 Organic Coatings
341 Hard Facings
342 Ceramic, Cermet and Refractory Coatings
343 Mechanical Finishes for Aluminum, Copper and Stainless Steel
344 Porcelain Enamels
346 Chemical Conversion Coatings
347 Preplated and Precoated Metals
348 Advertisements
328 Suppliers' Literature

## Electrodeposited Coatings

| Type → | Aluminum | Antimony | Arsenic | Bismuth | Cadmium | Chromium |
|---|---|---|---|---|---|---|
| BASE METALS | Magnesium, steel, copper, zinc, nickel, silver, gold | (experimental) | Brass | (experimental) | Steel, copper and its alloys, cast and malleable iron | Ferrous and nonferrous metals |
| PHYSICAL PROPERTIES | | | | | | |
| Ther Cond, Btu/hr/sq ft/°F/ft | 122 | 10.2 | — | 4.6 | 5.3 | — |
| Elec Res, microhm-cm | 2.8 | 41.7 | 35 | 119 | 7.5 | 14–66 |
| Color (natural) | White | White (bright) | Gray or black | White or gray | White (bright) | White (bright) or black |
| Reflectance When Polished (5000 A), % | — | 50 | — | — | — | — |
| Melting Point, F | 1220 | 1166 | 1139 | 520 | 610 | 2939 |
| Min Thickness, mil | 0.1 | — | — | — | 0.15 | 0.01 |
| MECHANICAL PROPERTIES | | | | | | |
| Brinell Hardness | — | — | — | — | 35–50 | 700–1000 |
| Abrasion Resistance[a] | Poor | — | — | — | Fair | Excellent |
| CORROSION RESISTANCE, $10^{-6}$ ipy | | | | | | |
| Atmosphere | — | — | — | — | 250–510 | — |
| Sea Water | 20–3400 | — | — | — | 700 | — |
| SOLDERABILITY | | | | | | |
| As Plated | — | — | — | — | Good | Poor |
| After 192-Hr Salt Spray | — | — | — | — | Poor | Poor |
| COST | Moderate | — | — | — | Moderate | Moderate |
| USES[b] | c, e | c, d | D | c | C, d, w | c, D, e, R, W |

| Type → | Cobalt | Copper | Gold | Indium | Iron | Lead |
|---|---|---|---|---|---|---|
| BASE METALS | Iron, steel, copper and its alloys | Most ferrous and nonferrous metals | Copper, brass, nickel, silver | Silver-plated steel | Ferrous metals | Most ferrous and nonferrous metals |
| PHYSICAL PROPERTIES | | | | | | |
| Ther Cond, Btu/hr/sq ft/°F/ft | — | 222 | 169 | — | 38.7 | 20.1 |
| Elec Res, microhm-cm | 6.2 | 3–8 | 2.4 | 8.4 | 10 | 22.6 |
| Color (natural) | Gray | Pink or red (bright) | Yellow (bright) | White | Gray | Gray |
| Reflectance When Polished (5000 A), % | — | 44 | 47 | — | 0.55 | — |
| Melting Point, F | 2723 | 1981 | 1944 | 311 | 2795 | 621 |
| Min Thickness, mil | — | 0.1 | 0.002 | 0.1 | — | 0.25 |
| MECHANICAL PROPERTIES | | | | | | |
| Brinell Hardness | — | 60–150 | 5 | — | 150–300 | 5 |
| Abrasion Resistance[a] | — | Fair | Poor | Poor | Good | Poor |
| CORROSION RESISTANCE, $10^{-6}$ ipy | | | | | | |
| Atmosphere | — | 54–464 | — | — | — | 9–27 |
| Sea Water | — | 2000 | — | — | — | 400–600 |
| SOLDERABILITY | | | | | | |
| As Plated | — | Good | Good | Good | Fair | — |
| After 192-Hr Salt Spray | — | — | Good | — | Poor | — |
| COST | — | Low | High | — | Low | Low |
| USES[b] | c, e, r | c, d, E | c, D, e | c, d, W | e, R, w | C, e, w |

Notes: See opposite page.

## Electrodeposited Coatings

| Type → | Magnesium | Manganese | Molybdenum | Nickel | Palladium | Platinum |
|---|---|---|---|---|---|---|
| BASE METALS | (experimental) | Iron, aluminum, copper and its alloys | Zinc, cadmium | Most ferrous and nonferrous metals | Copper and its alloys | Lead, tin, zinc, white gold |
| PHYSICAL PROPERTIES | | | | | | |
| Ther Cond, Btu/hr/sq ft/°F/ft | 91 | — | 83.8 | 34.4 | 40.6 | 40.2 |
| Elec Res, microhm-cm | 4.6 | 5 | 5.7 | 7.4–10.8 | 11 | 10 |
| Color (natural) | White | Gray | Gray | Gray, white (bright) | Bright | Gray (bright) |
| Reflectance When Polished (5000 A), % | 0.72 | — | 46 | 61 | — | 58 |
| Melting Point, F | 1204 | 2300 | 4748 | 2651 | 2820 | 3223 |
| Min Thickness, mil | — | — | — | 0.1 | 0.02 | Flash |
| MECHANICAL PROPERTIES | | | | | | |
| Brinell Hardness | — | — | — | 150–500 | — | — |
| Abrasion Resistance[a] | — | — | Excellent | Excellent | — | — |
| CORROSION RESISTANCE, $10^{-6}$ ipy | | | | | | |
| Atmosphere | — | — | — | 1–160 | — | — |
| Sea Water | 10,000–80,000 | — | — | 300–1000 | — | — |
| SOLDERABILITY | | | | | | |
| As Plated | — | — | — | Good | — | — |
| After 192-Hr Salt Spray | — | — | — | Poor | — | — |
| COST | — | — | — | Moderate | High | High |
| USES[b] | Experimental | Experimental | Experimental | C, D, E, R, W | c, D | c, D |

| Type → | Rhenium | Rhodium | Selenium | Silver | Tin | Titanium |
|---|---|---|---|---|---|---|
| BASE METALS | (experimental) | Most ferrous and nonferrous metals | (experimental) | Most ferrous and nonferrous metals | Most ferrous and nonferrous metals | Steel, nickel, copper |
| PHYSICAL PROPERTIES | | | | | | |
| Ther Cond, Btu/hr/sq ft/°F/ft | — | 50.9 | — | 244 | 36.3 | — |
| Elec Res, microhm-cm | 21 | 4.7 | 12 | 1.6 | 11.5 | 3.2 |
| Color (natural) | Gray (bright) | White (bright) | Gray | White (bright) | White | — |
| Reflectance When Polished (5000 A), % | — | 76 | — | 91 | — | — |
| Melting Point, F | 5732 | 3553 | 423 | 1760 | 448 | 3272 |
| Min Thickness, mil | — | 0.001 | — | 0.1 | 0.015 | — |
| MECHANICAL PROPERTIES | | | | | | |
| Brinell Hardness | 250 | 400–800 | — | 50–150 | 5 | — |
| Abrasion Resistance[a] | Good | Excellent | — | Poor | Poor | — |
| CORROSION RESISTANCE, $10^{-6}$ ipy | | | | | | |
| Atmosphere | — | — | — | — | 72–320 | — |
| Sea Water | — | — | — | 40 | 30–90 | — |
| SOLDERABILITY | | | | | | |
| As Plated | — | — | — | — | Good | — |
| After 192-Hr Salt Spray | — | — | — | — | Poor | — |
| COST | — | Moderate | — | High | Moderate | — |
| USES[b] | d | c, D | Rectifiers | C, D, e, w | Experimental | Experimental |

[a] Even though some electroplates abrade easily they may still have excellent appearance (e.g., gold and silver), or may even provide an excellent bearing surface (e.g., indium, silver and lead).

[b] Capital letter indicates frequent use, small letter infrequent. C = corrosion protection; D = decoration; E = electroforming; R = reclaiming; W = wear resistance.

*continued on next page*

## Electrodeposited Coatings

| Type → | Tungsten | Zinc | Zirconium | Cobalt-Nickel | Copper-Tin (bronze) | Copper-Zinc (brass) |
|---|---|---|---|---|---|---|
| BASE METALS | (experimental) | Ferrous metals | (experimental) | (experimental) | Steel, copper, brass, zinc | Iron, steel, aluminum, zinc |
| PHYSICAL PROPERTIES | | | | | | |
| Ther Cond, Btu/hr/sq ft/°F/ft | 84.7 | 64.2 | — | — | — | — |
| Elec Res, microhm-cm | 5.5 | 5.8 | 41 | — | — | — |
| Color (natural) | Gray | White (bright) | — | Gray | Pink (bright) | Yellow (bright) |
| Reflectance When Polished (5000 A), % | 0.49 | 55 | — | — | — | — |
| Melting Point, F | 6098 | 786 | 3452 | — | — | — |
| Min Thickness, mil | — | 0.15 | — | — | 0.5 | 0.1 |
| MECHANICAL PROPERTIES | | | | | | |
| Brinell Hardness | — | 40–50 | — | — | — | — |
| Abrasion Resistance[a] | — | Fair | — | Good | Good | Fair |
| CORROSION RESISTANCE, $10^{-4}$ ipy | | | | | | |
| Atmosphere | — | 8–210 | — | — | — | — |
| Sea Water | — | 1000–6000 | — | — | — | — |
| SOLDERABILITY | | | | | | |
| As Plated | Good | — | — | — | — | — |
| After 192-Hr Salt Spray | Poor | — | — | — | — | — |
| COST | — | Low | — | — | Moderate | Moderate |
| USES[b] | Experimental | C, d | Experimental | Magnetic | c, D, w | c, D |

| Type → | Lead-Tin | Nickel-Tin | Phosphorus-Nickel-Cobalt | Tin-Zinc | Tungsten-Nickel-Cobalt-Iron |
|---|---|---|---|---|---|
| BASE METALS | Steel, copper, brass | Most ferrous and nonferrous metals | — | Most ferrous and nonferrous metals | — |
| PHYSICAL PROPERTIES | | | | | |
| Ther Cond, Btu/hr/sq ft/°F/ft | — | — | — | — | — |
| Elec Res, microhm-cm | — | — | 110–118 | — | — |
| Color (natural) | White | White (bright) | Bluish (bright) | White | Gray |
| Reflectance When Polished (5000 A), % | — | 15–118 | — | — | — |
| Melting Point, F | — | — | — | — | — |
| Min Thickness, mil | 0.2 | 0.5 | — | 0.15 | — |
| MECHANICAL PROPERTIES | | | | | |
| Brinell Hardness | — | 625 (Vickers) | — | — | — |
| Abrasion Resistance[a] | Poor | Good | — | Good | — |
| CORROSION RESISTANCE, $10^{-4}$ ipy | | | | | |
| Atmosphere | — | — | — | — | — |
| Sea Water | — | — | — | — | — |
| SOLDERABILITY | | | | | |
| As Plated | Good | — | — | Good | — |
| After 192-Hr Salt Spray | — | — | — | Poor | — |
| COST | Moderate | Moderate | — | Moderate | — |
| USES[b] | c, w | C, D | C, d, e, w | C | C, e, r, w |

[a] Even though some electroplates abrade easily they may still have excellent appearance (e.g., gold and silver), or may even provide an excellent bearing surface (e.g., indium, silver and lead).

[b] Capital letter indicates frequent use, smaller letter infrequent. C = corrosion protection; D = decoration; E = electroforming; R = reclaiming; W = wear resistance.

## Sprayed Metal Coatings

| Type → | Aluminum | Babbitt A[a] | Brass (65:35) | Bronze AA[b] | Commercial Bronze | Manganese Bronze | Phospher Bronze |
|---|---|---|---|---|---|---|---|
| Specific Gravity | 2.41 | 6.67 | 7.45 | 7.06 | 7.57 | 7.26 | 7.68 |
| Ult Ten Str, 1000 psi | 19.5 | — | 12 | 29 | 11.5 | 12 | 18 |
| Strain at Ult Str, % | 0.23 | — | 0.45 | 0.46 | 0.42 | 0.46 | 0.35 |
| Rockwell Hardness | H72 | H58 | B22 | B78 | B18 | B27 | B20 |
| Shrinkage, in./in. | 0.0068 | — | 0.009 | 0.0055 | 0.011 | 0.009 | 0.010 |
| Spraying Speed, lb/hr | 18 | 95 | 32 | 24 | 24 | 36 | 31 |
| Spraying Efficiency, %[c] | 89 | 69 | 81 | 77 | 82 | 79 | 85 |
| Major Characteristics and Uses[d] | Good corrosion and heat resistance | Good bearing properties | Sprays fast. Fair machine finish | Hard, very wear resistant. Easily machined | Softest bronze. Fair machine finish | Excellent machine finish. Special uses only | Fair machine finish. Special uses only |

[a]Lead-free, high tin alloy. [b]Aluminum-iron-bronze. [c]Percent of metal deposited.
[d]All metals have about the same shiny surface after spraying, but surfaces of the various metals differ after machining.

| Type → | Tobin Bronze | Copper | Lead | Molybdenum | Monel | Nickel | 18-8 Stainless |
|---|---|---|---|---|---|---|---|
| Specific Gravity | 7.46 | 7.54 | 10.21 | 8.86 | 7.67 | 7.55 | 6.93 |
| Ult Ten Str, psi | 13 | — | — | 7.5 | 21 | 17.5 | 30 |
| Strain at Ult Str, % | 0.51 | — | — | 0.30 | 0.26 | 0.30 | 0.27 |
| Rockwell Hardness | B27 | B32 | — | C38 | B39 | B49 | B78 |
| Shrinkage, in./in. | 0.0104 | — | — | 0.003 | 0.009 | 0.008 | 0.012 |
| Spraying Speed, lb/hr | 36 | 29 | 80 | 8 | 17 | 18 | 21 |
| Spraying Efficiency, %[c] | 80 | 80 | 65 | 87 | 85 | 79 | 81 |
| Major Characteristics and Uses[d] | General purpose. Fair machine finish | Electrical uses; brazing | Good corrosion resistance. X-ray shielding | Used as bonding coat. Excellent bearing properties | Good corrosion resistance. Good machine finish | Good corrosion resistance. Fair machine finish | High corrosion resistance. Good wearing properties |

| Type → | High Cr Stainless | Steel (LS)[e] | Steel (0.10% C) | Steel (0.25% C) | Steel (0.80% C) | Tin | Zinc |
|---|---|---|---|---|---|---|---|
| Specific Gravity | 6.74 | 6.78 | 6.67 | 6.78 | 6.36 | 6.43 | 6.36 |
| Ult Ten Str, psi | 40 | 33.5 | 30 | 34.7 | 27.5 | — | 13 |
| Strain at Ult Str, % | 0.50 | 0.54 | 0.30 | 0.46 | 0.42 | — | 1.43 |
| Rockwell Hardness | C29 | C25 | B89 | B90 | C36 | — | H46 |
| Shrinkage, in./in. | 0.0018 | 0.002 | 0.008 | 0.006 | 0.0014 | — | 0.010 |
| Spraying Speed, lb/hr | 19 | 18 | 19 | 19 | 19 | 95 | 61 |
| Spraying Efficiency, %[c] | 81 | 87 | 87 | 87 | 87 | 73 | 66 |
| Major Characteristics and Uses[d] | High hardness and wear resistance. Grind finish | Good mechanical and finishing properties | Simple bearing surfaces and press fits. Excellent machine finish | Harder and lower shrinkage than 0.10C. Excellent machine finish | Very hard and wear resistant. Good bearing properties. Grind finish | Good corrosion resistance, especially with foods | Good all-around corrosion resistance |

[e]Low shrinkage.

## Hot Dip Coatings*

| Type → | **Aluminum** (aluminized) | **Zinc** (galvanized) | **Lead** | **Tin** | **Lead-Tin** (terne) |
|---|---|---|---|---|---|
| Base Metals | Steel | Steel | Steel and copper | Steel or copper | Steel |
| Thickness | Most commonly applied in thicknesses of 1 to 2 mils | For structural steel shapes, plates and bars, weight of coating should be 2 oz per sq ft | 8–40 lb per double base box | Sheet: 1.25–4.0 lb per double base box. Wire, strip: 0.005 mil. Fabricated parts: 0.3–0.5 mil | 8–40 lb per double base box |
| Important Properties | Combines corrosion res and heat reflectivity of aluminum with mechanical and physical properties of steel; withstands up to 900 F without discoloring and up to 1250 F without descaling; in some cases can be used up to 1650 F | Combines high corrosion res with low cost; has slower corrosion rate than iron; corrosion products are white and nonstaining; provides electrolytic protection to iron | Major advantage is high res to atmospheric corrosion and chemicals, especially sulfuric and hydrochloric acids, and brine; superficial protective oxide film regenerates itself when damaged; can withstand severe deformation | Very good res to tarnishing and staining indoors, pure rural atmospheres, and food; sheet can be severely deformed without damage (lends itself to stamping, drawing, rolling, lock-seaming and bending); sheet is readily soldered | Provides some of the advantages of tin coatings at lower cost; ductility and good adhesion allow deep drawing; excellent paint-holding properties |
| Limitations | Above 900 F, coating begins to alloy with base metal to form refractory layer which will not return to original state | Life of coatings is about five to ten times greater in rural than in industrial atmospheres containing sulfur and acid gases | Poor res to wear and abrasion; poor adhesion; pinholes may form during application; performs better in industrial than rural atmospheres | Presence of many minute pores causes accelerated corrosion, especially in wet environments; res to marine and industrial atmospheres not very good | Provides only mechanical protection against corrosion |
| Remarks | Corrosion res is often superior to that of galvanized steel, but aluminum coating is more expensive | Greater protection can be obtained by increasing thickness | Adhesion can be improved by adding small quantities of alloying ingredients; pinholes can be eliminated by slight working or burnishing | Corrosion res markedly improved by increasing thickness and controlling porosity | Corrosion res can be improved greatly by using organic coatings |
| Uses | High temp applications such as fire walls, water heater and oven liners, mufflers, heat exchanger tubes, space heater parts, combustion chambers | Roofing and siding, nails, wire, tanks, boilers, pails, and wide range of hardware for indoor and outdoor use | Wire, pole-line hardware, bolts, washers, tanks, barrels, cans, air ducts. Good adhesion of organic coatings has proved valuable for such outdoor uses as gutters, flashing and corrugated siding | Hot dipped tin coatings on food cans have largely been superseded by tin electroplates; however, the heavier coatings produced by hot dipping are useful for some fabricated parts and castings | If used in sufficient thickness, coatings provide good protection for such things as gasoline tanks and roofing, and benches and cabinets used in chemical laboratories |

* For all types except terne, two layers are formed on the base metal: the outer layer is generally relatively pure coating metal, the intermediate layer is an alloy of the coating metal and the base metal. Terne coatings generally contain 10–25% tin and 75–90% lead.

## Immersion Coatings

| Type ➡ | Electroless Nickel | Tin | Copper | Gold | Silver |
|---|---|---|---|---|---|
| Base Metals | Most ferrous and nonferrous metals | Copper, brass, bronze, aluminum, steel | Steel, brass, aluminum and printed circuit boards | Most ferrous and nonferrous metals | Most metals except lead, zinc, aluminum and other very active metals; copper, nickel and steel best |
| Thickness | From 1 to 5 mils, depending on end use | Decorative: 0.015 mil; heavy duty: up to 2 mils | From 0.1 to 1 mil | Usually about 0.001 mil | Usually about 0.001 mil, but sometimes as high as 0.03 mil |
| Important Properties | Because of their amorphous structure and phosphorus content (8–10%), these coatings have better abrasion resistance than electrolytic or wrought nickel; hardness is relatively high (about $R_c$ 50, which can be heat treated to $R_c$ 64) | Combines bright appearance, good frictional properties and ease of application with low cost | High electrical conductivity, good lubrication properties | Good electrical conductivity and emissivity; bright, attractive appearance | Bright, attractive appearance |
| Limitations | Generally more expensive than electroplated nickel | Corrosion resistance is only fair; plating usually stops when base metal is covered | Not especially noted for decorative appeal | Poor resistance to discoloration and abrasion | Poor resistance to tarnishing and abrasion |
| Remarks | Although coating is used primarily for functional properties, a smooth, bright deposit can be obtained with buffed metals | Heavier coatings can be produced by placing base metal in contact with a dissimilar metal, thereby generating an electric current and promoting additional plating | Unusual appearance can be used to advantage for such things as inexpensive hardware and casket parts | Relatively inexpensive due to extreme thinness; discoloration and abrasion resistance can be improved with a clear lacquer finish | Relatively inexpensive due to extreme thinness; can be protected somewhat against tarnishing with a clear lacquer finish |
| Uses | Protecting parts from corrosion and preventing product contamination. Tank car interiors, oil refinery air compressors, missile fuel injector plates, pumps, reciprocating surfaces; aluminum electronic devices (to facilitate soldering); stainless steel (to facilitate brazing) | Decorative finishing of small parts such as safety pins, thimbles and buckles; also used on copper tubing to prevent discoloration from water and on aluminum engine pins to provide lubrication during break-in periods | Because of their conductivity, these coatings have proved particularly useful for printed circuits. Because of their good lubrication properties, they are also used on steel wire in die forming operations | Principally used on costume jewelry, trophies, auto trim and many inexpensive novelties. Their conductivity and solderability have proved useful in electrical applications such as printed circuits, transistors and connectors. Emissivity properties valuable in some missile applications | Cheap decorative products, minor electronic parts and maintenance plating |

## Diffusion Coatings*

| Type → | Calorized | Carburized | Chromized | Cyanided, Carbonitrided |
|---|---|---|---|---|
| Base Metals | Carbon, low alloy steels | Carbon and alloy steels low enough in carbon content (<0.45%) to take up that element readily | Low and high carbon steels, many alloy steels, stainless steels, tool steels, cast iron, iron powder parts | Same steels as used for carburizing |
| How Applied | Aluminum introduced into surface by treating metal in powdered aluminum compound or aluminum chloride vapor, or by spraying and subsequently heat treating; alloy coating (5–40 mils) contains about 25% aluminum | Carbon introduced into surface by heating solid, liquid or gaseous carbon in contact with base metal at temperatures above the transformation range, generally 1450–1750 F | Chromium introduced into surface by heating metal in contact with a chromium-containing powdered compound at 1500–1900 F. High chromium-iron alloy is formed on low-carbon ferrous metals (3 mils); chromium carbide case is formed on high carbon metals (½–2 mils) | Carbon and nitrogen introduced into surface by heating metal in a liquid cyanide bath (cyaniding) or in a carbonaceous and nitrogeneous (carbonitriding) bath, the temperature ranging from 1200–1600 F |
| Important Properties | Resistance to high temperature oxidation (long time service at temperatures up to 1400 F); protects by sealing metal from surrounding air | High strength and toughness in core can be combined with extreme surface hardness; plain carbon steels are used if core properties are not too critical; alloy steels are used if strength and toughness are needed in core | High resistance to wear, abrasion and corrosion; high hardness (1600–1800 VPN) | Hard and wear resistant surface; warping is less serious than in carburizing; quenching is usually necessary for full hardness |
| Uses | Chemical and metal process pots, bolts, air heater tubes, and parts for furnaces and steam superheaters | Gears, cams, pawls, racks and shafts | Aircraft, railroad and automotive parts, combustion equipment, mechanical equipment, tools, heating apparatus | In general, same as carburized |

| Type → | Nickel-Phosphorus | Nitrided | Sherardized | Siliconized |
|---|---|---|---|---|
| Base Metals | Ferrous metals | Primarily special nitriding steels. Also medium carbon steels containing chromium and molybdenum, stainless steels, some cast irons | Ferrous and nonferrous metals | Low carbon (<0.25%), low sulfur (<0.04%) steels |
| How Applied | Nickel-phosphorus introduced into surface by painting metal with mixture of nickel oxide, dibasic ammonium phosphate and water, and then heating | Nitrogen introduced into surface by heating metal in contact with ammonia or other nitrogeneous material, the temperature ranging from 930–1050 F | Zinc introduced into surface by heating base metal in a zinc powder for 3–12 hr at 650–750 F | Silicon introduced into surface by heating metal in contact with silicon carbide and chlorine at 1700–1850 F |
| Important Properties | Corrosion resistance approaches that of stainless steel and high nickel alloys; must be heat treated in controlled atmosphere; little porosity; poor resistance to heat and abrasion | High wear resistance, retention of hardness at elevated temperatures; good resistance to certain types of corrosion; produces minimum distortion | Improves corrosion resistance; coatings are not as protective as plated or hot dipped zinc coatings, but are more uniform | High resistance to wear, heat and corrosion; improves hardness; surfaces are nongalling; case (5–10 mils) is brittle |
| Uses | Pipe and fittings | In general, same as carburized | Small steel parts such as nuts, bolts, and washers, or castings that must resist atmospheric corrosion | Pump shafts; cylinder liners; valves, valve guides and fittings; conveyor chain links |

* Surface alloying treatments for metals.

## Vapor Deposited Coatings

| Type → | Vacuum Metallized | Cathode Sputtered | Vapor Plated |
|---|---|---|---|
| Coating Metals | Primarily aluminum; also cadmium and selenium | Primarily gold and silver; also platinum and palladium; in general, any low-vapor-pressure metal | Primarily nickel; also iron, chromium, cobalt, molybdenum and some precious metals |
| Base Materials | Primarily zinc, steel, plastics; also aluminum, glass, paper | Most metals and nonmetallics | Most metals and nonmetallics |
| How Applied | Evaporation—Metal is brought in contact with hot filament (tungsten, molybdenum or platinum) in a vacuum of at least $10^{-4}$ mm of Hg; the metal evaporates (in 5–15 sec) and condenses on all cool surfaces that lie in straight path from filament | Ion bombardment—A high voltage (10,000 v or more) is applied across two electrodes; ion bombardment vaporizes the cathodic metal and deposits it as a crystalline, fine-grained coating on material placed near anode | Thermal decomposition ("gas plating")—Metal to be deposited must exist in the form of a gaseous compound that decomposes at a temperature higher than its vaporization temperature; part to be plated is heated above this decomposition temperature of the compound and inserted in the plating chamber |
| Important Properties | Deposition rates are slow; process is expensive compared to electroplating unless restricted to large runs of small or medium-sized parts and to thin coatings. For thin films (0.003 to 0.005 mil), vacuum metallizing is best method—it is low cost and produces finely controlled and uniform deposits which closely follow contours of base surface. Abrasion resistance is generally low. Corrosion resistance very good for cadmium coated parts | Lower vacuum is required than in vacuum metallizing (only 0.01–0.1 mm Hg) and hence less expensive equipment, but deposition rates are slower, and some metals, including aluminum, cannot be deposited. Thin films are generally highly porous, but deposits of 0.04 mil are satisfactory. Temperature rise produced in substrate is often higher than in vacuum metallizing. It is difficult to avoid oxide contamination | Method is adaptable to odd-shaped objects, deposits coatings with greater speed than any conventional plating process, makes possible the deposition of alloys, and is applicable to porous surfaces such as powder metal parts. Gaseous compounds are expensive and, in some cases, toxic |
| Uses | Aluminum-coated zinc or steel—hardware, costume jewelry, optical reflectors, instrument parts, automotive trim and interior hardware; selenium-coated nickel-plated aluminum—selenium rectifiers; aluminum-coated plastics—automotive interior hardware, panels, dials and trim; aluminum-coated glass—electroluminescent panels | Phonograph recording masters, surgical gauze, broadcasting transmitters, and jewelry | Thick coatings of refractory metals on wires; nickel-coated gasoline fuel delivery nozzles; and the previously impossible metallic coating of nylon and glass fibers |

## Organic Coatings [a]

| Type → | Alkyd | | | | | | Acrylic | Bituminous |
|---|---|---|---|---|---|---|---|---|
| | Alkyd | Alkyd-Amine | Alkyd-Phenolic | Alkyd-Silicone | Alkyd-Urea | Styrenated Alkyd | | |
| **CHEMICAL RESISTANCE** | | | | | | | | |
| Exterior Durability | E | E | E | E | E | G | E | E |
| Salt Spray | E | VG | E | E | G | G | E | E |
| Solvents—Alcohols | F | G | G | F | G | G | G | P |
| Solvents—Gasoline | G | E | E | E | E | E | G | P |
| Solvents—Hydrocarbons | G | E | E | P | E | E | F | P |
| Solvents—Esters, Ketones | P | P | F | P | P | P | P | P |
| Solvents—Chlorinated | P | P | F | P | P | P | P | P |
| Beverages, Food | F | G | VG | P | G | VG | VG | E |
| Salts | VG | E | E | F | E | E | VG | G |
| Ammonia | P | P | P | P | P | P | P | — |
| Alkalis [b] | G, G | VG, G | F, P | P, P | G, G | G, VG | G, F | E |
| Acids—Mineral [c] | F, P, P | G, F, P | VG, G, F | G, P, P | F, P, P | G, F, P | G, F, P | G, — , — [j] |
| Acids—Oxidizing [c] | P, P, P | F, P, P | G, F, P | P, P, P | F, P, P | F, P, P | F, P, P | — |
| Acids—Organic (acetic, formic, etc.) [c] | P, P, P | P, P, P | F, P, P | P, P, P | P, P, P | P, P, P | P, P, P | E, —, — [k] |
| Acids—Organic (oleic, stearic, etc.) | F | G | VG | G | F | F | F | E |
| Acid—Phosphoric | P | P | P | P | P | P | P | E |
| Water (salt, fresh) | F | G | E | E | F | G | E | E |
| **PHYSICAL PROPERTIES** | | | | | | | | |
| Sward Rocker Hard. (8th day) | 24 | 30 | 34 | 16 | 28 | 28 | 24 | — |
| Flexibility | E | VG | G | F | VG | G | E | E |
| Abrasion Res, cycles [d] | 3500 | >5000 | >5000 | 1000 | >5000 | >5000 | 2500 | — |
| Max Svc Temp, F | 200 | 250 | 250 | 1000 | 225 | 200 | 180 | 325 |
| Toxicity | None | Slight | None | Slight | Slight | Slight | None | — |
| Impact Res | VG | E | G | G | E | G | E | E |
| Dielec Properties | G | G | VG | E | G | G | VG | — |
| Adhesion to— | | | | | | | | |
| Ferrous Metals | E | E | E | G | E | E | VG | E |
| Nonferrous Metals | F | E | E | F | VG | E | VG | E |
| Old Paints | VG | G | G | E | G | VG | P | — |
| **DECORATIVE PROPERTIES** | | | | | | | | |
| Choice of Colors [e] | U | U | SL | U | U | U | U | L |
| Color Retention | G [f] | VG [f] | P [f] | E [f] | VG [f] | G [f] | E [f] | — |
| Initial Gloss | E | E | VG | E | E | E | E | P |
| Gloss Retention | E | G | F | E | F | G | E | — |
| **APPLICATION** | | | | | | | | |
| Ease of Application | E | Bake req | E | E | Bake req | E | VG | P-VG |
| Metal Surface Prep | Primer | No primer | No primer | Primer | No primer | No primer | Primer | No primer |
| Solvent for Appl [g] | Hyd | Hyd | Hyd | Hyd | Hyd | Hyd | Blend | — |
| Methods [e] | U | U | U | U | U | U | U | L |
| Cure [h] | A or B | B | A or B | A or B | B | A or B | A | A |
| Bake Drying Time [i] | 30 min (275 F) | 20 min (320 F) | 30 min (350 F) | 30 min (350 F) | 20 min (320 F) | 15 min (300 F) | — | — |
| Air Drying Times | | | | | | | | |
| Touch | 2 hr | — | 20 min | 45 min | — | 10 min | 5 min | 2 hr |
| Handle | 4 hr | — | 60 min | 2 hr | — | 30 min | 15 min | 24 hr |
| Re-Coat | 4 hr | — | 6 hr | 4–6 hr | — | 4 hr | 15 min | — |
| Hard | 12 hr | — | 6 hr | 12 hr | — | 4 hr | 12 hr | 24 hr |
| Cor. Res. | 48 hr | — | 48 hr | 12 hr | — | 48 hr | 24 hr | — |
| Coverage, sq ft/gal/mil | 450 | 450 | 450 | 500 | 450 | 400 | 350 | — |
| Coat Thk (avg), mil | 1.5 | 1.5 | 1.5 | 0.6 | 1.5 | 1.5 | 1.0 | 3–250 |
| Cost, ¢/sq ft/mil dry [l] | 1.50 | 1.75 | — | — | — | 1.75 | 2.75 | — |

[a] These data are intended only as a preliminary selection guide. Final selections should be made after consulting with coating formulator.
E = excellent; VG = very good; G = good; F = fair; P = poor.
[b] Two ratings are for dilute (20%) and concentrated, respectively.
[c] Three ratings are for dilute (10%), medium (10–30%) and concentrated, respectively.
[d] Taber CS–10 wheel.
[e] L = limited (pure white cannot be formulated): SL = slightly limited (difficulty in formulating whites and pastels); U = unlimited (any color can be formulated).
Notes [f] through [l] on opposite page.

## Organic Coatings [a]

| Type → | Cellulose | | Epoxy | | | | | | Fluorocarbon (air dried) |
|---|---|---|---|---|---|---|---|---|---|
| | Nitrocellulose | Butyrate | Epoxy (100%) | Epoxy-Amine | Epoxy-Ester | Epoxy-Melamine | Epoxy-Phenolic | Epoxy-Urea | |
| **CHEMICAL RESISTANCE** | | | | | | | | | |
| Exterior Durability | E | E | G | E | G | E | E | G | E |
| Salt Spray | E | E | E | VG | E | VG | VG | VG | E |
| Solvents—Alcohols | G | G | E | E | VG | E | E | E | F |
| Solvents—Gasoline | G | G | E | E | E | E | E | E | F |
| Solvents—Hydrocarbons | F | F | E | E | VG | E | E | E | P |
| Solvents—Esters, Ketones | P | P | F | VG | F | VG | E | VG | P |
| Solvents—Chlorinated | P | P | E | E | F | E | E | E | P |
| Beverages, Food | P | G | E | E | VG | E | E | E | E |
| Salts | G | VG | E | E | E | E | E | E | E |
| Ammonia | P | P | P | P | P | P | VG | P | E |
| Alkalis [b] | P, P | P, P | E, E | E, E | E, E | E, E | E, E | E, E | E, E |
| Acids—Mineral [c] | G, F, P | G, F, P | E, VG, G | E, VG, G | G, F, P | E, VG, G | E, E, E | E, VG, F | E, E, E |
| Acids—Oxidizing [c] | P, P, P | P, P, P | G, P, P | G, P, P | F, P, P | G, P, P | E, VG, P | F, P, P | E, E, E |
| Acids—Organic (acetic, formic, etc.) [c] | P, P, P | P, P, P | G, F, P | G, F, P | F, P, P | G, F, P | E, E, VG | F, P, P | E, E, E |
| Acids—Organic (oleic, stearic, etc.) | F | F | E | E | E | E | E | E | E |
| Acid—Phosphoric | P | P | P | P | P | P | E | P | E |
| Water (salt, fresh) | F | E | VG | G | VG | G | E | G | E |
| **PHYSICAL PROPERTIES** | | | | | | | | | |
| Sward Rocker Hard. (8th day) | 26 | 26 | 36 | 36 | 30 | 36 | 44 | 34 | 20 |
| Flexibility | E | E | E | G | G | VG | VG, E | VG | G |
| Abrasion Res, cycles [d] | 2500 | 2500 | >5000 | >5000 | >5000 | >5000 | >5000 | >5000 | 1000 |
| Max Svc Temp, F | 180 | 180 | 400 | 400 | 300 | 400 | 400 | 400 | — |
| Toxicity | None | None | Slight | Slight | Slight | Slight | Slight | Slight | Slight |
| Impact Res | E | E | G | G | E | G | G | G | E |
| Dielec Properties | P | G | VG | VG | VG | VG | VG | VG | E |
| Adhesion to— | | | | | | | | | |
| Ferrous Metals | VG | VG | E | E | E | E | E | E | VG |
| Nonferrous Metals | G | G | E | E | VG | E | E | E | VG |
| Old Paints | P | P | P | P | F | P | P | P | P |
| **DECORATIVE PROPERTIES** | | | | | | | | | |
| Choice of Colors [e] | U | U | SL | SL | SL | SL | L | SL | U |
| Color Retention | E [f] | E [f] | G [f] | G [f] | E [f] | G [f] | P [f] | G [f] | G |
| Initial Gloss | E | E | VG | VG | E | VG | VG | VG | E |
| Gloss Retention | VG | E | F | F | G | F | F | F | F |
| **APPLICATION** | | | | | | | | | |
| Ease of Application | VG | VG | Catalyst req | Catalyst req | E | Bake req | Bake req | Bake req | VG |
| Metal Surface Prep | Primer | Primer | No primer | No primer | Primer | No primer | No primer | No primer | Primer |
| Solvent for Appl [g] | Blend | Blend | Ketone | Blend | Hyd | Blend | Blend | Blend | Blend |
| Methods [e] | U | U | L | L | U | L | L | L | L |
| Cure [h] | A | A | A | A | A or B | B | B | B | A or B |
| Bake Drying Time [i] | — | — | — | — | 30 min (320 F) | 30 min (350 F) | 30 min (400 F) | 30 min (350 F) | — |
| Air Drying Times | | | | | | | | | |
| Touch | 5 min | 5 min | 45 min | 45 min | 1 hr | — | — | — | 5 min |
| Handle | 15 min | 15 min | 2 hr | 2 hr | 2 hr | — | — | — | 15 min |
| Re-Coat | 15 min | 15 min | 6–8 hr | 6–8 hr | 8 hr | — | — | — | 12 hr |
| Hard | 12 hr | 12 hr | 12 hr | 12 hr | 8 hr | — | — | — | 12 hr |
| Corr Res | 24 hr | 24 hr | 7–10 days | 7–10 days | 5 days | — | — | — | 12 hr |
| Coverage, sq ft/gal/mil | 200 | 200 | 450 | 500 | 450 | 500 | 450 | 500 | 200 |
| Coat Thk (avg), mil | 1.0 | 1.0 | 1.8 | 1.8 | 1.5 | 1.8 | 1.8 | 1.8 | 1.0 |
| Cost, ¢/sq ft/mil dry [j] | 2.50 | 2.75 | — | — | 1.75 | — | — | 2.00 | 15.00 |

Notes [a] through [e] on opposite page.
[f] Based on white coatings with titanium dioxide pigment. [g] Hyd = hydrocarbons; alc = alcohols.
[h] A = can be air dried; B = can be baked. In general, any coating that can be air dried or baked will perform better if baked.
[i] Full corrosion resistance is obtained, immediately upon cooling. [j] Not recommended with nitric acid.
[k] Not recommended with strong solutions of acetic acid.
[l] Based on high quality formulations; figures are meant to serve only as a rough guide.

*continued on next page*

## Organic Coatings [a]

| Type → | Phenolic | Polyamide (nylon) | Rubber | | | Silicone | Urethane | Vinyl | Vinyl-Alkyd (approx 1:1) |
|---|---|---|---|---|---|---|---|---|---|
| | | | Chlorinated Rubber | Neoprene | Hypalon | | | | |
| **CHEMICAL RESISTANCE** | | | | | | | | | |
| Exterior Durability | E | P | E | E | E | E | E | E | E |
| Salt Spray | E | F | E | E | E | E | E | E | E |
| Solvents—Alcohols | E | G | F | E | — | P | F–G | E | G |
| Solvents—Gasoline | E | G | G | F | P | VG | F–G | E | E |
| Solvents—Hydrocarbons | E | — | P | P | — | VG | F–E | G | P |
| Solvents—Esters, Ketones | E | — | P | G | — | P | F | P | P |
| Solvents—Chlorinated | G | — | P | P | — | P | P | P | P |
| Beverages, Food | E | — | G | F | — | P | VG | E | F |
| Salts | E | — | E | E | — | G | E | E | G |
| Ammonia | P | G | VG | E | E | P | P | E | P |
| Alkalis [b] | P, P | G, G | VG, F | E, E | — | P, P | VG, F | E, E | G, P |
| Acids—Mineral [c] | E, E, E | P, P, P | E, G, P | E, G, P [k] | E, E, E | G, P, P | G, F, P | E, E, G | VG, G, P |
| Acids—Oxidizing [c] | E, E, VG | — | E, E, P | G, F, P | — | P, P, P | G, F, P | E, VG, G | P, P, P |
| Acids—Organic (acetic, formic, etc.) [c] | G, F, P | P, P, P | G, P, P | P, P, P | — | P, P, P | G, F, P | E, P, P | G, F, P |
| Acids—Organic (oleic, stearic, etc.) | E | VG | E | F | — | P | F | E | E |
| Acid—Phosphoric | F | — | G | VG | E | P | F | E | F |
| Water (salt, fresh) | E | F | VG | E | E | E | E | E | E |
| **PHYSICAL PROPERTIES** | | | | | | | | | |
| Sward Rocker Hard. (8th day) | 38 | — | 24 | <10 | — | 16 | 35–65 | 20 | 26 |
| Flexibility | G | G | VG | E | E | F | E | E | E |
| Abrasion Res, cycles [d] | >5000 | — | >5000 | 5000 | — | 2500 | >5000 | >5000 | 2500 |
| Max Svc Temp, F | 350 | 300 | 250 | 200 | 250 | 1200 | 300 | 180 | 180 |
| Toxicity | None | — | Slight | None | — | Slight | Slight | None | None |
| Impact Res | G | VG | G | E | E | G | E | E | E |
| Dielec Properties | E | G | E | F | VG | E | E | E | G |
| Adhesion to— | | | | | | | | | |
| Ferrous Metals | E | VG | F | VG | VG | G | E | VG | VG |
| Nonferrous Metals | E | VG | VG | VG | VG | F | E | VG | G |
| Old Paints | G | — | E | — | — | E | F | G | P |
| **DECORATIVE PROPERTIES** | | | | | | | | | |
| Choice of Colors [e] | L | L | L | L | U | U | U | U | U |
| Color Retention | P [f] | — | G [f] | G | E | G [f] | G | VG [f] | E [f] |
| Initial Gloss | VG | G | F | P | P | E | E | G | E |
| Gloss Retention | F | — | F | F | — | E | P | F | E |
| **APPLICATION** | | | | | | | | | |
| Ease of Application | E | G | E | VG | VG | E | E | VG | VG |
| Metal Surface Prep | No primer | No primer | Primer | No primer | No primer | Primer | Primer | Primer | Primer |
| Solvent for Appl [g] | Alc | — | Hyd | Hyd | Hyd | Hyd | Blend | Blend | Blend |
| Methods [e] | U | L | U | U | U | U | U | L | U |
| Cure [h] | A or B | A | A or B | A or B | A | A or B | A or B | A or B | A |
| Bake Drying Time [i] | 30 min (350 F) | — | 15 min (300 F) | 15 min (300 F) | — | 1 hr (400 F) | 30 min (325 F) | 15 min (300 F) | — |
| Air Drying Times | | | | | | | | | |
| Touch | 10 min | — | 45 min | 15 min | 15 min | 45 min | 45 min | 15 min | 5 min |
| Handle | 30 min | — | 2 hr | 30 min | 30 min | 2 hr | 1–2 hr | 30 min | 15 min |
| Re-Coat | 30 min | — | 4–6 hr | 4 hr | 4 hr | 4–6 hr | 4–6 hr | 4–6 hr | 15 min |
| Hard | 4 hr | — | 4–6 hr | 4 hr | 4 hr | 12 hr | 18 hr | 4–6 hr | 12 hr |
| Corr Res | 24 hr | — | 24 hr | 7–10 days | 7–10 days | 12 hr | 5–7 days | 24 hr | 24 hr |
| Coverage, sq ft/gal/mil | 350 | — | 450 | 300–400 | 250–350 | 350 | — | 250 | 200 |
| Coat Thk (avg), mil | 1.5 | 2–30 | 1.5 | 2–10 | 2 | 1.0 | 1–2 | 1.0 | 1.0 |
| Cost, ¢/sq ft/mil dry [l] | 1.75 | — | 1.50 | — | — | 6.00 | — | 2.50 | — |

Notes: See previous two pages.

## Hard Facings

Hard facings (overlays applied by welding operations) are generally applied to surfaces which require high wear resistance. Service conditions which may be met, directly or indirectly, by hard facing include: abrasion (sliding or rolling), galling, impact, work hardening, elevated temperatures, thermal stresses, corrosion and erosion.

**Types.** Most hard facing alloys are proprietary alloys designed for special service conditions, but the basic types are summarized below. It can be misleading to group alloys by hardness or service use because it is primarily structure that determines their properties. Iron-base alloys, for example, can be austenitic, pearlitic, martensitic or a combination of these in the as-deposited, air cooled state. It is often difficult to determine what microstructure can be expected from a given rod.

**Thickness.** Thickness of hard facings ranges from 1/16 to ¼ in. depending upon the application. Parts that require a build-up greater than ¼ in. are usually given a primary layer with a lower cost material. Parts requiring extremely thin layers are generally hard faced with nickel-chomium-boron alloys which wet the base metal so readily that a uniform deposit 1/32 in. thick can be obtained.

**Surface finish.** Smoothness of a hard facing depends upon both material and application method. Nonferrous alloys, having more fluidity, yield the smoother deposits. Tungsten carbide rods produce a rough surface because the particles must be submerged in a matrix of softer material which wears away and exposes the rough carbide particles.

**BASIS METALS FOR HARD FACING**

| Metal ↓ | Suitability | Remarks |
|---|---|---|
| Low and Medium Carbon Steels | Up to 0.50 carbon steels particularly suitable | Pre- or post-heat treatment not required |
| High Carbon and Low Alloy Steels | Up to 1.10 carbon and 14 manganese steels are suitable if careful to prevent cracking | Annealed or as-rolled condition; generally post-heat treated |
| High Speed Steels | Not advisable; shrinkage cracks, strain checks | Annealed condition; post-heated and slowly cooled |
| High Chromium Steels | Susceptible to heat; require careful handling | Preheated to 1200 F; slow post-cooling |
| Manganese Steels | Difficult, due to heat disrupting grain structure. Arc welding best | Stainless steel often applied first as binding agent |
| Stainless Steels | Arc or gas method with care to avoid excessive strains | Parts should be preheated to temperature dependent on stainless type |
| Cast Irons | Difficult. White iron easy for small parts. Otherwise danger of localized overheating | Lower melting point than steel; crust forms on surface |
| Nonferrous Alloys | Not those with melting points below 2000 F | Monel is common and easiest; copper alloys difficult |

**TYPES OF HARD FACING ALLOYS**

| Type → | General Properties | Forms | How Applied | Typical Uses |
|---|---|---|---|---|
| FERROUS ALLOYS | | | | |
| **Hardenable.** Carbon steels; low, medium and high alloy steels; high speed steels | Alloys are listed in order of increasing hardness, corrosion and impact resistance. Medium-high levels of hardness and impact resistance obtainable, but abrasion and corrosion resistance lower than in other types | Mild steel rod with alloys in flux-coating; particles in thin tubes | Arc welding (bare and flux-coated rods) or gas welding (bare rods) | Base for subsequent hard facing with other types (particularly for thick facings); rock and earth-handling equipment |
| **Austenitic.** Chromium and chromium-nickel steels; high manganese steels; high chromium irons; high alloy irons | Provide principally austenitic deposits (except some straight chromium steels) hardenable by cold work. Fair degree of hardness with good impact and abrasion resistance extending into elevated temperatures | Cast rods | Arc welding (bare and flux-coated rods) or gas welding (bare rods) | Crushing equipment; such earth-moving equipment as bucket lips, crusher rolls and muller tires; plowshares |
| NONFERROUS ALLOYS | | | | |
| **Cobalt-base.** Medium carbon; high carbon | High corrosion resistance, good abrasion and impact resistance. Hardness less than high ferrous alloys but retained at elevated temperatures ("red hardness") | Solid rods cast in permanent or sand molds | Gas welding (use of torch is similar to brazing) | Valves, pump parts, dies; large areas where hairline cracks not permissible |
| **Nickel-base.** Nickel-chromium; nickel-chromium-tungsten molybdenum | Excellent heat and corrosion resistance, fair abrasion and impact resistance. Hardness is less than high ferrous alloys but retained at elevated temperatures ("red hardness") | Solid rods cast in permanent or sand molds | Gas welding (use of torch is similar to brazing) | Very thin sections; parts which must be hot formed or hot wiped; substitute for tungsten carbide rods |
| **Intermetallics.** Tungsten carbides; thers | Maximum hardness with excellent resistance to impact and corrosion. Despite brittleness, carbides have excellent resistance to fracture when backed up with steel. | Cast rod; particles in thin tube; powder; inserts | Rods by gas or arc; powder by spraying; inserts by "puddling" | Oil well drilling tools; mill hammers, augers, dipper bucket teeth and lips, mixing plows |

## Ceramic, Cermet and Refractory Coatings

| Type ↓ | Important Properties |
|---|---|
| **Mixtures of Porcelain Enamel Frits and Refractory Materials** | |
| NBS[a] A-19 | Prevents oxidation of noncritical steels at high temp. Protects low carbon steel to 1250 F and high temp austenitic alloys to 1550 F |
| NBS A-31 | Similar to A-19 coating but, since it must be applied in two coats, is only used for specialized applications |
| NBS A-417 | Protects noncritical steels against high temp oxidation. Has been largely supplanted by A-418 coating |
| NBS A-418 | Widely used to extend life of heat resisting steels such as Inconel, Inconel X, Nimonic 75, HS-21 and 18-8, 19-9 and 25-20 stainless steels. Protects up to 1750 F. Not recommended for low carbon steels |
| NBS N-143 | Has low absorption coefficient for thermal neutrons and is designed for nuclear applications. Protects 310 stainless, Nichrome V and Inconel against oxidation up to 2050 F |
| Proprietary Coatings for:[b] | |
| Low Carbon and Low Alloy Steels | Improves oxidation and corrosion resistance to 1400 F |
| 300 and 400 Stainless Steels | Extends service life of most alloys up to 1800 F. Special formulations protect against unusual abrasive or corrosive attack up to 2000 F |
| Aluminum | Extends operating temp of standard and some high strength alloys up to 1550 F |
| Titanium | Allows use of titanium up to 1500 F |
| Thin-Gage Metals | Protects foils 1 to 10 mils thick at temp up to 1750 F. Used on 300 and 400 stainless steels and superalloys |
| Extra High Temperatures | Special coatings for use up to 2100 F. Can be used on all alloys containing 45% of the combination of chromium (10% min), cobalt and nickel |
| Resistance to Galling | Provides low friction and prevents galling at temp from 800 to 1650 F. Can be used on all ferrous (and some nonferrous) alloys |
| **Pure Refractory Oxide Coatings** | |
| Aluminum Oxide (Alumina) | Provides high resistance to wear and abrasion, good thermal insulation, and high resistance to oxidation (3600 F melting point). Can be applied by variety of methods (e.g., flame spraying, Flame-Plating and plasma jet) to almost every ferrous and nonferrous metal, as well as some plastics and other non-metallic materials |
| Zirconium Oxide (Zirconia) | Because of higher melting point (4500 F) can be used at higher temp than alumina. However, is not as hard or as resistant to abrasion as alumina. Can be used on same materials as alumina |
| **Cermet Coatings[c]** | |
| Aluminum-Ceramic | Composed of a mixture of aluminum alloy powder and ceramic frits. Can be applied to carbon steels, low alloys and cast iron for oxidation protection to 1200 F. Has high resistance to thermal shock and impact |
| Chromium Carbide (flame sprayed) | High resistance to abrasion and oxidation up to 2900 F. Can be ground to smooth finish |
| Chromium Carbide (chromized) | Provides hard and wear resistant case on low carbon steels, many alloy and high chromium steels, and iron powder parts |
| Chromium-Nickel Boride | Protects iron and steel against attack by molten aluminum. Good resistance to thermal shock |
| Molybdenum Disilicide | Provides good oxidation resistance to 2900 F. Coating is brittle but this may not be important in non-structural uses |
| Nitrided Surfaces | Essentially, nitriding provides a cermet coating. Process is limited to certain grades of steel and forms an extremely hard case which retains hardness up to 1100 F and is not subject to fatigue |
| Silicon Carbide | Improves erosion resistance of graphite up to 4000 F. Highly resistant to acids and alkalis |
| Tungsten-Carbon and Tungsten-Boron | High density (0.53 lb per cu in.) is useful in increasing weight in restricted places |
| Tungsten Carbide | Provides extreme hardness and wear resistance. Can be applied to almost all metals |
| **Other Refractory Coatings[d]** | |
| Aluminum Silicate (mullite) | Protective coating for graphite |
| Iron Titanate | Similar to titanium dioxide in properties, but coating is softer and hence less useful |
| Iron Titanate: Gamma Aluminum (50:50) | Coating is conductive and has melting point of 2500 F. Not widely used |
| Titanium Dioxide | Provides hardness and wear resistance. Coating is tough, has excellent adhesion and is not brittle |
| Zirconium Silicate | Provides high hardness and resistance to wear, corrosion and thermal shock. Coating is nonconductive and has good adhesion |

[a] National Bureau of Standards.

[b] Many of these coatings are variations of NBS coatings. Coatings described are typical; many others are available for other base metals and special applications.

[c] In addition to the coatings described, recent announcement has been made of a number of other cermet coatings which can be applied by the plasma jet process. These coatings include refractory carbides of columbium, hafnium, tantalum, zirconium, titanium and vanadium. As of spring, 1959, these coatings are still largely in the experimental stage and little information is available on properties and applications. Molybdenum aluminide and nickel aluminide cermet coatings and rare earth (50% cerium oxide) refractory coatings can be applied by flame spraying but they do not appear to have any useful properties.

[d] In addition to the coatings described, a number of other refractory coatings can now be applied by the plasma jet process. These coatings are still experimental and property data is not yet available. The coatings encompass a wide variety of materials, including: 1) refractory oxides of thorium, hafnium, magnesium and cerium; 2) refractory metal compounds, such as borides of zirconium, tungsten, columbium, tantalum, titanium and chromium; 3) refractory metals, such as tungsten, tantalum, molybdenum and rhenium.

## Mechanical Finishes for Aluminum, Copper and Stainless Steel[a]

| Type ↓ | Appearance | How Finish Is Obtained[b,c] | Uses |
|---|---|---|---|
| **Smooth Bright** (buffed) | Brightest mechanical finish. Surface is smooth and lustrous, can be made mirror-bright by using fine abrasive, electro-brightening in final polishing, or (on Al) chemical brightening. Cu must be plated or clear-lacquered to preserve appearance | Two or three buffing operations (with progressively softer buffs and/or finer compound) following polishing or other finishing operations. Skilled operator needed to prevent buff-burned or pitted surfaces. Approx buffing wheel speeds: stainless 10,000; Al 8000; Cu 6–10,000 sfpm. Al usually given light caustic etch between buffing steps to remove embedded particles | For attractive appearance or high reflectivity. Usually economically feasible only for larger items or close tolerance parts. Examples: household appliances, sanitary equipment, auto and boat trim, light reflectors, jewelry, small objects d'art. Also for Al before anodizing |
| **Smooth Bright** (burnished) | Not as bright as buffed surface esp if surface has retained oxide coating or has not been machined. Brightness depends on treatment time and relative movement and pressure of burnishing media | Gentle tumbling in barrel with stainless steel balls 1/16–½ in. in dia and neutral soap solution (+ soap bark for Cu).[d] Time required: stainless, 1–4; Al, 1½–2½; Cu, 6–48 hr. Hard to get uniform finish on complex-shaped parts | Similar to above, but generally smaller, mass-produced parts or parts difficult to buff. Examples: pen points, eyelets, grommets, auto trunk locks, auto push-buttons |
| **Satin Semi-Bright** (wheel or belt polished) | Smoothest sheen of the satin finishes because of finer, more irregular scratches. Brightness depends on fineness of abrasive in final operation. Tampico brush wheels produce slightly duller surface | Several polishing operations following grinding.[e] Wheels may be fabric, felt or leather. Lubrication usually required in wheel polishing with finer abrasives; belts reduce danger of overheating. Approx speeds: stainless 4500–7500, Al 5–6000, Cu 6–9000 sfpm. Abrasive usually alumina or silicon carbide (neither emery nor silicon carbide recommended for stainless). Preliminary polishing of Cu often done by sand-bobbing (using abrasive and wheel wet with mineral oil) | Parts where attractive, low reflection finish is desired. Examples: dairy, bar and cafeteria equipment; utensils; auto and furniture handles, knobs, rosettes. Also to prepare for finer finishes |
| **Satin Semi-Bright** (wire brushed) | Smooth sheen; smoothness dependent on wire size (thinnest wire for smoothest finish). Usually brighter than satin finish produced by polishing | Wire brushing of low polished surface entirely free of grease or oil. Brushes usually 10 in. in dia. Low pressures used. Wheel speeds from 2000 rpm for polished sheet to 600 rpm for castings (castings usually dustblasted or medium sandblasted before brushing). Nitric acid dip may be used after brushing to dissolve embedded particles | Same as above. Widely used on Al, sometimes on Cu. Not used on stainless because of its hard surface |
| **Textured Semi-Bright** (hammered) | Decorative finish somewhat similar to wrought silver. Minor scratches and defects obscured | Hammering by hand. Parts may be heated in smoky fire and hammered until soot is embedded; polishing of high spots then produces special decorative effect | Used on Al and Cu. Examples: architectural and commercial products, giftware, novelty items |
| **Textured Semi-Bright or Matte** (embossed or engraved) | Patterned finish having wide variety of decorative effects | Sheet passed between embossing rolls or pantograph-engraved; recesses may be filled with enamel for contrast and decoration. Applied to polished, buffed, satin finished, sandblasted (Al) or vapor honed (stainless) surfaces | Decoration and increase in rigidity. Limited to flat work. Examples: building panels, doors, nonskid surfaces, auto trim, plaques, tablets, nameplates |
| **Textured Matte** (sandblasted) | Special decorative effects, esp by combination with other processes. Surface texture depends on size and type of abrasive, amount of air pressure, and movement and angle of nozzle. Surface collects dirt unless protected, as by clear lacquer | Spraying surface with fine abrasive or slurry by air pressure. Careful control of nozzle is needed for desired effects and to prevent distortion. Contrasting surfaces obtained by enameling, anodizing, blackening, highspot polishing, caustic etching, etc. | Primarily for Al.[f] Examples similar to above; not limited to flat pieces |

[a] Including aluminum and copper alloys.
[b] Stainless steel can be purchased with a number of different mill finishes. The bright cold rolled finish is usually specified for subsequent polishing or buffing. If severe forming is to be done, dull cold rolled may be preferable. Higher mill finishes available include polished, Tampico brush-finished and semi-mirror-finished.
[c] Aluminum mill finishes include a variety of embossed designs and a fluted finish.
[d] Another tumbling process—with granite chips, alumina or silica sand—is used to deburr and smooth stainless and aluminum parts, but does not produce as bright a surface and is not recommended for close tolerance parts.
[e] On aluminum, a somewhat brighter surface can be obtained by further finishing with steel wool and kerosene; a somewhat duller surface by low or coarse polishing followed by rubbing with steel wool and soapy water.
[f] Special effects on copper often achieved by engine turning. Stainless is usually vapor honed.

# Porcelain Enamels

### Composition

Porcelain enamels are inorganic glass coatings for metal that are formulated for specific applications. They are characterized by easy-to-clean, smooth, hard, lustrous surfaces that are resistant to attack by chemicals, heat and mechanical abrasion. They embrace a wide variety of compositions, all of which are similar in that they consist essentially of a glass matrix (usually alkali borosilicate) in which may be suspended crystalline opacifiers and pigments. When appreciable quantities of refractory compounds, such as alumina, chromic oxide or silica, are incorporated to increase heat resistance, these special porcelain enamels are termed ceramic coatings.

Conventional porcelain enamels for steel comprise one, two or three layers. The first layer is a dark colored 3 to 4-mil "ground coat" (analogous to an organic primer) containing an oxide of cobalt or nickel that promotes good adhesion to the steel. On other metals, where the oxide need not be present, the ground coat may be light colored or white. In addition to promoting adhesion, the ground coat also tends to cover or hide certain defects in the metal and on the metal surface. Where appearance is not important, the ground coat is frequently used as a single protective coating. Some of the single-coat porcelain enamels (the gray or speckled types) are attractive. They can also be made alkali resistant.

Ordinarily, one or two 3 to 5-mil layers of "cover coat" are applied to achieve a desired appearance or protection property. Two general types of cover coat are used: opaque white and non-opaque. Titanium dioxide, the opacifier used in most opaque white cover coats, is incorporated in the glass and crystallizes during the firing operation. It provides the high covering power that makes possible satisfactory coverage with a single 3 to 4-mil top coat. The oxides of tin, antimony and zirconium are also used as opacifiers, but to a lesser extent than titania.

### Base Metals

Porcelain enamels can be applied to most metals and alloys provided the metal remains solid at the firing temperature and does not oxidize excessively during firing. Because fusion is accomplished at high temperatures and involves cooling over a fairly large temperature range, the coefficient of thermal expansion (or contraction) of the porcelain enamel should be slightly lower than that of the metal to which it is applied. This assures that the coating will be under compression at the operating temperature of the coated part. Compression is desirable because the coating, being a glass, has about ten times the strength in compression that it has in tension.

In addition to most ferrous alloys, porcelain enamels can be applied to gold, silver, platinum, copper, aluminum and superalloys. The more commonly used metals are:

**Enameling iron.** Low carbon, low metalloid, rimmed steel, specifically designed and specially processed for porcelain enameling. It is produced in sheets of various gages from about 30 to 11, and in two grades: regular and deep drawing. It has good resistance to sagging and distortion during firing of the porcelain enamel and produces a minimum of surface defects in the coating.

**Cold rolled mild steel.** Low carbon rimmed steel sheets (usually AISI 1008 or 1010) of good surface quality, available as commercial and deep drawing grades. This metal is subject to more warping during firing than enameling iron and is more likely to produce defects in the coating. For these reasons porcelain enamels applied to cold rolled mild steel are usually fired at temperatures below 1450 F.

**Hot rolled steel plate.** Hot rolled, low carbon steel plates of heavy gage are used primarily in the fabrication of domestic hot water tanks and other structures requiring strength and corrosion resistance. This metal is not suited for parts where appearance properties are of vital importance.

**Special enameling steels.** Special steels of low metalloid content specially processed to accept porcelain enamel cover coats without the use of a ground coat. One type has an extremely low carbon content (0.003% or less) and another is titanium-bearing.

**Cast iron.** Gray iron castings of the following composition: 2.50 silicon, 3.00 carbon, 0.70 phosphorus, 0.60 manganese, 0.08 sulfur and 0.40% combined carbon. Must have reasonably dense and uniform structure and must be free from porosity, slag inclusions and segregation.

**Aluminum.** Wrought and extruded alloys include: 1100, 3003, 6061, 6062, and 6063. Cast alloys include: 43, 356 and 344X. In selecting aluminum alloys for porcelain enameling, it should be remembered that maturing temperatures of the coatings are above the annealing temperatures of the "common" alloys.

**Aluminized steel.** Combines strength, rigidity and sag resistance of steel with many of the advantages of aluminum.

**Stainless steel.** Important base metal for ceramic coatings for parts operating at temperatures up to 1200-1800 F. The 300 and 400 series are most commonly used.

### Appearance Properties

**Color.** Although certain colors are more difficult or expensive to control during application, the full spectrum of colors, including white and black, can be produced. Burgundies, purples and certain shades of orange and red are most difficult to control in production. Pigmenting materials are inorganic metallic compounds known as "ceramic oxides." Because they are chemically and thermally stable, they contribute to the color permanency associated with porcelain enamels.

Metallic lusters, such as copper, bronze, gold and platinum, can be produced, but are usually restricted to small patterns or designs.

**Texture.** Textural appearances available are best described by the method of producing them. These decorative processes include stippling or speckling, veiling, polytoning, graining and marbleizing, stenciling, printing, silk screening and decalcomania.

**Opacity.** The reflectance of white porcelain enamels ranges from 60 to 90%, as compared to 100% for magnesium oxide (ASTM Method C347 for Reflectance). Many tints of white extending into light pastels are also available.

### Application Methods

**Wet process.** Simply stated, porcelain enameling is the process of re-fusing powdered glass into a continuous layer on the surface of a metal. In the wet process, water is used as a vehicle to facilitate application of the powdered glass. The mixture of solid

particles suspended in water, called a slip, can be applied by any of the methods used for organic coatings: spraying, dipping or flow coating. After the liquid slip is applied, water is removed by drying. The film of dry particles on the metal is then fused by heating for a short time at the temperature established for the particular coating composition involved.

Firing temperatures range from 1000 F, or below, for porcelain enamel on aluminum, up to 2000 F, or above, for some ceramic coatings applied to high temperature alloys. Porcelain enamels applied to sheet steel are fired at about 1350-1600 F. Most ground coats are fired at 1450-1550 F; most cover coats at 1400-1500 F. The ground coat is usually fired at a temperature 25-50 F higher than the temperature at which the cover coat is to be fired, although a number of specific ground-and-cover-coat combinations have been developed in which ground-coated and cover-coated pieces can be fired at the same temperature. Wet process cast iron and some new low-firing porcelain enamels for steel mature at temperatures as low as 1200 F. Some chemically resistant porcelain enamels (called glass coatings) are fired at temperatures as high as 1650 or 1700 F.

**Dry process.** Used primarily for heavy sections of cast iron or steel plate. The bare shape is heated to about 1700 F and then removed from the furnace. The porcelain enamel, in the form of a fine dry powder, is sprinkled on the hot surface. The coated piece is returned to the furnace to complete fusion of the porcelain enamel and to produce the very glossy, fire-polished surface that is characteristic of this process. A high degree of skill is required.

### Chemical Properties

**Acid resistance at room temperature.** Porcelain enamels are tested for acid resistance at room temperature by the standard Porcelain Enamel Institute Test, PEI T-7 (ASTM C282). A porcelain enameled specimen is exposed to a 10% solution of citric acid for 15 min. The enamel is rated on the basis of the appearance of the treated area and the extent to which it retains soil. Ratings are: Class AA (no attack), A, B, C and D (complete loss of gloss).

**Boiling acid resistance.** Resistance to attack by boiling acid is evaluated in terms of weight loss per unit area produced by 2½-hr exposure to a boiling 6% solution of citric acid (ASTM C283).

**Mineral acid resistance.** Special porcelain enamels can be formulated to be resistant to attack by any mineral acid (except hydrofluoric) at any concentration and at temperatures up to the atmospheric boiling point of the acid.

**Weather resistance.** All porcelain enamels give excellent protection against corrosion if coverage is complete before installation, and if no severe mechanical damage occurs. For best resistance to loss of gloss and color change during prolonged weathering, only those porcelain enamels should be used that pass the acid resistance test described in the Porcelain Enamel Institute Specification for Architectural Porcelain Enamels on Steel for Exterior Use (PEI S-100). Most such porcelain enamels have acid resistance of Class A or better.

Certain red and yellow acid-resisting porcelain enamels containing cadmium-selenium pigments may fade on prolonged exposure to weather. A copper sulfate spot test (described in PEI S-100) can be used to select red and yellow porcelain enamels that are free from such fading.

**Alkali resistance.** All porcelain enamels are highly resistant to attack by alkaline solutions at room temperature; all porcelain enamels are strongly attacked by boiling concentrated caustic solutions. Special porcelain enamels are available that have excellent resistance to attack by hot dilute alkaline solutions, such as detergents.

### Thickness

Thickness of most porcelain enamel finishes will be in the following range:

| Porcelain Enamel | Thickness Range, mils |
|---|---|
| One Coat on Steel | 3-8 |
| Normal Two Coats on Steel | 7-11 |
| Multicoat Finishes on Steel | 11-25 |
| Wet-Process Cast Iron | 10-25 |
| Dry-Process Cast Iron | 25-70 |
| Aluminum (1 or 2 coats) | 2-10 |
| Stainless Steel | 2-10 |
| Copper | 2-20 |

Multicoat finishes are required for brilliant or saturated colors. Whites or pastel colors can be produced in one or two coats.

### Physical and Mechanical Properties

**Abrasion resistance.** Porcelain enamels combine a Mohs hardness of 4 to 7 with an exceptionally smooth surface, resulting in good resistance to abrasion and mechanical wear. Abrasion resistance of a porcelain enamel is evaluated by a standard test, PEI T-2 (ASTM C448-59T).

**Torsion resistance.** Torsion resistance is evaluated by twisting a porcelain enameled metal angle until the coating fails by chipping along the apex (PEI T-5; ASTM C409). Values for a 12-in. long angle vary from about 30 deg for heavy coatings to over 180 deg for thin one-coat finishes.

**Adherence.** Degree of bonding between the porcelain enamel and the underlying metal is evaluated by subjecting a specimen to a controlled severe deformation that fractures the coating. Adherence is evaluated in terms of the percentage of the deformed area to which the coating adheres after the treatment (PEI T-17; ASTM C313).

**Thermal shock resistance.** Porcelain enamels are normally unaffected by very fast heating, but may be damaged by very rapid quenching from high temperatures. In general, thin coatings have greater thermal shock resistance than thick coatings. Very thick coatings may fail when immersed in ice water from a temperature of 300 F; thinner coatings may be undamaged when quenched from 800 F. Ceramic coatings have been quenched repeatedly from 1600 F without damage.

**Heat resistance.** Most porcelain enamels are viscous at their firing temperatures. The upper temperature limit for prolonged exposure is about 400 °F below the firing temperature, although this temperature can be exceeded for brief periods without damage. The upper temperature limit for prolonged service will vary from about 600 F for porcelain enamels on aluminum to 1100 F for some porcelain enamels on steel. Ceramic coatings have been developed for temperatures above 2000 F.

## Chemical Conversion Coatings


| Purpose and Type ↓ | How the Coatings Compare | Metals That Can Be Coated[a] | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Aluminum | Cadmium | Copper | Iron | Magnesium | Silver | Steel | Tin | Titanium | Zinc |
| **To Improve Paint Bonding** | | | | | | | | | | | |
| Phosphate | Rough crystalline structure provides excellent paint adhesion. Better paint bond than chromate coatings. Corrosion confined to limited area when paint film damaged | X | X | | X | 0 | | X | 0 | | X |
| Chromate | Provides high corrosion protection because of nonporous structure. Paint adhesion generally not as good as with phosphate | X | X | 0 | | X | 0 | | | | X |
| **To Improve Corrosion Resistance** | | | | | | | | | | | |
| Anodic | Provides equal or better corrosion protection—at higher cost—than chromate | X | | | | X | | | | | 0 |
| Chromate | Generally provides much better corrosion resistance than phosphate. Nonporous structure acts as moisture barrier. If coating is broken, inhibiting action of soluble chromate retards corrosion of basis metal | X | X | X | | X | 0 | | | | X |
| Phosphate | Not generally used alone for corrosion protection. When treated with oils, waxes or stains, however, it provides good protection, especially on ferrous surfaces | X | 0 | | X | | | X | 0 | | X |
| Oxide and Other | Do not provide as much protection as other conversion coatings, but cost is lower | 0 | 0 | 0 | 0 | | | 0 | | | 0 |
| **For Decoration** | | | | | | | | | | | |
| Chromate | Available in wide variety of natural and dyed colors. Colors are not as light-fast as in colored anodic coatings | X | X | X | | X | | | | | X |
| Anodic | Can be colored with a large variety of dyes and pigments. Underlying metal can be used to impart attractive metallic sheen. Sealing required | X | | | | X | | | | | 0 |
| Phosphate | Little decorative value except when painted | X | X | | X | 0 | | X | 0 | | X |
| Oxide and Other | Black and blue-black coatings widely used to decorate ferrous, zinc and cadmium surfaces. Considerable number of colors producible on copper and aluminum | X | X | X | X | | | X | | | X |
| **To Aid In Cold Forming** | | | | | | | | | | | |
| Phosphate | By preventing metal-to-metal contact, lubricated coating facilitates deep drawing, cold heading, extrusion, and wire and tube drawing | X | | | X | | | X | | | X[b] |
| Oxide and Other | Special coatings have been developed for titanium | | | | | | | | | X | |
| **To Improve Wear Resistance** | | | | | | | | | | | |
| Phosphate | Maintains continuous oil film between bearing surfaces; prevents welding of surfaces under load | | | | X | | | X | | | |
| Anodic | Hard anodic coating with greater thickness and weight than conventional anodic coatings increases wear and abrasion resistance | X | | | | X | | | | | |

[a] X—Metals most commonly treated for purpose listed. O—Metals less commonly treated. [b] Electroplates.

## Preplated and Precoated Metals

| Surface and Coating Method ↓ | Base Metal | | Critical Functions, Properties | Typical Applications |
|---|---|---|---|---|
| | Metal | Form | | |
| **Aluminum** (hot dipped) | Low carbon steel or copper-bearing | Sheet, strip | High heat reflectivity. High temperature oxidation resistance. Forms refractory alloy at 1000 F. Strong, low cost base | Oven door liners, aircraft firewalls, auto mufflers, broiler and toaster parts, baffles for space heaters, jet engine parts |
| | Steel (ASTM A122) | Strand (7-wire) | Galvanic protection. Strong base. Longer life than zinc-coated steel | Guy wires, span wires, overhead ground wires |
| **Brass, Copper** (plated) | Low carbon steel | Sheet, strip | Decoration. Atmosphere resistance. Good solderability | Luggage, hardware, costume jewelry, tubing, frames, stands |
| | Zinc | Sheet, strip | Decoration | Molding, ornaments, trim, badges, buttons |
| **Bronze**[a] | Low carbon steel | Strip | Decoration. Atmosphere resistance. Strong base. Conserves copper | Ornamental trim, shell cases |
| **Chromium**[b] (plated) | Aluminum, brass, copper, zinc | Sheet, strip | Decoration | Toys, reflectors, trim, signs, auto accessories |
| | Low carbon steel | Sheet, strip | Decoration, atmosphere resistance | Heater and toaster shells, tubes |
| **Lead**[c] (plated) | Low carbon steel | Sheet, strip | Atmosphere resistance. Good solderability, drawability | Telephone cable sheathing, containers |
| (plated or hot dipped) | Copper (ASTM B101) | Sheet, strip | Atmosphere resistance | Roofing, flashing |
| (hot dipped) | Low carbon steel | Sheet, strip | Atmosphere resistance. Good solderability, drawability. Paint base | Ammunition boxes, ducts |
| **Terne**[d] (hot dipped) | Low carbon steel | Sheet | Atmosphere resistance. Good solderability, drawability. Paint base | Gasoline tanks, caskets, paint and oil containers, door frames |
| **Nickel**[e] (plated) | Low carbon steel | Sheet, strip | Decoration, atmosphere resistance | Toys, nameplates, trays, knives |
| **Tin** (plated) | Low carbon steel | Sheet, strip | Resistance to atmosphere, chemicals. Good solderability. Strong, low cost base | Food product cans, kitchenware, bearings (babbitting base), parts to be soldered |
| (hot dipped) | Low carbon steel | Sheet, strip | Same as above | Tin cans for food products |
| **Zinc** (plated) | Low carbon steel | Sheet, strip, flat wire | Atmosphere resistance. Galvanic protection. Strong, low cost base | Lighting fixtures, refrigerator parts, spools and reels, oil cans, signs |
| (hot dipped) | Low carbon steel (incl ASTM A123) | Plate, bar, sheet, strip, shapes | Same as above | Agricultural, refrigerator and air conditioning parts, auto mufflers |
| | Carbon or low alloy steel (ASTM A53) | Tubing, pipe, conduit | Same as above | Water pipe. Electrical and hot air conduits |
| | Low carbon steel | Wire | Same as above | Fencing |
| **Alkyd Baking Enamel** | Low carbon steel, aluminum | Strip | Decoration, atmosphere resistance | Venetian blinds, auto dashboards, lighting fixtures, awnings |
| **Polyvinyl Chloride** | Steel, aluminum, magnesium | Sheet, strip | Decoration. Resistance to atmosphere, chemicals. Abrasion resistance. Formability. Low cost base | Business machine housings, auto panels, television cabinets, air conditioner housings |
| **Vinyl Lacquer or Enamel** | Low carbon steel, aluminum, brass, zinc | Strip | Decoration. Atmosphere resistance. Formability | Caps, lipstick cases, garden tools, toys, eyelets, flashlight parts |
| **Other** | Steel, aluminum, brass, zinc | Strip | Same as above | Toys, reflectors, brackets, frames, caps, movie reels, ashtrays, auto moldings and trim, novelties |

[a] 90–10. [b] Over nickel. [c] Sometimes over copper. [d] 75–85% lead. [e] Over copper.



Here's the fast, economical way to protect vital parts and equipment against temperatures up to 4600°F . . . extreme abrasion . . . electrical energy . . . erosion and corrosion. Simply apply ROKIDE Ceramic Coatings — hard, crystalline refractory materials — which provide *positive* protection.

ROKIDE Coatings are supplied in rod form as "Z" Zirconium Oxide, "A" Aluminum Oxide, "C" Chrome Oxide, "ZS" Zirconium Silicate, and "MA" Magnesium Aluminate. To apply, rod is heated and the molten particles projected at high velocity against the prepared surface, where they adhere and solidify.

ROKIDE Coatings are extensively used for both military and industrial applications such as: missile components, bearing surfaces, extrusion dies, furnace and feed rolls, induction coils, igniter tips, strain gages, buffing fixtures, mechanical seal rings, pump shafts, capstan wheels, impellers, crucibles, etc.

ROKIDE Coatings are available from a number of strategically located job shop applicators or direct from Norton Company, Worcester, Mass., and Santa Clara, California. Find out how they can cut *your* maintenance and production costs. NORTON COMPANY, 350A New Bond Street, Worcester 6, Massachusetts.

# *Protect modern metals and materials*

## *with ROKIDE* Ceramic Coatings*

*Trade-Mark Reg. U. S. Pat. Off. and Foreign Countries



Write for full details on the ROKIDE Coating Process.

**NORTON**
**REFRACTORIES**
*Engineered . . . Rx . . . Prescribed*

*75 years of . . .* **Making better products . . . to make your products better**

**NORTON PRODUCTS:** Abrasives • Grinding Wheels • Machine Tools • Refractories • Electro-Chemicals — **BEHR-MANNING DIVISION:** Coated Abrasives • Sharpening Stones • Pressure-Sensitive Tapes

For more information, turn to Reader Service card, circle No. 453

# SOLVAY® CHEMICALS

## for { METAL FINISHING, CLEANING, PROTECTION

**MUTUAL® CHROMIC ACID**

**Uses:** Chromium plating.
Anodizing of aluminum to resist corrosion.
Pickling and bright dipping of copper, copper alloys, zinc, cadmium, aluminum, magnesium.
Active ingredient in chromate conversion coatings.
Packaged in Steel Drums.

**MUTUAL SODIUM BICHROMATE**

**Uses:** Pickling and bright dipping of copper, copper alloys, zinc, cadmium, aluminum, magnesium.
Active ingredient in chromate conversion coatings.
Packaged in Paper Bags, waterproof Burlap Bags, Fiber Drums, Steel Drums, Tank Cars, Tank Trucks.

**MUTUAL POTASSIUM BICHROMATE**

**Use:** Active ingredient in chromate conversion coatings.
Packaged in Paper Bags, Fiber Drums, Steel Drums.

**METHYLENE CHLORIDE**

**Use:** A most effective paint stripper. In specialized solvent-type formulations, quickly and thoroughly removes caustic-resistant organic finishes from wood, aluminum, etc.

**SOLVENTS**

**Methylene Chloride** (Also see above). Non-flammable. Low in toxicity. Used to dilute flammable solvents to raise flash points into the safety zone. Used with an evaporation retardant for cold dip degreasing of metal parts. Packaged in Drums, Tank Cars. **Carbon Tetrachloride.** Solvent for metal degreasing. Non-flammable. Packaged in Tank Cars, non-returnable Rheemcote Lined Drums. **Chloroform.** Non-flammable solvent. Packaged in Tank Cars, non-returnable Drums. **Monochlorobenzene.** Solvent of moderately high flash point. Packaged in Steel Drums, Tank Cars, Tank Trucks. **Ortho-dichlorobenzene.** Solvent of moderately high flash point. Packaged in non-returnable Steel Drums, Tank Cars, Tank Trucks.

**SODIUM NITRITE**

**Uses:** Forms an invisible, water-soluble gamma oxide protective film that guards metal surfaces against corrosion.
Used with nitrates for heat treating metal. Low melting point.
Used with caustic soda for blackening steel. Oxidizing agent.
Packaged in Barrels, Steel Drums, Bags, Tank Cars.

**HYDROGEN PEROXIDE**

**Uses:** Used as a depolarizer, to remove hydrogen gas from metal surface.
Used in metal salt solutions to purify. Removes iron in nickel plating.
Cleans, brightens metal surfaces.
Oxidizing agent for phosphate coatings.
Oxidizing agent for zinc phosphate baths. Removes iron.
Packaged in returnable Aluminum Drums, Tank Cars, Tank Trucks.

**METHYL CHLORIDE**

**Use:** In metal annealing salt baths, assists in dissolving oxide impurities.
Packaged in pressurized Tank Cars.

Allied Chemical

**SOLVAY PROCESS DIVISION**
61 Broadway, New York 6, N.Y.

*SOLVAY branch offices and dealers are located in major centers from coast to coast.*

**SOLVAY PROCESS DIVISION** 42-11
ALLIED CHEMICAL CORPORATION
61 Broadway, New York 6, N. Y.

Please send me further information on_____
(list products and uses that interest you)


Name_____

Company_____

Address_____

City_____ Zone_____ State_____

For more information, turn to Reader Service card, circle No. 378




*Photograph of the cupric oxide needles (magnified 6500x) produced by immersion of copper part in hot solution of Ebonol "C" Special.*

Treating copper and brass surfaces with Ebonol "C" Special will insure high adhesion for almost every type of coating. This patented product of Enthonics Research forms thousands of jet black cupric oxide needles per square inch. Once these needles become imbedded in the coat or adhesive, and the coating sets, adhesion is tight and long-lasting. Lacquers, enamels and plastics are all bonded firmly to copper or brass surfaces when these surfaces have been pre-treated with Ebonol "C" Special.

Use Ebonol "C" coatings to achieve extremely low reflectivity on military equipment and optical parts. The coatings absorb oil, giving better lubrication of copper surfaces. They resist corrosion and produce an attractive finish with little dimensional change. Heat radiating and absorbing abilities of the surface are increased. Printed circuit manufacturers oxidize copper foil in Ebonol "C" Special before coating with adhesive and bonding to the plastic laminate. Result: double the bond strength.

Write for the complete story on Ebonol "C." We promise it will be immediately rewarding.
Enthone, Incorporated, 442 Elm Street, New Haven, Connecticut.

ASARCO

**ENTHONE**


*A subsidiary of American Smelting and Refining Company*

**For more information, turn to Reader Service card, circle No. 411**

**ENGINEER'S NOTEBOOK**

# *Flame sprayed metal increases wear resistance better than 10 times*

## AIDS WEIGHT REDUCTION




Automatic setup for metallizing inner walls of aluminum cylinders used in lightweight gasoline engines. Cabinet in foreground houses six-station rotary setup; automatic control panels are at right.

Many methods, including cast-iron cylinder liners and chrome plating, have been tested for wear resistance in lightweight gasoline engine blocks of aluminum.

Best of these methods experienced breakdowns in less than 400 hours. Now they are metallized with METCO Sprabond (molybdenum alloy) as a bonding agent, followed by a coating of sprayed steel alloy.

Test runs of over 4,000 hours show little or no wear of the metallized surface. Finish thickness is .007"; weight – a few grams. Cast-iron liners weighed almost ½ pound.

Cylinder at left machined ready for flame spraying; one at right has been metallized and hone finished.






Closeup of automatic six-station rotary setup. Cylinders are individually rotated at 150 rpm. Cylinder is loaded on table at Station 1, moved through Stations 2 and 3 for pre-heating by torch. At Station 4, bonding coat is applied by the gun nozzle which feeds into the rotating cylinder. Low alloy steel is applied at Station 5 and cylinder cools at Station 6. Cylinder walls are finished by honing.

### New engineering data bulletin

Bulletin 136B—The METCO Flame Spraying Processes, provides basic engineering and application data on flame sprayed coatings of metals, ceramics, carbides and other high melting point materials. 16 pages. Send coupon for free copy.


**METCO INC.**

FORMERLY METALLIZING ENGINEERING CO., INC.

*Flame Spray Equipment and Supplies*

1187 Prospect Ave., Westbury, Long Island, N.Y.

Telephone: Edgewood 4-1300 Cable: METCO

In Great Britain: METCO. ,Ltd.
Chobham-near-Woking, England

Don Watson

**Please send Bulletin 136B.**

name title

company

address

city zone state

**For more information, turn to Reader Service card, circle No. 505**

# All that 'Quality' and 'Service' imply are yours with:




**OROTHERM HT**
Heat resistant 24Kt Acid Bright Gold, extremely low porosity, hard and ductile

**OROSENE 999**
24Kt Acid Bright Gold, tight grain, superior throwing and leveling power

**HG BRIGHT GOLD**
23+Kt Low Stress, Hard and Bright operates at room temperature, without free cyanide

**INDUSTRIAL 24Kt GOLD**
Ultra Pure Aqueous Potassium Gold Cyanide for soft stressless pure gold electroplates

**RHODIUM SULPHATE T. P.**
For High Purity, Low Stress fine grain Rhodium electroplating

Information on these products, or on any problem involving the electrodeposition of precious metals, are available without obligation. Write, phone, wire or TWX.

**RHENIUM-T**
Available for experimental plating

**INDIUM GOLD**
For semi-conductor plating

**ANTIMONY GOLD**
For semi-conductor plating

**GALLIUM GOLD**
For semi-conductor plating

**PROTECTOX**
Provides anti-tarnish protection for gold, silver, and copper

**TECH TIN**
Immersion Tinning at room temperature

**TECHOSOL 25**
Anionic detergent for free rinsing and cleaning

**ELECTROPLATING EQUIPMENT**
Custom engineered for all types of precious metal plating

**POTASSIUM GOLD CYANIDE**
Quality controlled and custom packaged to suit your requirements

**PLATINUM N**
A Superior Platinum concentrate for better plating

**PALLADIUM R. T.**
A highly efficient soluble Palladium for plating at room temperature

**SPECIAL PRECIOUS METAL ALLOYS**
Our research department welcomes inquiries on unusual combinations of precious metals

PRODUCTS OF RESEARCH

**Technic inc** ST 1-6100

P.O. BOX 965 PROVIDENCE 1 R.I. 7001 NO. CLARK ST. CHICAGO 26 ILL.

For more information, turn to Reader Service card, circle No. 562

# LASTING Eye Appeal
# PLEXTONE®

## multicolored textured finish for imaginative designers





In little more than a decade, Plextone has become an accepted industrial finish. Continuous research has resulted in new colors, new design effects, greater durability, wider application. Today, this textured, multicolored industrial finish has reduced costs up to 35 percent. Its one-coat application of two or more interlaced colors is sprayed at **one** time, from **one** gun! Shown above is just one of many pre-mixed Plextone colors available for prompt shipment.

For complete data and 1960 color card, mail the coupon today.

*Leadership in finishes since 1876*

**MAAS & WALDSTEIN CO.**

**2114 McCARTER HIGHWAY, NEWARK 4, N. J.**

Midwest Division: 1658 Carroll Avenue, Chicago 12, Ill.
Pacific Coast Division: SMITH-DAVIS CO., 10751 Venice Blvd., Los Angeles 34, Calif.

Maas & Waldstein Co.
2112 McCarter Highway, Newark 4, N. J.
Please rush color chips & complete data on new PLEXTONE.

Name_____

Title_____

Company_____

Street_____

City_____

For more information, turn to Reader Service card, circle No. 440

# NEW REINHOLD BOOKS FOR DESIGN ENGINEERS

*Emphasizes progress made in the industrial use of glass . . .*

## 1 GLASS
### Its Industrial Applications

by CHARLES J. PHILLIPS, *School of Ceramics, Rutgers, The State University*
**1960, 240 pages, $6.95**

COVERS THE MANUFACTURE, physical and chemical properties, and the industrial applications of all types of glass. It is directed to the users—engineers, scientists, production and purchasing personnel—who are involved in the design, specification, testing, purchase or sale of glass products. The book reflects all the recent advances in the field and includes new information on such subjects as glass bead reflectorization and the "float glass" process for making flat glass. The order of topics has been arranged for maximum continuity so that each topic is preceded by everything needed to understand it. Here is a thorough, semi-technical approach to the subject which provides an up-to-date treatment of all phases of the manufacture and use of glass.




*Covers metals, plastics, rubber, paints and cements . . .*

## 2 MATERIALS SELECTION FOR PROCESS PLANTS

by RUSSELL E. GACKENBACH, *Materials Engineer, Engineering and Construction Division, American Cyanamid Company*
**1960, 319 pages, $8.50**

THIS PRACTICAL HANDBOOK goes directly to the problem of material selection as encountered by the engineering, maintenance and production personnel of process plants. The book contains all necessary data on metals, plastics, rubbers, paints and cements. The author discusses corrosion-resisting qualities along with the mechanical properties and fabricating characteristics that must be considered in selecting the most suitable and most economical material for a particular purpose. The information contained in the book is presented in non-technical terms to be of the greatest use to that large group responsible for obtaining longer production runs, increased down time, and decreased maintenance and engineering costs.

*The first volume in the new Reinhold Space Technology Series . . .*

## 3 FUNDAMENTALS OF ROCKET PROPULSION

by ROBERT E. WIECH, JR. and ROBERT F. STRAUSS, *Thiokol Chemical Corporation, Reaction Motor Division*
**1960, 145 pages, $5.50**

PROVIDES an all-inclusive review of the rocket engine—its history, fundamentals of operation, design of components and methods of application. The material contained in the book is neither overly technical nor trivial in its presentation and scope. Chapters advance one step at a time through the basic laws governing rocket engine design; the need for and probable design of future engines; and the rocket engine's job in space flight and satellite missions. The authors fully describe all rocket engine types so that the function and operation of each is clearly understood. All basic rocket formulas derive from algebra, rather than the more difficult calculus. Here is an ideal reference for guidance and electronics engineers, propellant chemists, chemical and mechanical engineers, metallurgists, students, or anyone remotely connected with or interested in rocket propulsion and its future.




*A complete working manual of procedure . . .*

## 4 ORGANIZING THE TECHNICAL CONFERENCE

by HERBERT S. KINDLER, *Director of Technical and Educational Services Instrument Society of America*
**1960, 160 pages, $6.00**

THIS IS MORE than a book about holding technical conferences; it is a working manual that clearly charts the duties and activities of the organizing committee. It answers completely the questions of when to initiate, and how to plan, organize and conduct effective technical conferences, whether large or small. All facets of programming, promoting, documenting, administering and evaluating professional meetings of all kinds (symposia, workshops, seminars, lectures, clinics and exhibits) are explained. The book also analyzes and interprets key factors that contribute to a successful conference. The author removes the burden of confusion from both the inexperienced and experienced conference organizer from beginning to end. Here is invaluable information for any group or organization that wants more effective conference communications.

*Illustrates and describes approximately 1,000 relays of all types . . .*

## 5 THE RELAY GUIDE

by RAYMOND N. AUGER, *Technical Editor, Automatic Control*
**1960, 350 pages, $10.00**

A BOON TO ENGINEERS, this complete reference includes virtually all published data on hundreds of available models of relays from approximately 200 manufacturers. Now it is possible to find the ideal relay for any particular requirement in one convenient source. A huge undertaking, the guide contains 23 chapters of relay illustrations and descriptions according to relay type and includes data from the literature of every American manufacturer of relays. It presents application data, relay circuits, arc suppression information, relay definitions and terms in addition to relay descriptions. Custom-made relays for which no specific description is available are covered in a separate section. Here are almost 1,000 relays pictured and described in a single reference to save time and frustration in the selection process.

*The definitive work on a great originator . . .*

## 6 THE DYMAXION WORLD OF BUCKMINSTER FULLER

by ROBERT MARKS
**1960, 232 pages, over 350 photographs and drawings, $12.00**

Here is a thorough presentation of the life and work of one of the most original and controversial men of our time. Included are all the provocative Dymaxion projects—car, house, deployment units and transports, as well as Fuller's most recent work on Geodesic domes and space frames. The book also reveals the principles behind all these highly original design concepts. In addition, the fascinating pattern of thinking which evolved a system of geometry—Energetic and Synergetic—and a new system of map-making, is brilliantly analyzed. Throughout the book is splendidly illustrated with photographs and drawings that graphically depict the plans and structures, the today and tomorrow of Mr. Fuller's Dymaxion world.

**Free Examination Order Coupon**

**Reinhold Publishing Corporation**
**Dept. M-698, 430 Park Avenue**
**New York 22, N. Y.**

Send me the book(s) I have encircled below for 10 days' FREE EXAMINATION.

**1 2 3 4 5 6**

☐ Purchase price enclosed (Reinhold pays shipping costs)
☐ Bill me ☐ Bill company

Name .....

Address .....

City & Zone ..... State .....

SAVE MONEY! You save shipping charges by enclosing payment with order. Same return privilege. Please include 3% sales tax on N.Y.C. orders. DO NOT ENCLOSE CASH!

# KANIGEN®

*The proved nickel alloy chemical plating—available only from General American and its licensees*

KANIGEN is a chemically and metallurgically unique process for applying a hard, corrosion and abrasion resistant surface to most metals. KANIGEN is being used successfully for coating almost everything of any size—from the inside of a tank car to a tiny surgical needle—providing extreme uniformity of coating thickness even on complex shapes. Rack, jig or barrel plating may be used with KANIGEN.

You can rely on General American's integrity and experience and profit from its extensive research and development facilities. KANIGEN, of course, is patented to protect you from imitations.

KANIGEN is a trademark which identifies chemical nickel coating by General American Transportation Corporation and its licensees, the product resulting therefrom and compositions produced by them for use in chemical nickel coating.

KANIGEN is available from General American at East Chicago, Indiana; Sharon, Pennsylvania, and Compton, California, and from licensees in many cities. For further information, call or write.

## PHYSICAL PROPERTIES

Specific gravity ..... 7.9
Melting point ..... 1635 °F
Electrical resistivity
approximately 60 micro-ohms/cm/cm²
Coefficient of expansion
13 x $10^{-6}$ cm/cm per °C or
7.22 x $10^{-6}$ in/in per °F
Thermal conductivity
approximately 0.0105 to
0.0135 cal/cm sec °C (calculated)
Hardness
as plated—49 Rockwell C
heat treatable to 70 Rockwell C

---

World's largest production facilities for chemical nickel alloy plating on
Iron
Copper
Aluminum
Titanium
Beryllium
and their alloys

Pilot plant facilities are available for nickel alloy chemical plating on magnesium, uranium and non-metallics including thermosetting plastics, glass, ceramics.

*Kanigen Division*

**GENERAL AMERICAN TRANSPORTATION CORPORATION**

*135 South LaSalle Street • Chicago 3, Illinois*

KANIGEN GENERAL AMERICAN TRADE MARK

For more information, turn to Reader Service card, circle No. 420

# FROM MISSILES AND ROCKETS




## Precious Metals Plating Processes to meet your every requirement

The newest rockets, guided missiles, earth and sun satellites have a SEL-REX PRECIOUS METAL ELECTROPLATE on their electronic equipment and circuitry. The same quality and precision demanded by such applications is also being provided to leading jewelry manufacturers to help them make better, more salable products —at lower cost.

Whether you make missiles and rockets or provide lockets for misses, there's an *exclusive* SEL-REX PRECIOUS METALS PLATING PROCESS to meet your particular needs.

***SEL-REX BRIGHT GOLD** – the standard of the industry – twice as hard as ordinary 24K Gold Plate–mirror-bright in any thickness, directly from the bath.

***AUTRONEX® ACID GOLD**–for the exacting industrial application–mildly acid electrolyte–*absolutely no free cyanide* –plates at room temperature.

***DOPED GOLD PROCESSES**–doped with antimony or indium, depending on desired characteristics–best for Silicon and Germanium semiconductor applications.

***TEMPEREX®**–Produces pure 24K Gold electroplate which will withstand higher temperatures than any pure Gold plate known.

***THERMOKARAT®**–Produces exceedingly hard (470 Vickers) 18K Gold electroplate for decorative or industrial applications.

***RHODEX®** – a patented Rhodium plating process which yields compressively stressed, crack-free deposits, permitting thicker Rhodium electroplate than ever before possible.

***PLATANEX® L/S**–low stress Platinum plating process produces essentially nonporous electroplate for high temperature and other exacting industrial applications–no intermediate scratch brushing or burnishing required.

***KARATCLAD® GOLD PROCESSES** – acid Gold processes for decorative applications–Jeweler's Finish in any thickness, in a wide range of non-varying colors.

**BRIGHT RHODIUM PROCESS**–yields brilliant, fine grained, non-tarnishing deposits. Manufactured in our own air conditioned laboratories, its purity assures consistent quality results for all decorative applications.

***SILVREX® BRIGHT SILVER**–mirror-bright deposits in any thickness, operates at room temperature in current densities from 10 to 40 asf–hard and ductile deposits.

**SILVER SOL-U-SALT®**–a water soluble double cyanide salt –permits new ease and facility in the preparation of Potassium Silver Cyanide plating solutions.

**POTASSIUM GOLD CYANIDE**–the purest available–used in the preparation of our own exclusive Gold Plating Processes –manufactured in moisture controlled facilities.

**INDUSTRIAL SILVER PLATING PROCESSES**–a complete line of silver plating formulations for high speed industrial applications.


*Patented and patents pending.

Sel-Rex®

**SEL-REX CORPORATION**
**NUTLEY 10, NEW JERSEY**

World's largest selling precious metal electroplating processes and systems

For more information, turn to Reader Service card, circle No. 476




# New finish combination . . . pattern plus M&T Spray-on Vinyl protection

NOW YOU CAN SPRAY A VINYL COATING onto metal and produce a leather-like texture, or reproduce an existing metallic pattern in finest detail . . . thanks to new organosols developed by M&T. Equally important, your product gets all the heavy-duty protection that a *thick-film* vinyl finish provides against wear and corrosion.

You can choose your own color; in fact, you can *change* colors any time without obsoleting a large inventory of coated metal, as with laminates. Spraying permits application after fabricating operations, so scrap loss, seams and raw edges are eliminated. Typical use: trim or overall finish on washers, dryers and other appliances.

M&T Spray-on Vinyls are up to ten times more abrasion-resistant than ordinary textured enamels. They are inert to caustics, acids, alcohols, oxidation, water, salt; unaffected by grease, perspiration, inks; immune to marring, chipping, peeling. Write for more information.

M&T **coatings and finishes**
METAL & THERMIT CORPORATION
General Offices: Rahway, New Jersey

For more information, turn to Reader Service card, circle No. 542

# FREE DATA FILES

*on the complete*


*Allied Research*

## Line for Metal Finishing

### PROCESSES AND PRODUCTS FOR CORROSION PROTECTION, PAINT BASE, DECORATIVE FINISHING

A complete line including IRIDITE Chromate Conversion Coatings for non-ferrous metals, IRILAC Clear Protective Coatings for all metals, ISOBRITE Chemically Different Plating Brighteners and ARP Process Chemicals.

*If one of our present products does not meet your needs, we'll be glad to work with you to find an answer to your problem.*



### EQUIPMENT AND COMPLETE FINISHING SYSTEMS

Includes information on WAGNER Silicon and Selenium Rectifiers, WAGNER Auto-Loaders for transfer of racks and parts from conveyors to plating machines or between conveyors, Automatic and Semi-Automatic Plating Machines, Barrels, Tanks and other equipment.

*Also includes information on Process Engineering Service—complete plant design, specification and installation.*



### CHEMICALS AND SUPPLIES

Price and delivery information on a wide variety of plating room necessities, including ROLL-TOP Zinc anodes, FLAT-TOP copper anodes, ELECTROCOP Flat Copper anodes, Cadmium and Tin Anodes, Acid Replacements, Buffs, Chemicals, Cleaners and Maintenance Materials.




### NICKEL RECASTING SERVICE

Ask about our Subscription Plan which combines your new nickel purchases with a service to recast your butts and spears, resulting in substantial savings.

***WRITE DIRECT . . .*** **for your copies of these FREE DATA FILES, or contact your Allied Field Engineer. He's listed in the yellow pages under "Plating Supplies".**

*Allied Research Products, Inc.*

4004-06 EAST MONUMENT STREET • BALTIMORE 5, MARYLAND

BRANCH PLANT: 400 MIDLAND AVENUE • DETROIT 3, MICHIGAN

West Coast Licensee for Process Chemicals: I. H. Butcher Co.

European Agent: Stora Grusbergar, Storgatan 10, Stockholm, Sweden

*Chemical and Electrochemical Processes, Anodes, Rectifiers, Equipment and Supplies for Metal Finishing*


IRIDITE® Chromates | IRILAC® Coatings | ISOBRITE® Brighteners | ARP® Supplies | WAGNER Equipment

For more information, turn to Reader Service card, circle No. 379



## *Notes on* VACUUM-DEPOSITED COATINGS

***Front-surface mirrors coated with aluminum give perfect reflection without double images***




**Front-surface mirrors** recommended for optical, commercial and scientific uses are among the vacuum-deposited coating products supplied by Liberty Mirror.

**These front-surface mirrors** give a perfect single reflection. Back-surface mirrors may reflect a second image from the front surface of the glass. The reflective aluminum deposit is coated with hard quartz to increase durability.

**Applied to glass,** metal or plastic, vacuum-deposited coatings are used in such varied applications as toys, cameras, pin setters, wheel-alignment equipment, aircraft or missiles.

***Transparent phosphor coating illuminates with extreme resolution***




**Liberty Mirror's** evaporated coating technique gives this phosphor coating excellent resolution capabilities for use in electronic projection applications. The coating has a light output of 15 foot lamberts or greater, at a power dissipation level of 25 milliwatts with peak output using a screen voltage up to 15 kv.

**For assistance** in solving application problems, write Liberty Mirror Div., Libbey-Owens-Ford Glass Company, 811 Madison Ave., Toledo 1, Ohio.

For more information, circle No. 439

# PRESSURE SENSITIVE MIRRO-BRITE "MYLAR"*

made with

makes a dramatic difference on every product!



**PEEL OFF BACKING—ADHERE**

AVAILABLE IN—

- CHROME
- GOLD
- COPPER

• with or without PRESSURE SENSITIVE BACKING

There's nothing quite like Mirro-Brite Mylar to give every product added eye-appeal at modest cost. It can be used in die-cut panels, decorative strips, grillwork and a countless number of other ways, limited only by your imagination!

Select your pattern from any of 26 embossed designs in six metallic colors with or without pressure sensitive adhesive backing. Available in continuous rolls, cut-to-size sheets, die-cuts, or in widths as narrow as one-half inch. Wide variety of laminations, gauges and special effects. Check with our design engineering department for assistance in selection and application to meet individual requirements. No cost or obligation.

Write for free brochure and price list

**"PIONEERS IN METALIZED MATERIALS"**

Maker of Monsanto Ultron Vinyl Film

*A DuPont Polyster film

## COATING PRODUCTS, INC.

DEPT. PW-1 101 WEST FOREST AVE. ENGLEWOOD, N.J.
NEW JERSEY: LOwell 8-0610 NEW YORK: Wisconsin 7-4435

ALSO MIRRO-BRITE ACETATE, POLYSTYRENE, BUTYRATE AND VINYL

For more information, turn to Reader Service card, circle No. 520

# Flame spray refractory coatings at high speed—low cost

**Alumina—zirconia—tungsten carbide—for protection against high temperatures—blast abrasion.**



Rocket nose cone of metallic tungsten, flame sprayed on salt-covered mandrel. Salt is leached out with water to free finished part.





METCO Type 2P ThermoSpray Gun flame sprays a wide range of material in powder form, including tungsten carbide. Plasma Flame spray equipment also available.

METCO Type KD Machine flame sprays alumina and zirconia in rod form; provides highest application speeds for guns of this type—over 90% deposit efficiency.

METCO offers a complete range of flame spraying equipment for applying coatings of refractories and other high melting-point materials. Automatic electronic controls provide push-button operation for high-speed production, maximum deposit efficiencies.

**METCO Bulletin 136B provides basic engineering and application data on flame sprayed coatings of metals, ceramics, carbides and other high melting-point materials. Send off the coupon or write.**

METCO®

**METCO INC.**
FORMERLY METALLIZING ENGINEERING CO., INC.
*Flame Spray Equipment and Supplies*
1187 Prospect Ave., Westbury, L.I., N.Y. Telephone: Edgewood 4-1300 Cable: METCO
In Great Britain: METCO., Ltd., Chobham-near-Woking, England

Please send Engineering Data Bulletin on the METCO Flame Spray Processes.

name _____ title _____

company _____

address _____

city _____ zone _____ state _____

For more information, turn to Reader Service card, circle No. 504

# Luster-on®

**ECONOMICAL PROTECTIVE COATINGS FOR BRASS, ZINC, CADMIUM, COPPER, ALUMINUM**

The Chemical Corporation offers a complete line of uniform-controlled chromate conversion coatings that provide maximum protection in one, low-cost, simple operation. Available for immediate delivery as liquid or powder.

*Always Specify Luster-on —*

**FOR BRILLIANT CORROSION-RESISTANT FINISHES . . .** rivaling chrome for many applications where cost is a factor. Long-lasting, easily controlled application.

**FOR CLEAR, BRIGHT and IRIDESCENT COATINGS . . .** gives striking, attractive appearance with complete corrosion-protection . . . even when humidity and handling are involved during processing. Also yellow iridescent and olive drab for concealed parts or as a paint bond.

**FOR DECORATIVE COLOR . . .** on low-cost zinc. Brilliant golds, yellows, blues, greens, violets, reds, brass and copper hues.

**FOR ALUMINUM . . .** where surface hardness is not of prime importance. Excellent finish for paint bonding.

**FOR LASTING BRIGHTNESS . . .** on both copper and brass without noxious fuming.

**FOR DIE-CASTINGS . . .** one quick dip provides uniform finish, ideal as a base for painting.

We'd like to show you what Luster-on can offer you! Send in sample part today for free processing. Data sheets on request.

**Luster-on . . . the first and still the finest in conversion coatings.**


The Chemical Corporation
67 Waltham Ave., Springfield 9, Mass.

For more information, circle No. 555

*For economical under-paint protection*

# ask Oakite

OVER 50 YEARS CLEANING EXPERIENCE • OVER 250 FIELD SERVICE MEN • OVER 160 MATERIALS




These two panels were identically painted, scored with an "X", and exposed to salt spray test for 480 hours. The difference: the one on the right was first treated with an Oakite CRYSCOAT iron phosphate conversion coating.

This painted tubing was CrysCoated. Repeated punching did not break paint grip despite severe abuse and deformation.

## Oakite CRYSCOAT iron phosphate coatings cut the cost of corrosion-protection

You get proper protection *plus* economy with CrysCoat iron phosphate coatings.

First of all, they lock paint to steel, giving a superior paint grip under bending stresses. Bend tests show less chipping and flaking of paint. And note how paint held tight even at punched holes in the sample above.

Secondly, they keep corrosion from spreading at every scratch, as the panels above show so graphically.

But most important, they save money. Because CRYSCOAT iron phosphate processes *clean* as they phosphate. Because you need only a three-stage washer. Because *no* acid-proof equipment is required. You save both on equipment and production time. In addition, the smoother iron phosphate coatings soak up less paint than coarser phosphate coatings . . . giving you a sleek finish with one less coat.

It will pay you to *ask Oakite* about phosphating. You'll find the right one for *your* requirements in the complete CrysCoat line which includes both zinc and iron phosphate processes, for spray or tank, for room or elevated temperature operations. Meanwhile, write for Bulletin F-9475. Oakite Products, Inc., 32H Rector Street, New York 6, N. Y.

*it PAYS to ask Oakite*

OAKITE

over 50 Est. 1909 SCIENCE years' leadership in industrial cleaning

For more information, turn to Reader Service card, circle No. 547



*Engineered Ultrasonics simplifies tough cleaning jobs for Lycoming*

This 2-KW **Sonogen**® ultrasonic-cleaning installation was designed in collaboration with the Lycoming Division of Avco to handle the toughest jobs in the shop. Planned originally for close-tolerance gas-turbine parts whose complex geometry and heavy scale handicapped old-fashioned cleaning methods, it now works three shifts on air diffusers (photo) and other difficult parts pre-selected for efficient **Sonogen**® cleaning. Repeated cycling in conventional cleaning baths failed to remove all scale, oxide and soil; now the fast, efficient scrubbing action of **Sonogen**® cleans every surface thoroughly without re-cycling / Your problem may be different from Lycoming's, but the solution is probably the same — a **Sonogen**® ultrasonic-cleaning system engineered for your needs. Write today, giving us full details.

Since 1946 The Respected Name in Ultrasonics

**Branson**

**ULTRASONIC CORPORATION**

17 BROWN HOUSE ROAD, STAMFORD, CONN.


For more information, turn to Reader Service card, circle No. 552

get your own *SELECTOR* the easy way . . .

For only $3.00 you can get your own copy of M/DE's annual reference issue—the 1961 MATERIALS SELECTOR—plus 12 monthly issues of MATERIALS in Design Engineering.

You can see right now that M/DE's annual reference issue, the MATERIALS SELECTOR, is packed with the kind of reference data that makes selecting and specifying the right engineering materials, parts or finishes an easier, more efficient task for you. Remember, too, once you become a subscriber to M/DE you'll receive—every month—fast-reading, factual reports on important innovations and developments in metals, nonmetals, forms and finishes.

If you do not subscribe to MATERIALS in Design Engineering and want your own personal copy of the MATERIALS SELECTOR . . . fill in and mail the handy order card on page 583. We'll mail the MATERIALS SELECTOR to you, plus 12 monthly issues of MATERIALS in Design Engineering.



keep your eye on the "Ball" and step up inspection speeds

*with Branson Sonoray and Sonogate Ultrasonic Flaw-Detection Equipment*

SONORAY puts *all* ultrasonic pulse inspection techniques at your command, with the highest sensitivity and resolving power, smallest size and heft, of any instrument of its type . . .

SONOGATE puts the findings at your fingertips with instant visual warning of any flaw larger than a preselected critical size, so you observe the screen only when alerted by the signal on the transducer.

SONOGATE *Flaw Alarm, Model A, plugs into the instrument housing and provides three outputs: 1, 6.3V DC for red lights on the panel and on an extension cord for use on the transducer; 2, 5V DC off/on to actuate an aural alarm, flaw-marking device, or on/off recorder; and 3, a relay to control outside power.*

*Other more versatile* SONOGATES *will be described in subsequent announcements in this journal. For the full story on the* SONORAY *and its useful accessories, write for Bulletin T-200.*

*Since 1946 — The Respected Name in Ultrasonics*

**Branson INSTRUMENTS, INC.**

17 BROWN HOUSE ROAD • STAMFORD • CONNECTICUT

For more information, turn to Reader Service card, circle No. 521

**STEERE FLO-MOLDS**

**VINYL GRIPS and HANDLES at MINIMUM COST**





The Steere FLO-MOLD method makes possible beautiful finishes and even multi-color designs with low tooling costs. FLO-MOLDING is a dipping process for plastic-coating practically any shape metal part. Such articles as grips and handles can be dipped on an inexpensive form, or directly onto the part to be coated. In the latter method, the coating covers flaws, rivets and imperfections, eliminating the cost of prior finishing. Because no mold is used, there are no flash or mold marks to mar the finish.

FLO-MOLD plastic coatings are durable, corrosion and abrasion resistant and have excellent aging properties.

For complete details on a wide range of FLO-MOLD applications, write for brochure.

steere enterprises, inc.

422-424 SOUTH BROADWAY AKRON 8, OHIO

2316

For more information, turn to Reader Service card, circle No. 479


*Dampen Vibration... Silence Noises...*

ADD BEAUTY, COLOR, SALES APPEAL




WITH *Cellusuede Flock*

THE PRODUCT FINISH WITH 1000 USES













Every day product designers, industrial finish and material engineers are finding new, profitable uses for Cellusuede Flock — industry's most versatile product coating. With these cotton, rayon or acetate fibers, you can add new beauty, color, and sales appeal to your product, provide a durable protective finish, silence noises, or dampen vibration. Best of all, the soft velvet-like Cellusuede finish is easy to apply to wood, metal, plastic, fabrics, leather, cardboard, or paper surfaces, either on a modified or production line basis. It's inexpensive, more durable than fabric, and readily available in a wide range of textures and beautiful colors. Investigate today the profit possibility of using Cellusuede for your product.

*FREE BULLETIN — SAMPLES, TECHNICAL SERVICE •*

Write for 12-page bulletin illustrating profitable uses and applications. For help with a specific job, Cellusuede's technical service and unexcelled facilities are available for producing samples to meet your needs.



CELLUSUEDE PRODUCTS, INC.
Producers of Natural and Synthetic Flock

511 N. MADISON STREET • ROCKFORD, ILL.

For more information, turn to Reader Service card, circle No. 492

# SUPPLIERS' LITERATURE

## Forms, Shapes and Composites

**Molded Rubber Products.** Acushnet Process Co., 34 pp, illus. Design data, characteristics and uses of compression and transfer molded synthetic and natural rubber seals, diaphragms, o-rings and other products. **180**

**Aluminum Publications.** Aluminum Co. of America, 30 pp. Index to available literature on aluminum lists, with brief descriptions, items of interest to engineers, metallurgists, and metal users. Some of the subjects covered are aluminum alloys; design data; castings; forgings; fasteners; powders; wire, rod and strip; and uses of aluminum in the aircraft, appliance, automotive, electrical, processing, and heavy machinery industries. **181**

**Ductile Iron Parts.** American Cast Iron Pipe Co., Special Products Div., 36 pp, illus. Grades, dimensions, weights, uses and specifications for ductile iron piping, rolls and other parts. **182**

**Shaped Steel Wire.** Page Steel & Wire Div., American Chain & Cable Co., Inc., 16 pp, illus. Sizes, tempers and finishes of square, rectangular, round, oval, hexagonal and octagonal wire made of low and high carbon steels, iron and stainless steels. **183**

**Metal Powders.** Metals Disintegrating Co., Div. of American Marietta Co., illus. Description, specifications, properties and uses for all types of metal powders. **184**

**Bearing Bronze.** American Smelting & Refining Co., Continuous Cast Dept., 6 pp, illus., No. 301. Stock sizes and weights of solid and hollow continuous-cast bronze bars ½ to 9 in. in dia. **185**

**Wire Parts, Small Stampings.** Art Wire & Stamping Co., 4 pp, illus. Shows a variety of wire parts and small metal stampings in both ferrous and nonferrous metals. **186**

**Nonferrous Castings.** Atlantic Casting and Engineering Corp., 12 pp, illus. Uses, chemical composition, ASTM and Federal specifications, and physical and mechanical properties of brass, bronze and aluminum castings. **187**

**Rubber, Plastics O-Rings.** Auburn Mfg. Co., 20 pp, illus. Design data, properties and sizes of o-rings made of natural and synthetic rubber and plastics. **188**

**Magnesium Products.** Brooks & Perkins, Inc., 8 pp, illus. Shows the fabrication, assembly and finishing of magnesium tail cones for aircraft, teleprinter covers, gun turret enclosures and radar plotting equipment. Information also on other magnesium products. **189**

**Butyrate Pipe.** Busada Mfg. Corp., 4 pp, illus. Uses, general characteristics, prices and sizes of butyrate pipe and fittings. **190**

**Expanded Strip-Tubing.** Calumet & Hecla, Inc., Wolverine Tube Div., 8 pp, illus., No. 80. Advantages, alloys used, method of fabrication, sizes, and other data on seamless light-wall tube produced in strip form, rolled up for compact shipment, and then expanded into tubular form. **191**

**Steel Forgings.** Cameron Iron Works, Inc., Special Products Div., 44 pp, illus. Dimensions and weights of various shapes and forms forged of stainless and alloy steel. Shows how forgings are made. **192**

**Rubber Compounding and Molding.** Colonial Rubber Co., 16 pp, illus., No. C-60. General information on services and facilities available for producing rubber compounds and rubber moldings for a wide variety of uses. **193**

**Plastics and Rubber Extrusions.** Conneaut Rubber & Plastics Co., 4 pp, illus., No. CR-57. Information on compounding and production facilities available for the production of plastics and rubber extrusions. **194**

**Plastics Extrusions.** Crane Plastics, Inc., 8 pp, illus. Information on services and facilities available for the production of plastics extrusions. Included are a list of extrudable materials and products, and brief descriptions of several custom engineered plastics extrusions. **195**

**Reinforced TFE.** Dixon Corp., Plastics Div., 2 pp. Electrical, physical, mechanical and chemical properties of reinforced TFE. **196**

**High Alloy Castings.** Dodge Steel Co., 4 pp. Chart lists standard Alloy Casting Institute designations and chemical composition ranges of heat and corrosion resistant high alloy castings. **197**

**Fabricating Magnesium.** Dow Chemical Co., Dow Metal Products Co. Div., 8 pp, illus., No. 141-201-59. Information on machining (milling, drilling, sawing, etc.), forming (deep drawing, stretch forming, spinning, extruding, etc.), and welding (consumable electrode, spot, seam, etc.) magnesium and its alloys. **198**

**Metallic, Nonmetallic Forms.** Dumont Corp., 28 pp, illus. Information on honeycomb sandwich structures, metal-to-metal bonded parts, high temperature molded plastics, special purpose fiberglass laminates and hand lay-up custom moldings. **199**

**High Alloy Castings.** Duraloy Co., 20 pp, illus., No. G-159. Physical properties of corrosion resistant, heat resistant and abrasion resistant high alloys for static, centrifugal and shell molded castings. **200**

**Permanent Mold Castings.** Eaton Mfg. Co., Foundry Div., 18 pp, illus. Describes permanent mold process for producing gray iron castings. **201**

**Aluminum Castings.** Exalco Mfg. Co., 4 pp, illus. Information on standard and custom-made aluminum permanent mold castings. **202**

**Metallic, Nonmetallic Stampings.** Federal Tool & Mfg. Co., 6 pp, illus., No. 301. Design information, tolerances and specifications for stampings made of ferrous and nonferrous metals, and phenolic, nylon and epoxy resins. **203**

**Reinforced Plastics.** Firmaline Products of Crompton & Knowles, 4 pp, illus. Advantages, properties, typical applications and molding techniques for a line of reinforced plastics premix molding compounds. **204**

**Molded Plastics.** Plastics Div., General American Transportation Corp., 16 pp, illus. Information on the advantages and characteristics of molded plastics. Included is a description of services and facilities available for compression and injection molding, reinforced plastics molding, extrusion, and vacuum forming. **205**

**Aluminum Extrusions.** General Extrusions, Inc., 6 pp, illus. Properties, uses, surface finishes, lengths and tolerances of aluminum extrusions. **206**

**Steel Tubing.** General Motors Corp., Rochester Products Div., 12 pp, illus., No. 271. Typical applications of steel tubing made in both single and double walls. **207**

**Electrical Contact Materials.** Gibson Electric Co., 4 pp, illus., No. 601. Properties, available forms and uses of silver, palladium-nickel, silver-graphite and silver-tungsten electrical contact materials. **208**

**Nonferrous Metal Powders.** Glidden Co., Chemical Divs., Metals Dept., 6 pp. Information on lead and Resistox copper powders. **209**

**Metal Powder Parts.** Supermet Div., Globe Industries Inc., 4 pp, illus. Properties, advantages, types of parts, machinability, processes used, and other information on iron powder parts. **210**

**Ceramic Parts.** Globe-Union, Inc., Centralab Electronics Div., 4 pp, illus., No. 42-874. Reference folder contains 3 useful tables: temperature conversion from Centigrade to Fahrenheit, decimal equivalents of fractions, and mechanical and electrical properties of high alumina and steatite ceramics. Also included is a list of design considerations for ceramic products. **211**

**Rubber Parts.** Goshen Rubber Co., 8 pp, illus. Describes facilities for

*more literature on p 418*

*To get literature, use free post cards on pp 585-592*

# Forms, Shapes and Composites


PAGE

366 Design Features of Metal Forms
368 Castings
372 Extrusions
374 Impact Extrusions
375 Fabricated Sheet Metal Parts
380 Patterned Sheet
381 Forgings
384 Metal Powder Parts
386 Screw Machine Parts
387 Spinnings
388 Mechanical Tubing
392 Wire Parts, Forms and Assemblies
393 Plastics Parts
398 Rubber Parts
401 Composite Materials
408 Advertisements
364 Suppliers' Literature

## Design Features of Metal Forms

| Form ↓ | Choice of Materials | Complexity of Part | Maximum Size | Minimum Size | |
|---|---|---|---|---|---|
| Sand Castings | Wide—ferrous and nonferrous metals | Considerable—holes, bosses, locating pads | Great—largest forms made are sand castings | ⅛ in. is smallest practicable section | |
| Shell Mold Castings | Wide—same as above excepting low carbon steels | Moderate—limited by mold removal problem | <60 in. square. Best for smaller parts | 1/16-in. sections | |
| Permanent Mold Castings | Restricted—brass, bronze, aluminum | Limited—restricted by use of rigid molds | Moderate—50 lb is practical limit in aluminum | 1-oz. sections as thin as 0.1 in. | |
| Plaster Mold Castings | Narrow—brass, bronze, aluminum | Considerable—mold destroyed in removal | Moderate—up to 15 lb in most materials | Small—1/32-in.sections possible | |
| Investment Castings | Wide—includes materials hard to forge or machine | Considerable—very few limitations | Moderate—best for parts under 2 lb | Small—sections down to 0.030 in. | |
| Die Castings | Narrow—zinc, aluminum, brass, magnesium | Considerable—though costly dies might be required | Large—up to 75 lb in aluminum, 200 lb in zinc | Sections as small as 0.025 in. | |
| Drop Forgings | Medium—many ferrous, nonferrous alloys | Moderate—limited by die restrictions | Large | Small as fraction of an ounce | |
| Press Forgings | Medium—best for nonferrous alloys | Limited—but greater than drop forgings | Large—300-400 lb a practical maximum | Smaller than drop forgings | |
| Upset Forgings | Medium—many ferrous, nonferrous alloys | Limited to cylindrical shapes | Medium—9-in. bar about largest | Moderate—not comparable to casting | |
| Cold Headed Parts | Narrow—confined to steel, highly ductile alloys | Limited—less flexibility than forgings | Small—7 in. by ½ in. dia usual maximum | Small—⅛-in. dia parts can be made | |
| Continuous Cast Parts | Narrow—bronze, nickel bronze | Limited—can be complex in cross section only | Moderate—9 in. max dia | Moderate—5/32 in. for sections | |
| Extrusions | Medium—light metals, steels, copper, titanium, nickel alloys | Limited—can be complex in cross section only | Medium—8 to 21 in. max dia | Small—0.050-in. sections in aluminum and magnesium | |
| Impact Extrusions | Narrow—aluminum, magnesium, some steel | Limited—must be concentric | Small—6 in. dia in soft alloy, 4 in. in hard | Moderate—¾ in. dia smallest | |
| Roll Formed Shapes | Narrow—cold rolled steel, some aluminum | Restricted to thin and uniform cross sections | Large | Sections from 0.125 in. up | |
| Stamped and Press Formed Parts | Wide—all workable metals | Moderate—some design restrictions | Large | Small—sections as thin as 0.003 in. possible | |
| Metal Powder Parts | Moderate—iron, steels, nickel, brass, nickel alloys, refractory metals | Limited—powders flow poorly, do not transmit pressure | Small—parts less than 4 in. square best | Small—<1/16 in. dia possible | |
| Spinnings | Wide—many sheet metals | Limited—cylindrical or concentric shapes | Large—up to several feet in dia | Moderate—¼ in. dia in gages less than 0.040 in. | |
| Screw Machine Parts | Wide—best suited to highly machinable metals | Moderate—limited to rotational shapes | Medium—up to 6 in. long, 2½ in. dia | Small—<1/16 in. dia | |
| Electroformed Parts | Narrow—iron, copper, nickel, silver | Great—extreme complexity possible | Limited—½-in. sections can be built up | Small—0.005 in. or less | |
| Tubing | Wide—any ductile metal available in tubular form | Limited by sectional shapes of tubing | Usually 4 to 6 in. o.d.; up to 20 in. possible | Moderate—¼ in. o.d. | |
| Welded and Brazed Parts | Wide—dissimilar metals can be joined | Great—extremely complex shapes | Unlimited | Moderate | |

| | Mechanical Properties | Precision, Tolerances | Special Structural Characteristics | Surface Smoothness | Surface Detail | Remarks |
|---|---|---|---|---|---|---|
| | Fair to high depending upon metal cast | ±1/16–1/32 in./in., closer at extra cost | Good bearing structure | Poor | Poor | Usually require some machining before use |
| | Good—little porosity, few gas inclusions | ±0.003–0.005 in./in. | High quality for cast metals | Good | Good | Considered best of low cost castings |
| | Good—high in centrifugal castings | ±0.01–0.05 in. | As above | Good | Good | Large quantities allow production economies |
| | Fair | ±0.010–0.005 in. | — | Good | Good | Little finishing required |
| | Good | ±0.005 in./in. common, ±0.002 in./in. possible | High quality for cast metals | Excellent | Excellent | Best for parts too complicated for other casting |
| | Fair | ±0.001 in./in. | Special properties can be obtained through use of inserts | Good | Good | Most economical where applicable |
| | High | ±0.010–0.030 in. without joining | Grain flow provides toughness | Fair | Fair | Used where high strength is required |
| | High | ±0.005 in. | Hot working gives structural advantages | Fair | Fair | Closer tolerances and greater complexity than drop forgings |
| | High | Medium—compare to press forgings | Grain flow provides toughness | Medium | Medium | Best suited to small parts |
| | High | ±0.010 in. common, ±0.002 in. possible | Tough structure | High | Fair | High production rates |
| | Good to high depending on alloys | ±1/64 in., closer on rounds | High quality for cast metals | Good | Only as part of contour | Provides long section and complex shapes |
| | Good | ±0.005 in. common for nonferrous metals; ±0.125 in. for steels | Grain flow improves properties | Good | Only as part of contour | Sometimes used as blanks for other processes |
| | High—metal cold worked | ±0.001 in. common | Grain flow improves properties | Good | Good | Can eliminate machining |
| | Good | ±0.002 in. common | Cold work improves properties | Good | None | Requires large quantities |
| | Good to high | Good—to ±0.001 in. common | — | High | Good to excellent | Extremely low cost in quan, otherwise moderate |
| | Fair to good | Good—±0.001–0.005 in. common | Porosity can be controlled and complex materials formed | Fair | Fair | Can use materials not formable by other processes |
| | Good | Fair—±0.015–0.060 in. common; better at added cost | Grain flow, cold work improve properties | Good | None | Good for large pieces or short runs |
| | High | ±0.001–0.005 in. possible | — | Excellent | Good | High production rates, low cost |
| | Fair—lower than wrought | High—±0.002–0.0002 in. common | — | Excellent | Excellent | Best when complexity and accuracy essential |
| | Good—cold working improves properties | Good—depends on quality of tubing | Grain flow improves properties | Good | None | Good means of reducing costs |
| | Variable—depends upon components | Medium—not highly precise | Can combine parts with special properties | Depends on components | None | Often needed to meet design requirements |

## Castings

### General

**Sand castings.** These castings are usually the first type considered. A major advantage is their availability in almost limitless shapes and in extreme complexity. Sand castings can be extremely large, but there is a practical limit to their minimum size. The process is not recommended for thin-section castings.

When moderate quantities of a part are required, sand castings can be relatively inexpensive, despite the hand labor required. Practically any metal can be used, with the exception of the newer metals which react with air while in the molten state. For precision parts, sand castings are usually restricted to the light alloys and certain bronzes.

**Shell mold castings.** The major advantage of shell mold casting is its ability to produce parts having a high degree of dimensional accuracy and a finish of sufficiently high quality to eliminate most finishing operations.

In many respects, shell casting compares with sand casting, but with the exception that the mold in which the casting is poured is composed of a mixture of sand and resin which has been formed over a metal pattern and then baked. Shells can be made with extremely smooth surfaces, sharp corners and fine detail, all of which can be imparted to the finished castings.

The overall quality of shell mold castings is generally superior to that of sand castings due to absence of moisture and to the porosity of the shells which allows gases to escape. Their primary characteristic, however, is close dimensional tolerances. Often called precision sand casting, this method allows tolerances of ±0.002–0.005 in. per in. to be achieved. Some foundries have been able to hold dimensions even more closely on larger pieces.

The range of materials that can be cast in shell molds is quite wide—almost equal to that of sand casting. There are, however, a few metals and alloys that cause difficulties. For example, low carbon steels are prone to various surface defects; brasses and bronzes with high lead and tin contents are inclined to sweat and cause trouble; and magnesium requires the use of special inhibitors in the shell to prevent difficulties caused by the reaction of magnesium with oxygen and silica sand.

Major disadvantages of shell molding include: necessity for expensive metal patterns and fairly expensive equipment for making and heating the molds; expensive resin binders; inability to reclaim the sand economically; and limitations on size of castings. It is generally felt that for optimum combination of accuracy, economy and quality, castings should be no larger than about 25 lb.

**Slush castings.** This method is used to produce hollow castings in metal molds without using cores.

Molten metal is poured into the mold which is immediately turned upside down so that the metal remaining liquid can run out. This leaves a thin-walled casting whose thickness depends on the chilling effect of the mold and the time of operation. The casting is removed by opening the halves of the mold.

This method is used only for ornamental objects, statuettes, toys and other novelties. Metals used are lead, zinc and various low melting alloys. Cast parts are generally painted or finished to represent bronze, silver or other more expensive metals.

**Continuous castings.** Although the continuous casting process is used primarily for the production of aluminum, magnesium, steel and copper alloy bar, billet, ingot and cold rolling slabs, one method—known as the Asarco Process—is used to produce copper alloys in shapes roughly analogous to shapes produced by extrusion.

Primary advantages of all continuous casting processes—which consist essentially of continuously pouring molten metal into a mold, rapidly cooling the metal, and withdrawing it—are uniform cross section, grain structure and composition.

In the Asarco Process, used for phosphorized copper and many standard bronzes, castings can be produced with satisfactory surface finishes as rounds, tubes, squares and special shapes. Some of the parts made from Asarco continuous castings include valve guides, bushings, thrust washers, retainers, gears, brake disks, nozzles, seals, sleeves, lugs and bearings. Special advantages claimed for this process are "lower materials costs, faster production and better products."

Sizes of rods and tubes available range from ½ to 9 in. in dia.

**Permanent mold castings.** Parts must be of relatively simple design, but some complexity is possible by using sand cores with steel molds (semipermanent molding). Because of the relatively low temperature limit of the mold material, the process is limited to the lower melting alloys. Aluminum alloys are the most commonly cast. Copper-base alloys, magnesium and, more recently, gray iron are also cast in permanent molds.

Permanent mold castings are usually dense and fine-grained, and can be made with better surfaces and closer tolerances than sand castings. Molds may be preheated to the 700-800 F range to achieve high control. Tolerances must be wider than for die castings, shell mold castings and plaster mold castings.

**Plaster mold castings.** These castings are noted for their fine finishes which reflect the smoothness of the plaster in which they are cast. The insulating quality of the mold causes a slower cooling rate which results in a reduction of tensile strength and

elongation. Although plaster mold castings are used for some high production parts, they are usually considered for small to medium-sized lots. Molding costs are relatively high, but these costs are usually recovered because of the minimum of machining.

Because of the temperature limitations of the mold material, this method is restricted to casting alloys with a melting point below 2000 F. These include aluminum, magnesium, and some of the copper-base alloys, such as yellow brass, silicon bronze, beryllium bronze, aluminum bronze and manganese bronze. Some foundries restrict lead content to 1.5% because of the reactivity of lead with plaster; others claim to have cast 50% lead alloys without difficulty. Alloys containing silicon lend themselves to finer detail with better surface finish. When casting magnesium, special plaster compositions and handling techniques are required, as well as more ample feeding facilities in the mold.

**Centrifugal castings.** Parts are limited in size and shape, but for large runs there are cost advantages in the elimination of risers or feedheads and of cores in cylindrical shapes. Parts have a dense metal structure with impurities forced back to the center where they can be machined out. Any metal can be cast by this process, and the pressure exerted means that sections can often be thinner than if cast by static methods. A disadvantage is that heat transfer to walls of metal molds and to the center air space must be controlled. For this reason the mold cavity is sprayed with sand or a refractory coating. Limiting dimensions for cylinders are lengths up to 347 in. and diameters from 2 to 50 in. Tolerances are of the same order as in other close tolerance casting methods.

The centrifugal casting method—rotating the mold as the metal solidifies—has three variations: (1) true centrifugal casting—mold is rotated about its horizontal or vertical axis; used for mass production of pipe, large gun barrels and liners, cylinder liners, brake drums and aircraft engine cylinders; (2) semi-centrifugal casting—centrifugal force causes molten metal to flow from a central feeding reservoir into one or more sand molds rotated about their central axis; used primarily for wheels; (3) centrifuging—low rotational speeds are used and the castings need not have axes of rotation but are spaced about a central feed reservoir; used for nonsymmetrical objects such as bearing caps and small brackets.

**Investment castings.** These parts are formed using a pattern molded in wax, plastic, or frozen mercury. Each pattern type has characteristics that make it more suitable for certain parts. Wax permits the greatest flexibility of design and is the least costly. Plastics permit more rapid production of patterns and also allow a surplus of patterns to be stored for future use. Frozen mercury allows larger sizes to be cast and requires only a thin ceramic shell which, in turn, results in better metal quality. In general, investment cast parts offer dimensional tolerances superior to those of other castings, can be made in shapes too complex for metal powder parts, and can be made of metals with melting points too high for die casting. Mechanical properties are generally high.

Of the seven types of close tolerance castings (i.e., excluding sand castings), investment castings are matched only by shell moldings and centrifugal castings in the range of castable alloys available. These alloys include high melting ferrous alloys, copper alloys, special high temperature nonferrous alloys, and all castable aluminum and magnesium alloys.

*continued on next page*

**MACHINE FINISH ALLOWANCES**

| Metal ↓ | Pattern Size, in. | Bore, in. | Finish, in. |
|---|---|---|---|
| Cast Iron | Up to 12 | 1/8 | 3/32 |
| | 13 to 24 | 3/16 | 1/8 |
| | 25 to 42 | 1/4 | 3/16 |
| | 43 to 60 | 5/16 | 1/4 |
| | 61 to 80 | 3/8 | 5/16 |
| | 81 to 120 | 7/16 | 3/8 |
| | Over 120 | [g] | [g] |
| Malleable Iron[a, b, c, d] | Up to 6 | 1/16 | 1/16 |
| | 6 to 9 | 3/32 | 1/16 |
| | 9 to 12 | 3/32 | 3/32 |
| | 12 to 24 | 3/32 | 1/8 |
| | 24 to 35 | 3/16 | 3/16 |
| | Over 36 | [g] | [g] |
| Steel[e] | Up to 12 | 3/16 | 1/8 |
| | 13 to 24 | 1/4 | 3/16 |
| | 25 to 42 | 5/16 | 5/16 |
| | 43 to 60 | 3/8 | 3/8 |
| | 61 to 80 | 1/2 | 7/16 |
| | 81 to 120 | 5/8 | 1/2 |
| | Over 120 | [g] | [g] |
| Brass, Bronze, Aluminum[f] | Up to 12 | 3/32 | 1/16 |
| | 13 to 24 | 3/16 | 1/8 |
| | 25 to 36 | 3/16 | 3/32 |
| | Over 36 | [g] | [g] |

[a] When castings are constructed so that they warp more than the average amount, the allowances given should be increased.
[b] Disk grinding—only sufficient finish required to take care of draft and possible warpage.
[c] Coin pressing—practically no finish allowance required.
[d] For small parts, an allowance of 1/32-1/16 in. is satisfactory. Larger parts require a slightly greater allowance.
[e] Allowance ranges from 1/8 to 1 in. Values given for finish are normal for ordinary finishes on the drag side. For finished surfaces on the cope side, it is often necessary to double the allowance.
[f] For small or medium-sized nonferrous castings, 1/8 in. is a customary allowance, with correspondingly larger allowances on larger castings.
[g] Special instructions.

## Castings

Though the same general degree of accuracy is obtainable with all alloys, it is easier to obtain with the nonferrous alloys because of their higher fluidity and lower melting points.

**Die castings.** Only nonferrous alloys are suitable for die castings. The range of these alloys is adequate for most needs but more limited than for sand castings. Alloys used, in order of tonnage, are: zinc, aluminum, copper, magnesium, lead and tin. They can be grouped in low and high melting classes according to melting point:

Low melting alloys

| | |
|---|---|
| Zinc | 727 F |
| Lead | 484 F |
| Tin | 417 F |

High melting alloys

| | |
|---|---|
| Aluminum | 1115 F |
| Magnesium | 1110 F |
| Copper | 1600 F |

The high melting group are usually cast in cold chamber or air injection machines; the low melting alloys in plunger machines. Of all casting processes, die casting is by far the best suited to high production of quality parts. As in permanent mold casting, an advantage is derived from the high thermal conductivity of the steel used in the die. The resultant chilling effect promotes fine grained metallurgical structure. Though die castings are subject to varying degrees of porosity, proper engineering of the casting and die may confine it to noncritical areas.

### Design Factors

**Draft allowances.** Draft allowance is normally at least ½ in. per ft., although it often ranges from ¼ to ⅜ in. per ft. It is seldom less than 1 deg and ⅛ in. per ft. In sand and plaster mold casting, the mold is destroyed; therefore the draft required is only necessary to remove the pattern. Investment casting requires no draft, though ½ to 1 deg can be specified for single parting, noncored dies. Frozen mercury, wax and plastics patterns require no draft, but ½ deg is used with Kirksite dies.

*Permanent mold*—A minimum of 2 deg on each side is usually provided, though the range is 0 to 3 deg. In recesses, 2 deg on each side is a minimum with 5 deg desirable. The following figures (in. per in. of depth on one side) are fairly standard: magnesium—0.015, aluminum—0.015, bronze—0.020.

*Shell mold*—Draft angles are not as critical as for permanent mold castings. From ¼ to ½ deg is

**DIMENSIONAL TOLERANCES (In.)[a]**

| | |
|---|---|
| **Sand Castings** | |
| Gray Iron | 1/32–1/16 |
| Malleable Iron | 3/32 |
| Steel | 3/32 |
| Aluminum Alloys | 5/64 |
| Magnesium Alloys | 11/64 |
| Brass | 3/32 |
| Bronze | 1/8 |
| (Zinc, tin, lead not cast) | |
| **Shell Mold Castings** | |
| Ferrous | 0.001–0.003 in./in. possible. Commercially 0.010 to 0.015 are held on dimensions within mold half. Across parting line: 0.020–0.030 |
| Magnesium, Others | Same as ferrous |
| (Zinc, tin, lead not cast) | |
| **Permanent Mold Castings** | |
| Aluminum | 0.015 for first inch; then 0.002 in./in. Common total: 0.010–0.050 |
| Magnesium, Gray Iron, Others | Same as aluminum or slightly wider |
| (Steel, tin not cast) | |
| **Plaster Mold Castings** | |
| Brass, Bronze | 0.005 for first inch; then 0.001 in./in. Common total: 0.005 to 0.010 |
| Aluminum, Others | Same as brass and bronze |
| (Ferrous, zinc, tin, lead, copper not cast) | |
| **Investment Castings** | |
| Copper | 0.002–0.005 in./in. |
| Stainless Steel | 0.004–0.008 in./in. |
| Others | 0.003–0.006 in./in. |
| (Iron, some steels, zinc, tin, lead not cast) | |
| **Die Castings** | |
| Zinc | 0.0025 for less than 1 in.<br>0.001 in./in. for dimensions greater than 1 in. |
| Aluminum, Magnesium | 0.003 for less than 1 in.<br>0.001–0.002 in./in. for dimensions greater than 1 in. |
| Others | 0.005 for less than 1 in.<br>0.003 in./in. for dimensions greater than 1 in. |
| (Ferrous not cast) | |

[a]Tolerances are for usual commercial practice, stated for guidance only. In most cases closer tolerances can be held at increased cost. Tolerances are over-all unless stated as in. per in. All values are ± tolerances.

usually sufficient for shell mold castings.

*Die*—In general, a minimum of 2 deg per side is usually provided. The following draft tolerances (in.) are usually provided:

| | |
|---|---|
| Magnesium | 0.010[a] |
| Aluminum | 0.010-0.015 |
| Zinc | 0.005-0.007 |
| Brass, bronze | 0.015-0.020 |
| Tin, lead | 0.015 |

[a] In. per in. of depth, one side.

**Shrinkage allowances.** The following allowances (in. per ft) are usually provided:

| | |
|---|---|
| Cast iron | 1/8 |
| Malleable iron | 1/8 |
| Steel | 1/4 |
| Aluminum | 5/32 |
| Brass | 3/16 |

## Design Rules

1. Stress concentration is always a vital consideration. A larger amount of metal will have greater shrinkage and put an adjoining thin section under tension which may result in cracking. The design should incorporate fillets when there is a change of section thickness or to avoid sharp, interior corners. In addition to lowering stress concentration, fillets help achieve even cooling and shrinkage.

2. Continuous, intersecting ribs may cause trouble. Staggering the ribs will help prevent the build-up of high stresses.

3. Avoid large, flat areas with little or no support.

4. The parting line, particularly in die castings, is preferably located at the corner of the casting. Lines of demarcation remaining after flash removal will not be nearly as visible.

**MINIMUM SECTION THICKNESS (In.)[a]**

| | |
|---|---|
| **Sand Castings** | |
| Gray Iron[a] | 1/8–3/16 |
| White Iron | 1/8–3/16 |
| Malleable Iron | 1/8–3/16 |
| Steel | 3/16–1/4 |
| Aluminum | 1/8–3/16 |
| Magnesium | 3/16–1/4 |
| Brass, Bronze | 3/32–1/8 |
| **Shell Mold Castings[b]** | |
| Ferrous | 1/16–1/8 |
| Magnesium, Others | 1/16–1/8 |
| **Permanent Mold Castings** | |
| Aluminum | |
| < 3 In. | 3/32–1/8 |
| 3 to 6 In. | 5/32 |
| >6 In. | 3/16 |
| Gray Iron, Others | |
| <3 In. | 3/32–1/8 |
| 3 to 6 In. | 5/32 |
| >6 In. | 3/16 |
| **Plaster Mold Castings** | |
| Brass, Bronze | |
| 2 Sq In. | 0.040 |
| 4 to 6 Sq In. | 0.063 |
| <30 Sq In. | 0.093 |
| Aluminum, Others | |
| 2 Sq In. | 0.040 |
| 4 to 6 Sq In. | 0.063 |
| <30 Sq In. | 0.093 |
| **Investment Castings[b]** | |
| Copper | 0.030 |
| Stainless Steel | 0.050 |
| Others | 0.030 |
| **Die Castings** | |
| Zinc | |
| Small | 0.020–0.030 |
| Large | 0.050 |
| Aluminum | 0.035 |
| Magnesium | 0.050 |
| Aluminum Alloy | |
| Small | 0.045–0.055 |
| Large | 0.080 |
| Magnesium Alloy | |
| Small | 0.050–0.060 |
| Large | 0.080 |
| Copper | |
| Small | 0.06 |
| Large | 0.10 |
| Brass, Bronze | 0.050 |
| Tin | |
| Small | 0.030 |
| Large | 0.060 |
| Lead | |
| Small | 0.040 |
| Large | 0.070 |

[a] Usual minimum for various classes of gray iron is: class 20, 1/8; class 25, 1/8; class 30, 1/4; class 35, 3/16; class 40, 1/2; class 50, 1/2; class 60, 3/4.
[b] Avoid section differences where max : min ratio is more than 5 : 1.

## Extrusions

### General

Extrusions are used extensively as a means of making small parts of uniform cross section that might otherwise be made only through extensive machining. Long pieces of the desired cross section are extruded, then cut to desired lengths and subjected to any further operations that may be required.

**Advantages.** Extruded shapes are not considered to be highly precise as far as dimensional tolerances are concerned, but they do have the advantage of permitting the metal to be placed where it is most needed to attain desired strength and design characteristics. Relatively complex shapes can be extruded. Sharp corners and reentrant angles are readily obtainable. When precision is a requirement, final dimensions are achieved through machining. Extruding is sometimes used to make blanks for other processes, e.g., forging.

**Limitations.** Sizes are limited because of the excessive size of the presses required to extrude large sections, and because large shapes are likely to bend and distort excessively under their own weight and require expensive straightening operations. Any openings must be in the direction of the extruding action and uniform throughout the entire length of the extrusion.

**Materials.** Although in the past most extruded shapes have been made from aluminum, magnesium and copper alloys, the process has recently been expanded to include many types of steels. Steels and other high melting alloys are easy to extrude, but they are hard on die materials and require lubricants with special qualities. Titanium, lead, tin and zinc alloys are also extruded. For best results the ratio of billet size to finished extrusion should be large. When large ratios are used, the resulting extrusions are dense, homogeneous and free of porosity, and the metal properties compare favorably with those attained in forging. Ratios usually range from 20:1 to 40:1.

**Speed of output.** Rate of output of extruded shapes can affect cost, particularly if large quantities are required. Speeds range from 1½ to 700 fpm, depending on the basic material, the particular alloy and the shape being extruded. Magnesium is extruded at speeds of 4 to 100 fpm, aluminum somewhat faster, and copper alloys a little slower. Highest speeds are attained with nickel alloys and steels.

**Applications.** Conditions under which extruded shapes might be chosen are:

1. When a more efficient disposal of metal is desirable than is obtainable with rolled shapes or other metal forms.
2. Where several parts are now joined to provide a small assembly.
3. Where shapes are required that could not be obtained without difficult machining.
4. Where short pieces of an extrusion could replace small castings or forgings.

### Design Factors

**Tolerances.** Tolerances on extruded metal parts are held on such factors as straightness, flatness, twist, section thickness, angles, contours, and corner and fillet radii.

*Flatness*—On a 6-in. width, tolerance would be ±0.024 in., or about 0.004 in. per in. of width.

*Straightness*—On a 5-ft length, a 1/16-in. deviation from a straight line is normal. This deviation increases to ⅜ in. at 30 ft.

*Cross section*—Typical are tolerances ranging from ±0.006 in. on thicknesses of less than 0.125 in. up to ±0.080 in. on thicknesses or widths of 14-15 in.

*Cut ends*—Permissible deviation from the square is 1 deg.

*Curved surfaces*—Allowable deviation from a specified contour is 0.005 in. or 0.004 in. per in. of chord length, whichever is greater. This tolerance does not apply to an arc of more than 90 deg.

**Section thickness.** Thickness of sections usually ranges from 0.050 in. up to several inches. Ratios of thickness to width vary with materials used and are standardized for aluminum and magnesium extrusions. Aluminum alloys, such as 3003 and 6063 have a ratio of 8 in. wide to 3/32 in. thick; for 2014, it is 8 in. wide to ⅛ in. thick.

### Design Rules

1. Extruded shapes are usually restricted to those that can be contained within a circumscribing 21-in. circle. Within this range, parts can be made as solid, hollow or semihollow shapes; T, L or V sections; rectangles; and complex shapes.
2. Avoid extremely thin sections within a large circumscribing area.
3. Avoid semihollow sections with unbalanced die tongues.
4. Avoid sections with extreme thickness variation.
5. Avoid hollow shapes having unsymmetrical voids or inadequate thickness between voids.

### Stepped Extrusions


Stepped extrusions are commonly produced by utilizing two sets of extrusion dies.

In designing a stepped extrusion it is important to use dimensional tolerances that are realistic, yet avoid an excess of stock. Stepped extrusion tolerances have not been standardized, but those given in the accompanying sketches are typical. Straightness tolerances differ from those for normal extrusions. In addition, special tolerances apply to the step area and across the parting line when split dies are used.

Because of the inherent instability of split dies, cross section tolerances of stepped extrusions are usually greater than for normal extrusions. In locating parting lines, it is important to consider not only tolerances but also the ability to remove tools from the section. It is sometimes necessary to provide slight draft angles on extended elements.

Although the major and minor sections may frequently have a common plane, this is not a requirement of the process. In all cases, however, the major section must completely enclose the minor section. It is generally necessary to provide machining stock on all surfaces to obtain the required dimensional accuracy and surface finish.

Straightness of the over-all part is measured by deviation from a reference line, the junction or step area (8 in. on either side of the step) being excluded. Straightness of the minor or major portion of the extrusion is determined individually. Because of the difference in flow conditions in extruding the major and minor sections, the junction area usually presents the greatest straightening problems. Minor and major portions are usually furnished to standard extrusion straightness tolerances.



## Impact Extrusions

### General

Parts made by impact extruding cannot be very large or very small. They must be concentric in design, but can be provided with lugs, flutes and similar projections. Mechanical properties of impact extruded parts are usually high because of the tremendous amount of cold work involved in the process; this is particularly true of carbon steels.

Often a concentric impact extrusion is sectioned after forming to make two or more parts which could not otherwise meet the design requirements of impact extrusion. Examples are semicircular and U-shaped pieces.

**Comparisons.** Both impact extrusion and deep drawing use a combination of punch and die to form a hollow shell from a cold blank, and for some parts equivalent speeds are used. The difference lies in the manner in which deformation occurs. In impact extrusion the metal is forced through an orifice between punch and die under compressive stresses; in deep drawing the metal is pulled into the die by the punch and stressed in tension.

Both impact extrusion and ordinary extrusion force metal through a die under compressive stresses. However, the metal is generally cold worked in impact extrusion and hot worked in ordinary extrusion. In addition, impact extrusion produces a single component that may or may not require further operations, whereas ordinary extrusion generally produces a continuous cross section such as a rod, tube or structural shape.

An impact extruded part can be considered as a modified forging in which the flash forms the side walls. The part has a base that, in backward extrusion at least, is a forging, and side walls that are extrusions.

**Advantages.**

1. High speed production is possible.
2. Unit cost of mass produced parts is low.
3. Materials saving and excellent metal recovery are achieved.
4. Process requires few operations. Ribs, fins, holes, etc., are formed during extrusion.
5. Parts have dimensional uniformity with close diametrical tolerances.
6. Tooling is relatively cheap.
7. Surface finishes on the order of 20 to 70 microinches are obtainable.
8. Bottom thicknesses are independent of wall thicknesses.
9. Parts can be made with zero draft angles and sharp corner radii.
10. Parts have excellent properties; for example, cold formed low or medium carbon steel parts have mechanical properties equivalent to those of heat treated carbon and low alloy steels.

**Limitations.**

1. Relatively few alloys can be processed commercially at present.
2. Shapes that can be produced are limited.
3. Length-to-diameter ratio is restricted.
4. Maximum size of part is limited by press capacity.
5. Comparatively high equipment costs limit applications to relatively high production runs.

**COMMERCIAL SIZE RANGES FOR ALUMINUM IMPACT EXTRUSIONS**

| Material | Wall Thickness, in. | | Diameter, in. | |
|---|---|---|---|---|
| | Max | Min | Max | Min |
| 1070 (collapsible tubes)... | 0.010 | 0.0035 | 2½ | ⅛ |
| 1100, 3003..... | ½* | 0.010 | 6 | ¼ |
| Medium Strength Alloys.. | ½* | 0.040 | 5 | ⅛ |
| High Strength Alloys..... | ½* | 0.062 | 4 | ¼ |

*Some authorities state that the maximum wall thickness is "not known."

### Design Factors

**Sizes.** Part sizes and dimensional tolerances vary considerably, depending upon the metal. Some typical figures: in aluminum, wall thickness ranges from a maximum of ½ in. down to 0.010 in. in the soft alloys or 0.062 in. in the stronger alloys. Diameters of parts can be as great as 6 in. in the soft alloys and 4 in. in the hard alloys, and as small as ¾ in. Larger parts would require extremely high pressures, and smaller parts would involve excessive tool damage.

**Tolerances.** Typical commercial dimensional tolerances for aluminum are as follows. On walls as thin as 0.10 in., the tolerance can be held to 0.010 in. Over 0.15 in., the tolerance must be increased to 0.020 in. Diameters can be held to 0.010 in., but lengths are not usually guaranteed any closer than 3/16 in.

**Materials.** By far the most commonly used material for mechanical parts is aluminum and its alloys. More than a dozen different alloys are used, depending upon the end service requirements, but from the standpoint of extruding 1100 alloy is best.

In steels, best results are obtained with those containing up to 1.2% carbon, although several alloy steels are impact extruded regularly. Steel parts must be somewhat smaller and have greater wall thicknesses than similar parts in aluminum.

Magnesium slugs are heated to 500 to 700 F for impact extruding. Several different alloys can be used, but best results are obtained with alloy AZ31B.

Several other metals are impact extruded to a lesser degree. They include lead, tin, copper, zinc and zirconium.

# Fabricated Sheet Metal Parts

## Stampings and Press Formed Parts

**General.** Blanking, piercing, drawing, bending, ironing and coining are all done on hydraulic or mechanical presses, or on drop hammers. The folding up, and sometimes the piercing, of long shapes is done on press brakes. Wrap-around operations on small parts are done on multislide machines. Large quantities of drawn parts are made in eyelet or transfer presses with multiple stations.

Stampings which do not require deep draws and which are less than 6 in. in dia and 0.109 in. thick can be made from coil stock by using progressive dies which combine several operations at each stroke. Such costly dies are rarely justified for runs of less than 30,000 pieces. Sometimes duplicates are made side by side.

**Advantages and limitations.** Parts can be fairly complex in shape, but the extreme-low-cost advantages disappear as increasing complexity adds to the number of operations required. Because of the many variables in stamping design and stamping equipment, the extent of the advantages is greatly dependent on the knowledge and skill of the die designer. Finishes are good, and the parts are generally uniform and nonporous. Limitations include cost of tools, the roughness of sheared edges, and the difficulty inherent in substantially changing original stock thickness.

**Materials.** Nearly any metal that can be rolled can be used for stampings. Formed and drawn parts are usually made of soft temper materials, but parts can be heat treated after forming. Commonly used: carbon steels, particularly low carbon steels; copper; brass; bronze; aluminum; magnesium alloys; zinc; titanium; nickel alloys; stainless steels; and some alloy steels. A substantial variety of finishes are applied.

**Dimensional tolerances.** Stampings may be as thin as 0.003 in., or as heavy as ⅝ in., and may vary in size from tiny shapes to freight car ends. Dimensional tolerances vary with the thickness of the material and the size of the part. Tolerances of ±0.001 in. are available on dimensions up to 2 in., tolerances on the order of ±0.003 in. on dimensions up to 6 in. Heavy material calls for more generous tolerances. It is a general rule that when unnecessarily close tolerances are called for, more expensive tooling, higher costs of tool repair, and sometimes extra operations are required.

**Design rules.** In general, the following design rules apply to all stamping operations:

1. Material can frequently be strengthened by the addition of flanges, beads, corrugations or ribs.

2. Ribs and bosses should be at least four times as wide as deep, so the metal will stretch.

3. Hole edges may be extruded for greater thread length, etc. The depth of such extrusions without gathering operations should not exceed 15 to 20% of hole diameter.

4. Coining can force metal to flow and thus produce locating projections and grooves. This type of operation is particularly applicable to softer materials and smaller parts.



**COMPARATIVE FORMABILITY OF METALS[a]**

| Metal | Alloy | Rating |
|---|---|---|
| Aluminum | 1100-O | 100 |
| | 3003-O | 95 |
| Magnesium (hot formed) | | 95[b] |
| Aluminum | 6061-O | 92 |
| | 5052-O | 80 |
| | 7075-O | 75 |
| | 2024-O | 75 |
| | 2014-O | 75 |
| Deep Drawing Steel | 1008 | 75 |
| Zinc | | 75 |
| Soft Copper | | 75[b] |
| Commercial Steel | 1010 | 70 |
| Soft Brass | | 70 |
| Aluminum (as quenched) | 7075-W | 60 |
| | 2024-W | 60 |
| | 2014-W | 60 |
| Aluminum | 1100-¼H | 50 |
| Stainless Steel | Type 302 | 49 |
| | Type 304 | 46 |
| Aluminum | 3003-¼H | 45 |
| Stainless Steel | Type 321 | 43 |
| Aluminum | 5052-¼H | 40[b] |
| | 1100-½H | 40[b] |
| Titanium | | 40 |
| Stainless Steel | Type 347 | 40 |
| Aluminum | 3003-½H | 35[b] |
| | 5052-½H | 30[b] |

[a]Based on rating of 100 for 1100-O aluminum. [b]Tentative.

**PENETRATION OF PUNCH THROUGH METAL IN BLANKING OR PIERCING OPERATIONS**

| Metal | Annealed | | Partially Cold Worked | |
|---|---|---|---|---|
| | Resistance to Shearing, psi | Reduction or Penetration, % | Resistance to Shearing, psi | Reduction or Penetration, % |
| Lead | 3,500 | 50 | —[a] | —[a] |
| Tin | 5,000 | 40 | —[a] | —[a] |
| Aluminum | 8,000 | 60 | 13,000 | 30 |
| Zinc | 14,000 | 50 | 19,000 | 25 |
| Copper | 22,000 | 55 | 28,000 | 30 |
| Brass | 32,000 | 50 | 52,000 | 20 |
| Bronze (90–10) | — | — | 40,000 | 30 |
| Tobin Bronze | 36,000 | 25 | 42,000 | 17 |
| Steel | | | | |
| 0.10% C | 35,000 | 50 | 43,000 | 38 |
| 0.20% C | 44,000 | 40 | 55,000 | 28 |
| 0.30% C | 52,000 | 33 | 67,000 | 22 |
| 0.40% C | 62,000 | 27 | 78,000 | 17 |
| 0.60% C | 80,000 | 20 | 102,000 | 9 |
| 0.80% C | 97,000 | 15 | 127,000 | 5 |
| 1.00% C | 115,000 | 10 | 150,000 | 2 |
| Silicon Steel | 65,000 | 30 | — | — |
| Nickel | 35,000 | 55 | — | — |

[a]Anneals at room temperature.

*continued on next page*

## Fabricated Sheet Metal Parts

**MINIMUM BEND RADII FOR ALUMINUM SHEET[a]**

| Gage, in. ↓ | 7075-O, 7075-W[b] | 7075-T6 | 2024-O, 2024-W,[c] 2014-O | 2014-T3 | 2024-T3, 2014-T6 | 6061-O |
|---|---|---|---|---|---|---|
| 0.020 | 1/32 | 3/32 | 1/64 | 1/16 | 1/16 | 0 |
| 0.025 | 1/32 | 1/8 | 1/64 | 1/16 | 3/32 | 0 |
| 0.032 | 1/16 | 5/32 | 1/64 | 1/16 | 3/32 | 0 |
| 0.040 | 1/16 | 3/16 | 1/32 | 3/32 | 1/8 | 0 |
| 0.051 | 3/32 | 1/4 | 1/16 | 1/8 | 3/16 | 0 |
| 0.064 | 1/8 | 5/16 | 1/16 | 5/32 | 7/32 | 0 |
| 0.081 | 5/32 | 3/8 | 3/32 | 7/32 | 9/32 | 0 |
| 0.091 | 3/16 | 1/2 | 3/32 | 1/4 | 11/32 | 0 |
| 0.102 | 3/16 | 5/8 | 3/32 | 5/16 | 7/16 | 0 |
| 0.125 | 7/32 | 3/4 | 1/8 | 3/8 | 1/2 | 1/16 |
| 0.156 | 3/8 | 1 | 5/32 | 7/16 | 5/8 | 1/8 |
| 0.187 | 1/2 | 1 1/4 | 3/16 | 1/2 | 3/4 | 3/16 |

| Gage, in. ↓ | 6061-T4 | 6061-T6 | 5052-O | 5052-H32 1/4 Hard | 5052-H34 1/2 Hard | 5052-H38 3/4 Hard |
|---|---|---|---|---|---|---|
| 0.020 | 1/32 | 1/32 | 0 | 0 | 0 | 1/32 |
| 0.025 | 1/32 | 1/32 | 0 | 0 | 0 | 1/32 |
| 0.032 | 1/32 | 1/32 | 0 | 0 | 0 | 1/32 |
| 0.040 | 1/32 | 1/32 | 0 | 0 | 0 | 1/16 |
| 0.051 | 1/16 | 1/16 | 0 | 0 | 1/32 | 1/16 |
| 0.064 | 1/16 | 3/32 | 0 | 0 | 1/16 | 3/32 |
| 0.081 | 3/32 | 1/8 | 0 | 1/32 | 1/16 | 1/8 |
| 0.091 | 1/8 | 5/32 | 0 | 1/16 | 3/32 | 1/8 |
| 0.102 | 1/8 | 3/16 | 0 | 3/32 | 1/8 | 3/16 |
| 0.125 | 3/16 | 1/4 | 0 | 1/8 | 1/8 | 1/4 |
| 0.156 | 3/16 | 3/16 | 0 | 5/32 | 3/16 | 1/2 |
| 0.187 | 3/8 | 7/16 | 0 | 3/16 | 7/32 | 7/16 |

| Gage, in. ↓ | 5052-H38 Hard | 1100-H12 1/4 Hard | 1100-H14 1/2 Hard | 1100-H16 3/4 Hard | 1100-H18 Hard |
|---|---|---|---|---|---|
| 0.020 | 1/32 | 0 | 0 | 0 | 1/32 |
| 0.025 | 1/32 | 0 | 0 | 0 | 1/32 |
| 0.032 | 1/16 | 0 | 0 | 0 | 1/32 |
| 0.040 | 1/16 | 0 | 0 | 0 | 1/16 |
| 0.051 | 3/32 | 0 | 0 | 1/32 | 1/16 |
| 0.064 | 1/8 | 0 | 0 | 1/16 | 3/32 |
| 0.081 | 3/16 | 1/32 | 1/32 | 1/16 | 1/8 |
| 0.091 | 1/4 | 1/16 | 1/16 | 3/32 | 1/8 |
| 0.102 | 5/16 | 3/32 | 3/32 | 1/8 | 3/16 |
| 0.125 | 3/8 | 1/8 | 1/8 | 1/8 | 1/4 |
| 0.156 | 5/8 | 5/32 | 5/32 | 3/16 | 1/2 |
| 0.187 | 3/4 | 3/16 | 3/16 | 7/32 | 7/16 |

[a] Minimum allowable radii for bending aluminum alloy sheet depend on thickness, temper and composition. Values given in the table are for 90-deg bends and should be increased for bends greater than 90 deg.
[b] Freshly quenched and formed within 2 hr max, or 24 hr max if iceboxed at 32 F.
[c] Freshly quenched and formed within 1/2 hr max, or 24 hr max if iceboxed at 32 F.

**MINIMUM BEND RADII FOR MAGNESIUM ALLOY SHEET[a]**

| Alloy ↓ | Forming Temperature, F | | | | |
|---|---|---|---|---|---|
| | 70 | 300 | 400 | 500 | 600 |
| M1 | | | | | |
| Annealed (M1a) | 5T | 4T | 3T | 2T | 1T |
| Cold Worked (M1h) | 11T | 8 1/2T | 6 1/2T | 4 1/2T | — |
| AZ31 | | | | | |
| Annealed (AZ31Xa) | 3 1/2T | 2T | 1 1/2T | 1T | — |
| Cold Worked (AZ31Xh) | 7 1/2T | 3T | | | |
| AZ51X | | | | | |
| Annealed (AZ51Xa) | 6T | 4 1/2T | 3 1/2T | 2 1/2T | 2T |
| Cold Worked (AZ51Xh) | 9T | 6 1/2T | 4 1/2T | | |

Experimental values, where T = metal thickness.

**MINIMUM BEND RADII FOR AUSTENITIC STAINLESS STEELS[a]**

| | |
|---|---|
| Annealed | 1/2T to 1T |
| 1/4 Hard | 1T to 2 1/2T |
| 1/2 Hard | 2 1/2T to 4T |
| 3/4 Hard | 3T to 5T |
| Full Hard | 4T to 6T |

[a] Where T = metal thickness.

5. Unless the print calls for parts to be washed, deburred, flat within a given tolerance, or specially handled to reduce any marks, stampers make extra charges for such operations.

**Pierced parts.** The following design rules should generally be observed:

1. The diameter of a hole is measured by its smallest dimension (the edges of a pierced hole are not straight).

2. Hole diameters should be more than two-thirds of metal thickness (larger in hard materials), and never less than 0.030 in.

3. Distance between hole edges, or hole edge and outside periphery, should be greater than metal thickness. For combined operations, a minimum of 3/32 in. is desirable for the die to stand up.

4. If holes are dimensioned from the edges of parts, they may be pierced in the flat. If they are closely dimensioned from bends, secondary operations are necessary.

5. Holes near a bending edge should be a distance of 1 1/2 times metal thickness, plus bend radius, from formed angle. Long slots should be a distance of four or five times the metal thickness from a formed angle. Sometimes such holes are pierced after form-

**BEND ALLOWANCES IN STEEL SHEET[a]**

| Inside Bend Rad., in. ↓ | Metal Thickness, in. | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | .022 | .028 | .035 | .049 | .065 | .095 | .120 | .187 | .250 |
| .032 | .00072 | .00076 | .00082 | .00093 | .00105 | .00129 | .00148 | .00200 | — |
| .0625 | .00126 | .00131 | .00136 | .00147 | .00160 | .00183 | .00203 | .00255 | — |
| .093 | .00180 | .00185 | .00191 | .00202 | .00212 | .00238 | .00257 | .00309 | — |
| .125 | .00235 | .00240 | .00245 | .00256 | .00269 | .00292 | .00311 | .00364 | — |
| .156 | .00289 | .00294 | .00300 | .00311 | .00323 | .00346 | .00366 | .00418 | — |
| .1875 | .00344 | .00349 | .00354 | .00365 | .00378 | .00410 | .00420 | .00473 | — |
| .218 | .00398 | .00403 | .00409 | .00419 | .00432 | .00455 | .00475 | .00527 | — |
| .250 | .00453 | .00458 | .00463 | .00474 | .00487 | .00510 | .00529 | .00582 | — |
| .281 | .00507 | .00512 | .00517 | .00528 | .00541 | .00564 | .00584 | .00636 | — |
| .3125 | .00562 | .00567 | .00572 | .00583 | .00596 | .00619 | .00638 | .00691 | — |
| .343 | .00616 | .00620 | .00626 | .00637 | .00650 | .00673 | .00693 | .00745 | — |
| .375 | .00671 | .00675 | .00681 | .00692 | .00705 | .00728 | .00747 | .00800 | .00849 |
| .406 | .00725 | .00730 | .00735 | .00746 | .00759 | .00782 | .00802 | .00854 | .00903 |
| .4375 | .00780 | .00784 | .00790 | .00801 | .00813 | .00837 | .00856 | .00908 | .00958 |
| .468 | .00834 | .00839 | .00844 | .00855 | .00868 | .00891 | .00911 | .00963 | .01012 |
| .500 | .00889 | .00893 | .00899 | .00910 | .00922 | .00945 | .00965 | .01017 | .01067 |
| .531 | .00943 | .00948 | .00953 | .00964 | .00977 | .01000 | .01019 | .01072 | .01123 |
| .5625 | .00998 | .01002 | .01008 | .01019 | .01031 | .01055 | .01074 | .01126 | .01175 |
| .593 | .01052 | .01055 | .01061 | .01072 | .01084 | .01108 | .01127 | .01179 | .01230 |
| .625 | .01106 | .01111 | .01117 | .01128 | .01140 | .01161 | .01183 | .01235 | .01284 |
| .656 | .01161 | .01166 | .01171 | .01182 | .01194 | .01218 | .01237 | .01289 | .01339 |

[a]Allowance for 1 deg of bend; multiply value in table by number of degrees in bend.

**BEND ALLOWANCES IN ALUMINUM ALLOY SHEET[a]**

| Inside Bend Rad., in. ↓ | Metal Thickness, in. | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | .020 | .025 | .032 | .040 | .051 | .064 | .081 | .091 | .128 |
| .032 | .00070 | .00074 | .00079 | — | — | — | — | — | — |
| .0625 | .00125 | .00129 | .00135 | .00140 | .00149 | .00159 | — | — | — |
| .093 | .00179 | .00183 | .00188 | .00195 | .00203 | .00213 | .00226 | .00234 | — |
| .125 | .00234 | .00238 | .00243 | .00249 | .00258 | .00268 | .00281 | .00289 | .00317 |
| .156 | .00288 | .00292 | .00297 | .00304 | .00312 | .00322 | .00335 | .00343 | .00372 |
| .1875 | .00342 | .00347 | .00352 | .00358 | .00367 | .00377 | .00390 | .00398 | .00449 |
| .218 | .00397 | .00401 | .00406 | .00412 | .00421 | .00431 | .00444 | .00452 | .00481 |
| .250 | .00451 | .00455 | .00461 | .00467 | .00476 | .00486 | .00499 | .00507 | .00535 |
| .281 | .00506 | .00510 | .00515 | .00521 | .00530 | .00540 | .00553 | .00561 | .00590 |
| .3125 | .00560 | .00564 | .00570 | .00576 | .00584 | .00595 | .00608 | .00616 | .00644 |
| .343 | .00615 | .00619 | .00624 | .00630 | .00639 | .00649 | .00662 | .00670 | .00699 |
| .375 | .00669 | .00673 | .00679 | .00685 | .00693 | .00704 | .00717 | .00725 | .00753 |
| .406 | .00724 | .00728 | .00733 | .00739 | .00748 | .00758 | .00771 | .00779 | .00808 |
| .4375 | .00778 | .00782 | .00787 | .00794 | .00802 | .00812 | .00826 | .00834 | .00862 |
| .468 | .00833 | .00837 | .00842 | .00848 | .00857 | .00867 | .00880 | .00888 | .00917 |
| .500 | .00877 | .00891 | .00896 | .00903 | .00911 | .00921 | .00935 | .00943 | .00971 |
| .531 | .00942 | .00946 | .00951 | .00957 | .00966 | .00976 | .00989 | .00997 | .01051 |
| .5625 | .00996 | .01000 | .01005 | .01012 | .01020 | .01030 | .01043 | .01051 | .01080 |
| .593 | .01051 | .01055 | .01058 | .01065 | .01073 | .01083 | .01098 | .01105 | .01133 |
| .625 | .01105 | .01109 | .01114 | .01121 | .01129 | .01139 | .01152 | .01160 | .01189 |
| .656 | .01160 | .01164 | .01170 | .01175 | .01183 | .01193 | .01207 | .01214 | .01245 |

[a]Allowance for 1 deg of bend; multiply value in table by number of degrees in bend

*continued on next page*

## Fabricated Sheet Metal Parts

**DIMENSIONAL TOLERANCES FOR DRAWN PARTS (In.)**

| Thickness, in.[a] ↓ | Up to 2 In. Dia | Up to 6 In. Dia |
|---|---|---|
| 1/32 | ±0.005 | ±0.008 |
| 1/16 | ±0.006 | ±0.010 |
| 3/32 | ±0.008 | ±0.012 |
| 1/8 | ±0.010 | ±0.015 |
| 1/4 | ±0.015 | ±0.020 |

[a] Gage thickness of round shell to be drawn to height of 1/2 to 3/4 shell dia. Tolerances on irregular shapes are 20% higher.

**RECOMMENDED MAXIMUM REDUCTIONS IN DRAWING (%)[a]**

| | |
|---|---|
| Low Carbon Steel | 45 |
| Austenitic Stainless Steels | 50 |
| Copper | 45 |
| High Brasses (70–30, 63–37) | 50 |
| Tin Bronze | 50 |
| Aluminum (annealed, 1/4 hard) | 45 |
| Aluminum Alloys | |
| Annealed, 5052 (1/4 hard) | 45 |
| Heat Treatable, As Quenched | 40 |
| Zinc | 40 |

[a] Ratio of inside cup diameter to blank diameter.

**PERMISSIBLE STRETCH IN STRETCH FORMING THIN-WALLED SECTIONS (%)**

| | |
|---|---|
| Aluminum Alloys | |
| 2024-O, 7075-O | 10 |
| 2024 (-O, -T or as quenched) | 6[a] |
| 6061-O, 5052-O | 25 |
| Austenitic Stainless Steels (type 301) | |
| Annealed | 20[b] |
| 1/4 Hard | 15–20 |
| 1/2 Hard | 5–10 |
| 3/4 and Full Hard | 2 |

[a] Up to 10% in the web.
[b] Up to 30% for symmetrical and rigid sections.

ing, in which case a minimum of 3/32 in. for die wall is required.

**Formed parts.** The following design rules may be applied to formed parts:

1. The height of a formed projection should be greater than 1½ times material thickness, and preferably over ⅛ in. min.

2. Bends in metals which are not soft should be made at right angles to the grain or rolling direction of the metal.

3. Because of springback, which varies with materials and tempers, angular tolerances of at least one deg are necessary (more on short projections).

4. Minimum radii obtainable in a single operation are shown in the accompanying tables.

**Drawn shapes.** In drawing or forming the force applied exceeds the elastic limit of the metal without exceeding its tensile strength, causing permanent deformation.

1. When deep draws are required (i.e., cup diameter is less than 40% of blank diameter) not only are successive draws required, but it is often necessary to anneal the metal between draws.

2. On shallow draws, radii at the bottom of the drawn shape are usually three or four times the thickness of material, and radii under flanges are four to six times the thickness of material. Large flanges make it difficult to gather metal from the outside of the blank, and several operations may be needed to achieve a comparatively shallow draw.

3. Additional operations will produce a wider range of radii, and a flatter bottom on drawn parts.

4. The punch should cover about 60% of the blank area in any single draw. This means a ratio of depth to diameter of about 45%.

5. Unless a drawn part with variation in height of ±10% of depth is satisfactory, the part will have to be trimmed. Pinch trimming can be combined with other operations, but leaves a sharp edge.

6. The bottom of a cup cannot be drawn thinner than the side walls, but ironing can make cup walls 15% thinner than the bottom. Side walls may also be partially ironed to give steps.

7. Square or rectangular drawn shapes are more costly to tool.

8. Deep parts usually require a draft of 0.0005 to 0.0025 in. per in.

9. I.d. tolerances are affected by draft and out-of-roundness; dimensions thus affected are averaged in determining whether a part meets specified tolerances.

10. Drawing slant-wall shapes, like cones, calls for a greatly increased number of operations and should be specified only when vitally necessary.

11. If aluminum, zinc, or copper drawn symmetrical shapes are required, consider impact extrusions made in presses.

### Roll Formed Shapes

Roll formed shapes have been produced from material ½ to ¾ in. thick, but usually the material used in roll forming is less than 0.125 in. thick. Roll forming machines are capable of handling sheet and strip varying in width from a fraction of an inch up to as much as 80 in., though most shapes are made from material less than 20 in. wide.

Dimensional tolerances must be comparatively liberal, primarily because of variations in the thickness of the raw material. Usually dimensional tolerances of ±0.002 in. must be allowed.

### Short Run, Press Formed Parts

In the past, stampings and press formed parts could only be considered when huge quantities of parts were required. During the past few years, however, new techniques have been developed to extend the advantages of press forming to relatively small quantities of parts. These methods utilize soft die materials (which are easily worked but have short service lives), rubber blankets, or flexible punches or dies. These materials reduce die costs sufficiently to permit amortization of costs over comparatively small quantities of finished shapes.

**RECOMMENDED LIMITATIONS FOR RUBBER PAD FORMING**

| Metal → | Heat Treatable Aluminum Alloys | | Austenitic Stainless Steels | |
|---|---|---|---|---|
| | 0 | -T | Annealed | ¼ Hard |
| Max Sheet Thickness, in. | 0.187 | 0.064 | 0.078 | 0.032 |
| Recommended Flange Width (straight, not >90 deg), in.* | 1/16+ 2.5 T | 1/8+ 4 T | 3/16+ 4.5 T | 1/8 |
| Max Metal Thickness for Forming Flanges, in. | | | | |
| Stretch Flanges | 0.125 | Special methods required | 0.050 | 0.016–0.030 |
| Lightening Hole Flanges | 0.125 | 0.064 | External 0.060, internal 0.050 | External 0.040, internal 0.030 |

*T = metal thickness.

**PERMISSIBLE STRETCH IN PRESS-DIE AND HYDROPRESS RUBBER FORMING STRETCH FLANGES (%)**

| | |
|---|---|
| Aluminum Alloys | |
| 2024 (-O or as quenched) | 18[a], 12[b] |
| 7075 (-O or as quenched) | 18,[a] 12[b] |
| 2024-T | 12[a], 8[b] |
| 7075-T | 7[a] |
| 6061-O, 5052-O | 30 |
| Stainless Steels | |
| 301, 302, 304, 305, 308 (annealed) | 40 |
| 321, 347, 316, 330 (annealed) | 30 |
| 301, 302 (¼ hard) | 25 |
| 301, 302 (½ hard) | 10 |

[a]Routed edge. [b]Sheared edge.

**Rubber pad.** In the rubber pad or Guerin process, a rubber block or pad in the head of the press is used as the second die member to form a sheet metal blank around a punch or form block.

**Flexible female die.** One method is typified by the Hydroform press, which uses a flexible diaphragm covering a cavity filled with hydraulic fluid. The other method, the Marform press, utilizes a solid rubber pad which holds the blank, while regulated hydraulic pressure allows the punch to move into the pad, forming the part.

**Flexible punch.** Water or soluble oil is used as the male die member to force the sheet metal to conform to the configuration of the female die.

**Drop hammer forming.** Zinc-base alloys and lead are normally used for the dies since their low melting points permit rapid and economical fabrication of tools. In simple drop hammer work, there is no hold-down force on the blank; therefore, commonly encountered shapes have flanges and shallow depressions rather than drawn recesses. Parts are formed rather than drawn. Relatively deep draws can occasionally be accomplished with auxiliary devices and fixtures. Reverse contours and saddleback shapes are particularly difficult to form with a drop hammer.

**RECOMMENDED SINGLE DRAW LIMITATIONS FOR MARFORM PROCESS**

| Cup Dia, in. ↓ | Max Depth of Draw at Indicated Pressure, in. | | Min Thickness, in. |
|---|---|---|---|
| | 6000 psi | 12,000 psi | |
| 1 | 1/3 | 3/4 | 0.008 |
| 2 | 2/3 | 1½ | 0.010 |
| 3 | 1 | 2¼ | 0.015 |
| 4 | 1⅓ | 3 | 0.020 |
| 5 | 1⅔ | 3¾ | 0.025 |
| 6 | 2 | 4½ | 0.030 |
| 7 | 2⅓ | 5¼ | 0.035 |
| 8 | 2⅔ | 6 | 0.040 |

**MAXIMUM CUP DEPTH IN MARFORM PROCESS***

| Metal Thickness, in. ↓ | Max Cup Depth, in. |
|---|---|
| 0.064 | 5⅛ |
| 0.050 | 4⅜ |
| 0.037 | 4¼ |
| 0.032 | 4½ |

*Based on reduction from 12-in. dia blank to 4¼-in. dia cup, 15,000 psi forming pressure.

## Patterned Sheet Metal

| Type → | Coined | Embossed | Perforated | Expanded |
|---|---|---|---|---|
| How Obtained | Cold rolling with male or female pattern engraved on hardened, forged steel roll and impressed on one side of sheet only | Cold rolling with male pattern engraved on one steel roll and matching female pattern on other, i.e., pattern is impressed three-dimensionally | High speed stamping or punching operation | Spitting and cold drawing in continuous patterns |
| Advantages | Hide marks, blemishes, scratches; reduce friction on slides, etc.; less costly than Embossed | Advantages of Coined sheet plus increased strength by redistribution of metal (see below); increased surface for heat transfer applications | Allow passage of air and light; visibility for inspection of enclosure; inexpensive | Advantages of Perforated, plus increased strength and possibility of more varied patterns |
| Remarks | No strong evidence of increased mechanical properties; often used for decorative strip with complex pattern design | Some patterns increase rigidity as much as 108%, impact resistance 39% and yield strength 92% | Mechanical strength decreased; formability increased | Openings can be varied from 1/16 to 4 in. to suit function and appearance |
| Materials | Steel, aluminum, stainless steel in sheet and strip. Copper, bronze, brass, nickel silvers in strip | Mostly stainless steel, low carbon steel, and aluminum alloys. Some strip in copper alloys; some titanium | Mostly low carbon steel, aluminum and tin | Aluminum, steel, stainless steel, monel, copper, brass |
| Sizes | Sheet: 18 to 72 in. x 6 to 24 ft x 0.025 to 0.125 in. Strip: 4 to 6.5 in. x 0.010 to 0.093 in. | 5 to 52 in. x 6–16 ft x 0.018 to 0.250 in. | Steel: 16 to 26 gage; 36 x 96 to 48 x 120 in. Aluminum: 14 and 18 gage; 36 x 96 and 36 x 120 in. | 14 to 28 gage; 36 x 72 to 48 x 120 in. |
| Patterns | Unlimited; mostly fluted, pebbled, stippled, ribbed, and stucco. Depth ranges from 0.002 to 0.015 in., generally about 0.007 in. | Large variety; mostly wood or leather grained, diamond, square, and same as coined. Depth ranges from 0.002 into corrugated patterns | Round holes and rounded end slots parallel either to width or length | Almost all diamond-shaped patterns but some woven or wire-fence type patterns |
| Uses | Decorative applications; materials handling slides; appliance, architectural and furniture trim; jewelry; fish lures | Same as Coined; heat exchangers; fluid transmission units; applications requiring greater strength than Coined | Decorative applications; ventilating panels and covers; guards; baskets; partitions and trim | Same as Perforated; grills; sound absorbent units; enclosures; automotive and aircraft uses requiring strength |

"Patterned" is used here to include coined, embossed, perforated and expanded sheet and strip.

**Advantages.** Essentially the materials are intended for decorative use. In the case of flat sheet metal used over a large area, they prevent kinking and "oil-canning." They also diffuse light, eliminating harsh highlights on polished materials, or telltale highlights on distorted materials. In some cases they provide added strength and rigidity, or allow the use of lighter gage stock. Any changes in mechanical properties depend on the particular process, material and pattern.

**Finishes.** Most sheet metal products must be finished after fabrication, usually by some type of polishing or coating. The same end result can often be achieved more economically by using patterned sheet instead. Broad decorative and protective possibilities can also be achieved by judicious use of coatings over patterns. Colored textured metal is an outstanding example; the color may be applied by coating with pigment and baking, or by vacuum metallizing.

**Design Rules.** Patterned metals can be fabricated with standard tooling used for flat sheet metals. Depending on the alloy used, the materials can be blanked, punched, formed, stamped, moderately drawn, roll formed, lock-seam joined, riveted, soldered and welded.

Only for embossed sheet is any modification of standard techniques required:

1. Die clearance should be adjusted for cross-sectional thickness.
2. Bend radii should be at least twice the cross-sectional thickness unless bend lines fall along apexes of the design.
3. For severe bends the axis of bend should run at right angles to the pattern direction.
4. Draws under 1 in. will not usually cause pattern distortion, but actual depth of draw possible depends on pattern.
5. For resistance welding, copper wire braid can be laid between electrode and embossed pattern to form a nest.

# Forgings

## Cold Headed Parts

**General.** Cold headed parts are produced in a cold header, essentially a punch press laid on its side. Wire up to about 1 in. in dia is fed into the machine where it is automatically cut to size and positioned in the die with one end protruding from the die face. This end mushrooms out under the force of a punch; the head is formed between the die and punch faces.

**Uses.** Cold headed parts are economical when mass produced. The majority are mechanical fasteners which are produced at the rate of billions per year by each manufacturer.

**Advantages.**

1. Grain of the metal follows the contours of the part, avoiding surface weakening.
2. Alloys used are tough, ductile and resistant to cracking.
3. The required corner fillets increase fatigue strength.
4. Surface finish is excellent.
5. No stock is cut away.

**Disadvantages.**

1. Part must be shaped for extraction from the die.
2. There is a limit to the head volume and shape that can be upset without annealing.
3. Internal stresses may be left at critical points.
4. Size of parts is limited by capacity of cold headers.

**Materials.** Choice of a metal depends on the heading characteristics of the metal as well as the expected end service. Low and medium carbon steels, some alloy steels and brasses, and some aluminum alloys are most common. Other materials that have been cold headed include: beryllium copper, phosphor bronze, silicon bronze, nickel silver, monel, lead, zinc, silver and gold.

**Design Rules**

1. Head must taper evenly above and below point of maximum diameter.
2. A widely-spread thin head is more difficult to form.
3. Head heights should be between ¼ and ¾ of wire diameter.
4. Recessed heads require severe forming.
5. Embossing the top of the head increases costs.
6. Concentric heads are easiest to form.
7. Fillets must be provided on corners.
8. Allowable shank reduction is 60% or less.

**Tolerances.** The best guide to tolerances on cold headed parts are the standards developed by the American Society of Mechanical Engineers for cold headed bolts, screws and rivets. In general, shank diameters are held to ±0.003 in., head dimensions to ±0.005 in., and lengths to ±1/32 in.

## Open Die Forgings

Modern open die forging employs mechanical hammers or presses. Each part is heated several times and shaped individually by a highly skilled operator; therefore production rates are low. The major advantages are simplicity of tooling and the wider range of part sizes possible. Shapes are generally simple, and tolerances are much wider than for closed die forgings.

## Closed Die Forgings

**General.** Closed die forgings are produced by shaping hot plastic metal within closed dies; processes include drop, press or upset forging.

*Drop forgings*—A hammer forces the metal into the die by a series of impact blows. Major advantage is the speed of operation. These forgings are made in weights ranging from less than an ounce to several hundred pounds.

*Press forgings*—Similar to drop forgings but produced by squeezing in mechanical or hydraulic presses. Particularly adapted to symmetrical parts requiring one or two operations.

*Upset forgings*—Also produced by squeezing, but the dies grip the stock as well as form the impression. Upset forging is a hot forming process similar to cold heading, but can be used to produce parts weighing from a few ounces up to 500 lb.

**Design rules.** Dies must shape the part in the easiest possible manner, control the direction of flow, and hold required tolerances. For a large part, several dies may be required. Die blocks are usually made from alloy steel that has been forged to provide uniform properties. Some general design rules are:

1. Divide the impression as equally as possible between the top and bottom dies.
2. Keep the parting line in one plane if possible.
3. Taper the vertical sides to allow removal of the forging.
4. Avoid sharp radii and use fillets where possible.
5. Design ribs as low and wide as possible because they require a corresponding thin pocket in the die.
6. Generous sweeps and maximum draft angles should be provided for sections having a recess because they require that a corresponding raised section be machined into the die. (Raised sections wear rapidly because they get hotter.)
7. Group multiple forgings in die in such a way as to minimize preforming and flash.
8. Where possible, forge two interdependent parts together (e.g., bevel gears and pinions) to reduce die costs and material required.
9. In ring forging, pierce the pancake in such a way that the material removed can be used to produce a smaller ring, thus saving material.

*continued on next page*

## Forgings

### SHRINKAGE AND DIE WEAR TOLERANCES*

| Length or Width, in. ↓ | Shrinkage | | Max Net Wt, lb ↓ | Die Wear | |
|---|---|---|---|---|---|
| | Commercial, in. ± | Close, in. ± | | Commercial, in. ± | Close, in. ± |
| 1 | 0.003 | 0.002 | 1 | 0.032 | 0.016 |
| 2 | 0.006 | 0.003 | 3 | 0.035 | 0.018 |
| 3 | 0.009 | 0.005 | 5 | 0.038 | 0.019 |
| 4 | 0.012 | 0.006 | 7 | 0.041 | 0.021 |
| 5 | 0.015 | 0.008 | 9 | 0.044 | 0.022 |
| 6 | 0.018 | 0.009 | 11 | 0.047 | 0.024 |
| For Each Additional Inch Add | 0.003 | 0.0015 | For Each Additional 2 Lb Add | 0.003 | 0.0015 |
| For Example: | | | For Example: | | |
| 7 | 0.021 | 0.011 | 13 | 0.050 | 0.026 |
| 12 | 0.036 | 0.018 | 21 | 0.062 | 0.031 |

*Shrinkage and die wear tolerances shall not be applied separately. They shall be applied as the sum of the two and shall be measured in such a way as to eliminate draft or variations in draft. They apply to that part of the forging formed by a single die block, and to no dimension crossing the parting plane.

### DRAFT ANGLE TOLERANCES

| Type → | Drop Forgings | | Upset Forgings | |
|---|---|---|---|---|
| | Outside, deg | Inside Holes, deg | Outside, deg | Inside Holes, deg |
| Nominal Angle | 7 | 7 or 10 | 3 | 5 |
| Commercial Limits | 0–10 | 0–13 | 0–5 | 0–8 |
| Close Limits | 0–8 | 0–8 | 0–4 | 0–7 |

### QUANTITY TOLERANCES*

| No. of Pieces on Order ↓ | Over-Run, pieces | Under-Run, pieces | No. of Pieces on Order ↓ | Over-Run, % | Under-Run, % |
|---|---|---|---|---|---|
| 1–2 | 1 | 0 | 100–199 | 10 | 5.0 |
| 3–5 | 2 | 1 | 200–299 | 9 | 4.5 |
| 6–19 | 3 | 1 | 300–599 | 8 | 4.0 |
| 20–29 | 4 | 2 | 600–1249 | 7 | 3.5 |
| 30–39 | 5 | 2 | 1250–2999 | 6 | 3.0 |
| 40–49 | 6 | 3 | 3000–9999 | 5 | 2.5 |
| 50–59 | 7 | 3 | 10,000–39,999 | 4 | 2.0 |
| 60–69 | 8 | 4 | 40,000–299,999 | 3 | 1.5 |
| 70–79 | 9 | 4 | 300,000 up | 2 | 1.0 |
| 80–99 | 10 | 5 | | | |

*Quantity tolerances shall be the permissible over or under-run allowed for each release or part shipment of an order. Any shipping quantity within the limits of over and under-run shall be considered as completing the order. Commercial and close tolerances shall be the same amounts.

### THICKNESS TOLERANCES*

| Max Net Wt, lb ↓ | Commercial, in. | | Close, in. | |
|---|---|---|---|---|
| | Minus | Plus | Minus | Plus |
| 0.2 | 0.008 | 0.024 | 0.004 | 0.012 |
| 0.4 | 0.009 | 0.027 | 0.005 | 0.015 |
| 0.6 | 0.010 | 0.030 | 0.005 | 0.015 |
| 0.8 | 0.011 | 0.033 | 0.006 | 0.018 |
| 1.0 | 0.012 | 0.036 | 0.006 | 0.018 |
| 2.0 | 0.015 | 0.045 | 0.008 | 0.024 |
| 3.0 | 0.017 | 0.051 | 0.009 | 0.027 |
| 4.0 | 0.018 | 0.054 | 0.009 | 0.027 |
| 5.0 | 0.019 | 0.057 | 0.010 | 0.030 |
| 10.0 | 0.022 | 0.066 | 0.011 | 0.033 |
| 20.0 | 0.026 | 0.078 | 0.003 | 0.039 |
| 30.0 | 0.030 | 0.090 | 0.015 | 0.045 |
| 40.0 | 0.034 | 0.102 | 0.017 | 0.051 |
| 50.0 | 0.038 | 0.114 | 0.019 | 0.057 |
| 60.0 | 0.042 | 0.126 | 0.021 | 0.063 |
| 70.0 | 0.046 | 0.138 | 0.023 | 0.069 |
| 80.0 | 0.050 | 0.150 | 0.025 | 0.075 |
| 100.0 | 0.058 | 0.174 | 0.029 | 0.087 |

*Thickness tolerances for drop hammer forgings apply to the over-all thickness measured in a direction perpendicular to the fundamental parting plane of the dies. For upset forgings, thickness tolerances apply to the metal actually enclosed and formed by the dies, measured parallel to the direction of travel of the ram.

### FILLET AND CORNER TOLERANCES*

| Max Net Wt, lb ↓ | Commercial, in. | Close, in. |
|---|---|---|
| 0.3 | 3/32 | 3/64 |
| 1.0 | 1/8 | 1/16 |
| 3.0 | 3/32 | 3/64 |
| 10.0 | 3/16 | 3/32 |
| 30.0 | 3/32 | 7/64 |
| 100.0 | 1/4 | 1/8 |

*Fillet and corner tolerances apply to all intersection surfaces, even though drawings or models indicate sharp corners. If such drawings or models have or indicate fillet or corner dimensions of larger radii than these standards, such larger dimensions shall be considered as actually specified and the tolerances shall be "special tolerances."

Where a corner tolerance applies on the meeting of two drafted surfaces, the tolerance shall apply to the narrow end of such meeting and the radius will increase toward the wide end. The total increase in the radius will equal the length of the drafted surface in inches, multiplied by the tangent of the nominal draft angle.

**Materials.** One of the principal advantages of forgings is the wide range of materials that can be employed. All materials must have these requirements in common: the forging stock (billet, bloom, bar or extrusion) must be hot workable and must be internally sound and free from surface defects. Following is a list of the major classes:

*Carbon steels*—Low carbon (up to 0.25%) forgings for moderate conditions and for carburized parts where resistance to abrasion is important. Medium carbon (0.30 to 0.50%) forgings for more severe service; some heat treatment is generally desirable. High carbon (> 0.50%) forgings for hard surfaces and springs; heat treatment is essential to obtain other desired properties.

*Alloy steels*—Manganese, nickel, nickel-chromium, molybdenum, chromium, vanadium, chromium-vanadium, tungsten, silicon-manganese. Forgings from these steels are used wherever higher strength, resistance, durability, etc., are wanted. The proper selection of a particular composition, together with its subsequent heat treatment, depends upon the particular service requirements of the part.

*Corrosion and heat resisting, and stainless, steels*—These steels are usually high in chromium or nickel, or both. The particular type of corroding agent to be encountered determines the best composition. Generally, but not necessarily, forged surfaces should be polished to obtain full benefit of corrosion resistance properties.

*Iron*—Wrought iron and ingot iron are forged for special applications where ductility is required. Wrought iron furnishes a moderate degree of corrosion resistance. The copper-bearing irons and low carbon steels are in this class.

*Copper, brasses, bronzes*—Copper forgings have extensive applications in the electrical field. The brass and bronze alloys have moderate corrosion resistance properties. Some of the bronzes have moderately high strength and good bearing properties.

*Nickel, nickel-copper alloys*—Pure nickel is forgeable. The alloy of nickel and copper known as monel metal offers a desirable combination of strength, toughness and corrosion resistance.

*Light alloys* (aluminum, magnesium)—The light alloys have about one-third the weight of steel, and some have approximately the strength of low carbon steel. Forgeable alloys are available in both the aluminum and magnesium groups.

*Titanium*—Titanium and its alloys have been forged for the production of aircraft components. Special dies are necessary and intricate forgings require more stages than steel.

**Commercial forging practice.** Impression die forgings are sold by the piece and not by the pound. It is understood without specific mention that the excess metal or flash of forgings shall be removed by trimming, and that forgings shall be free from injurious defects.

*Quantity*—The quantity specified permits standard practice limits on over-runs and under-runs.

*Size*—Forgings within commercial size limits will be furnished unless closer tolerances are specified.

*Coining or sizing*—Closer tolerances may be obtained by additional hot or cold sizing operations.

*Surfacing conditions*—Forgings are furnished in a cleaned condition obtained by tumbling, pickling or blast cleaning unless otherwise specified.

*Special requirements*—Any special requirement, such as heat treatment or special tests, should be clearly stated.

*Preparation charges*—The production of impression die forgings requires the preparation of special dies and tools which may be charged to the customer as a separate item called "preparation charges." The customer has the exclusive right to use such dies and tools, but because the full cost is generally not included in such a charge he does not have the right to remove them without additional payment. Any such dies and tools are maintained in the future without further charges to the customer.

**Tolerances.** Standard tolerances given on these pages are for forgings up to 100 lb.

Special tolerances may be specified when regular tolerances are not applicable. Regular tolerances, shown here, are classed as "Commercial Standard" and "Close Standard."

**MISMATCHING TOLERANCES***

| Weight of Part ↓ | Commercial, in. | Close, in. |
|---|---|---|
| Net Weight up to— | | |
| 1 Lb | 0.015 | 0.010 |
| 7 Lb | 0.018 | 0.012 |
| 13 Lb | 0.021 | 0.014 |
| 19 Lb | 0.024 | 0.016 |
| Each Additional 6 lb Add | 0.003 | 0.002 |
| For Example: | | |
| 37 Lb | 0.033 | 0.022 |
| 55 Lb | 0.042 | 0.028 |

*Mismatching tolerances are independent of, and in addition to, any other tolerances. Mismatching is the displacement of a point—in that part of a forging formed by one die block of a pair—from its desired position when located from the part of the forging formed in the other die block of the pair. Mismatching does not include any displacement caused by variation in thickness of the forging, but is only the displacement in a plane parallel to the main or fundamental parting plane of the dies.

# Metal Powder Parts

### General

Metal powder parts are made by compacting loose metal powders in a die and subsequently sintering the compact to form a structural part. Additional operations may be used to obtain special results.

**Materials.** Materials combinations impossible by other processes are commonplace in metal powder parts. Among the materials used are: iron, steel, stainless steel, copper, brass, bronze, monel, nickel, tin, tungsten, zirconium, graphite, and various oxides and carbides. Powders of these materials are produced by a variety of methods, the most common being reduction of oxides or ores, electrolytic deposition, atomizing, mill grinding and thermal decomposition of carbonyls.

**Advantages.** Powder metallurgy permits the use of metallic combinations that would not be possible to melt, and permits close control over structure, which may be dense or porous as desired.

**Limitations.** Metal powder parts must be of relatively simple shape because: 1) dies must permit easy removal of parts, 2) most powders have poor flow qualities, and 3) it is difficult to transmit pressures through great depths of powder. Where other considerations make it practicable, more complex shapes can be produced by using costly, intricate dies and double-acting presses. Because powder metallurgy is not capable of holding extremely close dimensional tolerances, secondary sizing or coining operations are sometimes required. Size of metal powder parts is restricted both by available press sizes and by the difficulty of transmitting pressure through powder. Initial tool costs are high. Production volumes of less than 50,000 parts are normally not economical although there are cases where 10,000 parts or less have proved feasible.

**Mixing.** The powders are mixed with alloying additives and lubricants. In rare cases (e.g., preparation of prealloyed powders) thermal treatment may be required before compacting.

**Compacting.** Compacting (or pressing) to proper density and shape requires pressures of from 5 to 50 psi in mechanical or hydraulic presses. The dies are usually made of hardened tool steel or cemented carbides and must be lapped to a high polish.

**Sintering.** This operation is performed at a temperature which is usually 70 to 80% of the melting point of the major constituent. Sintering time ranges from ½ hr to several hours. Volatile materials are driven off and, if present in quantity, can result in porosity. The furnace atmosphere must be carefully controlled to prevent oxidation.

**Infiltrating.** In this additional step, sometimes desirable, a molten metal of lower melting point than the major constituent is forced into the part under pressure, penetrating and solidifying within the pores. Infiltration increases strength by 70 to 100%.

**Other operations.** Presintering may be used before parts are machined. Coining (or sizing) is often used to provide closer tolerances and increased strength; pressures used are equal to or greater than the initial pressure. Other operations possible include machining and case or precipitation hardening. A common finishing process is the introduction of oil into the pores of bearings.

### Properties of the Powders

The properties of metal powder parts are highly dependent on the qualities of the powders used. The most important of these are:

**Purity.** Clean particle surfaces insure good contact between particles (needed for optimum mechanical properties). The presence of foreign particles must to be held to a minimum, usually specified.

**Apparent density.** Apparent density (sometimes bulk density) is the weight of a unit volume of powder and is of particular importance in the pressing operation. The lower the value, the greater the volume of powder needed for a part of given size.

**Compressibility.** The ability of a metal powder to be pressed is important for both fabrication and end properties. Compressibility (ratio of volume of loose powder to volume of compact) is affected by physical characteristics of powder particles and distribution of particle size.

**Particle size distribution.** Also called sieve analysis, this property is usually expressed as the percentage by weight of powder that can be retained on each of a series of standard sieves of decreasing size. It affects press feed, dimensional changes during sintering, porosity of the compact, and final attainable density and strength.

**Flow rate.** The ease with which a metal powder can be fed into the die is determined by its flow rate. Low flow rates slow up automatic pressing operations and may require the use of vibrating equipment.

**Sintering properties.** Sintering is usually done in an inert, reducing or neutral atmosphere, or in a vacuum. The sintering temperature of metal powders is critical; therefore, for production purposes it is desirable to have a furnace with a reasonably wide temperature range.

**Green strength.** This is the powder's ability to be handled without breakage after compacting and before sintering.

### Properties of the Parts

Mechanical and physical properties of sintered parts are closely related to the final density that can be achieved. In general, as density of a metal powder part increases, strength also increases, and at 100% density the properties theoretically will be at least equal to those of solid stock.

As yet, few standard tests for determining mechanical properties have been established, and in many cases conventional methods are not adequate. In addition, it is not feasible to give detailed information concerning strength properties because they depend on so many variables (e.g., type and size of powder, pressing pressure, sintering temperature, coining and other operations). The table included here is a rough guide to the strength ranges that can be expected with the most common metal powder formulations.

### Production Factors

Metal powder parts may be classified in order of increasing difficulty of production according to each of three factors: design, tolerances and density.

**Design classification.** I—plain circular or profiled parts, II—plain circular or profiled parts with holes,

III—parts with external flanges, IV—parts with internal flanges, V—parts requiring multiple punch motions.

**Tolerance classification.** a—wide, b—medium, c—narrow.

**Density Classification.** 1—low (below 6.3 gm per cu cm), 2—medium (from 6.3 to 7.1 gm per cu cm), 3—high (above 7.1 gm per cu cm).

Thus, difficulty in producing metal powder parts ranges from Ia1 to Vc3.

## Design Factors

**Wall thickness.** A wall as thin as 0.030 in. is possible on small parts, but a general rule calls for a minimum thickness of 0.032 in. per in. of length of the section. Large variations in section thickness are undesirable.

**Tolerances.** There are two different classes of tolerances for metal powder parts: tolerances on dimensions which are tool dependent only, and tolerances that are dependent on both press and tool (generally only the overall dimension in the pressing direction). The accompanying table illustrates that the narrowest tolerances are obtainable only if the last processing step involves a sizing or coining operation, and in some cases a precipitation hardening treatment. These narrow tolerances compare with medium grinding or broaching tolerances. Tolerances for parts that are sintered but not sized compare with medium to wide tolerances for screw machine or milled parts.

## Design Rules

1. Cylinders, squares and rectangles are the most favorable shapes. When a shape deviates from these, it is essential that it be uniform in the direction of pressing.

2. Contours must be in a plane at right angles to the direction of pressing.

3. Avoid feather or knife edges; narrow, deep splines; thin projections; and sharp corners.

4. Radii of at least 0.010 in. should be provided in corners, and edges should be given a 45-deg chamfer.

5. Length of part in pressing direction is normally limited to 3 to 6 times the cross sectional area.

6. Use inserts sparingly as they are difficult to mold in.

7. Shoulders in a solid top punch require 1 to 5 deg taper to assist removal.

8. To prevent trapping powder in an acute angle between punch and die, a small horizontal step is recommended.

9. Use flat punches for less breakdown time.

10. An acute angle for a lead-in can sometimes be produced by a coining operation.

11. Undercuts cannot be molded.

12. Parts with multiple steps should be designed with a minimum width of 0.035 in. for each step.

13. Complete spheres cannot be molded.

14. Avoid re-entrant angles.

15. If a projection is opposite the blind end, one or the other must be modified.

16. Grooves in top face of parts can be molded within following limits: 30% of total height for curved grooves, 20% for square. A 5-deg min taper is necessary on vertical sides.

17. Avoid flats on flanges requiring thin punches.

18. Avoid vertical radii on edges.

19. Joining metal powder parts offers special difficulties.

20. Corrosion protection requires special precautions.

**TOLERANCES FOR METAL POWDER PARTS**

| Final Operation ↓ | Tolerances, in. per in.[a] | | |
|---|---|---|---|
| | Narrow | Medium | Wide |
| Coining[b] | 0.0052, — | 0.00208, 0.00132 | —, 0.0052 |
| Sintering | —, — | 0.00208, 0.00326 | 0.0084, 0.0208 |
| Case Hardening | —, — | 0.00208, 0.0052 | 0.0208, 0.0208 |

[a] The first tolerance refers to dimensions which are tool-dependent only; the second to those which are both tool and press-dependent. A dash means the particular class of tolerance is not held.
[b] And possibly precipitation hardening.

**PROPERTIES OF SOME COMMON TYPES OF METAL POWDER PARTS**

| Material[a] | Composition, % | Density, gm/cu cm | Ten Str, 1000 psi | Hardness (Rockwell) | Elong (1 in.), % | Compr Yld Str, 1000 psi[b] |
|---|---|---|---|---|---|---|
| Iron | | 6.5 | 22–26 | F20–30 | 2–5 | 18–21 |
| Iron | | 7.3 | 35–38 | B15–25 | 20–28 | 29–34 |
| Iron-Copper | Cu 1.5–2.5 | 7.0 | 35 | B30–50 | 10 | 26 |
| Iron-Copper-Carbon | Cu 1.5–2.5, C 0.25–0.60 | 7.0 | 42 | B35–60 | 7 | 38 |
| Iron-Copper-Carbon | Cu 1.5–2.5, C 0.6–1.0 | 7.0 | 50 | B60–80 | 5 | 48 |
| Iron-Carbon | C 0.25–0.60 | 6.5 | 27 | B20–30 | 2 | 23 |
| Iron-Carbon | C 0.6–1.0 | 7.0 | 48 | B55–75 | 3 | 45 |
| Iron-Carbon | C 0.6–1.0 | 6.5 | 35 | B35–45 | ½ | 27 |
| Infiltrated Iron | C 0.25 | 7.3 | 65 | B55–65 | 1 | 70 |
| Infiltrated Iron | C 0.6–1.0 | 7.3 | 100 | B65–75 | 0.5 | 120 |
| Stainless Steels | 304 and 316 | 6.0–6.5 | 40–75 | F64–85 | 12–25 | — |
| Copper | | 8.3 | 26–27 | H30–40 | 16–23 | 20–22 |
| Brass | Cu 78.5, Pb 1.5 | 7.5–7.8 | 29–33 | H72 | 16–29 | 14–18 |
| Bronze | Sn 9.5–10.5 | 6.8–7.2 | 16–20 | H65–90[c] | 2–3 | 15–20 |
| Nickel Silver | | 7.5–7.8 | 23–31 | H78–80 | 7–15 | 19 |

[a] Annealed condition except bronze. [b] At 0.1% offset. [c] Depends largely on degree of cold working.

## Screw Machine Parts

### General

**Advantages.** Perhaps the greatest advantage of screw machine parts is the extreme speed at which they can be produced. Production rates can reach—and even exceed—4000 parts per hr. Extremely close tolerances can be held. Finishes are usually superior to those attained by other methods. Since bar or tube stock is used as the raw material, mechanical properties are usually high.

**Limitations.** Scrap losses are usually high because the over-all size of the bar must be as great, or greater than, the largest diameter of the part.

**Materials.** Nearly any machinable metal can be used for screw machine parts if it is available in bar or tubular form. For best results, though, the material should be free machining and should not be too soft, too hard or too stringy (since such materials make it difficult to maintain production speeds and also cause inferior surface finish). The majority of screw machine parts are made from free-machining steels, free-cutting brasses, and aluminum and magnesium alloys.

### Design Rules

Restrictions are imposed by the requirement that all parts must have surfaces of rotation that are concentric with the axis of the stock being machined. However, interior and exterior undercuts are possible, and nearly any type of thread can be produced.

Square corners are not desirable. Chamfers are preferred, but if rounded edges are desired, liberal radii should be provided. Dimensions can be held to ±0.001 to ±0.003 in. without difficulty and, when necessary, they can be as close as 0.0005 in.

Maximum size is limited, but screw machine parts can be extremely small. The range of sizes normally encountered is ¼ in. up to 8 in. in dia, and a fraction of an inch up to 6-8 in. in length.

**MACHINABILITY RATINGS (Based on AISI B1112 = 100)**

| | |
|---|---|
| **Aluminum Alloys (wrought)** | |
| 3003 | Soft |
| 2011 | Excellent |
| 2014 | Average |
| 2017 | Average |
| 2018 | Average |
| 2024 | Average |
| 6151 | Soft |
| 5052 | Soft |
| 5056 | Average |
| 6061 | Soft |
| 6063 | Soft |
| 7075 | Average |
| **Aluminum Alloys (cast)** | |
| 43 | Soft |
| 85 | Soft |
| 108 | Soft |
| 113 | Average |
| 122 | Excellent |
| 138 | Average |
| 142 | Average |
| 195 | Average |
| 212 | Average |
| 214 | Average |
| 220 | Excellent |
| 319 | Soft |
| 355 | Soft |
| 380 | Soft |
| 750 | Excellent |
| **Coppers** | |
| Copper, 99.9% | 40 |
| Electrolytic Tough Pitch | 40–50 |
| Leaded Copper | 160 |
| Oxygen-Free Copper | 40 |
| Phosphorized Copper | 40 |
| Selenium Copper | 180 |
| Tellurium Phosphorized Coppers | 180 |
| **Copper Alloys** | |
| Aluminum Bronze (alpha), 92–95% | 60–80 |
| **Copper Alloys** (cont'd) | |
| Aluminum Bronze (duplex) | 60–100 |
| Architectural Bronze, 58% | 180 |
| Beryllium Copper, 97% | 40 |
| Cartridge Brass, 70% | 60 |
| Commercial Bronze, 90%—40 | |
| Forging Brass, 60% | 160 |
| Free Cutting Brass, 61.5% | 200 |
| Gilding Bronze, 95% | 40 |
| Gun Metal (cast), 95.8% | 60 |
| High Leaded Brass, 62% | 180 |
| Leaded Commercial Bronze, 89% | 180 |
| Leaded Naval Brass, 60% | 140 |
| Leaded Nickel Silver, 46% | 160 |
| Leaded Phosphor Bronze ($B_1$) | 100 |
| Leaded Phosphor Bronze ($B_2$), 94% | 200 |
| Leaded Silicon Bronze, 95.6% | 120 |
| Low Brass, 80% | 60 |
| Low Leaded Brass, 64% | 140 |
| Manganese Bronze, 59% | 60 |
| Muntz Metal, 60% | 80 |
| Naval Brass, 60% | 60 |
| Nickel Silvers | 40 |
| Phosphor Bronze, 92% (Grades A, C, D, E) | 40 |
| Red Brass, 85% | 60 |
| Silicon Bronze, 95.8% | 60 |
| **Irons** | |
| Cast Iron | |
| Soft | 80 |
| Medium | 65 |
| Hard | 50 |
| Ingot Iron | 50 |
| **Irons** (cont'd) | |
| Malleable Iron | |
| Standard | 120 |
| Pearlitic | 80 |
| Wrought Iron | 50 |
| **Magnesium Alloys** (wrought) | 500–2000 |
| **Nickel and Its Alloys** | |
| Nickel | 20 |
| Nickel Alloys (rolled) | 40–55 |
| Monel (cast) | 35 |
| Monel (rolled) | 40–55 |
| Monel, K | 40 |
| **Screw Machine Steels** | |
| SAE 1120 (leaded) | 140 |
| SAE X1112 | 140 |
| SAE 1112 | 100 |
| SAE X1314 | 90–95 |
| SAE X1315 | 90–95 |
| SAE 1120 | 70–75 |
| SAE X1335 | 70–75 |
| SAE X1350 | 70–75 |
| **Carburizing Steels** | |
| SAE X1020 | 50–65 |
| SAE 1025 | 50–65 |
| SAE 1020 | 50–65 |
| SAE 1015 | 50–65 |
| SAE 6120 (annealed) | 45–50 |
| SAE 6115 | 45–50 |
| SAE 3115 | 45–50 |
| SAE 4615 (annealed) | 45–50 |
| SAE 2315 (annealed) | 45–50 |
| SAE 3215 | 45–50 |
| **Heat Treating Steels** | |
| SAE 1035 | 55–60 |
| SAE 1040 | 55–60 |
| **Heat Treating Steels** (cont'd) | |
| SAE 1045 (annealed) | 55–60 |
| SAE 4130 (annealed) | 40–50 |
| SAE 4140 (annealed) | 40–50 |
| SAE 3140 (annealed) | 40–50 |
| SAE 6135 (annealed) | 40–50 |
| SAE 6140 (annealed) | 40–50 |
| SAE 6150 (annealed) | 40–50 |
| SAE 1335 (annealed) | 40–50 |
| SAE 1350 (annealed) | 30–40 |
| SAE 2330 (annealed) | 30–40 |
| SAE 2345 (annealed) | 30–40 |
| SAE 3140 | 30–40 |
| SAE 2345 | 30–40 |
| SAE 52100 (annealed) | 30–40 |
| **Stainless Steels** | |
| Type 405 | 55 |
| Type 406 | 50 |
| Type 430 | 50 |
| Type 442 | 60 |
| Type 443 | 60 |
| Type 446 | 65 |
| Type 430-F | 90 |
| Type 403 | 50 |
| Type 410 | 50 |
| Type 414 | 60 |
| Type 416 | 85 |
| Type 420 | 50 |
| Type 420-F | 70 |
| Type 431 | 54 |
| Type 440 | 40 |
| Type 501 | 70 |
| Type 502 | 70 |
| Type 302 | 35 |
| Type 303 | 60 |
| Type 304 | 45 |
| Type 309 | 48 |
| Type 316 | 46 |
| Type 317 | 45 |
| Type 321 | 50 |
| Type 347 | 48 |
| **Zinc** | 200 |

## Spinnings

**ADAPTABILITY OF METALS TO SPINNING**

| Material | Shallow Spinning | Deep Spinning |
|---|---|---|
| **Group 1—Aluminum and Its Alloys** | | |
| 1100-O | 1.00 | 1.00 |
| 3003-O | 1.00 | 0.99 |
| 2024-O | 0.65 | 0.45 |
| 5052-O | 0.80 | 0.55 |
| 6061-O | 0.90 | 0.80 |
| **Group 2—Copper and Its Alloys** | | |
| Copper (cold rolled, annealed) | 1.00 | 1.00 |
| Copper (hot rolled) | 0.99 | 0.88 |
| Yellow Brass | 0.99 | 0.92 |
| Cartridge Brass, 70% | 0.99 | 0.92 |
| Low Brass, 80% | 0.96 | 0.89 |
| Red Brass, 85% | 0.90 | 0.83 |
| Commercial Bronze, 90% | 0.88 | 0.80 |
| Gilding, 95% | 0.85 | 0.75 |
| Admiralty | 0.82 | 0.70 |
| Naval Brass | 0.75 | 0.45 |
| Muntz Metal | 0.55 | 0.30 |
| Phosphor Bronze A | 0.85 | 0.40 |
| Phosphor Bronze C | 0.85 | 0.45 |
| Cupro Nickel, 30% | 0.95 | 0.65 |
| Nickel Silver A | 0.95 | 0.65 |
| Silicon Bronze | 0.94 | 0.60 |
| **Group 3—Carbon and Low Alloy Steels** | | |
| Cold Rolled (deep drawing quality) | 1.00 | 1.00 |
| Vitreous Enameling (deep drawing and spinning quality) | 1.00 | 0.95 |
| Cold Rolled (standard) | 1.00 | 0.92 |
| Hot Rolled (pickled and oiled) | 1.00 | 0.92 |
| Hot Rolled (low carbon) | 0.90 | 0.55 |
| Hot Rolled (copper-bearing) | 0.88 | 0.51 |
| Lead Coated (long terne) | 1.00 | [a] |
| Galvannealed | 1.00 | [a] |
| Galvanized | 0.90 | [a] |
| High Strength | 0.45 | 0.15 |
| Carbon (0.40% and above) | 0.25 | 0.10 |
| **Group 4—Stainless Steels** | | |
| Type 302 | 0.98 | 0.60 |
| Type 304 | 0.98 | 0.90 |
| Type 305 (free-spinning) | 1.00 | 1.00 |
| Type 309S | 0.80 | 0.45 |
| Type 316 | 0.90 | 0.60 |
| Type 321 | 0.85 | 0.50 |
| Type 347 | 0.90 | 0.50 |
| Type 430 | 0.90 | 0.50 |
| **Group 5—Nickel and Its Alloys** | | |
| Monel (spinning quality) | 1.00 | 0.90 |
| Monel (special cold rolled, soft temper) | 1.00 | 0.85 |
| Inconel | 0.90 | 0.70 |
| Nickel (low carbon) | 1.00 | 1.00 |
| Nickel | 1.00 | 0.92 |
| Multimet N-155 | 0.90 | 0.50 |
| Hastelloy A | 0.75 | 0.35 |
| Hastelloy B | 0.70 | 0.30 |
| Hastelloy C | 0.50 | 0.10 |
| **Group 6—Miscellaneous Metals** | | |
| Lead | 0.96 | 0.90 |
| Pewter | 1.00 | 0.99 |
| Zinc | 1.00 | 1.00 |
| Tantalum | 0.86 | 0.45 |
| Magnesium | 0.80 | 0.45 |
| Molybdenum | 0.55 | 0.15 |

[a] Impractical—coating flakes off.

Cold spinning is done by applying localized pressure to a rotating disk of sheet metal to draw it over a male form. The form is usually of hardwood, sometimes metal, and must be polished smooth or surface roughness will show in the finished part.

**Advantages.** Simple, economical operation for small-lot production, particularly for shapes that can be withdrawn directly from a one-piece chuck. Multi-section or offset chucks can be used.

**Limitations.** Considerable skill is required by the operator because the spinning tool (a rounded-end wood or metal tool, or roller) is held and manipulated manually. Usually there is some thinning of the material.

**Design Factors.** The tolerances held by spinning operations are often closer than for drawn parts. It is also possible to neck over collapsible forms certain parts that could not be produced by drawing or shaping in positive dies.

**Materials.** Most metals, with the exception of magnesium and molybdenum, can be cold spun. Metals such as gold, silver, platinum, Kovar, Invar and Illium can be spun but require special handling.

**Adaptability.** Adaptability of metals to the spinning process is rated in the chart given above. The unit 1.00 is assigned to the type of material in each group that lends itself most readily to cold spinning. The lower the index, the higher the cost. These figures will vary slightly with contour, gage and size.

This analysis applies to manual metal spinning by the cold method. Where quantities warrant special automatic spinning setups, or where existing automatic setups can be used, difficult-to-form metals can be deep spun readily. The deep spinning ratings in the table do not apply under these conditions.

## Mechanical Tubing

### General

Mechanical tubing is manuactured specifically for further processing into fabricated tubular products. It is of uniform high quality and produced to close tolerances. In addition, it usually has good machining qualities and relatively high finish, and is available in a wide range of materials, analyses, shapes and sizes.

The word "tubing" is used to describe several different products, including pipe and casing; however, it refers more specifically to seamless or welded tubular forms which are manufactured to closer size tolerances than pipe. Another distinction is that practically all pipe is round in section.

**Advantages.** For some parts, such as relatively long, thin-walled cylindrical objects, tubing is the only answer. On the other hand, there are many uses where tubing competes with bar, punchings, machined parts, weldments and castings. In such cases tubing may offer savings in weight, inherent structural strength, and reduction in fabricating time and costs, particularly in machining operations.

The applications of tubing are extended by its ability to be worked and fabricated into parts by many methods (e.g., bending, swaging, spinning, flaring, machining, joining). Because of this adaptability, it actually serves as a semifinished form which can be further shaped into the finished product. In many applications the forming is of such a nature that the tubing practically loses its identity as such.

**Materials.** Carbon, alloy and stainless steels; copper and copper alloys; nickel and nickel alloys; aluminum and its alloys; magnesium alloys; and titanium. In addition, specialty tubing is made from a number of other, less common materials.

**Types.** Tubing is produced either seamless or welded. Seamless has no longitudinal seam (however, seamless tubing is often joined end to end by a circumferential weld). Welded tubing is manufactured from flat stock and has a longitudinal seam. Some of the materials mentioned above can be produced only in seamless or only in welded tubing.

**Comparisons.** Seamless and welded tubing are alike in many of their characteristics, but differ in others. Welded tubing is made with relatively thin walls. Seamless is produced in a larger range of sizes and wall thicknesses, including heavy walls. Closer wall thickness tolerances can be maintained with welded tubing than with seamless.

In mechanical properties, as-welded tube is about equal to the flat stock from which it is formed. Its properties are generally lower than those of cold drawn seamless tubing because of the improvement in properties resulting from cold work. However, drawn welded tubing compares with seamless in its properties. Both welded and seamless tube are closely comparable in their forming characteristics.

**TOLERANCES FOR TITANIUM TUBING[a]**

| Diameter, in.[b] ↓ | Cold Drawn[c] | | Extruded | |
|---|---|---|---|---|
| | O. D. Tol, in. | Wall Thk Tol, % | O. D. Tol, in. | Wall Thk Tol, % |
| Up to 1½ | 0.010[d] | 10 | — | — |
| 1½ to 3½ | 0.010 | 10 | — | — |
| 3½ to 5½ | 0.015 | 10 | 0.031 | 14[e] |
| 5½ to 8 | 0.030 | 10 | 0.047 | 12.5 |
| 8 to 10¾ | — | — | 0.063 | 12.5 |

[a] Round tubing. All values ±.
[b] Range is not inclusive of higher value.
[c] Welded or seamless; also welded with weld area cold worked.
[d] Some producers state 0.005 in. here.
[e] 12.5% if wall thickness is over 0.203 in.

**Temper and finish.** Tubing of most materials is furnished in a number of different conditions or tempers to meet specific forming or service requirements. It is also normally available in at least one or two standard finishes. The finishes depend upon the material and methods of manufacture. Where required, any one of a variety of special finishes can be had on order. For example, tubing can be obtained with a special inside surface, a special outside surface, or both. For applications such as plated parts, or parts requiring exceptionally smooth, uniform surfaces, the tubing can be furnished ground and polished.

### Design Factors

**Shape.** By proper design of the part and careful selection of the shape and size of the tubing, machining and other shaping operations can be cut to a minimum. The most common shape is the round section. Square and rectangular sections are often produced as standard shapes in a wide range of sizes. The following are some of the special shapes that can be produced on order: embossed; fluted outside, plain inside; fluted; hexagon; lip; octagon; pinion (longitudinal serrations on outside); polygonal outside, plain inside; reeded; roped; rope-fluted; rope-reeded; round outside, polygonal inside; and twisted.

**Cost.** Tubing may cost more than bar stock, but savings in processing often offset additional materials cost. Thus, drilling operations can be eliminated, and drills replaced by simple, less expensive boring tools. Boring can be done faster than drilling; chucking pressures are reduced. There is also less tool wear and fewer tool changes.

**Tolerances.** Round tubing has three cross-sectional dimensions which must be considered in ordering and fabricating. They are outside diameter (o.d.),

**DIAMETER TOLERANCES FOR CARBON AND ALLOY STEEL WELDED TUBING[a]**

| Diameter, in.[b] | Wall Thickness, BWG | Cold Rolled Carbon Steel | | | | Hot Rolled Carbon Steel | | |
|---|---|---|---|---|---|---|---|---|
| | | Standard Tolerance[c] | | Close Tolerance[d] | | Standard Tolerance[c] | | Close Tolerance[c] |
| | | O.D., in. | I.D., in. | O.D., in. | I.D., in. | O.D., in. | I.D., in. | O.D., in. |
| ¼ to ⅜ | 22 to 14 | 0.0025 | 0.009 | — | — | — | — | — |
| | 20 to 14 | — | — | 0.002 | 0.005 | — | — | — |
| | 16 to 14 | — | — | — | — | — | — | 0.002 |
| ⅜ to ½ | 22 to 16 | 0.003 | 0.005 | — | — | — | — | — |
| | 20 to 12 | — | — | 0.0025 | 0.0025 | — | — | — |
| | 16 to 12 | — | — | — | — | — | — | 0.0025 |
| | 14 to 12 | 0.003 | 0.009 | — | — | — | — | — |
| ½ to 1⅛ | 22 to 14 | 0.0035 | 0.005 | — | — | — | — | — |
| | 20 to 11 | — | — | 0.0025 | 0.0025 | — | — | — |
| | 16 to 11 | — | — | — | — | 0.0035[f] | 0.012[f] | 0.0025 |
| | 13 to 11 | 0.0035 | 0.008 | — | — | — | — | — |
| 1⅛ to 2 | 22 to 14 | 0.005 | 0.006 | — | — | — | — | — |
| | 20 to 9 | — | — | 0.003 | 0.003 | — | — | — |
| | 16 to 14 | — | — | — | — | 0.005 | 0.010 | — |
| | 16 to 9 | — | — | — | — | — | — | 0.003 |
| | 13 to 9 | 0.005 | 0.008 | — | — | — | — | — |
| | 13 to 7 | — | — | — | — | 0.005 | 0.015 | — |
| 2 to 2½ | 20 to 14 | 0.006 | 0.007 | — | — | — | — | — |
| | 20 to 9 | — | — | 0.004 | 0.004 | — | — | — |
| | 16 to 14 | — | — | — | — | 0.006 | 0.012 | — |
| | 16 to 9 | — | — | — | — | — | — | 0.004 |
| | 13 to 9 | 0.006 | 0.009 | — | — | — | — | — |
| | 13 to 6 | — | — | — | — | 0.006 | 0.016 | — |
| 2½ to 3 | 20 to 18 | 0.008 | 0.012 | — | — | — | — | — |
| | 18 to 9 | — | — | 0.005 | 0.005 | — | — | — |
| | 16 to 14 | — | — | — | — | 0.008 | 0.012 | — |
| | 16 to 9 | 0.008 | 0.010 | — | — | — | — | 0.005 |
| | 13 to 4 | — | — | — | — | 0.008 | 0.016 | — |
| 3 to 3½ | 20 to 9 | 0.009 | 0.012 | — | — | — | — | — |
| | 16 to 14 | — | — | — | — | 0.009 | 0.015 | — |
| | 13 to 4 | — | — | — | — | 0.009 | 0.020 | — |
| 3 to 4 | 18 to 8 | — | — | 0.006 | 0.006 | — | — | — |
| | 16 to 8 | — | — | — | — | — | — | 0.006 |
| 3½ to 4 | 20 to 8 | 0.010 | 0.015 | — | — | — | — | — |
| | 16 to 14 | — | — | — | — | 0.010 | 0.017 | — |
| | 13 to 4 | — | — | — | — | 0.010 | 0.021 | — |
| 4 to 5 | 16 to 14 | 0.020 | 0.020 | — | — | 0.020 | 0.022 | — |
| | 13 to 8 | 0.015 | 0.018 | — | — | — | — | — |
| | 13 to 4 | — | — | — | — | 0.015 | 0.026 | — |

[a] Round tubing. All values are ±.
[b] Range is not inclusive of lower value.
[c] Flash controlled to 0.005-in. max.
[d] Mandrel flash removed.
[e] Without mandrel. Same values hold for cold rolled close tolerance without mandrel.
[f] Diameter range for this tolerance is actually ¾ to 1½ in.

inside diameter (i.d.), and wall thickness or gage. In seamless and drawn welded tubing each of the dimensions may vary independently; therefore it is important to have a knowledge of the tolerances to which the tubing is manufactured. This information can be found in the accompanying tables.

*continued on next page*

## Mechanical Tubing

**WALL THICKNESS TOLERANCES FOR CARBON AND ALLOY STEEL WELDED TUBING[a]**

| Wall Thickness | | Wall Thickness Tolerance, in.[b] | |
|---|---|---|---|
| BWG | In. | Cold Rolled | Hot Rolled |
| 22 | 0.028 | +0.000, −0.003 | — |
| 20 | 0.035 | +0.000, −0.004 | — |
| 18 | 0.049 | +0.000, −0.004 to −0.005 | — |
| 16 | 0.065 | +0.000 to +0.002, −0.004 to −0.007 | +0.002, −0.006 to −0.010 |
| 14 | 0.083 | +0.000 to +0.002, −0.004 to −0.007 | +0.002 to +0.003, −0.006 to −0.012 |
| 13 | 0.095 | +0.000 to +0.002, −0.004 to −0.007 | +0.002 to +0.003, −0.006 to −0.012 |
| 12 | 0.109 | +0.000 to +0.003, −0.006 to −0.009 | +0.002 to +0.005, −0.006 to −0 012 |
| 11 | 0.120 | +0.000 to +0.003, −0.006 to −0.009 | +0.002 to +0.005, −0.008 to −0.012 |
| 10 | 0.134 | +0.000 to +0.003, −0.006 to −0.009 | +0.002 to +0.005, −0.008 to −0.012 |
| 9 | 0.148 | +0.000 to +0.003, −0.006 to −0.009 | +0.002 to +0.005, −0.008 to −0.012 |
| 8 | 0.165 | +0.000 to +0.003, −0.007 to −0.010 | +0.002 to +0.005, −0.008 to −0.012 |
| 7 | 0.180 | — | +0.002 to +0.005, −0.008 to −0.012 |
| 6 | 0.203 | — | +0.002 to +0.005, −0.010 to −0.013 |
| 5 | 0.220 | — | +0.002 to +0.005, −0.010 to −0.013 |
| 4 | 0.238 | — | +0.002 to +0.006, −0.010 to −0.018 |
| — | 0.250 | — | +0.006 to −0.018 |

[a] Round tubing.
[b] Ranges are given because tolerance varies with o.d.

**TOLERANCES FOR CARBON AND ALLOY STEEL SEAMLESS TUBING[a,b]**

| Diameter, in.[c] | Finish Annealed | | Soft Annealed | |
|---|---|---|---|---|
| | O.D. Tol, in. | I.D. Tol, in. | O.D. Tol, in. | I.D. Tol, in. |
| 5/16 to 1/2 | ±0.004[e] | — | +0.006, −0.002 | — |
| 1/2 to 1 1/2 | +0.005[d,e,f] | −0.005[d,e,f] | +0.008,[d,e,f] −0.002 | +0.002,[d,e,f] −0.008 |
| 1 1/2 to 3 1/2 | +0.010[d,e,f] | −0.010[d,e,f] | +0.015,[d,e,f] −0.005 | +0.005,[d,e,f] −0.015 |
| 3 to 5 1/2 | +0.015[d,f] | +0.005,[d,f] −0.015 | +0.023,[d,f] −0.007 | +0.015,[d,f] −0.025 |
| 5 1/2 to 8 | ±0.030[f,g] | ±0.035[f,g] | ±0.060[f,g] | ±0.070[f,g] |
| | ±0.020[h] | ±0.025[h] | ±0.040[h] | ±0.050[h] |
| | +0.030[d] | +0.015,[d] −0.030 | +0.045,[d,i] −0.015 | +0.037,[d,i] −0.053 |
| 8 to 10 3/4 | ±0.045[f,g] | ±0.050[f,g] | — | — |
| | ±0.035[h] | ±0.040[h] | — | — |
| | +0.045[d,i] | +0.015,[d,i] −0.040 | — | — |

[a] Applies to round cold finished tubing. Wall thickness tolerance is 10% except 15% for 3/16 to 1/2 in. dia.
[b] O.d. tolerances for hot finished tubing: ±0.023 for dia up to 3 1/2 in.; ±0.031 for 3 to 5 1/2 in.; ±0.047 for 5 1/2 to 10 3/4 in. Wall thickness tolerances for hot finished tubing: ±16.5% for wall thickness less than 0.109 in.; ±15% for 0.110 to 0.172 in.; ±14% for 0.173 to 0.203 in.; 12.5% for thicker walls.
[c] Below 8 in., ranges are not inclusive of higher figure.
[d] For tubes which cannot be successfully drawn over a mandrel (often true of those with: 1) i.d. <50% of o.d., 2) wall >25% of o.d., 3) wall >1 1/4 in. thk, 4) weight >90 lb per ft), i.d. tolerance is ±10% of the wall thickness and wall thickness tolerance is 12%.
[e] For certain other tubes which are not commonly drawn over a mandrel (specifically, those with i.d. <1/2 in., or with i.d. <3/4 in. when wall thickness >20% of o.d.), the wall thickness tolerance is 15% and the i.d. is governed by the standard tolerances for o.d. and wall thickness.
[f] Tubes with wall <3% of o.d. cannot be straightened properly without distortion and require an additional ovality tolerance of ±1/2% for the o.d. and i.d.
[g] When wall <5% of o.d. [h] When 5% of o.d. < wall < 7.5% of o.d. When wall >7.5% of o.d.

**TOLERANCES FOR STAINLESS STEEL TUBING[a]**

| Diameter, in.[b] | Diameter Tolerances[c] | | | Wall Thk, in. | Wall Thk Tol for Welded Tubing, in.[d,e] |
|---|---|---|---|---|---|
| | Seamless O.D. Tol, in. | Welded | | | |
| | | O.D. Tol, in. | I.D. Tol, in. | | |
| Up to 1/32 | 0.005 | 0.001 | 0.001 | 0.025 | 0.002-0.003 |
| 1/32 to 1/16 | 0.005 | 0.0015 | 0.0015 | 0.032 | 0.003-0.004 |
| 1/16 to 1/2 | 0.005 | 0.003 | 0.005 | 0.035 | 0.003-0.005 |
| 1/2 to 1 | 0.005 | 0.004 | 0.006 | 0.042 | 0.003-0.005 |
| 1 to 1 1/2 | 0.005 | 0.005 | 0.007 | 0.049 | 0.003-0.005 |
| 1 1/2 to 2 | 0.010 | 0.006 | 0.008 | 0.058 | 0.004-0.006 |
| 2 to 2 1/2 | 0.010 | 0.007 | 0.010 | 0.065 | 0.005-0.006 |
| 2 1/2 to 3 1/2 | 0.010 | 0.010 | 0.014 | 0.072 | 0.005-0.007 |
| 3 1/2 to 5 | 0.015 | 0.015 | 0.020 | 0.083 | 0.005-0.007 |
| 3 1/2 to 5 1/2 | 0.015 | — | — | 0.095 | 0.005-0.007 |
| 5 1/2 to 8 | 0.030 | — | — | 0.109 | 0.005-0.007 |
| 8 to 8 5/8 | 0.045 | — | — | 0.120 | 0.005-0.007 |
| | | | | 0.134 and over | 0.007-0.008 |

[a] Round tubing; annealed or as cold finished. All values are ±. [b] Ranges are not inclusive of upper values.
[c] Tolerances are general and subject to limitations by D/t ratio. Ovality tolerance is generally double the o.d. tolerance.
[d] Tolerance for seamless is ±10%; 15% when o.d. <1/2 in. [e] Ranges are given because tolerance varies with o.d.

### TOLERANCES FOR NICKEL AND NICKEL ALLOY SEAMLESS TUBING[a]

| Dia, in. | Dia Tol, in.[b,c] | Wall Thk Tol, %[b] |
|---|---|---|
| **Monel, A Nickel, Low Carbon Nickel** | | |
| Up to 3/8 | +0.005 | 12.5 |
| 3/8 to 1 1/2 | 0.005 | 10 |
| 1 1/2 to 4 1/2 | 0.010 | 10 |
| 4 1/2 to 6 | 0.015 | 12.5 |
| 6 to 7 1/2 | 0.020 | 12.5 |
| 7 1/2 to 8 3/8 | 0.025 | 12.5 |
| **Inconel, Inconel X, K Monel, Incoloy** | | |
| Up to 3/8 | 0.005 | 15 |
| 3/8 to 1 1/2 | 0.0075 | 10 |
| 1 1/2 to 3 1/2 | 0.010 | 10 |
| 3 1/2 to 4 1/2 | 0.015 | 10 |
| 4 1/2 to 6 | 0.020 | 12.5 |
| 6 to 6 3/8 | 0.025 | 12.5 |

[a] Round cold drawn. All tolerances ± except where otherwise indicated. Tolerances given here are applicable only to two dimensions at a time. Diameter ranges are not inclusive of lower values.
[b] The following applies only to tubes which cannot be successfully drawn over a mandrel: 1) If i.d. < 50% of o.d., the i.d. tolerance is ±10% of the wall thickness and the wall thickness tolerance is 12 1/2% for alloys in top part of table, 15% for others; 2) if i.d. < 1/8 in., the i.d. will be governed by standard tolerances for o.d. and wall thickness.
[c] Tubes with wall < 3% of o.d. cannot be straightened properly without distortion and require an additional ovality tolerance of ± 1/2% for the o.d. and i.d. Tubes furnished in soft annealed temper may possess ovality because of warpage during annealing or straightening and will not have tolerances as close as table indicates.

### TOLERANCES FOR SMALL DIAMETER TUBING[a]

| Dia, in.[b] | O.D. Tol, in. | I.D. Tol, in. |
|---|---|---|
| Up to 1/32 | +0.002 | −0.002 |
| 1/32 to 1/16 | +0.003 | −0.003 |
| 1/16 to 1/8 | +0.004 | −0.004 |
| 1/8 to 1 1/2 | +0.005 | −0.005 |

[a] Wall thickness tolerance is ±10%. These tolerances are general; suppliers specialising in particular materials or sizes often hold closer tolerances for standard tubing.
[b] Range is not inclusive of higher value.

### TOLERANCES FOR COPPER AND COPPER ALLOY SEAMLESS TUBE[a]

| Dia, in.[d] | Mean Diameter Tolerances, in.[b] | | Wall Thickness, in.[c] | Wall Thickness Tolerances, in.[c] | |
|---|---|---|---|---|---|
| | Nonrefractory | Refractory | | Nonrefractory | Refractory |
| Up to 1/8 | 0.002 | 0.0025[f] | Up to 0.018 | 0.001 −0.002 | 0.0015–0.0025 |
| 1/8 to 3/8 | 0.002 | 0.0025 | 0.018 to 0.025 | 0.002 −0.003 | 0.0025–0.004 |
| 3/8 to 1 | 0.0025 | 0.003 | 0.025 to 0.035 | 0.0025–0.004 | 0.003 −0.005 |
| 1 to 2 | 0.003 | 0.004 | 0.035 to 0.058 | 0.003 −0.007 | 0.004 −0.009 |
| 2 to 3 | 0.004 | 0.005 | 0.058 to 0.083 | 0.0035–0.010 | 0.0045–0.013 |
| 3 to 4 | 0.005 | 0.006 | 0.083 to 0.120 | 0.004 −0.011 | 0.005 −0.014 |
| 4 to 5 | 0.006 | 0.008 | 0.120 to 0.165 | 0.005 −0.012 | 0.007 −0.015 |
| 5 to 6 | 0.007 | 0.009 | 0.165 to 0.220 | 0.007 −0.014 | 0.009 −0.018 |
| 6 to 8 | 0.008 | 0.010 | 0.220 to 0.284 | 0.009 −0.016 | 0.012 −0.020 |
| 8 to 10 | 0.010 | 0.013 | 0.284 to 0.380 | 0.011 −0.018 | 0.015 −0.023 |
| | | | 0.380 and over | 5–6% | 6–8% |

[a] Round tubing. All values are ±.
[b] Tolerances apply to i.d. or o.d. except where otherwise indicated.
[c] Maximum deviation at any point; range indicates variation with o.d.
[d] Ranges are not inclusive of lower values. [e] Ranges are not inclusive of upper values.
[f] O.d. only; value for i.d. is 0.003 in.

### TOLERANCES FOR EXTRUDED AND DRAWN ALUMINUM TUBING[a]

| Diameter, in.[b] | Diameter Tol, in. | | Wall Thk, in. | Wall Thk Tol, in.[c] | |
|---|---|---|---|---|---|
| | Drawn | Extruded | | Drawn | Extruded |
| Up to 1/2 | 0.003 | — | Up to 0.047 | — | 0.006 |
| 1/2 to 1 | 0.004 | 0.010 | 0.010 to 0.035 | 0.002 | — |
| 1 to 2 | 0.005 | 0.012 | 0.036 to 0.049 | 0.003 | — |
| 2 to 3 | 0.006 | 0.015 | 0.047 to 0.061 | — | 0.007–0.010 |
| 3 to 4 | 0.008 | 0.015 | 0.062 to 0.077 | — | 0.008–0.012 |
| 4 to 5 | 0.008 | 0.025 | 0.050 to 0.083 | 0.004 | — |
| 5 to 6 | 0.010 | 0.025 | 0.078 to 0.124 | — | 0.009–0.015 |
| 6 to 8 | 0.015 | 0.035 | 0.084 to 0.120 | 0.005 | — |
| 8 to 10 | 0.020 | 0.045 | 0.121 to 0.203 | 0.006 | — |
| 10 to 12 | 0.025 | 0.055 | 0.125 to 0.249 | — | 0.009–0.020 |
| 12 to 12.875 | — | 0.065 | 0.204 to 0.300 | 0.008 | — |
| | | | 0.250 to 0.374 | — | 0.011–0.025 |
| | | | 0.301 to 0.375 | 0.015 | — |
| | | | 0.375 to 0.499 | — | 0.015–0.035 |
| | | | 0.376 to 0.500 | 0.020 | — |
| | | | 0.500 to 2.000 | — | 0.020–0.075 |

[a] Round tubing. All values are ±.
[b] Range is inclusive of upper value for drawn tubing, lower for extruded.
[c] Allowable deviation of mean from specified wall thickness.

### TOLERANCES FOR EXTRUDED MAGNESIUM TUBING[a]

| Dia, in.[b] | Mean Dia Tol, in. | Wall Thickness, in[b] | Mean Wall Thk Tolerance, in. | | |
|---|---|---|---|---|---|
| | | | O.D. to 2.99 | O.D. 3.00–4.99 | O.D >5.00 |
| Up to 1/2 | 0.008 | Up to 0.062 | 0.007 | 0.008 | 0.010 |
| 1/2 to 1 | 0.010 | 0.063 to 0.124 | 0.008 | 0.010 | 0.015 |
| 1 to 2 | 0.012 | 0.125 to 0.249 | 0 009 | 0.013 | 0.020 |
| 2 to 4 | 0.015 | 0.250 to 0.374 | 0.011 | 0.016 | 0.025 |
| 4 to 6 | 0.025 | 0.375 to 0.499 | 0.015 | 0.021 | 0.035 |
| 6 to 8 | 0.035 | 0.500 to 0.749 | 0.020 | 0.028 | 0.045 |
| 8 to 10 | 0.045 | 0.750 to 0.999 | — | 0.035 | 0.055 |
| 10 to 12 | 0.055 | 1.000 to 1.499 | — | 0.045 | 0.065 |

[a] Round. All values are ±. [b] Ranges are not inclusive of higher values.

## Wire Parts, Forms and Assemblies

**Advantages.** Wire forms, ranging from simple bent or ended wire to welded wire assemblies, are used in original design as well as to replace stampings, castings and forgings. In addition to the extreme design adaptability, wire forms offer economy, resiliency, lightness and decoration.

**Materials.** Although basic steel wire is used for the majority of wire forms, any material which can be drawn into wire may be used. Special types of steel wire include: galvanized (rust protection), Bethanized (rust and corrosion protection), coppered or tinned (attractive finish at low cost), spring wire (added stiffness and tensile strength), stainless steel (electropolished), and Copperweld, Nickelply and Copperply for special applications. Standard nonferrous metals include: monel, copper, bronze, brass and nickel silver. Special metals used are: aluminum, tungsten and molybdenum.

**Sizes.** Wire diameters from 0.035 in. (20 gage) to 0.375 in. (⅜ in.) are usually suitable for most wire form designs. Sizes as large as 0.5 in. or as small as 0.0015 in. are sometimes required. Etched wire is produced in sizes down to 0.00012 in.

**Finishes.** Wire products may be finished by electroplating, enameling or lacquering. The most popular plated finishes are: nickel, chromium, brass, cadmium and zinc. Special finishes include: anodized aluminum, plastics coating, and a black oxidized finish applied over zinc plate.

**Parts and Forms.** In addition to the parts and forms discussed below, drawings on this page illustrate standard wire end treatments.


*Eyes and ears*—Eyes are formed in plain or teardrop shapes by plain or centered bends. Ears may be formed on one or both sides.

*Upset pins*—Standard pins are produced from wire of 0.010 to 0.125 in. dia, of any workable alloy and in various head shapes. If both a flange and head, or two or more flanges, are required, at least 0.070 in. spacing between adjacent faces is desirable.


*Wire threadings*—Threads can be rolled or cut. Rolled thread has these advantages: less expensive; faster forming; no special fixtures; smaller dia wire required; chamfered end not necessary for easy starting. Cut thread has these advantages: stock size larger (or equal to) o.d. of thread; thread length not limited; can have chamfered end.

*Formed rings*—Rings may be formed on a wire ring coiler or a four-slide machine. Those formed on the slide machine do not butt perfectly; they are made from wire of 1/16 to 5/16-in. dia and in ring diameters of 1/2 to 2-in. i.d. Both flat and offset rings may be formed on the wire coiler. Wire diameter ranges from 1/16 to 5/16 in. and ring diameter from 5/8 to 3-in. o.d. Spiral rings are generally offset about one wire thickness.


**Welded wire assemblies.** For attaching wire together, or wire to strip, the most efficient operation is resistance spot welding. It is preferable that welds occur where two wires cross each other at right angles.




***Wire end treatments***




***Welded wire joints***



***Typical wire forms and welded assemblies***

# Plastics Parts

The form in which plastics materials should be specified is largely determined by the nature of the material. Plastics resins are either thermoplastic or thermosetting in nature. Thermoplastic resins soften and flow when heated and harden when cooled. For moldings, the polymer is usually supplied in granular form. After being heated to the fluid state it is charged to the mold or die, where it cools and hardens.

Thermosetting plastics do not soften when heated, but gradually lose properties as temperature increases, until they char and disintegrate. For moldings, thermosetting resins are usually supplied in a partially polymerized granular form, usually with some type of fibrous reinforcement. They flow to a limited degree on initial heating, but as heating continues they polymerize completely and cure to a hard infusible state.

## Molded Parts

**Injection molded parts.** The injection molding process for plastics is similar in nature to the die casting process for metals. A thermoplastic molding compound is heated to plasticity in a cylinder at a controlled temperature and forced under a pressure of 10,000 to 50,000 psi through sprue, runners and gates into a cool single or multiple cavity mold. The resin solidifies rapidly, the mold is opened, and the part or parts ejected.

The primary advantage of the process, as is the case with die castings, is the relatively low cost per part. Multiple cavity molds can often be used. The cycle is rapid, since parts can be removed from the mold as soon as they solidify sufficiently.

In some cases modifications of the injection molding process can be used to mold small parts of thermosetting resins. These processes are called jet, flow or offset injection molding. They make use of the fluid state of thermosetting molding materials before complete polymerization. The process is suitable only for relatively small parts, and is one that requires careful control of processing variables, such as temperature.

**Compression molded parts.** Compression molding is primarily used to mold thermosetting plastics, though in some instances it can be used economically to mold thermoplastics, e. g., vinyl phonograph records. Thermoplastic materials cannot usually be preformed, but are charged as powder or granules.

In compression molding, a partially polymerized thermosetting resin, usually in the form of a preform made from powder or granules, is placed in the heated mold cavity. The mold is closed, heat and pressure are applied, and the material flows and fills the mold cavity. The heat then fully polymerizes the material before the mold is opened and the part removed.

In the case of thermoplastic materials, heating softens the polymer, which flows and fills the mold. Then the mold is cooled and the part solidifies.

Less material is required for compression molding than for injection or transfer molding, since the material is placed directly in the mold, and no sprues, runners or gates are required. With thermosetting resins, the cycle is longer than in injection molding, since the part must be cured in the mold.

**Cold molded parts.** Cold molding is similar to compression molding in that it makes use of a split, or open, mold in which the material is charged. It differs from compression molding in that it uses no heat—only pressure on the order of 2000 to 12,000 psi. After the part is removed from the mold it is placed in an oven to cure to its final state.

Materials used for cold molding are classified as nonrefractory (organic) and refractory (inorganic). Organic types consist of binders — such as asphalts, oil derivatives and residues, and gum or resin solutions — and fillers, such as asbestos fibers and silica and magnesia compounds. Inorganic types consist of binders — such as cement, lime or silica — and fillers, such as asbestos.

Cold molded parts are primarily used for electrical components. The materials have excellent electrical insulating properties, as well as resistance to moisture and heat.

**Transfer molded parts.** Transfer molding of thermosetting materials is roughly analogous to injection molding of thermoplastics. The thermosetting molding compound is heated to plasticity in a transfer chamber, and is then fed to the mold cavity (or cavities) through sprue, runners and gates. After the mold is filled, heat is maintained for a predetermined period of time to fully polymerize and cure the part.

In comparison with compression molding, transfer molding is particularly advantageous where thin sections or delicate inserts are used. Since the design of runners and gates permits some control over where the material is to be fed to the mold, flow of the material can be more closely controlled than in compression molding. Also, closer tolerances can usually be held on transfer molded parts. On the other hand, transfer molds are usually more elaborate than compression molds, and there is a loss of material in the cull and sprue. Size of transfer molded parts is somewhat limited.

**Design factors.** Though it is difficult to generalize about design factors for injection, compression and transfer moldings, the following factors should be considered:

*Shrinkage*—Allowance must be made for shrinkage of the molding compound in design of the part. In addition to affecting dimensional accuracy of the part, shrinkage can introduce internal stress which may make the part unserviceable. Shrinkage values for the various plastics are given in the data sheets in Section 5 of this issue.

*Wall thickness*—Strength required both in service and during manufacture must be considered in designing wall thickness. In thermosetting materials, walls less than 0.062 in. thick are extremely difficult to obtain, and a minimum of 0.125 in. is preferred (see accompanying table).

*Draft*—A draft taper in deep drawn parts, in addition to making it easier to remove a part from the mold, creates a wedging action as the the mold is closed. When thermosetting materials are compression molded, converging tapers increase the density of the plastic in the upper sections. There are no precise formulas for taper, but the most liberal taper the design can allow should be provided. Tapers of less than 1 deg can be used for deep parts; e.g., television cabinets 6 to 24 in. deep have been molded with tapers as small as 0.001 in. per in.

*Tolerances*—A high degree of accuracy in molded parts is expensive to achieve. On small shapes, tolerances as close as $\pm 0.002$ in. are possible. When

## Plastics Parts

size is increased to a few inches, over-all tolerances increase to approximately ±0.005 in. On large pieces, tolerances of about ±0.001 to 0.002 in. per in. are obtainable. Tolerances closer than actually mandatory should not be specified; as specified accuracy increases, cost increases disproportionately.

**Design Rules.**

1. Use sufficient draft on long thin shapes to permit their withdrawal from the mold.

2. Minimize coring. When cores are used they should be easy to withdraw.

3. Avoid internal and external undercuts; they make withdrawal of parts difficult and require considerably more expensive molds.

4. Provide ample fillets on inside corners, and avoid sharp external edges and corners except at the parting line of the die.

5. Avoid large flat areas. Dappling or otherwise breaking up the surface is recommended.

6. Keep tolerances as liberal as possible. Excessively close tolerances add to cost because of increased die costs and high rejection rate.

7. Avoid abrupt changes in wall thickness.

8. Locate parting lines so that flash can be removed easily without marring surrounding areas.

9. Locate holes for easy coring.

10. Use ribs to achieve desired strength and stiffness. Ribs permit materials savings by reducing section thickness.

11. Use inserts for threaded holes where high stresses are anticipated or where considerable wear is to be encountered. Round inserts are preferred.

**WALL THICKNESS OF MOLDED PARTS (In.)**

| Material ↓ | Minimum | Small Parts | Average | Large Parts |
|---|---|---|---|---|
| THERMOSETTING | | | | |
| Phenolics | | | | |
| General Purpose & Flock-Filled | 0.050 | 0.062 | 0.125 | 0.187–1.000 |
| Fabric-Filled | 0.062 | 0.125 | 0.187 | 0.187–0.375 |
| Mineral-Filled | 0.125 | 0.125 | 0.187 | 0.200–1.000 |
| Alkyd | | | | |
| Glass-Filled | 0.040 | 0.093 | 0.125 | 0.187–0.500 |
| Mineral-Filled | 0.040 | 0.125 | 0.187 | 0.187–0.375 |
| Ureas, Melamines | | | | |
| Cellulose-Filled | 0.035 | 0.062 | 0.100 | 0.125–0.187 |
| Fabric-Filled | 0.050 | 0.125 | 0.125 | 0.125–0.187 |
| Mineral-Filled | 0.040 | 0.093 | 0.187 | 0.187–0.375 |
| THERMOPLASTIC | | | | |
| Acrylics | 0.025 | 0.035 | 0.093 | 0.125–0.250 |
| Cellulose Acetate | 0.025 | 0.050 | 0.075 | 0.125–0.187 |
| Cellulose Acetate Butyrate | 0.025 | 0.050 | 0.075 | 0.125–0.187 |
| Ethyl Cellulose | 0.035 | 0.050 | 0.062 | 0.093–0.125 |
| Polyamide | 0.015 | 0.025 | 0.060 | 0.093–0.125 |
| Polyethylene | 0.035 | 0.050 | 0.062 | 0.093–0.125 |
| Polystyrene | 0.030 | 0.050 | 0.062 | 0.125–0.250 |
| Polyvinyl Chloride | 0.093 | 0.062 | 0.093 | 0.125–0.250 |

### Castings

**Materials.** Any resin available in liquid form can be cast. Castable resins include phenolics, polyesters, epoxies, silicones and acrylics.

**Types of molds.** The type of mold used depends on the plastic, the size and shape of the part, and other design considerations.

*Draw mold*—No undercut is possible. Flutes and scallops must run in the direction of removal. Taper must be provided to break the vacuum and reduce friction. Castings are removed by force, and minimum wall thickness is critical, running from 1/8 in. on tiny parts to 3/16 in. on parts the size of radio cabinets.

*Split mold*—Undercuts may be provided if they do not prevent release from the separate parts of the mold. Minimum wall thickness is 3/16 in., and parts less than 0.1 lb are not commonly produced economically.

*Cored mold*—This type allows complexity of design, but is not usually feasible from a cost standpoint for parts less than 4 x 4 x 4 in. Molds require no taper. Minimum wall thickness is 3/16 in. Mold shrinkage allowance must be considered. Extremely large parts may be cast.

*Flexible mold*—Model may be constructed of wood, porcelain, metal, etc. Mold is of plaster with a lining of rubber latex or an elastomeric plastic. Epoxy materials may be cast in flexible molds, but most polyesters react with the lining material. Although parts cast in rubber molds cannot be held to the tolerances possible with matched metal molds, a reasonable degree of accuracy is reproducible. For example, on cast phenolic parts dimensions can be held to about ±0.004 in. per in. The degree of accuracy obtainable on any part depends on the oversize allowance used in making the master pattern, the care with which the pattern is made, and the degree of accuracy attained in calculating amount of shrinkage during cure of the rubber mold and the cast resin.

### Extrusions

In many cases, extruded parts are competitive with molded parts. Where many parts are required with a complicated cross section in one plane, the cross section can be produced by extrusion, and the parts formed by rapid, automatic cut-off to shape.

**Thermoplastics.** In extruding a thermoplastic, the molding powder is fed through a hopper to a chamber in which it is heated to plasticity at a controlled temperature. The plastic powder is then driven, usually by a rotating screw, through a die having the shape of the desired cross section. The process is continuous and is used to produce tube, rod, film and sheet, as well as other continuous shapes.

**Thermosets.** Reinforced thermosetting tube and rod can be produced by an extrusion process. The reinforcing fibers are fed continuously through a bath of liquid thermosetting resin and then through a die of the desired cross section. The extruded shapes then pass through a cylinder held at a controlled temperature to polymerize and cure the thermosetting resin. Extrusion speed must be relatively slow to provide sufficient time for complete cure.

### Thermoplastic Sheet Formed Parts

**Materials.** A variety of shapes and forms can be produced by thermoforming calendered, cast or extruded thermoplastic sheet. The materials that lend themselves to this method of forming include polystyrene and modified polystyrenes, acrylics, cellulose acetate and cellulose acetate butyrate, vinyl polymers and copolymers, and polyethylene. Use of this type of molding has grown with the development of relatively low cost extruded sheet to replace more expensive cast or calendered materials.

**Methods.** Essentially, thermoforming involves preheating the flat sheet to 180 to 360 F, the temperature depending on the material, and then forming by mechanical, air or hydraulic pressure to the desired shape. After cooling, the part is taken from the mold, and unwanted flanges are sawed or blanked from the part. All of the different processes have in common low forming pressures, and thus low cost molds and equipment (see box on next page for details on the types of parts producible by each method). In recent years, rapid-cycle forming machines have been developed to make sheet molding more practical for large production quantities.

### Reinforced Plastics Moldings

The term "reinforced plastics moldings," as used here and in the plastics industry, refers to parts produced by impregnating a reinforcing material, in the form of cloth or mat, with a liquid thermosetting or thermoplastic resin, laminating the material into multiple layers, and curing with heat and pressure to form a dense, hard solid. It does not include materials discussed later as "high pressure laminates," which are available from stock as flat sheet, rod or tube.

**Materials.** Resins used for reinforced plastics moldings include polyesters, phenolics, epoxies, melamines and silicones. Reinforcements include cloth or mat made from cotton, glass, asbestos and nylon. Glass reinforcements are most commonly used. Recently, there has been much interest in reinforcing thermoplastic resins, such as vinyls and acrylics, with cloth or mat made from thermoplastic synthetic fibers such as nylon. However, the bulk of reinforced plastics moldings today utilizes thermosetting resins.

**Methods.**

*Contact molding*—A low cost mold is used. Layers of reinforcing material are placed by hand against the mold surface; and resin is added, either by spraying or brushing after each layer is located. After sufficient layers of mat or cloth have been saturated with resin, they are allowed to harden without external application of heat and without applied pressure.

*Vacuum bag molding*—Procedure is similar to contact molding except that when lay-up is completed, a flexible sheeting, usually polyvinyl alcohol, is placed over the impregnated reinforcement and a vacuum is drawn between the sheeting and the mold surface. This provides about 12 psi pressure on the part, permitting higher glass content.

*Pressure bag molding*—Similar to vacuum bag molding except that a tailored bag is placed against the sheeting, and pressure is applied inside the bag to expand it against the impregnated reinforcement (sometimes pressure is applied directly on the sheeting). Pressures up to 50 psi are usually used, making high glass contents practical. Sometimes the entire assembly is placed in a large autoclave that contains hot air or steam at 50 to 100 psi pressure ("autoclave molding").

*Flexible plunger molding*—A metal female mold is usually employed and glass and resin are placed in the heated cavity. The plug portion is made of medium hard rubber, and is the approximate shape of the part to be molded. The rubber plug provides uniform, high and fluid pressure. High glass contents are possible. This method is not practical for large moldings because of the high pressures and the limitations of the flexible plunger.

*Vacuum injection molding*—Two molds, often made of glass-reinforced plastics, are used. The reinforcement is laid between the two molds and the resin is poured in a moat around the bottom. The resin is then sucked by vacuum up through the reinforcement. This tends to give air-free parts, and is used primarily for large parts. Glass contents are usually low.

*Matched die molding*—Can be used for parts up to about 60 sq ft in area, and is generally used for high production runs. Uses two metal molds which have a close-fitting, telescoping area to seal in the resin and trim the reinforcement. The molds are heated (with steam or electricity) to about 240 F. Where the length of run is sufficient, this method gives the lowest cost moldings and the highest production rates.

**Design rules.** Designing molded reinforced plastics parts is difficult because of the large number of variables encountered in the material and the process, and the difficulty of controlling some of them. These variables include: 1) composition of the resin, including fillers, catalysts and hardening agents, 2) geometry of the reinforcing material, 3) resin-reinforcement ratio, 4) degree of saturation of reinforcement by resin, and 5) temperature and time of cure.

The cardinal design rule, which cannot be overemphasized, is: consult the custom molder in the primary design stages. In addition, follow these general design rules:

1. Integrate parts.
2. Make prototypes.
3. Mold to dimensions; parts cannot be "sprung" after they are molded.
4. Use stress formulas valid for fiber-reinforced plastics.
5. Know the conditions of use.
6. Consider effects of the molding procedure.
7. Use sandwich construction for maximum strength-to-weight ratios.
8. To increase rigidity in stressed areas: a) increase the glass loading, b) use unidirectional reinforcement where practical, c) place flanges and lips on edges, d) use ribs, corrugations, beads and dimples, e) increase wall thickness, f) use curved sections rather than flat areas where possible, and g) use sandwich construction.
9. Avoid drastic changes in wall thickness.
10. Avoid sharp corners; use liberal radii.
11. Use maximum draft.
12. Avoid undercuts.

**continued on next page**

## Plastics Parts

### Thermoplastic Sheet Forming Methods

**Cold bending.** Simple circular or cylindrical shapes. The thicker the sheet, the larger the bend diameter must be to prevent high stress concentrations. Ex: consumer packages.

**Hot line bending.** Two-dimensional shapes with arc, angle or channel cross section. Gradual to sharp bends, depending on heating procedure. Ex: safety guards.

**Stretch forming** (hot draping, yoke forming). Two-dimensional or slightly compound shapes, especially large shapes. Subject to surface distortion. Not suitable for reproduction of fine details. Yoke forming provides more uniform thinning out and is suitable for longer runs than manual stretch forming. Ex: aircraft canopies.

**Plug and ring forming.** Shallow to deep drawn shapes with gradual to sharp angles and curves. Not suitable for highly accurate contours or fine mold details. Considerable surface distortion, especially at inside corners — unsuitable where optical properties are critical. Ex: trays.

**Slip forming.** Same as yoke forming or plug and ring forming except that much more uniform thickness and less optical or pattern distortion can be obtained throughout the part, especially in deep drawn shapes. Fluted edges obtained by increasing clearance. Ex: carrying cases.

**Free blowing or free vacuum forming.** Somewhat modified surface tension shapes (tending toward fishbowl shapes) determined by shape or clamping ring and depth of draw. Internal flanges. Tolerances ¼-½ in. Good optical properties. Vacuum method easier to control and preferred where 15 psi is sufficient pressure. Ex: aircraft domes.

**Ridge forming.** Simple or complex (with vacuum and/or air pressure) shapes with minimum surface distortion and low mold cost. Generous radii necessary to avoid tearing at ridges during forming. Combines possibilities of plug and ring forming, free blowing or free vacuum forming, vacuum forming and vacuum snapback forming. Ex: equipment housings.

**Vacuum forming or blow molding in female mold.** Usually limited to relatively shallow draws, and relatively large angles and radii—more so the thicker the sheet. Blow molding offers higher pressures and is therefore more suitable for smaller angles and radii, especially in thicker sheet; also reduces forming temperature required for thick sheet. Both produce some surface distortion—less so the more the shape of the mold resembles a surface tension shape. Ex: display signs.

**Blow-dieing.** Small, thin shapes having greatest perimeter larger than neck — especially closed spherical or modified spherical shapes. Not suitable for close tolerances. Ex: hollow toys.

**Vacuum forming over male plug** (drape forming). Shallow to deep drawn shapes with relatively sharp angles and curves can be made with good accuracy and reproduction of fine mold detail, and without excessive thinning out. More accurate than plug and ring forming but not as suitable for thick sheet. Subject to surface distortion, especially at bottom of draw. Ex: display signs.

**Vacuum snapback forming.** Especially suitable for modified surface tension shapes with minimum mark-off and closer tolerances (⅛ in.) than obtainable in free blowing or free vacuum forming. Simple snapback method not suitable for reverse curves or sudden contour changes, but more complex shapes and finer reproduction of mold detail are provided by additional vacuum or air pressure. Integral flanges. Combines possibilities of free vacuum forming and plug and ring forming. Ex: aircraft domes.

**Matched die molding** (embossing). Especially suitable for shallow draws, long runs and embossed surfaces. Relatively uniform thickness, good mechanical properties. Subject to surface distortion on both sides. Ex: watch crystals.

**Die pressing.** Small, simple shapes that can be approximated in precut blank and have somewhat varying thickness, or relatively great thickness compared to over-all size. Ex: brush backs.

13. Consider use of molded-in holes.
14. Consider mold shrinkage.
15. Design to practical dimensional tolerances.
16. Design to avoid warpage.

**Secondary fabrication.** See "High Pressure Laminates" below.

### High Pressure Laminates

The term "laminates" used here refers to those reinforced plastics materials formed by high pressures (over 1000 psi). Vulcanized fibre is also included because of the similarity of its applications. These materials are available as sheet, rod or tube.

**Materials.** Resins used include phenolics, melamines, silicones and epoxies, and reinforcements consist of

**MINIMUM COLD BENDING RADII FOR RIGID VINYL SHEETS**

| Calendered | | Planished | |
|---|---|---|---|
| Thickness, in. | Min Bend Rad., in. | Thickness, in. | Min Bend Rad., in. |
| 0.005 | | | |
| Long. | ½ | 0.010 | 12 |
| Trans. | 2 | 0.020 | 12 |
| 0.010 | | 0.030 | 14 |
| Long. | 1 | 0.040 | 14 |
| Trans. | 6½ | 0.050 | 18 |
| 0.015 | | | |
| Long. | 3 | | |
| Trans. | 9 | | |

cellulose paper, asbestos paper, or fabric or mat made from cotton, glass, asbestos or nylon fibers. Vulcanized fibre has only one component—cellulose. It is made by laminating chemically gelled paper, leaching out the chemical, and calendering. The resulting laminate is tough and hornlike, and has good electrical properties. Properties of standard NEMA (National Electrical Manufacturers' Assn.) laminates are given in Section 5 of this issue.

**Postforming.** Certain grades of laminates can be postformed by the use of heat and pressure. Temperatures, times and pressures vary with grade of laminate, thickness of material, and design. Temperatures generally range between 350 and 480 F, heating time usually ranges from a few seconds to a few minutes at most, and pressures range from a few pounds to several hundred pounds per square inch.

Although the following formability values should not be used for design, they do indicate general limits for postforming. Minimum radii are measured on the inside of bends, and apply to bends made lengthwise and crosswise. Smaller radii can be achieved with cloth-base laminates by orienting the sheet so that bends are made diagonally to the warp and fill directions.

| Thickness, in. | Min Bend Rad., in. |
|---|---|
| 1/32 | 1/32 |
| 1/16 | 3/32 |
| 3/32 | 3/16 |
| 1/8 | 5/16 |
| 3/16 | 9/16 |
| 1/4 | 1 |
| 5/16 | 1 3/4 |
| 3/8 | 2 1/2 |

Postforming grade laminates can be drawn to moderate depths. Both paper and cloth-base laminates in 1/16-in. thickness can be drawn to a depth of about 1¼ in. in a 3-in. dia spherical cup.

Vulcanized fibre can be formed by the use of moisture and pressure. Water softens or plasticizes the fibre to the extent that it can be formed under relatively low pressures, usually between 200 and 500 psi. In addition to forming in matched die presses, vulcanized fibre can be formed in standard sheet metal angle brakes and in punch presses if the design is simple and only a little moisture is required.

**Secondary fabrication.** Machining and other secondary operations carried out on reinforced plastics are similar for both low and high pressure moldings, as well as for laminates.

*Blanking and punching*—Use of a punch press with a hard, well-made blanking or punching die is the accepted production method for cutting flat stock, putting holes into side walls of moldings, and other piercing steps. Punching of reinforced plastics results in holes that are 0.002 to 0.010 in. smaller than the punch. Blanking gives parts 0.001 to 0.005 in. larger than the die. In each case, these values depend on a relation based on the thickness and the proportion of reinforcement. This "shrinkage" causes the material to seize the dies, so that a strongly loaded spring stripper mechanism is desirable. It has been estimated that a pressure of 20,000 psi (on the shear-edge area) is sufficient for blanking, punching and shearing.

*Shearing*—Shearing of ½-in. thick stock is quite feasible. For best results, the piece should have a width of at least twice the thickness of the parent stock. Shear gibs must be snug and blades sharp.

*Sawing*—Abrasive cutting wheels should be used whenever possible; rigid mounting of both the wheel and the work is important. A metal cutting blade, if used, should have coarse, offset, wide-spaced teeth.

*Drilling*—Accurately located holes on side walls are difficult to mold. Where small runs are made, and where precision is required, drilling is recommended. There is no limit to the thickness that can be drilled.

*Tapping*—Tapping is seldom performed, because the strength of a screw and tapped hole system is inferior to that of a nut and bolt assembly. Where light duty connecting is called for, self-tapping screws are satisfactory.

*Grinding*—Widely used to provide the taper in glass fiber-reinforced plastics fishing rods. Satisfactory automatic machines are in common use. Standard coolants are employed so that rapid feeds and minimized wheel loading are possible.

*Routing, milling, turning*—Routing is a practical production edging process and is faster and more accurate than jig-sawing where moderate numbers of irregular holes are to be cut. Milling and turning are not frequently required, but can be readily accomplished. Well-sharpened carbide or diamond-tipped tools provide good efficiency; speeds and feeds appropriate for brass are recommended.

**DESIGN FACTORS FOR GLASS-REINFORCED PLASTICS MOLDINGS•**

| Type of Molding ➡ | Bag | Flexible Plunger | Vacuum Injection | Matched Die |
|---|---|---|---|---|
| Inside Radius (min), in. | ½ | ½ | ½ | ⅛ |
| Molded-In Holes | Large only | No | No | Yes |
| Trimmed in Mold | No | No | No | Yes |
| Built-In Cores | Yes | Not rec | Yes | Not rec |
| Undercuts | Yes | Only slight | Not rec | No |
| Draft (min), deg | 5 | 1 | 3 | 1 |
| Thickness (min), in. | 1/10 | 1/16 | 1/10 | 1/32 |
| Practical Thickness (max), in. | 1 | ¼ | ½ | ¼ |
| Normal Thickness Variation, in. | ±0.020 | ±0.015 | ±0.020 | ±0.008 |
| Thickness Build-Up (max) | As desired | 2 to 1 max | As desired | 2 to 1 max |
| Corrugated Sections | Core better | Yes, 1-in. rad. | Yes | Yes |
| Metal Inserts | Yes | Not rec | Yes | Possible |
| Surfacing Mat | No | Yes | Not rec | Yes |
| Size of Part (max), sq ft | 2000 | 100 | 1000 | 175 |
| Metal Edge Stiffening | Not rec | Not rec | Not rec | Yes |
| Bosses | Possible | Possible | Possible | Possible |
| Fins | Yes | No | No | Short, yes |
| Molded-In Labels | Yes | Yes | Not rec | Yes |
| Raised Numbers or Letters | Yes | Yes | Yes | Yes |

•Not rec=not recommended at present time.

# Rubber Parts

## General

Although there are many similarities between rubber and plastics materials and forming methods, there are several important differences.

For one thing, the form in which *plastics* materials are specified is almost entirely determined by the nature of the material: the thermoplastic resins soften and flow under heat and pressure; the thermosetting plastics do not. *Rubber* materials, or elastomers, are very similar to thermoplastics when first placed in the mold, i.e., they soften when heated and flow under pressure. However, upon further heating, vulcanization, or crosslinking, occurs and the materials become roughly equivalent to thermosetting plastics. As a result, forming methods used for rubbers are generally similar to those used for thermosetting plastics and are specified not on the basis of materials used but on the basis of economics, shape of the part, and precision required.

Another major difference between plastics and rubber materials is the way in which rubber molding compounds are specified. Although there are many standard rubber compounds, most rubber parts are specified by performance characteristics rather than by specific materials. Each rubber material not only has its own special characteristics, but is capable of being modified to meet a wide variety of specific end service requirements.

A typical rubber compound contains, in addition to the base polymer, two types of ingredients: those that serve the general functions of vulcanizing and stabilizing the polymer, and those that serve special purposes such as reinforcement, bulking, stiffening, softening, coloring or reodorizing.

When specifying rubber parts, therefore, the designer should work very closely with the compounder and/or molder (often the same) and request a compound that: 1) provides the required service properties; 2) is capable of being processed with a minimum of waste and rejects; and 3) minimizes material, labor and power costs.

Rubber materials can be compounded to meet most requirements of hardness; tensile and compression properties; low temperature properties; tear, abrasion and impact resistance; resilience; adhesion; chemical and oil resistance; aging and weather resistance; and processability. However, extreme values cannot be obtained in one property without detracting from others, and some properties can be obtained only at the expense of others.

## Molded Parts

**Compression molded parts.** Most molded rubber parts are made by compression molding. In this process, an excess amount of uncured rubber compound is placed in the mold cavity so that a flash is formed between the mold plates. For simply shaped thin parts, the mold may consist of only a base plate (containing one or more cavities) and a cover plate. For deeper or more intricate shapes, it is necessary to design a mold consisting of three or more pieces.

Cores and inserts can be used to form holes and inner recesses. Close tolerances can be held on all dimensions except across the mold parting line. Parts are uniform, with good finish, and can be made in almost any hardness, color, shape or size. In comparison with other types of molding, compression molds are relatively cheap and can be operated with relatively low labor cost.

**Transfer molded parts.** In transfer molding, rather than loading the mold by placing stock directly in the mold cavities, the mold is closed empty and the rubber is forced into it through sprues, runners and gates. Advantages of transfer molding as compared to compression molding are: 1) minimized thickness variations in finished parts, resulting in closer tolerances; 2) practically no flash; 3) the ability to produce intricate parts not practical by compression molding; and 4) good finish.

Mold and press overhead costs, on the other hand, are generally higher (up to 50%); but labor costs are usually less. Not all compounds will flow suitably for this method. And although flash is minimized, sprue necks must be tumbled or trimmed off. Transfer molding, in general, is best suited to small parts.

**Injection molded parts.** Injection molding of rubber is similar to transfer molding in that the cavities are filled after the mold is closed by forcing stock through runners. The main difference between injection molding of rubber and injection molding of plastics is that the plastics material is fed from a heated cylinder by a piston into a cooler mold from which the finished part is removed as soon as it chills below its distortion temperature. Rubber materials, on the other hand, are injection molded by extruding the compound into a hot mold from a screw and barrel, and the finished part is removed from the cavities while hot.

Advantages of injection molding are similar to those of transfer molding: uniformity, close tolerances, good finish and thin trim flash. Changeover and setup time are relatively long, however, and equipment and maintenance are costly. In general, injection molding is suitable only for long production runs.

**Blow molded parts.** This molding technique, used for hollow parts, uses either of two methods: 1) pressure is derived from gases generated at curing temperature from decomposition of chemicals inserted into the hollow space when the stock is prepared for loading into the mold; or 2) air is forced through a hollow needle inserted through the mold wall into the cavity.

In either case, the pressure forces the stock against the contours of the mold cavity with sufficient force to shape it and hold it firmly in contact with the mold walls during the molding cycle.

**Design factors.** Although it is difficult to generalize, all of the following factors should be considered:

*Shrinkage*—All rubber compounds shrink on cooling from the vulcanization temperature to room temperature. However, shrinkage varies widely from about 0.006 in. per in. to as much as 0.050 in. per in., or more. Allowance for shrinkage depends on curing time, temperature and pressure, and the difference between the thermal expansion of the rubber compound and the mold material. Complex shapes may also cause irregular shrinkage, resulting in distortion of some dimensions. In general, it usually suffices to make the mold 1/64 in. per in. larger in each dimension than the desired finished part.

*Wall thickness*—Solid objects as thick as 12 in. and sections as thin as 0.005 in. are possible. Over such a wide range, however, compounding and vulcanization procedures must be designed to fit the type of product to be molded. Uniformity of wall thickness is not always essential; however, because

optimum vulcanization, or cure, is a function of time and temperature, very great differences in wall thickness are not desirable.

*Draft*—No draft is required on parts up to 85-90 durometer. Above this hardness range, parts more than ½ in. thick generally require a draft of ½-1 deg. If the part has a deep recess or a hole through it, the taper need only be on the core or the cavity, but not on both.

*Undercuts*—Both external and internal undercuts are probably achieved in molded rubber with greater ease than in any other material. However, on materials of 80-90 durometer they should be avoided.

*Holes*—There are few limitations regarding molded-in holes. Difficulties arise only with very small diameters, great depth, excessive hardness of compound, and improper mold design.

It is possible to produce parts with holes as small as 1/32 in. in dia and 5/8 in. long. Blind holes are more difficult to produce due to the possibility of pin breakage. However, blind holes ⅛ in. in dia and 1½ in. deep are possible. Threaded holes in soft rubber are not practical unless the threads are coarse wood or bottle threads.

*Tolerances*—Dimensional accuracy of molded rubber parts is controlled primarily by 1) the type of compound used, 2) the shape and thickness of the part, 3) mold design and construction, 4) shrinkage, and 5) amount of trim and finish.

Standard Rubber Manufacturers Assn. tolerances for precision molding (Class 1) and "Commercial" products (Class 3) are given in the tables below.

**Design Rules.**

1. Locate the parting line so that flash can be easily removed. On compression molded parts, for example, parting lines should be at the largest diameter.

2. Indicate on the part drawing exactly where flash is not permissible. Also give allowable limits on flash.

3. Avoid undercuts with 80-90 hard rubber. Provide a slight draft with 90-95 hard rubber. Although softer compounds do not require draft, it does facilitate removal from the mold and should be incorporated wherever possible.

4. Avoid fragile edges, allowing at least 1/16 in. thickness for all flanges.

5. Keep radii at edges and corners at least 1/32 in. for strength, good appearance and breakage resistance.

6. Keep sections as light and uniform as possible to reduce curing time and to insure uniform cure.

7. Construct molds with standard machine finish unless special finish is required. Polished or chromium-plated mold cavities are expensive and should be avoided.

8. Use a tolerance of ±15% when shear or compression rates are specified.

### Die, Lathe Cut Parts

Lathe cut parts are usually cut from extruded tubing or sleeves and are used for such things as gaskets, packings, disks, washers, seals, spacers, rings, bushings, etc. There are several different methods of cutting: the most accurate (and also most expensive) is hand cutting; the most economical (and least precise) is guillotine cutting.

Die cut parts are cut from vulcanized sheet or slabs with inexpensive steel dies. Flat parts with

**TOLERANCES OF MOLDED PARTS (CLASS 1)**

| Size, in. | Dimensions Not Affected By Flash | Dimensions Measured Across Flash |
|---|---|---|
| 0.000–0.499 | ±0.003 | ±0.005 |
| 0.500–0.999 | ±0.005 | ±0.008 |
| 1.000–1.999 | ±0.008 | ±0.010 |
| 2.000–2.999 | ±0.010 | ±0.013 |
| 3.000–3.999 | ±0.013 | — |
| 4.000–4.999 | ±0.015 | — |
| 5.000–7.999 | ±0.020 | — |

**TOLERANCES OF MOLDED PARTS (CLASS 3)**

| Size, in. | Dimensions Not Affected By Flash | Dimensions Measured Across Flash |
|---|---|---|
| 0.000–0.499 | ±0.010 | ±0.015 |
| 0.500–0.999 | ±0.010 | ±0.018 |
| 1.000–1.999 | ±0.015 | ±0.020 |
| 2.000–2.999 | ±0.020 | ±0.025 |
| 3.000–3.999 | ±0.025 | ±0.030 |
| 4.000–4.999 | ±0.030 | ±0.035 |
| 5.000–7.999 | ±0.045 | ±0.050 |

**TOLERANCES OF EXTRUDED PARTS**

| Tubing | | | | | | Special Shapes | |
|---|---|---|---|---|---|---|---|
| Length, in. | | Inside Dia, in. | | Outside Dia, in. | | Cross-Sectional Dimension, in. | |
| Range | Tol | Range | Tol | Range | Tol | Range | Tol |
| 0–1½ | ±1/64 | 0–½ | ±0.008 | 0–½ | ±1/64 | 0–¼ | ±1/64 |
| 1½–10 | ±3/64 | ½–1 | ±1/64 | ½–1 | ±1/32 | ½–½ | ±1/32 |
| 10–40 | ±1/16 | 1–3 | ±1/32 | 1–2 | ±3/64 | ½–1 | ±3/64 |
| 40–60 | ±¼ | — | — | 2–4 | ±1/16 | 1–2 | ±1/16 |

*continued on next page*

## Rubber Parts

large holes or cutouts are often cheaper to mold, however, due to waste in die cutting.

Practically any rubber material can be die cut into almost any shape and size, up to 19 × 36 in. (larger parts are made by cementing). Thickness of die cut parts generally runs from about 3/32 to 1 in., in 1/16-in. gradations. With thickness above ⅛ in., some concavity develops on punched edges. This is more pronounced the thicker and softer the material is. Holes more than half the thickness of the material are difficult to punch satisfactorily.

Tolerances for die cut parts are as follows:

| Thickness, in. | Tolerance |
|---|---|
| 1/4-1/32 | ±0.008 |
| 1/16-1/8 | ±0.016 |
| 5/32-3/8 | ±0.031 |
| 1/2 and over | ±0.047 |

### Extrusions

Extrusion, like calendering, is widely used to make blanks for molding. However, it is also a widely used method of forming rods, tubes, strips, channels, gaskets and other shapes.

An extruded rubber part differs from a molded rubber part in two ways: 1) the rubber is forced through a die under pressure, and 2) vulcanization does not take place in a cavity. In the process, the rubber compound is first warmed on a mill and then fed directly to the extruder in a continuous strip. The compound is forced through the die opening by a screw. The extruded material is then cut and the parts vulcanized under open steam in specially designed heating chambers.

The primary advantage of extruded parts is low setup and die costs and, consequently, low cost of finished parts.

Primary disadvantages are inability to hold close dimensional tolerances and limitations on shape and size of part. Tolerances must be liberal because the rubber swells on extrusion and shrinks when vulcanized. In some cases, swelling can amount to more than twice the die opening, depending on type of compound used, softness desired, plasticity of the rubber, and temperature, pressure and rate of extrusion. As a result, size and contour of the die must be adjusted to insure proper dimensions on the finished part.

Tolerances for extruded tubing and special shapes are given in the accompanying table.

### Rubber-to-Metal Molding

Many molded rubber products are functional only because they are bonded to metal parts. Typical of these parts are motor mounts, seals, instrument vibration dampeners, army tank tread blocks and industrial caster wheels. Primary characteristics of rubber-to-metal moldings are: absorption of shock loads, dampening of mechanical vibrations, suppression of noise, high strength and durability.

In general, rubber is bonded to mild steel, cast iron, stainless steel, die cast aluminum, bronze, brass and other metals and alloys. Recently, however, rubber has been successfully bonded to plastics, wood and other nonrigid materials. Adhesive strength of rubber-to-metal bonds often exceeds the tensile strength of the rubber compound itself.

When considering rubber-to-metal molding, cost must be taken into account. The quality or type of bond desired determines to a great extent the ultimate cost of the rubber-to-metal part. For example, to obtain adhesion on such functional parts as motor mounts, very close and costly controls are required on both metal and rubber preparation. With nonfunctional parts, such as some pads and bumpers which require only enough adhesion for assembly, these costly controls are not necessary.

The same adhesion values are not necessarily obtained with different metals. Iron and mild steel give the highest values. Different rubber compounds also give different values. Low tensile compounds, for example, do not give as high an adhesion value as high tensile compounds.

**Adhesion.** The two most commonly used methods of obtaining adhesion between rubber and metal involve 1) the use of special adhesives, and 2) a special brass plating on the metal surface.

Rubber containing sulfur may be bonded directly to yellow brass parts by molding against the metal under sufficient pressure. The bond obtained during vulcanization is believed to result from interaction of sulfur with the brass and the elastomer.

Most rubber compounds will not adhere directly to steel as they will to brass. In those cases an organic adhesive is used. To prepare the metal for adhesive bonding, it is first degreased and then blasted with sand or steel grit. The adhesive is applied and the rubber compound is molded to the prepared metal part.

There is no universal bonding agent and the selection of one is dependent upon the elastomer and the rubber compound used, the metal surface, the service requirements of the bonded part, and factory operating conditions.

Rubber-to-steel bonds can also be obtained by electroplating brass on the steel surface and then bonding the rubber to the plated coating as if it were a brass part. However, there are certain disadvantages to this method: plating conditions must be very carefully controlled because slight variations affect bond strength; and installation of brass plating equipment is costly.

**Design rules.** The following rules should be observed:

1. Keep heat buildup in the rubber compound to a minimum to prevent premature bond failure. The two most common causes of heat buildup are excessive ambient temperatures and undersize design.
2. Allow adequate space for distortion of the rubber under load.
3. Use metal inserts free from burrs and sharp edges to avoid cutting action on the rubber when under distortion.
4. Use fillets or design rounded metal corners to avoid areas of concentrated stress.
5. Keep loads on bonded surfaces no higher than about 250 psi.
6. Design metal inserts with close tolerances on dimensions which register in the mold. If large tolerances are necessary, they should be on the minus side.
7. Use smooth metals for best adhesion. Corrugations, knurling, etc., decrease adhesion.
8. Use large fillets at sections where rubber joins steel on flexed or stressed parts.

## Composite Materials

Composite materials actually include a wide range of divergent compositions. This discussion, however, will be limited to what are perhaps the six most frequently specified types: plastics-metal laminates, metal-wood laminates, clad metals, honeycomb sandwich structures, combination plastics laminates, and bi-metallic castings.

Each of the different compositions is designed to satisfy specific service requirements and offers special properties and characteristics. Composites are sometimes designed for high structural strength, sometimes for insulation, sometimes for decorative appeal and sometimes for special purposes. In general, all composite materials offer some of the following characteristics: low weight, low cost, simplified construction, high strength or stiffness, thermal insulation, fire resistance, moisture or water resistance, vibration or sound dampening, elimination of size limitations, atmospheric and chemical resistance, abrasion and wear resistance, and improved decorative qualities.

### Plastics-Metal Laminates

Although there are many possible combinations, vinyl-metal laminates probably account for about 90-95% of all plastics-metal laminates now used. A relatively new laminate, polyester-steel, is discussed briefly below.

The wide range of uses for vinyl-metal laminates includes electrical products, transportation equipment, luggage and carrying cases, household products and building applications. Their main advantages are: high decorative appeal, strength and light weight, resistance to wear and abrasion, resistance to most chemicals, and ease of fabrication.

**Materials.** In general, any ferrous or nonferrous base metal can be used. However, the three most common metals in use today are cold rolled steel, aluminum and magnesium. A steel base is selected where strength and low cost are dominant design factors. Aluminum is used where lightness and/or corrosion resistance is required. Magnesium is usually used only when extreme lightness is required (e.g., luggage and carrying cases).

Any of these base metals can be laminated with vinyl on one or both sides. Ordinarily, a single-side laminate is sufficient for product interiors. However, a double-side laminate may be required if the reverse side of the laminate must have special properties.

The reverse side of a laminate may also be provided with a wide variety of organic finishes or electroplates. For added decorative appeal and resistance to rust and corrosion, reverse sides can be easily plated with zinc, chromium, copper, cadmium or nickel without damaging or discoloring the vinyl layer.

**Properties.**

*Appearance*—Probably the most noteworthy characteristic of vinyl-metal laminates is their outstanding appearance. The number of textures and colors that can be produced is almost unlimited. Typical of the textures now being produced are leathers, textiles, wood grains, high gloss matte finishes, nonreflecting matte finishes, and marbleized finishes. All of these textures can be produced in practically any color.

*Chemical resistance*—The high-molecular-weight polyvinyl chloride resins used in vinyl laminates are inherently chemically stable. However, some types of vinyl films are given a clear protective coating of up to 2 mils for added resistance to corrosion, staining, abrasion and handling. In addition, vinyl laminates are also resistant to 48-hr exposure to such common media as petroleum, alkalis, citric acid, Clorox, ammonia, milk, animal oil, vegetable oil and greases.

*Abrasion, wear and heat resistance*—Vinyl-metal laminates have outstanding abrasion and wear resistance. In general, maximum recommended operating temperature is about 200 F. The laminates show no loss of adhesion and no tendency to delaminate after 600-hr exposure to 150 F. Laminates exposed to 210-250 F will not show any surface damage unless pressure is applied to the surface while it is hot.

**Thickness.** A vinyl film of 10 to 15 mils has proved satisfactory for most applications. However, films as thin as 4 mils and as thick as 25 mils, and higher, are available. Thickness of the base metal depends on the structural requirements of the application. The practical laminating thicknesses for steel are 0.012 in. to 0.06 in., for aluminum 0.016 in. to 0.125 in., and for magnesium 0.016 in. to 0.081 in. Sheets are available in sizes up to 52 × 120 in. and larger. Also, coil stock in 40-in. widths is available in almost any length.

**Forming, joining.** Vinyl-metal laminates are easily drawn and formed on existing equipment. The maximum draw that can be obtained is generally limited by the forming properties of the base metal. However, any draw that can be made in one operation is satisfactory; the metal cannot be annealed. Any die lubricant can be used; however, water-soluble or silicone-base lubricants are recommended.

Vinyl-metal laminates can be also crimped, bent and spun. Normal cutting and shearing operations are permissible provided the vinyl side of the laminate is exposed to the cutting edge. When shearing a double vinyl laminate, the side with the thinner vinyl film should be away from the cutting edge.

Vinyl-metal laminates can be readily fastened with conventional sheet metal screws, bolts, rivets, lock nuts, and speed nuts through drilled or pierced holes. Brazing and soldering do not produce very strong joints and are used only in a few isolated applications.

A resistance welding technique has recently been developed which makes it possible to produce a high strength weld on the back of a steel laminate without indenting or burning the vinyl or affecting its bond. Welding is accomplished by using two copper alloy electrodes that contact the workpiece on the same side.

**Polyester-metal laminates.** This relatively new plastics-metal laminate, consisting of polyester resin on strip steel, offers the following characteristics: good moisture, abrasion, weather and stain resistance; and the ability to be deep drawn, lock seamed, roll formed, sheared, crimped, bent and pierced. They can be joined only by mechanical means at present. However, new heat joining methods and adhesives are being investigated.

The laminate is available in any color and most textures, and is produced in widths up to 48 in. in continuous rolls.

*continued on next page*

## Composite Materials

### Metal-Wood Laminates

Although many combinations of metal facings and wood cores are possible, the most commonly used materials are steel and aluminum faces and plywood cores.

Metal-wood laminates are used for a wide range of applications, including truck and trailer side panels; railway car interiors, bulkheads and doors; kitchen cabinets; instrument boxes and cabinets; bus and truck doors; locomotive sheathing; foundry patterns; outdoor signs; and architectural applications of all kinds.

**Properties.** The primary advantage of metal-wood laminates is excellent rigidity at low weight and cost. A typical ¾-in. thick laminate, made of plywood sandwiched between faces of zinc-coated steel, has a stiffness factor equal to that of 1/16-in. thick solid oak, ⅜-in. thick aluminum plate, or ¼-in. thick steel plate. For the same conditions, 1 sq ft of the metal-wood laminate weighs 3.3 lb, as compared to 2.8 lb for oak (which has nearly twice the thickness), 5.4 lb for aluminum plate, and 10 lb for steel plate.

Other characteristics include: versatility (the laminates are available in a wide range of sizes, thicknesses, edges, cores and faces to meet specific end service requirements); uniformity; fire resistance; smooth surfaces; sound dampening; and ease of fabrication.

**Materials.** Virtually any combination of metal and wood can be produced. The three most widely used combinations are: 0.029-in. thick zinc-coated steel bonded to plywood on one or both sides; 0.020-in. thick aluminum alloy 3003 bonded to plywood on one or both sides; and 0.025-in. thick type 18-8 stainless bonded to plywood on one side only or with zinc-coated steel on the other.

Other laminates sometimes used involve faces of monel, lead, porcelain enameled steel, and a combination of aluminum and steel; and cores of wood veneer, wallboard, hardboard, balsa wood and insulation board.

**Sizes, thicknesses.** Standard widths, lengths and thicknesses of wood-metal laminates are as follows: for laminates consisting of zinc-coated steel on one or both sides or aluminum on one or both sides, available widths range from 30 to 48 in.; available lengths range from 72 to 144 in.; and thicknesses range from ¼ to 1 in.

For laminates consisting of stainless steel on one side alone or with zinc-coated steel on the other side, widths are 30, 36, or 48 in.; lengths are 96 or 120 in.; and thicknesses range from ¼ to 1 in. Greater thicknesses can be obtained if desired.

Tolerances on length and width are the same as those for the metals used. Thickness tolerances (including the metal faces) are held to ±0.015 in.

**Forming, joining.** Metal-wood laminates can be easily worked with standard tools. Generally, selection of the cutting tools should be determined by the metal facing. The laminates can be sawed, drilled, bored, notched and routed.

Although metal-wood laminates are usually used as flat sheets, panels with metal facing on one side only can be curved to a certain degree. For example, a ¼-in. panel with steel on one side can be bent to a 9-in. radius.

Metal-wood laminates can be joined by soldering (except those with aluminum faces), adhesive bonding and mechanical fastening, including sheet metal screws, bolts, machine screws, sleeve nuts, etc. For hinges, locks, hangers, handles and other hardware fittings, tapping plates should be used to eliminate through fasteners and add strength.

**STIFFNESS AND WEIGHT OF PLYWOOD-METAL LAMINATES[a]**

| Plywood Thickness, in. | No. of Plies | EA, 1000 lb/in. width [b] | | EI, 1000 sq in.-lb/in. width [c] | | Bending Moment (max), in.-lb/in. width | | Weight, lb/sq ft |
|---|---|---|---|---|---|---|---|---|
| | | Long. | Trans | Long. | Trans | Long. | Trans | |
| STEEL (0.024-in.) BOTH SIDES | | | | | | | | |
| ¼ | 3 | 1671 | 1628 | 28.9 | 27.3 | 388 | 366 | 2.79 |
| ⅜ | 3 | 1755 | 1755 | 63.8 | 58.8 | 604 | 556 | 3.13 |
| ⅜ | 5 | 1786 | 1724 | 62.7 | 59.9 | 596 | 566 | 3.13 |
| ½ | 5 | 1936 | 1784 | 112.5 | 104.8 | 822 | 765 | 3.53 |
| ⅝ | 5 | 2060 | 1870 | 175.1 | 163.8 | 1040 | 974 | 3.83 |
| ¾ | 5 | 2070 | 2070 | 249.7 | 239.6 | 1250 | 1200 | 4.23 |
| ¾ | 7 | 2070 | 2070 | 254.2 | 235.2 | 1270 | 1180 | 4.23 |
| 1 | 7 | 2185 | 2375 | 450.0 | 440.0 | 1720 | 1680 | 5.00 |
| 1⅛ | 7 | 2385 | 2385 | 594.1 | 579.2 | 2030 | 1975 | 5.35 |
| ALUMINUM (0.016-in.) BOTH SIDES | | | | | | | | |
| ¼ | 3 | 551.6 | 508.8 | 7.7 | 6.0 | 131 | 103 | 1.25 |
| ⅜ | 3 | 635.0 | 635.0 | 18.4 | 13.4 | 217 | 158 | 1.58 |
| ⅜ | 5 | 666.6 | 603.2 | 17.4 | 14.5 | 205 | 171 | 1.58 |
| ½ | 5 | 816.0 | 664.0 | 34.2 | 26.6 | 308 | 240 | 1.98 |
| ⅝ | 5 | 940.0 | 750.0 | 56.1 | 44.7 | 410 | 327 | 2.28 |
| ¾ | 5 | 950.0 | 950.0 | 81.3 | 71.1 | 499 | 437 | 2.68 |
| ¾ | 7 | 950.0 | 950.0 | 85.7 | 66.6 | 527 | 409 | 2.68 |
| 1 | 7 | 1065.0 | 1255.0 | 158.4 | 148.2 | 738 | 690 | 3.46 |
| 1⅛ | 7 | 1265.0 | 1265.0 | 211.1 | 196.2 | 875 | 813 | 3.81 |

[a] Longitudinal and transverse refer to direction of plywood face grain with respect to span length.
[b] EA is modulus of elasticity times cross-sectional area. Must be considered in composite materials.
[c] EI values computed on following basis: E for fir plywood is $1.6 \times 10^6$ psi for long plies and $80 \times 10^3$ psi for transverse plies; ultimate fiber stress in bending for fir is 8000 psi; for steel, E is $30 \times 10^6$ psi and ultimate fiber stress in bending is 60,000 psi; for aluminum, E is $10 \times 10^6$ psi and ultimate fiber stress is 24,000 psi.

## Combination Plastics Laminates

Plastics laminates combined with other materials can provide special combinations of properties that are not obtainable with any single material.

These combination laminates consist of various plastics laminates bonded to such other materials as copper, aluminum, rubber, etc. Specific characteristics offered by combination laminates include: 1) high strength-weight ratio; 2) excellent resistance to corrosion and chemicals; 3) great range of electrical characteristics; 4) dimensional stability over a wide temperature range; 5) high rigidity and strength for soft sealing materials; 6) good bearing surfaces; 7) great range of frictional characteristics; and 8) good fabrication characteristics and low production costs.

**Materials, forms.** Theoretically, any material can be combined with plastics laminates by adhesive bonding. However, because of similarities in design requirements for various types of end uses, several combinations have become somewhat standardized.

The most common plastics laminates used are the paper-base phenolics, such as NEMA grades XXXP, XX, XXP and XP. Other grades used quite frequently are C, CE, L and LE fabric-base phenolics; G-3 glass-melamine; G-5 glass-phenolic; and G-10 glass-epoxy.

The materials most commonly supplied in combination with plastics laminates are copper, natural and synthetic rubbers, cork, asbestos, steels, aluminum alloys, vulcanized fibre, and polyester and cellulose acetate films. Two grades of plastics laminates may also be combined.

Combination laminates are available in sheet, rod or tube form. In sheet form, the plastics laminate can be specified on one or both sides, or sandwiched between laminae of other materials. When a tubular form is used, the combination material consists of a plastics laminate covering a metal tubular core.

**Properties, uses.**

*Copper-faced laminates*—Probably the most widely used combination laminates are the copper-faced laminates used for printed circuits. Laminates are available with electrolytic or rolled copper foil in thicknesses of 0.00135 in. (1 oz), 0.0027 in. (2 oz) or greater, bonded to either one or both sides of an XXXP base. This grade is generally used because it has excellent insulation resistance, good punching qualities, and low dielectric losses even under high humidity conditions.

Bond strength for most copper-faced laminates is between 4 and 8 lb per in. width for 1-oz foil and slightly higher for 2-oz foil. Copper-faced laminates made by a new process have about twice the bond strength, but lower surface resistivity.

*Vulcanized fibre-clad laminates*—These combination laminates provide high arc resistance and a wide range of toughness, impact strength, rigidity and appearance, depending on the grade and thickness of the laminate and the fibre. They are used for such things as switchgear in both low and high voltage applications.

*Asbestos-clad laminates*—Asbestos paper bonded to plastics laminates provides a combination with high heat and arc resistance and is used for arc barriers and reflectors in high voltage arc interrupting devices.

*Aluminum-clad laminates* — These combination laminates are used extensively for engraving stock. They are also used as plate holders for x-ray machines where aluminum acts as the shield. Used as a piston head in aircraft shock struts, it provides the following advantages: it eliminates metal-to-metal contact, it is lightweight, mechanically strong, shock resistant, impervious to hydraulic oils, and stable over a wide temperature range. Aluminum-clad laminates also offer possibilities as a printed circuit material, but soldering remains a problem.

*Beryllium copper-clad laminates*—This composite material offers possibilities for printed circuits because of beryllium copper's good conductivity and nonmagnetic characteristics.

*Silver and gold-faced laminates*—The extremely high electrical conductivity of silver and gold makes these combination laminates particularly promising as electrical contact materials. The plastics laminate provides strength and insulation properties.

## Bimetallic Castings

Bimetallic castings are actually composite materials in which aluminum and magnesium alloys are molecularly bonded to steel, stainless steel and other ferrous metals.

In the process, the light metal is cast against a specially processed surface of the ferrous metal using any of the standard casting methods—sand, permanent mold, plaster mold, or pressure die casting. Typical uses for these composite materials are brake drums, engine cylinders, clutch rotors, guided missile control fins, impellers, pistons, gears, hydraulic manifolds and valve housings.

Main advantage of bimetallic castings is the ability to combine the strength, hardness, fatigue resistance, etc. of ferrous metals with the lightweight, high heat conductivity and other characteristics of light metals.

**Metals used.** Light metals used are pure aluminum and magnesium and any of their common casting alloys. Aluminum alloys include 43, 132, 142, 195, 220, 356, Almag 35, and Frontier 40-E; magnesium alloys include AZ92A, AZ63A and AZ91C.

Ferrous metals include gray, malleable, ductile and austenitic cast irons; and carbon, alloy and stainless steels. Aluminum and magnesium alloys can also be bonded to Inconel, the Nimonics, nickel, titanium and some other alloys.

**Properties.** In the case of iron and aluminum, the bond, which is essentially an intermetallic compound of the two, has a tensile strength of 15,000 psi and can withstand shearing stresses of the order of 7000 psi. The bond retains its properties at temperatures above 500 F and is both vibration-proof and leakproof. Galvanic attack is impossible because there are no voids at the interface.

**Design.** The major factor to be considered in designing bimetallic castings is the difference in expansion coefficients between the light metals and the various ferrous metals. Despite the difference, separation is generally prevented by the strength of the intermetallic bond.

Special attention must also be given to the selection of light metal casting alloys. It is generally not possible to solution treat (T-6) because of the thermal shock placed on the bond during quenching. Alloys specified should, therefore, either be usable in the as-cast condition or be responsive to artificial aging.

***continued on next page***

## Composite Materials

### Honeycomb Sandwich Structures

A wide variety of core and facing materials are possible with honeycomb sandwich structures, each composition offering a special combination of properties to meet specific end service requirements. In general, all honeycomb sandwich structures offer these characteristics: high strength-to-weight ratio; resistance to heat transfer and vibration; use of nearly any structural material; close tolerances; high speed production; and ease of fabrication.

Honeycomb sandwich structures are used in practically every aircraft or missile flying today. Typical of aircraft uses are wings, ailerons, rotor blades, trailing and leading edges, doors, flooring, bulkheads, stabilizers, radomes, fuselage sections, elevators and rudders. They are also used for such commercial applications as building wall panels, flooring for trailers, small boat hulls, shipboard doors and bulkheads, table tops, pallets, truck panels and doors, stressed skin buildings, furniture, etc. Some recent applications include gas turbine seals, oil seals, heat radiators, shock absorbers, electromagnetic shielding and noise suppressors.

**Honeycomb sandwich theory.** Honeycomb structures can be best compared to I-beams. The facings correspond to the flanges, the object being to place a high density, high strength material as far from the neutral axis as possible and thus increase the section modulus. The honeycomb core is comparable to the web of an I-beam which supports the flanges and allows them to act as a unit. The honeycomb, like the web, carries the shear stresses. However, honeycomb differs from I-beam webs in that it maintains continuous support for the facings, allowing the facings to be worked up to or above their yield strength without crimping or buckling. The adhesive which bonds the honeycomb to its facings must be capable of transmitting shear loads between the two components, thus making the entire structure an integral unit.

When the sandwich panel is loaded as a beam, the honeycomb and the bond resist shear loads while the facings resist the moments due to bending forces, and hence carry the tensile or compressive load. When loaded as a column, the facings alone resist the column forces while the core stabilizes the facings to prevent buckling.

Although comparable to I-beams, honeycomb sandwich structures are actually more efficient. The combination of high density facings and low density cores provides a much higher section modulus per unit density than any other known construction method. Thus, for an equivalent rigidity factor, weight of an aluminum-faced honeycomb sandwich structure beam is only ⅛ that of birch plywood, 1/10 that of solid aluminum and 1/16 that of solid steel.

**Facing materials.** Theoretically, any thin, bondable material with high tensile or compressive strength-weight ratio is a potential facing material for honeycomb panels. The materials most commonly used for facings are aluminum, steel, glass-reinforced plastics and wood. The facing can be finished with special exterior effects, such as decorative paints and enamels, or rough surfaces for anti-skid floor panels. In some cases, the skin may be embossed with a regular pattern to provide a special effect.

*Aluminum*—Alloys such as 7075-T6, 2024-T3 and 2014-T6 are commonly used facing materials in thicknesses from 0.010 in. to 0.064 in. for structural, as well as nonstructural, applications. Aluminum is generally not used for applications where temperatures exceed 400 F for long periods of time. Anodizing or coating with a protective resin can be done where increased corrosion resistance is desired.

*Stainless steel, superalloys*—Because of their good strength at elevated temperatures, these facings are finding increased usage in aircraft. Some of these facings have been found to perform satisfactorily at tempertaures as high as 2000 F. Porcelain enameled steel is also available for special applications.

*Glass-reinforced plastics*—Where parts must have a complex contour, glass-reinforced plastics are ideal. They also offer these special advantages: excellent weight control—it is easy to build up material where it is needed and leave faces thin where excess material is not needed; excellent insulation and heat reflections; excellent medium temperature strength; high strength-weight ratio; high impact strength; and compatibility with other materials.

*Plywood*—Plywood facings are available for both structural and nonstructural applications. The most common use of plywood facings, however, is in interior and exterior doors of buildings. Plywood facings for doors are usually bonded to a paper honeycomb core.

*Resin-impregnated paper*—Paper facing materials are generally used for flat, nonstructural panels such as interior walls and partitions.

**Core materials.** Honeycomb cores are produced from a number of materials, including aluminum, glass or asbestos-reinforced plastics, and paper. In addition, stainless steel, titanium, and some superalloy cores have been developed for special environmental applications. Theoretically, any metal that can be made into a foil and then welded, brazed or adhesive bonded can be made into a honeycomb.

*Aluminum*—Cores are supplied in the expanded or unexpanded form in thicknesses from 0.060 in. to 18 in. or more. By varying cell size and gage, honeycomb density can be closely controlled over a wide range. Aluminum core is available in cell sizes varying over a range of densities from 1.2 to 8.1 lb per cu ft.

The two most common aluminum alloys used are 3003-H19 and 5052-H39. The major difference between the two alloys is that the 5052 alloy has about 20% more compressive and shear strength at equal densities. Alloy 5056 is now available in a few cell sizes and densities.

*Stainless steels, superalloys*—These alloys are generally used where service temperatures are too high to permit use of aluminum or glass-reinforced plastics (this is also true of titanium). Alloys most

commonly used for temperatures above 900 F are these heat treatable stainless alloys: 17-7PH, PH 15-7Mo, AM-350 and AM-355; and these heat treatable superalloys: A-286, Inconel X and L 605.

Non-heat treatable metals, such as the plain austenitic stainless steels (AISI 321) and Inconel, are used for light loaded parts at temperatures up to about 1800 F. Above 1800 F, only the refractory metals, such as molybdenum, tantalum or columbium, can be used.

*Titanium*—Although titanium honeycombs are more or less competitive with stainless steel, their use is limited by difficulties encountered in forming and machining. Alloys most commonly used, however, are Ti-75, 6 Al-4 V, A110 and the DOD alloys.

*Glass-reinforced plastics*—Many formulations are available, most of which are made by impregnating a glass cloth with resin, expanding to a honeycomb structure, curing, and repeatedly coating with a polyester, phenolic, epoxy or silicone resin. These cores are generally available in cell sizes ranging between 3/16 in. and ⅜ in., and in thicknesses ranging from 0.060 in. to 18 in. Density, which ranges from 2.5 to 16 lb per cu ft, can be varied by changing cloth thickness and amount of coating. Glass-plastics cores are normally formed in regular blocks or slices but are available in slices pre-curved to specified contours.

*Paper*—Paper honeycomb is usually impregnated with a phenolic resin for strength, rigidity and moisture resistance. Cell sizes vary between ⅛ in. and 1.2 in. Standard core thicknesses are available from ¼ in. to 6 in. Depending on paper thickness and amount of impregnation, densities range between 1.5 and 4.0 lb per cu ft.

**Design.** The loads, their orientations and the configuration of the part determine the type of stresses which must be resisted. Generally, these stresses fall into the following categories: compression, tension, shear, peel and buckling. Honeycomb sandwich structures are almost always designed for flexural loading and therefore consist of thin, high density facings bonded to a relatively thick, low density honeycomb core.

The same formulas used to calculate stresses in I-beams can be used to determine the stresses developed in honeycomb panels. Other important design criteria include the following:

*Creep*—Creep properties of a honeycomb panel under load are primarily a function of the adhesive, the service temperature and the time at temperature. With proper selection of the adhesive, most creep requirements can be easily met.

*Impact*—In some cases, high concentrated impact loads, especially in flooring applications, outweigh all other design considerations. A thin facing material will generally satisfy all tensile and compressive requirements, but thicker facings are usually specified to resist impact. A thicker facing distributes the impact load over a wider area, thus reducing the stress on the core.

Often floor panels are designed with different facing thicknesses to provide maximum resistance at areas of greatest impact. When panels are subjected to extremely high impact loads, a thin wood veneer or layer of phenolic laminate is bonded to the facing.

*Fatigue*—Honeycomb sandwich structures are probably more resistant to fatigue than any other construction due to the continuous nature of the bonded surface. The most critical parts of the structure in regard to fatigue are the attachment points. When subjected to fatigue tests, a panel will usually fail at these points.

*Environment*—Temperature, time at temperature, moisture, and the existence of various fluids and gases are all important design considerations. However, all of these factors are dependent upon the materials being used. Suggested sandwich structures for elevated temperatures are given in the table at the bottom of this column.

**Joining.** Honeycomb sandwich structures can be joined by several methods.

Generally, honeycomb structures cannot withstand the compressive loads caused by bolts, rivets, screws, and other mechanical fasteners. However, a great number of inserts and special fasteners have been devised to overcome this problem. Inserts include wood, plastics or metal strips; molded-in plastics blocks; and aluminum spacer inserts.

Stainless steel and other heat resistant honeycombs can be joined by resistance welding and brazing.

The most common method used is adhesive bonding. Several types of adhesive are used: rubber-base cements, a combination of thermosetting resins and elastomeric polymers, epoxy resins, epoxy-phenolic systems, and duplex tapes consisting of a supported film adhesive (combination thermosetting resin and elastomeric polymer) on one side and a film of semi-liquid epoxy on the other.

**RECOMMENDED HIGH TEMPERATURE STRUCTURES**

| Temp, F | Core | Facing | Remarks |
|---|---|---|---|
| Up to 350..... | Aluminum | Aluminum | Retains ¾ strength at 300 F; 2/3 at 350 F |
| Up to 500..... | Glass-reinforced plastics | Steel or titanium | Retains good strength at 500 F; some resins begin to deteriorate after few hours |
| 350-1000..... | Steel | Steel or titanium | Depends on brazing materials, alloy used and temper; silver brazing alloys good to 850 F |

## Clad Metals

| Surface ↓ | Base Metal | | Critical Functions, Properties | Typical Applications |
|---|---|---|---|---|
| | Metal | Form | | |
| **Aluminum and Its Alloys** | | | | |
| Aluminum [a] | Low carbon steel | Strip | High temperature oxidation resistance. At 1000 F forms alloy with 85% emissivity. Cheaper than carbonated nickel or nickel-clad steel. Conserves nickel | Anode plates for electronic receiving tubes |
| Aluminum [b] | Low carbon steel | Strip | Same as above, but suitable for higher temperatures | Anode plates for receiving tubes where close spacing makes temperatures too high for aluminum |
| 1100 | Aluminum (2024) | Sheet | Atmosphere resistance. Galvanic protection. Strong base | Aircraft frames, cooking utensils, hardware |
| 6053 | Aluminum (2014) | Sheet | Atmosphere and wear resistance. Galvanic protection. Workable base | Power shovel bails, aircraft fittings, heavy duty forgings |
| 6053 | Aluminum (5056) | Wire | Same as above | Insect screening |
| 7072 | Aluminum (3003 or 3004) | Sheet | Atmosphere resistance. Galvanic protection. Workable, weldable base | Cooking utensils, gasoline and oil tanks, bus and train trim |
| 7072 | Aluminum (3003) | Tube | Same as above | Heat exchangers |
| 7072 | Aluminum (7075) | Sheet | Atmosphere resistance. Galvanic protection. Strong base | Aircraft structural parts |
| **Copper and Its Alloys** | | | | |
| Brass [c] | Low carbon steel | Strip | Decoration. Atmosphere resistance. Good solderability | Cosmetic cases, frames, gaskets |
| Brass [d] | Low carbon steel | Wire | Decoration. Atmosphere resistance. Strong base. Conserves brass | Curtain rods, indoor television antennas, lamp stands |
| Copper | Carbon steel | Wire, ribbon | Electrical conductivity. Atmosphere resistance. Strong base. Conserves copper | Lead-in wires for electronic tubes, communication and power lines, springs |
| | Aluminum (1100 or 5052) | Sheet, strip, tubing, wire, bars | Thermal, electrical conductivity. Good solderability. Lightweight base. Conserves copper | Waveguides, variable condenser blades, heat transfer fins, jewelry, shims, bushings |
| | Beryllium copper (25) | Strip | Electrical conductivity. Good spring properties | Current-carrying springs |
| | Low carbon steel | Strip | Atmosphere resistance. Thermal conductivity. Good solderability. Strong base. Conserves copper | Gaskets, automotive radiator tanks, electrical contacts and switches, immersion heater base plates |
| | High carbon steel | Strip | Electrical conductivity. Plating base. Good spring properties | Clips, thin-blade or spiral-type springs |
| | Low alloy steel (with boron) | Wire | Electrical conductivity. Atmosphere resistance. Strong base. Conserves copper | Grid support rods for electronic tubes, communication lines, plated costume jewelry |
| | Carbon or low alloy steel | Plate, heads | Resistance to corrosion, erosion. Conserves copper | Chemical process equipment |
| Cupro-Nickel | Low carbon steel | Strip | Same as above | Chemical process equipment |
| Phosphor Bronze [e] | Copper | Strip | Good spring properties. Base has high electrical conductivity | Current-carrying springs and blades |
| **Gold and Its Alloys** | | | | |
| Gold [e] | Bronze, nickel-silver, nickel, sterling silver | Strip, tubing wire | Decoration. Atmosphere resistance. Relatively low cost base | Jewelry, including watchcases, bracelets, rings, lockets |
| Gold [f] | Copper, brass, nickel, monel | Strip | Chemical resistance. Relatively low cost base | Bursting disks, other chemical process equipment |
| **Lead and Its Alloys** | | | | |
| Lead [g] | Copper, low carbon steel | Tubing | Chemical resistance. Good strength, high thermal conductivity | Heat exchanger coils for chemical process equipment |
| Lead | Low carbon steel | Plate, sheet, strip, rod | Chemical resistance. High density. Strong base | X-ray, radium, nuclear and chemical equipment |

[a] ½% silicon. [b] ½% silicon with 330 nickel on other side. [c] 70–30 or 85–15. [d] Over copper. [e] 10 K or more. [f] 14 K or more. [g] ASTM B29.

## Clad Metals

| Surface ↓ | Base Metal | | Critical Functions, Properties | Typical Applications |
|---|---|---|---|---|
| | Metal | Form | | |
| **Nickel and Its Alloys** | | | | |
| Inconel, Monel | Carbon or low alloy steel | Plate, heads | Resistance to corrosion, erosion. Low cost base. Conserves nickel | Process equipment |
| Nickel | Copper | Wire, ribbon | High temperature oxidation resistance. Electrical conductivity | Electrical circuits subjected to high temperatures |
| Nickel | Iron or carbon steel | Wire, ribbon | Atmosphere resistance. High temperature oxidation resistance | Grid support rods, lead-in wire for tubes; typewriter key levers, springs |
| A Nickel | Copper | Wire, ribbon | Corrosion resistance. Electrical conductivity | Electrical circuits subjected to corrosive atmospheres |
| A or L Nickel | Carbon or low alloy steel | Plate, heads | Resistance to corrosion, erosion. Low cost base. Conserves nickel | Process equipment |
| L Nickel | Brass, low carbon steel | Strip | Same as above | Process equipment |
| 330 Nickel | Low carbon steel | Strip | High temperature oxidation resistance. High emissivity. Conserves nickel | Anode plates for electronic receiving tubes |
| **Platinum and Platinum Group Alloys, Silver** | | | | |
| All | Copper, brass, bronze, nickel | Strip | Electrical contact properties. Chemical resistance. Low cost base | Electrical contacts, slip rings, chemical crucibles |
| Platinum | Copper, brass, bronze, nickel | Tubing, wire | High chemical resistance. Low cost base. Thermal conductivity | Heat exchangers for chemical processes |
| Platinum | Molybdenum | Wire | High work function (low primary electron emission). Refractory base | Grids for tubes, particularly for use with thoriated cathodes |
| Silver | Copper, nickel | Wire, ribbon | Atmosphere resistance. High temperature oxidation resistance. Electrical conductivity. Low cost base | High temperature coils, high frequency conductors, braiding for radar cables |
| | Aluminum (1100, 5052) | Strip | Electrical contact properties. Electrical conductivity. Lightweight, low cost base. Decoration | Conductors, contacts in aircraft electrical equipment. Costume jewelry |
| | Aluminum, brass | Tubing | Electronic transmission characteristics. Low cost base | Waveguides for electronic transmission lines |
| | Beryllium copper (25) | Strip | Electrical conductivity and contact properties. Good spring and fatigue properties | Contact arms for buzzer circuits, other current-carrying springs |
| | Copper, brass | Strip | Electrical contact properties. Low cost base | Electrical contacts, slip rings, flexible waveguides |
| | Invar | Strip | Good electrical contact properties. Low thermal expansion | Television antenna connectors |
| | Monel, nickel | Strip | Electrical contact properties. Corrosion resistance. Low cost base | Electrical contacts subject to corrosion or excessive wear |
| | Phosphor bronze (A,C,D) | Strip | Electrical conductivity and contact properties. Good spring properties | Electrical contact springs |
| **Stainless Steel** | | | | |
| Austenitic [a] | Copper | Strip | Resistance to corrosion, erosion. Thermal conductivity. Workable base | Heat exchangers for chemical processes |
| Ferritic [b] | Copper | Strip | Corrosion resistance. Thermal conductivity. Uniform heat transfer. Workable base. Decoration | Pots and pans |
| Stainless | Carbon or low alloy steel | Plate, heads | Resistance to corrosion, erosion. Workable, low cost base metal | Process equipment |
| Stainless | Low carbon steel | Sheet, plate | Same as above. Decoration | Process equipment, auto bumpers, grilles and trim, display cases, sterilizers |
| Ferritic | Low carbon steel | Strip | Corrosion resistance. Decoration. Workable, low cost base metal | Cooking utensils, auto bumpers, grilles and trim |

[a] 304, 310. [b] 430.

DOW | *Now in magnesium and aluminum*

# NEW DOW DEVELOPMENTS PROVIDE DESIGNERS WITH ADDED ADVANTAGES IN LIGHTWEIGHT MAGNESIUM

**Lightness, ease of fabrication and other features of magnesium contribute to improved designs for many products—from airplanes and missiles to luggage . . . from industrial machinery to cameras. Now, new developments by Dow provide greater design flexibility than ever before—in fabricated components you require, in materials and processes to facilitate your plant's operations.**



New sheet is bent without heated dies.

## NEW CLOSE SHEET TOLERANCES HELP SOLVE WEIGHT PROBLEMS

When the design problem is stress distribution versus weight, the new, closer magnesium sheet tolerances available from Dow upon special request offer a real advantage. As shown below, new tolerances are one *half* of standard tolerances. This permits designers to provide for required stress distribution, based on minimum thickness, *without* having to accommodate all the extra weight that might occur with the maximum thickness permissible with conventional tolerances.

Especially useful for aircraft and missile designers, this close tolerance sheet is also suggested for use in air-transported equipment or wherever minimum weight is critical.

COMPARISON OF TOLERANCES

*48-inch-wide sheet*

| Gauge | Close Tolerances | Standard Tolerances |
|---|---|---|
| .032" | ±.0013" | ±.0025" |
| .040 | ±.0015* | ±.003 |
| .050 | ±.002 | ±.004 |
| .063 | ±.002 | ±.004 |
| .071 | ±.002 | ±.004 |
| .080 | ±.002 | ±.004 |
| .090 | ±.002 | ±.004 |
| .100 | ±.0025 | ±.005 |
| .125 | ±.0025 | ±.005 |
| .160 | ±.004 | ±.008 |
| .190 | ±.005 | ±.010 |

*For HM21A-T8 .040" close tolerance is ±.002".

## NEW SPECIAL BEND SHEET ELIMINATES HEATED DIES

Critical bends can now be easily formed at room temperature — *without heated dies*—using Dow's new AZ31B-O Special Bend Sheet. Without cracking, it bends through an angle of 90° around a mandrel radius as small as two times the nominal sheet thickness. Among many suggested applications are housings for electronics equipment, truck cabs, shipping containers, plus such military uses as maintenance and personnel shelters and housings for ground support equipment.

BEND FACTORS


| Nominal thickness | Longitudinal bend factor | Transverse bend factor |
|---|---|---|
| 0.040"–0.100" | 2.0 | 2.5 |
| 0.101"–0.190" | 2.5 | 3.0 |

Tensile yield strength meets Federal Specifications AA-M-44.

## PRECISION MAGNESIUM EXTRUSIONS CUT MACHINING COSTS

Dow precision magnesium extrusions provide exact-tolerance finished or semi-finished components and eliminate many costly multiple machining operations. Exacting tolerances are even possible with sharp V's, deep notches, thin slots, sharp serrations, as well as precision diameter tubing. And with precision extrusions, cost of materials is also frequently less because high-property alloys to withstand extensive machining are not needed.

Applications include bearing blocks, impact extrusion stock, parts for business machines, printing furniture, screw machine stock, shaft shear keys, spacers and airfoil configurations.



Exact-tolerance extrusions cut machining costs.

## NEW FINISHES BROADEN APPLICATIONS FOR MAGNESIUM

*Porcelain enamel,* a practically foolproof way to avoid corrosion, can now be applied to magnesium, using a Dow-developed pretreatment to assure adhesion. Suggested applications—display signs, building panels, cooking ware, home appliances, engine parts.

*Dow 20 chrome pickle* provides a uniform paint-base for casting alloys with high aluminum content.

*Dow 21 ferric nitrate bright pickle,* as a spray or dip, provides long-lasting protection under clear baking enamels or lacquer.

*Clear anodic coating,* applied in less than a minute, provides maximum protection under lacquer or varnish, which may be tinted in a wide range of colors.


*Nickel plating,* by immersion instead of electroplating, simplifies processing, improves nickel surface. For electronics equipment, printing plates and cylinders, other surfaces requiring extreme wear resistance.

*Vinyl* may be laminated before cold-forming magnesium sheets—also bonds to hot-formed shells. For luggage, carrying cases, other applications.



Vinyl-laminate adds sales appeal to carrying cases, luggage.

## DOW CASTS MAGNESIUM IN INTRICATE DESIGNS



Casting incorporates tubeless passages.

Cast-in tubeless passageways, thin sections, close tolerances and other intricate designs are all available in castings made in production quantities at Dow's sand and permanent mold foundry.


## NEW ALLOY ELIMINATES STRESS RELIEF AFTER WELDING

A newly developed Dow alloy for magnesium sheet and plate, ZE10A, containing zinc and rare earth metal, does away with the need for stress relief after welding . . . particularly advantageous in building large structures. Suggested applications – large shipping and storage containers, even tank-trailer bodies. So that designers can take full advantage of this new sheet and plate material, Dow also provides magnesium extrusions in alloys requiring no post-welding stress relief.

## VAST PRODUCTION FACILITIES FOR MAGNESIUM AND ALUMINUM

The Dow Metal Products Company offers a new die casting plant, a sand and permanent mold foundry, a fabrication plant plus the huge Madison plant for sheet, plate and extrusions. At Madison, for example, is the giant 13,200-ton press that extrudes king-size sections of magnesium or aluminum—up to 30 inches across and 80 feet long.

For more information about the new magnesium developments shown here, or for help in any design or fabrication problem involving magnesium or aluminum, contact the nearest Dow sales office. Or write THE DOW METAL PRODUCTS COMPANY, Midland, Michigan, Merchandising Department 1053CD11.




King-size extrusions make possible freedom in design.

DOW **THE DOW METAL PRODUCTS COMPANY**

*Division of The Dow Chemical Company*

For more information, turn to Reader Service card, circle No. 405



**NEW DIMENSIONS IN DESIGN**

**NEW CONCEPTS OF ECONOMY**

# ACIPCO CERAM-SPUN Steel Tubing

In all types of industry, versatile Acipco centrifugally spun tubing is giving the design engineer greater freedom. Furnished with the exact combination of physical, chemical and metallurgical properties required by design, manufacturing and service conditions, high quality Acipco tubing helps create both new dimensions in design and new concepts of economy.

You can order any combination of lengths, O.D.'s and wall thicknesses because Acipco is not limited by equipment sizes. This new ceramic mold process can economically produce an infinite variety of lengths, from a minimum of 4′ to a maximum of 20′ as cast, and longer lengths can be produced by fabricating.

If you design, manufacture, or use parts requiring tubular metal stock as a component, an investigation of the versatility of Acipco tubing and the flexibility of Acipco's integrated facilities for spinning, heat treating, machining, fabricating and testing will be worth your while.

## COMPLETE FACILITIES

**SPINNING**

Acipco Steel Tubes are centrifugally spun to exact physical and metallurgical specifications. The exact size and metal analysis your process or project requires is assured.

**FABRICATION**

Complete, integrated facilities for machining, welding, finishing and heat treating of tubular parts save shipping time and expense for Acipco customers.

**TESTING**

Facilities for both hydrostatic and air testing, as well as for other physical and chemical analyses and tests, are available as part of complete Acipco steel tube service.

**INSPECTION**

Expert inspection, including radiography, during all phases of production, helps keep Acipco steel tube quality high.

**TECHNICAL ASSISTANCE**

A staff of highly trained engineers, metallurgists, chemists and craftsmen serves the designer and manufacturer who specify Acipco Steel Tubes.

**SIZE RANGES:** Tubes are produced in lengths from 4′ to 20′; longer lengths can be made by welding. O.D.'s from 2.25″ to 50″—wall thicknesses from .25″ to 8″.

**ANALYSES:** All alloy grades in steel and cast iron, including heat and corrosion resistant stainless steels, plain carbon steel and special non-standard analyses.

**FINISHES:** As cast, rough machined, or finish machined, including honing and grinding. Complete welding and machine shop facilities are available.

ACIPCO

SPECIAL PRODUCTS

DIVISION OF AMERICAN CAST IRON PIPE CO.

BIRMINGHAM 2, ALABAMA

For more information, turn to Reader Service card, circle No. 381

# *The seams don't show*

Beautiful fit, beautiful look, beautiful soft drink dispenser. Beautiful job of close tolerance molding by General American. Working from wooden patterns, General American engineers designed six individual moldings. The shrinkage of each separate part was calculated to the thousandths of an inch. General American made the tools with the same precision.

Result—when this soft drink dispenser is assembled the seams are practically unnoticeable. In addition, the selection of the proper plastic, combined with General American's skill in molding, provides a product with very good luster, high impact properties, excellent stain resistance—and a reasonable price tag.

If you have a part or product that could or should be made of plastics, consult General American. In plastics, *it pays to plan with General American.*

## *in this 6-piece soft drink dispenser*




GENERAL AMERICAN TRANSPORTATION CORPORATION

*Plastics Division*

*135 South LaSalle Street • Chicago 90, Illinois*


*Offices in Principal Cities*

PLASTICS DIVISION GENERAL AMERICAN TRADE MARK

For more information, turn to Reader Service card, circle No. 421

# Why ACADIA LATHE-CUT SYNTHETIC RUBBER SEALS

## can save you money in *STATIC* or *MOVING* seal applications



MOLDED O-RING SEAL

LATHE-CUT SEAL

This seal will save you money with no performance sacrifice. Minimum tooling cost, no molds, no costly delays. Can be made up to 25" I.D.

Acadia Synthetic Rubber Parts are of the highest quality components, processed for oil resistance, good aging properties, resistance to heat. They can be furnished in any dimension or special compound you desire to precision tolerances. They are another example of Acadia's ability to SAVE YOU MORE..SERVE YOU BETTER.

*There's an Acadia Sales engineer near you to serve you. Write us today, and we'll put him in touch with you immediately.*


**ACADIA** *Synthetic* **PRODUCTS**

DIVISION OF WESTERN FELT WORKS
Dept. D, 4021-4139 West Ogden Avenue, Chicago 23
*Branch Offices in Principal Cities*

MANUFACTURERS AND CUTTERS OF WOOL FELT

For more information, turn to Reader Service card, circle No. 376

A DRAMATIC DEMONSTRATION OF THE NEW CLAD-REX 102 LAMINATE



Boiling water provides a positive test for two deep drawn* vinyl-clad parts. Neither special care in forming, nor post curing has been used to prepare either part.

Almost within a matter of seconds, the part formed of conventional vinyl-clad metal (at right) begins delaminating at the corners.

Even after as long as four hours of boiling, the part formed of new Clad-Rex 102 laminate (at left) still shows no delamination whatsoever.

# New Clad-Rex vinyl-clad metal sharply reduces limitations in deep drawing and heat exposure

Has your interest in vinyl-clad metals been cooled because your product is deep drawn? . . . or because your product is exposed to elevated temperatures? . . .

Now, you can solve the problem with new Clad-Rex 102. It's a new vinyl-metal laminate that is, in effect, a single element of material. Clad-Rex 102 combines *for the first time* the ultimate properties of sheet metal with the optimum characteristics of vinyl.

Call or write for facts of this major technological breakthrough by the extensive research laboratories of Simoniz Company.

*Depth of draw equal to six times radius of corner

VINYL-METAL LAMINATES BY **CLAD-REX**® DIVISION OF SIMONIZ COMPANY

**11514 W. King Street • Franklin Park, Illinois**

**Telephone: GLadstone 1-2323**

22C

For more information, turn to Reader Service card, circle No. 404

*TubeXperience in action*



# TUBING MAY LOOK ALIKE

## But one is a better buy

And that is another reason why anyone concerned with the use of tubing should keep continually abreast of the materials available to him. The subject is not one that can be learned and remembered—it is being ceaselessly revised. Here at Superior, world's largest producer of small-diameter tubing, development of new materials is a program that has no end. As technology advances, so does our range of analyses.

Over 120 materials are offered. Included are analyses that have been modified in order to meet changing requirements and more exotic service conditions. In the selection of the right material from our big array can lie your opportunity to meet challenging problems of design or to enhance the performance of your applications already devised—perhaps even lower your unit cost through longer service life.

We also offer you excellent service through a network of knowledgeable distributors coast to coast. And you can freely call on us, in complete confidence, if you have some tough problem and wish to share its complexities. For interesting particulars, send for a copy of our Bulletin 42. Superior Tube Company, 2006 Germantown Ave., Norristown, Pa.

## AMONG OUR NEWER MATERIALS

### Grades putting the little-used metals to service

**Zircaloy-4.** An alloy of zirconium, tin, iron, and chromium. Essentially like Zircaloy-2 except for the absence of nickel, it is less subject to hydrogen embrittlement. For this reason, this new zirconium alloy is being investigated for use as fuel element cladding in nuclear reactors, its principal application thus far.

**Columbium Alloy with 1% Zirconium.** This is one of several columbium alloys with which we are experimenting. Already it is being used to replace the unalloyed metal as fuel element cladding in nuclear reactors because it is twice as strong at elevated temperatures. It is a soft, ductile alloy, easily welded or fabricated. In certain applications its corrosion resistance is superior to that of unalloyed columbium.

**Tantalum.** We have been drawing tantalum tubing since 1945. The higher purity grades now produced permit new possibilities to be foreseen where weight is not a factor (0.60 lb/cu in.). It has a high melting point: 5425°F. Of significance is its excellent resistance to acids. It is easily cold-worked and weldable to itself. One of the growing applications for tantalum tubing has been for thermocouple sheathing where its outstanding corrosion resistance can be used to excellent advantage.

**Beryllium.** Pure beryllium tubing drawn and sized in the hot condition has wide use in the nuclear and aircraft/missiles industries because of its combination of characteristics, such as low neutron absorption, desirable thermal properties, and high strength-to-weight ratio.

**Send for technical bulletins on the above**

## PUT THE "SUPER ALLOYS" TO WORK FOR YOU

### Alloys for high-temperature strength

In 1948 and again in 1957 we published data on "Super Alloy" tubing. Within the last three years we have been able to accumulate a vast amount of additional information on the subject. We present it in detail in our Bulletin 71, just off the press. Covered are eight of the "Super Alloys," those which have attracted the most interest and apparently have the greatest potential for usefulness. We want you to have a copy—drop us a line.

## STANDARD AND SPECIAL SUPERIOR TUBING MATERIALS

| Standard | | Special |
|---|---|---|
| **Stainless** | | **Stainless** |
| 303 | 321 Super Pressure | 317 |
| 304 | 347 | D319 |
| 304 Hydraulic Qual. | 347 Hydraulic Qual. | 330 |
| 304 Super Pressure | 347 Super Pressure | 405 |
| 304L | 348 | 416 |
| 305 | 403 Mod. | 17-7PH[2] |
| 309 | 410 | N-155[3] |
| 310 | 420 | 19-9DL[4] |
| 316 | 430 | PH15-7 Mo[2] |
| 316 Super Pressure | 430 Ti | |
| 316L | 446 | |
| 321 | 502 | |
| 321 Hydraulic Qual. | A-286[1] | |
| **Nickel and Nickel Alloys** | | **Nickel and Nickel Alloys** |
| Low Carbon Nickel[5] | Inconel X[5] | D Nickel[5] |
| A Nickel[5] | Ni-Span C[5] | DURANickel[5] |
| Monel[5] | Hastelloy C[6] | Nionel[5] |
| 403 Monel[5] | Hastelloy X[6] | Inconel 702[5] |
| K Monel[5] | Haynes 25[6] | Hastelloy F[6] |
| R Monel[5] | 80% Ni-20% Cr Alloy | Permalloy[7] |
| Inconel[5] | Invar | Waspalloy |
| **Copper Base Alloys** | | **Copper Base Alloy** |
| 30% Cupronickel | OFHC Copper | Berylco # 10[8] |
| Beryllium Copper | Deoxidized Copper | |
| Constantan | | |
| **Reactive Metal** | | **Reactive Metals** |
| Unalloyed Titanium A-40 | | Zirconium |
| | | Zircaloy-2 |
| | | Zircaloy-3 |
| | | Zircaloy-4 |
| | | Columbium |
| | | Tantalum |
| | | Vanadium |
| **Carbon Steels** | | |
| C-1008 | MT-1020 | |
| C-1008 Diesel | C-1025 | |
| MT-1010 | C-1035 | |
| MT-1015 | C-1045 | |
| Leaded C-1020 | E-1095 | |
| Ingot Iron | | |
| **Alloy Steels** | | |
| 4130 | 4140 | |
| 4130 Bourdon | 4150 | |
| 4130 Super Pressure | 4615 Diesel | |
| 4132 | 8630 | |
| 52100 | | |
| **Glass Sealing Alloys** | | |
| (446) 27% Chrome | Sylvania # 4[9] | |
| 42% Nickel-Iron | Rodar[10] | |
| 52% Nickel-Iron | Kovar [11] | |
| Therlo[12] | | |

**Registered Trademarks**

[1]Allegheny Ludlum Steel Corp.
[2]Armco Steel Corp.
[3]Union Carbide Corp.
[4]Universal Cyclops Steel Corp.
[5]International Nickel Co.
[6]Haynes Stellite Co.
[7]Western Electric
[8]Beryllium Corp.
[9]Sylvania Electric Products, Inc.
[10]Wilbur B. Driver Co.
[11]Stocked and sold through the Stupakoff Div. of the Carborundum Co., Latrobe, Pa., TM Reg. U.S. Patent Office, Westinghouse Electric Corp.
[12]Driver-Harris Co.

**Superior Tube**

**The big name in small tubing**

**NORRISTOWN, PA.**

*All analyses .010 in. to 5/8 in. OD—certain analyses in light walls up to 2½ in. OD*

**West Coast: Pacific Tube Company, Los Angeles, California • FIRST STEEL TUBE MILL IN THE WEST**

**For more information, turn to Reader Service card, circle No. 469**



# IPC has a new baby!

I.P.C.'s extensive research in the area of fluorocarbon plastics has given birth to *a whole new series of custom seals, ball seats, diaphragms, V, cup and flange packings.*

Designated as the F-C series, these thoroughly tested components are literally a blend of I.P.C. synthetic rubbers and fluorocarbon plastics. This unique combination produces seals and packings with *lower friction, less torque, better corrosion resistance and reduced shaft wear.*

You can handle increased pressures . . . higher shaft speeds *and* most high temperature applications with F-C seals and packings. Special molding machinery and techniques have been developed by I.P.C. to produce this combination. Synthetic rubber, fluorocarbon plastics and steel cases are brought together in one operation to provide the last word in high quality case seals.



IPC

OIL SEALS
PACKINGS
PRECISION MOLDING
*Custom designed for your application.*

*There's good reason to look at the newest member of I.P.C.'s* custom family *in terms of your sealing problems. Do it soon; Won't you?*

## INTERNATIONAL PACKINGS CORPORATION

Bristol, New Hampshire

© IPC

P4


For more information, turn to Reader Service card, circle No. 432

# COMPLETE HIGH ALLOY CASTING SERVICE

**CENTRIFUGAL CASTINGS • STATIC CASTINGS • SHELL MOLDED CASTINGS**

**resisting corrosion, high temperatures, abrasion**

## CENTRIFUGAL CASTINGS




Because of the specially desirable characteristics imparted to the metal in a centrifugal casting, this type is showing up more and more in design and purchase specifications. Each casting must have a straight concentric bore, the diameter of which is controllable.

The important point to remember about centrifugal castings is that the metal is exceptionally uniform in structure and dense, brought about partly because metal molds are used which produce an increased chilling effect and improved density. The centrifugal force practically eliminates the possibility of blow holes or gas pockets. In fact, this same force gives much the same effect on the casting that is obtained when forging or working a bar or ingot.

Outside diameters from 2½" to 32", lengths generally 24" to 180".

## STATIC CASTINGS




These are the so-called conventional type of castings, utilizing stationary sand molds. With our large battery of electric furnaces, we can operate with considerable flexibility. We have very small furnaces permitting us to cast economically just a "few" small lightweight pieces. Or we can combine our melting capacities to produce a single heavy tonnage piece. With all available furnaces working, we can carry on a variety of melts simultaneously.

Static castings can be produced in weights ranging from a few ounces to single castings 7 tons and heavier; wide range of alloying combinations, including the new HOM.*


*Covered by U.S. Patents

## SHELL MOLDED CASTINGS



For several years now we have been producing in steadily increasing tonnages a great variety of high alloy castings by the shell molded method.

Shell molded castings can be made very economically when smaller pieces on a mass production basis are involved. The weight of the individual piece can range from an ounce or two to several pounds. The major advantage in a shell molded casting over other types of casting is in the exceptionally close adherence to design dimensions plus usually a much superior surface. Subsequent machining of the part is practically eliminated. From the design point of view, the shell molded piece can be cast in more intricate design and with thinner sections than when conventional castings are used.



If the casting used in your equipment has to meet high temperature (anything up to 2300°F) and/or corrosion, why not discuss your requirements with our metallurgical staff? Our company can call upon more than 35 years of experience in this exacting business of high alloy castings. In the meanwhile, if you would like to have a copy of our latest catalog, write or call our nearest office for Catalog No. G-159.

ALLOY CASTING INSTITUTE ACI MEMBER




**The DURALOY Company**

**OFFICE AND PLANT: Scottdale, Pa.**

**EASTERN OFFICE: 12 East 41st Street, New York 17, N. Y.**
**CHICAGO OFFICE: 332 South Michigan Avenue**
**DETROIT OFFICE: 23906 Woodward Avenue, Pleasant Ridge, Mich.**

**For more information, turn to Reader Service card, circle No. 409**



# What other process could do it so well?

All things considered, there's really only one *best* way to produce this typical die casting application.

When you figure that it must be built at the lowest possible unit cost, must use a production method that is highly flexible to accommodate the unusual shape, and must maintain a variety of close tolerances . . . only die casting *could* do the job.

Working closely with Twin City engineers, this manufacturer *designed* for die casting to get the maximum out of the process. By thinking in terms of die casting right from the drawing boards he eliminated many production and finishing jobs, saved on unit costs, saved on machining.

Possibly you're producing a part by some more costly, less flexible, less accurate process than die casting. If you think that might be true, contact Twin City Die Castings Company. Twin City engineers can probably save you money. They have for hundreds of customers.

**. . . only DIE CASTING can**

**✓ cut your costs**

**✓ offer such flexibility**

**✓ provide such accuracy**

*FOR PROOF . . . CALL, WRITE OR WIRE:*

**TWIN CITY DIE CASTINGS CO.**

3351 TALMAGE AVENUE S. E. • MINNEAPOLIS 14, MINNESOTA

TELEPHONE MIDWAY 6-7528

RESEARCH PARTICIPANT

For more information, turn to Reader Service card, circle No. 489

## SUPPLIERS' LITERATURE

### Forms, Shapes and Composites

*cont'd from p 364*

producing custom-made parts, seals and components of natural, synthetic and silicone rubber compounds. **212**

**Perforated Metal Sheets.** Harrington & King Perforating Co., Inc., 6 pp, illus. Sizes, gages and materials of perforated metal sheets carried in stock. **214**

**Fabricated Silicone Rubber.** Haveg Industries, Taunton Div., 6 pp, illus. Information on silicone rubber seals for the aircraft, electronic and appliance industries; precision molded parts; extruded parts; and die cut parts. **215**

**Sponge Iron.** Hoeganaes Sponge Iron Corp., 20 pp, illus. Tells what sponge iron is, traces its origin, outlines its properties, characteristics, and use in quality steel. **216**

**Beryllium Copper Parts.** Instrument Specialties Co., Inc., 20 pp, illus., No. 10. Design information, properties and uses of beryllium copper springs and screw machine products. **217**

**Aluminum Extrusions.** Jarl Extrusions, Inc. Information on producing and anodizing alumi-extrusions. **218**

**Aluminum Hand Forgings.** Kaiser Aluminum & Chemical Sales, Inc., 20 pp, illus. Alloys and tempers, heat treatment, property guarantees, specifications and tolerances of aluminum hand forgings. **219**

**Custom Forgings.** Lenape Hydraulic Pressing and Forging Co., 108 pp, illus., general catalog. Information on services and facilities available for custom forging of pressure vessel connections and manways. Included is a price list. **220**

**Reinforced Plastics Moldings.** G. B. Lewis Co., 24 pp, illus. Information on properties, tests, design, tools and dies, molding methods, fabrication and assembly, finishing and painting, and other data on reinforced plastics molding. **221**


**Specially Shaped Wire.** Little Falls Alloys, Inc., 4 pp, illus. Properties, specifications and available alloys in which specially shaped round, flat, square and rectangular wire is available. **222**

**Meehanite Castings.** Meehanite Metal Corp., 4 pp, illus., No. 32. Physical, mechanical, and thermal properties of general and heat resisting Meehanite metal castings. **223**

**Porous Metal Components.** Mott Metallurgical Corp., 4 pp, illus. Information on controlled porosity stainless steel used for precision components. **225**

**Silicone Rubber.** Moxness Products, Inc., 4 pp, No. 310. Properties of low compression set, general purpose, high strength, fuel and oil resistant, high temperature and

*more literature on p 422*




Both of these connecting rods were designed for use in the same automotive air conditioning compressor.

# WHICH CONNECTING ROD COSTS LESS?

One glance tells you it's the aluminum connecting rod at the right. Two pieces are easier and less expensive to fabricate than five.

By designing this connecting rod as a Kaiser Aluminum forging, Lennox Tool & Machine Builders of Lima, Ohio, cut costs for their customer, Airtemp Division, Chrysler Corporation.

The steel connecting rod formerly used required five different pieces, including three bronze inserts for wrist pin and crankshaft bearings, plus two connecting rod bolts. Plenty of precision machining was also required.

The new aluminum connecting rod consists of only two pieces, plus the two connecting rod bolts. For this part, the forging itself was bored to provide a hard mirror-finish surface for wrist pin and crankshaft bearings, thus eliminating the three bronze inserts.

Strength? The aluminum forging meets every strength and dimensional stability requirement specified for the compressor application. In fact, the life expectancy of forged aluminum rods and steel rods with bronze insert is virtually the same!

This is another example of how strong, lightweight Kaiser Aluminum forgings can simplify design and cut material, machining and assembly costs. To find out how Kaiser Aluminum forgings can save you money, mail the coupon now!

KAISER ALUMINUM®

THE BRIGHT STAR OF METALS

®TRADEMARK KAISER ALUMINUM & CHEMICAL CORP.

Kaiser Aluminum & Chemical Sales, Inc.,
Dept. FO-124M, Kaiser Center
300 Lakeside Drive, Oakland 12, Calif.

Please send me the latest aluminum forgings design packet describing the many advantages of aluminum forgings for commercial use.


NAME_____

COMPANY_____

ADDRESS_____

CITY_____ ZONE____ STATE_____

For more information, turn to Reader Service card, circle No. 508




# ALUMINUM PERMANENT MOLD CASTINGS

evaluate today
progress tomorrow

The method of casting that assures density, homogeneous structure, with surfaces that take a high finish. Illustrated castings indicate how other metals are cast with aluminum to meet specific performances. For more ideas and recommended applications, write for new brochure. Our permanent mold engineers will be happy to work with you.

**Exalco** MANUFACTURING CO.

46 SHELDON ROAD • BEREA, OHIO • BEREA 4-2091

For more information, turn to Reader Service card, circle No. 412

**NEWS** FOR MATERIAL DESIGN ENGINEERS

*Here... from one source... are two new developments of signal importance to design engineers in all industries.*

## ALNICUS®

**a high energy permanent magnet material developed by the Magnetic Materials Division of U. S. Magnet & Alloy Corporation – now makes it possible to custom design magnetic devices in virtually any size and shape with the highest magnetic power ever achieved.**

ALNICUS 75®, with its nominal energy product of more than 7.5 million gauss-oersteds, broadens the scope of magnet applications. For example – with commercially produced ALNICUS 75® it is now possible to have **increased magnetic energy with no increase in unit size or weight... or, retain the same high magnetic energy with a lighter, smaller unit!** More important... **ALNICUS 75® can be cast into virtually any size or shape... because it maintains its high magnetic power in all configurations.**

## ZEMO®

**an entirely new and exclusive development for making precise high alloy castings in a way that provides for closer tolerances in high quality steel.**

Developed by USMAC... Steel Castings Division of U. S. Magnet & Alloy Corporation... ZEMO high integrity steel castings are actually lower in overall cost – yet, of the highest quality. Zemo castings, produced in USMAC's modern, high efficiency plant are delivered in a condition which precludes a number of expensive finishing operations. Thus, because there is considerably less finishing and machining required – **you save both time and money.**

If you are involved in material or product design you will be interested in the following brochures:

**ALNICUS®** Brochure #12 – address Magnetic Materials Division

**ZEMO®** Brochure #11 – address USMAC Steel Castings Division

**U. S. MAGNET & ALLOY CORP.**
**266 Glenwood Avenue**
**Bloomfield, New Jersey**

For more information, circle No. 530

# *From National-Standard . . .*

# SPECIALTY WIRE and Metal Products

Whatever your product, if it requires high-quality, specialty wire, wire cloth, flat spring steel or perforated metal, National-Standard Company's specialized manufacturing and engineering services are important to you.

**FOR OVER 50 YEARS** National-Standard has been a leader in the development of special wire and metal products for special applications, with emphasis on alloys, finishes, corrosion resistance, strength, elongation and adhesion properties. And today, National-Standard maintains leadership through the constant development of new materials, new techniques, new services, plus precise control and meticulous care in manufacturing to the most exacting specifications.


**EXPERIENCED ENGINEERING** help for jobs requiring specialty steel and wire to meet unique applications is available to you from National-Standard. Write for additional information to National-Standard Company, Niles, Michigan.



**SPECIALTY WIRE** is engineered for the most difficult applications by National-Standard. Just a few of the many specialties are: drawn wire in fine sizes of stainless and high carbon steel; electro-coated steel wire with nickel, copper, brass and other coatings; a wide variety of finishes such as bright, galvanized, liquor, tin, bronze, etc.; music spring wire; special-purpose wire strand and flat and tubular braid in steel and other metals; and high-temperature alloy wires such as Inconel-X, NS-25 (L605), NS-A286, René 41, NS-1000.




**HIGH-CARBON SPRING STEEL** from National-Standard's Athenia Steel Division is produced with a wide variety of tempers, finishes, colors, tolerances and forming characteristics to fit your special requirements. Athenia products include flat steels in widths up to 6½" tempered and 16" cold rolled or annealed with thicknesses from .001 to .060 depending on width.



**PERFORATED METAL** from the Cross Perforated Metals plant of National-Standard is a quality product of clean-walled, burr-free steel or aluminum. The complete line of Cross perforated metal designs fills the requirements of hundreds of products where beauty and style must be combined with rugged functional utility.

**INDUSTRIAL WIRE CLOTH** from the Reynolds Wire Division can be provided in standard or special weaves in a complete range of meshes, metals, alloys and coatings in all normally required widths. Reynolds Wire Cloth is woven in widths from 24 to 48 inches, but special widths under 24 or over 48 can be supplied on request.



NS NATIONAL STANDARD COMPANY

**NATIONAL-STANDARD COMPANY**

***Niles, Michigan***

For more information, turn to Reader Service card, circle No. 449




# HERE'S A HELPFUL AND CONVENIENT REFERENCE SOURCE

*for* ***COMPARATIVE SPECIFICATIONS***
***CHEMICAL ANALYSES***
***MINIMUM PHYSICAL PROPERTIES***

**...clearly charted in SHENANGO'S new Bulletin No. 157**

This invaluable chart of nonferrous alloys centrifugally cast by Shenango is readily available upon request. For your free copy, write to this publication or the Centrifugally Cast Products Division, The Shenango Furnace Company, Dover, Ohio.




SHENANGO CENTRIFUGAL CASTINGS

COPPER, TIN, LEAD, ZINC BRONZES · ALUMINUM AND MANGANESE BRONZES
MONEL METAL · NI-RESIST · MEEHANITE METAL · ALLOY IRONS · DUCTILE IRON

For more information, turn to Reader Service card, circle No. 466


## SUPPLIERS' LITERATURE

### Forms, Shapes and Composites

*cont'd from p 418*

low temperature silicone rubber compounds. **226**

**Impact Extrusions.** Mueller Brass Co. Mechanical properties and dimensional tolerances of round, rectangular and square impact extrusions. **227**

**Zirconium Metal Parts.** Zirconium Metals Corp. of America, Div. of National Lead Co., 5 pp. Composition, corrosion resistance, mechanical properties, machinability and uses of reactor and commercial grades of zirconium metal parts. **228**

**Superalloy Wire.** National-Standard Co., 6 pp. Series of charts give engineering data on ten superalloy wire materials. **229**

**Wire Cloth.** Newark Wire Cloth Co., 4 pp, illus. How to select, use and check various grades and types of wire cloth. **230**

**Metal Powder Part Design.** New Jersey Zinc Co., 24 pp, illus. General information on the powder metal process and its current uses. Covered are compositions and properties of nonferrous alloys, commercial tolerances, practical design suggestions and costs. **231**

**Perforated Rubber, Fabrics.** Perforating Industries, Inc., 16 pp, illus., No. 57. Information on perforating, slitting and blanking of various nonmetallic materials. **232**

**Plastics-Impregnated Wood.** Permali Inc., 6 pp, illus. Dimensional data, uses, and mechanical, physical and electrical properties of laminated thin wood veneers that are impregnated under vacuum with a special synthetic resin. **233**

**Aluminum Extrusions.** Precision Extrusions, Inc., 12 pp, illus., No. 5909. Mechanical properties, standard tolerances, pricing factors, and recommended uses of aluminum extruding alloys. **234**

**Molded Plastics.** Pyramid Products Inc., 4 pp, illus. Facilities available for custom injection molding. **235**

**Iron Powders.** Pyron Corp., 8 pp, illus. Chemical and physical properties, and composition of hydrogen-reduced iron powders. **236**

**Metal Stampings.** Reichert Float & Mfg. Co. Information on new processes and equipment used to form and deep draw intricate light and heavy metal stampings. **237**

**Forgings.** Rhode Island Tool Co., 26 pp, illus., No. 75. Dimensions, properties, prices and uses for drop and upset forgings, eye and special bolts, studs, cap screws, and nuts. **238**

**Metal Stampings.** Rockwell-Standard Corp., Stamping Div., 8 pp, illus. Describes facilities for producing stampings and assemblies in any metal or alloy. **239**

*more literature on p 428*

For more information, circle No. 380 ➤




d'ARAZIEN

# Alcoa puts the metal where you want it

More than a hundred tons of Douglas DC-8 kiss the runway on forged aluminum wheels like this one. Strength and lightness are obvious requirements. Even more essential is reliability through landing and after landing to guard the safety of passengers and crew.

Logically enough, rugged aluminum forgings were elected for the job. Then came many hours of Alcoa skill in die design, demonstrated in the remarkable zebra stripes visible in the cross section. They represent the aluminum grain flow* and illustrate how the tough aluminum grain is forged to withstand the shock loads of landing impact, plus the cyclic fatigue of rotation, all with a wide margin of safety.

Alcoa forges these wheels with a unique combination of blocker and finishing dies to put the metal exactly where it's needed. Alcoa Alloy 2014-T6 assures excellent machinability for the designer and producer, Bendix Products Division, Bendix Aviation Corporation. And Alcoa's forging plants, with hydraulic press capacities up to 50,000 tons, provide on-the-nose deliveries.

Think of Alcoa® Forgings when strength and lightness are rigid design requirements. Producing a complete line of forgings, Alcoa forges more large and complex shapes than any other supplier. Aluminum Company of America, 919 Alcoa Building, Pittsburgh 19, Pennsylvania.

**The patterns shown in the illustration were produced in Alcoa's Research Laboratories as part of a study of grain flow developed by the dies used to forge the DC-8 wheel.*

*Alcoa puts the metal where you want it—in castings, forgings, impacts, extrusions and screw machine parts.*

ALCOA ALUMINUM

ALUMINUM COMPANY OF AMERICA

For exciting drama watch "Alcoa Presents" every Tuesday, ABC-TV, and the Emmy Award winning "Alcoa Theatre" alternate Mondays, NBC-TV

Your Guide to the Best in Aluminum Value




# Alcoa puts the metal where you want it

How BIG an impact have you seen lately? Alcoa can now make them up to 12 in. in diameter and 60 in. long.

When Alcoa's new 2,500-ton press hits an aluminum alloy slug, a giant impact is formed with the combined strength of an extrusion and forging.

Like their small brothers, these big new impacts can save you money. They are produced in one fast operation. There's no parting line to be ground. No scale to be removed. No draft to be cut off. Impacts have forged bases and extruded sections. Multiple parts can often be combined into one integral impact eliminating welded or mechanical joints. Machining is reduced, and excessive material waste is eliminated.

You can get these big new Alcoa® Impacts in many alloys with tensile strengths up to 75,000 psi. Also made from aluminum powder metallurgy alloys which provide excellent properties at elevated temperatures.

Alcoa Impacts are unfailingly sound. They have smooth, corrosion-resistant surfaces. You can have them in plain or complex shapes with design features combining those of forgings and extrusions—flanges, steps, multiple walls, bosses, ribs.

In impacts, as well as forgings, castings, extrusions and screw machine parts . . . Alcoa puts the metal where you want it. A call to Alcoa can mean ingenious design solutions. Start now; write for *Metal in Motion*, Alcoa's new 34-page brochure on impacts. Aluminum Company of America, 909-L Alcoa Building, Pittsburgh 19, Pa.

**ALCOA ALUMINUM**

ALUMINUM COMPANY OF AMERICA

Alcoa puts the metal where you want it . . . in impacts, castings, forgings, extrusions and screw machine parts.

For more information, turn to Reader Service card, circle No. 380


# KEEP AHEAD WITH HAVEG
# PRECISION PLASTIC MOLDINGS

## BECAUSE...

Only Haveg offers such versatile and complete precision plastic molding facilities, technical "know how" and experience.

Haveg works with every known molding material to provide the most economical moldings. . . with properties necessary to meet the most rigid specifications.

Today Haveg is literally making design dreams come true . . . through its extensive research and development laboratory facilities as well as the best quality control laboratory within the industry.





***Shown in photo are:***

**(a) A series of crab locks molded from nylon.**

**(b) Electrical connectors for making and breaking as many as 41 electrical circuits at one time are used in missile tracking equipment.**

**(c) Comparator chart in background enlarges connectors 10 times and checks the accuracy of all holes and inserts.**

**(d) Pick-up head for stereophonic record player. This is a complicated but very small part in which three inserts are molded into the head.**



*Keep Ahead* with **HAVEG®**

FIRST IN *Engineered* PLASTICS

## CUSTOM ENGINEERED FABRICATED SILICONE RUBBER

Many highly specialized procedures are essential to produce the superior quality so closely identified with Haveg. Expert tool design and construction, rigid process control and complete testing facilities are but a few of the vital operations in Haveg's quality assurance program. The Haveg engineered parts shown here are being used with great success in aircraft, missile, electronic, appliance and other applications because of these important features.



1. **High Temperatures—up to +600°F.**
2. **Low Temperatures—down to −150°F.**
3. **Excellent Electrical Properties at High Temperatures.**
4. **Low Compression Set Characteristics.**
5. **Long Life—unaffected by weather and ozone.**
6. **Wide Choice of Colors.**

Haveg formulations maintain their physical and chemical characteristics under the most adverse conditions. By combining with use-proven reinforcing agents—Dacron*, Teflon* and Fiber Glass, Haveg can develop for the user a particular property, or a multiplicity of properties, such as strength, low coefficient of friction, maximum resistance to fuel, oil, chemicals and heat.

Strict adherence to the highest of standards of quality control permits Haveg to guarantee the quality of every shipment of Fabricated Silicone Rubber.

For further information, or any of Haveg's products and facilities, write, wire or phone—our engineers will be glad to work closely with you. All transactions will of course be confidential.

*Registered trade-mark of E. I. duPont deNemours & Co., (Inc.)

# KEEP AHEAD WITH HAVEG


# HAVELEX®

(formerly G. E. Mycalex)

Haveg's Precision Molded Rigid Inorganic Insulation Material offers all these unique advantages

- **Dimensional Stability**
- **1000°F Continuous Temperature Resistance**
- **Dielectric Strength**
- **Mechanical Strength**
- **Low Loss Factor**
- **Low Power Factor**
- **Arc Resistance**
- **No Moisture Absorption**

Havelex is composed of special glass reinforced with mica. Grey to white in color, this dense stone-like material provides an ideal insulator for wide ranges of ambient operating conditions and electrical stresses. The unusual combination of properties in Havelex plus Haveg's ability to provide precision molded tolerances and intricate shapes permit unlimited design possibilities. Complex metal inserts can be permanently molded in position, facilitating component assembly and assuring end product reliability.




***Recent noteworthy applications of Havelex pictured here are:***

**(A) Disconnect Assembly nearly 5 inches in diameter with massive inserts—Havelex provides the electrical insulating "heart" of this disconnect device used in "on the ground" service to military jet aircraft. If for any reason the power disconnection is made while the aircraft is drawing its electrical power from the airport installation, an instantaneous disconnection is insured by this device; hence, protection against personal injury or equipment damage.**

**(B) Transistor Test Socket—three stainless Steel tubes (.010" wall) integrally molded into Havelex body. A key component in reliability testing of transistors in high ambient temperatures.**

**(C) Ionizer Component—air filter unit for home heating system.**

***Haveg's Taunton Division offers you a complete plastics molding service, including:***

**Custom Compression and Transfer Molding**
**Custom Automatic Molding**
**Custom Injection Molding**
**Custom Specialty Molding (Polyesters and Diallyl Phthalates)**
**Sealing Caps and Tubes**
**Custom Fabricated Silicone Rubber**
**Custom Havelex Molding (formerly G. E. Mycalex)**
**Complete Mold Making Facilities**

*Keep Ahead with* HAVEG®

FIRST IN *Engineered* PLASTICS

**TAUNTON DIVISION**

**HAVEG INDUSTRIES, INC.**

336 Weir Street • Taunton, Massachusetts

*Other Operating Divisions:* **American Super-Temperature Wires, Inc.** – Burlington, Vermont • **Blow Molding Division** – Bridgeport, Connecticut • **Chemical Materials Division** – Wilmington, Delaware **Haveg Corporation** – Wilmington, Delaware • **Hemisphere Products Corporation** – Rio Piedras, Puerto Rico • **Reinhold Engineering & Plastics Co., Inc.** – Norfolk, California

# Sandusky Centrifugal Castings
## for unlimited cylindrical applications

Do the products pictured here spur your imagination? These are typical of the cylindrical products we are casting centrifugally and machining to precise requirements for many prominent manufacturers and military branches. Write for: Sandusky Centrifugal Castings Bulletin #200. Contains application data and specifications on more than 70 ferrous and non-ferrous alloys in a range of properties that is a designer's dream.

**SANDUSKY** CENTRIFUGAL CASTINGS
**FOUNDRY & MACHINE CO.**
SANDUSKY, OHIO



SANDUSKY QUALITY
CENTRIFUGAL CASTINGS

*TYPES:* Rolls, Sleeves, Rings, Bearings, Bushings, Liners, Bands, Drums, Cylinders, Tubes, Shells, Retorts, Pressure Vessels, Pressure Piping.

*SIZES:* From 7" to 54" O.D. —lengths up to 33 feet.

*MATERIALS:* Stainless, Carbon and Low Alloy Steels; full range of Copper-Base and Nickel-Base Alloys.

◀ For more information, circle No. 428

▲ For more information, turn to Reader Service card, circle No. 463


# Heat Problem?

## DUMONT CAN HELP

**High-temperature insulation for missile components is a major space-age problem... and a Dumont specialty. Polaris and Minuteman already testify to the experienced skills of Dumont in high-pressure molding of reinforced plastics. Characteristic of Dumont's ability to meet new challenges with new solutions is the development of the first tactical lightweight plastic exhaust nozzle to combine structural and insulating components into a single assembly. The future of missile flight is dependent upon thermal insulating requirements of rocket motors, nose cones, re-entry vehicles. Dumont's advanced techniques of high-pressure compression and autoclave molding, supported by process and materials development, are already prepared to meet those requirements.**

**Dumont's experience and technology in the field of high-temperature insulation and sandwich structures are available through its technical service staff. Learn how Dumont's facilities and abilities can help you find insulation answers. Write today for Brochure D.**

*DUMONT MANUFACTURING CORPORATION*
*Subsidiary of DUTRON Corporation*
*607 Irwin Street, San Rafael, California*




## SUPPLIERS' LITERATURE

### Forms, Shapes and Composites

*cont'd from p 422*

**Centrifugal Castings.** Sandusky Foundry & Machine Co., 16 pp, illus. Tells how centrifugal castings are made, and shows the use of these castings in unfired pressure vessels and nuclear equipment. **240**

**Nonferrous Centrifugal Castings.** Centrifugally Cast Products Div., Shenango Furnace Co., 8 pp, illus., No. 157. Specifications, chemical composition and physical properties of nonferrous alloys used in centrifugal castings. Shows parts and assemblies produced by the centrifugal method. **241**

**Vinyl-Metal Laminates.** Clad Rex Div., Simoniz Co., 8 pp, illus. Gives physical, chemical and thermal properties, and abrasion resistance of vinyl-metal laminates. **242**

**Small Tubing.** Superior Tube Co., 12 pp, No. 42. Series of charts give information on how to select tubing for a specific application. Covered are 84 grades of carbon, stainless, and alloy steels; nickel and nickel alloys; copper-base alloys; glass sealing alloys; and reactive metals. **243**

**Clad Metals.** Texas Instruments, Inc., Metals & Controls Div., 10 pp, illus., No. GP-1A. Characteristics, types, and uses of clad metal thermostats and electrical contacts. **244**

**Precision Die Castings.** Twin City Die Castings Co., 14 pp, illus. Facilities for making precision die castings from zinc, aluminum and lead-base alloys. **245**

**Steel Castings.** Unitcast Corp., illus., No. 649A. Testing facilities for insuring high quality production of steel castings. **246**

**Precision Steel Castings.** USMAC Steel Castings Div., U. S. Magnet & Alloy Corp., 4 pp, illus. Information on a process for manufacturing high integrity, close tolerance steel castings. The process replaces some sand casting methods and is said to eliminate many expensive and time consuming finishing operations. **247**


**Stainless Steel Castings.** Waukesha Foundry Co., Castings Div., 8 pp, illus., No. SS. Physical properties and uses of martensitic, ferritic and austenitic stainless steel castings. **248**

**Aluminum Extrusions.** R. D. Werner Co., Inc., 4 pp, illus. Sizes and uses of aluminum extruded and roll formed shapes. **249**

**Synthetic Rubber Products.** Western Felt Works, Acadia Div., 6 pp, illus. Shows various types of molded, extruded, die cut and lathe cut synthetic rubber parts. **250**

**Plastics Extrusions.** Yardley Plastics Co., 4 pp, illus. Facilities for producing extruded plastics parts including profile extrusions, gaskets and tubing. **251**

◀ For more information, circle No. 553




# Powder metallurgy cuts parts costs up to 75% for manufacturers of products like these

Why not find out now if powder metallurgy holds the answer to your high parts costs?

Send Glidden a sketch of any part, plus the quantity desired. Glidden, with the help of qualified parts fabricators in your area, will determine, first, whether the part can be made with metal powder. If it can, you will receive cost quotations that may show really worthwhile savings—similar to savings realized by an increasing number of manufacturers who have found that metal powder parts can be mass-produced faster, better, more economically.

As a leading supplier of metal powders, Glidden works closely with parts producers. In this way, several staffs of experienced technicians may be at your disposal—to provide complete technical service and suggest possible design changes that may bring even lower parts costs.




QUALITY Glidden PRODUCTS


**RESISTOX METAL POWDERS**

The Glidden Company
Chemicals Division • Metals Department
Hammond, Indiana

COPPER POWDER • LEAD POWDER • TIN POWDER • BRASS POWDER • ALLOY POWDER • FILTER POWDER
CUPRIC OXIDE • CUPROUS OXIDE • CUPROUS SULFIDE • CUBOND COPPER BRAZING PASTE • COPPER PIGMENT

For more information, turn to Reader Service card, circle No. 550

# CATCHES MOLTEN URANIUM




Zirconium Liner fabricated for lower reactor vessel inlet plenum in a commercial power installation. 8' diameter in 12 sections.

# Zr
## ASSEMBLIES
## MADE TO ORDER

...MACHINED
...WELDED
...FINISHED

Facilities are now available for fabricating Zirconium metal assemblies to your specifications. Quotations on making finished items involving machining, welding or finishing will be supplied upon request. Equipment is also available for producing simple or complex shapes of Hydrided Zirconium. Finished shapes or conventional mill items are supplied in commercial, reactor grade or Zircaloy compounds. Technical information or counsel will be furnished upon request.

**ZIRCONIUM METALS CORP. OF AMERICA**
*Division of National Lead Company*
111 BROADWAY, NEW YORK CITY



Scatter Rings Used in Radiation Research | Zirconium Metal Cathode | Valve Resists Severe Corrosion | Crucibles Cast Less To Use

For more information, turn to Reader Service card, circle No. 487

New edition just published!
**The official handbook of the industry's own society...**

# PLASTICS ENGINEERING HANDBOOK
## 3rd EDITION
**of the Society of the Plastics Industry, Inc.**



**1960**
**Over 600 Double-Column Pages**
**Larger 7" x 10" Format**
**Over 500 Illustrations, Tables and Charts**
**2 Special Fold-out Inserts**
**$15.00—No Increase in Price Over Previous Edition**

The best arranged, most clearly written reference on plastics materials, methods and fabrication is now revised, expanded and completely up-to-date. Reviewers throughout the world have hailed previous editions as the most useful source of information ever made available to one industry. This new edition adds the advances made since 1954, advances so numerous that the handbook now appears in a larger, double-column format. Entirely new material is that on nomenclature, cellular plastics, decorating, welding, and plastics as adhesives. The book describes every step in the manufacturing operation, and includes the experience and know-how of over 200 technicians and authorities. The text is fully illustrated with hundreds of photographs, tables and charts. Some of the charts alone provide data of inestimable value to the plastics plant. Here is an immense amount of current information in the revision of a book with a giant reputation for accuracy, thoroughness and dependability. It is truly the definitive guide to the plastics industry.

Subjects New to the 3rd Edition:
**NOMENCLATURE**
**CELLULAR PLASTICS**
**DECORATING**
**WELDING**
**PLASTICS AS ADHESIVES**

*Examine It Free for 10 Days*
**MAIL THIS COUPON NOW**

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-709, 430 Park Avenue**
**New York 22, N. Y.**

Send me a copy of PLASTICS ENGINEERING HANDBOOK, 3RD EDITION for 10 days' Free Examination.

☐ Total purchase price enclosed.
☐ Bill me. ☐ Bill company.

NAME.....

ADDRESS.....

CITY & ZONE..... STATE.....

**SAVE MONEY!** Enclose $15.00 with order and Reinhold pays all shipping costs. Same return privilege. Please add 3% sales tax on N.Y.C. orders. DO NOT ENCLOSE CASH!




# PERMALI
## *the laminate of many uses!*

**...as a non-metallic structural material**—tensile strengths to 30,000 p.s.i.—parts to 13 feet long and 5 inches thick—tailored mechanical properties to fit your needs—machines easily to engineering tolerances.

**...as a dielectric**—high dielectric strength—low power factor—used by every major heavy electrical equipment manufacturer.

**...as a non-metallic fastener**—available off the shelf as studs, continuously threaded rods or bolts with matching square or hexagon nuts.

**...as a silent gear**—special grade gives uniform tooth strength. Diameters to 48", face widths to 4".

**...as thermal insulation at very low temperatures**—Permali retains most of its mechanical strength at the temperature of liquid gases.

**...as a neutron shield**—a special grade provides structural strength while shielding against fast neutrons.

**And** Permali, Inc. can design, machine or build your parts or structures regardless of size.

*Technical literature on any or all the above applications available on request to*

**PERMALI, Inc.**
P. O. Box 718
Mt. Pleasant, Pa.
Telephone: Kimball 7-2353
TWX: MT PL PA 161

For more information, turn to Reader Service card, circle No. 529

# NIAGARA 100 MESH
## HYDROGEN REDUCED IRON POWDER
**Is The Answer To Your Dimensional Growth Problems**

**This table shows the high tensile strength obtainable for iron-copper-structural parts:**

| Sintering Conditions | Copper Content % | Sintered Density GRM/cc | Dimensional Change From Tool Size %/inch | Tensile Strength p.s.i. |
|---|---|---|---|---|
| TEMP: 2050°F TIME: 45 Mins. ATMOS: Hydrogen | 0 | 5.8 | —0.25 | 18000 |
| | 3 | 5.8 | —0.10 | 27000 |
| | 5 | 5.8 | +0.20 | 36000 |
| | 7 | 5.8 | +0.30 | 40000 |
| | 10 | 5.8 | —0.01 | 42000 |

**In addition to these properties NIAGARA IRON offers you:**
GOOD MOLDING CHARACTERISTICS • HIGH PHYSICAL PROPERTIES
DEPENDABLE UNIFORMITY OF SHIPMENTS

**For information & technical data write:**

**PYRON COMPANY—AMCO DIVISION**
**AMERICAN METAL CLIMAX, INC.**
**Box E, LaSalle Sta., Niagara Falls, N.Y.**

**For more information, turn to Reader Service card, circle No. 526**

---

# custom molders of FIBERGLASS reinforced polyester




**Your product, in whole or in part, may be ideally suited for adaption to an incredibly strong, amazingly lightweight, beautifully textured Lewis one piece molding.**

**Let our experienced plastic engineering staff study your product, whether it be in existence, or still in blueprint form.**

**√ MOLDED-IN COLORS** **√ WON'T ROT OR RUST** **√ LIGHTER THAN ALUMINUM**
**√ STRENGTH LIKE STEEL** **√ CHEMICAL RESISTANT** **√ SOUND DEADENING**



Fiberglass reinforced plastics stimulate fresh, modern style appeal... and are exciting new sales potentials to a wide variety of consumer and industrial products. And no wonder, for the outstanding physical characteristics of this basic new material, plus its many profitable production advantages, create great interest and impact everywhere. Dimensional stability... chemical resistance... tolerance to temperature extremes... rust-proof, rot-proof, corrosion-proof... and a limitless variety of lasting colors molded-in for life... all these benefits, and many more, are to be found with Lewis reinforced polyester moldings.

More and more leading manufacturers are depending on Lewis for quality reinforced plastic moldings. Our trained engineers are ready to assist you in converting your product to this new material.


## G. B. LEWIS COMPANY
**Department MS** • **WATERTOWN, WISCONSIN**

**For more information, turn to Reader Service card, circle No. 438**

---

# ASARCO
## DISTRIBUTORS for ASARCON CONTINUOUS-CAST BRONZE

**ALABAMA**
**Birmingham**
Dixie Bronze Co., Inc.
FA 4-4588
J. M. Tull Metal & Supply Co., Inc.
FAIRFAX 3-1612
**ARKANSAS**
**Little Rock**
Arkansas Foundry Company
FRANKLIN 2-6261
**CALIFORNIA**
**Los Angeles**
Kingwell Bros., Ltd.
LUDLOW 2-7427
**San Francisco**
SUTTER 1-0514
**CONNECTICUT**
**Guilford**
Knapp Foundry Co., Inc.
GLENDALE 3-2744
**Seymour**
The Derby Castings Co.
TUXEDO 8-2581
**Stratford**
The Ellsworth Steel & Supply Co.
EDISON 7-3317
**FLORIDA**
**Jacksonville**
J. M. Tull Metal & Supply Co., Inc.
EVERGREEN 7-5561
**Miami**
J. M. Tull Metal & Supply Co., Inc.
NEWTON 5-0365
**Tampa**
J. M. Tull Metal & Supply Co., Inc.
TAMPA 3-6741
**GEORGIA**
**Atlanta**
J. M. Tull Metal & Supply Co., Inc.
JACKSON 5-3871
**ILLINOIS**
**Chicago**
Bronze Bearings, Inc.
AVENUE 2-2337
Ray M. Ring Co., Inc.
ESTERBROOK 9-0300
**Peoria**
Ray M. Ring Bearing Co.
PEORIA 3-8171
**Rockford**
Rockford Tool & Transmission Co.
ROCKFORD 2-7711
**INDIANA**
**East Chicago**
Ray M. Ring Co., Inc.
E. CHICAGO 8020
SAGINAW 3-8560
**Indianapolis**
W. J. Holliday & Co., Div. of Jones & Laughlin Steel Corp.
MELROSE 3-3311
**South Bend**
Powell Tool Supply, Inc.
ATLANTIC 9-5578
**KENTUCKY**
**Louisville**
Williams & Co., Inc.
JUNIPER 3-7781
**LOUISIANA**
**New Orleans**
Standard Brass & Mfg. Co.
AUDUBON 1381
**Shreveport**
Standard Brass & Mfg. Co.
SHREVEPORT 29483
**MARYLAND**
**Baltimore**
Bronze Specialities, Inc.
LEXINGTON 9-1906
**MASSACHUSETTS**
**Boston**
Kelco Metal Products Co.
HUBBARD 2-1737
**MICHIGAN**
**Detroit**
Copper & Brass Sales, Inc.
FOREST 6-6200
Meier Brass & Aluminum Co.
JORDAN 6-3902
**Grand Rapids**
Copper & Brass Sales, Inc.
EMPIRE 1-6681
**Kalamazoo**
Bard Tool and Equipment Co.
FIRESIDE 3-2691
**Lansing**
Superior Brass & Aluminum Co.
IV 2-2754
**Muskegon**
Towne Hardware & Supply Co.
7-2651
**MINNESOTA**
**Minneapolis**
R. G. Eide, Inc.
FE 8-4846
**MISSOURI**
**Kansas City**
Associated Bearings Co.
VALENTINE 1-5393
Hubbell Metals, Inc.
BALTIMORE 1-7760
**St. Louis**
Hubbell Metals, Inc.
FRANKLIN 1-0212
**NEBRASKA**
**Grand Island**
The Island Supply Co.
DUPONT 2-8567
**Omaha**
T. S. McShane Co., Inc.
JACKSON 1273
**NEW JERSEY**
**Carlstadt**
E. A. Williams & Son
GENEVA 8-0800
MARKET 31979
(New York LA 4-9545)
**Newark**
Federal Foundry Sales, Inc.
MARKET 2-6330
**Perth Amboy**
Gregg's Brass Foundry
HILLCREST 2-2086
**NEW YORK**
**Brooklyn**
Ramsay, Inc.
STERLING 8-1144
**Buffalo**
Kencroft Associates, Inc.
RIVERSIDE 1520
RIVERSIDE 2020
**Rochester**
Ontario Metal Supply, Inc.
HAMILTON 6-1630
**Syracuse**
Wellsville Bronze Foundry, Inc.
GLENVIEW 4-3231
**Troy**
The Troy Belting & Supply Co., Inc.
AS 2-4920 (in Albany 3-6121)
**OHIO**
**Akron**
Akron Welding and Spring Co.
JEFFERSON 5-2187
**Cleveland**
Copper & Brass Sales, Inc.
ENGICOTT 1-6757
The Bearing Bronze Casting Co.
MICHIGAN 1-6520
**Cincinnati**
Reliable Castings Corp.
KIRBY 1-2627
**Columbus**
Williams & Co., Inc.
AXMINISTER 4-1623
**Dayton**
The Bristol Brass Corp. of Ohio
FULTON 8185
**Toledo**
The Seeger Brass Company
CHERRY 8-5321
Williams & Co., Inc.
GREENWOOD 5-8661
**PENNSYLVANIA**
**Easton**
R. T. Schaller Co.
EASTON 2-2435
**Latrobe**
Latrobe Foundry Machine & Supply Co.
KEYSTONE 7-3341
**Philadelphia**
Brass & Copper Sales, Inc.
GLADSTONE 7-2500
Renewal Service, Inc.
BALDWIN 9-6330
**Pittsburgh**
Pennsylvania Industrial Supplies Co., Inc.
ALLEGHENY 1-5010
Pittsburgh Brass Mfg. Co.
ATLANTIC 1-8761
**RHODE ISLAND**
**Providence**
Clifford Metal Sales Co., Inc.
UNION 1-4100
**SOUTH CAROLINA**
**Greenville**
J. M. Tull Metal & Supply Co., Inc.
CEDAR 3-8366
**TENNESSEE**
**Memphis**
Memphis Bearing & Supply Co.
JACKSON 6-7543
**Nashville**
Dixie Bearings, Inc.
CHAPEL 2-7351
**TEXAS**
**Beaumont**
Standard Brass & Mfg. Co.
TERMINAL 3-2641
**Houston**
Standard Brass & Mfg. Co.
CAPITOL 56531
**Port Arthur**
Standard Brass & Mfg. Co.
YUKON 5-9377
**WISCONSIN**
**Milwaukee**
Badger Bearing Co.
BROADWAY 2-0231
**CANADA**
**Lachine, Quebec**
Federated Metals Canada, Ltd.
MELROSE 7-3591
**Scarborough, Ontario**
Federated Metals Canada, Ltd.
PLYMOUTH 7-3246



Note minimum clean-up necessary between casting of this 6-tooth pump impeller and finished part. (Illustrated parts are 4" in diameter.)

*Custom shapes in continuous lengths:*

## ASARCON®

### CONTINUOUS-CAST BRONZE CASTINGS

Before you design or produce a copper base alloy part, investigate the economy and efficiency of Asarco continuous casting. You can order the alloy and shape you need, in the exact lengths you need. Continuous Cast Asarcon Bronze alloys meet SAE, ASTM, and government specifications—but they are superior to the same alloys cast other ways, in hardness, yield, tensile and impact strength. In fact, you may be able to substitute an Asarcon Bronze for an aluminum or manganese bronze. Write for complete data to Continuous-Cast Department, American Smelting and Refining Company, Barber, N. J. or Whiting, Indiana.

Immediately available from stock: **ASARCON 773 BEARING BRONZE** (SAE 660)—260 sizes of rods and tubes. Complete range of sizes from ½" to 9" diameters. Immediately available from stock in 105" lengths. Special shapes produced to order.


ASARCO

AMERICAN SMELTING AND REFINING COMPANY

**CONTINUOUS CAST DEPARTMENT**


West Coast Distributor: Kingwell Bros., Ltd., 457 Minna Street, San Francisco, Calif. In Canada. Federated Metals Canada, Ltd., Toronto and Montréal. Distributors in many principal cities.

For more information, turn to Reader Service card, circle No. 384



ROD AND TUBING


TORQUE CONTROL BUSHINGS



O-RINGS


SHAFT SEALS


BUSHINGS


BEARING SURFACES


VALVE SEALS


CUP PACKINGS


THRUST WASHERS

BASIC SHAPES AND FABRICATED PARTS IN


RULON®

REINFORCED TFE RESIN*

*Dupont Teflon



SHEETS


CUSTOM EXTRUSIONS


GASKETS


TAPE


BEARING RETAINERS


PISTON RINGS

Design engineers note! RULON adds extra values to your products . . . low friction performance even without lubrication . . . wide temperature adaptability (−350° to +500° F) . . . high resistance to wear and deformation . . . and practically universal chemical inertness. Unlike nylon and many other materials, RULON won't swell in presence of moisture.

*RULON is the sure relief to many a design headache. For RULON engineering Brochure #9572, write*

**DIXON CORPORATION**
**BRISTOL, RHODE ISLAND**

See our Catalog in Sweet's Product Design File



Dixon

Suppliers of basic shapes and fabricated parts in Rulon and Teflon

For more information, turn to Reader Service card, circle No. 493

*Just Published*

# AUTOMATING THE MANUFACTURING PROCESS

**by GEORGE F. HAWLEY**

*Director of Development & Engineering*
*Automation Engineering Laboratory, Inc.*
*Stamford, Conn.*

**1959**
**176 pages**
**$4.95**




"The author's somewhat unconventional literary style together with his generous use of practical illustrative examples makes for a book which is both easily read and pleasant reading. The ideas which he has presented are, in my opinion, eminently sound and merit the attention of all people concerned with the use and development of special automatic machinery."

—RICHARD S. SPENCE
*Associate Professor*
*Department of Mechanical Engineering*
*Rensselaer Polytechnic Institute*

This book helps management and production personnel gain a greater appreciation of the risks encountered in successful automation, while designers and development engineers will find ideas which should minimize their failures. The author presents problems involved in inventing and designing machinery for specific operations, such as assembly of components, packaging of individual products, bottle capping, feeding, etc. He also spells out some of the pitfalls involved in automation and discusses in detail the roles of the inventor, design engineer and production planner. The book's intensely practical approach to complex mechanical problems will appeal to all who are confronted with unnecessarily costly operations.

*Examine It Free for 10 Days*
**MAIL THIS COUPON NOW**

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-716, 430 Park Avenue**
**New York 22, N. Y.**

Send me a copy of AUTOMATING THE MANUFACTURING PROCESS for 10 days' Free Examination.

☐ Total purchase price enclosed.
☐ Bill me. ☐ Bill company.

NAME_____

ADDRESS_____

CITY & ZONE_____ STATE_____

**SAVE MONEY!** Enclose $4.95 with order and Reinhold pays all shipping costs. Same return privilege. Please add 3% sales tax on N.Y.C. orders. DO NOT ENCLOSE CASH!



# WE PROVIDE A HAPPY ENDING TO YOUR TUBING PROBLEMS

*Top design people depend on top tubing people!*

Comprehensive GM Steel Tubing facilities quickly deliver your tubing processed to slip into your production line like an eel through oil. Typical are facilities for end-processing tubing to your requirements. We can hold O.D. or I.D. tolerances to a plus or minus .0015″ by end sizing. And by swaging, your O.D. tolerances can be held as close as plus or minus .002″. You can have external beading or recessing and we can rod draw to exceptionally close tolerances. Shearing, upsetting, flattening, piercing—we do all of them expertly. Just ask a GM Steel Tubing Sales Engineer. We're at your service.

GM STEEL TUBING
BY ROCHESTER PRODUCTS

**ROCHESTER PRODUCTS DIVISION OF GENERAL MOTORS, ROCHESTER, NEW YORK**

For more information, turn to Reader Service card, circle No. 462

# "Who's best at meeting SPECS for short run stampings?"



# FEDERAL

**SHORT RUN STAMPINGS**






*Freddy Federal says:* "Every stamping job you give us, big or small, tough or easy, gets Federal's continuous step-by-step inspection. Highly skilled tool makers use exclusive Federal techniques to make dies for your stampings, with an accuracy equal or superior to ordinary methods, at cost savings up to 80%. Federal has the special equipment and experience needed to meet your particular stamping tolerance and design requirements. Added to this is the personal interest of Federal craftsmen who take great pride in having their work please you. Try us today by sending your part or print for a prompt air-mail quotation. If time is short, just ask for a reply by phone or wire. Let Federal stampings meet your specs!"

*Write for illustrated Catalog No. 301 with money-saving stamping design tips.*

**FEDERAL TOOL & MFG. CO.**
3652 Alabama Avenue
Minneapolis 16, Minnesota

**FEDERAL SHORT RUN STAMPING, INC.**
952 Lyell Avenue
Rochester 6, New York

**FEDERAL STAMPING COMPANY**
7352 Atoll Avenue
No. Hollywood, California

For more information, turn to Reader Service card, circle No. 418



*Presenting the first book in the new*
REINHOLD SPACE TECHNOLOGY SERIES



## Fundamentals of ROCKET PROPULSION

**by RAYMOND E. WIECH, JR. and ROBERT F. STRAUSS,**
*Supervisors, Research Group*
*Thiokol Chemical Corporation*
*Reaction Motors Division*

**1960, illustrated, 145 pages, $5.50**

HERE IS an all-inclusive review of the rocket engine—its history, fundamentals of operation, design of components and methods of application. The book's level is one that bridges the gap between the popular and the highly technical. Chapters advance one step at a time through the basic laws governing rocket engine design; the design and operation of current engines; the need for and probable design of future engines; and the rocket engine's job in space flight and satellite missions. The book fully describes all rocket engine types so that the function and operation of each is clearly understood. All basic rocket formulas derive from algebra, rather than the more difficult calculus. Explanations of new terms and illustrations of uncommon devices abound to further the reader's grasp of the subject. Extensive bibliographies following each chapter lead to additional or more advanced information. The authors use a thorough, easily followed approach throughout. As a result, here is an ideal reference for propellant chemists, chemical and mechanical engineers, metallurgists, guidance and electronics engineers, students, or anyone remotely connected with or interested in rocket propulsion and its future.

*Examine It Free For 10 Days*
**MAIL THIS COUPON NOW**

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-717, 430 Park Avenue**
**New York 22, N. Y.**

Send me a copy of FUNDAMENTALS OF ROCKET PROPULSION for 10 days' Free Examination.
☐ Total purchase price enclosed
☐ Bill me ☐ Bill company

Name_____
Address_____
City & Zone_____ State_____

SAVE MONEY! Enclose $5.50 with order and Reinhold pays all shipping costs. Same return privilege. Please add 3% sales tax on N.Y.C. orders. *DO NOT ENCLOSE CASH!*




# PRECISION WIRE FORMS



**Send a sample or blue print for estimates.**

Art Wire specializes in wire forms designed for today's automatic production lines . . . manufactured with the precision and uniformity that assure the economy of an uninterrupted work flow. Reduced down-time, and the lower costs made possible by Art Wire's modern production methods mean greater savings to you, and greater profit in your operations.

**ART WIRE AND STAMPING CO.**
13A Boyden Place, Newark 2, N. J.

For more information, circle No. 387

# WERNER



## NEW EXTRUSION SPEEDS PRODUCTION OF WESTINGHOUSE FLUORESCENT FIXTURE

Werner's ability to produce a complex aluminum fixture to precise tolerances eliminated an assembly line bottleneck ...and simplified production of this new Westinghouse fluorescent fixture.

Lighter than the extrusion previously used, the new 73-inch aluminum housing is supplied cut to length, with end caps welded in place. Channels in the extrusion replace mounting holes and make the unit completely waterproof. Drilling, tapping and weatherproofing operations previously required to hold the reflector in place have been eliminated.

Werner aluminum extrusions may help you cut assembly costs and smooth out your production problems. Send us prints and specifications today. Werner engineers will be glad to work with you.

**WERNER ALUMINUM**


☐ Please send me new handbook of WERNER ALUMINUM EXTRUSIONS
☐ Have salesman call

Name _____

Company _____

Address _____

City _____ State _____




**R. D. WERNER CO., INC. • 1616 OSGOOD ROAD • GREENVILLE, PA.**

For more information, turn to Reader Service card, circle No. 532

QUALITY ENGINEERED
FUNCTIONAL
RUBBER PARTS

TETRASEALS

O-RINGS

CUSTOM
MADE
PARTS

FOR
CUSTOM
COMPOUNDED
PRECISION
FABRICATED

Go Goshen RUBBER
PARTS
SEALS
PRODUCTS

If your problem involves high or low temperatures, extra-close tolerances or other advanced requirements, "Go Goshen" for the know-how and the techniques to help you.

Goshen Rubber Co., INC.

3111-O S. TENTH ST. • GOSHEN, INDIANA

For more information, turn to Reader Service card, circle No. 424

share a mold—
divide the cost
AT ATLANTIC CASTING



*Typical Atlantic Production Mold-Half (18" x 12")*

**PRODUCTION COSTS FOR PRECISION CASTINGS SHOWN ABOVE WERE SHARED BY THE FOLLOWING COMPANIES:**

*General Electric Company; Intertype Corporation; Westinghouse Electric Corporation; Air Reduction Corporation; United Shoe Machinery Corporation; I.T.E. Circuit Breaker Company; Ordnance Corps. Dept. of Army; Vonnegut Hardware Company.*

**PRECISION CASTINGS COST LESS AT ATLANTIC** because production molds are shared by up to fifteen different customers and fifty castings. Standard production molds are produced and poured on a continuous basis and when an order for a casting is completed, the portion of the mold vacated is immediately utilized for another casting, while production proceeds without interruption.

**TOOLING COSTS CUT!**

Atlantic mold-sharing requires only one inexpensive, brass pattern, quickly produced and easily altered.

**LABOR COSTS CUT!**

Pouring as many as fifty castings in a single mold allows substantial reduction in labor costs per casting. This saving is passed on to you.

**LEAD TIME CUT!**

Continuous mold production with Atlantic's standardized interchangeable tooling allows immediate adjustments in scheduling to conform to your delivery requirements. Deliveries start in as little as two weeks on new orders—one week on reorders.

**SEND OR CALL TODAY FOR ATLANTIC'S NEW CASTING CATALOG.**

ATLANTIC
CASTING and ENGINEERING CORP.
810 Bloomfield Avenue • Clifton, N. J.
PRescott 9-2450

For more information, turn to Reader Service card, circle No. 391


# A NEW HIGH

## IN METALLURGICAL PROPERTIES FROM EXOTIC METALS

Jet engine components made from Cameron forgings have hit a new high in forming and in metallurgical refinements, developing not only room temperature properties 20% over specifications but, more importantly, producing these same over-specification values at elevated temperatures.


With our special forging techniques, one heat and one push produce uniform properties from surface to center, and from hub end to flange end. Even in high density alloys, interesting economy is effected. Favorable billet to finished forging weight ratio means less of the expensive material is used in each operation. Because of improved grain structure and close controls throughout the entire process, machining qualities are excellent.

All this, of course, gives our customers a better component functionally and economically. Check the accompanying comparison of the specification values and obtained values on the two jet turbine rotating components shown—let us show you what we can do with your problem forgings—just CALL, WRITE, or COME BY




**JET ENGINE TURBINE DISC — MATERIAL: INCO 901**

| | T.S. | Y.S. .2% | E.L. | R.A. | S.R. 1200° F. 80,000 lb./sq. in. |
|---|---|---|---|---|---|
| | 175,000 | 128,000 | 20 | 23 | 225 hrs. |
| Spec. | 150,000 | 100,000 | 12 | 15 | 23 hrs. |



**JET ENGINE TURBINE SHAFT — MATERIAL: WASPALLOY**
**Reproducible Properties**

| | T.S. | Y.S. .02% | E.L. | R.A. | S.R. 1350° F. 70,000 lb./sq. in. |
|---|---|---|---|---|---|
| | 196,200 | 131,700 | 23 | 32 | 71 hrs. |
| Spec. | 160,000 | 90,000 | 15 | 18 | 23 hrs. |




**Cameron**
**IRON WORKS, INC.**


SPECIAL PRODUCTS DEPARTMENT
P. O. Box 1212, Houston, Texas


For more information, turn to Reader Service card, circle No. 566

# H&K PERFORATED MATERIALS

## *for Industrial or Decorative Uses*


Square holes


Slots


Oval holes

**Types of FINISHES**- Decorative sheets in aluminum can be delivered color anodized or with brushed finish. Steel sheets, painted, lacquered or Japanned. All decorative patterns can be embossed if requested.


**Types of FABRICATING** — Shearing, rolling, welding and forming services are available.

**PERFORATED SHEETS CARRIED IN STOCK** — Many patterns (industrial and decorative) are carried in stock at our warehouses for immediate delivery. Thousands of odd size pieces are also available if your requirements are small. SEND FOR H & K STOCK LIST BROCHURE.


*Write for 156 Page General Catalog No. 75 Today*

**Types of MATERIALS** — All metals — wood — plastics — cloth fabrics — paper. Facilities enable the perforating of materials furnished in sheets, coils, rolls or plates.

**Types of PERFORATIONS** — H & K has thousands of different die patterns to perforate round holes — slots — squares — triangles — oval shapes — burred, indented, tapered, stabbed, collared or lipped perforations — architectural grilles — louvres — decorative patterns — processing screens and precision sieves with tolerance held to ± .0005".


Round holes


Oblong holes


Ornamental patterns

THE **Harrington & King** PERFORATING CO., INC.


*Chicago Office and Warehouse*
5671½ Fillmore Street
Chicago 44, Illinois

*New York Office and Warehouse*
112 Liberty Street, Dept. S
New York, New York

For more information, turn to Reader Service card, circle No. 427

LFA

## . . . . . ROUND, SQUARE AND FLAT SPECIAL ALLOY WIRE is Used to Make Millions of Tiny Forms and Springs for Industry.



**Modern production applications (printed circuit, spring, connectors, terminals, tabs) require all types, shapes and finishes (solder dipped and plated, etc.) of special alloy wire for production of miniature and sub-miniature formed parts.**

**These new production techniques reduce costs, more importantly, are a guarantee of better quality control, positive size holding and minimizing finish problems.**

BERYLLIUM COPPER
Silvercote ®
titanium
phosphor bronze
ni-clad-ti
ALUMINUM
Hot Solder Dipped - Tinned -

## LITTLE FALLS ALLOYS, INC.

189 CALDWELL AVENUE, PATERSON 1, NEW JERSEY

For more information, turn to Reader Service card, circle No. 524



# Specialists in RUBBER COMPOUNDING and MOLDING

- **ANY COMPOUND FORMULATION**
- **ANY MOLDED SHAPE**
- **ANY QUANTITY**

COLONIAL RUBBER COMPANY has a long record of achievement in helping product designers and manufacturers meet rubber parts requirements efficiently and economically. Complete laboratory facilities, large molding and fabricating plant and mold-making machine shop, enable Colonial to deliver top quality molded parts quickly. We compound from such polymers as: NATURAL RUBBER, S.B.R., BUNA N, NEOPRENE*, HYPALON*, VITON A and B*, POLYURETHANE ELASTOMER, POLYACRYLIC, BUTYL, CHLORINATED BUTYL, "SILICOL"** and others. Particularly outstanding are the many special "Silicol" silicone rubber compounds our chemists have developed to meet unusually rigid performance requirements in aircraft and missile applications. All manufacturing is under strict quality control, *accurately* meeting any commercial or government specification.

1843-A

## *100% GREATER TENSILE AND TEAR STRENGTH FOR SEALS AND GASKETS WITH COLONIAL'S* REINFORCED "SILICOL" SILICONE RUBBER SHEET ▶

Desired by design engineers for rubber components subject to severe stress-strain forces. Ideal for diaphragms, gaskets, electrical insulation. Available reinforced with glass fibre, nylon fibre, or cloth of your choice, either for custom molding by Colonial, or in sheets for die-cutting and fabricating in your own plant.



***WRITE, WIRE OR PHONE COLONIAL*** for prompt information, project analysis, and recommendations . . . or send prints and details for immediate quotations.

*Reg. T.M.'s of The DuPont Company
**Reg. T.M. of Colonial Rubber Co.



**Colonial RUBBER COMPANY**

706 Oakwood Street — AXminster 6-9611

RAVENNA, OHIO

For more information, turn to Reader Service card, circle No. 569




# BUSADA BUTYRATE TUBING

TRANSPARENT — COLORLESS

Consistently high quality . . . Clear . . . durable . . . economical. ¾" to 8½" O.D. 6 ft. and 20 ft. lengths, ¼" thickness.

**BUSADA BUTYRATE PIPE AND FITTINGS**
First choice of many of the nation's leading firms because it's easier to install, easier to inspect, won't corrode . . . speeds liquid flow.

**BEFORE YOU BUY GET BUSADA'S QUOTATION**

## Busada Manufacturing Corporation

32-19 Downing Street — Flushing 54, New York

For more information, turn to Reader Service card, circle No. 394

for extruded aluminum

## team up with JARL






### *Wider Range of Extruded Sizes and Increased Production Capacity Made Possible by Jarl's 1960-61 Expansion Program.*

Jarl's unique new 3300-ton press extrudes solid shapes up to a 10½" circumscribing circle, and hollow tubular sections to approximately a 7" diameter. A new 940-ton press provides additional capacity for lighter, smaller shapes. New fabricating equipment of various kinds is being installed. Jarl's four presses, new 100-ton hydraulic stretcher, new materials handling and trailer-truck facilities now offer maximum production versatility and continued assurance of making scheduled deliveries on time. Teaming up with Jarl means sharing in the many advantages resulting from Jarl's progressive, smooth-functioning, work-flow systems. Telephone (*Rochester*) LUdlow 6-2660.

STOCK DIES AVAILABLE—ALUMILITE ANODIZING

**JARL EXTRUSIONS, INC. LINDEN AVENUE, EAST ROCHESTER, N. Y.**

For more information, turn to Reader Service card, circle No. 523

**For Quality and Economy Use**

THE MALLEABLE

**For Service Contact...**

**CONNECTICUT**
Connecticut Mall. Castings Co., New Haven 6
Eastern Malleable Iron Co., Naugatuck
New Haven Malleable Iron Co., New Haven 4

**DELAWARE**
Eastern Malleable Iron Co., Wilmington 99

**ILLINOIS**
Central Fdry. Div., Gen. Motors, Danville
Chicago Malleable Castings Co., Chicago 43
Moline Malleable Iron Co., St. Charles
National Mall. and Steel Castings Co., Cicero 50
Peoria Malleable Castings Co., Peoria 1
Wagner Castings Company, Decatur

**INDIANA**
Albion Malleable Iron Company, Muncie Division, Muncie
Link-Belt Company, Indianapolis 6
National Mall. & Steel Castings Co., Indianapolis 22

**IOWA**
Iowa Malleable Iron Co., Fairfield

**MASSACHUSETTS**
Belcher Malleable Iron Co., Easton

**MICHIGAN**
Albion Malleable Iron Co., Albion
Auto Specialties Mfg. Co., Saint Joseph
Cadillac Malleable Iron Co., Cadillac
Central Fdry. Div., Gen. Motors, Saginaw

**MINNESOTA**
Northern Malleable Iron Co., St. Paul 6

**MISSISSIPPI**
Mississippi Malleable Iron Co., Meridian

**NEW HAMPSHIRE**
Laconia Malleable Iron Co., Laconia

**NEW YORK**
Acme Steel & Mall. Iron Works, Buffalo 7
Frazer & Jones Company Division Eastern Malleable Iron Co., Solvay
Oriskany Malleable Iron Co., Inc., Oriskany
Westmoreland Mall. Iron Co., Westmoreland

**OHIO**
American Malleable Castings Co., Marion
Central Fdry. Div., Gen. Motors, Defiance
Dayton Mall. Iron Co., Ironton Div., Ironton
Dayton Mall. Iron Co., Ohio Mall. Div., Columbus 16
Maumee Malleable Castings Co., Toledo 5
National Mall. and Steel Castings Co., Cleveland 6

**PENNSYLVANIA**
Buck Iron Company, Inc., Philadelphia 22
Erie Malleable Iron Co., Erie
Lancaster Malleable Castings Co., Lancaster
Lehigh Foundries Company, Easton
Meadville Malleable Iron Co., Meadville
Pennsylvania Malleable Iron Corp., Lancaster

**TEXAS**
Texas Foundries, Inc., Lufkin

**WEST VIRGINIA**
West Virginia Mall. Iron Co., Point Pleasant

**WISCONSIN**
Belle City Malleable Iron Co., Racine
Chain Belt Company, Milwaukee 1
Federal Malleable Company, Inc., West Allis 14
Kirsh Foundry Inc., Beaver Dam
Lakeside Malleable Castings Co., Racine
Milwaukee Malleable & Grey Iron Works, Milwaukee 46

**These companies are members of the Malleable Castings Council**

For more information, circle No. 443




Photo-elastic stress patterns produced by models photographed with polarized light are one of the modern analytic tools available for ever-increasing perfection of Malleable iron castings.

## For Greatest Strength Per Dollar... Use Malleable

To improve quality and cut costs, you'll find nothing better than Malleable iron castings. They provide more strength per dollar than any other metal, ferrous or non-ferrous! With Malleable you also get proven toughness, uniform quality and unsurpassed machinability.

See for yourself how much Malleable castings will improve your products and cut your costs. Send drawings or an outline of your requirements to a nearby Malleable castings producer who displays this symbol—

MEMBER
MALLEABLE
CASTINGS COUNCIL

For detailed information on "Strength Characteristics of Malleable Iron Castings", contact any of the progressive companies listed on the opposite page, or Malleable Castings Council, Union Commerce Building, Cleveland 14, Ohio.



# Chart new paths in printed circuits with Panelyte®

As new uses for printed circuits are developed, and new, more demanding designs are specified—count on Panelyte Copper-Clad Laminates for consistently superior quality.

At present, you can choose from a wide range of properties in four different grades. But St. Regis® Panelyte is working to perfect structural qualities which will meet your *future* needs, as well.

Whether you're looking for better machinability and adhesion, superior chemical resistance, closer thermal tolerances or any special combination of characteristics, bring your copper-clad laminate specifications to Panelyte. We can supply Panelyte in the following grades: Paper Phenolic Base—XP, XXP, XXXP; Glass Melamine—G5; Glass Silicone—G7; Glass Epoxy—G10, G11. For complete information and the address of your nearest Panelyte distributor, write Dept. MDE 1160, St. Regis Paper Co., 150 E. 42nd St., N.Y., N.Y.

St.Regis PANELYTE®

For more information, turn to Reader Service card, circle No. 561



1. Wolverine Capilator Catalog



2. Wolverine Aluminum Catalog




3. Opportunities Unlimited



4. Wolverine Trufin Catalog




5. Copper Refrigeration Tube Book



6. Measure of Tubemanship



7. Design & Cost Comparison




8. Process Flowsheets




9. Statement of Scope



10. Water Heater Catalog



11. Commercial Tubing Book



12. Wolverine Serves The Refrigeration Industry




13. Copper Water Tube Catalog



14. Wolverine Corrosion Chart

# When it comes to tube... come to Wolverine

From Wolverine Tube, manufacturers can obtain a great variety of tubular products. These range from such products as tiny, plug-drawn Wolverine Capilator® used for restriction purposes, to commercial copper tube up to 6 inch O.D. and aluminum tube to 3 inch O.D.


Illustrated on this page—and reading like tubing's "best seller" list—is the latest Wolverine Tube literature dealing with all the company's products and specialized services. Look these catalogs over. A request, on your letterhead, will bring you the catalog . . . or catalogs . . . of your choice without delay or obligation. Just write Dept. F—TODAY!

**WOLVERINE TUBE**
DIVISION OF
**Calumet & Hecla, Inc.**
DEPT. F, 17296 SOUTHFIELD RD., ALLEN PARK, MICH.
Manufacturers of Quality-Controlled Tubing
J-8990
PLANTS IN DETROIT, MICHIGAN, AND DECATUR, ALABAMA.
SALES OFFICES IN PRINCIPAL CITIES.

**PLANTS LOCATED:**




DETROIT, MICHIGAN



DECATUR, ALABAMA

MADE IN U.S.A.
TO THE STANDARDS
OF AMERICAN INDUSTRY
★★★★★★★

For more information, turn to Reader Service card, circle No. 486




# Wire shaped to fit your design...

• If your design involves wire with special or unusual cross-section, PAGE shaped wire can save material, eliminate machining, forming, forging or similar operations. When you specify PAGE shaped wire, you get these additional advantages:

**The shape you need** • PAGE can furnish all of the standard shapes, such as squares, ovals, flats and keystones, as well as hundreds of special shapes made to your own drawings and specifications.

**Extra strength** • PAGE shaped wire is stronger than hot-rolled material. The cold drawing of PAGE shaped wire increases tensile strength, yield point and hardness—improves both wear resistance and machineability.

**Many grades of steel** • You can specify low carbon, high carbon, alloy or stainless steels, and Armco ingot iron. We'll be glad to recommend the steel best suited to your application.

**Accuracy** • Both the cross-sections and contours of PAGE shaped wires are extremely accurate, the result of careful cold-drawn or cold-rolled processes in our mill.

**Packaged right** • PAGE shaped wire is furnished in either standard or special coils of exact weight. Straightened and cut wire is available in either exact or random lengths. It's packaged in bare bundles, wrapped in waterproof paper, burlapped, in cartons, boxes, Leverpaks, or in other ways to meet your requirements.

***Write for Book*** • **DH-1226** *contains data on carbon and alloy steel weights—explains how to calculate areas of common shapes—lists physical properties of steel wire. Write us at Monessen, Pa., for a copy.*

ACCO **PAGE MANUFACTURERS WIRE**

**Page Steel and Wire Division • American Chain & Cable Company, Inc.**

Monessen, Pa., Atlanta, Chicago, Denver, Detroit, Houston, Los Angeles, New York, Philadelphia, Portland, Ore., San Francisco, Bridgeport, Conn.


# PAGE

*-the source for answers to wire problems*

For more information, turn to Reader Service card, circle No. 564

Find the answers to *your* engineering questions in

# PROCESSING OF THERMOPLASTIC MATERIALS




**1959**
**706 pages**
**$18.00**
**Profusely illustrated**

Here are hundreds of pages of the latest and best engineering information on all phases of thermoplastics processing. Twenty leading plastics engineers provide specific and useful data on fundamentals, applications and processing properties. Over 150 sections embrace the entire subject in a reliable and practical manner. Early reviews and comments convey a brisk enthusiasm over the clarity of the writing, the high level of dependability and the complete coverage.

The editor is E. C. BERNHARDT of the Polychemicals Department, E. I. du Pont de Nemours & Co., Inc.

Sponsored by the SOCIETY OF PLASTICS ENGINEERS, INC.

**MAJOR HEADINGS:** FUNDAMENTALS: Flow Behavior of Thermoplastics; Heat Transfer and Thermodynamics; Mixing and Dispersing. APPLICATIONS: Extrusion; Injection Molding; Calendering; Mixing and Dispersing Processes; Sheet Forming; Forming of Hollow Articles; Sealing and Welding. PROCESSING PROPERTIES.

*Examine It Free For 10 Days*

**MAIL THIS COUPON NOW!**

**REINHOLD PUBLISHING CORPORATION**
**Dept. M-718, 430 Park Avenue**
**New York 22, N. Y.**

Send me a copy of PROCESSING OF THERMOPLASTIC MATERIALS for 10 days' Free Examination. After 10 days, I will send you $18.00 plus postage or I will return the book and owe nothing


NAME _____

ADDRESS _____

CITY & ZONE _____ STATE _____

**SAVE MONEY:** Enclose payment, and Reinhold pays all the shipping costs. Same return privilege; refund guaranteed. Do not enclose cash!

# EXTRUSION SPECIALISTS



## Profiles · Sheet · Moldings

**Compounding to meet specific design requirements in Vinyls, standard and linear Polyethylene, Teflon 100, Nylon, Polypropylene, Polystyrene, Styrene rubber co-polymers and others**

Complete technical facilities, our own die shop, a wide range of extruder types and sizes, and rigid quality control standards, enable Conneaut to deliver quickly top-quality extrusions, competitively priced.

We can, for example, provide plastic sheet, either rigid or elastomeric, for fabrication by heat welding or vacuum forming, in gauges from .025" to .250" in various widths. We can furnish extrusion molded slugs up to several hundred pounds for further machining in your plant or we can furnish the final part machined to your specifications. Formulations can be varied to meet design requirements. For nuclear applications, additives such as elemental boron, boron carbide, lead oxide or cadmium oxide can be incorporated. We can furnish profiles in any extrudable cross-section to extremely close tolerances and hold the tolerances through the length of the run. If desired, we can heat-seal, punch or otherwise fabricate the extruded profile to your specifications.



***IF IT IS EXTRUDABLE IN PLASTIC***
**CONNEAUT *CAN EXTRUDE IT***
**Quickly, Accurately, Economically**

Write, wire, or phone 51-961, Conneaut, for prompt information, project analysis, recommendations or quotations.



The new research facilities of Conneaut Rubber & Plastics Co.

1844-A

# CONNEAUT
## RUBBER & PLASTICS CO.
*CONNEAUT, OHIO*

A UNIT OF
THE UNITED STATES STONEWARE COMPANY

For more information, turn to Reader Service card, circle No. 501




Designing a new part or product? Checking parts in present assemblies in an effort to improve product performance . . . extend service life . . . reduce assembly operations . . . lower costs?

Call on Acushnet. We've provided the solution to troublesome production, performance and cost problems in the products of innumerable manufacturers, large and small.

Custom engineered to meet the special requirements of your particular application, an Acushnet precision-molded rubber part could be the answer you've been looking for.

Acushnet

*Acushnet Rubber Data Handbook sent when requested on your company letterhead. Also available; brochures on Rubber-To-Metal Bonding, and Silicone Rubber Parts.*

**ACUSHNET PROCESS COMPANY**

**Address all communications to 750 Belleville Ave., New Bedford, Mass.**

**For more information, turn to Reader Service card, circle No. 498**


*For more data on*

**FILAMENT WOUND REINFORCED PLASTIC PARTS**

**METAL POWDER STRUCTURAL PARTS**

**DESIGNING METAL STAMPINGS**

Reprints of **MATERIALS IN DESIGN ENGINEERING MANUALS** on these engineering materials are now available at 35¢ per copy. Each Manual is a complete and comprehensive discussion to guide you in materials selection and use. If you would like copies, write today.

**"Filament Wound Reinforced Plastics: State of the Art,"** 20 pp. This popular reprint is a 3-part report that tells you (1) what you can expect from filament wound reinforced plastics parts, (2) how to select and evaluate the materials, and (3) how process variables affect end service properties. Data are supplemented by helpful charts, tables and photographs.

**"Designing for Metal Powder Structural Parts,"** 12 pp. Metal powder compacts can provide outstanding service at minimum cost for engineers and designers who are familiar with their advantages and limitations. This manual helps you determine the properties of various powder mixtures, and select suitable designs and applications to take full advantage of these properties. The manual covers: Ferrous and nonferrous materials, Design pointers, Finishing, Economics, and Typical applications.

**"Designing Metal Stampings,"** 16 pp. A designer not fully informed on the stamping process can cost his company a lot of money by failing to consider stampings when he should or by designing stampings that result in costly production. This manual tells how to design for the stamping process; covers blank layout, holes, bends, radii, tolerances; and discusses the working characteristics of the metals commonly used.

---

*For copies of* M/DE *Manuals at 35¢ each, write to:*

**Reader Service Department**
**MATERIALS IN DESIGN ENGINEERING**
**430 Park Avenue, New York 22, N. Y.**

# Over a million ceramic pieces...



# DAILY!

## Centralab's enormous facilities for ceramic production can serve your company, too!

1,215,000 ceramic pieces are produced in an average day at CENTRALAB! Some are big, some are small. Some require exacting tolerances and intricate machining; others are less complex, but still require appropriate facilities for quantity production.

The CENTRALAB Ceramic Design Handbook is available for your use. Write for your copy, or consult Sweet's Product Design File (folio 4a/ce).

**SOME STATISTICS ON CENTRALAB'S FACILITIES**

**29 Kilns**

A variety of linear, circular, and oven types, in a comprehensive range of sizes to meet any need.

**85 Presses**

Specialized equipment for forming, extruding, pelleting.

**175 Precision Machines**

Equipment for grinding, polishing, boring, threading, etc. to tolerances ±.0002".

**226,600 sq. ft. of floor space**

devoted to ceramic engineering and production.

**Centralab**

CRL

X-6009

The Electronics Division of Globe-Union Inc.
**946D E. Keefe Avenue • Milwaukee 1, Wisconsin**
In Canada: P. O. Box 400, Ajax, Ontario

**ELECTRONIC SWITCHES • VARIABLE RESISTORS • CERAMIC CAPACITORS • PACKAGED ELECTRONIC CIRCUITS • ENGINEERED CERAMICS**

For more information, turn to Reader Service card, circle No. 396

# RITCO FORGINGS



## ...their accuracy alone merits your design consideration!

**Close-tolerance accuracy** which eliminates the need for costly machining is, in itself, a sound reason for specifying Ritco Forgings. A flawlessly smooth surface which helps speed product assembly is still another. Combine these advantages with a forged-in toughness which assures maximum impact resistance and fatigue strength at points of greatest shock and stress and it's easy to see why more and more design engineers write Ritco into their plans. *All* things considered, it will pay you to learn more about Ritco "Bright Finish" Forgings now. Send us your blueprints for estimates at no obligation.



Ritco also offers complete machining facilities and makes Special Fasteners and Upsets of ferrous and non-ferrous metals. What are your requirements?

**RHODE ISLAND TOOL COMPANY**
*Member Drop Forging Association*
156 WEST RIVER STREET • PROVIDENCE 1, R. I.

For more information, turn to Reader Service card, circle No. 461




* Leather • Asbestos • Nylon • Vinyl • Teflon • Silicone Rubber • Neoprene • Rubber Cork • Fibre • Compositions • Phenolics • Cloth • Felt • Paper • Cardboard • Plastics Brass • Steel • Copper • Aluminum • Kel-F • Viton A • Mylar • Other Special Materials

Send specifications or blueprints for prompt quotations and recommendations. No obligation.

**THE AUBURN MANUFACTURING CO.**
302 Stack St., Middletown, Conn.

New York, N. Y.; Rochester, N. Y.; Detroit, Mich.; Chicago, Ill.; Minneapolis, Minn.; Pittsburgh, Pa.; Cincinnati, Ohio; Ridgewood, N. J.; Atlanta, Ga.; Memphis, Tenn.; St. Louis, Mo.; Washington, D. C.

For more information, turn to Reader Service card, circle No. 389

*Custom*
## Perforating

—on all types of flexible materials, rigid sheets, and foam.

plastics
cellophane
paper
fabrics
rubber

in sheets and rolls up to 72" wide

Whatever your perforating needs, PERFORATING INDUSTRIES has the specialized equipment and know-how to handle the job. Rely on us if you're looking for quality workmanship, prompt delivery, and fair pricing. *Write today for our free catalog!*


**Perforating Industries, Inc.**
*609 Commerce Road, Linden, N. J. · WAbash 5-0350*

For more information, turn to Reader Service card, circle No. 454

**Intricacy • smoothness • soundness**



# only a Wauke-Sha Ceramic-Type Casting can duplicate the intricacy, smooth finish, soundness ... to absolute tolerances ... in unlimited size



- intricate parts with no costly machining
- hairline reproduction of detail
- no cracking or tearing
- no porosity, internal voids, cracks
- no surface gas holes, blemishes, non-metallic inclusions

Absolute dimensional accuracy plus greatly increased heat and stress resistance are critical to today's intricate designs. Wauke-Sha process will provide low-cost castings to fill these demands . . . castings which are, in many cases, more accurate than machining, with "as cast" dimensional tolerances of ±.005" per inch.

Full design flexibility is a major advantage of this newly developed casting technique. Thin-wall designs require no expensive machining; no fear of voids with light and heavy adjacent sections.

*For further information on Wauke-Sha Ceramic Type Castings write:*

Waukesha Foundry Company

**Dept. F-S2, Waukesha Foundry Co., Waukesha, Wis.**

For more information, turn to Reader Service card, circle No. 495

# WHY

ARE ZINC DIE CASTINGS *the most widely used* ?

*because* the ZAMAK alloys have advantages over the other die casting materials...

# WHY

has the use of nonferrous metal powders *increased faster than* ferrous powders ?

*because* HORSE HEAD brass and nickel silver powders have so many outstanding advantages

HORSE HEAD PRODUCTS ®

- . . . bright, lasting finish at low costs
- . . . range of alloys for controlled properties
- . . . closer control of dimensional tolerances
- . . . superior machinability
- . . . excellent corrosion resistance without plating
- . . . wide range of electrical properties
- . . . attractive color

For more information, circle No. 452

## RANGE OF MECHANICAL PROPERTIES

| | ZINC ALLOYS | ALUMINUM ALLOYS | MAGNESIUM ALLOYS |
|---|---|---|---|
| Impact Strength | 43-48, CHARPY (toughest) | 2-8, CHARPY | 1-2, IZOD |
| Tensile Strength | 41,000-48,000 (strongest) | 30,000-45,000 | 30,000-33,000 |
| Shearing Strength | 31,000-38,000 (toughest) | 19,000-28,000 | 20,000 |
| Elongation | 7-10 (most ductile) | 2-9 | 1-3 |
| Brinell Hardness | 82-91 (hardest) | 50-80 | 60-62 |
| **CASTING CHARACTERISTICS** | | | |
| Ease, Speed of Casting | (easiest) | | |
| Maximum Feasible Size | (greatest) | | |
| Complexity of Shape | (most complex) | | |
| Dimensional Accuracy | (most accurate) | | |
| Minimum Section Thickness | (thinnest) | | |
| Surface Smoothness | (smoothest) | | |
| **COST** | | | |
| Die Cost* | (lowest) | | |
| Production Cost | (lowest) | | |
| Machining Cost | (next to lowest) | | |
| Finishing Cost** | (lowest) | | |
| Cost per piece*** | (lowest) | | |
| **EXTENT OF USE** | | | |
| Extent of Use | (most used) | | |

*Dies for casting the low melting point alloys are least expensive and have longest life.

**Includes polishing and buffing expense as well as ease of applying all types of commercial finishes, both electrodeposited and organic.

***Based on die and fuel costs, production speed and machining and finishing costs.

| NOMINAL RANGE | HORSE HEAD BRASSES | HORSE HEAD NICKEL SILVERS |
|---|---|---|
| Copper | 70-90% | 64% |
| Nickel | — | 18% |
| Lead | 0-1.75% | 0-1.5% |
| Zinc | remainder | remainder |
| **PROPERTIES AND CONSTANTS** | | |
| Tensile Strength | 23,000-41,000 | 23,000-31,000 |
| Elongation | 8-34 | 7-15 |
| Rockwell H Hardness | 58-81 | 78-80 |
| Electrical Conductivity | 154,000-205,000 | 32,000 |




**SEND FOR THESE USEFUL BOOKLETS**

They will show you in detail how you can apply these cost-saving processes to your product. [illegible] and many illustrations of practical application are presented for reference.



HORSE HEAD PRODUCTS

THE NEW JERSEY ZINC COMPANY

160 Front Street, New York 38, N. Y. — 221 North LaSalle St., Chicago 1, Ill.



*for*

# CORROSIVE SERVICE

# wire cloth

In many metals including...

**STAINLESS STEEL**
**MONEL • NICHROME**
**PHOSPHOR BRONZE**
**ALUMINUM**
**BRASS • COPPER**

For many uses involving...

**FILTER CLOTH • SIEVES**
**STRAINERS • SCREENS**
**BACKING CLOTH**
**WIRE GUARDS**
**BOLTING CLOTH**
**SPACE CLOTH**
**BASKETS**

If you have a tough corrosion problem and need wire cloth or wire cloth parts, here's a source of supply that knows the answers. We are proud of the quality of our cloth...accurate mesh count, close tolerance wire diameter, precision weaving...plus the know-how necessary to specify the proper alloy for **your** service conditions.

NEWARK for ACCURACY

Write or call us today if you have a problem calling for anti-corrosive wire cloth or wire cloth parts. Send for Bulletin F-C.

**Newark Wire Cloth COMPANY**

**351 Verona Avenue • Newark 4, New Jersey**

**For more information, turn to Reader Service card, circle No. 527**


## INFORMATION PLEASE!

Want more data on products advertised in this section?

Each advertisement has a circle number, and all you have to do is circle the same number on one of the Reader Service cards (beginning page 585) to get literature detailing engineering data, properties, applications and other useful information from the manufacturer of the product(s) you are interested in. The card is postpaid.

This useful materials information service can also bring you any of the literature listed on page 364. Review the advertisements and the literature listings, then make use of this free service. A moment of your time is all it takes. The literature you will receive has been prepared especially to help you solve materials application problems.

Reminder: For Reader Service Cards, please see page 585.




# THE MAN FROM MUELLER BRASS CO.

## REPRESENTS *ONE DEPENDABLE SOURCE* FOR COPPER, BRASS, ALUMINUM AND PLASTIC PRODUCTS


Because the diversified facilities of his company encompass a wide range of manufacturing methods, the Man From Mueller Brass Co. is in the unique position of being able to offer you an intelligent, unbiased analysis and recommendation of the one best method of producing your particular part. When you are designing, specifying and purchasing fabricated parts . . . call in the Man From Mueller Brass Co. You will get the best product at the best price . . . made the *one best way!*



FORGINGS




COLD-PREST® IMPACT EXTRUSIONS




SCREW MACHINE PRODUCTS




SAND CASTINGS




FORMED COPPER TUBE



SPECIAL ALLOY ROD FOR FORGINGS AND SCREW MACHINE PRODUCTS



SINTEEL® POWDERED METAL PRODUCTS



CUSTOM EXTRUDED PLASTIC SHAPES AND INJECTION MOLDINGS


MUELLER BRASS CO.

# MUELLER BRASS CO.

PORT HURON 21, MICHIGAN

287-R

For more information, turn to Reader Service card, circle No. 565



## HOW MANY METAL POWDER PARTS?

Metal powder applications continue to expand as more and more manufacturers put powder metallurgy to work. Today's product designer has at his disposal an almost endless number of applications for metal powders. Industry has discovered that the process results in savings in material, manpower and equipment . . . while improving the quality and uniformity of the various fabricated parts.

Metals Disintegrating Company is prepared to supply any manufacturer, anywhere in the world, a specific grade of powder in aluminum, tin, copper, plus other metals or alloy powders in a wide range of particle sizes. In addition, our laboratory facilities are at your disposal to help you select the correct grade and material for your product.

**METALS DISINTEGRATING COMPANY**

Division of American-Marietta Company

General Offices, Department X, Elizabeth 8, N. J.

For more information, turn to Reader Service card, circle No. 568


# *Nowhere else can you buy more* EXPERIENCE...



. . . in the design, development, and manufacture of aerial delivery systems.



. . . in the design and manufacture of lightweight missile support cabinets and consoles.



. . . in the design and manufacture of magnesium gun turret enclosures.



. . . in high precision manufacture of satellite structural assemblies.



. . . in the design and manufacture of lightweight radar reflectors, plotting board systems and related equipment.



. . . in the design and manufacture of housings, transit cases, pressurized equipment and containers.

. . . in the design and production of all types of lightweight assemblies—of magnesium, aluminum, titanium, zirconium and beryllium.

*Write for Magnesium and Titanium Data Book and more information about B&P's unique experience.*

**BROOKS & PERKINS, INC.**

1916 WEST FORT ST. • DETROIT 16, MICHIGAN

61-T-1

For more information, turn to Reader Service card, circle No. 513



# Why compromise one requirement to satisfy another?



## Fiberglass Polyester PRE-MIX can be tailored to exact specifications

Firmaline's *pre-mix products offer:*

- **design flexibility**
- **light weight**
- **strength-durability**
- **molded-in color**
- **high dielectric strength**
- **corrosion resistance**
- **dimensional stability**
- **impact resistance**
- **excellent weathering**
- **fire retardance**
- **low cost**



FIRMALINE compounds and molds its own PRE-MIXES. Each is designed for a specific need, providing optimum properties and permitting efficient molding in modern presses.

A recognized pre-mix specialist as well as molder of regular fiberglass parts, Firmaline's experience and technical staff make possible the compounding and molding of an unusual variety of materials. Let us help you.

*Write for technical data*

**FIRMALINE**

**PRODUCTS**

**of Crompton and Knowles**

For more information, circle No. 537

# BOSSERT®


## STAMPINGS AND ASSEMBLIES

Solve Your Design and Manufacturing Problems


You need no capital equipment, inventory or floor space to obtain large, intricate stampings and assemblies like these . . .



**Welded Steel Meter Body Assembly** weighs 300 pounds. Diaphragm cover, 31¾" x 27½" x 4¼" x ¼" thick. 24 stamped components, 44 resistance welded bolts. 263" of arc welded joints. Complete unit tested at 100 pounds pressure.



**Welded Aluminum Electronic Chassis Assembly** weighs 17 pounds. Overall dimensions, 23¾" x 20⅞" x 7⅝". 28 formed parts, 123 certified spot welds.




◀ **Welded Steel Electrical Cabinet Assembly** weighs 67 pounds. Dimensions, 25" x 14" x 30". 24 component parts. 24 tack welds, 36 spot welds, riveting and 6" of arc welding. Painted.

WRITE FOR FREE BULLETIN B-2
Rockwell-Standard Corporation,
Stamping Division, Dept. K-1, Utica, N.Y.

**ROCKWELL-STANDARD**
CORPORATION
Stamping Division, Utica, New York

For more information, turn to Reader Service card, circle No. 517

# Pyramid



*SPECIALISTS*
at **AUTOMATION**
OF ALL INJECTED THERMOPLASTICS
**NYLON · DELRIN · LEXAN**
**POLYPROPYLENE · VINYL**
*SOME STOCK MOLDS FOR*
**BUSHINGS · GEARS · RIVETS**

**SEND PRINTS** *FOR PROMPT QUOTATIONS*

**Pyramid Products**

**Plastic Division, 3967 E 93, Cleveland 5, Ohio**

For more information, turn to Reader Service card, circle No. 458

PE

**A PROMPT DEPENDABLE MILL SOURCE**

**EXTRUDED ALUMINUM**

SHAPES

TUBES

RODS

BARS

**5,000 STANDARD SHAPES WITHOUT DIE CHARGE**—prompt mill-run service on a wide variety of shapes.

**SPECIAL SHAPES** — quickly, economically produced, even small runs, to fill specific needs. Free "Extrusioneering" service to help you cut costs.

**NON-COMPETITIVE MILL SERVICE** — producing extrusions only. We do not fabricate or manufacture other products.

**COMPLETE FACILITIES**—die making, billet casting, range of presses for economical production, and standard finishing.

*Write* **FOR "EXTRUSIONEERING NEWS"** Free bulletins give case reports and helpful technical data.

PE

**PRECISION EXTRUSIONS, INC.**
727 E. GREEN AVENUE — BENSENVILLE, ILL.
PHONE: POrter 6-0340 • (Chicago) NAtional 5-4600

*Chicagoland's Oldest Most Experienced Aluminum Extruder*

REGIONAL SALES OFFICES
INDIANAPOLIS MILWAUKEE GRAND RAPIDS MINNEAPOLIS DETROIT
CLifford 1-8525 BRoadway 2-1307 GLendale 6-1382 WAlnut 2-6888 TUxedo 1-5400

For more information, turn to Reader Service card, circle No. 554

# Can You Use BETTER Gray Iron Castings?

## Eaton's Continuing Research and Development Programs Assure You the BEST—Engineered to Your Individual Needs

### EATON PERMANENT MOLDING




Because of the denser, non-porous, homogeneous structure, Eaton Permanent Mold Castings meet critical quality requirements. The finer dispersion of graphite provides a better material where free machinability and accuracy are essential in critical machining operations. Eaton annealed gray iron castings are available in sizes from one tenth of a pound to fifty pounds.

### EATON SHELL CORING



The Eaton process of Shell Coring in permanent mold and shell molded castings provides better internal surface finish and higher dimensional accuracy. Where more than ordinary quality and control of contour are required, the Eaton process offers distinct design advantages and greater uniformity in intricately cored sections.

### EATON SHELL MOLDING




Eaton Shell Molding provides more closely controlled metallurgy and hardness for applications requiring pearlitic structures, close dimensional control, and complex designs and contours. Eaton Shell Mold Castings require less machining and finishing, with resulting savings in material, tooling, and shipping.

***Send for Illustrated Descriptive Literature***

**EATON**

**FOUNDRY DIVISION**
**MANUFACTURING COMPANY**
**VASSAR, MICHIGAN**


**For more information, turn to Reader Service card, circle No. 509**



# MOXNESS


LOGICAL SOURCE FOR EXTREME TEMPERATURE (−170° F. to 600° F.) SILICONE and FLUOROCARBON* PRODUCTS

**Product Engineering! Tooling! Precision Production! Moxness offers a complete ONE-STOP service for solving extreme temperature problems. Let us work with you at the planning stage. Write for the Moxness story today!**




## PRECISION MOLDING

Mass production of precision parts ranging from phase lead insulating caps of silicone rubber (shown at far left designed for room temperature vulcanizing) to switch parts of mineral-filled silicone resin (lower right, designed to retain dimensional stability at temperatures of 2000° F.) calls for precision production techniques gained only through experience.




## PRECISION BONDING

Environment proof limit switches (like this one for airborne equipment) call for completely sealed construction. These seals (shown in red) are silicone rubber bonded to metal by Moxness . . . evidence of Moxness ability to handle the most exacting requirements in this specialized field.


## PRECISION EXTRUDING

Large, small, simple or complex . . . here are samples of the wide range of quality silicone rubber extrusions you can expect from Moxness. Special equipment and an exclusive process developed by Moxness also assures you of paying less for precision extrusions when you order from Moxness.



## PRECISION TAPES

The coil shown here is being insulated with NEW Guide Line Triangular MOX-TAPE which provides homogeneous void-free insulation for motors (class H and B) with a single wrap. Mox-Tape fuses to itself . . . eliminates messy pastes or adhesives. Cuts taping time 50 to 60%.



*DU PONT VITON, TEFLON; 3M KEL-F

**MOXNESS** Subs. Nat'l Rivet and Mfg. Co.

**MOXNESS PRODUCTS, INC.**

1965 INDIANA STREET • RACINE, WISCONSIN

For more information, turn to Reader Service card, circle No. 541



*For more data on*

**SHORT RUN PRESS-FORMED PARTS**

**MECHANICAL TUBING**

**METAL STAMPINGS**

Reprints of **MATERIALS IN DESIGN ENGINEERING MANUALS** on these engineering materials are now available at 35¢ per copy. Each Manual is a complete and comprehensive discussion to guide you in materials selection and use. If you would like copies, write today.

**"Short Run Press-Formed Parts,"** 16 pp. This summary helps you adapt the mass production press to economical forming of relatively small quantities of sheet metal parts. Tells about rubber press pad, flexible female die, flexible male die and drop hammer methods; kind of parts each can form; aids you in designing for short run production. Methods are discussed in light of: Forming Principles; Materials Formed; Advantages and Limitations; Design Considerations.

**"Mechanical Tubing"** (20 pp.) a versatile, basic metal form manufactured specifically for further processing into fabricated parts. Its advantages of inherent structural strength, weight saving, and reduction of production time and costs make it attractive for the design of a wide variety of products. This manual outlines the available types and shapes of mechanical tubing, the ways in which it can be fabricated, and typical applications. It gives the principal characteristics of these tubing materials: Steel, Stainless, Copper, Nickel, Aluminum, Magnesium, Titanium and Specialty Alloys.

**"Designing Metal Stampings,"** 16 pp. A designer not fully informed on the stamping process can cost his company a lot of money by failing to consider stampings when he should or by designing stampings that result in costly production. This manual tells how to design for the stamping process; covers blank layout, holes, bends, radii, tolerances; and discusses the working characteristics of the metals commonly used.

---

*For copies of* M/DE *Manuals at 35¢ each, write to:*

Reader Service Department

**MATERIALS IN DESIGN ENGINEERING**

430 Park Avenue, New York 22, N. Y.

# PROPERTIES OF MEEHANITE METAL

## GENERAL ENGINEERING TYPES

| | GM | GA | GB | GC | GD | GE |
|---|---|---|---|---|---|---|
| Tensile Strength — psi | 55,000 | 50,000 | 45,000 | 40,000 | 35,000 | 30,000 |
| Modulus of Elasticity — psi | 22,000,000 | 20,000,000 | 18,000,000 | 17,000,000 | 14,500,000 | 12,000,000 |
| Modulus of Rupture — psi | 93,000 | 88,950 | 84,700 | 82,000 | 74,100 | 61,000 |
| Compression Strength — psi | 200,000 | 175,000 | 160,000 | 150,000 | 130,000 | 120,000 |
| Fatigue Strength — psi | 25,000 | 22,000 | 19,000 | 17,500 | 15,000 | 13,700 |
| Shear Strength — psi | over 55,000 | 48,000 | 44,000 | 40,000 | 35,000 | 30,000 |
| Impact Strength — Charpy — ft. lbs. | 8.0 | 7.2 | 5.8 | 4.5 | 3.2 | 2.1 |
| Brinell Hardness (as cast) | >217 | >207 | >207 | >195 | >183 | >174 |
| Machinability Rating | 50 | 48 | 48 | 47 | 44 | 38 |
| Specific Gravity | 7.34 | 7.31 | 7.28 | 7.25 | 7.22 | 7.06 |

## HEAT RESISTING TYPES

| | HE | SP HE | HD | HB | HR | SC | HS |
|---|---|---|---|---|---|---|---|
| Maximum Working Temperature | Thermal Shock | Thermal Shock | 1150°F | 1400°F | 1450°F | 1650°F | 1700°F |
| Tensile Strength — psi | 30,000 | 35,000 | 33,000 | 38,000 | 40,000 | 27,000 | 60/100,000 |
| Modulus of Elasticity — psi | 10,000,000 | 14,000,000 | 17,500,000 | 19,000,000 | 21,000,000 | 17,500,000 | 23,000,000 |
| Transverse Strength — lbs. | 2300 | 2800 | 2600 | 2860 | 2860 | 1500 | 4000 |
| Deflection — inches | .28 | .28 | .24 | .26 | .24 | .17 | .40 |
| Brinell Hardness (as cast) | < 207 | < 241 | 223 Approx. | 300 or over | 300 or over | >228 | >196 |
| Thermal Conductivity 50°-450°F BTU/Hr./Sq. Ft./Inch Thickness/°F | 298 | 300 | 325 | 360 | 350 | 278 | 290 |
| Coefficient of Thermal Expansion Per °F — from 100°F to 1000°F | .00000666 | .00000670 | .00000709 | .00000728 | .00000743 | .00000674 | .00000740 |

## NODULAR "S" TYPES

| | SP-80 | SH-100 | SF-60 | HS | WS |
|---|---|---|---|---|---|
| Tensile Strength — psi | 80/100,000 | 100/170,000 | 60/80,000 | 60/100,000 | 60/80,000 |
| Yield Strength — psi | 60/75,000 | 70/130,000 | 45/60,000 | 45/75,000 | 50/65,000 |
| Elongation | 3%-10% | 1%-5% | 15%-25% | 2%-10% | 2%-4% |
| Brinell Hardness | 207/267 | 263/600 | 150/190 | >196 | 400/525 |
| Impact (ft. lbs.) | 45/60 | 35/50 | 60/115 | up to 115 | up to 180 on 1.2" bar |

## ABRASION RESISTING TYPES

| | WA | WAH | W | SPECIAL WB | WS | WH | AQ |
|---|---|---|---|---|---|---|---|
| Tensile Strength — psi | >50,000 | up to 70,000 | >50,000 | 40/50,000 | 60/80,000 | >30,000 | >65,000 |
| Brinell Hardness | 227/350 | 250/600 | >550 | 350/600 | 400/525 | 575 | up to 550 |

## CORROSION RESISTING TYPES

| | $CB_3$ | CC | KC |
|---|---|---|---|
| Tensile Strength — psi | >45,000 | 40/45,000 | >32,000 |
| Modulus of Elasticity — psi | 19,000,000 | 19,000,000 | 14,000,000 |
| Compression Strength — psi | 160,000 | 160,000 | 130,000 |
| Brinell Hardness (as cast) | >197 | 187 up | >197 |
| Service | Concentrated Sulphuric Acid | Acids and Chemicals | Resistance to Alkalies |

Meehanite metals meet a real demand by industry for engineering materials of known and consistent properties. Specify Meehanite today and be sure of obtaining uniformly sound castings. For more information write for your free copy of the HANDBOOK OF MEEHANITE METAL.

For more information, circle No. 446

# MEEHANITE METAL

The American Laundry Machinery Co., Rochester, N. Y.
Atlas Foundry Co., Detroit, Mich.
Banner Iron Works, St. Louis, Mo.
Barnett Foundry & Machine Co., Irvington, N. J.
Casting Service Corp., LaPorte, Indiana and Bridgman, Michigan
Centrifugally Cast Products Div., The Shenango Furnace Co., Dover, Ohio
Crawford & Doherty Foundry Co., Portland, Ore.
Dayton Casting Co., Dayton, Ohio
Empire Foundry Co., Tulsa, Okla.
Florence Pipe Foundry & Machine Co., Florence, N. J.
Fulton Foundry & Machines Co., Inc., Cleveland, Ohio
General Foundry & Mfg., Flint, Mich.
Georgia Iron Works, Augusta, Ga.
Greenlee Foundries, Inc., Chicago, Ill.
Hamilton Foundry Inc., Hamilton, Ohio
Johnstone Foundries, Inc., Grove City, Pa.
Kanawha Manufacturing Co., Charleston, W. Va.
Kennedy Van Saun Mfg. & Eng. Corp., Danville, Pa.
Lincoln Foundry Corp., Los Angeles, Calif.
Oil City Iron Works, Corsicana, Texas
Palmyra Foundry Co., Inc., Palmyra, N. J.
The Henry Perkins Co., Bridgewater, Mass.
Pohlman Foundry Co., Inc., Buffalo, N. Y.
Rosedale Foundry & Machine Co., Pittsburgh, Pa.
Ross-Meehan Foundries, Chattanooga, Tenn.
Sonith Foundries of FMC, Indianapolis, Ind.
Standard Foundry Co., Worcester, Mass.
The Stearns-Roger Mfg. Co., Denver, Colo.
Vulcan Foundry Co., Oakland, Calif.
Washington Iron Works, Seattle, Wash.
Dorr-Oliver-Long, Ltd., Orillia, Ontario
Hartley Foundry Div., London Concrete Machinery Co., Ltd., Brantford, Ontario
Otis Elevator Co., Ltd., Hamilton, Ontario

MEEHANITE METAL CORPORATION, NEW ROCHELLE, NEW YORK

## · BETTER DESIGN
## · GREATER ECONOMY
## with LENAPE
## PRESSURE VESSEL ACCESSORIES

**Here are a few profitable new ideas that give pressure vessel designers and builders alike the ultimate in flexibility and economy:**



### SEAMLESS FLANGES AND EXTENSIONS

- Full ID opening
- Easy, low cost attachment
- Choice of 3 bodies (extensions) for optimum reinforcement and design flexibility
- Widest choice of materials

*See page 9 of Lenape General Catalog.*



### LENAPE DISHED COVERS

- Contoured for better appearance —less weight
- Cost less than blind flanges
- Ideal for mixer mounts, heaters, float controls, special connections, etc.

*See pages 48-49 of Lenape General Catalog.*



### LENAPE WEDGE MANWAY

- Eliminates bolts and yokes
- Easiest to open and close
- Most economical manway available

*See page 73 of Lenape General Catalog.*



### STUDDING OUTLETS

- Compact design with amazingly low silhouette — minimum clearance
- Inherent reinforcement
- Economical and easy to attach

*See pages 36-41 of Lenape General Catalog.*

**For details and specifications on the complete line of Lenape Pressure Vessel Accessories and Manways, write for 96-page General Catalog.**

Red Man Products

**LENAPE**

LENAPE HYDRAULIC PRESSING & FORGING CO.
DEPT. 112 WEST CHESTER, PENNSYLVANIA

For more information, turn to Reader Service card, circle No. 437



**HOEGANAES**

***manufacturer of IRON and STEEL POWDERS for***

**POWDER METALLURGY • CUTTING & SCARFING • CHEMICAL FIELD • PLASTIC INDUSTRY • ATOMIC ENERGY • WELDING ELECTRODES**

Your metal parts fabricator offers you a valuable powder metallurgy service — by working with you on your metal parts problems; or write us direct.

**HOEGANAES SPONGE IRON CORP.**

*Sales Office and Plant*
**RIVERTON, NEW JERSEY**

For more information, turn to Reader Service card, circle No. 570



## FOR TOP OF THE LINE MODELS




For more information, turn to Reader Service card, circle No. 422


# I-S SPRINGS of beryllium copper *can help you*


## IMPROVE YOUR PRODUCT'S QUALITY, REDUCE YOUR COST, INCREASE YOUR PRODUCTION

Instrument Specialties Company specializes in the design and custom manufacture of age-hardened alloy springs. With our specially developed processes and machines, our engineers are able to realize the fullest performance potential from the superior spring materials around which I-S service to designers and manufacturers has been developed.




## FOR HIGH PRODUCTION






### STRIP SPRINGS


Fabricated from beryllium copper.
Easily handled, readily broken apart by hand or used in automatic or semi-automatic assembling devices and contact riveting machines.
Individual pieces may be broken off without trace of burr.
Eliminate sorting, untangling and handling of loose pieces.
Springs may be produced in strips to various shapes; formed angles may be held within plus or minus one degree.
Heat treated in multiple fixtures to insure uniformity, close tolerances, and elimination of variations in spring-back.

### COIL SPRINGS

Made from laboratory tested beryllium copper wire. Special coiling and heat treating equipment insures 100% uniformity.
Guaranteed rigid tolerances held on diameter and load tests at specified deflection.
These factors combine to assure increased service life through higher endurance strength – make products perform more consistently by eliminating drift, set or fatigue. Furthermore, they eliminate expensive hand adjustment and reduce inspection costs of finished product.

## FOR LOW ACTIVITY





### HIGH FREQUENCY SPECIALTIES

We are equipped to supply standard mating parts for use with 2C-39, 2C-40, 2C-43 and 3C-37 tubes, or custom made parts in related fields.
Grounding strips and contact fingers can be supplied in standard or special contours.
"Flea" contacts for co-planer type subminiature tubes and transistors.

### SHORT-RUN SERVICE

For those who need quick delivery of parts in pilot quantities or require a low-cost proving ground for spring designs. I-S methods eliminate expensive tooling. Laboratory controlled, precision produced—yet at lower cost than is possible with permanent, high-activity tools.
We are equipped to handle conventional beryllium copper stampings and screw machine products in short runs or in high production.

"MICRO ... PROCESSED" I-S BERYLLIUM COPPER SPRINGS

### A COMPLETE ENGINEERING AND SAMPLE SERVICE


When your product is in the design stage, let us show you how I-S springs of beryllium copper may be designed to fit your needs. Ample stock, flexible facilities, short set-up time speed production of sample lots and trial orders.

## INSTRUMENT SPECIALTIES CO., INC.

224-A Bergen Boulevard — Little Falls, New Jersey

Telephone: CLifford 6-3500

For more information, turn to Reader Service card, circle No. 431



Actual size

# STEEL PARTS FROM POWDER METALLURGY

HI DENSITY

CARBURIZED

Take advantage of the highest quality powder metallurgy available today! If you use hobbed gears—or other structural parts—in quantity, Supermet Hi Density parts can save you big money. At a single pressing all of the gears above are produced 90% of theoretical solid, carburized conventionally, and given after-treatments such as plating (you can't do this with ordinary powder metal parts). Supermet makes gears up to 1.25 sq. in. cross-section to your specs in iron, alloy steel, carbon steel or stainless. We regularly work to ASTM B309-58T Class A and B densities. Because of our modern, fully equipped toolroom, we can readily fabricate and maintain your tooling.

GLOBE

SUPERMET DIVISION
GLOBE INDUSTRIES, INC.
1466 Cincinnati St.
Dayton 8, Ohio
*free technical literature*

POWDER METAL PARTS mpi INDUSTRIES FEDERATION

Supermet is often the "supplier of last resort"—we deliver on time those difficult powder metal parts on which others fail. Send a part print today for a prompt engineering analysis—take advantage of the strength of steel with the economy of powder metallurgy.

For more information, turn to Reader Service card, circle No. 474

RIGID AND flexible

# PLASTIC EXTRUSIONS

CRANE engineers solve intricate design problems and cut costs on precision extrusions — **rigid** or **flexible** — in a wide range of thermoplastics. CRANE in-plant material compounding and tooling save time and money. Write for brochure showing how CRANE plastic extrusions — **custom-made** or from **stock dies** — have been serving production manufacturers for fifteen years.

## CRANE PLASTICS, INC.

503 HUTTON PLACE
COLUMBUS 15, OHIO

**Find out how CRANE can help solve YOUR problems. Send prints or specifications.**



For more information, turn to Reader Service card, circle No. 497

# QUALITY CONTROLLED STAMPINGS



EXACTING TOLERANCES
Deep Drawn, Light and Medium


COPPER
BRASS
ALUMINUM
MONEL
STAINLESS
HIGH CARBON
ALLOY STEELS

BLANKING
PIERCING
FORMING
DRAWING
COINING
DRILLING
TAPPING
TESTING
SWEDGING
HEAT TREATING
ANNEALING
SILVER BRAZING
ASSEMBLING

*Write for free brochure—*


The Reichert **FLOAT & MANUFACTURING CO.**
2271 Snead Avenue • Toledo 5, Ohio
ESTABLISHED 1924

For more information, turn to Reader Service card, circle No. 488



**ALIRON® Copper-Base and Copper-Cored**


Three-layer and five-layer materials used for anodes in rectifier and amplifier tubes. Provide longer power output life . . . uniform heat dissipation . . . high electrical conductivity . . . improved anode reradiation . . . and reduce costs.




**COPPER CLAD KOVAR***


For thermal compression bonding of glass seals in transistor applications. Kovar matches expansion rate of glass . . . copper is used as heat sink. Heat transfer is improved . . . permits cold welding, instead of seam welds . . . reduce production time in packaging.

*REG. T. M. OF WESTINGHOUSE ELECTRIC CORP.



**RECTANGULAR WAVE GUIDE TUBING and COLLECTOR OR SLIP RINGS**

For transmission lines in electronic equipment. Seamless tubing made of gold or silver-lined copper or nickel alloys; carbon and stainless steel. Available to government MS90035 or customers specifications. Collector rings are fabricated from gold, silver, platinum, alloys and clad metals.



**TIN CLAD NICKEL**

An improved material for Germanium transistor base tabs, emitters and collector connectors. Pure tin or tin alloy inseparably bonded to electronic grade nickel eliminates voids and inclusions. Provides perfect wetting during soldering . . . improves performance . . . lowers costs.





**PLATINUM THERMOCOUPLE WIRE**

Pure platinum, 10% or 13% rhodium platinum wire in either standard or premium grade, calibrated to emf values established by National Bureau of Standards, available from stock. Supplied in commercial grade 99.8 or where requested to 99.999. Shipped spooled and packaged in dust-proof containers.





**COPPER-CORED GLASS SEALING WIRES**

Featuring a sound metallurgical bond, these wires give five to ten times greater conductivity (depending upon application) than solid 52 Alloy Wire of equal diameter . . . they facilitate miniaturization. Features include: leakproof seal between alloy and core, high electrical and thermal conductivity, lower costs.




**ALUMINUM-IRON ALLOYS**

For magnetic applications requiring low core losses and high permeability at low flux densities in current and pulse transformers, relays, gyro mechanisms, servomechanisms, missile guidance systems, etc.



**SOLID, CLAD and CORED WIRE**

Gold and silver and their alloys clad to copper and alloys, nickel and alloys, carbon and stainless steels. .003" diameter (min.) up to rod size 1" diameter. Applications include, electronic tubes, center conductors for coaxial cable, communications equipment, capacitors, resistors, etc.




**RHODIUM PLATING SOLUTIONS**

Used for industrial and decorative plating to provide brilliance, corrosion and tarnish protection. Services include: Analytical service for electroplating bath control, testing, consultation and laboratory analysis, bath analysis, and complete refinery facilities to reclaim contaminated solutions.

For more information, circle No. 491

## GENERAL PLATE CLAD METALS Solve Design Problems — Provide High Performance Reliability — Reduce Costs

General Plate Clad precious-to-base or base-to-base metals are inseparably bonded by a patented solid-phase bonding process without the use of brazing alloys or other intermediate material.

If you are seeking metals with useful characteristics that can't be found in a single metal or alloy, investigate clad metals. If you want stronger or lighter components — or better electrical and mechanical properties — or fewer corrosion problems — or if you are interested in conserving critical metals or reducing parts costs, you can profit by using General Plate Clad Metals.

Write for a General Plate Clad Base Metals catalog today. Or better yet, why not talk over your requirements with a competent field engineer? His knowledge of the applications of clad metals is yours for the asking. No obligation, of course.

**TEXAS INSTRUMENTS**
**INCORPORATED**
METALS & CONTROLS DIVISION
1660 FOREST STREET • ATTLEBORO, MASS.

**GENERAL PLATE PRODUCTS:** Clad Metals • Electrical Contacts • Truflex® Thermostat Metal • Gold, Silver, Platinum and other Precious Metal Products

for

# Custom Plastics Extrusions

consult

## YARDLEY



### TUBING

Special shapes or standard, rigid or flexible, in diameters from ½" to 16". Our engineers have developed advanced techniques that can save time and money on the right shape for your specific needs.

### SPECIAL SHAPES

We extrude any shape in a variety of formulations to meet a wide range of design and performance requirements. Our complete tool and die shop is staffed with skilled technicians. We maintain a library of more than 400 section dies, one of which may fit your product design.



### FABRICATED PARTS

We shape, flatten, curve, swedge, drill and perform other fabricating operations to make plastic parts ready for your production lines. Close tolerance, absolute uniformity, dimensional stability and high-gloss finish are standard production requirements at Yardley.



*Write for Bulletin 180 — and for prompt quotation send us your prints*

**YARDLEY PLASTICS CO.**
140 PARSONS AVE., COLUMBUS 15, OHIO

For more information, turn to Reader Service card, circle No. 490

# CONTACT Gibson FIRST

## FOR SPECIALIZED SKILL IN MAKING CONTACT ASSEMBLIES

- **EXPERIENCE** Gibson engineering knowhow in developing economical contact assemblies for your product is unsurpassed.
- **COMPLETE SERVICE** Gibson offers a complete line of contact materials, forms and assemblies to fill requirements of your product.
- **FLEXIBILITY** Gibson's versatility in adapting the right Gibsiloys or other contacts to your product—coupled with round-the-clock production—enables us to give you what you want . . . on time. Our one field is electrical contacts. Consult Gibson first about contacts.



*Write for GIBSON Catalog C-520 or see our catalog in Sweet's.*

Gibsiloy ELECTRICAL CONTACTS — *Manufactured by* GIBSON ELECTRIC COMPANY

Box 545, DELMONT, PA.


For more information, turn to Reader Service card, circle No. 535

# NOW...

## porous-metal components designed to meet your most rigorous specifications

This new booklet shows you how Mott *controlled porosity* of high-temperature metals gives you . . .

1. Complex shapes or flat stock
2. Wide range of high-temperature metals
3. Heat resistance from —450° to 1,800° F.
4. Tensile strength from 5,000 to 30,000 psi.
5. Uniform or differential permeability
6. Unprecedented control over pore size and pore distribution




Send for your copy today!

**MOTT METALLURGICAL CORP.**
272 Huyshope Ave., Hartford, Conn.

For more information, turn to Reader Service card, circle No. 548

# NOW! Stainless UNITCASTINGS!

**A Complete Range of Cast Steels . . . Carbon . . . Low Alloy . . . Heat Resistant and Corrosion Resistant (Stainless)**

Unitcast . . . one of America's most progressive foundries . . . completely mechanized for high quality steel castings at a lower *finished* cost. $CO^2$, Shell or Green sand processes make Unitcast facilities a versatile source for all types of steel castings. Check the range of specifications below for your specific requirements. Detailed brochures on request.



**CORROSION RESISTANT (STAINLESS)**

| CSTG | TYPE | C | Cr | Ni | Other | AISI | SAE |
|---|---|---|---|---|---|---|---|
| CA-15 | 12-1 | .15 max | 11.5-14.0% | 1% max | — | 414 | 51414 |
| CA-40 | 12-1 | .20-.40 | 11.5-14.0% | 1% max | — | — | — |
| CB-30 | 20-2 | .30 max. | 18.0-22.0% | 2% max | — | — | — |
| CC-50 | 28-4 | .50 max | 26.0-30.0% | 4% max | — | — | — |
| CE-30 | 28-10 | .30 max | 26.0-30.0% | 8-11% | — | — | — |
| CF-8 | 20-10 | .08 max | 18.0-21.0% | 8-11% | — | 308 | — |
| CF-20 | 20-10 | .20 max | 18.0-21.0% | 8-11% | — | — | — |
| CF-8M | 20-10 | .08 max | 18.0-21.0% | 9-12% | 2-3% Mo. | 316 | 30316 |
| CF-12M | 20-10 | .12 max | 18.0-21.0% | 9-12% | 2-3% Mo. | — | — |
| CF-8C | 20-11 | .08 max | 18.0-21.0% | 9-12% | 8xC min-1% max Cb (or) 10xC min-1.35% max Cb+Ta | 347-348 | 30347 |
| CF-16F | 20-10 | .16 max | 18.0-21.0% | 9-12% | 1.50% Mo. max-.20/.35% Se | 303 Se | — |
| CH-20 | 24-14 | .20 max | 22.0-26.0% | 12-15% | — | 309 | 30309 |
| CK-20 | 25-21 | .20 max | 23.0-27.0% | 19-22% | — | 310 | 30310 |

**HEAT RESISTANT**

| CSTG | TYPE | C | Cr | Ni | Other |
|---|---|---|---|---|---|
| HA | 9-0 | .20 max | 8.0-10.0% | — | .90-1.20% Mo. |
| HC | 28-4 | .50 max | 26.0-30.0% | 4% max | — |
| HD | 28-5 | .50 max | 26.0-30.0% | 4-7% | — |
| HE | 28-10 | .20-.50 | 26.0-30.0% | 8-11% | — |
| HF | 21-10 | .20-.40 | 19.0-23.0% | 9-12% | — |
| HH | 26-12 | .20-.50 | 24.0-28.0% | 11-14% | .20% N max |
| HI | 28-16 | .20-.50 | 26.0-30.0% | 14-18% | — |
| HK | 26-20 | .20-.60 | 24.0-28.0% | 18-22% | — |
| HL | 30-20 | .20-.60 | 28.0-32.0% | 18-22% | — |
| HN | 21-25 | .20-.50 | 19.0-23.0% | 23-27% | — |
| HT | 15-35 | .35-.75 | 13.0-17.0% | 33-37% | — |
| HU | 19-39 | .35-.75 | 17.0-21.0% | 37-41% | — |
| HW | 12-60 | .35-.75 | 10.0-14.0% | 58-62% | — |
| HX | 17-66 | .35-.75 | 15.0-19.0% | 64-68% | — |

**LOW ALLOY**

| | GRADE OF STEEL → | T-LOY 14 AISI-8625 | | T-LOY 42 AISI-8640 | |
|---|---|---|---|---|---|
| CHEMICAL ANALYSIS | CARBON | 0.30% – 0.38% | | 0.38% – 0.46% | |
| | MANGANESE | 0.70% – 0.90% | | 0.70% – 0.90% | |
| | SILICON | 0.60% MAXIMUM | | 0.60% MAXIMUM | |
| | NICKEL | 0.40% – 0.90% | | 0.90% – 1.10% | |
| | CHROME | 0.40% – 0.60% | | 0.60% – 0.80% | |
| | MOLYBDENUM | 0.11% – 0.25% | | 0.25% – 0.35% | |
| | PHOS & SULPHUR | 0.04% MAXIMUM | | 0.04% MAXIMUM | |
| | HEAT TREATMENT | NORM DRAW | OIL QUENCHED 1200° F. DRAW / 900° F. DRAW | NORM DRAW | OIL QUENCHED 1200° F. DRAW / 900° F. DRAW |
| PHYSICAL PROPERTIES | TENSILE STRENGTH P.S.I. | 90,000 | 105,000 / 150,000 | 100,000 | 120,000 / 175,000 |
| | YIELD POINT P.S.I. | 60,000 | 85,000 / 125,000 | 75,000 | 100,000 / 145,000 |
| | ELONGATION IN 2" | 22% | 17.0% / 10.0% | 12% | 12% / 10% |
| | REDUCTION OF AREA | 40% | 35.0% / 25.0% | 25% | 28% / 25% |
| | BRINELL HARDNESS | 187 MIN | 217-246 / 302-340 | 200-250 | 240 MIN / 350 MIN |

PHYSICAL PROPERTIES BASED ON .505" TEST BAR TURNED FROM A STANDARD 1¼" CAST TEST COUPON

**CARBON**

| | GRADE OF STEEL → | LOW CARBON AISI-1020 | MEDIUM CARBON AISI-1025 | MED.-HIGH CARBON AISI-1035 | HIGH CARBON AISI-1045 |
|---|---|---|---|---|---|
| CHEMICAL ANALYSIS | CARBON | 0.22% MAX. | 0.20-0.30% | 0.30-0.40% | 0.40-0.50% |
| | MANGANESE | 0.75% MAX.* | 0.75% MAX.* | 0.75% MAX.* | 0.75% MAX.* |
| | SILICON | 0.60% MAX. | 0.60% MAX. | 0.60% MAX. | 0.60% MAX.* |
| | PHOSPHORUS | 0.05% MAX. | 0.05% | 0.05% MAX. | 0.05% MAX. |
| | SULPHUR | 0.05% MAX. | 0.05% | 0.05% MAX. | 0.05% MAX. |
| PHYSICAL PROPERTIES | TENSILE STRENGTH | 60,000 PSI | 70,000 PSI | 75,000 PSI | 85,000 PSI |
| | YIELD POINT | 30,000 PSI | 38,000 PSI | 42,000 PSI | 53,000 PSI |
| | ELONGATION IN 2" | 24% | 24% MIN | 18% | 18% |
| | REDUCTION OF AREA | 35% | 36% | 30% | 30% |
| | BRINELL HARDNESS | 100-140 | 140-170 | 160-190 | 180-220 |
| IMPORTANT NOTES | LOW CARBON—Note: For each .01% Carbon below maximum, an increase of .04% Manganese will be allowed up to 1.00% Manganese. Residual alloys shall be controlled so as not to exceed at any time the following: Copper—.50%, Nickel—.50%, Chromium and Molybdenum—.25%, Tungsten—.10%. Total of all unspecified alloys not to exceed 1.00%. | | | | |
| | MEDIUM CARBON—Note: For each .01% Carbon below maximum, an increase of .04% Manganese will be allowed up to 1.00% Manganese. | | | | |
| | *MED.-HIGH CARBON—Note: For each .01% Carbon below maximum, an increase of .025% Manganese will be allowed over the maximum. | | | | |
| | *HIGH CARBON—Note: For each .01% Carbon below maximum, an increase of .025% Manganese will be allowed up to 1.00% Manganese. | | | | |

**LET UNITCAST ENGINEERS HELP ANALYZE YOUR REQUIREMENTS—WRITE, OR CALL TODAY!**

**Unitcast**

**SPECIFICATION STEEL CASTINGS**

**Unitcast Corporation**
**TOLEDO 9, OHIO**

**Canadian-Unitcast Steel, Ltd.**
**SHERBROOKE, QUEBEC**

**For more information, turn to Reader Service card, circle No. 482**

# SUPPLIERS' LITERATURE

## Joining and Fastening

**High Pressure Seals, Fasteners.** A. P. M. Co., 4 pp, illus., No. C. General information, military specifications and typical uses of a line of high pressure seals, boots and mechanical fasteners. **252**

**Sealing Compound.** American Marietta Co., Presstite Div., 2 pp, illus. Properties, uses and installation data for a sealing compound that performs well in an alternating freezing and thawing environment. **253**

**Sealant for Metal Parts.** American Sealants Co., 6 pp, illus. Properties, uses and application data for a liquid sealant used on metal parts. **254**

**Adhesives.** BB Chemical Co., Bostik Dept., 4 pp, illus. Characteristics, available types, typical uses, and advantages of a line of adhesives for bonding metals, plastics, fabrics, leather, glass and wood products. **255**

**Mechanical Fasteners.** Boots Aircraft Nut Corp., 8 pp, illus. Engineering data, specifications, sizes and other information on a line of inserts designed to provide screw threads for joining sheet metal, plastic and metal castings, and wood and composition materials. **256**

**Fluorocarbon Etchant.** Chemgineers, Inc., 2 pp, No. 369. Information on a solution used to prepare the surface of fluorocarbon plastics for bonding, including instructions on cleaning, methods of application and safety precautions. **257**

**Fast Setting Adhesive.** Eastman Chemical Products, Inc., subsidiary of Eastman Kodak Co., 4 pp, illus. Characteristics; advantages; mechanical properties; aging, chemical, and temperature resistance; typical applications; and other information on a fast setting adhesive. **258**

**Increasing Fatigue Life of Bolts.** Elastic Stop Nut Corp. of America, 32 pp, illus., No. 5930. Discussion of fatigue and its significance with respect to threaded high tensile fasteners, and methods of increasing and controlling fatigue life. **259**

**Silver Brazing.** American Platinum Div., Engelhard Industries, Inc. General information, characteristics, advantages, and typical uses of silver brazing. **260**

**Epoxy Adhesives, Coatings.** H. B. Fuller Co., 48 pp. Properties, characteristics, directions for use, and typical applications of epoxy adhesives, sealants and protective coatings. **261**

**Die Cast, Molded Fasteners.** Gries Reproducer Corp., 8 pp, illus., No. 2002. General information, properties, specifications, advantages, uses, and other information on a line of die cast zinc alloy and molded nylon fasteners. **262**

**Mechanical Fasteners.** Grip Nut Co., subsidiary of Heli-Coil Corp., 16 pp, illus. Characteristics, advantages, specifications, sizes, and other engineering data on a line of mechanical fasteners. Included is a price list. **263**

**Brazing Alloys.** Handy & Harman, 4 pp, illus., No. 80. Information on the use of silver brazing alloys for joining cast iron to steel, stainless steel, copper, brass, cemented carbides and monel. **264**

**Cold Headed Fasteners.** John Hassall, Inc., 18 pp, illus., No. 106. Information on cold headed monel, Inconel, steel and stainless steel rivets, nails, screws and threaded parts. **265**

**Mechanical Fasteners.** Huck Mfg. Co., 24 pp, illus. Driving cycles, strength data, typical applications, grip ranges, significant dimensional data, whole size recommendations and other information on a line of mechanical fasteners. **266**

**Adhesives.** Interchemical Corp., Finishes Div., 8 pp, illus., No. 7/in. General characteristics, formulations, and typical applications of a line of custom formulated adhesives. **267**

**Adhesives.** Dutch Brand Div., Johns-Manville Sales Corp., 10 pp, illus. Briefly describes the company's line of elastomeric adhesives for bonding a number of materials. Shows company facilities. **268**

**Welding Electrodes.** Lincoln Electric Co., 20 pp, illus, No. 7000.2. Information on arc welding electrodes for hard surfacing and for welding stainless steel, nonferrous metals and cast iron. **269**

**Silver Brazing Preforms.** Lucas-Milhaupt Engineering Co., brazing handbook. Advantages, available types and shapes, silver and aluminum alloy calculation chart, discussions of soft solders and fluxes, and other information on silver brazing preforms. **270**

**Self-Locking Nuts.** Mac Lean-Fogg Nut Co., 8 pp, illus., No. 7-Ma. Properties, uses and dimensions of self-locking nuts. **271**

**Structural Adhesives.** Minnesota Mining & Mfg. Co., Adhesives, Coatings & Sealers Div., 900 Bush Ave., St. Paul 6, Minn., 16 pp, illus. Information on design, bonding and use of a line of structural adhesives. Included are properties, curing data, joint design and case histories illustrating how adhesives solve structural assembly problems. Write directly to Minnesota Mining on company letterhead.

**Mechanical Fasteners.** National Machine Products Co., 8 pp, illus. Information on sizes, uses and advantages of a line of mechanical fasteners. **273**

**Adhesives, Coatings.** Raybestos-Manhattan, Inc., Adhesives Dept., 16 pp, illus., No. 700. Properties and uses of adhesives, coatings and sealers. **277**

**Screw Fastening Aluminum.** Reynolds Metals Co., 48 pp, illus., No. 802-203. Information on various types of standard and special fasteners and fastening systems used to join aluminum assemblies. **278**

**Lock Screw Fasteners.** Russell, Burdsall & Ward Bolt & Nut Co., 3 pp, illus. Advantages and dimensions of spin-lock screws. **279**

**Socket Head Cap Screws.** Set Screw & Mfg. Co., 4 pp, illus. Dimensional standards, tolerances, sizes, uses, characteristics, and advantages of socket head cap screws. **280**

**Fastener Catalog.** Simmons Fastener Corp., 44 pp, illus. Dimensional drawings, specifications, characteristics, advantages, and applications of a line of mechanical fasteners. **281**

**Brazing Stainless Steel.** Stalker Corp., 4 pp, illus. High temperature, copper hydrogen, and silver brazing of stainless and high strength alloy steels. **282**

**Screw Thread Root Design.** Standard Pressed Steel Co., 20 pp, illus. Discusses shape at the root of screw threads as a function of tension bolt failures, and describes how to avoid such failures. **283**

**Fastening Analysis.** Tinnerman Products, Inc., 4 pp, illus., No. 336. Describes a fastening analysis service for reducing costs and speeding production of such products as washing machines, toys, and automobiles. **284**

**Methods for Joining Metals.** Linde Co., Div. of Union Carbide Corp., 36 pp, illus. Discusses various welding techniques for joining ferrous and nonferrous metal parts such as tanks, railroad cars, condensers and bulldozers. **285**

**Epoxy Pellets.** Epoxy Products, a Div. of Joseph Waldman & Son. Information on the use of epoxy pellets for sealing, encapsulating, embedding, impregnating, potting, bonding, and ruggedizing. **287**

**Brazing Alloys.** Wall Colmonoy Corp., Brazing Alloys, 4 pp, illus., No. SD-23. Information on a line of nickel-chromium-boron high temperature brazing alloys. **288**

**Nylon Screws.** Weckesser Co., 3 pp, illus. Advantages, characteristics, uses and installation data for black nylon screws and nuts. **289**

*To get literature, use free post cards on pp 585-592*

# Joining and Fastening of Materials


PAGE

470 Joinability of Materials

472 Brazing and Soldering Alloys

476 Welding Electrodes and Rods

484 Adhesives

487 Mechanical Fasteners

492 Advertisements

468 Suppliers' Literature

## Joinability of Materials[a]

| Material ↓ | Arc Welding | Oxyacetylene Welding | Resistance Welding | Brazing | |
|---|---|---|---|---|---|
| Cast Iron | Common by shielded metal arc where ductile weld not required | Rec with cast iron rods; braze welding if no corr or thermal stress | Seldom; if used, flash welding preferred | Dfclt; easiest for quality-controlled and Ni-cont types | |
| Carbon and Low Alloy Steels | Rec for low carbon and low alloy, common for medium, dfclt for high; all processes | Rec with rods of same comp for low carbon, low alloy; incr C makes more dfclt | Rec for low carbon and low alloy; flash and upset used as C incr dfclt | Rec for low, medium carbon; dfclt for high; seldom for heat treated alloy steels | |
| Stainless Steel | Rec for 200 and 300 series, common for 400 series; all processes[b] | Common for thin gages, dfclt for thicker | Rec for 300 series; 400 series susceptible to hardening | Rec with silver brazing alloys[b] | |
| Aluminum, Magnesium | Common by inert gas; Al slightly easier than Mg | Common for Al <1 in., Mg & M1 alloy; others dfclt | Common; Mg more dfclt, though spot welding used | Common for Al alloys and Mg alloy M1 | |
| Copper and its Alloys | Common by inert gas; electrolytic Cu joints not high str | Common for most; seldom for phosphor and aluminum bronzes | Common by upset or modified flash upset methods | Rec for Cu and high Cu brasses; ease with bronzes varies widely | |
| Nickel and its Alloys | Rec for Ni, monel, Inconel; all processes | Common for Ni, monel, Inconel | Rec for most; Inconel X dfclt | Rec | |
| Titanium | Common by inert gas | No | Common by spot and flash welding | Difficult | |
| Lead, Zinc | Common for lead by inert gas; no for zinc | Common | Dfclt for zinc, but spot and seam used; no for lead | No | |
| Thermoplastics | (Heated tool welding.) Rec for acrylic sheet, common for most TP sheet | (Hot gas welding.) Rec for polyethylene, PVC; common for other TP's | (Induction welding.) Common for polyethylene, acrylic; metal insert remains integral | No | |
| Thermosets | No | No | No | No | |
| Elastomers | No | No | No | No | |
| Ceramics | No | Seldom | No | No | |
| Glass | Seldom | (Blow torch.) Common | No | No | |
| Wood | No | No | No | No | |
| Leather | No | No | No | No | |
| Fabric | No | No | No | No | |
| Dissimilar Metals | Dfclt; used where melting points are within about 50 °F; galvanic action danger | Dfclt; used when melting points are within about 50° F; galvanic action danger | Dfclt; special procedures because of different thermal prop.; galvanic action danger | Ranges from dfclt to common depending on deg of dissimilarity | |
| Metals to Nonmetallics | No | No | No | No | |
| Dissimilar Nonmetallics | (Hot gas welding.) Dfclt; used on TP's of same basic type | (Hot gas welding.) Dfclt; used on TP's of same basic type | No | No | |
| Dissimilar Thicknesses | Common | Common | Common | Rec | |

[a] Abbreviations used in the table: TP = Thermoplastic. TS = Thermosetting. Elast = Elastomeric. Rec = Recommended; easily accomplished with excellent results. Common = Commonly and widely used, though some care may be necessary. Dfclt = Difficult; special precautions, equipment, etc., necessary. Seldom = Can be done with more or less difficulty, but not common for one reason or another. No = Not used; impossible or highly specialized case if ever used.

[b] The 300 series requires post weld heat treatment if subjected to corrosive environments.

| | Soldering | Adhesive Bonding (TS, TP, Elast) | Adhesive Bonding (modified compounds) | Threaded Fastening | Riveting and Metal Stitching |
|---|---|---|---|---|---|
| | Seldom; graphite and high silicon content prevent bonding | Common with TS, seldom with TP | Common with epoxy 100% solids; dfclt with solvent-dispersed phenolic | Common; esp self-tapping, also integrally cast studs, hooks, etc. | Rec with large solid rivets in structural uses |
| | Dfclt for lower carbon; seldom for higher carbon | Common with TS, seldom with TP | Common with epoxy 100% solids in paste form | Rec with all types; most fasteners made of same mtls | Rec with solid rivets for high shear, medium ten str uses |
| | Common for 300 series with high tin solders; dfclt for 400 series | Common with TS, seldom with TP | Common with epoxy 100% solids in paste form | Rec with bolts and nuts, common with others | Common with solid stainless steel rivets for high shear str uses |
| | Seldom; special solders available | Rec with TS, common with others, but no alkaline adh | Rec with all types | Common with self-tapping screws, inserts, others | Common with small solid aluminum rivets, or semi-tubular where low stress |
| | Rec for copper, brass, bronze in that order | Common with TS, seldom with TP, but no natural rubber adh | Common with epoxy 100% solids as paste or film | Common with fasteners available in similar mtls | Common with small solid copper alloy rivets, seldom with semi-tubular |
| | Common with high tin solders or others rel non-corr | Common with TS, seldom with TP | Common with epoxy 100% solids as paste or film | Rec with fasteners available in similar mtls | Common with small solid nickel alloy rivets, seldom with semi-tubular |
| | Seldom | Seldom with TS, no TP | Common with epoxy 100% solids, heat and pressure-cured | Common; some Ti fasteners available | No |
| | Rec with low melting solders | Rec with TS, TP, Elast in that order | Rec with all types | Rec with self-tapping screws, inserts, special fasteners | Rec with semi-tubular or split rivets, seldom with solid |
| | No | Common with Elast for cryst types; solvent selection care nec to avoid crazing | Seldom; phenolic-Buna N most used | Seldom; inserts are used, also special fasteners | Rec with tubular rivets; stitching common (limited thk) |
| | No | Common with TS; solvent selection care nec to avoid crazing | Common with modified epoxies on TP–TS compounds | Common with self-tapping screws, elevator bolts, inserts | Rec with semi-tubular rivets |
| | No | Rec with phenolic, epoxy and neoprene adhesives | Common with epoxy-polysulfide, phenolic-elastomers | Seldom; inserts are used, also special fasteners | Rec with tubular or split rivets; stitching common |
| | No | Rec with epoxy, common with other TS adhesives exc ureas | Rec with vinyl-phenolics, modified epoxies, phenolic-elastomers | Common with nuts, washers and bolts, esp load-indicating types | Seldom; semi-tubular rivets used |
| | No | Rec with TS, common with Elast | Rec with vinyl-phenolics, phenolic-elastomers | Common with plastics fasteners, seldom with elevator bolts | Seldom; TP semi-tubular rivets used |
| | No | Rec; phenolic for soft plywood, melamine-urea for laminations, PVC for furniture | Rec with solvent-dispersed phenolic-elastomers, latex emulsions | Rec with wood and lag screws, self-tapping screws, inserts, dowels, etc. | Common. Semi-tubular rivets for hard woods, tubular rivets for soft |
| | No | Rec with Elast, common with TS | Rec with asphalt and latex emulsions, solvent dispersions | Seldom | Rec with tubular and split rivets, and stitching or stapling |
| | No | Rec with Elast, polyvinyl acetate and cellulosic adh | Rec with asphalt and latex emulsions | Seldom | Rec with split rivets, stitching |
| | Rec except where galvanic corr must be considered | Rec with TS exc solvent-dispersed types | Rec with epoxy 100% solids | Common but galvanic action may be a danger | Common although galvanic action is a danger |
| | No | Rec. TP for shear str; TS Elast for peel str | Rec with solvent-dispersed phenolic-elastomers | Common using self-tapping screws, inserts, special fasteners | Rec with self-tapping screws, inserts, stitching |
| | No | Rec; type varies with porosities being joined | Rec; type varies with porosities being joined | Seldom | Rec with lag screws, stitching, special fasteners |
| | Rec | Rec where load is not peel | Rec with all types | Rec, esp bolts | Rec, esp stitching |

# Brazing and Soldering Alloys

### Classification

Unlike welding filler metals, these alloys melt at lower temperature than the metals being joined —brazing alloys above 800 F, soldering alloys below.

**Brazing Alloys.** Alloys are classified by chemical composition. The two most common groups are silver alloys and copper and copper alloys. All must melt and flow freely at a lower temperature than the metals being joined, adhere to the surfaces being joined, and not oxidize or volatize too freely.

**Brazing fluxes.** Choice of the proper brazing flux is extremely important. Fluxes minimize oxidation, dissolve oxides that may have formed, and promote free flowing of the filler metal. A great number of proprietary fluxes are available, each with specific recommendations for use. Most of them can be classified as high temperature (above 1500 F), general-purpose low-temperature, or special purpose.

**Soldering alloys.** The most widely used soft solders are those composed of tin and lead, with or without other minor alloying elements. Other types include lead-silver, silver-tin-lead, bismuth-tin-lead, indium-bearing and aluminum solders.

**Soldering fluxes.** The most important factor in producing a sound soldered joint is the proper choice and use of a flux. The many available fluxes can be classified in two groups—corrosive and noncorrosive.

### Brazing and Soldering Methods

Similar methods of heating are used for brazing and soldering. However, the furnace and salt dip methods are seldom used for soldering, and the soldering iron is not used for brazing. The most common methods use:

**Soldering iron.** The "iron" has a copper tip which is generally heated electrically. It is used mostly for electrical connections.

**Torch.** Oxyacetylene, oxyhydrogen or other gas flame torches are widely used for repair work.

**Induction heating.** Parts are assembled in a fixture which positions them inside an induction coil. Advantageous for large quantities of small parts.

**Electric block.** Similar to resistance welding with lower current. Used for small electrical parts.

**Salt dip.** Brazing alloy is preloaded into the work and parts are dipped into molten salt bath. Advantageous for dissimilar thicknesses and aluminum.

**Metal dip.** Parts are dipped in bath of molten brazing or soldering alloy. Used for irregular shapes.

**Furnace.** Brazing alloy is preloaded into work (usually held in jigs) which is then heated to brazing temperature in a controlled atmosphere furnace. Economical for large volumes of work.

### Design Factors

**Comparisons.** Though brazed joints are not as strong as welded, the lower temperatures required are advantageous in that the process is faster, is performed more economically, and results in less distortion. Soldered joints are not recommended where any stress will be applied.

**Joint design.** Three basic types of joints are used in brazing: butt, scarf and lap. Lap joints are preferred where maximum strength is preferred. Butt joints are not recommended for soldering.

**SOLDERING FLUXES**

| Flux ↓ | Characteristics | Uses |
|---|---|---|
| Rosin | Noncorrosive, nonconducting, nonhygroscopic | Electrical |
| Tallow | Very mildly corrosive | Lead, brass, clean copper |
| Olive Oil or Gallipoli Oil | Very mildly corrosive | Pewter, block tin |
| Stearic Acid | Mildly corrosive, almost nonconductive | Electrical, lead |
| Aniline Phosphate or Aniline Chloride | Mildly corrosive, almost nonconductive | Electrical |
| Lerulinic Acid in Alcohol | Mildly corrosive, almost nonconductive | Tin cans |
| Lactic Acid, Phthalic Acid and Phosphoric Acid Mixed with Tallow, Resin, etc. | Mildly corrosive, slightly conductive | Electrical |
| Zinc Chloride | Corrosive | Iron, steel, zinc, copper, brass, bronze; terne and lead plate |
| Zinc Chloride and Hydrochloric Acid | Corrosive | Stainless steel, nickel, monel |
| Zinc Chloride and Hydrofluoric Acid | Corrosive | Brasses and bronzes containing aluminum, silicon and manganese |
| Orthophosphoric Acid | Corrosive | High tensile manganese bronze |
| Numerous Proprietary Pastes Usually Containing Zinc Chloride | Corrosive | — |
| Zinc Chloride and Ammonium Chloride | Corrosive | Iron, zinc, copper, brass, bronze |
| Dilute Hydrochloric Acid | Corrosive | Dirty zinc |
| Fused Salts of Zinc Chloride and Ammonium Chloride | Corrosive | Dipping method |

### Definitions

**Eutectic.** An alloy which has a melting *point* and not a *range*.

**Liquidus.** The lowest temperature at which the alloy is completely liquid.

**Melting range.** The range from the liquidus to the solidus temperature.

**Solidus.** The temperature at which the alloy begins to melt.

## TYPICAL SOFT SOLDERS

| ASTM Type ↓ | Nominal Composition | Solidus, F | Liquidus, F | Spec Grav | Ten Str, 1000 psi | Applications |
|---|---|---|---|---|---|---|
| **TIN-LEAD ALLOYS** | | | | | | |
| 70A, 70B... | Sn 70, Pb 30, Sb 0.12–0.50..... | 361 | 378 | 8.32 | 6.8 | Soldering Zn-coated ferrous metals; coating metals |
| ..... | Sn 62, Pb 38..... | 361 | 361 | — | — | General purpose; eutectic al oy |
| 60A, 60B... | Sn 60, Pb 40, Sb 0.12–0.50..... | 361 | 374 | 8.65 | 6.4 | General purpose, esp where temp needs critical |
| 50A, 50B... | Sn 50, Pb 50, Sb 0.12–0.50..... | 361 | 421 | 8.85 | 5.9 | General purpose; most commonly used for iron, steel, Cu alloys, Zn. Domestic plumbing |
| 45A, 45B... | Sn 45, Pb 55, Sb 0.12–0.50..... | 361 | 441 | 8.97 | — | Auto radiator cores, roofing seams |
| 40A, 40B... | Sn 40, Pb 60, Sb 0.12–0.50..... | 361 | 460 | 9.3 | 5.8 | Wiping lead pipes, cable sheaths. Auto radiator cores, galvanized iron and Zn heating units |
| 35A, 35B... | Sn 35, Pb 65, Sb 0.25–0.50..... | 361 | 477 | 9.5 | — | General purpose; wiping solder |
| 30A, 30B... | Sn 30, Pb 70, Sb 0.25–0.50..... | 361 | 491 | 9.7 | 5 6 | Machine, torch, dip, wiping methods |
| 25A, 25B... | Sn 25, Pb 75, Sb 0.25–0.50..... | 361 | 511 | 10.00 | — | Machine, torch methods |
| 20B..... | Sn 20, Pb 80, Sb 0.5..... | 361 | 531 | 10.20 | 5.3 | Joining metal parts $<\frac{1}{4}$ in. thk; filling dents or seams in auto bodies; coating metals |
| 15B..... | Sn 15, Pb 85, Sb 0.50..... | 361 | 550 | 10.50 | — | Joining, coating; tinning auto bodies |
| 10B..... | Sn 10, Pb 90, Sb 0.50..... | 361 | 570 | 10.80 | — | Joining, coating |
| 5A, 5B..... | Sn 5, Pb 95, Sb 0.12–0.50..... | 518 | 594 | 11.30 | 3.4 | Joining and coating, esp at high temp to 250 F |
| **TIN-LEAD-ANTIMONY ALLOYS*** | | | | | | |
| ..... | Sn 94, Pb 0.2, Sb 4–6..... | 450 | 464 | — | — | General purpose |
| 40C..... | Sn 40, Pb 58, Sb 1.8–2.4..... | 365 | 448 | 9.23 | — | Same as 50A, 50B |
| 35C..... | Sn 35, Pb 63.2, Sb 1.6–2.0..... | 365 | 470 | 9.44 | — | General purpose; wiping |
| 30C..... | Sn 30, Pb 68.4, Sb 1.4–1.8..... | 364 | 482 | 9.65 | — | Torch, machine methods |
| 25C..... | Sn 25, Pb 73.7, Sb 1.1–1.5..... | 364 | 504 | 9.96 | — | Same as above |
| 20C..... | Sn 20, Pb 79, Sb 0.8–1.2..... | 363 | 517 | 10.17 | — | Machine soldering and coating; tipping |
| **TIN-LEAD-INDIUM ALLOYS** | | | | | | |
| ..... | Sn 37.5, Pb 37.5, In 25.0..... | 274 | 358 | — | — | Where res to strong alk soln needed (high cost) |
| **SILVER-LEAD AND SILVER-CADMIUM ALLOYS** | | | | | | |
| 2.5 S..... | Sn 0, Pb 97.5, Sb 0.40, Ag 2.3–2.7. | 579 | 579 | 11.35 | 5.0 | Cu, brass and similar metals with torch heating. Suitable for high temp but not for humid environ. |
| 1.5S..... | Sn 1, Pb 97.5, Sb 0.40, Ag 1.3–1.7. | 588 | 588 | 11.28 | — | Cu, brass and similar metals with torch heating. Sealing tin cans. High temp use |
| ..... | Ag 5, Cd 95..... | 640 | 750 | — | — | High temp use |
| **CADMIUM-ZINC AND LEAD-CADMIUM-ZINC ALLOYS** | | | | | | |
| ..... | Pb 90, Cd 8, Zn 2..... | 410 | 530 | — | — | Zn and galvanized parts |
| ..... | Cd 82.5, Zn 17.5..... | 508 | 508 | — | — | Zn-base die castings; high temp |
| **LOW MELTING ALLOYS (BISMUTH-CONTAINING)** | | | | | | |
| ..... | Bi 56, Pb 22, Sn 22..... | 203 | 220 | — | — | Special uses where low mp needed in soldering or svc |
| ..... | Bi 67, Pb 16, Sn 17..... | 203 | 300 | — | — | Same as above |
| ..... | Bi 40, Sn 60..... | 281 | 338 | — | — | Same as above |
| ..... | Bi 42.5, Pb 32.7, Sn 11.3, Cd 8.5. | 158 | 194 | — | — | Same as above |
| ..... | Bi 58, Sn 42, Zn 4..... | 266 | 266 | — | — | Same as above |
| **ALLOYS FOR SOLDERING ALUMINUM** | | | | | | |
| ..... | Sn 55–70, Zn 30–45..... | 630 | — | — | — | Range of special alloys for Al; also used on Mg |
| ..... | Sn 75, Zn 25..... | 401 | 500 | — | — | Soldering capacitors to Al sheets |
| **ALLOYS FOR SOLDERING MAGNESIUM** | | | | | | |
| ..... | Sn 60, Zn 40..... | 630 | — | — | — | Magnesium |
| ..... | Cd 60, Zn 30, Sn 10..... | 315 | — | — | — | General purpose |
| ..... | Cd 90, Zn 10..... | 500 | — | — | — | Magnesium |

* Not recommended for use on galvanized iron, cadmium or zinc parts.

*continued on next page*

## Brazing and Soldering Alloys

**BRAZING FILLER METALS**

| AWS-ASTM Class ↓ | Major Composition % | Available Forms | Solidus, F | Liquidus, F | Special Factors |
|---|---|---|---|---|---|
| **ALUMINUM-SILICON** | | | | | |
| BAlSi-1 | Si 4.0–6.0, Al bal | Strip, wire, rod | 1070 | 1165 | — |
| BAlSi-2 | Si 6.8–8.2, Al bal | Coated sheet | 1070 | 1135 | Only as coating on 3003, 5951 |
| BAlSi-3 | Si 9.3–10.7, Cu 3.3–4.7, Al bal | Strip, wire, rod | 970 | 1085 | — |
| BAlSi-4 | Si 11.0–13.0, Al bal | Strip, wire, powder | 1070 | 1080 | Highly corr res |
| **COPPER-PHOSPHORUS** | | | | | |
| BCuP-1 | P 4.75–5.25, Cu bal | Strip, wire | 1305 | 1650 | More ductile than others; less fluid |
| BCuP-2 | P 6.75–7.50, Cu bal | Rod | 1305 | 1485 | Very fluid |
| BCuP-3 | P 6.00–6.50, Ag 4.75–5.25, Cu bal | Wire, rod, powder | 1195 | 1500 | Very fluid |
| BCuP-4 | P 6.75–7.80, Ag 5.75–6.25, Cu bal | Rod, powder | 1185 | 1380 | — |
| BCuP-5 | P 4.75–5.25, Ag 14.50–15.50, Cu bal | Strip, wire, rod, powder | 1185 | 1500 | Suitable where close fits cannot be held |
| **SILVER** | | | | | |
| BAg-1 | Ag 44–46, Cu 14–16, Zn 14–18, Cd 23–25 | Strip, wire, rod, powder | 1125 | 1145 | Free flowing, narrow melting range |
| BAg-2 | Ag 34–36, Cu 25–27, Zn 19–23, Cd 17–19 | | 1125 | 1295 | Free flowing, broader melting range than above |
| BAg-3 | Ag 49–51, Cu 14.5–16.5, Zn 13.5–17.5, Cd 15–17, Ni 2.5–3.5 | | 1195 | 1270 | Good wetting action on carbide; wide melting range; good corr res |
| BAg-4 | Ag 39–41, Cu 29–31, Zn 26–30, Ni 1.5–2.5 | | 1240 | 1435 | Same as above, but freer flowing |
| BAg-5 | Ag 44–46, Cu 29–31, Zn 23–27 | | 1250 | 1370 | Wets, flows well; malleable, ductile |
| BAg-6 | Ag 49–51, Cu 33–35, Zn 14–18 | | 1270 | 1425 | Same as above; low elec res, high ductility |
| BAg-7 | Ag 55–57, Cu 21–23, Zn 15–19, Sn 4.5–5.5 | | 1145 | 1205 | Less stress corr cracking on stainless, some Ni alloys |
| BAg-8 | Ag 71–73, Cu 27–29 | | 1435 | 1435 | Free flowing except on ferrous metals |
| BAg-9 | Ag 64–66, Cu 19–21, Zn 13–17 | | 1280 | 1325 | — |
| BAg-10 | Ag 69–71, Cu 19–21, Zn 8–12 | | 1335 | 1390 | — |
| BAg-11 | Ag 74–76, Cu 21–23, Zn 2.5–3.5 | | 1365 | 1450 | — |
| **COPPER-GOLD** | | | | | |
| BCuAu-1 | Au 37.25–37.75, Cu bal | Strip, wire | 1775 | 1815 | [f] |
| BCuAu-2 | Au 79.75–80.25, Cu bal | Strip, wire | 1620 | 1630 | [f] |
| **COPPER** | | | | | |
| BCu | Cu 99.90 min | Strip, wire, rod | 1980 | 1980 | Free flowing |
| **COPPER-ZINC** | | | | | |
| BCuZn-1 | Cu 58.0–62.0, Zn bal | Strip, wire, rod | 1650 | 1660 | Free flowing; mod str |
| BCuZn-2 | Cu 57.0 min, Sn 1.0, Zn bal | Strip, wire, rod | 1630 | 1650 | Free flowing; higher str than above |
| BCuZn-3 | Cu 56.0 min, Sn 1.10, Mn 1.0, Ni 1.0, Zn bal | Strip, wire, rod | 1590 | 1630 | Used for capillary brazing |
| BCuZn-4 | Cu 50.0–55.0, Zn bal | Grain | 1570 | 1595 | Low mp; somewhat brittle |
| BCuZn-5 | Cu 50.0–53.0, Sn 3.0–4.5, Zn bal | Grain | 1585 | 1610 | Used for capillary brazing |
| BCuZn-6 | Cu 46.0–50.0, Ni 9.0–11.0, Zn bal | Strip, wire, rod | 1690 | 1715 | Generally used to make V fillet |
| BCuZn-7 | Cu 46.0–48.0, Ni 10.0–11.0, Ag 0.30–1.0, Zn bal | Strip, wire, rod, powder | 1685 | 1710 | High mp; good color match |
| **MAGNESIUM** | | | | | |
| BMg | Al 8.3–9.7, Zn 1.7–2.3, Mg bal | Wire, rod | 770 | 1110 | Good corr res; high str, ductility |
| **HEAT RESISTING MATERIALS** | | | | | |
| BNiCr | Ni 65–75, Cr 13–20, B 2.75–4.75[b] | Strip, wire, powder | 1850 | 1950 | Retains prop. to 2000 F |
| BAgMn | Ag 84–86, Mn 14–16 | Strip, wire, rod | 1760 | 1780 | Good str at 500–900 F |

[a] Immersion in 10% sulfuric acid restores copper color.
[b] BCuP-1: particularly resistance, and some furnace brazing.
[c] Lap and tee; strong, ductile joint; shear strength 20–30,000 psi.
[d] BAg-7 particularly for furnace brazing.
[e] All ferrous and nonferrous metals except Al, Mg, Ti and other metals melting below 1500 F. BAg-9, 10, 11 are used together for step brazing.

| Brazing Methods | Brazing Temp Range, F | Flux | Nature of Joint | Color of Braze | Uses |
|---|---|---|---|---|---|
| Furnace, dip | 1150–1185 | ↑ | Lap. Clearance <0.010 in. for laps <¼ in. long; but >0.025 in. for longer laps | Gray | Wrought Al alloys: 1100, 3003, 3004, 5050, 6951, 6053, 6061, 6062, 6063. Cast Al alloys: A612, C612 |
| Furnace | 1120–1140 | Essential | | Gray | |
| Furnace, dip | 1060–1185 | | | Gray | |
| Torch, dip, furnace | 1090–1185 | ↓ | | Gray | |
| ↑ | 1450–1700 | ↑ | Clearance: 0.002–0.005 in.[e] | Lt Gray[e] | Cu, Cu alloys; limited use for Ag. |
| | 1350–1550 | Self-fluxing on copper; flux rec on other metals | Clearance: 0.001–0.003 in.[e] | Lt Gray | W, Mo. Do not use on ferrous alloys containing more than 10% Ni. Not rec for sulfurous atm above room temp |
| All methods[b] | 1300–1550 | | Clearance: 0.002–0.005 in.[e] | Lt Gray | |
| | 1300–1500 | | Clearance: 0.001–0.003 in.[e] | Lt Gray | |
| ↓ | 1300–1500 | ↓ | Clearance: 0.003–0.005 in.[e] | Lt Gray | |
| ↑ | 1145–1400 | ↑ | ↑ | Lt Yellow | Unstabilized types of stainless[e] |
| | 1295–1550 | | | Lt yellow | Where tolerances cannot be as closely controlled[e] |
| | 1270–1500 | | | Whitish yellow | Joining carbide tool tips to tool shanks[e] |
| | 1435–1650 | | Lap rec; butt sometimes used. Clearances 0.002–0.005 in. Fatigue str about that of metals being joined (to 27,000 psi). Tough, ductile, high impact str; ten str, 50–60,000 psi | Lt yellow | Carbide tip brazing[e] |
| | 1370–1550 | Required unless brazing is done in vacuum or inert atm | | Lt yellow | Elec equip.; food and dairy equip. where Cd-containing alloys might be prohibited[e] |
| All methods[d] | 1425–1600 | | | Lt yellow | Same as above |
| | 1205–1400 | | | Whitish | Food and dairy equip.[e] |
| | 1435–1650 | | | White | Assembling electronic tubes[e] |
| | 1325–1550 | | | Whitish | Particularly with sterling silver[e, f] |
| | 1390–1600 | | | Whitish | Same as above |
| ↓ | 1450–1650 | ↓ | ↓ | Whitish | Same as above |
| Induction, furnace, resistance | 1815–2000 | None[g] | — | Copperish | Special alloy for joining parts in electron tube assemblies |
| Same as above | 1630–1850 | None[g] | — | Copperish | Same as above |
| Furnace[h] | 2000–2100 | None[i] | Clearance: 0.000–0.002 in.[j] | Yellow | Ferrous metals; Ni and Cu-N alloys |
| Torch, furnace, induction | 1670–1750 | ↑ | ↑ | Yellow | Steels, Ni and Cu alloys |
| " | 1670–1750 | | | Yellow | Same as above |
| " | 1670–1750 | | | Yellow | Same as above |
| " | 1600–1700 | Required; borax-boric acid commonly used | Lap, butt; clearances 0.002–0.005 in. High str in shear and tension | Pale yellow | Steels, Ni alloys |
| " | 1620–1700 | | | Grayish yellow | Same as above |
| All methods | 1720–1800 | | | Gray | Same as above |
| All methods | 1690–1800 | ↓ | ↓ | Gray | Same as above |
| Torch, furnace, dip; sometimes others except resistance | 1120–1160 | Req; fluxes contain KCl, NaCl, some fluorides | Lap; clearances 0.004–0.010 in. | Gray | Mg alloy M1A |
| Furnace, generally using controlled dry $H_2$ atm | 2000–2150 | None in red. atm; otherwise necessary | Variable | Gray | Stainless steels, high Ni alloys; jet engines |
| Same as above | 1780–2100 | Same as above | Variable | Gray | Stainless steels, high Ni alloys; lower temp than BNiCr |

[f] Variation in brazing temp permits step brazing.
[h] Using $H_2$ or dissociated ammonia atmosphere.
[j] Otherwise same nature as CuZn alloys.
[g] In reducing atmosphere or vacuum; otherwise borax-boric acid flux.
[i] Except on metals with oxide constituents.
[k] Total Fe + Si + C = 10% max.

## Welding Electrodes and Rods

### Classification

Welding rods and electrodes are generally grouped broadly according to the major metal (or metals) of which they are composed. Some are also grouped by the metals which they are used to weld. (These two classifications are often identical because it is usually desirable to weld base metals with a filler metal of similar composition.) A few groups of rods and electrodes are also defined by the welding method with which they are used.

Each broad group of rods and electrodes is further classified according to one or more of the following factors: chemical composition; coating, current and welding position; mechanical properties; appearance of the weld; intended end use. The key chart below is designed to indicate the method of classifying

**EXPLANATION OF AWS-ASTM ROD AND ELECTRODE CLASSIFICATION NUMBERS**
**(And Key to the Charts in This Welding Section)**

| Electrode or Rod Group ↓ | AWS-ASTM Spec | Sample Class No.[a] | Type of Specified Conditions Indicated by Class No.[b] | See Table No. . . |
|---|---|---|---|---|
| WELDING IRONS AND STEELS | | | | |
| **Mild Steel** (coated and covered) | A233-58T | E6010 | 60—properties; 10—manner of use[c] | 2a, 2b |
| **Low Alloy Steel** (covered) | A316-58T | E7010[c] | 70—properties; 10—manner of use | 2a, 2b |
| | | E7010-A1[c] | 70—properties; 10—modifies comp; A1—comp of weld | 2a, 2c |
| **Stainless Steel** (covered) | A251-46T | E308ELC-15 | 308—comp of weld; ELC—modifies comp; 15—manner of use. Properties are also specified[d] | 3 |
| **Stainless Steel** (bare)[f] | A371-53T | ER308L | 308—comp as mfd; L—modifies comp | 3 |
| **For Welding Cast Iron**[e] | A398-56T | RCuAl-A2 | CuAl—comp as mfd; A2—modifies comp. Visual examination of weld is also specified[d] | 4 |
| **For Gas Welding Irons and Steels** | A251-46T | GA65 | A65—properties | 5 |
| WELDING NONFERROUS METALS | | | | |
| **Copper and Copper Alloy** | B225-53T (electrodes) | ECuAl-A2 | CuAl—comp as mfd; A2—modifies comp. Properties are also specified[d] | 6 |
| | B259-52T (rods) | RCuAl-A2 | CuAl—comp as mfd; A2—modifies comp | 6 |
| **Nickel and Nickel Alloy** | B295-54T (covered electrodes) | E3N10[h] | 3—base metal; 1—welding method; 0—comp of core as mfd. Comp of weld, tensile strength are also specified[d] | 7 |
| | B304-56T (bare electrodes and rods) | ERN60 | 6—welding method; 0—comp as mfd | 8 |
| **Aluminum and Aluminum Alloy** | B184-43T (covered electrodes) | Al-2 | 2—comp of core as mfd | 9 |
| | B285-54T (bare electrodes and rods) | R-CN42A[i] | CN42—comp as mfd | 9 |
| **Magnesium and Magnesium Alloy**[f] | No specifications; alloys can be joined by gas welding and inert-gas shielded arc processes. In general, filler metal should have same composition as alloy being joined | | | |
| **Lead and Zinc** | No specifications; gas welding most commonly used. In general, filler metal should have same composition as alloy being joined | | | |

[a] The first letter of the designation is either "E" for electrode or "R" for rod.
[b] The figures used are samples, e.g., the "10" for mild steels may be 11, 12, etc., each indicating a different manner of use. Properties = Mechanical properties of the deposited weld metal. (The figures approximate the minimum tensile strength in units of 1000 psi.) Manner of use = Type of current, polarity (if d.c.), welding position, type of covering.
[c] These figures also indicate modifications of specified properties and whether or not weld composition is specified.
[d] Specified, but not represented in the classification number.
[e] Must be classified one way or the other, not both.
[f] Used as both rods and bare electrodes. As rods—atomic hydrogen and inert-gas metal arc (nonconsumable electrode) welding. As bare electrodes—submerged arc and inert-gas metal-arc (consumable electrode) welding.
[g] Includes rods for oxyacetylene and carbon arc welding, covered electrodes for shielded metal arc welding. Types included here are: cast iron, copper-base, nickel-base and mild steel.
[h] The "N" designates "nickel."
[i] The "A" designates "aluminum."

**1—TYPICAL PROPERTIES OF MILD STEEL ARC WELDED DEPOSITS**

| AWS—ASTM Class ↓ | Ten Str, 1000 psi | Yld Point, 1000 psi | Elong (in 2 in.), % | Red. of Area, % | Impact Str, ft-lb* | Endur Limit, 1000 psi | Brinell Hardness |
|---|---|---|---|---|---|---|---|
| E4510, E4520 | 45 | — | 5 | — | — | — | — |
| E6010 | 60–68 | 48–58 | 22–28 | 35–60 | 30–40, 15–25 | 28–32 | 140–160 |
| E6011 | 60–70 | 48–61 | 22–30 | 35–60 | 30–40, 15–25 | 28–32 | 140–160 |
| E6012 | 60–78 | 48–65 | 17–22 | 20–40 | 20–30, 5–15 | — | 150–170 |
| E6013 | 60–78 | 48–65 | 17–22 | 25–50 | 25–35, 5–20 | — | 150–170 |
| E6020, E6030 | 60–68 | 48–58 | 25–30 | 40–60 | 25–35, 15–25 | 30–34 | 150–170 |
| E6027 | 60–68 | 48–55 | 25–30 | 40–60 | 25–35, 15–25 | 30–34 | 150–170 |
| E6014 | 60–72 | 48–60 | 17–25 | 30–50 | 25–35, 15–25 | — | — |
| E7014 | 70–85 | 58–77 | 17–25 | 30–50 | 25–35, 15–25 | — | — |
| E6015, 6016 | 60–72 | 48–60 | 22–35 | 55–75 | 35–50, 25–40 | — | 140–160 |
| E7015, 7016 | 70–76 | 58–62 | 22–35 | 55–75 | 35–50, 25–40 | — | — |
| E6018 | 60–72 | 48–60 | 22–30 | 55–75 | 35–50, 25–40 | — | — |
| E7018 | 70–85 | 58–70 | 22–30 | 55–75 | 35–50, 25–40 | — | — |
| E6024 | 60–72 | 48–60 | 17–22 | 20–40 | 25–35, 10–20 | — | 150–170 |
| E7024 | 70–85 | 58–75 | 17–22 | 20–40 | 25–35, 10–20 | — | 150–170 |
| E6028 | 60–72 | 48–60 | 22–30 | 55–75 | 35–50, 25–40 | — | — |
| E7028 | 70–85 | 58–74 | 22–30 | 55–75 | 35–50, 25–40 | — | — |

* Charpy keyhole. First value is at 70 F, second at −40 F.

each group according to American Welding Society specifications.

In some cases there is a choice offered by the specification; the manufacturer may be allowed to select one of several classification methods, or may be allowed to list an electrode by more than one classification.

The numbered charts on this and the following six pages classify the rods and electrodes within each group by the applicable method and also give other information, such as method of use, typical properties and some common applications.

### Welding Processes

**Arc welding.** A group of processes wherein coalescence is produced by heating with an electric arc. The metal to be welded is one pole of an electric circuit and the electrode is the other pole. A suitable gap forms a heat generating arc. (The metal participates in the production of heat but is not the sole source.) Carbon or metal electrodes may be used. If covered metal electrodes are used the process is referred to as *shielded*. There are other methods of shielding, such as using an inert gas (helium or argon), or a blanket of granular, fusible material on the work (referred to as *submerged arc welding*).

**Braze welding.** Uses a brazing torch but is classified technically as a welding process because the filler metal is distributed by gravity and not, as in brazing, by capillary action.

**Gas welding.** A group of processes wherein coalescence is produced by heating with a gas flame, most commonly obtained by the combustion of acetylene with oxygen (*oxyacetylene welding*).

**Resistance welding.** A group of processes wherein coalescence is produced by the heat generated from resistance to flow of electric current through the work, and by pressure. Heat is generated in two places: in the body of the work where only the resistivity of the material determines the amount of heat; and at contact surfaces where resistivity is affected by pressure, surface oxides and compounds, and surface roughness and cleanliness. No fluxes or filler metals are used. Various types of resistance welding processes are named according to the method of determining pressure points. Examples

### Definitions

**Filler metal.** A broad term for the metal added in making a weld. It may or may not carry electric current.

**Rod.** Filler metal, in wire or rod form, which does not carry current. Rods are used in gas welding or in arc welding with a separate carbon or tungsten electrode.

**Electrode.** The current-carrying element. With three exceptions, it is also the filler metal. Carbon and tungsten electrodes are not filler metals. The third exception is the "resistance welding electrode," a term applied to the part of the resistance welding machine that transmits current (and usually pressure) to the work. A resistance welding electrode may be in the form of a wheel, bar, cylinder, clamp, etc.

**Bare, lightly coated, covered.** Terms which apply to filler metals (either rods or electrodes) used in arc welding. However, since rods are usually bare, the terms are generally reserved for filler metal electrodes. The purpose of a light coating is primarily to stabilize the arc. "Covered" wires have a relatively thick coating which protects the molten metal from the atmosphere, improves weld metal properties, and stabilizes the arc.

## Welding Electrodes and Rods

**2a—MILD AND LOW ALLOY STEEL COVERED ELECTRODES**
**(Classified by Current, Welding Position and Covering)**

| AWS-ASTM Class ↓ | Current, Polarity | Welding Position[a] | Covering | Slag[b] | Deposition Rate | Arc Characteristics |
|---|---|---|---|---|---|---|
| Exx10[c] | D.c. reversed | F, V, OH, H | High cellulose sodium | Thin | Slow | Spray, deep penetration |
| E6011 | A.c. or d.c. reversed | F, V, OH, H | High cellulose potassium | Thin | Slow | Spray, deep penetration |
| E6012 | A.c. or d.c. | F, V, OH, H | High titania sodium | Dense | Medium | Globule, medium penetration |
| Exx13 | A.c. or d.c. straight | F, V, OH, H | High titania potassium | Medium | Med fast | Globule, shallow penetration |
| Exx14 | A.c. or d.c. | F, V, OH, H | Iron powder, titania | Medium | Med fast | Globule, medium penetration |
| Exx15 | D.c. reversed | F, V, OH, H | Low hydrogen sodium | Heavy | Medium | Globule, medium penetration |
| Exx16 | A.c. or d.c. reversed | F, V, OH, H | Low hydrogen potassium | Heavy | Medium | Globule, medium penetration |
| Exx18 | A.c. or d.c. reversed | F, V, OH, H | Iron powder, low hydrogen | Heavy | Fast | Globule, shallow penetration |
| Exx20[a] | A.c. or d.c. | H fillets, F | High iron oxide | Heavy | Fast | Spray, medium penetration |
| E6024 | A.c. or d.c. either polarity | H fillets, F | Iron powder, titania | Heavy | Fast | Spray, shallow penetration |
| E6027 | A.c. or d.c. | H fillets, F | Iron powder, iron oxide | Heavy | Fast | Spray, medium penetration |
| Exx28 | A.c. or d.c. reversed | H fillets, F | Iron powder, low hydrogen | Dense | Fast | Spray, deep penetration |
| E6030 | A.c. or d.c. either polarity | F | High iron oxide | Dense | Fast | Spray, deep penetration |

[a] F = flat, V = vertical, OH = overhead, H = horizontal. [b] All slag deposits are readily removable except E6012 which is rated "fair."
[c] When xx = 45, the only column in this table that applies is "Welding Position." Current and polarity of 4510 and 4520 are not specified, but generally d.c. straight polarity is used. These two electrodes are not covered but are either sulcoated or light coated.

**2b—MILD AND LOW ALLOY STEEL COVERED ELECTRODES**
**(Classified by Minimum Mechanical Properties)[a, b]**

| AWS-ASTM Class ↓ | Ten Str, 1000 psi | Yld Point, 1000 psi | Elong (in 2 in.), % |
|---|---|---|---|
| MILD ALLOY STEEL ELECTRODES | | | |
| 4510, 4520 | 45 | Not spec | 5 |
| 6010, 6011 | 62 | 50 | 22 |
| 6012, 6013, 6014, 6024 | 67 | 55 | 17 |
| 6015, 6016, 6018, 6028 | 67 | 55 | 22 |
| 6020, 6027, 6030 | 62 | 50 | 25 |
| LOW ALLOY STEEL ELECTRODES | | | |
| 70xx | 70 | 57 | 22[c] |
| 80xx | 80 | 67 | 19[d] |
| 90xx | 90 | 77 | 17[c] |
| 100xx | 100 | 87 | 16[f] |
| 110xx | 110 | 97 | 15 |
| 120xx | 120 | 107 | 14 |

[a] Classification by mechanical properties is represented by the first two digits. For low alloy steel electrodes the digits are exactly the minimum tensile strength in units of 1000 psi. For mild alloy steel the digits are approximately the minimum tensile strength.
[b] Chemical composition of low alloy steel welds is an alternative classification (see 2c). Chemical composition of mild alloy steel welds is additionally specified for electrodes of the following classes: Exx14-15-16-18-24-28. For these classes the maximum percentage composition is: Mo 0.30, Cr 0.20, Mn 1.25, Ni 0.30, V 0.08 (in addition the sum total of these elements shall not exceed 1.50%) and Si 0.90.
[c] Elongation is 25% for 7020. [c] Elongation is 14% for 9013.
[d] Elongation is 16% for 8013. [f] Elongation is 13% for 10013.

**2c—LOW ALLOY STEEL COVERED ELECTRODES**
**(Classified by Chemical Composition of Weld)[a]**

| ↓ AWS-ASTM Class | Composition (max), % |
|---|---|
| CARBON-MOLYBDENUM STEEL | |
| A1 | C 0.12, Mo 0.40–0.65 |
| CHROMIUM-MOLYBDENUM STEEL | |
| B1 | C 0.12, Cr 0.40–0.65, Mo 0.40–0.65 |
| B2L | C 0.05, Cr 1.00–1.50, Mo 0.40–0.65 |
| B2 | C 0.12, Cr 1.00–1.50, Mo 0.40–0.65 |
| B3L | C 0.05, Cr 2.00–2.50, Mo 0.90–1.20 |
| B3 | C 0.12, Cr 2.00–2.50, Mo 0.90–1.20 |
| B4L | C 0.05, Cr 1.75–2.25, Mo 0.40–0.65 |
| NICKEL STEEL | |
| C1 | C 0.12, Ni 2.00–2.75 |
| C2 | C 0.12, Ni 3.00–3.75 |
| C3 | C 0.12, Ni 0.80–1.10 |
| MANGANESE-MOLYBDENUM STEEL | |
| D1 | C 0.12, Mo 0.25–0.45, Mn 1.25–1.75 |
| D2 | C 0.15, Mo 0.25–0.45, Mn 1.65–2.00 |
| OTHER (min %)[b] | |
| G | Mo 0.20, Cr 0.30, Mn 1.00, Si 0.80, Ni 0.50, V 0.10 |

[a] Classification of low alloy steel electrodes by chemical composition can be found in AWS-ASTM specification A316–58T. Compositions are represented by a code following the standard classification, modified by the second two digits. This table gives only the percentages of the major elements.
[b] Deposit need have minimum of only one of elements listed.

are: *spot welding* (two welding tips pressing the work together in one spot at a time); and *projection welding* (welding dies are used and pressure points determined by projections designed as an integral part of the work). Other processes are named according to the speed of effecting contact and pressure and their timing with reference to the heating cycle (*flash* and *upset*).

## 3—STAINLESS STEEL RODS AND ELECTRODES

| Covered Electrodes | | Rods and Bare Electrodes | | Applications | Min Mechanical Properties of Covered Electrode Deposits | |
|---|---|---|---|---|---|---|
| AWS-ASTM Class[a] ↓ | Major Composition of Weld Metal, %[b] | AWS-ASTM Class[c] ↓ | Major Composition As Manufactured, %[b] | | Ten Str, 1000 psi | Elong (in 2 in.), % |
| E308..... | C 0.08, Cr 18.0–21.0, Ni 9.0–11.0 | ER308.... | C 0.08, Cr 19.5–22.0, Ni 9.0–11.0 | Weld base metal of similar composition | 80 | 35 |
| E308ELC .. | C 0.04, Cr 18.0–21.0, Ni 9.0–11.0 | ER308L... | C 0.03, Cr 19.5–22.0, Ni 9.0–11.0 | Low C reduces carbide precipitation, avoiding intergranular corrosion without need for stabilizers | 75 | 35 |
| E309..... | C 0.15, Cr 22.0–25.0, Ni 12.0–14.0 | ER309.... | C 0.12, Cr 23.0–25.0, Ni 12.0–14.0 | Weld similar alloys, wrought or cast. Weld 18–8 for severe corrosion conditions | 80 | 35 |
| 309Cb..... | C 0.12, Cr 22.0–25.0, Ni 12.0–14.0, Cb+Ta 0.70–1.00 | ..... | ..... | Primarily weld type 347 clad steel or dissimilar metals. Cb stabilizes against intergranular corrosion, provides high strength at high temperatures | 80 | 30 |
| E309Mo... | C 0.12, Cr 22.0–25.0, Ni 12.0–14.0, Mo 2.00–3.00 | ..... | ..... | Primarily weld type 316 clad steels or dissimilar metals (similar to E309 with Mo added, C reduced) | 80 | 35 |
| E310..... | C 0.20, Cr 25.0–28.0, Ni 20.0–22.0 | ER310.... | C 0.08–0.15, Cr 25.0,[d] Ni 20.0[d] | High strength, ductility useful in welding such hardenable steels as armor plate. Also weld clad steels | 80 | 30 |
| E310Cb.... | C 0.12, Cr 25.0–28.0, Ni 20.0–22.0, Cb+Ta 0.70–1.00 | ..... | ..... | Same uses as E309Cb | 80 | 25 |
| E310Mo... | C 0.12, Cr 25.0–28.0, Ni 20.0–22.0, Mo 2.00–3.00 | ..... | ..... | Same uses as E309Mo | 80 | 30 |
| E312..... | C 0.15, Cr 26.0–31.0, Ni 8.5–10.5 | ..... | ..... | Primarily weld cast alloys of similar composition. A recent use: weld dissimilar metals when one is high in nickel | 95 | 22 |
| E316..... | C 0.08, Cr 17.0–20.0, Ni 11.0–14.0, Mo 2.00–2.50 | ER316.... | C 0.08, Cr 18.0–20.0, Ni 12.0–14.0, Mo 2.0–2.5 | Weld similar alloys containing 2 to 3% Mo. Molybdenum content provides creep resistance at high temperatures | 80 | 30 |
| E316ELC .. | C 0.04, Cr 17.0–20.0, Ni 11.0–14.0, Mo 2.00–2.50 | ER316L... | C 0.03, Cr 18.0–20.0, Ni 12.0–14.0, Mo 2.0–2.5 | Primarily weld extra low carbon, molybdenum-bearing austenitic alloys | 75 | 30 |
| E317..... | C 0.08, Cr 18.0–21.0, Ni 12.0–14.0, Mo 3.00–4.00 | ER317.... | C 0.08, Cr 18.5–20.5, Ni 13.0–15.0, Mo 3.25–4.0 | Weld similar alloys that must meet severe corrosion requirements involving sulfuric and sulfurous acids, salts | 80 | 30 |
| E318..... | C 0.08, Cr 17.0–20.0, Ni 11.0–14.0, Mo 2.00–2.50, Cb+Ta 1.00[e] | ..... ... | ..... | Primarily weld metals of similar composition (identical to E316 with Cb added) | 80 | 25 |
| E330..... | C 0.25, Cr 14.0–17.0, Ni 33.0 min | ER330.... | C 0.15–0.25, Cr 15.0–17.0, Ni 34.0[d] | Repair defects in alloy castings; weld similar alloys. Nickel content gives heat and scale resistance above 1800 F | 75 | 25 |
| E347..... | C 0.18, Cr 18.0–21.0, Ni 9.0–11.0, Cb+Ta 1.00[f] | ER347.... | C 0.08, Cr 18.5–21.0, Ni 8.5–10.5, Cb+Ta 1.00[g] | Usually weld Cr-Ni alloys of similar composition stabilized with Cb or Ti | 80 | 30 |
| E410..... | C 0.12, Cr 11.0–14.0, Ni 0.60 | ER410.... | C 0.07–0.12, Cr 12.0–14.0, Ni 0.6, Mo 0.6 | Weld similar alloys; deposit overlays on carbon steels for corrosion, erosion and abrasion resistance. Air-hardening, it requires preheat and post-heat treatment to obtain ductility | 70 | 20 |
| ..... | ..... | ER420.... | C 0.25–0.40, Cr 12.0–14.0, Ni 0.6 | Similar to E410, but better resistance to corrosion, abrasion | — | — |
| E430..... | C 0.10, Cr 15.0–18.0, Ni 0.60 | ER430.... | C 0.10, Cr 15.5–17.0, Ni 0.6 | Similar to E410. Cr limit gives adequate corrosion resistance, yet retains ductility | 70 | 20 |
| E502..... | C 0.10, Cr 4.0–6.0, Ni 0.40, Mo 0.45–0.65 | ER502.... | C 0.10, Cr 4.5–6.0, Ni 0.4, Mo 0.45–0.65 | Weld similar metals, usually pipe or tubing | 60 | 20 |

[a] The complete classification numbers are *Exxx-15* or *Exxx-16*. The *–15* suffix indicates a lime covering, *–16* a lime or titania covering. Polarity and welding position requirements are the same as those listed in chart 2 for Exx-15 and Exx-16.
[b] Maximum percentages unless otherwise specified. Carbon analysis required to nearest 0.01%.
[c] For consumable electrode welding, d.c. reversed polarity is preferred.
[d] Minimum. [e] Minimum is 6 x C. [f] Minimum is 8 x C. [g] Minimum is 10 x C.

continued on next page

## Welding Electrodes and Rods

**4—RODS AND ELECTRODES FOR WELDING CAST IRON**

| AWS-ASTM Class [a] ↓ | Common Name[b] | Welding Method | Remarks | Uses |
|---|---|---|---|---|
| RCI | Cast iron | Oxyacetylene | Produces machinable deposit of same color, composition and structure as base metal | Fill in or build up new or worn gray iron castings. General fabrication, salvage, repair |
| ECI | Cast iron | Arc; a.c. or d.c. reversed polarity | Basically RCI with heavy covering. Weld metal flows readily; light slag easily removable | Weld and repair gray iron castings; faster than oxyacetylene for repairing small defects |
| RCI-A | Alloy cast iron | Oxyacetylene | Similar to RCI but higher melting. Weld metal more fluid; welding more rapid | Gray or alloy cast iron to obtain greater tensile strength and finer grain structure than RCI |
| RCuZn-A[c] | Naval brass | Oxyacetylene | Better strength, corr res than basic 60 Cu-40% Zn alloy. Deposits 70–90 Bhn | Where color match is not required and weldments are not subject to electrolytic corrosion or high temperature service |
| RCuZn-B[c] | Manganese bronze | Oxyacetylene | Better strength, hardness, corr res than 60 Cu-40% Zn alloy. Deposits 80–110 Bhn | Same as above |
| RCuZn-C[c] | Low-fuming bronze | Oxyacetylene | Diminishes zinc oxidation (fuming). Slightly higher mechanical properties than naval brass or manganese bronze; deposits 80–110 Bhn | Same as above |
| RCuZn-D[c] | Nickel bronze | Oxyacetylene | Color is silver rather than yellow. Low fuming. Deposits 90–110 Bhn | Same as above |
| ECuAl-A2[d], RCuAl-A2[c] | Aluminum bronze (9–11 Al, 1.5% Fe) | Electrodes—arc welding; a.c. and d.c. reversed polarity. Rods—carbon arc welding | Low m.p. permits rapid welding to minimize distortion. Yld and ten str twice those of ECuSn alloys (below) | Weld the new higher strength cast irons. Overlay corrosion and wear resistant surfaces |
| ECuSn-A[d] | Phosphor bronze (4.8–5.8% Sn) | Arc; d.c. reversed polarity | Deposits 70–85 Bhn | Weld cast iron and overlay bearing and corrosion resistant surfaces |
| ECuSn-C[d] | Phosphor bronze (7.0–9.0% Sn) | Same as above | Deposits 85–100 Bhn. Higher yld and ten str than ECuSn-A | Same as above |
| ENi | Nickel | Arc; flat specified but other positions have been used | Rapid, widely used. Even without preheating, deposits can be machined | Weld ordinary gray irons to themselves or to other ferrous and nonferrous materials; light and medium-sized castings. Reclamation and repair |
| ENiFe | Nickel-iron | Same as above | Same as above, but higher ten str and ductility | Weld various cast irons to steel and other ferrous and nonferrous materials; heavy and highly stressed sections. Better than ENiFe for castings containing more than 0.20% P |
| ENiCu-A | Nickel-copper (55–60% Ni) | Same as above | Similar to ENiFe | Similar to ENiFe |
| ENiCu-B | Nickel-copper (63–70% Ni) | Same as above | Similar to ENi | Similar to ENi |
| ESt | Mild steel | Arc; a.c. or d.c. reversed polarity | Designated specifically for cast iron; has a low m.p. Covering and deposits not readily machinable | Largely confined to repair of small pits and cracks in cast iron; some larger repairs if casting requires no machining |

[a] Chemical symbols for the major elements of the composition are used to classify these rods and electrodes. In other cases, CI = cast iron and St = steel. The letter, or letter and number, following the hyphen indicates a modification of a standard composition.
[b] For exact chemical composition as manufactured, see ASTM A398–56T.
[c] Also a standard classification under Copper and Copper Alloy Welding Rods.
[d] Also a standard classification under Copper and Copper Alloy Welding Electrodes.

**Other welding processes.** Each process has variants not described and less commonly used. There are also special processes such as *flow welding, forge welding, thermit welding* and *induction welding.* All of these are described in detail in the *Welding Handbook* of the American Welding Society.





***Fig 1**—The five basic welding joint designs.*





***Fig 2**—The four basic weld types for arc and gas welding.*





***Fig 3**—The four basic welding positions.*

**5—RODS FOR GAS WELDING IRONS AND STEELS [a]**

| AWS-ASTM Class ↓ | Weld Treatment[b] | Min Ten Str, 1000 psi | Min Elong (in 2 in.), % |
|---|---|---|---|
| GA65 | SR | 65 | 20 |
| | NSR | 72 | 17 |
| GA60 | SR | 60 | 25 |
| | NSR | 62 | 20 |
| GA50 | SR | 50 | 28 |
| | NSR | 52 | 23 |
| GB65 | SR | 65 | 18 |
| | NSR | 72 | 15 |
| GB60 | SR | 60 | 20 |
| | NSR | 62 | 15 |
| GB45 | NSR | 45 | — |

[a] Mechanical tests are performed on welds made by either 1/8- or 1/4-in. rods and on plates 3/4 in. thick (except GB45 which requires a 3/8-in. plate).
[b] SR = stress relieved; NSR = non-stress relieved.

## Design Factors

Welding is a basic production method whose end product is a metal part or form termed a "weldment." Weldments must be considered in competition with castings, forgings and other fabricated forms, as well as other joining methods.

**Sizes and shapes.** A wide range of thicknesses, sizes and shapes can be joined by welding. Parts as thin as 1 mil and as thick as 20 in. have been welded commercially. Plate and sheet stock are the most widely used forms, but forgings, castings, extrusions and rolled shapes are also used in fabricating weldments.

**Tolerances.** The two principal factors influencing tolerances are distortion from the welding operation and the tolerances of the metal forms that make up the weldment. The tolerances on the various metal forms, such as flat stock, castings, forgings and rolled sections, are easily obtainable. But degree of welding distortion is a function of a great many things, and exact values cannot be given. The following tolerances seem to be those most commonly achieved:

1. Small parts containing very little welding, 1/8 in.
2. Moderately large parts containing a small amount of welding, 1/4 in.
3. Large structures containing moderate amounts of welding, 3/8 in.
4. Large, complicated structures, and structures containing large amounts of welding, 3/8 to 1/2 in.

*continued on next page*

## Welding Electrodes and Rods

**6—COPPER AND COPPER ALLOY RODS AND ELECTRODES**

| AWS-ASTM Class ↓ | Common Name | Welding Method[a] | Current, Polarity | Min Ten Str, 1000 psi | Brinell Hardness | Applications |
|---|---|---|---|---|---|---|
| ECu, RCu.... | Copper | IGMA (E, R), CA (R), OG (R) | D.c. straight | 25 | 25–40[b] | Light gage Cu up to 3/16 in.—R[c]; heavier gage—E. Deoxidized Cu (R)[c, f] |
| ECuSi, RCuSi-A.... | Silicon bronze (Si 2.8–4.0%) | IGMA (E, R), SMA (E), CA (R), OG (R) | D.c. reverse (E), d.c. straight (R) | 50 | 80–100 | Primarily for welding Cu, CuSi and CuZn to themselves (E, R) and to steel (R)[c, f]. Mtl over 1/16 in. thk (E).[d] Silicon bronze; overlay for corr res (E)[e]. CuSi alloys (R)[c] |
| RCuSi-B..... | Silicon bronze (Si 1.02–2.0%) | CA, OG | D.c. straight | 35 | 60–85 | Red brass piping[c]. Cu, CuSi and CuZn[f]; Cu to steel[f]; galvanized iron[f] |
| RCuSn..... | Phosphor bronze (Sn 4.0–6.0%) | CA, IGMA-NC | D.c. straight | 35 | 70–85 | Cu[c, f] and CuSn[c] |
| ECuSn-A[i].... | Phosphor bronze (Sn 4.8–5.8%) | SMA, IGMA-C | D.c. reverse | 35 | 70–85 | Weld phosphor bronzes of similar comp. "A" and "C" (below) used interchangeably for Cu, brasses, bronzes, cast iron, dissimilar metals |
| ECuSn-C[i].... | Phosphor bronze (Sn 7.0–9.0%) | SMA, IGMA-C | D.c. reverse | 40 | 85–100 | Same as above, but "C" provides higher ten and yld str, higher hardness |
| ECuNi, RCuNi | Copper nickel | SMA (E), OG (R), IGMA-NC(R) | D.c. reverse (E), d.c. straight (R), a.c. (R) | 50 | 60–80 | CuNi alloys (10–30%) to themselves to provide good corr res |
| RCuZn-A[i].... | Naval brass | BW, OG | — | 50 | 70–90 | Brass[c]. Cu, bronze, Ni alloys, steel, cast and malleable iron[h] |
| RCuZn-B[i].... | Manganese bronze | BW | — | 55 | 80–110 | Steel and cast iron[h]. As surfacing filler metal for building up bearings |
| RCuZN-C[i].... | Low-fuming bronze | BW, OG | — | 57 | 80–110 | General purpose |
| RCuZn-D[i].... | Nickel bronze | BW, OG | — | 60 | 90–110 | Steel and cast iron[h] |
| ECuAl-Al, RCuAl-Al... | Aluminum bronze (iron-free) | IGMA (E, R), CA (R) | D.c. reverse (E), a.c. (R)[c], d.c. straight (R)[c, f] | 55 | 100–158 (E), 100–130 (R)[f], 100–150 (R)[c] | Annealed aluminum bronze plate, sheet and strip (E, R). Repair castings (E, R)[c, f]. Overlay bearing and corr res surfaces (E, R)[c] |
| ECuAl-A2[i], RCuAl-A2[i]. | Aluminum bronze (Fe 3.0–4.25%) | IGMA (E, R), SMA (E), CA (R) | D.c. reverse (E)[d, e], d.c. straight (R)[c, f], a.c. (E[e], R[c]) | 60 (E), 65 (R) | 130–150 (E)[e], 150–170 (E)[d], 100–130 (R)[d], 100–150 (R)[c] | Aluminum bronze, high str CuZn alloys, silicon bronze, nickel alloys, ferrous alloys, dissimilar metals. Repair castings; overlay bearing and corr res surfaces |
| ECuAl-B, RCuAl-B... | Aluminum bronze (Fe 3.0–4.25%) | SMA (E), CA (R), IGMA-NC(R) | D.c. reverse (E), d.c. straight (R)[c, d], a.c. (E, R[c]) | 65 (E), 70 (R) | 140–180 (E), 140–180 (R)[f], 180–220 (R)[c] | Similar to above, but provides higher phys prop. Weld nonferrous metals to steel (E,R)[c] |

[a] Method symbols are: IGMA = inert-gas metal arc welding (–C = consumable electrode; –NC = nonconsumable electrode); OG = oxyacetylene welding, CA = carbon arc welding, SMA = shielded metal arc welding (covered electrodes), BW = braze welding.
[b] Rockwell F.
[c] Inert-gas metal arc (nonconsumable electrode) welding.
[d] Inert-gas metal arc (consumable electrode) welding.
[e] Oxyacetylene welding.
[f] Carbon arc welding.
[g] Shielded metal arc welding (covered electrode).
[h] Braze welding.
[i] Also a standard classification under Rods and Electrodes for Welding Cast Iron.

**Joint design.** There are five fundamental types of arc or gas welded joints (see Fig 1) and four basic types of welds (see Fig 2), but variations of these are used to satisfy particular requirements. Resistance welding commonly employs the lap joint, although flash welding requires a butt joint.

**Welding positions.** Welds are classified by four basic positions; for each, certain electrodes are recommended or not recommended. The position terms—flat, vertical, horizontal and overhead—can be applied to all types of welds, but they are illustrated here for the groove weld (see Fig 3).

[a] Used with shielded metal arc welding process.
[b] These electrodes are used to join alloys of same composition as the electrode. When first digit of designation is *3*, electrode is used primarily to join similar alloys to themselves; when first digit is *4*, electrode is used to weld a nickel or nickel-base alloy to steel, to overlay a nickel or nickel-base alloy on steel, or to weld the clad side of nickel or a nickel-base alloy clad steel.
[c] Used to weld not only mill products but also castings of suitable welding quality.
[d] Also used to weld such copper-nickel alloys as 70–30, 80–20 and 90–10 to themselves.
[e] Also used for a number of dissimilar metal combinations.
[f] Age hardened.
[g] Also used to weld alloys of similar composition to steel-clad materials or other metals.

**7—NICKEL AND NICKEL ALLOY COVERED ELECTRODES [a]**

| AWS-ASTM Class[b] ↓ | Alloy | Common Name | Min Ten Str, 1000 psi |
|---|---|---|---|
| E3N10 | Nickel-copper (C 0.40, Mn 4, Cb+Ta 0%) | Monel[c,d] | 70 |
| E3N11 | Nickel (C 0.75) | Nickel[c] | 55 |
| E3N12 | Nickel-chromium-iron | Inconel[c] | 80 |
| E3N14 | Nickel-copper-aluminum | K monel[c] | 100[f] |
| E3N19 | Nickel-chromium-iron-titanium | Inconel X | 115[f] |
| E3N1B, E4NiB | Nickel-molybdenum | Hastelloy B[g] | 100 |
| E3N1C, E4NiC | Nickel-molybdenum-chromium | Hastelloy C[g] | 100 |
| E4N10 | Nickel-copper (C 0.15, Mn 2.50, Cb+Ta 3%) | Monel | — |
| E4N11 | Nickel (C 0.10%) | Nickel | — |
| E4N12 | Nickel-chromium | Inconel | — |

**8—NICKEL AND NICKEL ALLOY RODS AND BARE ELECTRODES**

| AWS-ASTM Class[a] ↓ | Alloy | Common Name | Welding Method[b] |
|---|---|---|---|
| RN40 | Nickel-copper (Mn 2, Al 0, Ti 0) | Monel | OG[c] |
| ERN60 | Nickel-copper (Mn 1, Al 1.25, Ti 1.50–3.00) | Monel | IGMA, At. $H_2$ |
| RN41 | Nickel (Mn 0.35, Fe 0.40, Ni 97 min, Al 0, Ti 0.50) | Nickel | OG[c] |
| ERN61 | Nickel (Mn 1, Fe 1, Ni 93 min, Al 1.50, Ti 2.00–3.50) | Nickel | IGMA, At. $H_2$ |
| RN42 | Nickel-chromium-iron (Ni 72 min, Cb+Ta 0) | Inconel | OG, IGMA[d] |
| ERN62 | Nickel-chromium-iron (Ni 70 min, Cb+Ta 1.50–3.00) | Inconel | IGMA, At. $H_2$, OG |
| RN43 | Nickel-copper-silicon | — | OG[e] |
| ERN64 | Nickel-copper-aluminum | K Monel | IGMA, At. $H_2$[f] |
| ERN69 | Nickel-chromium-iron-titanium | Inconel X[g] | IGMA, At. $H_2$[f] |
| ERN6N | Nickel-chromium-titanium | Nimonic 7s | IGMA, At. $H_2$ |
| ERN7B | Nickel-molybdenum | Hastelloy B | At. $H_2$, IGMA, Sub Arc |
| ERN7C | Nickel-molybdenum-chromium (Cr 14.5–16.5, Mo 15–17, W 3.00) | Hastelloy C | At. $H_2$, IGMA, Sub Arc |
| ERN7W | Nickel-molybdenum-chromium (Cr 4–6, Mo 23–26, W 0) | Hastelloy W[h] | At. $H_2$, IGMA, Sub Arc |

[a] These rods and electrodes are used to weld alloys of similar composition.
[b] For the IGMA process, argon and d.c. reversed polarity are preferred for electrodes; either argon or helium and d.c. straight polarity with rods. Welding method symbols used are: OG = oxyacetylene; IGMA = inert-gas metal arc; At. $H_2$ = atomic hydrogen; Sub Arc = submerged arc.
[c] Gross porosity usually results when arc welding is employed.
[d] Do not use inert-gas metal arc method on sheet ⅛ in. thick and heavier.
[e] Used to weld monel which has 55–60% Ni, or any monel when absence of flux desirable.
[f] Responds to age hardening.
[g] Used to weld Inconel X and Inconel W.
[h] Used to weld such dissimilar metal combinations as Cr-Ni-Fe steels to cast cobalt alloys.

**9—ALUMINUM AND ALUMINUM ALLOY RODS AND ELECTRODES**

| AWS-ASTM Class ↓ | Major Composition As Manufactured | Alloys Welded[a] |
|---|---|---|
| BARE ELECTRODES AND RODS[b] | | |
| R-996A, E-996A | Al 99.6 min | 996A |
| R-990A, E-990A | Al 99.0 min | 990A, M1A, G1A, clad M1A |
| R-C4A | Cu 4.0–5.0 | CS42A, C4A |
| R-CN42A | Cu 3.5–4.5, Ni 1.7–2.3 | CN42A |
| R-CS41A, E-CS41A | Cu 3.9–5.0, Si 0.50–1.2 | Clad CS41A |
| R-G1A, E-G1A | Mg 1.0–1.8 | M1A, G1A, clad M1A |
| R-GM50A, E-Gm50A | Mg 4.9–5.6, Mn 0.05–0.20 | MG11A, Gr20A, clad MG11A, GS42A, GS11A |
| R-GR20A, E-GR20A | Mg 2.2–2.8, Cr 0.15–0.35 | MG11A, GR20A, clad MG11A |
| R-GR40A, E-GR40A | Mg 3.1–3.9, Cr 0.15–0.35 | MG11A, GR20A, GS11A, clad MG11A, GS42A, GR40A |
| R-MG11A, E-MG11A | Mn 1.0–1.5, Mg 0.8–1.3 | MG11A, clad MG11A |
| R-S5B, E-S5B | Si 4.5–6.0, Bi 0.05 | M1A, MG11A, G1A, GR20A, CS11A, clad M1A, clad MG11A, S5A |
| R-SC51A | Si 4.5–5.5, Cu 1.0–1.5 | SC51A |
| R-SG70A | Si 6.5–7.5, Mg 0.20–0.40 | SG70A |
| R-ZG61A | Zn 5.2–6.0, Mg 0.50–0.65 | ZG61A |
| COVERED ELECTRODES[c] | | |
| Al-2 | Al 99.0 min | Pure aluminum (min ten str 12,000 psi) |
| Al-43 | Si 4.5–6.0, Al bal | General purpose (min ten str 14,000 psi) |

[a] These ASTM alloy designations apply to all forms except die castings.
[b] Welding methods include gas, shielded carbon arc, inert-gas metal arc and atomic hydrogen.
[c] Used with d.c. current, preferably in flat position.

# Adhesives

## Selection


**Classification.** There are many ways to classify adhesives, none of which is satisfactory by itself. The five tables included here, each using a different breakdown, must therefore be referred to as a group. Classifying by chemical composition (Table 1) is most usual, but the newer modified compounds are omitted because they represent the blending of several chemical groups, and because the use of tradenames often obscures the chemical designation. In addition, in only a limited sense is the relationship between the type of materials being joined and the chemical type of the modified compounds a factor in selecting the adhesive.

These new adhesive "alloys" include: phenolic elastomers (e.g., phenolic-neoprene, phenolic-Buna N); vinyl phenolics (phenolic-vinyl, phenolic-polyvinyl butyral, phenolic-polyvinyl formal); modified epoxies (epoxy-phenolic, epoxy-polyamide, epoxy-polysulfide).

The other four tables apply to the single-resin adhesives as well as to these new modified compounds. In addition there are two factors which must be given more attention than the tables indicate:

**Time.** All classifications (as well as tack and bond strength properties) are related to time in various ways—shelf and pot life, tack life, length of time of application of heat and pressure, time lapse before handling parts, time lapse before end service.

**End service conditions.** Only by knowing and considering all the factors of end service, as well as all factors discussed in the tables here, can the formulator recommend a particular chemical composition with particular bonding requirements, vehicle, form and flowability. New formulations are devised where necessary. Also, it is not uncommon to use *two* adhesive formulations (allowing the first to dry before applying the second) to obtain the desirable advantages of each, or to obviate an undesirable effect of contact between the second adhesive and the surface.




***Some examples** of good joint design.*

## Definitions

**Emulsion.** Adhesive type in which basic resin is a water-insoluble liquid (or solid particles) stably dispersed in water. Emulsifying agents are added to decrease surface tension. Some emulsions also contain a small amount of solvents (5%) to increase tackiness and improve water resistance.

**Glue line thickness.** Thickness of the fully dried adhesive layer.

**Lay down thickness.** Thickness of the applied wet adhesive coating.

**100% reactive.** Also "100% solids." Generally a modified epoxy resin-base paste, this adhesive type contains no solvent and cures at room temperature or higher.

**Pot life.** Length of time adhesive remains usable after being put into serviceable condition.

**Shelf life.** Length of time adhesive can be stored without deterioration (also known as "can stability").

**Solvent dispersion.** Adhesive type in which basic resin is in solvent solution and bonding is done by evaporation of the solvent (solvent release). A wide variety of solvents are used: ketones, toluol, naphtha, hydrocarbons, alcohol, acetone, etc. Solvent content generally varies from 10 to 50% for thermoplastic and thermosetting adhesives, from 50 to 95% for elastomeric.

**Tack.** The charateristic ("stickiness") that causes one surface, coated with adhesive, to adhere to another upon contact. Tack time may range from a few seconds to an almost indefinite period.

**Wet strength.** The bond strength realized immediately after adhesive-coated surfaces are joined and before cure occurs.

## Methods

Adhesive bonding lends itself to complex automatic set-ups using spray guns, flow guns, paint rollers, etc. to apply the adhesive; pressure rolls, heavy presses, ovens, autoclaves, etc. to develop the bond. However, hand bonding with solvent-dispersed adhesives is common, and an understanding of the five steps involved can be applied to other methods:

1. **Surface preparation**—Surfaces should be smooth; must be clean and dry. Precleaning generally involves abrasive or chemical cleaning (ceramics, metals), light sanding (wood), chemical removal of mold release or plasticizer bloom (rubber, plastics), etc.

2. **Adhesive preparation**—Placing adhesive in a serviceable state may require mixing, thinning, reactivating, etc.

3. **Applying adhesive**—Varies from sticking coated film or tape or nameplate in place to use of trowel, squeeze bottle, hand roller, brush, etc.

**1—CLASSIFIED BY CHEMICAL COMPOSITION GROUP**

| Type → | Natural | Thermoplastic | Thermosetting | Elastomeric |
|---|---|---|---|---|
| Examples of Type | Casein, blood albumin, hide, bone, fish, starch (plain and modified); rosin, shellac, asphalt; inorganic (sodium silicate, litharge-glycerin) | Polyvinyl acetate, polyvinyl alcohol, acrylic, cellulose nitrate, asphalt, oleoresin | Phenolic, resorcinol, phenol-resorcinol, epoxy, urea, melamine, alkyd | Natural rubber, reclaim rubber, butadiene-styrene (GR-S), neoprene, acrylonitrile-butadiene (Buna-N), silicone |
| Most Used Form | Liquid, powder | Liquid, some dry film | Liquid, but all forms common | Liquid, some tape |
| Common Further Classifications | By vehicle (water emulsion is most common but many types are solvent dispersions) | By vehicle (most are solvent dispersions or water emulsions) | By bonding requirements (heat and/or pressure most common but some are catalyst types) | By bonding req (all are common). Also by vehicle (most are solvent dispersions or water emulsions) |
| Bond Characteristics | Wide range, but generally low strength; good res to heat, chemicals | Good to 150–200 F; poor creep strength; fair peel strength | Good to 200–500 F; good creep strength; fair peel strength | Good to 150–400 F; never melt completely; low strength; high flexibility |
| Major Type of Use | Household, general purpose, quick set, long shelf life | Unstressed joints; designs with caps, overlaps, stiffeners | Stressed joints at slightly elevated temp | Unstressed joints on lightweight materials; joints in flexure |
| Materials Most Commonly Bonded | Wood (furniture), paper, cork, liners, packaging (food), textiles, some metals and plastics. Industrial uses giving way to newer types, esp in woodworking | Formulation range covers all materials, but emphasis on nonmetallics, esp wood, leather, cork, paper, etc., because these are less likely to require stressed joints | Depends greatly on specific type: epoxies for dissimilar materials and plastics; phenolics for metal, glass and wood; ureas and melamines extensively for wood; alkyds for metal laminations. | Few used "straight" for wood, rubber, fabric, foil, paper, leather, plastics films; also as tapes. Most modified with synthetic resins |

**2—CLASSIFIED BY BONDING TYPE[a]**

| General Type ↓ | Specific Types Available[b] | Forms Used | Remarks |
|---|---|---|---|
| Heat | Rm temp to 450-F types available; 250 to 350-F types most common | Formulated in all forms; liquid most common | Applying heat will usually increase the bond strength of any adhesive, even rm temp types |
| Pressure | Contact to 500-psi types available; 25 to 200-psi types most common | Formulated in all forms; liquid + powder most common | Pressure types usually have greater strength (not true of modified epoxies) |
| Time | Types requiring a few seconds to a week available; ½ to 24-hr types most common | Formulated in all forms | Time required varies with pressure and temp applied and immediate strength |
| Catalyst | Extremely varied in terms of chemical cataiyst required; may also contain thinners, etc. | Two components—paste (or liquid) + liquid | Sometimes catalyst types may require elevated temp (<212 F) and/or pressure instead of, or in addition to, a chemical agent |
| Vulcanizing | Varied types requiring addition of a chemical agent (usually sulfur); may also contain a catalyst | Two liquid components | Premixed types requiring 250 to 350 F for vulcanization are available |
| Reactivation | Types requiring heat or solvent or second coating of adhesive | Dry film or previously applied liquid | Heat type is best for nonporous surfaces and/or max strength |

[a] Formulations may be a combination of two or more of these types.
[b] Types stated as being most common refer to modified or "alloy" adhesive compounds.

**4. Assembly**—Accomplished during tack life of adhesive (5 min to 1 hr for porous surfaces, but can be extended) or after reactivating dried coating.

**5. Bond development**—Drying out of the solvent usually takes 1 to 60 min. Heat can be applied by warm air, infrared lamps or hot plate; pressure by

## Adhesives

**3—CLASSIFIED BY VEHICLE***

| Type → | Solvent Dispersion | Water Emulsion | 100% Reactive ("100% solids") |
|---|---|---|---|
| Form | Liquids, pastes, tapes, supported films | Liquids | Pastes, films |
| Adhesive Alloy | Elastomer (rubber or vinyl butyral) + thermosetting resin (phenolic, sometimes epoxy or alkyd) | Reclaimed rubber + asphalt; milk latex | Usually modified epoxies (others for films) |
| Bonding Requirements | Usually pressure and/or heat, solvents (reactivation type) | Heat and/or pressure | Contact pressure; choice of rm temp or heat curing |
| Advantages | Flowability; easy to apply in film or tape form and from dispensing bottles. Can be reactivated after drying. Allows widest choice to formulator | Most inexpensive of the three. Eliminates fire hazard. Consistency can be varied by adding water | No time wait for solvent release. Eliminates fire hazard. No attack on vulnerable adherends. High heat resistance. Fills voids |
| Limitations | Care must be taken to allow for solvent release if both surfaces are nonporous (not usually recommended). Solvent may interact unfavorably with certain plastics | Usually limited to bonding where at least one surface is nonporous. Some types require high pressure. Freezing damages bonding properties | Peel, stretch and impact properties not usually as high as in others. Not freely flowing. Usually supplied as two-component adhesive requiring mixing. High shear strength falls rapidly above specified temp |
| Remarks | Elastomer adds flexibility, peel and impact strength | Curing characteristics highly influenced by added modifiers | Highly suited for metal-to-metal bonds, electrical uses |

* This method of classification is the most common for modified compounds, but omits "contact-bond" and "pressure-sensitive" adhesives. Contact-bond adhesives adhere to themselves for a specified period of time after the coating has dried. Pressure-sensitive types adhere to almost any surface for an almost indefinite period of time after drying.

**4—CLASSIFIED BY FORM**

| Type ↓ | Remarks | Advantages |
|---|---|---|
| **Liquid** | Most common form; practically every formulation available. Principally solvent-dispersed | Easy to apply. Viscosity often under control of user. Major form for hand application |
| **Paste** | Wide range of consistencies. Limited formulations; principally 100% solids modified epoxies | Lends itself to high production set-ups because of less time wait. High shear and creep strengths |
| **Powder** | Require mixing or heating to activate curing | Longer shelf life; mixed in quantities needed |
| **Mastic** | Applied with trowel | Void-filling, nonflowing |
| **Film, tape** | Limited to flat surfaces, wide range of curing ease | Quick and easy application. No waste or runover; uniform thickness |
| **Other** | Rods, supported tapes, precoated copper for printed circuits, etc. | Ease of application and cure for particular use |

**5—CLASSIFIED BY FLOWABILITY***

| Type ↓ | Form or Vehicle Type | Advantages |
|---|---|---|
| **Flow** | Liquid, light or heated pastes, solvent dispersion, water emulsion | Fills crevices, fills complex joints, evens glue line, smooths surface |
| **Nonflow** | Heavy paste, trowelable mastic, void-filling epoxy, 100% solids | Applies vertically, requires no "clean-up," fills voids and gaps, does not sag |

* There is no fine line of distinction between these types. In addition, flowability is affected by such factors as: temperature, pressure, joint design, time left standing, mixing of catalysts or solvents.

weighted hand rollers, metal weights or squeeze rolls. With nonporous surfaces, solvent must be dried out before final assembly pressure; for such application heat reactivation types are often used (applying heat and/or pressure after assembly of dried coated parts), but stronger bonds are developed by using 100%-reactive adhesives rather than solvent-dispersed.

### Joint Design

Joints should be designed to keep the adhesive in shear and avoid cleavage and peel stresses. Typical good joint designs are shown by the accompanying sketches.

The type of strength under consideration (particularly peel vs shear) is extremely important in adhesive bonding.

Joint properties are also a function of the thickness of the glue line. Shear and creep strength are highest for thin films (0.001 to 0.003 in.), but heavier films may exhibit higher flexibility, toughness and cleavage strength.

Because there are so many factors involved in adhesive selection, compromise may be necessary. To aid the formulator in making this compromise, and to minimize cost, safety factors included in specifications should be only as high as absolutely necessary.

# Mechanical Fasteners

Mechanical fastening is the most versatile and most widely used method for joining materials and parts. In the broadest sense, mechanical fasteners can be classified in two groups: threaded types (semipermanent) and rivets (permanent).

### Threaded Fasteners

**Types.** The accompanying table describes the most common types of threaded fasteners (including washers). Some other types include:

*Screws*—In addition to variations (e.g., spanner heads, wing heads, split points), of every screw described, there are many special types, such as: sealing, twin head, one-way set and load-indicating.

*Bolts*—Many special head variations are available for the bolts described. Two important types not listed are sealing bolts (designed with an integral rubber washer under the head) and blind bolts (expander nut pulled back into sleeve by hydraulic gun, then core bolt inserted). Still more specialized bolts include: track, blow, tap, bent, load-indicating, crating, rib, and drive and locking stud bolts.

*Nuts*—There are nuts to mate with almost every type of bolt described. Other types include: acorn, anchor, clinch weldments (attached by spot welding), roofing, wing or thumb, and grommets.

*Washers*—Special types include: countersunk, sealing, sleeve, load-indicating, pipe and laminated.

**Thread series.** Most common threads are designated "Unified and American" and are either "coarse" or "fine," depending on the number of threads per inch for a specific diameter. The coarse series is for general use where quick assembly is desired; the fine series for aeronautical and similar work. Other series (e.g., 8-thread), as well as other standards (e.g., Whitworth), are in use.

**Thread class.** Class refers to the tolerance in manufacture and to the allowances permissible. The majority of screws and bolts are produced to class 2A (external tolerances and positive allowances); nuts to 2B (internal tolerances). Where closeness of fit is required, classes 3A and 3B may be used. Various fits are obtained by combining male and female threads of different classes.

**Materials.** Although the use of low carbon steel is widespread, all common metals, as well as some thermoplastics, are used in critical applications. To obviate galvanic corrosion, it is often desirable to use fasteners made from a material similar to those being joined. However, the corrosive effect must be weighed against such factors as increased strength and greater holding power.

*Screws*—Carbon and stainless steels, brass, silicon bronze and aluminum are often standard or available on order. Special materials available in limited types include die cast zinc alloys and several thermoplastics (nylon is most common). Zinc and cadmium-plated screws are often standard, and other electroplates are available on order. Other finishes and coatings include anodized, carbonized and black oxide.

*Bolts and nuts*—Carbon, alloy and stainless steels are standard for almost every type, but brass, naval bronze, monel and aluminum are often standard as well. Special materials available in some types include: malleable iron, silicon bronze, titanium, sintered brass, nylon and other thermoplastics. Finishes and coatings include those available for screws. Nuts, however, are often supplied with one of the following additional finishes: nickel and silver-plated, molybdenum disulfide, chromate, phosphate, and chromium oxide diffusion.

*Washers*—Most standard nut materials are also used for washers. Special materials include chromium-molybdenum steel, galvanized steel, vulcanized fibre and extruded nylon. Sealing washers generally are rubber—natural, silicone, neoprene or nitrile. Standard electroplated finish is usually cadmium, but zinc, nickel, tin, copper and chromium are not uncommon. Other finishes include phosphate and oil.

**Design.** Details of design depend upon many factors, including the type, style and material of the fastener which has been selected after consideration of end service conditions, materials being joined, speed and ease of assembly required, and ease and frequency of disassembly required. Loading should be in shear rather than tension. When assembly of the fastener requires that pressure, sharp blows or torque be applied to one side of the joint, that side should be the one having the thicker or harder material.

**Descriptive nomenclature.** Threaded fasteners are available with many types of shanks, heads, locking devices, etc.—some standardized and many not—which makes it impractical to define the hundreds of terms used. In addition, fastener terminology is apt to be overlapping, making it difficult, in theory, to distinguish between such items as bolts and screws, or machine screws and certain cap screws. Recent standards, for instance, include stove bolts with machine screws.

In the accompanying tables types have been distinguished according to general practice, rather than theory, as much as possible. In addition, the word "top" has been coined. Industry uses the word "head" for two purposes: to refer to the shape (generally as viewed from the side), and to refer to the design for a particular tool (generally recognizable by viewing from the top). The word "top" used in the tables refers to the latter. For example, a slotted round head (round as viewed from the top and slotted on top for a conventional screwdriver) is listed here as: top—slotted, head—round.

### Rivets

Riveting is the fastest production fastening method of producing fairly strong joints with unskilled labor, yet with a high degree of consistency. Rivets are driven either hot or cold, by hammering or peening or by applying steady pressure from one or both sides. The shear strength of solid rivet joints is equal to or higher than that of most common threaded fasteners. Tubular and split are lower in strength, particularly tensile.

Design factors are similar to those for threaded fasteners. Joints are either lap or butt (using butt strap). Minimum recommended rivet spacing is usually three times the body diameter of the rivet. Allowable distances from edges are usually based on the rivet body diameter; 1½D for hot-driven rivets and 2D for cold-driven.

Materials from which rivets are fabricated include iron, low carbon steel, stainless steel, brass, copper, monel, aluminum, nickel silver and several thermoplastics. Coatings and finishes of all types can be ordered.

The table on p 453 describes the most common types of rivets.

***tables start on next page***

## Mechanical Fasteners

**THREADED FASTENERS—SCREWS**

| Type ↓ | Description | Made of . . . | Selection Features | Uses |
|---|---|---|---|---|
| **Wood** | Top—slotted or cross-recessed. Head—flat, round or oval. Thread—single, some double; point—gimlet. Also drive screws, hanger bolts, dowel screws | Low and medium carbon steels; alloy and stainless steel, monel, others | General use | Wood, and thin sheets of other material to wood |
| **Cap** | Top—hex or fluted socket; head—smooth or knurled. Top—slotted; head—round, flat, fillister or hex. Thread—coarse or fine; 8-thread; point-chamfer. Also top—plain; head—hex or knurled | Carbon and stainless steel, brass, bronze, monel, aluminum | General use with tapped holes or nuts. Shank usually not fully threaded. Socket type (most used) has closer fit than machine screws | Fastening metal parts and components |
| **Machine** | Top—slotted or cross-recessed; head—round, flat, oval, undercut (flat or oval), fillister, truss, binding or pan. Also hex heads, tops plain or slotted. Thread—coarse or fine; point—sheared | Carbon and stainless steel, brass, silicon bronze, monel, aluminum | Same as cap, but usually full-thread shank and smaller dia. Slotted type most used, generally with nut | Same as cap |
| **Tapping** (thread-forming) | ASA "A": Top—slotted or recessed; head—flat, oval, round, pan, fillister, truss or hex; thread—spaced; point—gimlet. "B": Same but blunt point. "BP": Same but cone point. "C": Same but blunt tapered point and machine thread | Case hardened steel; others on special order | A—general sheet metal screw; B—heavier duty; BP—misaligned parts; C—higher strength | All—Sheet metal, wood, asbestos, cloth to sheet metal. C—Cast iron, die cast zinc, steel, bronze and brass forgings, plastics |
| | Drive screws. 1) Top—plain; head—round; point—dog; thread—multiple with large helix angle. 2) Top—plain; head—pan; point—cone; thread—annular in upper section, but lower section has multiple threads with large helix angle | Case hardened steel; others on special order | Forms mating thread as hammered or pressed; can be applied with hopper-fed machines | Permanent fastenings. 1) Castings, heavy-gage sheet, plastics. 2) Fabric, leather or fiber to sheet metal |
| **Thread-Cutting** | ASA "D", "F", "G" and "T": Top—slotted or recessed; head—flat, oval, round, pan, truss or hex; thread—machine; point—blunt. Types differ in cutting edge: D—one off-center slot; F—several flutes; C—one centered through-slot; T—one wide slot. ASA "BF", "BG" and "BT" similar to F, G and T, respectively, but have spaced thread | Case hardened steel; stainless steel on special order | Minimum driving torque; fewer chips; increased resistance to stripping out | As above, but thin sections, particularly bosses in brittle plastics, plywood |
| **Lock** | Various proprietary types, such as: 1) preassembled lead washer; 2) variation of A.N. thread form; 3) longitudinal insert; 4) nylon pellet insert; and 5) annular expansion insert. Other types include: preassembled screw and lock washer, screw with locking teeth under head, slotted head fitting into counterbored hole with insert forced into slot. Also, liquid sealants used with standard screws | 1—Heat treated alloy steel. 2—All std screw mtls. 3—Steel (incl stainless), brass, aluminum; insert is fluorocarbon plastic. 4—Carbon and stainless steel, aluminum alloy, brass, bronze. 5—Heat treated alloy steel; insert is bronze | 1—Washer extrudes around tapered head. 2—Locks on full length of thread by reforming mating thread. 3—Insert does not project, has gradual torque build-up. 4—Insert projects slightly, locks whether or not screw is seated. 5—Insert expands when compressed, remains when screw is removed | Widely used, esp in mass production. Various types allow joining all metals and many plastics. Particular use depends on such factors as: permanent or disassembly; ease of assembly; amount of torque to assemble or disassemble; type of stress—rotational, vibration, thermal; sealing properties |

## THREADED FASTENERS—BOLTS AND NUTS

| Type ↓ | Description | Made of . . . | Selection Features | Uses |
|---|---|---|---|---|
| **Regular** (general use) | External hexagon or square head, generally used with nut of same shape. "Regular"—unfinished (not machined on any surface except threads); coarse threads. "Regular semifinished"—bolt heads and nuts are machined on bearing surface to provide washer face (or nuts may have chamfered corners); coarse threads. "Finished"—same as regular semifinished but closer body tolerance; threads—coarse, fine and 8-thread. Std. machine screw nut is "regular" | Carbon and alloy steel, stainless steel, brass, naval bronze, monel, aluminum | Longer bolts are similar to hexagon cap screws, shorter to hexagon machine screws, but the hex head is more common with bolts, as is the use of nuts. Bolts come in greater standard lengths, are sturdier and are classified differently | Widely used for all materials. For larger parts and greater stresses than screws. Where material too soft or hard, or too thin, to be tapped. Where threaded shanks easily accessible |
| **Jam Nut** | Similar to Regular or Heavy, but thinner | Same as above | Higher shear str; lower ten str than above | Often used with full nut for locking action |
| **Lag Bolt** | Head—square; point—gimlet or cone. Also known as lag screw | Low carbon steel | — | Fasten wood together or any material to masonry |
| **Round Head Bolt** | Two body styles (std dia and undersized) with coarse threads. Bolts include: 1) round head, square neck; 2) round head, short square neck; 3) round head, ribbed neck; 4) round head, fin neck; 5) 114-deg-countersunk square neck; 6) round head; 7) elevator (flat, large dia head; square neck); 8) ribbed head—slotted and unslotted; 9) step (like elevator but round head); 10) countersunk | Carbon and alloy steel, stainless steel, brass, naval bronze, monel, aluminum | These bolts differ in the method used to prevent rotation during bolting. Each is inserted in a hole which mates with the neck. Head types are selected by appearance or need for flush tops | For 1) wood, 2) steel, 3) hard wood and plastics, 4) wood, 5) wood, 6) any material where there is no other way to prevent rotation, 7) soft materials, 8) flooring, 9) resilient materials to steel, 10) metal to wood |
| **Stud Bolt** (stud) | A stud is a rod threaded either completely or on both ends. Types include: tap end (one end to produce interference fit in tapped hole, other for nut); double end (both ends for nuts); continuous thread; hangar bolt (one end has lag screw thread) | Low carbon steel | Advantageous where length adjustment desirable | Widely used for castings (permanently assembled) and for soft metal and plastic parts |
| **Place Bolt** | Flexible zone is formed by slotted segments in the upper face of a hex bolt head and a circular recess in the lower face, providing a controlled spring action which increases elastic elongation | Carbon and alloy steel; others available | Provides resistance to loosening by vibration and minimizes fatigue failure | Cylinder heads, flywheel housings, bearings (cap screw), connecting rods |
| **Locknut** | Huge variety of proprietary locknuts, most of which can be classified as one of the following types: 1) free-spinning (no locking action until seating begins, e.g., integral toothed washers), 2) prevailing torque (locking depends on some form of interference between male and female threads, e.g., deforming threads or forcing lead or angle), 3) spring action (designed to take advantage of natural spring of the material or with auxiliary springs, e.g., slotted segments; arched base with prongs to lock against threads) | Nuts—carbon steel generally std; also stainless, brass, monel, aluminum. Springs—heat treated spring steel usually std; also stainless, brass, phosphor bronze, beryllium copper. Inserts—bronze usually std; also brass, aluminum, steel | Locknuts remain tight under vibration and replace the use of wire or cotter pins in a hole drilled through bolt and nut. Each type designed for specific use in terms of materials, end service conditions, ease of assembly, etc. | Mass produced automobiles, appliances, machinery, aircraft, furniture, toys, etc. |

*continued on next page*

## Mechanical Fasteners

**THREADED FASTENERS—WASHERS AND INSERTS**

| Type ↓ | Description | Made of . . . | Selection Features | Uses |
|---|---|---|---|---|
| Plain Washer | Plain, flat, circular washer standardized in o.d. and i.d. dimensions (ASAB27.2–1953) and with suggested thicknesses. Form series are: light, medium, heavy, extra heavy | Almost all materials used for nuts | Provide increased bearing surface for bolt heads or nuts, thus distributing load over larger area. Also prevent marring, improve appearance | Widely used with nuts and bolts |
| Lock Washer | Split spring type. Washer is split and shaped like a single turn of a slight helix. Free height is about twice the washer thickness; gap is small enough to prevent entangling. Same four series as plain washers | Carbon steel, stainless 302 or 420, aluminum-zinc alloy, phosphor and silicon bronze, K monel. Not all materials in all four series | Prevents loosening of bolt under vibration. Split-spring type allows occasional disassembly and reassembly; tang of helix may mar work surface | Widely used for most plain threaded screws and bolts |
| | Tooth type. Teeth on i.d., o.d. or both. Variety of shapes and tooth types designed for specific uses | Carbon steel, phosphor bronze | Same as above, but thinner than split-spring, not recommended for frequent disassembly | External tooth type for bolts; internal tooth type for screws |
| | Spring type. Some proprietary types: domed, conical, waved, countersunk, cap, folded rim, tab, irregular hole, wood spring | Medium carbon and stainless steel, bronze, aluminum, beryllium, copper, K monel | Provides strong locking with varied other features | Special uses, generally on softer materials |
| Insert | May be threaded bushings, studs, etc., cast or molded integrally with part. Many proprietary inserts are molded in or inserted after part is formed. Noncircular cross sections resist turning; undercuts resist tensile pull. Some types are: 1) slotted body, exterior fins, 2) slotted and tapered body containing four-eared disk below threaded portion, 3) spool-shaped spacer, 4) helical coil of diamond-shaped wire (also locking type with center loop of coil octagon-shaped), 5) disk-shaped with edge groove around middle, 6) threaded, with embedded nylon pellet, 7) two-piece: threaded insert and lock ring | 1) Aluminum alloy, 2) brass, 3) aluminum alloy, 4) stainless, phosphor bronze, Hastelloy C, 5) brass, steel, stainless, aluminum, 6) low carbon steel, 7) low carbon steel. Most inserts can be obtained in other materials, e.g., brass, bronze, aluminum, monel | Added strength for soft materials. 1) Allows expansion pressure against hole and screw. 2) Disk is forced down to spread four tapered segments. 3) Through-bolt or threaded. 4) Coil has both internal and external thread; inserted in tapped hole. 5) Locked by swaging tool. 6) Uses standard screwdriver. 7) Outer teeth of lock ring broach into parent material | Limited to parts thick enough to hold insert. 1) Wood, plastics, soft metals. 2) Replace molded-in inserts. 3) Sandwich panels. 4) Where weight and wear are problems; used in damaged tapped holes. 5) Plastics sheet, soft sheet metal. 6) Nonferrous metals. 7) Hard materials (resists vibration and stress); soft materials (resists wear) |

## RIVETS, STITCHING AND STAPLING

| Type ↓ | Description | Uses |
|---|---|---|
| **RIVETS** | | |
| Large Solid | Dia from ½–1¼ in. Head—button, high button, cone, pan or countersunk (flat or round). Neck—straight or swell (exc countersunk). Special heads include: machine, globe, wheel, trunk. Wrought iron and steel are std mtls; others available | High production, permanent assembly operations requiring high tensile and shear strength and generally not requiring airtight or watertight joints. Aircraft, ships, trains, bus and truck bodies, etc. |
| Small Solid | Head—flat, countersunk, button, pan, truss, tinners', coopers' or belt | As above (generally cold riveting is used on small rivets, hot riveting on large) |
| Semi-Tubular | Shallow hole, extruded or drilled in shanks, does not exceed shank dia. Variety of heads include: oval, flat countersunk, tinners', cone | Where stress is low, or primarily shear. Metals, ceramics, hard plastics and woods; through predrilled or prepunched holes. Aircraft, cameras, toys |
| Tubular | Hole in shank is deeper than dia but less than ½ in. Rivet compresses material within shank. Head variety same as above | Where stress is low, or primarily shear. Leather, soft plastics, rubber, soft woods, fabrics. Leather cases, golf bags, sheet metal |
| Split | Slot milled in shank forms two sharp prongs that pierce material without weakening it | Where stress is low, or primarily shear. Light-gage metal, plastics, wood, fibreboard, leather |
| Shouldered | Shoulder beneath head is made to spec. Either coldformed or coldheaded and turned | Where pivot or bearing surface req within joined members. Automotive parts, vending machines |
| Blind | Proprietary types, of which most are one of these: 1) sleeve—either hollow (mandrel pulled back through; may be plugged if desired), or self-plugging (after mandrel is pulled through it is trimmed off to leave solid rivet); 2) pin driven through tapered hole in rivet to expand it, then lip peened over pin head; 3) type for which a special assembly tool is basic, e.g., a gun grips pull-through mandrel, clinches rivet, continues to pull until head or stem breaks; 4) explosive charge contained within shank is detonated (by riveting iron, etc.) to expand rivet to fill hole and form bulb on end. Materials are: cadmium-plated steel, aluminum alloy, brass, stainless, monel, etc. | Where backing up the rivet is impractical, usually due to inaccessibility. 1) Lends itself esp to automatic setting; hollow is not as strong but can be plugged by any mtl desired and with umbrella head to match design. 2) High shear str, good ten str. 3) High assembly rate; rivet has high str clinch but is not completely hole-filling. 4) Extremely high assembly rate; widely used to fasten both metals and nonmetallics; nearly equiv in str to solid rivet |
| Other | Some special rivets are: outside prong, compression, decorative spot, precious metal, brake lining | Special uses |
| **METAL STITCHING AND STAPLING** | | |
| Stitching and Stapling | Joining two or more materials with 18-gage wire fed from a coil, cut to length, formed, driven through and clinched. High assembly rate, but limited to thin parts, e.g., joining 0.093-in. aluminum strips. Loop clinches are best for nonstructural joints, flat clinches for stressed. Stapling differs in using preformed fasteners. Std mtls include high carbon steel, stainless, and phosphor bronze | For sheet and strip stock of all materials, but preferably joining soft nonmetallics to metal. Also sandwich materials |

# Characteristics of typical Raybestos-Manhattan Ray-BOND® Adhesives

| NUMBER | TYPE | CHARACTERISTICS | USES |
|---|---|---|---|
| R-81001<br>R-81002<br>R-81008 | Thermosetting synthetic rubber, synthetic resin; heat setting. Solids range from 18 to 40%. | Flexible, resistant to oils, solvents; requires heat and pressure for cure. | For bonding metals, plastics, friction materials to themselves or to each other. Not recommended for use on assemblies where bond line temp. might exceed 400°F for prolonged periods in application. Short term to 600°F. |
| R-82004 | Synthetic rubber, synthetic resin; emulsion adhesive; cold setting; solvent evaporation type. | Flexible, good peel strength, medium drying; gains strength upon loss of solvent; exhibits good strength up to 270°F for nonstructural applications. | For bonding nonporous or semiporous materials to themselves and to various metals—plastics, decorative metal parts, leather, etc. |
| R-82005<br>R-82006<br>R-82007<br>R-82008 | Synthetic rubber, synthetic resin; solvent evaporation type. Solids range from 17 to 30%. | Flexible, good peel strength, quick drying; gains strength upon loss of solvent; not to be used on parts that might be subjected to temperatures in excess of 180°F; sprays well. | General laminating adhesive for plywood, chipboard, hardboard, paper and metal honeycomb, composition base materials to each other or to rigid plastic and metal. |
| R-82013 | Synthetic rubber, synthetic resin; cold setting or heat setting. | Flexible, good peel strength, quick drying; gains strength upon loss of solvent. | General-purpose adhesive for nonstructural parts. Vinyl (PVC) to plastic, metal, cloth, and buna-N type rubbers to metal or to themselves. |
| R-84001<br>R-84002 | Synthetic resin; hot melt type. | Flexible, to be heated to 250-300°F and applied. Strength obtained upon cooling. Ball and ring melt test, 205°F. | General purpose adhesive for bonding most materials including mylar and polyethylene. Recommended as a nonstructural adhesive for applications where the bond line temperature will not exceed 200°F. |
| R-84029 | Synthetic resin; heat setting. | Heat resistant to 650°F; some degree of flexibility; resistant to oils, solvents, water, brake fluids. | For bonding friction material to friction material or to steel where some degree of flexibility is desired. |
| R-86008 | Synthetic resin; 2-component system. | Good electrical properties, low shrinkage. Heat distortion point of 178°F. Pot life 30 min. | Casting, encapsulating and potting. Metal to metal, ceramic to metal, glass to metal. |
| R-86009 | Synthetic resin; 2-component system. | Salt water resistant; semi-flexible; room temperature curing. | Bonding rubber to rubber, metal or wood. Cyclizing necessary for optimum results. |
| R-86020 | Special synthetic resin; single component system. | High tensile strength; excellent resistance to most chemical acids and alkalies. Heat resistant to 400°F; unlimited pot life. | For bonding metal to metal, ceramic to metal, metal to plastics. |
| R-86044 | Special synthetic resin base; 2-component system. | Room temp. curing; 40 min. working life. | For bonding etched Teflon to metal, glass to glass, where optimum chemical resistance is desired. |
| R-87001 | Synthetic rubber base. | Good adhesion; high peel strength up to 270°F; contains no flammable solvents. | For bonding fabrics to fabrics. |

## RAYBESTOS-MANHATTAN manufactures these 7 classes of adhesives, coatings and sealers:

1. Heat setting, synthetic resin adhesives, coatings, and sealers (not epoxy)
2. Cold setting, synthetic resin adhesives (not epoxy)
3. Heat setting, synthetic resin, synthetic rubber adhesives
4. Cold setting, synthetic resin, synthetic rubber adhesives
5. Rubber base adhesives
6. Synthetic resin sealants, and coatings (not epoxy)
7. Epoxy base adhesives, coatings and sealers; casting, encapsulating and potting compounds

Experienced Raybestos-Manhattan technicians will give you the benefits of more than 20 years of experience in the production of bonded assemblies and the manufacture of adhesives, coatings and sealers. They will provide you with full technical information and recommendations on the latest methods proved most efficient in many successful applications. Why not call on Raybestos-Manhattan engineers today to cut costs or improve production in your operations.




R/M Bulletin No. 701 contains helpful engineering information on Ray-Bond adhesives, protective coatings and sealers. Write for your free copy.

RAYBESTOS-MANHATTAN, INC.

ADHESIVES DEPARTMENT, Bridgeport, Conn. • Chicago 31 • Detroit 2 • Cleveland 16 • Los Angeles 58

For more information, turn to Reader Service card, circle No. 459

# CUT TOTAL BRAZING COSTS *BY AS MUCH AS 75%* WITH SILVALOY PREFORMS




***CHECK THESE ADVANTAGES OF SILVALOY PREFORMS.***

1. Accurate control of quantity of alloy used on a job.
2. Enables operator to maintain uniform quality in brazing operation.
3. Allows alloy to be placed internally to flow outward to joint boundaries—aids in obtaining positive filling of the joint and a quick visual inspection for quality.
4. Simplifies feeding of alloy all around a diameter.
5. Internal placement of Silvaloy in large joints where flow distances are excessive.
6. Permits mechanization of brazing operation through furnace, induction, dip, resistance, gas burner or other suitable heating methods.
7. Silvaloy rings, segments, wire shapes, slugs, washers, discs, powders and plymetals are available *to your exact specifications!*

A Silvaloy technical expert will be glad to assist in planning for preforms. He can help you to save as much as 40% in labor costs—as much as 35% in brazing materials—speed production and improve brazing results in your plant. Call or write the Silvaloy distributor in your area.


***SEND FOR "A COMPLETE GUIDE TO SUCCESSFUL SILVER BRAZING"***

**ENGELHARD**
**INDUSTRIES, INC.**
AMERICAN PLATINUM & SILVER DIVISION
231 NEW JERSEY RAILROAD AVE. • NEWARK 5, NEW JERSEY

**SALES OFFICES: SAN FRANCISCO • LOS ANGELES • CHICAGO • NEW YORK • PROVIDENCE • MIAMI • ORLANDO • DALLAS**





SILVALOY DISTRIBUTORS: A.B.C. METALS CORPORATION • DENVER • AUSTIN-HASTINGS COMPANY, INC. • CAMBRIDGE • WORCESTER • HARTFORD • BURDETT OXYGEN COMPANY • CLEVELAND • CINCINNATI • COLUMBUS • AKRON • DAYTON • YOUNGSTOWN • MANSFIELD • FINDLAY • DELTA OXYGEN COMPANY, INC. MEMPHIS • EAGLE METALS COMPANY • SEATTLE • PORTLAND • SPOKANE • NOTTINGHAM STEEL & ALUMINUM DIV. A. M. CASTLE & COMPANY • CLEVELAND OLIVER M. VAN HORN CO., INC. • NEW ORLEANS • FORT WORTH • HOUSTON • PACIFIC METALS COMPANY LTD. • SAN FRANCISCO • SALT LAKE CITY LOS ANGELES • SAN DIEGO • PHOENIX • STEEL SALES CORPORATION • CHICAGO • MINNEAPOLIS • INDIANAPOLIS • KANSAS CITY • GRAND RAPIDS DETROIT • ST. LOUIS • MILWAUKEE • LICENSED CANADIAN MANUFACTURER • ENGELHARD INDUSTRIES OF CANADA, LTD. • TORONTO • MONTREAL

For more information, turn to Reader Service card, circle No. 390

*One*  *of these*

CAN IMPROVE YOUR PRODUCT...

SIX GREAT
# MACLEAN-FOGG
LOCK NUTS

| | | |
|---|---|---|
| MF **UNI-TORQUE** |  | A free starter with lock at the top. Withstands severe vibrations. Cuts assembly time. |
| MF **TWO-WAY** |  | The Lock's in the center of nut. Can be applied from either end. Permits bolt end to be flush with, or below, top of nut. |
| MF OPEN END **CAP NUT** |  | Has two-way center-of-nut lock. Used on furniture, appliances, toys, lawn mowers, tools, etc. |
| MF UNI-TORQUE **FLANGE NUT** |  | Combination lock nut and washer. Use on oversized holes; where extra bearing surface is needed. |
| MF **"WHIZ-LOCK"** FLANGE NUT |  | This one spins on. Serrations take a firm grip on work. Break loose torque higher than seated torque. |
| MF PILOT TYPE **WELD NUT** |  | You can have it with or without lock. Simplifies assemblies by means of self-locating pilot. |

CIRCLE NUMBER FOR ILLUSTRATED CATALOG 


MAC LEAN-FOGG
# MF LOCK NUTS

**MacLean-Fogg Lock Nut Company**
5535 N. WOLCOTT AVENUE
CHICAGO 40, ILLINOIS

1925 35 1960
ANNIVERSARY

For more information, turn to Reader Service card, circle No. 441



No. 16 of a series




## Eastman 910 Adhesive solves another production bottleneck

The A. W. Haydon Company, Waterbury, Connecticut, makes a newly-designed timing device for automatic telephone switchboards.

The nylon timer gears and associated cams had to be molded separately due to their complex shape, then joined on an assembly-line.

Fast-setting, high-strength Eastman 910 Adhesive proved to be the economical, easy-to-use means of bonding these nylon parts.

In assembly, the gear and cam are held in a simple jig and a drop of adhesive is applied. The mating surfaces are brought together and held for a few moments. *Within 10 seconds a strong bond is formed, and the part is assembled into the timer.*

Eastman 910 Adhesive is making possible faster, more economical assembly-line operations and new design approaches for many products. It is ideal where extreme speed of setting is important, or where design requirements involve joining small surfaces, complex mechanical fasteners or heat-sensitive elements.

Eastman 910 Adhesive is used as it comes. No mixing, no heating. Simply spread the adhesive into a thin film between two surfaces. Light manual pressure triggers setting. With most materials, strong bonds are made within minutes.

What production or design problem can this unique adhesive solve for you?




**Bonds Almost Instantly with Contact Pressure**
**No Heat...**
**No Catalyst...**

For a trial quantity (⅓-oz.) send five dollars to Armstrong Cork Co., Industrial Adhesives Div., 9113 Dunbar Street, Lancaster, Pa., or to Eastman Chemical Products, Inc., Chemicals Div., Dept. E-13, Kingsport, Tenn. (Not for drug use)
*See Sweet's 1960 Prod. Des. File, 7/E*

For more information, circle No. 401

# HANDY ALLOY DATA SHEET

HANDY & HARMAN ENGINEERING DEPARTMENT
82 FULTON STREET, NEW YORK 38, N. Y.

ALLOY LIST

## Handy & Harman Silver Brazing Alloys

## ...The COMPLETE line that meets all specifications and production needs

Need to join any combinations of metals—ferrous and nonferrous? Investigate the vast number of products, assemblies and parts that are being joined better by silver brazing alloys. Handy & Harman, the Number One Source of, and Authority On Brazing Alloys and Methods makes—and makes readily available—the following silver brazing alloys:

**HANDY & HARMAN SILVER BRAZING ALLOYS**

| NAME | COMPOSITION PERCENTAGE Ag | Cu | Zn | Other | MELTING POINT °F | °C | FLOW POINT °F | °C | TROY OUNCES PER CU. IN. |
|---|---|---|---|---|---|---|---|---|---|
| EASY-FLO | 50 | 15½ | 16½ | (18 Cd)† | 1160 | 625 | 1175 | 635 | 5.0 |
| EASY-FLO 3 | 50 | 15½ | 15½ | (16 Cd-3 Ni) | 1170 | 630 | 1270 | 690 | 5.0 |
| EASY-FLO 45 | 45 | 15 | 16 | (24 Cd) | 1125 | 605 | 1145 | 620 | 4.9 |
| EASY-FLO 35 | 35 | 26 | 21 | (18 Cd) | 1125 | 605 | 1295 | 700 | 4.9 |
| SIL-FOS | 15 | 80 | | (5 P) | 1185 | 640 | 1300 | 705 | 4.5 |
| SIL-FOS 5 | 5 | 88¾ | | (6¼ P) | 1185 | 640 | 1300 | 705 | 4.4 |
| TEC* | 5 | | | (95 Cd) | 640 | 340 | 740 | 395 | 4.6 |
| TEC-Z* | 5 | | 16.6 | (78.4 Cd) | 480 | 250 | 600 | 315 | 4.5 |
| BRAZE 071 (SN #7)† | 7 | 85 | | (8 Sn) | 1225 | 665 | 1805 | 985 | 4.8 |
| " TL | 9 | 53 | 38 | | 1410 | 765 | 1565 | 850 | 4.5 |
| " ATT | 20 | 45 | 30 | (5 Cd) | 1140 | 615 | 1500 | 815 | 4.6 |
| " 202 (AT SPEC)† | 20 | 45 | 35 | | 1315 | 715 | 1500 | 815 | 4.7 |
| " NE | 25 | 52½ | 22½ | | 1250 | 675 | 1575 | 855 | 4.7 |
| " 251 (AE)† | 25 | 57½ | 17½ | | 1270 | 690 | 1625 | 885 | 4.7 |
| " NT | 30 | 38 | 32 | | 1250 | 675 | 1410 | 765 | 4.7 |
| " DT | 40 | 36 | 24 | | 1235 | 670 | 1415 | 770 | 4.8 |
| " SS | 40 | 30 | 28 | (2 Ni) | 1220 | 660 | 1435 | 780 | 4.8 |
| " 404 (SS-5)† | 40 | 30 | 25 | (5 Ni) | 1220 | 660 | 1580 | 860 | 4.7 |
| " DE | 45 | 30 | 25 | | 1225 | 665 | 1370 | 745 | 4.8 |
| " ETX | 50 | 34 | 16 | | 1250 | 675 | 1425 | 775 | 5.0 |
| " 541 (4772)† | 54 | 40 | 5 | (1 Ni) | 1340 | 725 | 1575 | 855 | 5.1 |
| " 560 (ER)† | 56 | 22 | 17 | (5 Sn) | 1145 | 620 | 1205 | 650 | 5.0 |
| " 580 (EB)† | 57½ | 32½ | | (7 Sn-3 Mn) | 1120 | 605 | 1345 | 730 | 5.1 |
| " RT | 60 | 25 | 15 | | 1245 | 675 | 1325 | 720 | 5.0 |
| " 603 (RT-SN)† | 60 | 30 | | (10 Sn) | 1115 | 600 | 1325 | 720 | 5.2 |
| " 630 (RSNI)† | 63 | 28½ | | (6 Sn-2½ Ni) | 1275 | 690 | 1475 | 800 | 5.1 |
| " EASY | 65 | 20 | 15 | | 1240 | 670 | 1325 | 720 | 5.1 |
| " 655 (RE-MN)† | 65 | 28 | | (5 Mn-2 Ni) | 1385 | 750 | 1560 | 850 | 5.2 |
| " MEDIUM | 70 | 20 | 10 | | 1275 | 690 | 1360 | 740 | 5.1 |
| " BT | 72 | 28 | | | 1435 | 780 | 1435 | 780 | 5.2 |
| " HARD | 75 | 22 | 3 | | 1365 | 740 | 1450 | 790 | 5.3 |
| " 752 (TR #1)† | 75 | | 25 | | 1300 | 705 | 1330 | 720 | 5.1 |
| " IT | 80 | 16 | 4 | | 1340 | 725 | 1490 | 810 | 5.3 |
| " 852 (85 Ag-15 Mn)† | 85 | | | (15 Mn) | 1760 | 960 | 1780 | 970 | 5.1 |
| PREMABRAZE 610 | 61 | 24 | | (15 In) | 1155 | 625 | 1305 | 705 | 5.0 |

*A Solder—Not a Brazing Alloy. †Former Names

Space does not permit listing the many special alloys, formulated for a particular or unique application. Handy & Harman Brazing Engineers and Technical Service are always ready to work closely with you on metal joining problems and methods.

Comprehensive technical literature covering all aspects of brazing methods and alloys awaits your request.

**GET THE FACTS FROM BULLETIN 20**

This informative booklet gives a good picture of silver brazing and its benefits...includes details on alloys, heating methods, joint design and production techniques. Write for your copy.




*Your No. 1 Source of Supply and Authority on Brazing Alloys*

**HANDY & HARMAN**

General Offices: 82 Fulton St., New York 38, N. Y.

Offices and Plants: Bridgeport, Conn. • Chicago, Ill. • Cleveland, Ohio • Dallas, Texas • Detroit, Mich. Los Angeles, Calif. • New York, N. Y. • Providence, R. I. • San Francisco, Calif. • Montreal, Canada • Toronto, Canada

*DISTRIBUTORS IN PRINCIPAL CITIES*

For more information, turn to Reader Service card, circle No. 506



# PICK

## the Bostik number that best answers your Design-Adhesive Needs

| Bostik Adhesive | Principal use* | Characteristics* |
|---|---|---|
| 258 | Fabric to Rubber | Fast break — Quick grab |
| 528-72 | General Purpose Latex<br>Leather to Leather — Paper etc. | High tack — Quick grab |
| 601 | Polyethylene to itself<br>Paper and Foil | Low adhesion — High tack |
| 1007 | Metal primer | Excellent adhesion to metals |
| 1008 A&B | Primer for rigid plastics<br>Neoprene to primed surfaces<br>Neoprene to itself | High tack |
| 1024 A&B | Neoprene to itself<br>Neoprene to primed surfaces | Good heat resistance |
| 1125 A&B | Neoprene to Neoprene | MIL-C-5540 Long-lasting band, long working period |
| 1142 | Neoprene inflatables<br>General purpose Neoprene to itself and to Metal | MIL-A-1154B Excellent bonds |
| 2003 A&B | Natural rubber to itself | MIL-C-5539 Long-lasting bond |
| 2022 | Paper to Paper | Excellent tack — Advertising layouts |
| 2032 A&B | Leather to rubber | Excellent adhesion — good tack |
| 2102 | Pressure sensitive | High solids — High tack-knife coat |
| 2293 | Wallboard and hardboard to concrete and dry wall construction | One way, excellent bond |
| 3035 | General purpose | Permanent bond to many surfaces, including metals |
| 4025 | Butyral fabric to itself | Short tack, excellent adhesion |
| 4034 | Saran to itself and metals<br>General purpose | MIL-C-4003 Good oil resistance |
| 4040 | Vinyl to vinyl and other materials. | Good aging, resistance to discoloration — Long tack |
| 4500 | Metal to Wood | One way heat activation |
| 4585 | General purpose | Good oil, water and detergent resistance |
| 7008 | Metal to Metals | Reactivation by heat used extensively in electronics for speakers |
| 7026 | Metal to plastics<br>Metal to Rigid paper<br>Metal to Metals | Used to bond rigid plastics to metal with heat and pressure |
| 7028 A&B | Metal to plastics<br>Ceramics to other materials<br>Metal primer | Adheres various rubbers to metal without tie cements, heat and pressure required. |
| 1178 | Seam Sealant | Neoprene, black |
| 1179 | Seam Sealant | Neoprene, clear |
| 7058 | Seam Sealant | Vinyl affinity — Good light stability — clear in color |
| 4777-81 | Pressure sensitive coating | Clear in color. Good tack applied by roller coater |

. . . then write for data sheets re: your choice and any others that look promising.

*types include natural, synthetic reclaim rubber and synthetic resin


**Bostik®**
**ADHESIVES**

**BB CHEMICAL COMPANY • 784 MEMORIAL DRIVE • CAMBRIDGE 39, MASSACHUSETTS**

For more information, turn to Reader Service card, circle No. 563

# SETKO self-locking set screws

***WIN FOR YOU EVERY TIME!***




**ONE OF THESE NUMBERS COULD BE YOUR WINNING ANSWER TO:**

- **Increased product reliability**
- **Lower costs**
- **More dependable performance**

Whatever your requirements demand — better holding power, resistance to vibration, ease of application, etc.—chances are you'll find the *right* answer among the many types of self-locking set screws made by Setko. Many of the styles illustrated here can be combined with various head styles, points or locking actions to give you a set screw that will fit your *specific needs best,* at the lowest cost.

Why not join the hundreds of companies who have been winning lower costs and better product performance with the exclusive holding characteristics of Setko self-locking set screws?

**SEND FOR FREE SELECTOR CHART AND TEST SAMPLES!**

Exclusive Setko self-locking set screws selector chart lists over 1,001 possible combinations. Write for your copy and test samples.

SETKO

Send us your specifications for Free Engineering recommendations.



**Set Screw & Mfg. Co.**

**149 Main Street, Bartlett, Illinois**


●Pat. 2,778,265 *Pat. Applied for 822

We specialize in solving puzzling screw problems

For more information, circle No. 465

# ANSWERS to specific fastening problems ...by SIMMONS

**Economy, design flexibility, quick and easy installation, strength, and smooth, dependable action are advantages of these Simmons Fasteners, made for a variety of special applications. Whatever your fastening problem, engineering aid is available from Simmons.**




**HOOK-LOCK**–Springless, positive-locking latch which lies flat against mounting surface, open or closed. Provides high closing pressure and load-carrying capacity. For military as well as commercial container applications.




**SPRING-LOCK**–Perfect, proved blind rivet for removable covers and panels on electric and electronic equipment, sheet-metal automobile parts, appliances.

Plastic Spring-Lock Shelf Supports with "heart of steel" help refrigerator makers cut costs, speed production, simplify servicing.







**SEND TODAY** for your copy of the Simmons catalog, with specifications, applications, installation instructions for all Simmons Fasteners. Samples are available. For special assistance, describe your requirements.



**LINK-LOCK**–Ideal latching device where heavy locking pressure is necessary. Available in heavy, medium, light duty, for use in military and commercial containers and demountable construction.




**DUAL-LOCK**–Impact and vibration-proof high-load butt-joint fastener that will not accidentally unlock or loosen. Recess in panels or surface mount. Withstands 7000-lb. tension.




**QUICK-LOCK**–For assembling removable panels and access doors. Locked by a 90° turn. Various sizes and types, for weather-tight electrical units, cowlings, access panels.


LINK-LOCK




HINGE-LOCK



**HINGE-LOCK**–A rugged pressure hinge which provides a strong seal along the hinge line of gasketed equipment containers and transit cases. Matched hardware with LINK-LOCK.



**ROTO-LOCK**–Versatile fastener for butt or right-angle joints in portable shelters, partitions, knock-down shipping boxes, etc. Solidly built, springless.



**CLAMP-LOCK**–A simple and strong, positive-locking clamp for fast assembly (and disassembly) of permanent or temporary rooms and buildings of flanged-panel construction.

## SIMMONS FASTENER CORPORATION

**1759 North Broadway, Albany 1, New York**

See our condensed catalog in Sweet's Product Design File

**For more information, turn to Reader Service card, circle No. 467**



GRIPCO TOPLOCK NUT
One piece all metal

GRIPCO CLINCH NUT
With or without self-locking threads. Hex collar prevents turning when torqueing bolt.

GRIPCO PILOT-PROJECTION WELD NUT
With or without self-locking threads. Centering collar positions nut and protects threads from weld spatter.

# You get these "extras" when you specify GRIPCO®


# FASTENERS—

**Service**—40 sales representatives all over the country for prompt, fast service.

**Reliability**—Quality controlled by the oldest established lock nut manufacturer in the U.S.

**Stock**—Large inventories to ensure out of stock delivery on all catalogued items.

Speed production and lower costs on your products with this GRIP NUT family of GRIPCO FASTENERS. Qualified fastener engineers are available for consultation on all your assembly problems. Consult the yellow pages in your phone book under "GRIPCO" for the one nearest you.



GRIPCO CENTERLOCK NUT
Locking feature in the center for fast feeding. Can be applied from either end.



GRIPCO COUNTERSUNK WELD NUT
With or without self-locking threads. Countersink protects threads from weld spatter.

## Other Gripco Products:

- Brass Toplock or Centerlock nuts.
- Miniature weld and clinch nuts, with or without lock.
- Toplock and Centerlock Hi Nuts.
- Standard Semi-finish full and jam nuts.
- Stainless Steel lock, weld and semi-finish nuts.
- Cold formed special nuts or parts to print.

*Send for samples and NEW CATALOG today*

## GRIP-NUT COMPANY

125

101 BROAD ST.
SOUTH WHITLEY, INDIANA
Phone: South Whitley 723-5111

*Subsidiary of Heli-Coil Corporation, Danbury, Conn.*

**For more information, turn to Reader Service card, circle No. 536**

# BRAZE stainless with NICROBRAZ® alloys



Brazing stainless assemblies for high temperature, high stress service requires the right brazing filler metal. One of the thirteen Nicrobraz nickel-base alloys has the qualities to satisfy your specific needs. Let Wall Colmonoy assist you in your choice.

Nicrobraz alloys are clean and consistent, controlled by laboratory tests. Available as powder, wire, sheet, and special forms, for preplacement on furnace brazed parts. For torch brazing, both rod and flux-powder pastes are made.




Write for more information about Nicrobraz, the best researched, most extensive line of stainless brazing filler metals and brazing aids.


## WALL COLMONOY CORPORATION

*Stainless Processing Division*

19345 JOHN R STREET • DETROIT 3, MICHIGAN

HARD-SURFACING & BRAZING ALLOYS

**For more information, turn to Reader Service card, circle No. 503**




# brazing handbook

***Contains Information On . . .***

- Designing for Preforms
- Round and Flat Wire Rings
- Curved Washers and Shims
- Types of Blanked and Edgewound Washers
- No Tangle Notch Coil Rings
- Types of Flux and Applications
- Alloy Selection Charts
- Gold, Silver and Aluminum Brazing Alloys — Soft Solders

***Send for your free copy today!***

## LUCAS-MILHAUPT *Engineering Co.*


***5061 South Lake Drive, Cudahy, Wisconsin***

**For more information, turn to Reader Service card, circle No. 551**

# 8 ways to use versatile E-FORM EPOXY PELLETS

Developed to overcome the measuring and handling drawbacks of liquid epoxy, E-FORM EPOXY PELLETS are non-toxic, dry, easy-to-handle units that can be provided in the exact size, shape, volume and formulation required for any insulating, adhesive, chemical resistant or flame-resistant application! Variations of cure temperature, color, flow and viscosity, heat dissipation, thermal expansion, physical and adhesive strength, flexibility, etc., are available to raise production efficiency, save time, cut rejects drastically and raise the standard of component performance.

***Here are 8 ways to use versatile E-FORM EPOXY PELLETS in your plant now:***





For complete technical data on any or all of these techniques, write to

**EPOXY PRODUCTS**

A DIVISION OF JOSEPH WALDMAN & SONS

137 Coit Street, Irvington, New Jersey

ESsex 5-6000




For more information, turn to Reader Service card, circle No. 510

**Presents all factors controlling the best choice . . .**

# FILLER METALS for JOINING

*New!*




**1959, 250 pages, $7.00**
**Profusely illustrated**

by **ORVILLE T. BARNETT,**
*Metals Research Department,*
*Armour Research Foundation, Chicago, Illinois*

This much-needed reference presents reasons for, and summarizes industrial practice in selecting the proper filler metal for any metal joining situation. It covers all of the ferrous and non-ferrous joining metals. Welding, brazing and soldering are treated with major emphasis on products for manual and automatic arc welding. Available materials are discussed in terms of applicability, mechanical properties and degree of availability. Where many filler metals are offered for a single application, factors controlling the best choice are outlined.

The book supplements the many excellent specifications prepared by the American Welding Society in cooperation with the American Society of Testing Materials, and includes the National Electrical Manufacturers Association color codings and new alloy designations of the Aluminum Association.

Ten chapters are devoted to arc welding electrodes, and another to automatic welding of mild and low alloy steels which discusses materials in an area where no specifications exist as yet. The chapters on new iron powder electrodes, latest developments in non-ferrous metals, surfacing and tungsten electrodes contain much material that has never been published before.

Over 84 experts in the field of joining reviewed portions of the text and made many pertinent and useful suggestions.

Here is a handy reference for welding engineers, designers, and welders who are interested in knowing when and where to use individual filler metals; for purchasing agents who want to look up competing products; and for anyone in welded fabrication who needs to choose among the great variety of products being marketed.

**CONTENTS**

Introduction
E6010 Electrodes
E6011 Electrodes
E6012 Electrodes
E6013 Electrodes
Low Hydrogen Mild Steel Electrodes
E6020-E6030 Electrodes
Iron Powder Electrodes for Mild Steel
Low-Alloy High-Strength Electrodes
Cast Iron
Stainless Steel
Automatic Welding, Mild and Low Alloy Steels
Aluminum and Aluminum Alloys
Copper and Copper Alloys
Nickel and Nickel Alloys
Surfacing
Tungsten Electrodes
Brazing
Soldering

*INCLUDES—*

*All ferrous and non-ferrous joining metals*

*Welding, brazing and soldering*

*Applicability, mechanical properties and degree of availability*

*Specifications, color codings and new alloy designations*

**Examine It Free for 10 Days**
**MAIL THIS COUPON NOW!**

**REINHOLD PUBLISHING CORPORATION**
Dept. M-703, 430 Park Avenue, New York 22, N. Y.

Please send me a copy of FILLER METALS FOR JOINING for *Free Examination.* After 10 days, I will send you $7.00 plus shipping costs or I will return the book and owe nothing.

NAME .....
ADDRESS .....
CITY AND ZONE .....STATE .....

SAVE MONEY! Enclose $7.00 with order and Reinhold pays all shipping costs. Same return privilege. Please add 3% sales tax on N.Y.C. orders. DO NOT ENCLOSE CASH!

# RB&W FASTENERS THAT SOLVE SPECIAL PROBLEMS

116th year

### TENSILOCK® SCREWS AND NUTS

"Tensilock," the high tension locking fastener, bites with hardened ratchet teeth . . . holds tight. High residual tension, tooth grip, and spring action of flexible flange make required loosening torque as much as 40% more than tightening torque. ®TM



### PIGMENTED DELRIN® LOCK NUTS

RB&W open-end acorn nuts of pigmented Delrin feature excellent strength, rigidity, dimensional stability, low cost, reusability, corrosion resistance. Constant prevailing torque. Metallic gray and other colors. Two sizes: No. 10 develops 500-600 lbs. clamping force; ¼-inch develops 600-700 lbs.




®Dupont Trade Mark

### SPIN-LOCK SCREWS

These RB&W screws offer in flat head and filister head design a locking action similar to that of RB&W's Tensilock® screws. They have ratchet-like teeth that bite into the bearing surface when tightened and resist loosening from vibration or temperature cycling. Reusable. Wide range of sizes.



### POWDERED METAL PARTS



A variety of small parts is presently being produced by RB&W from powdered brass and stainless steel. Facilities can handle a wide variety of other small shapes, including nuts, gears, bushings, spacers, levers, cams, etc. Such sintered parts offer substantial production savings. Contact us with your requirements.

### STAKED LOCK NUTS



Staked on opposite sides for positive grip and spring tension locking effect. Available in regular double chamfered style or acorn style (illustrated), in aluminum, steel, silicon bronze.




### WELDING FASTENERS

RB&W standard welding screws have welding projections on top or bottom of head. Sizes from No. 6 through ½ inch. Welding Nuts can also be supplied.

## Cold heading creates quality parts the low cost way

METAL FORCED to cold flow into shape results not only in savings but also in stronger parts. With uncut flow lines, the piece is better able to withstand stress concentrations.

No value analysis of product components is really complete without exploring what cold heading machines can do. Some examples:




**ELIMINATE EXTRA OPERATIONS.** Leveling screw (A), formerly made by riveting flat disc to set screw, now emerges as a stronger, single piece from a cold header.

**ONE PIECE BETTER THAN TWO.** Cold headed hose clamp screw (B) has integral flange which, after head is slotted, is forced up to form screwdriver shield. Before, piece was in two parts . . . with screw made on screw machine, and the shield a stamping fitted around head in extra assembly operation.

**FASTER THAN FORGING.** Shifter lever (C) is bent into double "L" automatically in bolt header . . . replacing 2-stage forging operation. The header does it at high speed from continuous rod.

**METAL FLOWS TO SHAPE—NO WASTE.** No longer cut on screw machine, insert screw (D) for plastic parts cost 40% less. Cold header uses just the amount of metal required. The threading and knurling, too, are done automatically at high speed.

## RUSSELL, BURDSALL & WARD BOLT AND NUT COMPANY

*RB&W fasteners—Strong Point of any assembly*

**Plants at:** Port Chester, N.Y.; Coraopolis, Pa.; Rock Falls, Ill.; Los Angeles, Calif. **Additional sales offices at:** Ardmore (Phila.) Pa.; Pittsburgh; Detroit; Chicago; Dallas; San Francisco.

**See our catalog in Sweets Product Design File**

For more information, turn to Reader Service card, circle No. 543

## do you make full use of your

# MATERIALS SELECTOR?

The typical Materials in Design Engineering reader puts the SELECTOR to good use all year round. Here are some facts revealed by a series of five studies involving more than 1,000 readers like yourself.

**READERSHIP**



**96%** of all M/DE subscribers refer to or look through the SELECTOR.

**USERSHIP**



**79%** make use of it to make actual selections or to write specifications.

**FREQUENCY OF USE**



The average subscriber refers to the SELECTOR at least once a week.

**NUMBER OF USERS**



**3.9** persons, on the average, use each copy.

**DURATION OF USE**



**97%** keep it until the succeeding edition is published.

**READER SERVICE**



MOST M/DE subscribers make use of the reader service card to get additional information on advertised products or to obtain the latest technical literature available from suppliers. You can take advantage of this **free** service by turning to the insert on page 585.

# Directory Section

## Suppliers of Materials

## Addresses of Suppliers



# THE DIRECTORY

This Directory is designed to be a comprehensive and up-to-date source of suppliers of engineering materials, forms, finishes and closely related services. The listings were compiled from information received from more than 3000 manufacturers, from official information made available by trade associations, and from many other sources.

## HOW TO USE THE DIRECTORY

The Directory consists of two sections. In the first, the categories of materials, forms, finishes and related services are arranged alphabetically; suppliers in each category also are listed alphabetically with their geographical location indicated by state abbreviations. The many cross references make it easy to find any given category. In general, suppliers of basic or "mill" forms of materials, such as sheet, are listed under the particular materials, whereas suppliers of "fabricated" forms, such as forgings, are listed under the form.

Key letters in parenthesis following names of suppliers provide two kinds of additional information: 1) the basic materials in which a supplier furnishes a particular fabricated form, and 2) the basic forms in which a supplier furnishes a particular material (see key at right). For example, if you are looking for suppliers of magnesium sand castings, you will look for those suppliers of sand castings whose names are followed by the letter "e." Similarly, if you are looking for suppliers of cellulose acetate rod, you will look for those suppliers of cellulose acetate whose names are followed by the letters "bb."

Further information on a particular supplier's product can often be found by consulting an advertisement in this issue. Advertisers' names are bold-faced under the appropriate categories, and the pages on which their advertisements appear are listed following their names. Page numbers of advertisements are also given in the complete Index to Advertised Products, p 8, and the complete Index to Advertisers, pp 9-10.

The second part of the Directory contains a complete alphabetical list of suppliers and their addresses. To find the address of a division of a company, look up the name of the parent company (always given with the division name in the first part of the Directory).

*In compiling a directory of this nature it is impossible to avoid errors and omissions. We will welcome corrections and suggestions. Please address them to Directory Editor,* MATERIALS IN DESIGN ENGINEERING, *430 Park Ave., New York 22, N. Y.*

**MATERIALS**

- **a** Aluminum and its alloys
- **b** Copper and its alloys
- **c** Iron and its alloys (except steel)
- **d** Lead and its alloys
- **e** Magnesium and its alloys
- **f** Nickel and its alloys
- **g** Steels
- **h** Titanium and its alloys
- **j** Zinc and its alloys
- **k** Thermoplastics
- **l** Thermosetting plastics
- **m** Elastomers

**BASIC FORMS**

- **n** Anodes
- **o** Bar
- **p** Base resins, polymers or gums
- **q** Billets
- **r** Custom formed parts (incl. specialties)
- **s** Fibers
- **t** Film
- **u** Foams (component materials or products)
- **v** Foil
- **w** Ingot
- **x** Laminating, casting resins
- **y** Molding compounds
- **z** Plate
- **aa** Powder
- **bb** Rod
- **cc** Sheet
- **dd** Strip
- **ee** Tubing
- **ff** Wire

**The listings and other data in this directory are compiled from sources believed reliable by the publisher. The publisher, however, does not represent or guarantee the accuracy of said listings and data, and no responsibility is assumed therefor.**

# Suppliers of Materials

## ABS

(acrylonitrile-butadiene-styrene)

Bolta Products Div., General Tire & Rubber Co., Mass (cc)
Crane Plastics, Inc., Ohio (bb,dd,ee)
Colonial Plastics Mfg. Co., Div. of Van Dorn Iron Works Co., Ohio (bb,cc,dd)
Conneaut Rubber and Plastics Co., Div. of U. S. Stoneware Co., Ohio (bb, cc,dd,ee)
Denver Plastics Inc., Colo (bb,cc,dd,ee)
Goodrich, B. F. Chemical Co., Ohio (p,y)
Kaufman Glass Co., Del (bb,cc,dd, ee)
Lus-Trus Corp., Mich (dd,ee)
Madin Plastics Inc., NJ (y,cc)
**Marbon Chemical Div., Borg-Warner Corp., Ind** (y)—Ad pp 235-242
Naugatuck Chemical Div., U.S. Rubber Co., Conn (p,y)
Polymer Chemical Co., Ohio (x)
U.S. Rubber Co., Footwear Div., Ill (cc)
Western Plastics Corp., Wash (ee)
Western Textile Products Co., Mo (ee)

## Acetal Plastics

**Albany Novelty Mfg. Co., Mass (t,cc)**
**Anderson Assoc., Inc., Ohio (y)**
**Bamberger, Claude P., Inc., NJ (y)**
Belding Corticelli Industries, NY (y)
**CrystalX Corp., Pa (t,bb,cc,dd,ee)**
**Davis, Joseph Plastics Co., NJ (t,y, bb,cc,dd,ee)**
du Pont de Nemours, E.I. & Co., Inc., Del (p,t,x,y)
Heyden Newport Chemical Corp., American Plastics Corp. Div., NY (bb,cc,dd,ee)
National Vulcanized Fibre Co., Del (bb,cc,ee)
Pennsylvania Fluorocarbon Co., Inc., Pa (ee)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
**Shawinigan Resins Corp., Mass (p)**
**Superior Plastics, Inc., Ill (bb,cc,ee)**

## Acetate

(see Cellulose Acetate)

## Acrylate Rubber

(see Acrylic Rubber)

## Acrylic Plastics

**Ace Plastic Co., NY (bb,cc,dd,ee)**
**Adhesive Products Corp., NY (x)**
**American Molding Powder & Chemical Co., NY (y)**
**American Products Mfg. Co., Inc., La (t,bb,cc)**
**Anchor Plastics Co., Inc., NY (bb,dd, ee)**
**Anderson Assoc., Inc., Ohio (y)**
**Artus Corp., NJ (cc,dd)**
Auburn Plastic Engineering, Ill (bb, cc,ee)
**Auburn Plastics, Inc., NY (bb,dd,ee)**
**Bamberger, Claude P., Inc., NJ (y)**
**Blank, Arthur & Co., Inc., Mass (cc)**
**Borden Co., Borden Chemical Div., NY (p)**
**Cadillac Plastic & Chemical Co., Mich (p,x,bb,cc,dd,ee)**
**Cast Optics Corp., NJ (cc)**
Catalin Corp. of America, NY (p)
**Chemical Development Corp., Mass (p)**
**Colonial Kolonite Co., Ill (bb,cc,ee)**
**Colton Chemical Co., Div. of Air Reduction Co., Inc., Ohio (p)**
Comco Plastics, Inc., NY (bb,cc,dd,ee)
**Commercial Plastics & Supply Corp., NY (bb,cc,dd,ee)**
Crane Plastics, Inc., Ohio (bb,dd,ee)
**CrystalX Corp., Pa (t,bb,cc,dd,ee)**
**Curbell, Inc., NY (bb,cc,dd,ee)**
**Denver Plastics, Inc., Colo (bb,cc,dd, ee)**
Dow Chemical Co., Plastics Div., Mich (s)
du Pont de Nemours, E.I. & Co., Inc., Del (p,s,x,y)
**Dura Plastics of New York, Inc., NY (bb,cc,dd,ee)**
**Durable Formed Products, Inc., NY (cc,ee)**
Dyna-Therm Chemical Corp., Calif (p)
**Eljay Corp., Md (bb,cc,dd,ee)**
Foss Mfg. Co., Id (cc)
Fry Plastics International, Calif (bb, cc)
**Galigher Co., Utah (bb,cc,dd,ee)**
**General Aniline & Film Corp., NY (cc)**
General Plastics Corp., Ind (cc)
**General Plastics Mfg. Co., Wash (bb, cc,dd,ee)**
Gering Plastics, Div. of Studebaker-Packard Corp., NJ (y)
Glass Laboratories, Inc., NJ (bb, dd, ee)
Grigoleit Co., Ill (p,s)
**H & R Industries, Pa (bb,cc,dd,ee)**
Hauger-Beegle Asso., Inc. Ill (t)
Heyden Newport Chemical Corp., American Plastics Corp. Div., NY (bb,cc,dd,ee)
**Industrial Plastics Corp., Ind (bb,dd)**
**Jet Specialties Co., Inc., Calif (bb, dd,ee)**
**K S H Plastics, Inc., Mo (bb,cc,dd)**
Kaufman Glass Co., Del (bb,cc,dd,ee)
**Luminous Resins, Inc., Ill (y)**
Lus-Trus Corp., Mich (cc,ee)
**Midwest Plastic Products Co., Ill (cc, dd)**
**Muehlstein, H. & Co., Inc., NY (p, y,cc)**
**Norrich Plastics Corp., NY (bb,cc,ee)**
**Perfex Plastics, Inc., Ill (bb,dd)**
**Philrus Products Co., NJ (bb,cc,dd, ee)**
**Plast-Ad Mfg. Co., Ind (bb,cc,dd,ee)**
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Plastic Compounding Corp., Sub. of Plastiglide Mfg. Corp., Calif (y)
**Plastic Materials, Inc., NY (y)**
Polycast Corp., Conn (cc)
**Pyramid Industries, Inc., Pa (ee)**
Radiation Applications, Inc., NY (bb, cc,dd,ee)
Reeo Plastics Corp., Mass (y)
Rohm & Haas Co., Pa (y,cc)
Russell Mfg. Co., Conn (s)
**Schwab Plastics Corp., Mich (bb,cc, dd,ee)**
**Scranton Plastic Laminating Corp., Pa (cc)**
**Snyder Mfg. Co., Inc., Ohio (cc)**
**Southern Plastics Co., SC (bb,cc,dd, ee)**
**Superior Plastics, Inc. Ill (bb,dd)**
Union Carbide Corp., Union Carbide Chemical Co. Div., Textile Fibers Dept., NY (s)
**United Shoe Machinery Corp., Mass (p)**
Western Felt Works, Ill (cc)
**Westlake Plastics Co., Pa (t,y,bb,cc, dd,ee)**
**World Plastics, NY (bb,cc,dd,ee)**

## Acrylic Rubber

**Adhesive Products Corp., NY (x)**
Bond International, Inc., Mich (y,ee)
**Borden Co., Borden Chemical Div., NY (p)**
**Castle Rubber Co., Pa (y,bb,cc,dd,ee)**
Chicago-Allis Mfg. Corp., Ill (p)
**Continental Rubber Works, Pa (bb, cc,dd,ee)**
**Dryden Rubber Div., Sheller Mfg. Corp., Ill (y,ee)**
Dyna-Therm Chemical Corp., Calif (p)
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (y,cc,ee)
**Flexible Tubing Corp., Conn (ee)**
Garlock Packing Co., NY (y,cc)
**General Plastics Mfg. Co., Wash (bb, cc,dd,ee)**
**Goodrich, B.F. Chemical Co., Ohio (p,cc)**
**Maloney, F.H. Co., Tex (y)**
**National Gasket & Washer Mfg. Co., Inc., NY (bb,cc,dd,ee)**
**Norrich Plastics Corp., NY (bb,cc,dd, ee)**
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
**Polymer Chemical Co., Ohio (x)**
Roth Rubber Co., Ill (cc)
**Russell Mfg. Co., Conn (s)**
**Southern Plastics Co., SC (bb,cc,dd,ee)**
**Vulcan Rubber Products Div., Reeves Bros., Inc., NY (p,y,cc)**
Wasco Products, Inc., Mass (cc)
Western Felt Works, Ill (y,cc,dd,ee)
Williams-Bowman Rubber Co., Ill (y,bb,cc,dd,ee)

## Acrylonitrile-Butadiene Rubber

**Adhesive Products Corp., NY (x)**
American Hard Rubber Co., Div. of Amerace Corp., NY (bb,cc,dd)
**American Rubber Products Corp., Ind (u,bb,cc,dd,ee)**
**Anderson Assoc., Inc., Ohio (y)**
**Automotive Rubber Co., Inc., Mich (cc,dd)**
**Belko Corp., Md (y)**
Bond International, Inc., Mich (y,ee)
**Borden Co., Borden Chemical Div., NY (p)**
**Castle Rubber Co., Pa (y,bb,cc,dd,ee)**
Chicago-Allis Mfg. Corp., Ill (p)
**Continental Rubber Works, Pa (bb, cc,dd,ee)**
Dayton Rubber Co., Ohio (y,bb,cc,dd, ee)
**Dryden Rubber Div., Sheller Mfg. Corp., Ill (y,ee)**
**Faultless Rubber Co., Ohio (y,bb,ee)**
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (y,cc,ee)
**Firestone Tire & Rubber Co., Ohio (p)**
**Flexible Tubing Corp., Conn (ee)**
Garlock Packing Co., NY (y,bb,cc,dd, ee)
**Geauga Industries Co., Ohio (y,bb,dd)**
**Goodrich, B.F. Chemical Co., Ohio (p, cc)**
Goodyear Tire & Rubber Co., Chemical Div., Ohio (p)
**Goshen Rubber Co., Inc., Ind** (y)—Ad p 438
**Hewitt-Robins, Inc., Conn (cc,ee)**
**Home Rubber Co., NJ (y,bb,cc,dd,ee)**
**Lee Rubber & Tire Corp., Republic Rubber Div., Ohio (p,y,cc,dd,ee)**
Luzerne Rubber Co., NJ (bb,cc,dd,ee)
**Maloney, F.H. Co., Tex (y)**
Marbon Chemical Div., Borg-Warner Corp., Ind (p,x,y)
**Martin Rubber Co., Inc., NJ (y,dd,ee)**
**Mid-States Rubber Products, Inc., Ind (y)**
**National Gasket & Washer Mfg. Co., Inc., NY (bb,cc,dd,ee)**
**Naugatuck Chemical Div., U.S. Rubber Co., Conn** (p,y)—Ad p 247
Paeco Rubber Co., Inc., Ohio (y,dd,ee)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
**Parker, Stearns & Co., Inc., NY (y, bb,cc,dd,ee)**
**Polymer Chemical Co., Ohio (x)**
Prince Rubber & Plastic Co., Inc., NY (bb,cc,ee)
Raybestos-Manhattan, Inc., Plastic Products Div., Pa (x)
Roberts Toledo Rubber Co., Ohio (ee)
Roth Rubber Co., Ill (y,cc)
**Rubatex Div., Great American Industries, Inc., Va (u)**
Saran Lined Pipe Co., Div. of Michigan Pipe Co., Mich (y,cc)
**Sheller Mfg. Corp., Mich (u)**
Southern Plastics Co., SC (bb,cc,dd, ee)
**Stockwell Rubber Co., Inc., Pa (y,bb, cc,dd)**
**Technical Specialties Co., NY (dd)**
**Toyad Corp., Pa** (u)—Ad p 260
Trostel, Albert Packings, Ltd.,Wis (y)
**U.S. Rubber Co., NY (p)**

Vulcan Rubber Products Div., Reeves Bros., Inc., NY (p,y,cc)
Vulcanized Rubber & Plastics Co., Pa (y)
Westlake Plastics Co., Pa (bb,cc,dd)
Western Felt Works, Ill (y,cc,dd,ee)
Williams-Bowman Rubber Co., Ill (y,bb,cc,dd,ee)

## Adhesives

(see also Tapes)

Adhesive Products Corp., NY (k,l,m)
Alcylite Plastics & Chemical Corp., Calif (k,l)
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY (l)
American Cyanamid Co., Plastics & Resins Div., NY (l)
American Hard Rubber Co., Div. of Amerace Corp., NJ (k,l,m)
American Metaseal Corp., NJ (l)
American Products Mfg. Co., Inc., La (k,m)
American Sealants Co., Conn (l)
Angier Adhesives Div., Interchemical Corp., Mass (k,l,m)
Arabol Mfg. Co., NY (k)
Aries Laboratories, Inc., Conn (l)
Armour & Co., Adhesive Div., Ill (k,m)
Armstrong Cork Co., Pa (k,l,m)
Armstrong Products Co., Ind (l)
Atlantic Bag Co., NY (l)
Avery Label Co., Decorative Products Div., Ohio (l)
Avondale Co., Ill (k,l,m)
B. B. Chemical Co., Bostik Dept., Mass. (k,l,m)—Ad p 496
Babbitt Chemical Co., Inc., Mass (k)
Beck, I. & Sons, Inc., NY (m)
Belding Corticelli Industries, NY (k,l,m)
Belko Corp., Md (m)
Biggs, Carl H. Co., Inc., Calif (k,l)
Bisonite Co., Inc., NY (l)
Borden Co., Borden Chemical Div., NY (k,l,m)
California Metal Enameling Co., Calif (k,m)
Campro Co., Ohio (k)
Capac Mfg. Corp., Mich (k,l,m)
Catalin Corp. of America, NY (l)
Ceilcote Co., Ohio (k,l,m)
Chemical Coatings & Engineering Co., Inc., Pa (k,l,m)
Chemical Development Corp., Mass (k,l)
Chemical Process Co., Calif (l)
Chemical Products Corp., RI (k,m)
Chrysler Corp., Cycleweld Div., Mich (k,l,m)
Ciba Co., Inc., NY (l)
Clinton Co., Ill (k,l,m)
Coast Pro-Seal & Mfg. Co., Calif (l,m)
Colonial Kolonite Co., Ill (k)
Connecticut Hard Rubber Co., Conn (m)
Continental Can Co., Conolite Div., Del (l)
Cooper, Peter Corp., NY (k)
Co-Polymer Chemicals Inc., Mich (l)
Cordo Chemical Corp., Conn (k,l,m)
CrystalX Corp., Pa (k)
Dacar Chemical Products Co., Pa (k,l,m)
Dayton Rubber Co., Ohio (k,l,m)
Dennis Chemical Co., Mo (k,m)
Devcon Corp., Mass (k,l)
Douglas & Sturgess, Calif (l,m)
Dow Corning Corp., Mich (m)
du Pont de Nemours, E.I. & Co., Inc., Del (k)
Durable Formed Products, Inc., NY (k)
Dyna-Therm Chemical Corp., Calif (k,l,m)
Eastman Chemical Products, Inc., Sub. of Eastman Kodak Co., NY (k)—Ad p 494
Electro Chemical Engineering & Mfg. Co., Pa (k,l,m)
Electronic Production & Development, Inc., Chemical Div., Calif (l)
Emerson & Cuming, Inc., Mass (k,l,m)
Everlite Corp., Wash (k,l,m)
Fanner Mfg. Co., Munray Products Div., Ohio (k)
Fibercast Div., Youngstown Sheet & Tube Co., Okla (l)
Flexfirm Products, Calif (k)
Fluorocarbon Co., Calif (l)
Formica Corp., Sub. of American Cyanamid Co., Ohio (l)
Foss Mfg. Co., Id (l)
Franklin Glue Co., Ohio (k)
Fry Plastics International, Calif (k,l)
Fuller, H.B. Co., Minn (k,l,m)
Furane Plastics, Inc., Calif (l)
General Electric Co., Silicone Products Dept., NY (k,l)
General Mills, Inc., Chemical Div., Ill (k,l)
General Plastics Mfg. Co., Wash (k,l,m)
Gomar Mfg. Co., Inc., NJ (k)
Goodrich, B.F. Industrial Products Co., Ohio (k)
Goodyear Tire & Rubber Co., Chemical Div., Ohio (k)
Great Lakes Carbon Corp., NY (l)
Hadley Bros.-Uhl Co., Mo (m)
Hardman, H.V. Co., Inc., NJ (l)
Haskelite Mfg. Corp., Mich (k,l,m)
Haveg Industries, Inc., Del (l)
Hayes Adhesive Co., Inc., Mo (k,l)
Hiller Aircraft Corp., Adhesive Engineering Div., Calif (l)
Hughes Glue Co., Mich (k,l,m)
Hughson Chemical Co., Div. of Lord Mfg. Co., Pa (k,l,m)
Hysol Corp., NY (k,l,m)
Industrial Polychemical Service, Calif (k,l,m)
Interchemical Corp., NY (k,l,m)
Interchemical Corp., Finishes Div., NJ (k,l)
Jamestown Finishes, NY (k)
Johns-Manville Corp., NY (k,l,m)
Johns-Manville Corp., Dutch Brand Div., Ill (m)
Kendall Co., Polyken Sales Div., Ill (k,l)
Lee Rubber & Tire Corp., Pa (m)
Maas & Waldstein Co., NJ (k,l)
Magic Iron Cement Co., Ohio (k)
Magnesium Co. of America, Ind (k,l)
Maloney, F.H. Co., Tex (k,l,m)
Manhattan Adhesives Corp., NY (k,l,m)
Mansol Ceramics Co., NJ (l)
Marbiette Corp., NY (l)
Marbon Chemical Div., Borg-Warner Corp., Ind (k,l)
Mesa Plastics Co., Calif (l)
Midland Adhesive & Chemical Corp., Mich (k,l,m)
Minnesota Mining & Mfg. Co., Adhesives, Coatings & Sealers Div., Mich (k,l,m)
Miracle Adhesives Corp., NY (k,m)
Monsanto Chemical Co., Plastics Div., Mass (l)
Morningstar-Paisley Inc., NY (k)
Mystik Adhesive Products, Inc., Ill (k,l,m)
Narmco Industries, Inc., Narmco Materials Div., Calif (l,m)
National Casein Co., Ill (k,l)
National Starch & Chemical Corp., Structural Products Div., NY (k,l,m)
Naugatuck Chemical Div., U.S. Rubber Co., Conn (k,l,m)
Nukem Products Corp., NY (k)
Ohio Adhesives Corp., Ohio (k,l,m)
Parker Paint Mfg. Corp., Ind (k)
Pawling Rubber Corp., NY (k,l)
Pecora, Inc., Pa (k,m)
Permacel, NJ (k,l,m)
Perry-Austen Mfg. Co., NY (l,m)
Peterson, D.J. Co., Wis (k)
Pierce & Stevens Chemical Corp., NY (k,l,m)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (k,l,m)
Plast-Ad Mfg. Co., Ind (k,l)
Poly Resins, Calif (l)
Polymer Chemical Co., Ohio (k,l,m)
Polymer Corp. of Pennsylvania, Sub. of Polymer Corp., Pa (k)
Polymer Industries, Inc., Conn (k,l,m)
Presstite Div., American-Marietta Co., Mo (k,lm)
Quelcor, Inc., Pa (l)
Radiation Applications, Inc., NY (k,l,m
Randolph Products Co., NJ (k,l,m)
Raybestos - Manhattan, Inc., Adhesives Div., Conn (k,l,m)—Ad p 492
Reichhold Chemicals, Inc., NY (k,l)
Ren Plastics, Inc., Mich (l)
Reynolds Aluminum Supply Co., Ga (k,l)
Riverside Plastics Corp., NY (l)
Rohm & Haas Co., Pa (k,l)
Rubber & Asbestos Corp., NJ (k,l,m)
Rubber & Plastics Compound Co., Inc., NY (k)
St. Clair Rubber Co., Mich (m)
Sauereisen Cements Co., Pa (k,l)
Schwartz Chemical Co., Inc., NY (k,l,m)
Shell Chemical Co., NY (l)
Sillcocks Miller Co., NJ (k)
Snyder Mfg. Co., Inc., Ohio (k)
Southern Adhesives Corp., Va (k,l,m)
Standard Insulation Co., NJ (l)
Steelcote Mfg. Co., Mo (l)
Stockwell Rubber Co., Inc., Pa (m)
Superior Plastics, Inc., Ill (k)
Surprenant Mfg. Co., Mass (k)
Swedlow, Inc., Calif (l)
Swift & Co., Adhesives Dept., Ill (k,m)
Synco Resins, Inc., Conn (k,l)
Toyad Corp., Pa (m)—Ad p 260
U B S Chemical Corp., Mass (k,l,m)
Union Paste Co., Mass (k,l)
United Shoe Machinery Corp., Mass (k,l,m)
U.S. Stoneware Co., Ohio (k,l)
Waldman, Joseph & Sons, Epoxy Products Div., NJ (l)—Ad p 499
Waterman Industries, Inc., Calif (k,l)
Western Plastics Corp., Wash (k)
Westlake Plastics Co., Pa (k)
Williamson Adhesives, Inc., Ill (k,l,m)

## Alkyd Plastics

Adhesive Products Corp., NY (x)
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY (p,y)
American Cyanamid Co., Plastics & Resins Div., NY (p)
Anderson Assoc., Inc., Ohio (y)
Archer-Daniels-Midland Co., Minn (p)
Booty Resineers Div., American-Marietta Co., Ohio (p)
Dyna-Therm Chemical Corp., Calif (p)
Electrofilm, Inc., Calif (t)
Fiber Glass Industries, Inc., NY (u,x,y,cc)
Foss Mfg. Co., Id (cc)
General Electric Co., Insulating Materials Dept., NY (p)
Glaskyd, Inc., Ohio (y)
Hays Mfg. Co., Pa (y)
Hercules Powder Co., Inc., Del (p)
Jones-Dabney Co., Div. of Devoe & Raynolds Co., Inc., Ky (p)
Kurz Kasch, Inc., Ohio (y)
Naugatuck Chemical Div., U.S. Rubber Co., (p,x,y)
Panelyte Div., St. Regis Paper Co., NJ (x,y)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Reichhold Chemicals, Inc., NY (p)
Schenectady Varnish Co., Inc., NY (p)
Sherwin-Williams Co., Ohio (p)
Specialty Resins Co., Calif (p)
Westinghouse Electric Corp., Micarta Div., SC (p)

## Alloy Steels

(see Steel)

## Aluminides

(see Refractories)

## Aluminized Metals

(see Precoated Metals)

## Aluminizing

(see Immersion Coatings)

## Aluminum and Its Alloys

Acme Tube, Inc., NJ (ee)
Adams Engineering Co., Inc., Fla (q,ee)

### KEY

**MATERIALS**

a—Aluminum and its alloys
b—Copper and its alloys
c—Iron and its alloys (except steel)
d—Lead and its alloys
e—Magnesium and its alloys
f—Nickel and its alloys
g—Steels
h—Titanium and its alloys
j—Zinc and its alloys
k—Thermoplastics
l—Thermosetting plastics
m—Elastomers

**BASIC FORMS**

n—Anodes
o—Bar
p—Base resins, polymers or gums
q—Billets
r—Custom formed parts (incl. specialties)
s—Fibers
t—Film
u—Foams (component materials or products)
v—Foil
w—Ingot
x—Laminating, casting resins
y—Molding compounds
z—Plate
aa—Powder
bb—Rod
cc—Sheet
dd—Strip
ee—Tubing
ff—Wire

Advance Screw Products Co., Inc., Wis (o)
Advance Stamping Co., Mich (dd)
Aerolite Extrusion Co., Ohio (n,o,bb, dd,ee)
Alabama Wire Co., Inc., Ala (ff)
Albert Pipe Supply Co., Inc., NY (ee)
Alcasco Foundry, Ill (w)
Alloys & Chemicals Mfg. Co., Inc., Ohio (w,aa)
All-State Welding Alloys Co., Inc., NY (ff)
Alofs Mfg. Co., Mich (cc,dd,ff)
Alpha Metals, Inc., NJ (v)
Aluminium Ltd. Sales, Inc., NY (q,w)
Aluminum Co. of America, Pa (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Aluminum Billets, Inc., Ohio (q)
Aluminum Foils Co., Tenn (v)
American Brass Co., Sub. of Anaconda Co., NY (cc,dd,ee)
American Nickel Alloy Mfg. Corp., NY (w,aa)
American Silver Co., NY (v,dd,ee,ff)
American Smelting & Refining Co., NY (w)
Anaconda Aluminum Co., Sub. of Anaconda Co., Ky (o,q,v,w,z,bb,cc,dd,ee)
Apex Smelting Co., Ill (o,q,w,bb)
Arcos Corp., Pa (ff)
Armet Alloys, Inc., Ohio (w)
Arrow Metal Products Corp., NJ (cc)
Atlantic Powdered Metals, Inc., NY (aa)
Atlantic Steel Co., Ga (o,cc)
Auld, D.L Co., Ohio (o,bb,cc,dd,ff)
Aurora Refining Co., Ill (w)
Babson Dow Mfg. Co., Mass (o)
Badger Aluminum Extrusions, NY (o, q,dd,ee)
Baer Bros. Bronze Powder Co., Inc., Mass (aa)
Bay State Refining Co., Inc., Mass (w)
Belmont Smelting & Refining Works, Inc., NY (n,w,aa)
Biddle Screw Products Co., Ind (o, bb,ee)
Bohn Aluminum & Brass Corp., Mich (o,q,bb,ee)
Bonnell, William L. Co., Inc., Ga (bb,ee)
Both, O.A. Corp., Mass (aa)
Bridgeport Brass Co., Conn (o,bb,cc, dd,ee)
Bridgeport Rolling Mills Co., Conn (dd)
Briel Industries, Inc., Ind (q,w)
Brinkerhoff Brass & Bronze Works, Inc., NY (z,bb,cc,dd,ee)
Bunting Brass & Bronze Co., Ohio (o)
Caspers Tin Plate Co., Ill (cc,dd)
Castle, A.M. & Co., Ill (o,z,bb,cc,dd, ee,ff)
Central Fabricators, Inc., Ohio (z,bb, cc,ee)
Channel Master Corp., NY (q,ee)
Clad-Rex Corp., Ill (cc)
Clark Perforating Co., Mich (cc,dd)
Clarksville Foundry & Machine Works, Tenn (o,w,z,ee)
Cleveland Electro Metals Co., Ohio (w)
Commercialores, Inc., SC (aa)
Copper & Brass Sales, Inc., Mich (o, z,bb,dd,ee,ff)
Corson Industries, Pa (q,bb,ee)
Craft Metal Spinning Co., Ill (cc)
Crane Co., Metals Div., Pa (aa)
Crescent Bronze Powder Co., Ill (aa)
Designers Metal Corp., Ill (cc)
Dixie Aluminum Corp., Ga (o,q,bb,ee)
Dormont Mfg. Co., Pa (ee)
Dow Metal Products Co., Div. of Dow Chemical Co., Mich (z,cc,ee,ff)
Dudek & Bock Spring Mfg. Co., Ill (ff)
Eastern Rolling Mills, Inc., NY (cc,dd)
Edgcomb Steel & Aluminum Corp., NJ (o,z,cc,dd,ee)
Empire Metal Co., NY (o,q,w)
Essex Industrial Products Div., Essex Wire Corp., Ind (ff)
Essex Wire Corp., Magnet Wire Div., Ind (ff)
Eynon-Dakin Co., Mich (ee)
**Fairmont Aluminum Co., W. Va**
(cc,dd)—Ad p 161
**Federated Metals Div., American Smelting and Refining Co., NY**
(o,w)—Ad p 173
Flynn, Michael Mfg. Co., Pa (o,bb,ee)
Foamalum Corp., Ill (foamed)
Foil Div., Reynolds Metals Co., Va (v)
**Frasse, Peter A. & Co., Inc., NY**
(o,z,bb,cc,dd,ee,ff)—Ad p 179
Fromson Orban Co., Inc., NY (o,z, bb,cc,dd,ee,ff)
**Frontier Bronze Corp., NY**
(w)—Ad p 178
General Cable Corp., NY (ff)
General Extrusions, Inc., Ohio (o,bb, ee)
General Smelting Co., Pa (w)
Gold Leaf & Metallic Powders, Inc., NY (aa)
Harbot Die Casting Corp., NJ (w)
Hardy, Charles, Inc., NY (aa)
Harris, Benjamin & Co., Ill (w)
Harvey Aluminum, Calif (o,q,w,bb,ee)
Hayden Wire Works, Inc., Mass (aa)
Haydon Corp., NY (ee)
Hexcel Products, Inc., Calif (v)
Himmel Bros. Co., Conn (o)
Hommel, O. Co., Pa (aa)
Horton-Angell Co., Mass (ee,ff)
Houston Blow Pipe & Sheet Metal Works, Tex (o,z,cc)
Hunter Engineering Co., Calif (o,bb, cc,dd,ee)
Industrial Foil Div., Aluminum Co. of America, Pa (foil)
Inshield Die & Stamping Co., Ohio (cc,dd)
Jackson Steel Products, Inc., NY (ee)
Jarl Extrusions, Inc., NY (o,q,bb,ee)
Jeliff, C.O. Mfg. Corp., Conn (ff)
Jobbins, William F., Inc., Ill (w)
Johnston Foil Div., Standard Packaging Corp., Mo (v,cc)
Kaiser Aluminum & Chemical Sales, Inc., Ill (n,o,q,v,w,z,bb,cc,dd,ee,ff)
Kawecki Chemical Co., NY (w)
Kawneer Co., Mich (o,q,z)
Kinkead Industries, Inc., Ill (q,z,cc, dd)
Kirk, Morris P. & Son, Calif (w)
Korhumel Steel & Aluminum Co., Ill (o,z,bb,cc,dd,ee,ff)
Laminated Shim Co., Conn (cc)
Langsenkamp, F.H. Co., Ind (o,z,bb, cc,dd,ee,ff)
Light Metals, Inc., Ind (n)
Lockhart Iron & Steel Co., Pa (o, z,bb,cc,dd,ee)
Lucas-Milhaupt Engineering Co., Wis (dd,ff)
Lundquist Tool & Mfg. Co., Inc., Mass (cc,dd)
Magna Mfg. Co., Inc., NJ (aa)
Magnode Products, Inc., Ohio (o)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass. (o,ee)
Malone Bronze Powder Works, Inc., NY (aa)
May, Inc., Tex (o,bb,ee)
McGregor-Michigan Corp., Mich (ee)
Metal Goods Corp., Mo (o,z,bb,cc,dd, ee,ff)
Metallizing Co. of Los Angeles, Inc., Calif (bb,ff)
Metallizing Engineering Co., Inc., NY (ff)
Metals Disintegrating Co., Inc., NJ (aa)
Morrisville Foundry Co., Inc., Vt (bb)
Mueller Brass Co., Mich (bb)
Murray, A.B. Co., Inc., NJ (ee)
National Aluminum Co., Ohio (bb,ee)
National Lead Co., NY (o,bb,ee)
National U.S. Radiator Corp., Plastic Metals Div., NY (aa)
Navan Products, Inc., Sub. of North American Aviation, Inc., Calif (w)
Nesor Alloy Products Co., NJ (ff)
New Jersey Aluminum Extrusion Co., Inc., NJ (bb,ee)
New Jersey Metals Co., NJ (w)
Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (w)
Norrich Plastics Corp., Screw Machine Products Div., NY (o,bb,ee)
Nuclear Metals, Inc., Mass (bb,dd,ee)
Olds Alloys Co., Calif (ee)
Olin Mathieson Chemical Corp., Metals Div., NY (o,q,w,z,bb,cc,dd,ee,ff)
Ormond Mfg. Co., Inc., NJ (dd,ff)
Penn Extrusion Corp., Pa (ee)
Pioneer Aluminum, Inc., Calif (o,z,bb, cc,ee)
Pfister Tubing Corp., NJ (ee)
Precision Tube Co., Inc., Pa (ee)
Purdy, A. R. Co. Inc., NJ (o,z,bb,cc, dd,ee,ff)
Quaker State Metals Co., Pa (cc)
Rathbone Corp., Mass (bb)
Reade Mfg. Co., Inc., NJ (aa)
Republic Foil, Inc., Conn (v)
Republic Metals Co., Inc., NY (o,v, w)
Revere Copper & Brass, Inc., NY (o,q, v,w,z,bb,cc,dd,ee)
Reynolds Aluminum Supply Co., Ga (o, z,bb,cc,dd,ee,ff)
Reynolds Metals Co., Va (o,q,v,w,z,aa, bb,cc,dd,ee,ff)
Rigidized Metals Corp., NY (cc,dd)
Rodney Metals, Inc., Mass (v,dd)
Roebling's, John A. Sons Div., Colorado Fuel & Iron Corp., NJ (dd,ff)
Ryerson, Joseph T. & Son, Inc., Ill (o,q,z,bb,cc,dd,ee,ff)
Saginaw Bearing Co., Mich (o)
Sail, George Metals Co., Inc., Pa (w)
**Scovill Mfg. Co., Mill Products Div., Conn**
(bb,cc,dd)—Ad pp 169-170
Security Sash & Screen Co., Mich (cc)
**Sel-Rex Corp., NJ**
(n)—Ad p 356
Sherwatt Equipment & Mfg. Co., Inc., NY (ff)
Smith-Moon Steel Co., Inc., Kan (o,z,cc)
Sonken-Galamba Corp., Kan (q,w)
Southern Aluminum Finishing Co., Inc., Ga (o,z,bb,cc,dd,ee)
Standard Metals Corp., Mass (ee)
Star Heel Plate Co., Inc., NJ (ff)
Stranahan Foil Co., Inc., NJ (v)
Sun Steel Co., Ill (cc,dd)
Techalloy Co., Inc., Pa (n,dd)
Texas Instruments, Inc., Metals & Controls Div., Mass (v)
Trim Alloys, Inc., Mass (o,bb,ee)
Ullmann, Inc., Wis (o,ee)
United Screw & Bolt Corp., Ill (bb, cc,dd,ff)
United Smelting & Aluminum Co., Inc., Conn (cc,dd)
U.S. Bronze Powder Works, Inc., NJ (aa)
U.S. Extrusions Corp., NY (bb)
U.S. Gasket & Shim Co., Ohio (v)
U.S. Reduction Co., Ind (w)
United Wire & Supply Corp., RI (ee, ff)
Universal Converting Corp., Mass (o, bb,ee)
Utility Mfg. Co., Mass (bb)
Vanadium Corp. of America, NY (w)
Vulcan Rail & Construction Co., NY (o,z,ee)
Wallace Tube Co., Div. of Wallace Supplies Mfg. Co., Ill (ee)
Warner Mfg. Corp., NJ (o,bb,ee)
Waterman Industries, Inc., Calif (o,bb, cc,dd,ee)
Wells Aluminum Corp., Ind (o,bb,ee)
Werner, R.D. Co., Pa (o,q,w,bb,ee)
White Metal Rolling & Stamping Corp., NY (o,q,bb,ee,ff)
Whitehead Metal Products Co., Inc., NY (o,w,z,bb,cc,dd,ee,ff)
Wilder Mfg. Co., Inc., Calif (o,cc)
Wilson-Hurd Mfg. Co., Inc., Wis (cc)
Wright, Albert Screw Machine Products, Calif (bb)

## Aluminum Bronze
(see Copper)

## Anodes
(see specific metal)

## Anodic Coatings
(see Conversion Coatings)

## Asbestos
Aerojet-General Corp., Structural Materials Div., Calif (r)
American Asbestos Textile Corp., Pa (r,s)
American Brakeblok Div., American Brake Shoe Co., Mich (r)
American Smelting & Refining Co., NY (s)
Asbestos Corp. of America, NJ (r,s)
Asbestos Textile Co., Inc., Ill (r,s,cc)
California Metal Enameling Co., Calif (r)
Carey, Philip Mfg. Co., Ohio (r,s,cc)
Carolina Asbestos Co., NC (r)
Chicago Gasket Co., Ill (cc)
Connell Asbestos Mfg. Co., NY (r)
Dumont Corp., Calif (r,z,bb,cc,ee)
Firestone Tire & Rubber Co., World Bestos Div., Ind (r,cc)
Garlock Packing Co., NY (r,s,cc,ee)
Gatke Corp., Ill (r)
General Asbestos Gasket Mfg. Corp., Mo (r)
General Gasket, Inc., Conn (r)
Hall, C. P. Co., Ohio (s)
Insulation Mfrs. Corp., Ill (ee)
Johns-Manville Corp., NY (r,s,aa,cc,ee)
Keasbey & Mattison Co., Pa (s,cc,ee)
**Lake Asbestos of Quebec, Ltd., Sub of American Smelting & Refining Co., NY**
(r,s,cc)—Ad pp 316-317
Mica Fabricating Co., NJ (s)
National Gasket & Washer Mfg. Co., Inc., NY (r,cc)
Nicolet Industries, Inc., NY (r,s,cc,ee)
North American Asbestos Corp., Ill (r,s)
Panelyte Div., St. Regis Paper Co., NJ (bb,cc)
Peerless Products Industries, Ill (r)
Philadelphia Asbestos Corp., Pa (r)
Precision Paper Tube Co., Ill (ee)
Prince Rubber & Plastics Co., Inc., NY (cc,dd)
Raybestos-Manhattan, Inc., NJ (bb,cc)
Raybestos-Manhattan, Inc., Raybestos Div., Conn (r)
Riegel Paper Corp., NY (r)
Rogers Corp., Conn (cc)
Rostone Corp., Ind (r)
Ruberoid Co., NY (s)
Russell Mfg. Co., Conn (r,s)
Smith Chemical & Color Co., Inc., NY (aa)
Southern Asbestos Co., NC (r,s,ee)
Standard Asbestos Mfg. Co., Ill (r,s)
Staver Co., Inc., NY (r,cc)
Stone Paper Tube Div., Stone Straw Corp., Washington, DC (ee)
Superior Mfg. Co., Pa (r)
Union Asbestos & Rubber Co., Ill (r, cc,ee)
U.S. Polymeric Chemicals, Inc., Conn (s)
U.S. Rubber Co., NY (s)
U.S. Stoneware Co., Ohio (r)
Vellumoid Co., Mass (r,cc)
Victor Mfg. & Gasket Co., Ill (r,cc)

## Balsa Wood
(see Wood)

## Bar
(see specific metal)

Suppliers of Materials

## Beryllium

**Advance Stamping Co., Mich (dd)**
**American Silver Co., Inc., NY (v,dd)**
**Babson Dow Mfg. Co., Mass (o)**
Belmont Smelting & Refining Works, Inc., NY (o,aa)
**Beryllium Corp., Pa** (o,q,w,aa,bb)—Ad p 157
Bridgeport Brass Co., Conn (dd)
**Brinkernoff Brass & Bronze Works, Inc., NY (dd)**
**Brush Beryllium Co., Ohio** (o,q,v,w,z,aa,bb,cc,dd,ee)—Ad p 171
Craft Metal Spinning Co., Ill (cc)
**Dudek & Bock Spring Mfg. Co., Ill (ff)**
**Hardy, Charles, Inc., NY (aa)**
**Hayden Wire Works, Inc., Mass (ff)**
**Inshield Die & Stamping Co., Ohio (dd)**
**Instrument Specialties Co., Inc., NJ** (bb,dd,ff)—Ad p 463
**Landquist Tool & Mfg. Co., Inc.,** Mass (cc,dd)
**Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (dd,ff)**
**Mallory, P.R. & Co., Inc., Ind (bb, dd)**
**Norrich Plastics Corp., Screw Machine Products Div., NY (o,bb)**
**Nuclear Metals, Inc., Mass (w,bb,cc, dd,ee,ff)**
**Olds Alloys Co., Calif (ee)**
**Riverside-Alloy Metal Div., H. K. Porter Co., Inc., NJ** (bb,ff)—Ad p 160
Rodney Metals, Inc., Mass (v,dd)
**Sel-Rex Corp., NJ** (n)—Ad p 356
Seymour Mfg. Co., Conn (bb)
Stauffer-Temescal Co., Calif (o,q,w)
**Superior Tube Co., Pa** (ee)—Ad pp 414-415
Texas Instruments, Inc., Metals & Controls Div., Mass (v)

## Beryllium Copper

(see Copper)

## Billets

(see specific metal)

## Bismuth and Its Alloys

**Alpha Metals, Inc., NJ (o,q,v,bb,cc,dd)**
**American Metal Climax, Inc., NY** (o,w,aa)
Anaconda Co., NY (o)
Belmont Smelting & Refining Works Inc., NY (n,o,w,aa)
**Cerro de Pasco Sales Corp., NY** (w)—Ad p 178
Division Lead Co., Ill (o,ff)
**Empire Metal Co., NY (n,o,q,w,bb,ff)**
Federated Metals Div., American Smelting & Refining Co., NY (o,w)
**Hardy, Charles, Inc., NY (aa)**
**Hayden Wire Works, Inc., Mass (aa)**
Metals Disintegrating Co., Inc., NJ (aa)
**Peerless Alloy Co., Colo (o,w)**
**Republic Metals Co., Inc., NY (o,w)**
**River Smelting & Refining Co., Ohio (o)**
**Sel-Rex Corp., NJ** (n)—Ad p 356
United Refining & Smelting Co., Ill (n,o,q,w,z,bb,cc,dd,ff)
**U.S. Smelting, Refining & Mining Co., NY (w,dd)**

## Borides

(see Refractories)

## Brass

(see Copper)

## Brazing Alloys

Abalon Precision Mfg. Corp., NY
All-State Welding Alloys Co., Inc., NY
Alofs Mfg. Co., Mich
**American Platinum & Silver Div., Engelhard Industries, Inc., NY** —Ad p 493
American Products Corp., Ill
American Silver Co., NY
Ampco Metal, Inc., Wis
Belmont Smelting & Refining Works, Inc., NY
Bridgeport Brass Co., Conn
Burgess-Norton Mfg. Co., Ill
Composite Industriai Metals, Inc., RI
Crucible Steel Co. of America, Pa
Dana Corp., Auburn Div., Ind
Dormont Mfg. Co., Pa
Electric Materials Co., Pa
Eutectic Welding Alloys Corp., NY
Falstrom Co., NJ
Farrelloy Co., Pa
**General Findings & Supply Co., Industrial Div., Mass**
Glidden Co., Ind
Glidden Co., Chemical Divs., Metals Dept., Ind
Goldsmith Bros. Div., National Lead Co., Ill
**Handy & Harman, NY** —Ad p 495
Hayden Wire Works, Inc., Mass
Haynes Stellite Co., Div. of Union Carbide Corp., Ind
Inland Mfg. Co., Neb
International Nickel Co., Inc., NY
Jervis Corp., Mich
Kenmore Machine Products, Inc., NY
Kinkead Industries, Inc., Ill
Kling Metal Spinning & Stamping Co., NY
Kwikset Powdered Metal Products, Calif
Lincoln Iron Works, Vt
**Lucas - Milhaupt Engineering Co., Wis** —Ad p 498
Machine Products Corp., Ohio
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass.
Mansol Ceramics Co., NJ
McDowell Mfg. Co. Pa
Revere Copper & Brass, Inc., NY
Rockwell Engineering Co., Ill
Sall, George Metals Co., Inc., Pa
Trenton Pipe Nipple Co., NJ
United Wire & Supply Corp., RI
Uniworld Research Corp. of America, Ohio
Vanadium-Alloys Steel Co., Pa
Victor Equipment Co., Calif
**Wall Colmonoy Corp., Stainless Process Div., Mich** —Ad p 498
Waterman Industries, Inc., Calif
West Haven Foundry Co., Conn
Western Gold & Platinum Co., Sub. of Wilbur B. Driver Co., Calif
Whitehead Metal Products Co., Inc., NY

## Bronze

(see Copper)

## Buna N Rubber

(see Acrylonitrile-Butadiene Rubber)

## Butadiene Styrene

(see Styrene Butadiene)

## Butyl Rubber

(see Isoprene-Isobutylene Rubber)

## Butyrate

(see Cellulose Acetate Butyrate)

## Cadmium

Allied Research Products, Inc., Md (n)
**Alpha Metals, Inc., NJ (o,q,v,bb,cc,dd)**
**American Metal Climax, Inc., NY (n,o,w,aa,bb)**
**American Silver Co., NY (v,dd)**
**American Smelting & Refining Co., NY (n,q,w)**
**American Zinc Sales Co., Mo (n,o,z)**
**Anaconda Co., NY (o)**
**Anchor Metal Co., Inc., NY (w)**
**Auld, D.L. Co., Ohio (n)**
Belmont Smelting & Refining Works, Inc., NY (n,o,v,w,z,aa,cc)
**Bunker Hill Co., Calif (n,o)**
**Cerro de Pasco Sales Corp., NY** (z,bb)—Ad p 178
**Division Lead Co., Ill (v,cc)**
**Eagle-Picher Co., Ohio (q)**
**Empire Metal Co., NY (n,o,q,w,bb,ff)**
**Federated Metals Div., American Smelting & Refining Co., NY (n,o,w)**
**Goldsmith Bros. Div., National Lead Co., Ill (o,w)**
**Hamilton Watch Co., Precision Metals Div., Pa (v,cc,dd)**
**Hardy, Charles, Inc., NY (aa)**
**Harshaw Chemical Co., Ohio (n)**
**Hayden Wire Works, Inc., Mass (ff)**
**Hull, R.O. & Co., Inc., Ohio (n)**
**International Minerals and Metals Corp., NY (w)**
**Lucas-Milhaupt Engineering Co., Wis (dd,ff)**
**Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (dd,ee,ff)**
**McGean Chemical Co., Ohio (n,dd)**
Metals Disintegrating Co., Inc., NJ (aa)
**Modern Plating Corp., Ill (n)**
**New Jersey Metals Co., NJ (n)**
**New Jersey Zinc Co., NY (n)**
**Octagon Process, Inc., NY (n,o,q,w,z, bb,cc,dd)**
**Peerless Alloy Co., Colo (o,w)**
**Republic Metals Co., Inc., NY (n,o,w)**
**River Smelting & Refining Co., Ohio (w)**
**St. Joseph Lead Co., NY (n,o,w)**
**Sel-Rex Corp., NJ** (n)—Ad p 356
**Stevens, Frederic B., Inc., Mich (n)**
**Triangle Conduit & Cable Co., Inc., NJ (ff)**
**Udylite Corp., Mich (n,bb,cc,ff)**
**United Refining & Smelting Co., Ill (n,o,q,w,z,bb,cc,dd,ff)**
**U.S. Smelting, Refining & Mining Co., NY (o,w,bb)**

## Calorized Coatings

(see Diffusion Coatings)

## Carbides

(see Cermets, Refractories and specific metal)

## Carbon, Graphite

Aerojet-General Corp., Structural Materials Div., Calif (r)
American Metal Products Co., Mich (bb,cc,dd,ee)
**Becker Bros. Carbon Co., Ill (r,z,aa, bb,cc,ee)**
**Black Bear Co., Inc., NY (aa)**
**Blaco Mfg. Co., Ohio (aa)**
**Carbone Corp., NJ (r)**
**Dixon, Joseph Crucible Co., NJ (z, aa,bb)**
**Electro Chemical Engineering & Mfg. Co., Pa (r)**
Gibson Electric Co., Pa (r,aa)
**Graphite Metallizing Corp., NY (r)**
Graphite Products Corp., Ohio (aa)
**Graphite Specialties Corp., NY** (r,bb,ee)—Ad p 309
Great Lakes Carbon Corp., NY (r,z,bb)
**Heil Process Equipment Corp., Ohio (r)**
**Henrite Products Corp., Ohio (r)**
**Hofford Varnish Co., Inc., NJ (r)**
**Industrial Tectonics, Inc., Mich (r)**
**Markal Co., Ill (z)**
McGee Chemical Co., Inc., Pa (aa)
**Metallized Carbon Co., NY (r)**
**Morganite, Inc., NY (r,bb,ee)**
**National Carbon Co., Div. of Union Carbide Corp., NY** (r,s,z,aa,bb,ee)—Ad p 307
**Ohio Carbon Co., Ohio** (r,z,aa,bb,cc,ee)—Ad p 322
**Pure Carbon Co., Inc., Pa (bb)**
**Russell Mfg. Co., Conn (r,s)**
**St. Marys Carbon Co., Pa (r,z)**
**Serwell Products Co., Ohio (aa)**
**Smith Chemical & Color Co., Inc., NY (aa)**
**Speer Carbon Co., Pa** (r)—Ad p 318
**Stackpole Carbon Co., Pa** (r,z,bb,ee)—Ad p 320
Superior Carbon Products, Inc., Ohio (r)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

United Carbon Products Co., Mich (r, z,aa,bb,cc,ee)
U.S. Graphite Co., Div. of Wickes Corp., Mich (r)
U.S. Polymeric Chemicals, Inc., Conn (s)

## Carbon Steel

(see Steel)

## Casting Resins

(see specific plastic or rubber)

## Castings, Centrifugal

Al-Fin Div., Arthur Tickle Engineering Works, Inc., NY (a,e)
All Metals Precision Casting Corp., NY (a,b,g)
Allegheny Ludlum Steel Corp., Pa (g)
Alloy Precision Castings Co., Ohio (a, b,c,e,f)
American Brake Shoe Co., NY (a,b,j)
**American Cast Iron Pipe Co., Ala**
(a,c,f,g)—Ad p 410
American Crucible Products Co., Ohio (b)
Ampco Metal, Inc., Wis (b)
Asco Sintering Corp., Calif (a,b)
Baldwin-Lima-Hamilton Corp., Pa (a, b,f)
Bendix Foundries Div., Bendix Aviation Corp., NJ (a,e)
Blaw-Knox Co., Pa (f,g)
Buckeye Brass & Mfg. Co., Ohio (a)
Bunting Brass & Bronze Co., Ohio (b)
Calorizing Co., Pa (f,g)
Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich (c,g)
Centrifugal Casting Co., Calif (c,f,g)
Centrifugal Casting Co., NY (a,b,c,f, h,j)
Centrifugal Casting Machine Co., Okla (a,b)
Centr-O-Cast & Engineering Co., Mich (a)
Comet Metal Products Co., Inc., NY (d)
Cooper Alloy Corp., NJ (g)
Copper & Brass Sales Inc., Mich (b)
Curtiss-Wright Corp., Metal Processing Div., NY (g)
Cyril Bath Co., Ohio (g)
Dayton Foundry, Calif (c)
Derby Castings Co., Conn (a,b)
Division Lead Co., Ill (d)
**Duraloy Co., Pa**
(f,g)—Ad p 417
Electric Steel Foundry Co., Ore (f,g,h)
Electro-Alloys Div., American Brake Shoe Co., Ohio (g)
Engineered Castings Div., American Brake Shoe Co., NY (c,g)
Florence Pipe Foundry & Machine Co., NJ (c)
Frasse, Peter A. & Co., Inc., NY (g)
General Alloys Co., Mass (f)
General Electric Co., Foundry Dept., NY (a,b)
Haynes Stellite Co., Div. of Union Carbide Corp., Ind (f)
Hi-Grade Alloy Corp., Ill (d,j)
Hughes Tool Co., Tex (g)
Humphrey Castings, Inc., Calif (a,b,f, g)
Illinois Precise Casting Co., Ill (a, b,f,g)
International Nickel Co., Inc., NY (f)
Janney Cylinder Co., Pa (a,b,c,f)
Johnson Bronze, Pa (b)
Kay-Brunner Steel Products, Inc., Calif (g)
Kelsey-Hayes Co., Metals Div., NY (f)
Lebanon Steel Foundry, Pa (g)
Linton Precision Casting Co., Ind (a, b,c,f,g,j)
Magnolia Metal Co., NJ (b)
Mallory, P.R. & Co., Inc., Ind (b)
McCarter Iron Works, Inc., Pa (c,g)
**Meehanite Metal Corp., NY**
(c)—Ad p 461
Metal Goods Corp., Mo (a,b,c,f)
Metals Processing Div., Curtiss-Wright Corp., NY (f,g)
Milwaukee Aluminum & Brass Foundry, Wis (a,b)
Misco Precision Casting Co., Mich (c, f,g)
Moccasin Bushing Co., Tenn (b)
National Bearing Div., American Brake Shoe Co., Pa (b)
National Lead Co., NY (b,d)
National Lead Construction Co., Inc., NJ (l)
Ohio Steel Foundry Co., Ohio (f)
Oil City Iron Works, Tex (c)
Olds Alloy Co., Calif (a,b,d,f)
Oregon Metallurgical Corp., Ore (h)
Precision Castparts Corp., Ore (b,f,g)
Precision Founders, Inc., Calif (a,b,c,f, g,j)
Precision Metalsmiths, Inc., Ohio (a, b,c,d,f,g)
Quality Electric Steel Castings, Inc., Tex (g)
Rockwell Engineering Co., Ill (a,b,c,g)
Ryerson, Joseph T. & Sons, Inc., Ill (g)
Saginaw Bay Industries, Inc., Mich (a,e)
**Sandusky Foundry & Machine Co., Ohio**
(b,f,g)—Ad p 427
Schilling Bronze Co., NY (b,d,f,j)
Sheller Mfg. Corp., Mich (j)
**Shenango Furnace Co., Centrifugally Cast Products Div., Ohio**
(b,c,f)—Ad p 422
Sorbo-Mat Process Engineers, Mo (c)
State Foundry & Machine Co., Wis (c)
Staver Co., Inc., NY (d)
Swayne-Robinson & Co., Ind (a,c)
Terre Haute Bronze & Brass Foundry, Ind (b)
Thys Co., Calif (a,b,c,f,g)
True Alloys, Inc., Mich (a,b,d,j)
U.S. Pipe & Foundry Co., Ala (c,g)
Uniworld Research Corp. of America, Ohio (c)
Utica Drop Forge & Tool Co., NY (f, g)
Vollrath Co., Wis (g)
Weatherhead Co., Ind (j)
West Steel Casting Co., Ohio (f)
Winters Foundry & Machine Co., Inc., Ohio (a,b)
Wisconsin Centrifugal Foundry, Inc., Wis (a,b,d,f,g)

## Castings, Die

A & A Die Casting Co., Calif (j)
Able Tool & Engineering Co., Ill (a,j)
Accurate Die Casting Co., Ohio (a,e,j)
Accurate Metal Weather Strip Co., Inc., NY (j)
Admiral Die Castings Div., Portable Electric Tools, Inc., Ill (a,j)
Advance Pressure Castings, Inc., NY (a,j)
Advance Tool & Die Casting Co., Wis (a,j)
Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich (a,j)
Allen-Stevens Corp., NY (j)
Aluminum Co. of America, Pa (a)
Ambrit Industries, Inc., Calif (a,d,j)
American Aluminum Castings Co., NJ (a)
American Foundries Co., Mich (c)
American Foundry & Machine Div., Elmco Corp., Utah (g)
Auel Industries, Pa (j)
Auld, D.L. Co., Ohio (a,j)
Aurora Metal Co., Ill (b)
Badger Die Diecasting Corp., Wis (a,j)
Belmont Smelting & Refining Works, Inc., NY (a,d)
Bendix Foundries Div., Bendix Aviation Corp., NJ (a,e)
Briel Industries, Inc., Ind (a)
Brown Lipe Chapin Div., General Motors Corp., NY (j)
Centrifugal Casting Machine Co., Okla (a)
Centr-O-Cast & Engineering Co., Mich (a)
Century Die Casting Co., Ill (a,j)
Char-Lynn Co., Diecasting Div., Minn (a,j)
Chicago White Metal Casting, Inc., Ill (a,j)
Cincinnati Foundry Co., Ohio (c)
Comet Metal Products Co., Inc., NY (j)
Conneaut Die Casting Co., Ohio (a,j)
Continental Die Casting Corp., Mich (j)
Crown Metal Co., Wis (d)
Crucible Steel Co. of America, Pa (c,f,g)
Davis Products Corp., NY (j)
Dayton Bronze Bearing Co., Ohio (a,j)
Dayton Malleable Iron Co., Ohio (a)
Die Cast Products, Inc., Calif (a,j)
Diecast Corp., Mich (a,j)
Division Lead Co., Ill (d)
Doehler-Jarvis Div., National Lead Co., Ohio, (a,b,e,j)
Dollin Corp., NJ (a,d,j)
Dow Chemical Co., Dow Metal Products Co. Div., Mich (e)
Duane Specialties, Ltd., NJ (j)
Du-Wel Metal Products, Inc., Mich (a,j)
Eclipse-Pioneer Div., Bendix Aviation Corp., NJ (a,c)
Electric Autolite Co., Ohio (a,j)
Evans Metal Co., Ga (a,d,j)
Federal Die Casting Co., Ill (a)
General Electric Co., Foundry Dept., NY (b)
General Motors Corp., Fabricast Div., Ind (a)
Grammes, L.F. & Sons, Inc., Pa (j)
Grand Rapids Brass Co., Mich (j)
Grey, C.M. Industries, Inc., NJ (a,j)
Gries Reproducer Corp., NY (j)
Hamilton Die Cast, Inc., Ohio (a,j)
Hampden Brass & Aluminum Co., Mass (a,j)
Harbot Die Casting Corp., NJ (a)
Hardy Mfg. Corp., Ind (j)
Harvey Aluminum Sales, Inc., Calif (a)
Harvill Corp., Calif (a,b,e,j)
Hercules Fastener Co., Ill (j)
Hilfinger Corp., Ohio (j)
Hoover Co., Die Casting Div., Ohio (a, j)
Humphrey Castings, Inc., Calif (a)
Jersey Plastic & Die Casting Co., NJ (a,j)
Jervis Corp., Mich (a,j)
Kaiser Aluminum & Chemical Sales, Inc., Ill (a)
Kamin Die Casting & Mfg. Co., Ill (a,j)
Kent Castings Corp., Mich (j)
Kiowa Corp., Iowa (a,j)
Krone, Paul Die Casting Co., Ill (a,j)
La France Precision Casting Co., Pa (j)
Lake Erie Foundry Co., NY (c)
Latrobe Die Casting Co., Pa (a,d,j)
Lester Castings, Inc., Ohio (a,j)
Light Metals, Inc., Ind (a,e)
Litemetal Dicast, Inc., Mich (e)
Littlestown Hardware & Foundry Co., Inc., Pa (a)
Livingston-Tyler Products, Ohio (j)
Madison Kipp Corp., Wis (a,j)
Magline Inc., Mich (a,e)
Mallory, P.R. & Co., Inc., Ind (b,h)
Manor Die Cast Corp., Ohio (a)
**Meehanite Metal Corp., NY**
(c)—Ad p 461
Meta-Mold Aluminum Co., Sub. of Dayton Malleable Iron Co., Wis (a,e)
Milwaukee Die Casting Co., Wis (a,d,j)
Missouri Diecasting Co., Mo (a,j)
Model Brass Co., Inc., Ill (a,b)
Mohawk Foundries, Inc., Ohio (a)
Moldcast Products, Inc., NJ (a)
Monarch Aluminum Mfg. Co., Ohio (a,j)
Monarch Tool & Mfg. Co., Ky (j)
Mt. Vernon Die Casting Corp., Conn (a)
National Die Casting Co., Ill (a,j)
National Lead Co., NY (a,b,d,e,j)
National Lead Construction Co., Inc., NJ (d)
National Lock Co., Ill (j)
National Malleable & Steel Castings Co., Ohio (j)
National Supply Co., Pa (g)
New England Die Casting Co., Conn (a,j)
**New Jersey Zinc Co., NY**
(j)—Ad pp 452-453
New Products Corp., Mich (a,e,j)
Newton-New Haven Co., Conn (a,j)
Norgren-Stemac, Inc., Colo (j)
Olderman Mfg. Corp., Conn (j)
Paragon Die Casting Co., Ill (a,j)
Paramount Die Casting Co., Mich (a, e,j)
Parker White Metal Co., Pa (a,d,f,j)
Peasley Products, Inc., Conn (a,j)
Phoenix Die Casting Co., NY (a,j)
Pittsburgh Die & Casting Co., Pa (a,j)
Pressure Castings, Inc., Ohio (a,j)
Production Die Casting Co., Tex (a,e,j)
Rangers Die Casting Co., Calif (a,j)
Republic Die Casting Co., Mo (a,j)
Republic Metals Co., Inc., NY (d)
Rockwell Engineering Co., Ill (a,b,c,g)
Rupert Diecasting Co., Mo (a,j)
Ryerson, Joseph T. & Sons, Inc., Ill (a,g)
St. Louis Diecasting Corp., Mo (a,j)
St. Marys Foundry Co., Ohio (c)
Sargent & Greenleaf, Inc., NY (a,j)
Schilling Bronze Co., NY (a,b,d,f,j)
Schneider, Bowman Co., Inc., Pa (c)
Schultz Die Casting Co., Ohio (a,j)
Sillcocks Miller Co., NJ (a,c,d,j)
Southern Metal Products Co., La (a)
Star Heel Plate Co., Inc., NJ (a,j)
Staver Co., Inc., NY (d)
Stella Products Corp., NJ (j)
Sterling Die Casting Co., NY (a,j)
Stewart-Warner Corp., Stewart Die Casting Div., Ill (a,e,j)
Stoody Co., Calif (a,b,d,e)
Superior Die Casting Co., Ohio (a,j)
Thompson Products, Light Metals Div., Ohio (a)
Titan Metal Mfg. Co., Pa (b)
Tower Grove Foundry, Mo (c)
**Twin City Die Casting Co., Minn**
(a,d,j)—Ad p 418
Veeder-Root, Inc., Conn (j)
Vulcan Rail & Construction Co., NY (a,c,g)
Weber-Knapp Co., NY (a)
West Irving Die Casting Co., Ill (a)
Westland Die Casting, Inc., Calif (a,j)
Wheaton Die Casting Corp., NJ (a,j)

## Castings, Investment

Aerojet-General Corp., Structural Materials Div., Calif (a)
All Metals Precision Casting Corp NY (a,b,g)
Alloy Precision Castings Co., Ohio (a b,c,e,f,g)
Arwood Corp., NY (a,b,e,g)
Atlantic Casting Engineering Corp., NJ (a,b)
Austenal Co., Div. of Howe Sound Co., NY (a,c,f,g)
Bone Engineering Corp., Calif (a,b,f,g)
Buckeye Brass & Mfg. Co., Ohio (a, b,c,g)
Casting Engineers, Inc., Ill (a,b,c,f,g)
Centrifugal Casting Co., NY (a,b,e,f, h,j)
Chrysler Corp., Mich (a,b,c,e,f,g,h,j)
Electric Steel Foundry Co., Ore (h)
Electronicast Div., Nilsen Mfg. Co., Ill (a,b,c,e,f,g,h,j)
Engineered Precision Casting Co., NJ (a,b,c,f,g)

Suppliers of Materials

General Motors Corp., Fabricast Div., Ind (a,f)
Gray-Syracuse, Inc., NY (a,b,c,f,g)
Harcast Co., Inc., Pa (a,b,c,f,g)
Haynes Stellite Co., Div. of Union Carbide Corp., Ind (c,f,g)
Hawkridge Bros. Co., Mass (a,b,c,e,f,g,h,j)
Hitchiner Mfg. Co., Inc., NH (a,b,c,f,g)
Howard Foundry Co., Ill (a,b,c,f,g)
Humphrey Castings, Inc., Calif (a,b,f,g)
Illinois Precise Casting Co., Ill (a,b,f,g)
International Nickel Co., Inc., NY (f)
Investment Casting Co., NJ (a,b,c,f,g)
Jelrus Precision Casting Corp., NY (a,b,c,e,f,g,h,j)
Joseff-Hollywood Co., Calif (a,b,c,g)
Kolcast Industries Div., Thompson Products, Inc., Ohio (a,c,f,g)
Lawrence Laboratory, Calif (a,b,e)
Lebanon Steel Foundry, Pa (g)
Linton Precision Casting Co., Ind (a,b,c,f,g,j)
Loeffler, J. M. Machine Co., Pa (b)
Lynn Casting Corp., Calif (a,b,d,f,g)
Manco Products, Inc., Mich (f,g)
**Meehanite Metal Corp., NY**
(c)—Ad p 461
Mercast Mfg. Corp., Calif (a,b,c,e,f,g)
Metal Goods Corp., Tex (f)
Midwest Precision Castings Co., Ohio (a,b,c,f,g)
Misco Precision Casting Co., Mich (c,f,g)
National Precision Casting Corp., Div. of Beryllium Corp., Pa (a,b,c,f,g)
Omni-Metal Castings, Inc., NY (a, b,c,f,g)
Oregon Metallurgical Corp., Ore (h)
Picco, Inc., Calif (a,b,c,f,g)
Precision Castparts Corp., Ore (b,f,g)
Precision Founders, Inc., Calif (a, b,c,f,g,j)
Precision Metalsmiths, Inc., Ohio (a, b,c,d,f,g)
Rausch Mfg. Co., Inc., Minn (a,b)
Rockwell Engineering Co., Ill (a,b,c,g)
Rode, Inc., Mass (a,b)
Rolle Mfg. Co., Pa (a,b,e,f,g)
Solon Foundry, Inc., Ohio (a,e)
Star Heel Plate Co., Inc., NJ (a,b)
Staver Co., Inc., NY (d)
Thompson, K.W. Tool Co., NY (a,b, c,e,f,g,h,j)
Thys Co., Calif (a,b,c,f,g)
United Shoe Machinery Corp., Mass (g)
Uniworld Research Corp. of America, Ohio (c,f)
Vascoloy-Ramet Corp., Ill (b,g)
Wall Colmonoy Corp., Stainless Process Div., Mich (c,f)
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (a,b,c,f,g,h)
York Casting, Inc., NY (a,b,c,e,f,g, h,j)
Z & H Mfg. Co., NY (a,b,c,e,f,g,h,j)

## Castings, Nonmetallic
(plastics and rubber)

Ace Plastic Co., NY (l)
Acushnet Process Co., Mass (m)
Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich (k,l)
Allied Resinous Products, Inc., Ohio (k)
American Agile Corp., Ohio (k)
Amos Molded Plastics Div., Amos-Thompson Corp., Ind (k)
Apex Reinforced Plastics Div., White Sewing Machine Corp., Ohio (l)
Auburn Plastic Engineering, Ill (k)
Automotive Rubber Co., Inc., Mich (m)
Biggs, Carl H. Co., Inc., Calif (k,l)
Boonton, Molding Co., NJ (k,l,m)
Buckeye Molding Co., Ohio (k)
Cadillac Plastic & Chemical Co., Mich (k)
Campro Co., Ohio (k)
Cast Optics Corp., NJ (k,l)
Celicote Co., Ohio (l)
Chemical Coatings & Engineering Co., Pa (k,l,m)
Chemical Development Corp., Mass (l)
Conneaut Rubber & Plastics Co., Div. of U.S. Stoneware Co., Ohio (k)
Disogrin Industries, Inc., NY (m)
Douglas & Sturgess, Calif (l,m)
Duriron Co., Inc., Ohio (l)
Eby, Hugh H. Co., Pa (k,l)
Eclipse Plastic Industries, Inc., Fla (k)
Electric Auto-Lite Co., Ohio (k,l)
Electronic Production & Development, Inc., Chemical Div., Calif (k)
Eljay Corp., Md (l)
Emerson & Cuming, Inc., Mass (k,l,m)
Foss Mfg. Co., Id (l)
Fry Plastics International, Calif (k,l)
General Mills, Inc., Chemical Div., Ill (k,l)
Goodrich, B.F. Industrial Products Co., Ohio (k)
Grimes Mfg. Co., Plastic Research Products, Ohio (l)
Hays Mfg. Co., Pa (l)
Hysol Corp., NY (l)
Kerrco, Neb (k,l,m)
Kurz Kasch, Inc., Ohio (l)
Madin Plastics Inc., NJ (k)
Marblette Corp., NY (l)
Mechanical Rubber Products Co., NY (l)
Minnesota Rubber & Gasket Co., Minn (k,m)
Mobay Chemical Co., Pa (m)
Munray Products Div., Fanner Mfg. Co., Ohio (k,m)
New England Tape Co., Div. of United-Carr Fastener Corp., Mass (l)
Polymer Corp. of Pennsylvania, Sub. of Polymer Corp., Pa (k)
Pyrosil, Inc., Ohio (l)
Quelcor, Inc., Pa (k)
Reinhold Engineering & Plastics Co., Inc., Calif (l)
Ren Plastics, Inc., Mich (l)
Sewell Mfg. Co., Mich (l)
Sierra Electric Corp., Calif (k,l)
Superior Plastics, Inc., Ill (k)
Sylvania Electric Products, Inc., Parts Div., Pa (k,l)
Thombert, Inc., Iowa (l,m)
Trostel, Albert Packing, Ltd., Wis (l)
Tuff Clad, Inc., Ohio (k)
U.S. Stoneware Co., Ohio (k)

## Castings, Permanent Mold

A C F Industries, Inc., NY (e)
Abco Aluminum & Brass Works, Tex (a,d)
Acme Aluminum Foundry Co., Ill (a)
Advance Aluminum Castings Corp., Ill (a)
Al-Fin Div., Arthur Tickle Engineering Works, Inc., NY (a,e)
Aluminum Alloys Corp., Mich (a)
Aluminum Co. of America, Pa (a)
Aluminum Casting & Engineering Co., Wis (a,j)
Aluminum Industries, Inc., Ohio (a)
Aluminum Permanent Mold Co., Mich (a)
American Aluminum Castings Co., NJ (a)
American Brake Shoe Co., NY (a,b, c,g,j)
American Metal Climax, Inc., NY (b)
Apex Steel Corp., Ltd., Calif (g)
Baldt Anchor, Chain & Forge Div., Boston Metals Co., Pa (a,b)
Belmont Smelting & Refining Works, Inc., NY (a,d,j)
Bendix Foundries Div., Bendix Aviation Corp., NJ (a,e)
Bohn Aluminum & Brass Corp., Mich (a)
Briggs-Shaffner Co., NC (a)
Bronze & Steel Die Casting Co., Ill (b)
Buckeye Brass & Mfg. Co., Ohio (a, b,j)
Bunker Hill Co., Calif (d,j)
Bunting Brass & Bronze Co., Ohio (a,b)
Calumet Div., Calumet & Hecla, Inc., Mich (c)
Centrifugal Casting Machine Co., Okla (a)
Centr-O-Cast & Engineering Co., Mich (a)
Chattanooga Aluminum Foundry, Inc., Tenn (a)
Cochrane Foundry, Inc., Pa (a,b,j)
Crobalt, Inc., Mich (g)
Crown Metal Co., Wis (d)
Davis Products Corp., NY (j)
Dayton Malleable Iron Co., Ohio (a)
Derby Castings Co., Conn (a)
Dirilyte Co. of America, Inc., Ind (b)
Division Lead Co., Ill (d)
Dixie Bronze Co., Ala (a,b,f)
Dostar Foundry & Machine Co., Mich (c)
**Dow Chemical Co., Dow Metal Products Co. Div., Mich**
(e)—Ad pp 408-409
**Eaton Mfg. Co., Foundry Div., Mich**
(c)—Ad p 459
Eclipse-Pioneer Div., Bendix Aviation Corp., NJ (a,e)
Electric Steel Foundry Co., Ore (f,g)
Enterprise Wheel & Car Corp., Va (a)
Est Co., Inc., Wis (a,e)
**Exalco Mfg. Co., Ohio**
(a)—Ad p 420
Fairfield Aluminum Casting Co., Iowa (a)
Flynn, Michael Mfg. Co., Pa (a)
Forest City Foundries Co., Ohio (c)
Foster Aluminum Alloy Products Corp., NY (a)
General Aluminum Mfg. Co., Ohio (a,e)
General Electric Co., Foundry Dept., NY (c)
General Motors Corp., Fabricast Div., Ind (a)
Gilbert Brass & Foundry Co., Mo (a)
Gillett & Eaton, Inc., Minn (a,c)
Hampden Brass & Aluminum Co., Mass (a)
Harvill Corp., Calif (a,e)
Howard Foundry Co., Ill (a,e)
Humphrey Castings, Inc., Calif (a)
Johnson Bronze Co., Pa (b)
Kaiser Aluminum & Chemical Sales, Inc., Ill (a)
Lebanon Steel Foundry, Pa (g)
Light Metals, Inc., Ind (a,e)
Light Metals Dept., American Brake Shoe Co., NJ (a,e)
Littlestown Hardware & Foundry Co., Inc., Pa (a)
Magline, Inc., Mich (a,e)
Magnolia Metal Co., NJ (b)
Mallory, P.R. & Co., Inc., Ind (h)
Manco Products, Inc., Mich (b)
Manor Die Cast Corp., Ohio (a)
Mansfield Brass & Aluminum Corp., Ohio (a)
Marshall Car & Wheel Foundry Co., Inc., Tex (c)
McLanahan & Stone Corp., Pa (c)
**Meehanite Metal Corp., NY**
(c)—Ad p 461
Metal Mold Magnesium Corp., Wis (e)
Meta-Mold Aluminum Co., Sub of Dayton Malleable Iron Co., Wis (a,e)
Moccasin Bushing Co., Tenn (b)
Mohawk Foundries, Inc., Ohio (a)
Moldcast Products, Inc., NJ (a)
Monarch Aluminum Mfg. Co., Ohio (a)
Morse, Fred W. Co., RI (a,j)
National Aluminum Mfg. Co., Ill (a)
National Lead Construction Co., Inc., NJ (d)
Nuclear Metals, Inc., Mass (a,b,c,e,f, g,h)
Olds Alloys Co., Calif (b,d,f)
Oregon Metallurgical Corp., Ore (h)
Parker, Charles Co., Conn (a,j)
Peasley Products, Inc., Conn (a,j)
Permold Co., Ohio (a)
Philadelphia Bronze & Brass Corp., Pa (a,b,f)
Quality Aluminum Casting Co., Wis (a)
Rockwell Engineering Co., Ill (a,b,c,g)
Rolle Mfg. Co., Pa (a,e)
Saginaw Bay Industries, Inc., Mich (a,e)
Sandusky Foundry & Machine Co., Ohio (b,f,g)
Schilling Bronze Co., NY (a,b,d,f,j)
Schmeller Aluminum Foundry Co., Ohio (a)
Skookum Co., Inc., Ore (g)
Sorbo-Mat Process Engineers, Mo (c)
Standard Magnesium Corp., Okla (e)
Star Heel Plate Co., Inc., NJ (a,b)
Staver Co., Inc., NY (d)
Sterling Aluminum Products, Inc., Mo (a)
Stewart-Warner Corp., Stewart Die Casting Div., Ill (a)
Superb Light Alloys, Inc., NY (a,e)
Texas Foundries, Inc., Tex (c,g)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Thompson Products, Light Metals Div., Ohio (a)
Tickle, Arthur Engineering Works, Inc., NY (a)
True Alloys, Inc., Mich (a,b,d,j)
Universal Castings Corp., Ill (a,b)
Vulcan Rail & Construction Co., NY (a,c)
Waterman Industries, Inc., Calif (a)
Wellman Bronze & Aluminum Co., Ohio (a,e)
Williams, A.C. Co., Ohio (e)
Winters Foundry & Machine Co., Inc., Ohio (a)
Wisconsin Aluminum Foundry Co., Inc., Wis (a,b)

## Castings, Plaster Mold

Aerojet-General Corp., Structural Materials Div., Calif (a)
Al-Fin Div., Arthur Tickle Engineering Works, Inc., NY (a,e)
All Metals Precision Casting Corp., NY (a,b)
Alloy Precision Castings Co., Ohio (a, b,c,e,f,g)
Aluminum Co. of America, Pa (a)
American Aluminum Casting Co., NJ (a)
**Atlantic Casting Engineering Corp., NJ**
(a,b)—Ad p 438
Bean, Morris & Co., Ohio (a)
Beloit Foundry Co., Ill (c)
Bendix Foundries Div., Bendix Aviation Corp., NJ (a)
Chattanooga Aluminum Foundry, Inc., Tenn (a)
Curtiss-Wright Corp., NY (g)
Derby Castings Co., Conn (a)
Eclipse-Pioneer Div., Bendix Aviation Corp., NJ (a,e)
General Motors Corp., Fabricast Div., Ind (a)
Hampden Brass & Aluminum Co., Mass (a)
Humphrey Castings, Inc., Calif (a)
Larson, W. O. Foundry Co., Ohio (c)
Lebanon Steel Foundry, Pa (g)
Light Metals Dept., American Brake Shoe Co., NJ (a)
Lincoln Foundry Corp., Calif (c)
Loeffler, J. M. Machine Co., Pa (b)
**Mechanite Metal Corp., NY**
(c)—Ad p 461
Mercast Mfg. Corp., Calif (a,b,c,e, f,g)
Ohio Precision Castings, Inc., Ohio (a,b,f)
Olderman Mfg. Corp., Conn (b)
Oregon Metallurgical Corp., Ore (h)
Rockwell Engineering Co., Ill (a,b,c,g)
Ross-Meehan Foundries, Tenn (c,g)
Schilling Bronze Co., NY (a,b,d,f,j)
Schneider, Bowman Co., Inc., Pa (c)
Solon Foundry, Inc., Ohio (a,e)
Sorbo-Mat Process Engineers, Mo (c)
True Alloys, Inc., Mich (a,b)
Universal Castings Corp., Ill (a,b)
Wayne Foundry & Stamping Co., Mich (j)
Western Iron & Foundry Co., Inc., Kan (c)

## Castings, Sand

Abco Aluminum & Brass Works, Tex (a,b,d,f,j)
Acco Steel Casting Div., American Chain & Cable Co., Inc., Pa (b, c,g)
Acme Aluminum Foundry Co., Ill (a)
Acme Foundry & Machine Co., Kan (c)
Acme Foundry & Machine Co., Okla (c)
Advance Foundry Co., Ohio (c)
Aelco Foundries, Inc., Wis (a,b,d,e, f,g)
Albany Car Wheel Co., Inc., NY (c)
Albert Lea Foundry-Queen Products Div., King-Seeley Corp., Minn (c)
Albion Malleable Iron Co., Mich (c)
Alcasco Foundry, Ill (a,b)
Al-Fin Div., Arthur Tickle Engineering Works, Inc., NY (a,e)
Allegheny Foundry Co., Pa (c)
Allegheny Ludlum Steel Corp., Pa (g)
Allied Steel Castings Co., Ill (g)
Alloy Cast Steel Co., Ohio (g)
Alloy Steel Casting Co., Pa (f,g)
Almont Mfg. Co., Mich (c)
Alten Foundry & Machine Works, Inc., Ohio (c)
Aluminum Alloys Corp., Mich (a)
Aluminum Co. of America, Pa (a,e)
Aluminum Industries, Inc., Ohio (a)
Aluminum Permanent Mold Co., Mich (a)
Amalgamated Steel Corp., Ohio (g)
American Aluminum Casting Co., NJ (a)
American Brake Shoe Co., NY (a, b,j)
American Car & Foundry Div., ACF Industries, Inc., NY (c)
American Cast Iron Pipe Co., Ala (c,f,g)
American Crucible Products Co., Ohio (b)
American Foundries Co., Mich (c)
American Laundry Machinery Co., NY (c)
American Light Alloys, Inc., NJ (a, e)
American Manganese Steel Div., American Brake Shoe Co., Ill (g)
American Metal Climax, Inc., NY (b)
American Sanitary Mfg. Co., Ill (b)
American Steel Foundries, Ind (g)
American Steel Foundries, Ill (g)
Ampco Metal, Inc., Wis (b)
Apex Foundry, Inc., Mich (c,e,f)
Apex Steel Corp., Ltd., Calif (g)
Arkansas Foundry Co., Ark (c)
Arneson Foundry Co., Wis (c,g)
Arnold Engineering Co., Ill (a,c,f)
Arzt, T.L. Foundry Co., Ill (c)
Atlantic Foundry Co., Ohio (c,g)
Atlantic Steel Castings Co., Pa (g)
Atlas Brass Foundry, Calif (b)
Atlas Foundry Co., Ohio (c)
Atlas Foundry & Machine Co., Wash (c,g)
Atlas Foundry & Mfg. Co., Calif (c)
Auto Specialties Mfg. Co., Mich (c)
Badger Malleable & Mfg. Co., Wis
Baldwin-Lima-Hamilton Corp., Pa (a, b,f,g)
Banner Iron Works, Mo (c)
Barnard Foundry Co., Inc., Mass (b)
Barnett Foundry & Machine Co., NJ (c)
Baxter Foundry & Machine Works, Inc., Id (a,b,c)
Bay City Electric Steel Casting Co., Mich (g)
Bay City Foundry Co., Mich (c)
Bay State Tool & Machine Co., Mass (g)
Bean, Morris & Co., Ohio (c)
Bearium Metals Corp., NY (b)
Beaver Valley Alloy Foundry Co., Pa (c,g)
Bellaire Stove Co., Ohio (c)
Belle City Malleable Iron Co., Wis (c)
Beloit Foundry Co., Ill (c)
Bendix Foundries Div., Bendix Aviation Corp., NJ (a,e)
Beryllium Corp., Pa (b)
Bethlehem Steel Co., Pa (c,g)
Bierman-Everett Foundry Co., NJ (a, b,c)
Bignall Co., NY (c)
Black-Clawson Co., Ohio (c)
Blaw-Knox Co., Pa (f,g)
Bond, Charles Co., Pa (c)
Bonnot Co., Ohio (c)
Briggs-Shaffner Co., NC (a,c)
Brinkerhoff Brass & Bronze Works, Inc., NY (a)
Bruce Foundry and Mfg. Co., Mich (c)
Buckeye Iron & Brass Works, Ohio (a,b)
Bunting Brass & Bronze Co., Ohio (b)
Butler Engine & Foundry Co., Inc., Pa (a,b,c)
Cadillac Malleable Iron Co., Mich (c)
Calorizing Co., Pa (f,g)
Calumet Div., Calumet & Hecla, Inc., Mich (c)
Calumet Steel Castings Corp., Ind (g)
Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich (c,g)
Canton Malleable Iron Co., Ohio (c)
Carondelet Foundry Co., Mo (c,f,g)
Case, J.I. Co., Wis (c)
Castalloy Co., Inc., Mass (a,e)
Casting Service Corp. of Michigan, Mich (c)
Central Casting Div., King-Seeley Corp., Mich (c)
Chain Belt Co., Wis (c)
Chambersburg Engineering Co., Pa (c)
Chattanooga Aluminum Foundry, Inc., Tenn (a)
Chicago Aluminum Castings, Ill (a)
Chicago Hardware Foundry Co., Ill (a,b,c)
Chicago Malleable Castings Co., Ill (c)
Cincinnati Foundry Co., Ohio (c)
Clark Bros. Co. Div., Dresser Operations, Inc., NY (c)
Clarksville Foundry & Machine Works, Tenn (c)
Cleveland Foundry & Mfg. Co., Inc., Tenn (c)
Clinton Metal Products Co., Ohio (a)
Cochrane Foundry, Inc., Pa (a,b,j)
Columbian Bronze Corp., NY (a,b,d)
Columbiana Pump Co., Ohio (c)
Commercial Iron Works, Calif (c)
Commercial Steel Casting Co., Ohio (g)
Compton Foundry, Calif (c)
Continental Gin Co., Ala (c)
Cooper Alloy Corp., NJ (g,h)
Cooper-Bessemer Corp., Ohio (c) (a,b)
Copper & Brass Sales, Inc., Mich (c)
Crawford & Doherty Foundry Co., Ore (c)
Crown Non-Ferrous Foundry, Inc., Pa (a,b,f)
Crucible Steel Casting Co., Pa (g)
Curtiss-Wright Corp., Metals Processing Div., NY (f,g)
Dalton Foundries, Inc., Ind (c)
Darling Valve & Mfg. Co., Pa (c)
Dayton Bronze Bearing Co., Ohio (a,b)
Dayton Foundry, Calif (c)
Dayton Malleable Iron Co., Ohio (a, c)
Decatur Casting Co., Ind (c)
Decrow Engineering Corp., NY (a,b)
De Laval Steam Turbine Co., NJ (c)
Derby Castings Co., Conn (a,b)
De Sanno Foundry & Machine Co., Calif (a,b)
Detroit Brass & Malleable Co., Mich (c)
Deuscher, H.P. Co., Ohio (c)
Dexter Foundry Div., Philco Corp., Iowa (c)
Dirilyte Co. of America, Inc., Ind (b)
Division Lead Co., Ill (d)
Dixie Bronze Co., Ala (a,b,f)
Dodge Steel Co., Pa (g)
Dormont Mfg. Co., Pa (b)
**Dow Chemical Co., Dow Metal Products Co. Div., Mich**
(e)—Ad pp 408-409
Driver-Harris Co., NJ (f)
Ductile Iron Foundry, Inc., Conn (c)
Duluth Brass Works Co., Minn (a,b)
**Duraloy Co., Pa**
(g)—Ad p 417
Duriron Co., Inc., Ohio (c,g)
East Birmingham Bronze Foundry Co., Ala (a,b)
Eastern Malleable Iron Co., Del (g)
Eclipse-Pioneer Div., Bendix Aviation Corp., NJ (a,e)
Ehrsam, J.B. & Sons Mfg. Co., Kan (c)
Elchinger, Charles F., La (a,b)
Electric Materials Co., Pa (b)
Electric Steel Foundry Co., Ore (f,g)
Electro-Alloys Div., American Brake Shoe Co., Ohio (g)
Electron Corp., Colo (c,f)
Elk Engineering Works, Inc., Pa (a,b,c)
Elkhart Foundry & Machine Co., Inc., Ind (c)
Elkhart Iron Works, Mich (c)
Elyria Foundry Div., Chromalloy Corp., Ohio (c)
Emmaus Foundry & Machine Co., Pa (a,b,c)
Empire Foundry Co., Inc., Calif (c,g)
Empire Steel Castings, Inc., Pa (g)
Engineered Castings Div., American Brake Shoe Co., NY (c)
Enterprise Wheel & Car Corp., Va (a, b,c)
Erie Bronze Co., Pa (a,b)
Erie Casting Co., Pa (c)
Erie Malleable Iron Co., Pa (c)
Eureka Electric Products Co., Pa (a,b)
Fahralloy Co., Ill (g)
Fairbanks, Morse & Co., Wis (c)
Fairfield Aluminum Castings Co., Iowa (a)
Falk Corp., Wis (g)
Federal Malleable Co., Wis (c)
Fischer Casting Co., Inc., NJ (a)
Fitchburg Foundry, Inc., Mass (c)
Flood City Brass & Electric Co., Pa (a,b)
Florence Pipe Foundry & Machine Co., NJ (c)
Florin Foundry & Mfg. Co., Pa (c)
Forest City Foundries Co., Ohio
Fort Pitt Steel Casting Div., Pittsburgh Steel Foundry Corp., Pa (f,g)
Fort Worth Steel & Machinery Co., Tex (c)
Foster Aluminum Alloy Products Corp., NY (a)
Frederick Iron & Steel, Inc., Md (c)
Fremont Casting Co., Mass (c)
Frontier Bronze Corp., NY (a,b,f)
Fulton Foundry & Machines Co., Inc., Ohio (c)
G & C Foundry Co., Ohio (c)
Gale Mfg. Co., Mich (c)
Gartland Foundry Co., Ind (c)
General Alloys Co., Mass (f)
General Electric Co., Foundry Dept., NY (a,b,c,f,g)
General Foundry & Mfg. Co., Mich (c)
General Malleable Corp., Wis (c)
General Metals Corp., Calif (c)
General Motors Corp., Central Foundry Div., Mich (c)
General Motors Corp., Fabricast Div., Ind (a)
General Steel Castings Corp., Ill (g)
Georgia Iron Works, Ga (c)
Gibson & Kirk Co., Md (a,b,f)
Gilbert Brass Foundry Co., Mo (a,b)
Gillett & Eaton, Inc., Minn (a,c)
Glover Machine Works, Ga (g)
Gluntz Brass & Aluminum Foundry Co., Ohio (a,b,j)
Goslin Birmingham Mfg. Co., Inc., Ala (c,g)
Gowanda Furnaces, Inc., NY (c)
Grafton Foundry Co., Wis (c)
Graham, James Co., Conn (b)
Gra-Iron Foundry Corp., Iowa (c)
Green Bay Foundry & Machine Works, Wis (a,b,c)
Greenlee Foundry Co., Ill (c)
Grimm Foundry Co., Inc., NJ (c)
Gunite Foundries Corp., Ill (c,g)
H & H Foundry Machine Co., Pa (c)
Hallstead Foundry, Inc., Pa (c)
Hamilton Foundry & Machine Co., Ohio (c)
Hampden Brass & Aluminum Co., Mass (a,b,j)
Hansell-Elcock, Ill (c)
Hardinge Mfg. Co., Pa (c)
Hartford Electrical Steel Corp., Conn (g)

Haynes Stellite Co., Div. of Union Carbide Corp., Ind (f)
Hays Mfg. Co., Pa (b)
Headford Bros. & Hitchins Foundry Co., Iowa (c)
Helmick Foundry-Machine Co., WVa (c)
Hewitt, John Foundry Co., NJ (a,b,c)
Hica, Inc., La (f,g)
Hills-McCanna Co., Ill (d)
Hobbs, Clinton E. Co., Mass (a,b,c)
Hodgson Foundry Co., Ill (a,b,c,d)
Hoffman Bronze & Aluminum Casting Co., Ohio (a,b)
Homestead Valve Mfg. Co., Pa (a,b,c,f)
Howard Foundry Co., Ill (a,b,c,e,f,g)
Humphrey Castings, Inc., Calif (a)
Hunt-Spiller Mfg. Corp., Mass (c,g)
I-F Mfg. Co., Ohio (c)
Illinois Iron & Bolt Co., Ill (a,f)
Independence Stove & Mfg. Co., Mo (c)
Indiana Brass Co., Inc., Ind (b)
Industrial-Ferguson Foundry Corp., NJ (a,b,f,j)
International Nickel Co., Inc., NY (f)
Iowa Malleable Iron Co., Iowa (c)
Ironton Malleable Div., Dayton Malleable Iron Co., Ohio (c)
Irwin-Sensenich Corp., Pa (c)
Jamestown Malleable Iron Corp., NY (c)
Jessop Steel Co., Pa (c,g)
Johnson Bronze Co., Pa (b)
Johnstone Foundries, Inc., Pa (c)
Kaiser Aluminum & Chemical Sales, Inc., Ill (a)
Kanawha Mfg. Co., W. Va (c)
Kansas City Hay Press Co., Mo (c)
Kay-Brunner Steel Products, Inc., Calif (g)
Keen Foundry Co., Inc., Ind (c)
Kelly Foundry Co., Pa (c)
Kingsport Foundry & Mfg. Corp., Tenn (a,b,c,f)
Klinzing, A.F. Co., Inc., Wis (c,g)
Koehring Co., Wis (c)
Kramer Bros. Foundry Co., Ohio (c)
Kutztown Foundry & Machine Corp., Pa (c)
L F M Mfg. Co., Inc., Sub. of Rockwell Mfg. Co., Kan (g)
Laconia Malleable Iron Co., NH (c)
Lake Erie Foundry Co., NY (c)
Lakeside Bronze, Inc., NY (a,b)
Lakeside Malleable Casting Co., Wis (c)
Langsenkamp-Wheeler Brass Works, Inc., Ind (a,b)
La Porte Foundry Co., Ind (c)
Larson, W.O. Foundry Co., Ohio (c)
Lattimer Foundry and Machine Co., Pa (a)
Lawrence Copper & Bronze Co., Pa (b)
Lawton, C.A. Co., Wis (a,c)
Lebanon Steel Foundry, Pa (g)
Le Baron, E.L. Foundry, Mass (c)
Lee Bros. Foundry Co., Inc., Ala (b)
Lehigh Foundries Co., Div. of Lehigh, Inc., Pa (c)
Leitelt Bros., Inc., Ill (a,b)
Letukas Foundry Inc., Ind (c)
Lewistown Foundry & Machine Co., Pa (a,c,d)
Liberty Foundry Co., Mo (c,g)
Light Metals, Inc., Ind (a,e)
Light Metals Dept., American Brake Shoe Co., NJ (a)
Lincoln Foundry Corp., Calif (c)
Lincoln Iron Works, Vt (a,c,g)
Link-Belt Co., Ill (c)
Littite Foundries, Inc., Mich (c)
Littlestown Hardware & Foundry Co., Inc., Pa (a,b,c)
Lloyd & Scott Brass Foundry, Inc., Del (a,b)
Lodge Mfg. Co., Tenn (c)
Lodi Iron Works, Inc., Calif (c)
Loeffler, J. M. Machine Co., Pa (b)
Long Beach Iron Works, Calif (c)
Long Foundry Co., Wash (c)
Lorain Brass Co., Ohio (b)
Los Angeles Steel Casting Co., Calif (g)
Ludlow Valve Mfg. Co., Inc., NY (c)
Lumen Bearing Co., NY (b,d,j)
Lynchburg Foundry Co., Castings Div., Va (c)
Macaulay, H.C. Foundry Co., Calif (c)
Mackintosh-Hemphill Div., E.W. Bliss Co., Pa (g)
Madison Foundry Co., Ohio (c)
Magline, Inc., Mich (a,e)
Mallory, P.R. & Co., Inc., Ind (b,f,h)
Manco Products Inc., Mich (b)
Mansfield Brass & Aluminum Corp., Ohio (a,b)
Marshall Car Wheel & Foundry Co., Inc., Tex (c)
Massillon Steel Casting Co., Ohio (g)
McLanahan & Stone Corp., Pa (c)
McNally Pittsburgh Mfg. Co., Kan (c)
Meadville Malleable Iron Co., Pa (c)
**Mechanite Metal Corp., NY** (c)—Ad p 461
Merrimac Brass, Mass (a,b,d,e,f)
Merriman Bros., Inc., Mass (b)
Metal Goods Corp., Mo (f)
Metropolitan Iron Foundry, NY (a,c)
Midwest Foundry Co., Div. of L.A. Darling Co., Mich (c,g)
Midwestern Foundries, Inc., Ind (c)
Milwaukee Aluminum & Brass Foundry Wis (a,b)
Milwaukee Malleable & Grey Iron Works, Wis (c)
Milwaukee Valve Co., Wis (a,b)
Minneapolis Electric Steel Castings Co., Minn (g)
Missouri Steel Castings Co., Mo (g)
Moccasin Bushing Co., Tenn (b)
Model Brass Co., Inc., Ill (a,b)
Modern Brass Foundry & Mfg. Co., Ohio (a,b)
Mohawk Foundries, Inc., Ohio (a)
Moline Malleable Iron Co., Ill (c)
Monroe Steel Castings Co., Mich (g)
Montague Machine Co., Mass (b,c,f)
Moore Dry Dock Co., Calif (b,g)
Morrisville Foundry Co., Inc., Vt (c)
Morse, Fred W. Co., RI (a,j)
Mount Vernon Furnace & Mfg. Co., Ill (c)
**Mueller Brass Co., Mich** (a,b)—Ad p 455
Muskegon Piston Ring Co., Mich (b,e)
National Aluminum Co., Inc., Wis (a,b)
National Aluminum & Brass Foundry, Inc., Mo (a,b)
National Bearing Div., American Brake Shoe Co., Pa (b)
National Brass Works, Inc., Calif (a,b,d,f)
National Grey Iron Foundry, Ill (c)
National Malleable & Steel Castings Co., Ohio (c,g)
National Steel & Shipbuilding Corp., Calif (c)
National Supply Co., Pa (g)
Neenah Foundry Co., Wis (c)
Newman Bros., Inc., Ohio (a,b)
Noble & Wood Machine Co., NY (c)
North Wales Foundry Co., Inc., Pa (c)
Northern Malleable Iron Co., Minn (c)
Nutmeg Crucible Steel Co., Conn (g)
Oak Hill Foundry & Machine Works, Ohio (c)
Oakes Bronze & Aluminum Co., Ohio (a,b)
Oakland Foundry & Machine Co., Mich (c)
Ohio Malleable Div., Dayton Malleable Iron Co., Ohio (c)
Ohio Precision Castings, Inc., Ohio (a,b,f)
Ohio Steel Foundry Co., Ohio (f,g)
Oil City Iron Works, Tex (c)
Oklahoma Steel Castings Div., American Steel & Pump Corp., Okla (g)
Olderman Mfg. Corp., Conn (b)
Olds Alloys Co., Calif (a,b,d,f)
Olympic Steel Works, Wash (g)
Omaha Steel Works, Neb (g)
Oregon Brass Works, Ore (a,b)
Oregon Metallurgical Corp., Ore (h)
Overmyer Mould Co., Inc., Ind (c,f,g)
Owen Pattern Foundry & Mfg Co., Inc., Va (a,b)
Pacific Brass Foundry of San Francisco, Calif (a,b,d,f,j)
Pacific Foundry Co., Ltd., Calif (c,g)
Palmyra Foundry Co., Inc., NJ (c)
Parker, Charles Co., Conn (a,b)
Parker-Street Castings Co., Ohio (c)
Paulson, Thomas & Son, Inc., NY (a,b,f,j)
Payne, F.S. Co., Mass (c)
Pelton Steel Casting Co., Wis (g)
Penn Steel Castings Co., Pa (g)
Peoria Malleable Casting Co., Ill (c)
Pequonnock Foundry, Inc., Conn (c)
Perfecto Cast, Calif (f,g)
Perkins, Henry Co., Mass (c)
Permold Co., Ohio (a)
Pettibone Mulliken Corp., Ill (g)
Philadelphia Bronze & Brass Corp., Pa (a,b,f)
Pittsburgh Foundry & Machine Co., Pa (c)
Pittsburgh Steel Foundry Corp., Pa (g)
Pohlman Foundry Co., Inc., NY (c)
Portland Iron Works, Ore (c)
Posey Iron Works, Inc., Pa (c,g)
Potts, C. & G. Co., Ind (c)
Pratt, William E. Foundry Div., Joslyn Mfg. & Supply Co., Ill (c)
Prescott Co., Mich (a,c)
Pusey & Jones Corp., Del (c)
Quaker Alloy Casting Co., Pa (c,f,g)
Quality Aluminum Casting Co., Wis (a)
Quality Electric Steel Castings, Inc., Tex (g)
Quincy Steel Casting Co., Mass (g)
Racine Steel Castings Co., Belle City Malleable Iron Div., Wis (c)
Refinery Castings Co., Tex (g)
Reliance Foundry Co., Ohio (c)
Rensselaer Valve Co., NY (c)
Richmond Foundry & Mfg. Co., Inc., Va (a,b,c,d,f,j)
Ridge Foundry, Calif (c)
Riverside Foundry & Galvanizing Co., Mich (a,b,c,f)
Rockwell Engineering Co., Ill (a,b,c,g)
Rolle Mfg. Co., Pa (a,e)
Rosedale Foundry & Machine Co., Pa (c)
Ross-Meehan Foundries, Tenn (c,g)
Saginaw Bearing Co., Mich (a,b)
St. Louis Malleable Casting Co., Mo (c)
St. Louis Steel Casting, Inc., Mo (g)
St. Marys Foundry Co., Ohio (c)
Sall Bros. Co., Ill (a,b)
San Francisco Iron Foundry, Calif (a,c)
Sandy Hill Iron & Brass Works, NY (a,b,c)
Saran Lined Pipe Co., Div. of Michigan Pipe Co., Mich (c,g)
Sargent & Greenleaf, Inc., NY (a,b)
Savannah Machine & Foundry Co., Foundry Div., Ga (a,b,c,d)
Schaefer-Goodnow Foundries, Inc., Pa (c)
Schilling Bronze Co., NY (a,b,d,f,j)
Schmelier Aluminum Foundry Co., Ohio (a)
Schneider, Bowman Co., Inc., Pa (c)
Scottdale Ozone Co., Pa (a,c)
Scovill Mfg. Co., Mill Products Div., Conn (b)
Scudder, E. J. Foundry & Machine Co., NJ (f,g)
Scullin Steel Co., Mo (g)
Selma Foundry & Machine Co., Ala (c)
Sequoia Metalcraft Co., Inc., Calif (e)
Shakopee Foundry Co., Minn (c)
Shartle Div., Black-Clawson Co., Ohio (a,b,c)
Sheffield Foundry Co., Ill (c)
Sherman & Reilly, Inc., Tenn (a,c,g)
Shriver, T. & Co., Inc., NJ (a,b,c,d)
Sibley Machine & Foundry Corp., Ind (c)
Sillcocks Miller Co., NJ (b,j)
Sinclair Co., Mass (a,b)
Sioux City Foundry & Boiler Co., Iowa (a,c)
Sivyer Steel Casting Co., Wis (g)
Smith, A.P. Mfg. Co., NJ (c)
Smith & Winchester Mfg. Co., Conn (a,b,c,g)
Solon Foundry, Inc., Ohio (a,b,e)
Somerset Foundry & Machine Co., Pa (a,c,d)
Sonith Foundries Div., Food Machinery & Chemical Corp., Ind (b,c)
Sorbo-Cast Corp., NJ (c)
Sorbo-Mat Process Engineers, Mo (c)
Southern Metal Products Co., La (a)
Sparta Foundry Div., Muskegon Piston Ring Co., Mich (c)
Spencer's, I.S. Sons, Inc., Conn (a,b,c)
Spring City Foundry Co., Pa (c)
Springer's Foundry Co., Inc., Ind (a,c)
Springfield Foundry Co., Mass (c)
Spuck Iron & Foundry Co., Mo (c)

## KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Stainless Foundry & Engineering, Inc., Wis (f)
Standard Casting Corp., Ill (a,b,d)
Standard Foundry Co., Mass (c)
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa (g)
Star Heel Plate Co., Inc., NJ (c,g)
State Foundry & Machine Co., Wis (c)
Stearns-Roger Mfg. Co., Colo (c)
Sterling Brass Foundry, Inc., Ind (c)
Sterling Foundry Co., Inc., Ill (a, b,c)
Sterrit-Thomas Foundry Co., Pa (c)
Stillman White Foundry Co., Inc., RI (a,b,d)
Strong Steel Foundry Co., NY (g)
Stulz-Sickles Co., NJ (g)
Superb Light Alloys, Inc., NY (a,e)
Superior Foundry, Inc., Ohio (c,g)
Swayne-Robinson & Co., Ind (a,c)
Swedish Crucible Steel Co., Mich (g)
Swett, A.L. Iron Works, NY (c)
Taylor & Co., Inc., NY (c)
Taylor & Boggis Foundry, Ohio (c)
Taylor-Wharton Co., Div. of Harsco Corp., NJ (g)
Terre Haute Bronze & Brass Foundry, Ind (b)
Terre Haute Malleable & Mfg. Corp., Ind (c)
Texas Foundries, Inc., Tex (c,g)
Thys Co., Calif (g)
Tickle, Arthur Engineering Works, Inc., NY (a)
Tower Grove Foundry, Mo (c)
Trenton Brass Co., NJ (b)
True Alloys, Inc., Mich (a,b,d,j)
Turner & Seymour Mfg. Co., Conn (c)
Union Iron Works, Wash (c,g)
**Unitcast Corp., Ohio**
(g)—Ad p 467
U.S. Magnet & Alloy Corp., NJ (c, f,g)
U.S. Pipe and Foundry Co., Ala (c)
Uniworld Research Corp. of America, Ohio (c,f)
Utica General Jobbing Foundry, Inc., NY (c)
Utica Radiator Corp., NY (c)
Valley Iron Works, Inc., Minn (c)
Valley Steel Casting Co., Mich (g)
Viking Pump Co., Iowa (c)
Vollrath Co., Wis (a,b,g)
Vulcan Foundry Co., Calif (c)
Vulcan Rail & Construction Co., NY (a,c,g)
Wagner Malleable Iron Co., Ill (c)
Wall Colmonoy Corp., Stainless Process Div., Mich (c,f)
Waltham Foundry Co., Mass (a,c)
Washington Iron Works, Wash (c)
Waterman Industries, Inc., Calif (a, b,c)
Waukesha Foundry Co., Wis (a,b,f,g)
Wayne Agricultural Works, Inc., NC (b,c)
Wayne Foundry & Stamping Co., Mich (d,j)
Weber-Knapp Co., NY (a)
Webster Mfg. Inc., Ohio (c)
Wellman Bronze & Aluminum Co., Ohio (a,e)
Werner Foundry & Machine Co., Pa (c)
West Haven Foundry Co., Conn (a,b,d, f,j)
West Point Foundry & Machine Co., Div. of Batson-Cook Co., Ga (a,c,d)
West Steel Casting Co., Ohio (f,g)
Western Automatic Machine Screw Co., Ohio (c)
Western Foundry & Machine Works, Inc., Kan (c)
Western Iron & Foundry Co., Inc., Kan (c)
Westlectric Castings, Inc., Calif (g)
Westmoreland Malleable Iron Co., NY (c)
Williams, A.C. Co., Ohio (e)
Williams, E.A. & Son, NJ (a,b)
Winters Foundry & Machine Co., Inc., Ohio (a,b,d,f,j)
Wisconsin Aluminum Foundry Co., Inc., Wis (a,b)
Wollaston Foundry Corp., Mass (c)
Woodruff & Edwards, Inc., Ill (c)
Worthington Corp., NJ (c)
Zenith Foundry Co., Wis (c)

## Castings, Shell Mold

Abco Aluminum & Brass Works, Tex (a,b,d,f,j)
Aelco Foundries, Inc., Wis (a,b,f,g)
Albion Malleable Iron Co., Mich (c)
Alloy Precision Castings Co., Ohio (a, b,c,e,f,g)
Alloy Steel Casting Co., Pa (f,g)
Almont Mfg. Co., Mich (c)
American Aluminum Casting Co., NJ (a)
American Cast Iron Pipe Co., Ala (c)
American Manganese Steel Div., American Brake Shoe Co., Ill (g)
American Steel Foundries, Ill (g)
Ampco Metal, Inc., Wis (b)
Arwood Corp., NY (a,b,e,g)
Atlas Foundry & Mfg. Co., Calif (a,b, c,g)
Aurora Metal Co., Ill (b)
Austenal Co., Div. of Howe Sound Co., NY (a,c,f,g)
Auto Specialties Mfg. Co., Mich (g)
Baxter Foundry & Machine Works, Inc., Ind (c)
Bendix Foundries Div., Bendix Aviation Corp., NJ (a,e)
Bethlehem Steel Co., Pa (g)
Blaw-Knox Co., Pa (f,g)
Buckeye Brass & Mfg. Co., Ohio (a,b)
Cadillac Malleable Iron Co., Mich (c)
Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich (c)
Castalloy Co., Inc., Mass (a,e)
Chicago Hardware Foundry Co., Ill (a, b,c)
Chicago Malleable Castings Co., Ill (c)
Cochrane Foundry, Inc., Pa (a,b,j)
Cooper Alloy Corp., NJ (g)
Crawford & Doherty Foundry Co., Ore (c)
Crobalt, Inc., Mich (g)
Crucible Steel Casting Co., Pa (g)
Curtiss-Wright Corp., Metals Processing Div., NY (f,g)
Dayton Malleable Iron Co., Ohio (c)
Dirilyte Co. of America, Inc., Ind. (b)
Dodge Steel Co., Pa (g)
**Duraloy Co., Pa**
(f)—Ad p 417
**Eaton Mfg. Co., Foundry Div., Mich**
(c)—Ad p 459
Eclipse-Pioneer Div., Bendix Aviation Corp., NJ (a,e)
Electric Steel Foundry Co., Ore (f,g)
Electro-Alloys Div., American Brake Shoe Co., Ohio (g)
Electron Corp., Colo (c)
Emmaus Foundry & Machine Co., Pa (a,b,c)
Empire Steel Castings, Inc., Pa (g)
Erie Casting Co., Pa (c)
Fischer Casting Co., Inc., NJ (a)
Forest City Foundries Co., Ohio (c)
Fort Pitt Steel Casting Div., Pittsburgh Steel Foundry Corp., Pa (f,g)
Foster Aluminum Alloy Products Corp., NY (a)
Gale Mfg. Co., Mich (c)
General Electric Co., Foundry Dept., NY (f,g)
General Motors Corp., Central Foundry Div., Mich (c)
General Motors Corp., Fabricast Div., Ind (a)
Gilbert Brass Foundry Co., Mo (a,b)
Grimm Foundry Co., Inc., NJ (c)
Gunite Foundries Corp., Ill (c,g)
Haynes Stellite Co., Div. of Union Carbide Corp., Ind (f)
Hica, Inc., La (g)
Hobbs, Clinton E. Co., Mass (a,b,c)
Howard Foundry Co., Ill (a,b,c,e,f,g)
Investment Casting Co., NJ (a,b,c,f,g)
Ironton Malleable Div., Dayton Malleable Iron Co., Ohio (c)
Jamestown Malleable Iron Corp., NY (c)
Laconia Malleable Iron Corp., NH (c)
Lakeside Malleable Casting Co., Wis (c)
Lebanon Steel Foundry, Pa (g)
Lehigh, Inc., Pa (c)
Liberty Foundry Co., Mo (c,g)
Light Metals Dept., American Brake Shoe Co., NJ (a)
Link-Belt Co., Ill (c)
Loeffler, J.M. Co., Machine & Brass Works, Pa (b)
Lumen Bearing Co., NY (b)
Lynchburg Foundry Co., Castings Div., Va (c)
Mallory, P.R. & Co., Inc., Ind (b)
Marshall Car Wheel & Foundry Co., Inc., Tex (c)
Massillon Steel Casting Co., Ohio (g)
McCarter Iron Works, Inc., Pa (c,g)
**Meehanite Metal Corp., NY**
(c)—Ad p 461
Mercast Mfg. Corp., Calif (a,b,c,e,f,g)
Michigan Steel Casting Co., Div. of Consolidated Foundries & Mfg. Corp., Mich (g)
Midwest Foundry Co., Div. of L.A. Darling Co., Mich (c,g)
Misco Precision Casting Co., Mich (c,f, g)
Missouri Diecasting Co., Mo (a,b,c,g)
National Bearing Div., American Brake Shoe Co., Pa (b)
National Lead Construction Co., Inc., NJ (d)
National Malleable & Steel Castings Co., Ohio (c)
Northern Malleable Iron Co., Minn (c)
Ohio Steel Foundry Co., Ohio (f,g)
Oklahoma Steel Casting Div., American Steel & Pump Corp., Okla (g)
Olderman Mfg. Corp., Conn (j)
Olympic Steel Works, Wash (g)
Oregon Brass Works, Ore (a,b)
Oregon Metallurgical Corp., Ore (h)
Pacific Brass Foundry of San Francisco, Calif (a,b,f,j)
Parker, Charles Co., Conn (a,b)
Pelton Steel Casting Co., Wis (f,g)
Perfecto Cast, Calif (f,g)
Pettibone Mulliken Corp., Ill (g)
Pratt & Letchworth Div., Dayton Malleable Iron Co., Inc., NY (g)
Pusey & Jones Corp., Del (c)
Quaker Alloy Casting Co., Pa (c,f,g)
Ridge Foundry, Calif (c)
Rockwell Engineering Co., Ill (a,b,c,g)
Rolle Mfg. Corp., Pa (a,e)
Ross-Meehan Foundries, Tenn (c,g)
Sail Bros. Co., Ill (a,b)
Schilling Bronze Co., NY (a,b,d)
Sorbo-Mat Process Engineers, Mo (c)
Spencer's, I.S. Sons, Inc., Conn (c)
Star Heel Plate Co., Inc., NJ (a,b, c,g)
State Foundry & Machine Co., Wis (c)
Superb Light Alloys, Inc., NY (a,e)
Taylor & Co., Inc., NY (c)
Texas Foundries, Inc., Tex (c,g)
Trenton Brass Co., NJ (b)
True Alloys, Inc., Mich (a,b,d,j)
**Unitcast Corp., Ohio**
(g)—Ad p 467
U.S. Magnet & Alloy Corp., NJ (c,f,g)
Uniworld Research Corp. of America, Ohio (c,f)
Utica General Jobbing Foundry, Inc., NY (c)
Utility Steel Foundry, Calif (c,g)
Wall Colmonoy Corp., Stainless Process Div., Mich (c,f)
Waterman Industries, Inc., Calif (b,c)
**Waukesha Foundry Co., Wis**
(a,b,f,g)—Ad p 451
Wayne Agricultural Works, Inc., NC (b,c)
West Steel Casting Co., Ohio (f,g)
Western Automatic Machine Screw Co., Ohio (c)
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (a,b,c,f,g,h)
Winters Foundry & Machine Co., Inc., Ohio (a,b,d,f,j)
Woodruff & Edwards, Inc., Ill (c)
Zenith Foundry Co., Wis (c)

## Cellophane

(see Cellulose, Regenerated)

## Cellulose Acetate

aaRBee Plastic Co., Calif (y)
Ace Plastic Co., NY (bb,cc,dd,ee)
Adhesive Products Corp., NY (x)
Albany Novelty Mfg. Co., Mass (t)
American Hard Rubber Co., Div. of Amerace Corp., NJ (bb,dd,ee)
American Products Mfg. Co., La (t)
Anchor Plastics Co., Inc., NY (bb, dd,ee)
Auburn Plastic Engineering, Ill (bb, cc)
Auburn Plastics, Inc., NY (bb,dd,ee)
Bamberger, Claude P., Inc., NJ (p,y)
Blank, Arthur & Co., Inc., Mass (t, cc)
Cadillac Plastic & Chemical Co., Mich (t,bb,cc,dd,ee)
Carroll, J.B. Co., Ill (cc)
**Celanese Plastics Co., Div. of Celanese Corp. of America, NJ**
(p,s,t,y,cc)—Ad pp 271-274
Celluplastic Corp., NJ (bb,ee)
Chemical Development Corp., Mass (p)
**Chicago Molded Products Corp., Campco Div., Ill**
(t,cc)—Ad p 243
Coating Products, Inc., NJ (t,cc)
Colonial Kolonite Co., Ill (t,bb,cc, dd,ee)
Comco Plastics, Inc., NY (cc,dd)
Commercial Plastics & Supply Corp., NY (bb,cc,ee)
Cosmos Plastics Co., Ohio (u)
Craftint Mfg. Co., Ohio (cc)
Crane Plastics, Inc., Ohio (bb,dd,ee)
CrystalX Corp., Pa (t,bb,cc,dd,ee)
Curbell, Inc., NY (cc)
Davis, Joseph Plastics Co., NJ (t, y,bb,cc,dd,ee)
Denver Plastics, Inc., Colo (u)
Dobeckmun Co., Div. of Dow Chemical Co., Ohio (x)
du Pont de Nemours, E.I. & Co., Inc., Del (p,s,cc)
Dura Plastics of New York, Inc., NY (cc)
Dyna-Therm Chemical Corp., Calif (p)
Eastman Chemical Products, Inc., Sub. of Eastman Kodak Co., NY (p,y)
Eastman Kodak Co., NY (t,cc)
Eljay Corp., Md (cc)
Fry Plastics International, Calif (t,cc)
General Gasket, Inc., Conn (t,cc)
General Plastics Mfg. Co., Wash (bb,cc,dd,ee)
Gering Plastics, Div. of Studebaker-Packard Corp., NJ (y)
Glass Laboratories, NY (bb,dd,ee)
Gomar Mfg. Co., Inc., NJ (cc)
Hastings & Co., Inc., Pa (t)
Heyden Newport Chemical Corp. American Plastics Corp. Div., NY (bb,cc,dd,ee)
Industrial Plastics Corp., Ind (bb,dd
Insulation Mfrs. Corp., Ill (t,cc,dd
Jet Specialties Co., Inc., Calif (bb cc,dd,ee)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Knoedler Chemical Co., Pa (bb,cc
Luminous Resins, Inc., Ill (y)
Lus-Trus Corp., Mich (cc,ee)
Midwest Plastic Products Co., Ill (t,cc)
Monsanto Chemical Co., Plastics Div., Mass (t)
Muehlstein, H. & Co., Inc., NY (y)
National Gasket & Washer Mfg. Co., Inc., NY (cc,dd)
New England Tape Co., Div. of United-Carr Fastener Corp., Mass (bb,cc)
Nixon Nitration Works, NJ (bb,cc,ee)
Norrich Plastics Corp., NY (bb,cc,ee)
Omni Products Corp., NY (y,bb,cc)
Ormond Mfg. Co., Inc., NJ (cc,dd)
Pacific Coast Foil Co., Calif (t)
Panelyte Div., St. Regis Paper Co., NJ (cc)

Suppliers of Materials

**Perfex Plastics, Inc., (bb,dd,ee)**
**Philrus Products Co., NJ (cc,dd)**
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
**Plast-Ad Mfg. Co., Ind (cc)**
Plastic Compounding Corp., Sub. of Plastiglide Mfg. Corp., Calif (y)
**Plastic Materials, Inc., NY (y)**
**Precision Paper Tube Co., Ill (ee)**
**Pyramid Plastics, Inc., Ill (dd,ee)**
**Reed Plastics Corp., Mass (y)**
**Rosco Laboratories, NY (cc)**
**Rowland Products, Inc., Conn (x,bb, cc,dd,ee)**
**Russell Mfg. Co., Conn (s)**
**Schwab Plastic Corp., Mich (u,bb,cc, dd,ee)**
**Scranton Plastic Laminating Corp., Pa (cc)**
**Simon Products Co., Ill (t,cc)**
**Snyder Mfg. Co., Inc., Ohio (t,cc)**
**Southern Plastics Co., SC (bb,cc,dd, ee)**
Stone Paper Tube Div., Stone Straw Corp., **Washington, DC (ee)**
**Sunlites Plastics, Inc., Wis (bb,dd,ee)**
**Superior Plastics, Inc., Ill (bb,cc,dd, ee)**
Western Felt Works, Ill (cc)
**Westlake Plastics Co., Pa (bb,cc,dd, ee)**
**World Plastics, NY (bb,cc,dd,ee)**

## Cellulose Acetate Butyrate

**aaRBee Plastic Co., Calif (y)**
**Ace Plastic Co., NY (bb,cc,dd,ee)**
**Adhesive Products Corp., NY (x)**
**Albany Novelty Mfg. Co., Mass (t,cc)**
American Hard Rubber Co., Div. of Amerace Corp., NJ (bb,dd,ee)
**American Molding Powder & Chemical Co., NY (y)**
Anchor Plastics Co., Inc., NY (bb,dd, ee)
**Anderson Assoc., Inc., Ohio (y)**
**Anesite Co., Ill (ee)**
**Auburn Plastic Engineering, Ill (t,bb, cc,ee)**
**Auburn Plastics, Inc., NY (bb,cc, dd,ee)**
**Bamberger, Claude P., Inc., NJ (p,y)**
Bischoff Chemical Corp., NY (u)
**Blank, Arthur & Co., Inc., Mass (t,cc)**
Busada Mfg. Corp., NY (ee)
**Cadillac Plastic & Chemical Co., Mich (bb,cc,dd,ee)**
**Carroll, J.B. Co., Ill (cc)**
**Celluplastic Corp., NJ (bb,ee)**
**Chicago Molded Products Corp., Camco Div., Ill (t,cc)**
**Coating Products, Inc., NJ (t,cc)**
**Colonial Kolonite Co., Ill (t,bb,cc,ee)**
**Columbus Coated Fabrics Corp., Ohio (u)**
**Comco Plastics, Inc., NY (cc,dd,ee)**
**Commercial Plastics & Supply Corp., NY (bb,cc,ee)**
Cosmos Plastics Co., Ohio (u)
Crane Plastics, Inc., Ohio (bb,dd,ee)
**CrystalX Corp., Pa (t,bb,cc,dd,ee)**
**Davis, Joseph Plastics Co., NJ (t,y, bb,cc,dd,ee)**
**Denver Plastics, Inc., Colo (u)**
**Dobeckmun Co., Div. of Dow Chemical Co., Ohio (x)**
**Durable Form Products, Inc., NY (cc, ee)**
**Dryden Rubber Div., Sheller Mfg. Corp., Ill (y)**
Eastman Chemical Products, Inc., Sub. of Eastman Kodak Co., NY (p,y)
Eastman Kodak Co., NY (t,cc)
**Fidelity Chemical Products Corp., NJ (u)**
Fry Plastics International, Calif (t,cc)
**General Gasket, Inc., Conn (t,cc)**
**General Plastics Corp., Ind (cc)**
**General Plastics Mfg. Co., Wash (bb, cc,dd,ee)**
Gering Plastics, Div. of Studebaker-Packard Corp., NJ (y)
Glass Laboratories, NY (bb,dd,ee)
**Gomar Mfg. Co., Inc., NJ (cc)**
Grigoleit Co., Ill (p,s)
Heyden Newport Chemical Corp., American Plastics Div., NY (bb,cc, dd,ee)
**Hydrawlik Co., NJ (bb,dd)**
**Industrial Plastics Corp., Ind (bb,dd)**
**Jet Specialties Co., Inc., Calif (bb, cc,dd,ee)**
**K S H Plastics, Inc., Mo (bb,cc,dd)**
Kaufman Glass Co., Del (bb,cc,dd,ee)
**Luminous Resins, Inc., Ill (y)**
Lus-Trus Corp., Mich (cc,ee)
**Midwest Plastic Products Co., Ill (t, cc)**
**Muehlstein, H & Co., Inc., NY (y)**
New England Tape Co., Div. of United-Carr Fastener Corp., Mass (bb,cc)
**Nixon Nitration Works, NJ (bb,cc,ee)**
**Omni Products Corp., NY (y,bb,cc)**
**Panelyte Div., St. Regis Paper Co.,** NJ (cc)
**Perfex Plastics, Inc., Ill (bb,dd,ee)**
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Plastic Compounding Corp., Sub. of Plastiglide Mfg. Corp., Calif (y)
Polymer Corp., Pa (y)
Precision Paper Tube Co., Ill (ee)
Pyramid Plastics, Inc., Ill (dd,ee)
**Rowland Products, Inc., Conn (x,bb,cc, dd,ee)**
**Schwab Plastic Corp., Mich (u,bb,cc, dd,ee)**
**Scranton Plastic Laminating Corp., Pa (cc)**
Shoe Form Co., Inc., De Witt Plastics Div., NY (cc,dd,ee)
**Snyder Mfg. Co., Inc., Ohio (t,cc)**
**Southern Plastics Co., SC (bb,cc,dd, ee)**
**Sunlites Plastics, Inc., Wis (bb,dd, ee)**
**Superior Plastics, Inc., Ill (bb,cc, dd,ee)**
Western Felt Works, Ill (cc)
**Western Plastics Corp., Neb (bb, dd,ee)**
**Westlake Plastics Co., Pa (bb,cc,dd, ee)**
World Plastics, NY (bb,cc,dd,ee)

## Cellulose Nitrate

Adhesive Products Corp., NY (x)
Chemical Development Corp., Mass (p)
Columbus Coated Fabrics Corp., Ohio (u)
**Crescent Plastics, Inc., Ind (ee)**
du Pont de Nemours, E.I. & Co., Inc., Del (p)
General Gasket, Inc., Conn (t)
Hercules Powder Co., Inc., Del (p)
Kaufman Glass Co., Del (cc)
Nixon Nitration Works, NJ (bb,cc,ee)
Omni Products Corp., NY (bb,cc)
Panelyte Div., St. Regis Paper Co., NJ (cc)
Rowland Products, Inc., Conn (x,cc)
**Wasco Products, Inc., Mass (cc)**
Western Felt Works, Ill (cc)

## Cellulose Propionate

**aaRBee Plastic Co., Calif (y)**
Adhesive Products Corp., NY (x)
American Hard Rubber Co., Div. of Amerace Corp., NJ (bb,ee)
**Anchor Plastics Co., Inc., NY (bb,dd, ee)**
**Anderson Assoc., Inc., Ohio (y)**
**Celanese Plastics Co., Div. of Celanese Corp. of America, NJ**
(p,y)—Ad pp 271-274
Eastman Chemical Products, Inc., Sub. of Eastman Kodak Co., NY (y)
Glass Laboratories Inc., NY (bb,dd,ee)
**Panelyte Div., St. Regis Paper Co.,** NJ (cc)
**Perfex Plastic, Inc., Ill (bb,dd)**
**Southern Plastics Co., SC (bb,cc,dd,ee)**
**Superior Plastics, Inc., Ill (ee)**
**World Plastics, NY (bb,cc,dd,ee)**

## Cellulose, Regenerated

(e.g., Cellophane)

**Adhesive Products Corp., NY (x)**
**American Viscose Corp., Pa** (s,t)—Ad p 313
**Blank, Arthur & Co., Inc., Mass (t)**
**Dobeckmun Co., Div. of Dow Chemical Co., Ohio (x)**
du Pont de Nemours, E.I. & Co., Inc., Del (s,t,cc)
Foss Mfg. Co., Id (t)
Kaufman Glass Co., Del (cc)
**Mason Envelope Co., Inc., NY (t)**
**Olin Mathieson Chemical Corp., Packaging Div., NY (t)**
**Pacific Coast Foil Co., Calif (t)**

## Cemented Carbides

(see Cermets)

## Centrifugal Castings

(see Castings)

## Ceramic Coatings

(see Inorganic Coatings)

## Ceramics, Alumina

Alite Div., U.S. Stoneware Co., Ohio (r)
American Lava Corp., Tenn (r,z,bb,ee)
Brunswick Corp., Va (r,u)
CFI Corp., NY (r,bb,ee)
Carborundum Co., NY (r,z,aa,bb,ee)
Carborundum Co., Refractories Div., NJ (r,s,z,aa,bb,cc,ee)
**Centralab Div., Globe Union, Inc., Wis**
(r,bb,cc)—Ad p 449
Continental Coatings Corp., Ohio (aa)
Coors Porcelain Co., Colo (r,bb,ee)
Corning Glass Works, NY (r)
Diamonite Products Mfg. Co., Ohio (r,z,bb,cc,ee)
Du-Co Ceramics Co., Pa (r,bb,ee)
Electric Autolite Co., Ceramic Div., Ohio (r,u,z,bb,ee)
Electro Refractories & Abrasives Corp., NY (r)
Engineered Ceramics Mfg. Co., Ill (r, z,bb,ee)
Frenchtown Porcelain Co., NJ (r,bb, cc,ee)
Gladding, McBean & Co., Technical Ceramic Div., Calif (r,u,z,bb,cc,ee)
Gulton Industries, Inc., NJ (r,aa,bb,ee)
Louthan Mfg. Div., Ferro Corp., Ohio (z)
Mansol Ceramics Co., NJ (r)
**McDanel Refractory Porcelain Co., Pa**
(r,bb,cc,ee)—Ad p 308
Metallizing Engineering Co., Inc., NY (aa)
Metallizing Co. of Los Angeles, Inc., Calif (r,bb)
Monsanto Chemical Co., Inorganic Chemicals Div., Mo (aa)
Morganite Inc., NY (r,z,aa,bb,ee)
National Beryllia Corp., NJ (r,z,bb, cc,ee)
Norton Co., Mass (r,z,aa,bb,ee)
Pyrosil, Inc., Ohio (r)
Saxonburg Ceramics, Inc., Pa (r,z,bb, cc,ee)
U.S. Stoneware Co., Ohio (r)
Western Gold & Platinum Co., Sub. of Wilbur B. Driver Co., Calif (r, z,aa,bb,cc,ee)
Zirconium Corp. of America, Ohio (r, z,bb,ee)

## Ceramics, Corundum

Carborundum Co., NY (r,z,bb,ee)
Electrical Refractories Co., Ohio (r)
Engineered Ceramics Mfg. Co., Ill (r, z,bb,ee)
Metallizing Engineering Co., Inc., NY (aa)
Morganite Inc., NY (r,z,bb,ee)

## Ceramics, Forsterite

American Lava Corp., Tenn (r,z,bb,ee)
CFI Corp., NY (r,bb,ee)
Corning Glass Works, NY (r)
Du-Co Ceramics Co., Pa (r,bb,ee)
General Ceramics Div., Indiana General Corp., NJ (r, bb, ee)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Gladding, McBean & Co., Technical Ceramic Div., Calif (r,z,bb,cc,ee)
Saxonburg Ceramics, Inc., Pa (r,z,bb, ee)

## Ceramics, Rare Earth

Continental Coatings Corp., Ohio (aa)
Electric Autolite Co., Ohio (r)
Engineered Ceramics Mfg. Co., Ill (r, z,bb,ee)
Metallizing Engineering Co., Inc., NY (aa)
National Beryllia Corp., NJ (r,z,bb, cc,ee)
Nuclear Metals, Inc., Mass (r)
Research Chemicals Div., Nuclear Corp. of America, Calif (aa,bb)
Zirconium Corp. of America, Ohio (r, z,aa,bb,ee)

## Ceramics, Steatite

American Lava Corp., Tenn (r,z,bb,ee)
CFI Corp., NY (r,bb,ee)
Carborundum Co., NY (r,z,bb,ee)
Carborundum Co., Refractories Div., NJ (r,z,bb,ee)
**Centralab Div., Globe Union, Inc., Wis** (r,bb,cc)—Ad p 449
Du-Co Ceramics Co., Pa (r,bb,ee)
Gladding, McBean & Co., Technical Ceramic Div., Calif (r,z,bb,cc,ee)
Louthan Mfg. Div., Ferro Corp., Ohio (r,ee)
Mansol Ceramics Co., NJ (r)
Saxonburg Ceramics, Inc., Pa (r,z,bb, ee)
Star Porcelain Co., NJ (r,z,bb,cc,ee)
Steward, D. M. Mfg. Co., Tenn (r,z, bb,ee)
Wisconsin Porcelain Co., Wis (r,bb, cc,ee)

## Ceramics, Whiteware

American Lava Corp., Tenn (r,z,bb,ee)
Carborundum Co., NY (r,z,bb,ee)
Du-Co Ceramics Co., Pa (r,bb,ee)
Frenchtown Porcelain Co., NJ (r,bb, cc,ee)
General Ceramics Div., Indiana General Corp., NJ (r, bb, ee)
Gladding, McBean & Co., Technical Ceramic Div., Calif (r,z,bb,cc,ee)
Knight, Maurice A. Co., Ohio (r,ee)
Saxonburg Ceramics, Inc., Pa (r,z, bb,ee)
Star Porcelain Co., NJ (r,z,bb,cc,ee)
Steward, D. M. Mfg. Co., Tenn (r, z,bb,ee)
Wisconsin Porcelain Co., Wis (r,bb, cc,ee)

## Ceramics, Other

Akron Porcelain Co., Ohio (r)
American Lava Corp., Tenn (r,z,bb,ee)
**Amersil Quartz Div., Engelhard Industries, Inc., NJ** (r,s,z,aa,bb,cc,ee)—Ad p 159
Arnold Engineering Co., Ill (r)
Beryl Ores Co., Colo (aa,cc)
Brunswick Corp., Va (r,u)
Brush Beryllium Co., Ohio (r,z,aa,bb, ee)
Carborundum Co., NY (r,s,u,z,aa,bb, ee)
Carborundum Co., Refractories Div., NJ (r,z,aa,bb,cc,ee)
**Centralab Div., Globe Union, Inc., Wis** (r,bb,cc)—Ad p 449
Continental Coatings Corp., Ohio (aa)
Coors Porcelain Co., Colo (r,bb,ee)
Corning Glass Works, NY (r)
Electric Autolite Co., Ohio (r)
Electrical Refractories Co., Ohio (r, ee)
Electro Refractories & Abrasives Corp., NY (r)
Emerson & Cuming, Inc., Mass (u, aa,cc)
Engineered Ceramics Mfg. Co., Ill (r, z,bb,ee)
Ferroxcube Corp. of America, NY (r, bb)
Frenchtown Porcelain Co., NJ (r,bb, cc,ee)
Gladding, McBean & Co., Technical Ceramic Div., Calif (r,z,bb,cc,ee)
Gulton Industries, Inc., NJ (aa)
Knight, Maurice A. Co., Ohio (r,ee)
Laboratory Equipment Corp., Mich (r, z,bb,cc,ee)
Louthan Mfg. Div., Ferro Corp., Ohio (r,z,bb,ee)
Malvern Brick & Tile Co., Ark (r)
Mansol Ceramics Co., NJ (r)
**McDanel Refractory Porcelain Co., Pa** (r,bb,cc,ee)—Ad p 308
Metal & Thermit Corp., NJ (aa)
Metallizing Engineering Co., Inc., NY (aa)
Metallizing Co. of Los Angeles, Inc., Calif (r,bb)
Monsanto Chemical Co., Inorganic Chemicals Div., Mo (aa)
Mycalex Corp. of America, NJ (r,z,aa, bb,cc,ee)
National Beryllia Corp., NJ (r,z,bb, cc,ee)
Nuclear Metals, Inc., Mass (r)
Pyrosil, Inc., Ohio (r,z,aa,bb,cc,ee)
Saxonburg Ceramics, Inc., Pa (r,z,bb, ee)
Star Porcelain Co., NJ (r,z,bb,cc,ee)
Steward, D. M. Mfg. Co., Tenn (r,z, bb,ee)
Taunton Div., Haveg Industries, Inc., Mass (r)
U.S. Stoneware Co., Ohio (r)
Wisconsin Porcelain Co., Wis (r,bb, cc,ee)
Zirconium Corp. of America, Ohio (r, z,aa,bb,ee)

## Cermets

Aerojet-General Corp., Structural Materials Div., Calif (r)
Allegheny Ludlum Steel Corp., Pa (r)
**American Brakeblok Div., American Brake Shoe Co., Mich (r)**
American Lava Corp., Tenn (r,z,bb,ee)
**American Sinteel Corp., NY (r)**
Brush Beryllium Co., Ohio (r,aa)
**Carborundum Co., NY (r)**
**Climax Molybdenum Div., American Metal Climax, Inc., NY (r)**
Continental Coatings Corp., Ohio (aa)
**Emerson & Cuming, Inc., Mass (r,u)**
**Firth Sterling, Inc., Pa (r)**
**General Electric Co., Metallurgical Products Dept., Mich (r)**
**Hardy, Charles, Inc., NY (aa)**
**Hayden Wire Works, Inc., Mass (r, u,aa)**
**Haynes Stellite Co., Div. of Union Carbide Corp., Ind (r)**
**Hommel, O. Co., Pa (aa)**
**Industrial Tectonics, Inc., Mich (r)**
**Kanthal Corp., Conn (bb)**
**Kennametal, Inc., Pa** (r,aa,bb,ee)—Ad p 306
**Metal Carbides Corp., Ohio (r)**
**Metal Hydrides, Inc., Mass (aa)**
Metallizing Engineering Co., Inc., NY (aa)
**Metallizing Co. of Los Angeles, Inc., Calif (bb)**
**Nuclear Metals, Inc., Mass (r,bb,cc, ee)**
**St. Eloi Corp., Ohio (r,z,aa)**
Sintercast Div., Chromalloy Corp., NY (r)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (r,aa)
**U.S. Stoneware Co., Ohio (r)**

## Chemical Conversion Coatings

(see Conversion Coatings)

## Chlorinated Polyether

Hercules Powder Co., Inc., Del (y)
National Vulcanized Fibre Co., Del (bb,cc,ee)
Toyad Corp., Pa (u)

## Chloroprene Rubber

(Neoprene)

**Adhesive Products Corp., NY (x)**
**American Rubber Products Corp., Ind (u,bb,cc,dd,ee)**
**Atlas Mineral Products Co., Pa (c)**
**Auburn Rubber Co., Inc., Ind (cc)**
**Automotive Rubber Co., Inc., Mich (cc, dd)**
**Belko Corp., Md (y)**
Bond International, Inc., Mich (y,ee)
**Brown Rubber Co., Inc., Ind (u)**
**Capac Mfg. Corp., Mich (y,cc)**
**Castle Rubber Co., Pa (y,bb,cc,dd,ee)**
**Chemical Coatings & Engineering Co., Inc., Pa (x,y)**
**Chicago Rubber Co., Inc., Ill (u,y)**
**Colonial Rubber Co., Div. of U.S. Stoneware Co., Ohio** (y,cc,dd)—Ad p 441
**Continental Rubber Works, Pa (bb,cc, dd,ee)**
**Coyne & Paddock, Inc., NY (cc)**
**Dayton Rubber Co., Ohio (y,bb,cc, dd,ee)**
**Dryden Rubber Div., Sheller Mfg. Corp., Ill (y,ee)**
**du Pont de Nemours, E.I. & Co., Inc., Del** (p)—Ad p 231
**Dutch Brand Div., Johns-Manville Corp., Ill (u,y,cc,dd)**
Dyna-Therm Chemical Corp., Calif (p)
**Electro Chemical Engineering & Mfg. Co., Pa (t,cc)**
**Faultless Rubber Co., Ohio (u,y,bb, ee)**
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (s,u,y,cc,ee)
**Flexfirm Products, Calif (s)**
**Flexible Tubing Corp., Conn (ee)**
**Foamade Industries, Mich (u)**
**Garlock Packing Co., NY (y,bb,cc,dd, ee)**
**Geauga Industries Co., Ohio (y,bb,dd)**
**Goodrich, B.F. Co., Conn (u)**
Goshen Rubber Co., Inc., Ind (y)
**Hewitt-Robins, Inc., Conn (cc,ee)**
**Home Rubber Co., NJ (y,bb,cc,dd,ee)**
**Knight, Maurice A., Ohio (cc)**
**Maloney, F.H. Co., Tex (y)**
**Martin Rubber Co., Inc., NJ (y,dd,ee)**
**Mid-States Rubber Products, Inc., Ind (y)**
**National Gasket & Washer Mfg. Co., Inc., NY (bb,cc,dd,ee)**
**Naugatuck Chemical Div., U.S. Rubber Co., Conn (y)**
**Paeco Rubber Co., Inc., Ohio (y,dd, ee)**
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
**Parker, Stearns & Co., Inc., NY (y, bb,cc,dd,ee)**
**Pawling Rubber Corp., NY (bb,dd,ee)**
**Polymer Chemical Co., Ohio (x)**
Prince Rubber & Plastics Co., Inc., NY (bb,cc,ee)
Raybestos-Manhattan, Inc., Plastics Products Div., Pa (x)
**Republic Rubber Div., Lee Rubber & Tire Corp., Ohio (p,y,cc,dd,ee)**
Roberts Toledo Rubber Co., Ohio (ee)
**Rogers Corp., Conn (u,y,cc,dd)**
Roth Rubber Co., Ill (y,cc)
**Rubatex Div., Great American Industries, Inc., Va (u)**
Russell Mfg. Co., Conn (r,ee)
**Sheller Mfg. Corp., Mich (u)**
**Snyder, M.L. & Son, Inc., Pa (cc,ee)**
**Standard Products Co., Mich (y)**
**Stockwell Rubber Co., Inc., Pa (u,y, bb,cc,dd)**
**Technical Specialties Co., NY (dd)**
**Toyad Corp., Pa** (u)—Ad p 260
Trostel, Albert Packing Ltd., Wis (y)
**U.S. Rubber Co., Kem-Bio Dept., Conn** (u)—Ad p 250
U.S. Stoneware Co., Ohio (y)
**Vulcan Rubber Products Div., Reeves Bros., Inc., NY (p,y,cc)**
**Vulcanized Rubber & Plastics Co., Pa (y)**
Western Felt Works, Ill (y,cc,dd,ee)
Williams-Bowman Rubber Co., Ill (y, bb,cc,dd,ee)

## Chlorosulfonated Polyethylene Rubber

**Adhesive Products Corp., NY (x)**
**Atlas Mineral Products Co., Pa (cc)**
**Automotive Rubber Co., Inc., Mich (cc,dd)**
**Belko Corp., Md (y)**
Bond International, Inc., Mich (y,ee)
**Castle Rubber Co., Pa (y,bb,cc,dd,ee)**
**Chemical Coatings & Engineering Co., Inc., Pa (x,y)**
Chicago-Allis Mfg. Corp., Ill (p)
**Continental Rubber Works, Pa (bb,cc, dd,ee)**
**Dayton Rubber Co., Ohio (y,bb,cc,dd, ee)**
**Dryden Rubber Div., Sheller Mfg. Corp., Ill (y,ee)**
du Pont de Nemours, E. I. & Co., Inc., Del (p)
**Electro Chemical Engineering & Mfg. Co., Pa (t,cc)**
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (y,cc,ee)
**Flexfirm Products, Calif (s)**
**Hewitt-Robins, Inc., Conn (cc,ee)**
**Home Rubber Co., NJ (y,bb,cc,dd,ee)**
**Maloney, F.H. Co., Tex (y)**
**Paeco Rubber Co., Inc., Ohio (y,dd,ee)**
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Prince Rubber & Plastics Co., Inc., NY (cc,ee)
**Republic Rubber Div., Lee Rubber & Tire Corp., Ohio (p)**
Roberts Toledo Rubber Co., Ohio (ee)
**Rogers Corp., Conn (cc,dd)**
Stockwell Rubber Co., Inc., Pa (cc)
Swan Rubber Co., Ohio (ee)
**Toyad Corp., Pa** (t,u)—Ad p 260
Trostel, Albert Packing, Ltd., Wis (y)
**Vulcan Rubber Products Div., Reeves Bros., Inc, NY (p,y,cc)**
Western Felt Works, Ill (y,cc,dd,ee)
Williams-Bowman Rubber Co., Ill (y,bb,cc,dd,ee)

## Chlorotrifluoroethylene

(see Fluorocarbon)

## Chromate Coatings

(see Conversion Coatings)

## Chromium

**Alloy Metal Powder, Inc., Iowa (aa)**
**Alloy Metal Products, Inc., Iowa (o,w)**
**American Nickel Alloy Mfg. Corp., NY (w,aa)**
Arcos Corp., Pa (ff)
Belmont Smelting & Refining Works, Inc., NY (w,aa)
**Chicago Development Corp., Md (aa)**
**Foote Mineral Co., Pa (aa)**
**Hardy, Charles, Inc., NY (aa)**
**Hayden Wire Works, Inc., Mass (aa)**
**Hull, R.O. & Co., Inc., Ohio (n)**
**K. & L. Plating Co., Pa (z)**

Kawecki Chemical Co., NY (aa)
Lakeland Industries, Minn (z)
Metal Hydrides, Inc., Mass (aa)
Metal & Thermit Corp., NJ (w)
Metals Disintegrating Co., Inc., NJ (aa)
Michigan Seamless Tube Co., Mich (ee)
Modern Plating Corp., Ill (n)
Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)
Nuclear Metals, Inc., Mass (w,bb,dd, ee)
Republic Steel Corp., Steel & Tubes Div., Ohio (ee)
**Sel-Rex Corp., NJ** (n)—Ad p 356
Shieldalloy Corp., NJ (aa)
Stevens, Frederic B., Inc., Mich (n)
**Union Carbide Metals Co., Div. of Union Carbide Corp., NY** (w,aa)—Ad p 181
Vanadium Corp. of America, NY (w)
**Waimet Alloys Co., Mich** (w)—Ad p 82

## Chromized Coatings

(see Diffusion Coatings)

## Clad Metals

(key letters refer to base metals; see also Laminates, Metal-Metal)

Alabama Wire Co., Inc., Ala (a)
Al-Fin Div., Arthur Tickle Engineering Works, Inc., NY (a,e)
Allegheny Ludlum Steel Corp., Pa (g)
Aluminum Co. of America, Pa (a)
American Silver Co., NY (b,c,f,g)
Arrow Metal Products Corp., NJ (a)
Bart Mfg. Corp., NJ (a,b,c,e,f,g,h)
Bartlett-Thompson Co., Inc., Mass (a, b,f)
Bishop, J. & Co. Platinum Works, Pa (f,g)
Borg-Warner Corp., Ill (g)
Bridgeport Brass Co., Conn (b,f,g)
Chicago Bridge & Iron Co., Ill (g)
Chicago Development Corp., Md (h)
Clad-Rex Corp., Ill (a,g)
Composite Industrial Metals, Inc., RI (a,b,c,d,e,f,g,h,j)
Copper & Brass Sales, Inc., Mich (a)
Darby Corp., Kan (a,f,g)
Delco Moraine Div., General Motors Corp., Ohio (a,d)
Driver-Harris Co., NJ (f)
Electric Materials Co., Pa (c)
Electric Steel Foundry Co., Ore (f,g)
Electronic Parts Mfg. Co., Inc., NJ (b,f)
Enamel Products Co., Ohio (a,g)
Fromson Orban Co., Inc., NY (b,f,g)
General Alloys Co., Mass (f,g)
General Finding & Supply Co., Industrial Div., Mass (b)
Horton-Angell Co., Mass (b,f)
Improved Seamless Wire Co., RI (b,f)
Jessop Steel Co., Pa (g)
Johnson Bronze, Pa (a,b,d,g)
Kaiser Aluminum & Chemical Sales, Inc., Ill (a)
Kassel Export Co., Inc., NJ (b,c,g)
Kewaunee Engineering Corp., Wis (c)
Knapp Mills Inc., NY (a,b,d,g)
Leach & Garner Co., Industrial Div., Mass (b,f)
Lukens Steel Co., Pa (a,b,e,f,g,h)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (b,c,f,g)
Manufacturers & Fabricators, Inc., Ohio (f,g)
Metal Goods Corp., Mo (f)
National Galvanizing Co., Pa (g)
National Lead Co., NY (d)
National Lead Construction Co., Inc., NJ (d)
Nuclear Metals, Inc., Mass (a,b,c,e, f,g,h)
Olin Mathieson Chemical Corp., Metals Div., NY (a)
Parish Pressed Steel Div., Dana Corp., Pa (a,g,j)
Presswork, Inc., Mich (b,d)
Republic Steel Corp., Ohio (g)
Revere Copper & Brass, Inc., NY (b)
Reynolds Metals Co., Va (a)
Riverside-Alloy Metal Div., H.K. Porter Co., Inc., NJ (b,f)
Rockwell Engineering Co., Ill (a,b, c,g)
Saginaw Bearing Co., Mich (b,g)
Sandy Hill Iron & Brass Works, NY (g)
Seattle Boiler Works, Inc., Wash (g)
Sharpsville Steel Fabricators, Inc., Pa (g)
Sheldon, M.L. & Co., Inc., NY (f)
Somers Brass Co., Inc., Conn (f)
Standard Metals Corp., Mass (a,b,c, f,g)
Sun Steel Co., Ill (a,e,g)
Superior Steel Div., Copperweld Steel Co., Pa (g)
Sylvania Electric Products, Inc., Parts Div., Pa (b,g)
**Texas Instruments, Inc., Metals & Controls Div., Mass** (a,b,c,f,g,h)—Ad p 465
Werner, R.D. Co., Pa (a,g)
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (f,g,h)
Whitehead Metal Products Co., Inc., NY (f)
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY (f,g)
Worcester Wire Works Div., National-Standard Co., Mass (g)

## Claddings

(see Organic Coatings; Clad Metals)

## Coated Metals

(see Precoated Metals)

## Coatings

(see specific type)

## Cobalt and Its Alloys

African Metals Corp., NY (aa)
Alloy Metal Products, Inc., Iowa (o, w)
American Nickel Alloy Mfg. Corp., NY (w,aa)
Austenal Co., Div. of Howe Sound Co., NY (w)
Belmont Smelting & Refining Works Inc., NY (n,w,aa)
Cannon-Muskegon Corp., Mich (w)
Crucible Steel Co. of America, Titanium & Vacuum Metals Product Div., Pa (o,q,w,z,cc,dd)
**Driver, Wilbur B. Co., NJ** (v,bb,dd,ff)—Ad p 185
Driver-Harris Co., NJ (bb,dd)
Dudek & Bock Spring Mfg. Co., Ill (ff)
Elgin National Watch Co., Abrasives Div., Ill (o,bb,dd,ff)
Foote Mineral Co., Pa (aa)
General Electric Co., Metallurgical Products Dept., Mich (q,w,aa,bb,cc, dd)
Hamilton Watch Co., Precision Metals Div., Pa (v,w,bb,cc,dd)
Hardy, Charles, Inc., NY (aa)
Haynes Stellite Co., Div. of Union Carbide Corp., Ind (o,q,v,w,z,bb,cc, dd,ee,ff)
**Hoskins Mfg. Co., Mich** (bb,dd)—Ad p 177
K. & L. Plating Co., Pa (z)
Kelsey-Hayes Co., Metals Div., NY (o,q,v,w,z,bb,cc,dd,ff)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (o)
McGean Chemical Co., Ohio (aa)
Metal Hydrides, Inc., Mass (aa)
Michigan Seamless Tube Co., Mich (ee)
New Jersey Metals Co., NJ (w)
Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)
Nuclear Metals, Inc. Mass (w)
Sierra Metals Corp., Sub. of American-Marietta Co., Ill (w)
Stauffer-Temescal Co., Calif (o,q,w,z, bb,cc,dd,ee,ff)
Texas Instruments, Inc., Metals & Controls Div., Mass (v,dd)
Trent Tube Co., Sub. of Crucible Steel Co. of America, Pa (ee)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
Vanadium-Alloys Steel Co., Pa (aa)
**Waimet Alloys Co., Mich** (w)—Ad p 82
Wall Colmonoy Corp., Stainless Process Div., Mich (w,bb)
Wallingford Steel Co., Conn (dd,ee)
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,v,w,z,bb,cc,dd, ee)

## Cold Extrusions

(see Impact Extrusions)

## Cold Headed Parts

Abbott Ball Co., Conn (b,g)
Acme Machine Products Div., Serrick Corp., Ind (g)
Albany Products Co., Inc., Conn (b,f)
Allied Products Corp., Mich (g)
Allmetal Screw Products Co., Inc., NY (f,g,h)
Aluminum Co. of America, Pa (a)
American Car & Foundry Div., ACF Industries, Inc., NY (g)
Ampco Metal, Inc., Wis (b)
Anti-Corrosive Metal Products Co., Inc., NY (g)
Armco Steel Corp., Sheffield Div., Mo (g)
Art Wire & Stamping Co., NJ (a,b,c, d,f,g)
Bead Chain Mfg. Co., Conn (a,g)
Bethlehem Steel Co., Pa (g)
Camcar Screw & Mfg. Co., Ill (a,g,h)
Central Screw Co., Ill (a,b,c,f,g)
Champion Rivet Co., Ohio (c,g)
Chandler Products Corp., Ohio (g)
Chicago Rivet & Machine Co., Ill (a, c,g)
Chicago Screw Co., Div. of Standard Screw Co., Ill (a,b,c,f,g)
Clark Bros. Bolt Co., Conn (a,b,c,g)
Clendenin Bros., Inc., Md (a,b,c)
Cleveland Cap Screw Co., Ohio (a, b,f,g,h)
Columbus Bolt & Forging Co., Ohio (a,b,g)
Deringer Metallurgical Corp., Ill (a, b,c,d,f,g)
Division Lead Co., Ill (d)
Eaton Mfg. Co., Reliance Div., Ohio (a,g)
Elco Tool & Screw Corp., Ill (a,b,c,g)
Electric Materials Co., Pa (b)
General Chain & Mfg. Corp., Ohio (g)
General Findings & Supply Co., Industrial Div. Mass (b,f)
Gibson Electric Co., Pa (f)
Greene, G.G. Corp., Pa (g)
Grip Nut Co., Ind (a,b,g)
Harper, H.M. Co., Ill (a,b,f,g,h)
Hartford Machine Screw Co., Div. of Standard Screw Co., Conn (a,b,c,f,g)
Hassall, John, Inc., NY (a,b,c,d,f,g)
Hercules Fastener Co., Ill (a,b,c,g,j)
Huck Mfg. Co., Mich (a,g)
Jaques Co., Mass (a,b,e,f,g,h)
Johnston & Funk Titanium Corp., Ohio (h)
Koehler Mfg. Co., Mass (c)
Lamson & Sessions Co., Ohio (a,b,c,f, g,h)
McKinney Mfg. Co., Pa (a,b,c,d,f,g)
Metal Goods Corp., Mo (f)
Mid-West Screw Products Co., Mo (a, b,c,g)
Milford Rivet & Machine Co., Conn (a,b,c,g)
Midland Screw Corp., Ill (a,b,c,d,e, f,g,j)
Murray Tube Works, Inc., NJ (a,b,j)
National Lock Co., Ill (a,b,c,d,g)
National Lock Co., Fastener Div., Ill (a,b,c,d,g)
National Screw & Mfg. Co., Ohio (a,b, f,g)
Parish Pressed Steel Div., Dana Corp., Pa (g)
Pheoll Mfg. Co., Inc., Ill (a,b,c,g)
Plume & Atwood Mfg. Co., Conn (a,b, g)
Pusey & Jones Corp., Del (c)
Reed & Prince Mfg. Co., Mass (a, b,c,g)
Republic Steel Corp., Ohio (g)
Rockwell Engineering Co., Ill (a,b,c, g)
Rome Mfg. Div., Revere Copper & Brass, Inc., NY (a,b)
**Russell, Burdsall & Ward Bolt & Nut Co., NY** (a,b,g)—Ad p 501
Scovill Mfg. Co., Mill Products Div., Conn (a,b)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Shakeproof Div., Illinois Tool Works, Ill (a,b,g)
Standard Pressed Steel Co., Pa (a,b,f,g,h)
Thompson-Bremer & Co., Ill (a,b,c,f,g,h)
Townsend Co., Engineered Fasteners Div., Pa (a,b,g)
Tubular Rivet & Stud Co., Mass (a,b,c,f,g)
Union Screw & Mfg. Co., Pa (a,g)
United Screw & Bolt Corp., Ill (a,b,g)
United-Carr Fastener Corp., Mass (b,g)
Weatherhead Co., Ind (g)
Wesbar Stamping Corp., Wis (a,c,g)
Western Automatic Machine Screw Co., Div. of Standard Screw Co., Ohio (a,b,c,f,g)
Zeller Corp., Ohio (g)

## Columbium and Its Alloys

American Silver Co., NY (v,dd,ee,ff)
Bishop, J. & Co. Platinum Works, Pa (ee)
Bridgeport Brass Co., Conn (ee)
Damascus Tube Co., Pa (ee)
du Pont de Nemours, E. I. & Co., Inc., Del (w)
**Fansteel Metallurgical Corp., Ill** (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)—Ad p 174
General Electric Co., Metallurgical Products Dept., Mich (q,w,aa,bb,cc,dd)
Hamilton Watch Co., Precision Metals Div., Pa (v,dd)
Hardy, Charles, Inc., NY (aa)
Hoskins Mfg. Co., Mich (ff)
Johnston & Funk Titanium Corp., Ohio (bb,ff)
Kawecki Chemical Co., NY (o,q,v,w,z,aa,bb,cc,dd,ff)
**Kennametal, Inc., Pa** (o,v,aa,dd)—Ad p 306
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (o,ee)
Mallory-Schwarzkopf Metals, Inc., NY (o,v,w,z,bb,cc,dd,ee,ff)
Molybdenum Corp. of America, Pa (o,w,z,aa,bb,cc,dd)
Nuclear Metals, Inc., Mass (w,bb,dd,ee)
Oregon Metallurgical Corp., Ore (w)
Rodney Metals, Inc., Mass (v)
Shieldalloy Corp., NJ (o,aa)
Stauffer-Temescal Co., Calif (o,q,v,w,z,bb,cc,dd,ee,ff)
**Superior Tube Co., Ill** (ee)—Ad pp 414-415
Techalloy Co., Inc., Pa (dd,ff)
Texas Instruments, Inc., Metals & Controls Div., Mass (v,dd)
Tube Distributors Co., Inc., NY (ee)
Tube Reducing Corp., NJ (ee)
**Union Carbide Metals Co., Div. of Union Carbide Corp., NY** (w,aa)—Ad p 181
United Screw & Bolt Corp., Ill (bb,cc,dd,ff)
Universal-Cyclops Steel Corp., Pa (o,q,z,cc)
Vanadium Corp. of America, NY (w)
**Wah Chang Corp., NY** (n,v,w,aa,bb,dd,ff)—Ad p 164
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,v,w,z,bb,cc,dd,ee)

## Composition Board

(see Wood)

## Compression Moldings

(see Moldings)

## Conversion Coatings, Anodic

(anodizers)

Abalon Precision Mfg. Corp., NY
Abco Aluminum & Brass Works, Tex
Accurate Anodizing Corp., Ill
Acme Plating Co., Ohio
Aerolite Extrusion Co., Ohio
Alchemize Corp., Ill
Aluminum Billets, Inc., Ohio
Aluminum Finishing Corp., Ind
Aluminum Specialty Co., Wis
American Emblem Co., Inc., NY
Auld, D.L. Co., Ohio
B & T Metals Co., Ohio
Badger Aluminum Extrusions, NY
Biddle Screw Products Co., Ind
Bonnell, William L. Co., Inc., Ga
Briggs-Shaffner Co., NC
Brinkerhoff Brass & Bronze Works, Inc., NY
Brown Lipe Chapin Div., General Motors Corp., NY
Brooks & Perkins, Inc., Mich
Chicago Thrift-Etching Corp., Ill
Coil Anodizers, Inc., Mich
Colonial Alloys Co., Pa
Commercial Screw Products Co., Ohio
Corson Industries, Pa
Croname, Inc., Ill
Designers Metal Corp., Ill
Diversey Corp., Metal Industries Div., Ill
Doehler-Jarvis Div., National Lead Co., Ohio
Dollin Corp., NJ
Edna Lite Optical Co., Inc., NY
Engineering Products & Specialties, Inc., RI
Fox Co., Ohio
General Extrusions, Inc., Ohio
Hull, R.O. & Co., Inc., Ohio
Industrial Chromium Corp., Mass
Jarl Extrusions, Inc., NY
Jervis Corp., Mich
Kees, F.D., Mfg. Co., Neb
Kinkead Industries, Inc., Ill
Leed, H.A. Corp., Conn
Magnesium Co. of America, Ind
Magnesium Elektron, Inc., NY
Merz Machine & Tool Works, Ind
Metal Finishers, Inc., Md
Mirro Aluminum Co., Wis
Modern Plating Corp., Ill
National Aluminum Co., Ohio
National Galvanizing Co., Pa
National Gasket & Washer Mfg. Co., Inc., NY
National Lock Co., Ill
Nylok Corp., NJ
Olean Electro Plating Co., NY
Pfister Tubing Corp., NJ
Plume & Atwood Mfg. Co., Conn
Promat Div., Poor & Co., Ill
Reed & Prince Mfg. Co., Mass
Reynolds Metal Co., Va
Rustproofing & Metal Finishing Corp., Mass
Sager Metal Strip Co., Ill
Sanford Process Co., Inc., Calif
Saramar Aluminum Co., Ohio
Schwartz Chemical Co., Inc., NY
Southern Aluminum Finishing Co., Inc., Ga
Spencer Nahm Co., Calif
Stevens, Frederic B, Inc., Mich
Trenton Pipe Nipple Co., NJ
Trim Alloys, Inc., Mass
Vanamatic Co., Ohio
W L S Stamping Co., Ohio
Woodstock Div., Electric Autolite Co., Ill
Youngstown Mfg. Inc., Ohio

## Conversion Coatings, Chromate

(formulations)

Abalon Precision Mfg. Corp., NY
Acme Plating Co., Ohio
Alchemize Corp., Ill
**Allied Chemical Corp., Solvay Process Div. NY** —Ad p 349
**Allied Research Products, Inc., Md** —Ad p 358
Amchem Products, Inc., Pa
**Chemical Corp., Mass** —Ad p 360
Colonial Alloys Co., Pa
Conversion Chemical Corp., Conn
Diamond Alkali Co., Ohio
Dollin Corp., NJ
Enthone, Inc., Conn
Heatbath Corp., Mass
Hull, R.O. & Co., Inc., Ohio
Lacquer & Chemical Corp., NY
MacDermid, Inc., Conn
Metal & Thermit Corp., NJ
Mitchell-Bradford Chemical Co., Conn
Modern Plating Corp., Ill
Neilson Chemical Co., Mich
Nylok Corp., NJ
Oakite Products, Inc., NY
Octagon Process, Inc., NY
Parker Paint Mfg. Corp., Ind
Parker Rust Proof Co., Mich
Pennsalt Chemicals Corp., Pa
Pierce & Stevens Chemical Corp., NY
Prestole Corp., Ohio
Promat Div., Poor & Co., Ill
Thompson & Co., Pa
Turco Products, Inc., Calif
Vanamatic Co., Ohio
Woodstock Div., Electric Autolite Co., Ill
Zeller Corp., Ohio

## Conversion Coatings, Chromate

(coaters)

Abalon Precision Mfg. Corp., NY
Accurate Anodizing Corp., Ill
Acme Plating Co., Ohio
Amchem Products, Inc., Pa
American Agile Corp., Ohio
American Emblem Co., Inc., NY
Brooks & Perkins, Inc., Mich
Clad-Rex Corp., Ill
Colonial Alloys Co., Pa
Diversey Corp., Metal Industries Div., Ill
Dollin Corp., NJ
Du-Wel Metal Products, Inc., Mich
Eaton Mfg. Co., Reliance Div., Ohio
Electrofilm, Inc., Calif
Falstrom Co., NJ
Farwell Metal Fabricating, Minn
Hardy Mfg. Corp., Ind
Kelley Mfg. Co., Tex
Lacquer & Chemical Corp., NY
Metal Finishers, Inc., Md
Metal & Thermit Corp., NJ
Modern Plating Corp., Ill
National Lock Co., Ill
Norgren-Stemac, Inc., Colo
Nylok Corp., NJ
Olean Electro Plating Co., NY
Prestole Corp., Ohio
Promat Div., Poor & Co., Ill
Rustproofing & Metal Finishing Corp., Mass
Sommer Metalcraft Corp., Ind
Spencer Nahm Co., Calif
United-Carr Fastener Corp., Mass
W L S Stamping Co., Ohio
Witt Cornice Co., Galvanizing Div., Ohio
Worth Co., Wis
Zeller Corp., Ohio

## Conversion Coatings, Oxide

(formulations)

Birchwood Chemical Co., Minn
Dollin Corp., NJ
Du-Lite Chemical Corp., Conn
Enthone, Inc., Conn
Heatbath Corp., Mass
Houghton, E.F. & Co., Pa
Hull, R.O. & Co., Inc., Ohio
MacDermid, Inc., Conn
Mitchell-Bradford Chemical Co., Conn
Modern Plating Corp., Ill
Neilson Chemical Co., Mich
Nylok Corp., NJ
Parker Paint Mfg. Corp., Ind
Prestole Corp., Ohio
Promat Div., Poor & Co., Ill
Tube Reducing Corp., NJ
Union Carbide Metals Co., Div. of Union Carbide Corp., NY
Vanamatic Co., Ohio
Zeller Corp., Ohio

## Conversion Coatings, Oxide

(coaters)

Biddle Screw Products Co., Ind
Diversey Corp., Metal Industries Div., Ill
Dollin Corp., NJ
Kelley Mfg. Co., Tex
Metal Finishers, Inc., Md
Metallizing Co. of Los Angeles, Inc., Calif
Modern Plating Corp., Ill
National Lock Co., Ill
Nylok Corp., NJ
Plume & Atwood Mfg. Co., Conn
Prestole Corp., Ohio
Rustproofing & Metal Finishing Corp., Mass
Spencer Nahm Co., Calif
United-Carr Fastener Corp., Mass
W L S Stamping Co., Ohio
Worth Co., Wis

## Conversion Coatings, Phosphate

(formulations)

Ainsworth Precision Castings Co., Div. of Harsco Corp., Mich
Amchem Products, Inc., Pa
Ashtabula Mfg. Co., Ohio
Detrex Chemical Industries, Inc., Mich
Dollin Corp., NJ
Enthone, Inc., Conn
Farrelloy Co., Pa
Fidelity Chemical Products Corp., NJ
Houghton, E.F. & Co., Pa
Hull, R.O. & Co., Inc., Ohio
Kelite Corp., NJ
MacDermid, Inc., Conn
Magnuson Products Corp., NY
Mitchell-Bradford Chemical Co., Conn
Modern Plating Corp., Ill
Neilson Chemical Co., Mich
Northwest Chemical Co., Mich
Nylok Corp., NJ
Oakite Products, Inc., NY
Octagon Process Inc., NY
Panther Chemical Corp., Tex
Parker Rust Proof Co., Mich
Pennsalt Chemicals Corp., Pa
Plume & Atwood Mfg. Co., Conn
Prestole Corp., Ohio
Promat Div., Poor & Co., Ill
Rustproofing & Metal Finishing Corp., Mass
Sharon Steel Corp., Pa
Thompson & Co., Pa
Turco Products, Inc., Calif
Union Carbide Metals Co., Div. of Union Carbide Corp., NY
Vanamatic Co., Ohio
Whitfield Chemical Co., Mich
Wyandote Chemicals Corp., Mich
Zeller Corp., Ohio

## Conversion Coatings, Phosphate

(coaters)

Almco Steel Products Corp., Ind
Amchem Products, Inc., Pa
Ashtabula Mfg. Co., Ohio

Biddle Screw Products Co., Ind
Brandt, Charles T., Inc., Md
Clad-Rex Corp., Ill
Diversey Corp., Metal Industries Div., Ill
Dollin Corp., NJ
Electrofilm, Inc., Calif
Falstrom Co., NJ
Farwell Metal Fabricating, Minn
Grand Rapids Brass Co., Mich
Hardy Mfg. Corp., Ind
Kelley Mfg. Co., Tex
Metal Finishers, Inc., Md
Modern Plating Corp., Ill
National Lock Co., Ill
National Metal Products Co., Pa
Nylok Corp., NJ
Prestole Corp., Ohio
Rustproofing & Metal Finishing Corp., Mass
Spencer Nahm Co., Calif
United Shoe Machinery Corp., Mass
United-Carr Fastener Corp., Mass
W L S Stamping Co., Ohio
Witt Cornice Co., Galvanizing Div., Ohio
Woodstock Div., Electric Autolite Co., Ill
Worth Co., Wis

## Copper and its Alloys

Acme Tube, Inc., NJ (ee)
Ajax Metal Div., H. Kramer Co., Pa (w)
Alcasco Foundry, Ill (w)
**Allied Research Products, Inc., Md** (n)—Ad p 358
Alloy Metal Products, Inc., Iowa (o,w)
Alofs Mfg. Co., Mich (dd)
Alpha Wire Corp., NY (ff)
American Brass Co., Sub. of Anaconda Co., NY (n,o,z,bb,cc,dd,ee,ff)
American Crucible Products Co., Ohio (o)
American Manganese Bronze Co., Pa (o,bb)
**American Metal Climax, Inc., Amco Div., NY** (n,o,q,w,aa)—Ad pp 165-168
American Metal Climax Inc., NY (n, o,q,w,aa)
American Nickel Alloy Mfg. Corp., NY (o)
American Silver Co., NY (v,dd,ee,ff)
American Smelting & Refining Co., NY (n,q,w)
American Steel and Wire Div., U. S. Steel Corp., Ohio (ff)
Ampco Metals, Inc., Wis (o,z,cc,dd,ee)
Anaconda Co., NY (n,q,v,w,cc)
Arcos Corp., Pa (ff)
Atlantic Powdered Metals, Inc., NY (aa)
Atlantic Steel Co., Ga (cc,dd)
Atlas Brass Foundry, Calif (o)
Auld, D.L. Co., Ohio (n,cc,dd,ff)
Avins Industrial Products Corp., NY (ee)
Avril, G.A. Co., Ohio (w)
Babson Dow Mfg. Co., Mass (o)
Baer Bros. Bronze Powder Co., Inc., Mass (aa)
Bart Mfg. Corp., NJ (aa)
Barth Smelting Corp., NJ (w)
Bay State Refining Co., Inc., Mass (w)
Belmont Smelting & Refining Works, Inc., NY (n,q,w,aa)
**Beryllium Corp., Pa** (o,q,w,z,bb,cc,dd,ee,ff)—Ad p 157
Biddle Screw Products Co., Ind (o,bb, ee)
Bohn Aluminum & Brass Corp., Mich (bb,ff)
Both, O.A. Corp., Mass (aa)
**Bridgeport Brass Co., Conn** (n,o,bb,cc,dd,ee,ff)—Ad p 176
Bridgeport Rolling Mills Co., Conn (dd)
Brinkerhoff Brass & Bronze Works, Inc., NY (z,bb,cc,dd,ee,ff)
Bristol Brass Corp., Conn (o,z,bb,cc, dd,ff)
Brush Beryllium Co., Ohio (o,q,w,z,dd)
Bullock, W.J., Inc., Ala (w)
Cerro de Pasco Sales Corp., NY (w,ee,ff)
Chase Brass & Copper Co., Sub of Kennecott Copper Corp., Conn (n,o, z,bb,cc,dd,ee,ff)
Chicago Extruded Metals Co., Ill (bb)
Clark Perforating Co., Mich (cc,dd)
Columbia-Geneva Steel Div., U.S. Steel Corp., Calif (ff)
**Continuous Cast Products Dept., American Smelting & Refining Co., NJ** (o,q,bb,ee)—Ad p 433
Copper & Brass Sales, Inc., Mich (n, o,q,v,z,bb,cc,dd,ee,ff)
Craft Metal Spinning Co., Ill (cc)
Crescent Bronze Powder Co., Ill (aa)
Crucible Steel Co. of America, Titanium & Vacuum Metals Product Div., Pa (o,q,w,z,cc,dd)
Designers Metal Corp., Ill (cc)
Detroit Float & Stamping Co., Mich (o,bb,dd,ee)
Dixon Sintaloy, Inc., Conn (o)
Dormont Mfg. Co., Pa (ee)
**Driver, Wilbur B. Co., NJ** (v,bb,dd,ff)—Ad p 185
Driver-Harris Co., NJ (bb,dd)
Dudek & Bock Spring Mfg. Co., Ill (ff)
Eastern Rolling Mills, Inc., NY (cc, dd)
Electric Materials Co., Pa (n,o,bb)
Electronic Parts Mfg. Co., Inc., NJ (ff)
Empire Metal Co., NY (n,o)
Erskine Precision Wire Corp., Pa (ff)
Essex Industrial Products Div., Essex Wire Corp., Ind (ff)
Essex Wire Corp., Magnet Wire Div., Ind (ff)
Eynon-Dakin Co., Mich (ee)
Federated Metals Div., American Smelting and Refining Co., NY (n, o,q,w,bb,ee)
Fromson Orban Co., Inc., NY (z,cc, dd,ee)
General Cable Corp., NY (ff)
Glidden Co., Ind (aa)
**Glidden Co., Chemical Divs., Metals Dept., Ind** (aa)—Ad p 429
Gold Leaf & Metallic Powders, Inc., NY (aa)
Grand Rapids Brass Co., Mich (z)
Greenback Industries, Inc., Mich (aa)
H & H Tube & Mfg. Co., Mich (b)
Hamilton Watch Co., Precision Metals Div., Pa (v,bb,cc,dd,ff)
Hardy, Charles, Inc., NY (aa)
Harris, Benjamin & Co., Ill (w)
Harshaw Chemical Co., Ohio (n)
Harvey Aluminum, Calif (o,bb)
Hayden Wire Works, Inc., Mass (ff)
Hettleman K. & Sons., Inc., Md (w)
Hodgson Foundry Co., Ill (n,o,z)
Hoffman Bronze & Aluminum Casting Co., Ohio (n)
Hommel, O. Co., Pa (aa)
Horton-Angell Co., Mass (n,o,bb,cc,dd, ee,ff)
**Hoskins Mfg. Co., Mich** (bb,dd)—Ad p 177
Houston Blow Pipe & Sheet Metal Works, Tex (o,cc)
Hudson, Inc., NJ (w)
Hull, R.O. & Co., Inc., Ohio (n)
**Hussey, C.G. & Co., Div. of Copper Range Co., Pa** (n,o,z,bb,cc,dd,ee,ff)—Ad p 180
Inshield Die & Stamping Co., Ohio (dd)
Inspiration Consolidated Copper Co., NY (n,o,q)
**Instrument Specialties Co., Inc., NJ** (dd)—Ad p 463
International Minerals and Metals Corp, NY (w)
International Powder Metallurgy Co., Inc., Pa (z,aa,ee)
Jelliff, C.O. Mfg. Corp., Conn (ff)
Jordan-Rogers Co., Calif (ff)
K. & L. Plating Co., Pa (z)
Kassel Export Co., Inc., NJ (v,ff)
Kelsey-Hayes Co., Metals Div., NY (o,q,v,w,z,bb,cc,dd,ff)
Kenmore Machine Products, Inc., NY (ee)
Kinkead Industries, Inc., Ill (cc,dd)
Lakeland Industries, Minn (z)
Laminated Shim Co., Conn (cc)
Langsenkamp, F.H. Co., Ind (o,z,bb, cc,dd,ee,ff)
Lavin, R. & Sons, Inc., Ill (n,w)
Leach & Garner Co., Industrial Div., Mass (v,bb,cc,dd,ee,ff)
Lewin-Mathes Div., Cerro De Pasco Corp., Mo (q,w,bb,ee)
Loewenthal Metals Corp., Ill (w)
Lundquist Tool & Mfg. Co., Inc., Mass (cc,dd)
Mackenzie Walton Corp., RI (ee)
Magna Mfg. Co., Inc., NJ (aa)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (o,dd,ee,ff)
Mallory, P.R. & Co., Inc., Ind (o, bb,dd,ff)
Malone Bronze Powder Works, Inc., NY (aa)
Malone Metal Powders, Inc., NJ (aa)
McGean Chemical Co., Ohio (n,aa,dd)
McGregor-Michigan Corp., Mich (ee)
Metal & Thermit Corp., NJ (n)
Metallizing Co. of Los Angeles, Inc., Calif (ff)
Metals Disintegrating Co., Inc., NJ (aa)
Miller Co., Conn (dd)
Modern Plating Corp., Ill (n,o,dd,ff)
Mueller Brass Co., Mich (bb)
Murray, A.B. Co., Inc., NJ (ee)
National Electric Div., H.K. Porter Co., Pa (ff)
National Lead Co., NY (ee)
Nesor Alloy Products Co., NJ (dd,ff)
New England Brass Co., Mass (cc,dd)
New England Electrical Works, Inc., NH (ff)
New England Smelting Works, Inc., Mass (w)
**New Jersey Zinc Co., NY** (aa)—Ad pp 452-453
New Haven Copper Co., Conn (n,z,cc, dd)
New Jersey Metals Co., NJ (n,w)
Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)
Nippert Electric Products Co., Ohio (bb,dd)
Norrich Plastics Corp., Screw Machine Products Div., NY (o,bb)
Norwalk Powdered Metals, Inc., Conn (aa)
Okonite Co., Sub. of Kennecott Copper Corp., NJ (bb,ff)
Olds Alloys Co., Calif (ee)
**Olin Mathieson Chemical Corp., Metals Div., NY** (cc,dd)—Ad p 155
Ormond Mfg. Co., Inc., NJ (dd,ff)
Peerless Roll Leaf Co., Div. of Howe Sound Co., NJ (v,dd)
Penn Brass & Copper Co., Pa (ee)
Phelps Dodge Copper Products Corp., NY (dd)
Phelps Dodge Refining Corp., NY (n,o)
Plume & Atwood Mfg. Co., Conn (bb, cc,dd,ff)
Precision Tube Co., Inc., Pa (ee)
Rathbone Corp., Mass (o,bb)
Republic Metals Co., Inc., NY (n,w)
Revere Copper & Brass, Inc., NY (n, o,v,z,bb,cc,dd,ee)
Revere Copper & Brass, Inc., Foil Div., NY (v)
Reynolds Aluminum Supply Co., Ga (o, bb,cc,dd,ee)
Rigidized Metals Corp., NY (cc,dd)
River Smelting & Refining Co., Ohio (w)
**Riverside-Alloy Metal Div. H.K. Porter Co., Inc., NJ** (bb,dd,ff)—Ad p 160
Rodney Metals, Inc., Mass (v,dd)
Roebling's, John A. Sons Div., Colorado Fuel & Iron Corp., NJ (bb,dd, ff)
Rome Mfg. Div., Revere Copper & Brass, Inc., NY (n)
Saginaw Bearing Co., Mich (o,q)
Sall, George Metals Co., Inc., Pa (w)
Sandusky Foundry & Machine Co., Ohio (ee)
Schumann, I. & Co., Ohio (w)
**Scovill Mfg. Co., Mill Products Div., Conn** (bb,cc,dd,ee,ff)—Ad pp 169-170
**Sel-Rex Corp., NJ** (n,aa)—Ad p 356
**Seymour Mfg. Co., Conn** (bb,dd,ff)—Ad p 178
Shenango Furnace Co., Centrifugally Cast Products Div., Ohio (ee)
Sherwatt Equipment & Mfg. Co., Inc., NY (ff)
Sipi Metals Corp., Ill (w)
**Somers Brass Co., Inc., Conn** (v,dd)—Ad p 162
Sonken-Galamba Corp., Mo (w)
Stamford Rolling Mills Co., Inc., Conn (cc)
Standard Metals Corp., Mass (ee,ff)
Star Heel Plate Co., Inc., NJ (ff)
Stauffer-Temescal Co., Calif (q,w)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Stevens, Frederic B., Inc., Mich (n)
Sylvania Electric Products, Inc., Parts Div., Pa (ff)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (ff)
Terre Haute Bronze & Brass Foundry, Ind (bb,cc,dd,ee)
Texas Instruments, Inc., Metals & Controls Div., Mass (v)
Thinsheet Metals Co., Conn (cc)
Titan Metal Mfg. Co., Pa (o,bb)
Triangle Conduit & Cable Co., Inc., NJ (bb,ee,ff)
Udylite Corp., Mich (n,o,bb)
Ullmann, Inc., Wis (o,ee)
U.S. Bronze Powder Works, Inc., NJ (aa)
U.S. Metal Products Co., Pa (w)
United Wire & Supply Corp., RI (ee,ff)
Universal Castings Corp., Ill (w)
Utility Mfg. Co., Mass (o,bb)
Viking Copper Tube Co., Ohio (ee)
Volco Brass & Copper Co., NJ (cc)
Wallace Tube Co., Div. of Wallace Supplies Mfg. Co., Ill (ee)
Waterbury Rolling Mills, Inc., Conn (cc,dd)
Wells, A.H. & Co., Inc., Conn (ee)
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,v,w,z,bb, cc,dd,ee)
Whitaker Metals Corp., Mo (aa)
Whitehead Metal Products Co., Inc., NY (o,z,bb,cc,dd,ee,ff)
Wisconson Centrifugal Foundry, Inc., Wis (ee)
Wright, Albert Screw Machine Products, Calif (bb)

## Cordierite

(see Ceramics)

## Cork

Armstrong Cork Co., Pa (r)
Conolite Div., Continental Can Co., Del (bb,cc,ee)
Coyne & Paddock, Inc., NY (cc)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (r,aa,cc)
Dutch Brand Div., Johns-Manville Corp., Ill (r,cc)
Enamel Products Co., Ohio (r)
General Gasket, Inc., Conn (r)
Hollingsworth & Vose Co., Mass (r)
National Gasket & Washer Mfg. Co., Inc., NY (r,cc)
Newth Rubber Co., RI (cc)
Peerless Products Industries, Ill (r)
Sheller Mfg. Corp., Mich (r,bb,cc,ee)
Sillcocks Miller Co., NJ (r)
Spring Packing Corp., Ill (r)
Staver Co., Inc., NY (r,cc)
Superior Mfg. Co., Pa (r)
United Cork Cos., NJ (r)
Wisconsin Gasket & Mfg. Co., Wis (r)

## Corrugated Metals

Aetna Steel Co., Fla (g)
Albert Pipe Supply Co., Inc., NY (g)
Aluminum Co. of America, Pa (a)
Armco Steel Corp., Ohio (g)
Atlantic Steel Co., Ga (g)
Bethlehem Steel Co., Pa (g)
Biersach & Niedermeyer Co., Wis (a,b,g)
Cartwright, R. Tube Products Co., Mich (a)
Clendenin Bros., Inc., Md (a)
Cobra Metal Hose Div., DK Mfg. Co., Ill (b,f,h)
Colonial Alloys Co., Pa (a)
Conner Mfg. Co., Ky (c)
Edgcomb Steel & Aluminum Corp., NJ (a,g)
Electric Steel Foundry Co., Ore (g)
Empire-Reeves Steel Div., Universal-Cyclops Steel Corp., Pa (g)
Gulfoy Cornice Works, Calif (a,c)
Illinois Zinc Co., Div. of Hydrometals, Inc., Ill (j)
Inland Steel Co., Ill (g)
Johnson Metal Hose, Inc., Conn (b,f,g)
Jones & Laughlin Steel Corp., Pa (g)
Kaiser Aluminum & Chemical Sales, Inc., Ill (a)
Kelley Mfg. Co., Tex (a,g)
Levinson Steel Co., Pa (a,g)
New York Iron Roofing & Corrugating Co., Inc., NJ (a,g)
Olin Mathieson Chemical Corp., Metals Div., NY (a)
Powell Pressed Steel Co., Ohio (a,g)
Republic Steel Corp., Ohio (g)
Revere Copper & Brass, Inc., NY (a,b)
Reynolds Aluminum Supply Co., Ga (a,g)
Reynolds Metals Co., Va (a)
Rockwell Engineering Co., Ill (a,b,c,g)
Ryerson, Joseph T. & Son, Inc., Ill (g)
Stawer Co., Inc., NY (a,b,c,d,e,f,g,h,j)
Sun Steel Co., Ill (a,g,h)
U.S. Steel Corp., Pa (g)

## Cupro-Nickel

(see Copper)

## Diallyl Phthalate

(DAP)
Alcylite Plastics & Chemical Corp., Calif (x,y)
Chemicals & Plastics Div., Food Machinery & Chemical Corp., NY (p,x,y)
Cordo Chemical Corp., Conn (x,y)
Cordo Molding Products, Inc., Conn (y)
**Durez Plastics Div., Hooker Chemical Corp., NY**
(y)—Ad pp 232-233
Dyna-Therm Chemical Corp., Calif (p)
F M C Organic Chemicals Div., Food Machinery & Chemical Corp., NY (p)
Fiber Glass Industries, Inc., NY (x,y,cc)
Formica Corp., Sub. of American Cyanamid Corp., Ohio (bb,cc,dd)
Hays Mfg. Co., Pa (y)
Maloney, F.H. Co., Tex (y)
Mesa Plastics Co., Calif (p,y,bb,cc)
**Rogers Corp., Conn**
(y)—Ad p 261
Specialty Resins Co., Calif (p,x)
Synthane Corp., Pa (bb,cc,dd,ee)
U.S. Polymeric Chemicals, Inc., Conn (s)

## Die Castings

(see Castings)

## Diffusion Coatings

(calorized, chromized, sherardized)
Alloy Surfaces Co., Inc., Del
Calorizing Co., Pa
Chromalloy Corp., NY
Chromizing Corp., Calif
Colonial Alloys Co., Pa
General Extrusions, Inc., Ohio
Kelley Mfg. Co., Tex
Metal Finishers, Inc., Md
Modern Plating Corp., Ill
Nylok Corp., NJ
Sheldon, M.L. & Co., Inc., NY
Tickle, Arthur Engineering Works, Inc., NY
Vanamatic Co., Ohio

## Dip Coatings

(see Immersion Coatings; Galvanizers)

## Dispersion Coatings

(see Organic Coatings)

## Drawn, Pressed Parts

(not incl. stampings)
Abaion Precision Mfg. Corp., NY (a,b,c,g)
Ackermann Mfg. Co., W. Va (g)
Acme Metal Spinning, Inc., Minn (a,b,c,d,e,f,g,h,j)
Acme Stamping & Wire Forming Co., Pa (a,b,g)
Acorn Sheet Metal Mfg. Co., Inc., Ill (a,g)
Alco Products, Inc., NY (g)
AllianceWall Div., AllianceWare, Inc., Ohio (g)
Alloy Products Corp., Wis (a,f,g,h)
Aluminum Co. of America, Pa (a)
Aluminum Goods Mfg., Wis (a,g)
Aluminum Specialty Co., Wis (a,g)
American Aluminum Co., NJ (a,b)
American Brass Co., Sub. of Anaconda Co., NY (b)
American Car & Foundry Div., ACF Industries, Inc., NY (a,e,g)
American Forge & Mfg. Co., Pa (g)
American Machine & Foundry Co., Cleveland Welding Div., Ohio (f,g,h)
American Silver Co., Inc., NY (a,b,e,f,g)
Anchor Metal Spinning Co., Ohio (a,b,c,d,f,g)
Anthes Div., Gleason Corp., Iowa (a,g)
Armco Steel Corp., Sheffield Div., Mo (g)
Arrow Metal Products Corp., NJ (a)
Arvin Industries, Inc., Ind (a,g)
Associated Spring Corp., Wallace Barnes Steel Div., Conn (g)
Atlas Metal Parts Co., Wis (a,b,c,g)
Auld, D.L. Co., Ohio (c)
Belmont Smelting & Refining Works, NY (a,b,g)
Bethlehem Steel Co., Pa (g)(a,b,g)
Boots Aircraft Nut Corp., Conn (g)
Brandt, Charles T., Inc., Md (a,b,e,g)
**Brooks & Perkins, Inc., Mich**
(a,e,g,h)—Ad p 457
Brown Lipe Chapin Div., General Motors Corp., NY (g)
Cly-Del Mfg. Co., Conn (a,b,f,g,j)
Colonial Alloys Co., Pa (a)
Columbus Bolt & Forging Co., Ohio (a,b,g)
Commercial Shearing & Stamping Co., Ohio (a,f,g)
Consolidated Fruit Jar Co., NJ (a,b,c,d,g,j)
Cooley, W.J. & Co., Tenn (a,b,c,g)
Crosby Co., NY (a,b,g)
Crown Metal Co., Wis (d)
Crucible Steel Co. of America, Pa (g,h)
Cuyahoga Stamping Co., Ohio (a,b,g)
Cyril Bath Co., Ohio (a,e,f,g,h)
Dahlin, C. A. Co., Ill (a,b,d,e,f,g,j)
Dana Corp., Auburn Div., Ind (g)
Dayton Rogers Mfg. Co., Minn (a,b,c,g,j)
Detroit Stamping Co., Mich (a,b,g)
Dirilyte Co. of America, Inc., Ind (a,b)
Division Lead Co., Ill (d)
Dow Chemical Co., Dow Metal Products Co. Div., Mich (e)
Eastern Tool & Mfg. Co., NJ (a,b,c,d,g,h)
Eastern Tool & Stamping Co., Inc., Mass (a,b,c)
Eaton Mfg. Co., Reliance Div., Ohio (g)
Edgcomb Steel & Aluminum Corp., NJ (g)
Electric Autolite Co., Ohio (c)
Electric Materials Co., Pa (b)
Electric Steel Foundry Co., Ore (g)
Etched Products Corp., NY (a,b,g)
Evans, George Corp., Ill (a)
Falstrom Co., NJ (a,b,e,f,h)
Farwell Metal Fabricating, Minn (a,b,e,f,g)
Fletcher Enamel Co., W. Va (a,b,c,d,e,f,g)
Forg, Peter Mfg. Co., Mass (a,b,c,h)
Frasse, Peter A. & Co., Inc., NY (a,g)
Garco Mfg. Co., Inc., Ill (a,b,c,e,f,g,h,j)
General Alloys Co., Mass (a,b,f)
General Findings & Supply Co., Industrial Div., Mass (b,f,g)
Geuder, Paeschke & Frey Co., Wis (a,c,f,g)
Grammes, L.F. & Sons, Inc., Pa (a,b,c,g)
H & H Tube & Mfg. Co., Mich (b)
Hydroforming Co. of America, Ill (a,b,f,g,h)
Ideal Can Co., Mass (a,b,g)
Illinois Zinc Co., Div. of Hydrometals, Inc., Ill (j)
Ingersoll Products Div., Borg-Warner Corp., Ill (g)
Inland Steel Co., Ill (g)
International Silver Co., Eyelet Specialty Div., Conn (a,b,g)
Irwin-Sensenich Corp., Pa (g)
Jones & Laughlin Steel Corp., Pa (g)
Kees, F.D. Mfg. Co., Neb (a,g)
Kelley Mfg. Co., Tex (a,g)
Kelsey-Hayes Co., Mich (g)
Kling Metal Spinning & Stamping Co., NY (a,b,c,d,e,f,g,j)
Koehler Mfg. Co., Mass (a,b,c,g)
Lakewood Metal Products, Inc., Conn
Lansing Stamping Co., Mich (g)
Latrobe Steel Co., Pa (g)
Leake Engineering Co., Mich (a,b,c,d,e,f,g,h,j)
Leake Stamping Div., Monarch Products Co., Mich (a,b,f,g,h)
Lenape Hydraulic Pressing & Forging Co., Pa (a,b,g)
Linde Co., Div. of Union Carbide Corp., NY (g)
Lukens Steel Co., Pa (a,b,e,f,g,h)
Lundquist Tool & Mfg. Co., Inc., Mass (a,g)
Magline, Inc., Mich (a,e)
Magnesium Co. of America, Ind (a,e)
Magnesium Products of Milwaukee, Inc., Wis (a,e)
Mahon, R.C. Co., Mich (a,g)
Manganese Steel Forge Co., Pa (g)
Manufacturers Service, Inc., Ohio (a,b,g)
Matthiessen & Hegeler Zinc Co., Ill (j)
Midwest Stamping & Mfg. Co., Ohio (a,b,f,g)
Milwaukee Stamping Co., Wis (a,b,g)
Mirro Aluminum Co., Wis (a)
Morse, Fred W. Co., RI (a,b,c,g,j)
Morton Mfg. Co., Ill (a,g)
National Metal Products Co., Pa (a,b,d,g,j)
National Moldite Co., NJ (c)
Nichols, L.O. & Son Mfg. Co., Mo (a,b,c,g)
Nichols Wire & Aluminum Co., Iowa (a)
Nippert Electric Products Co., Ohio (b)
Olean Electro Plating Co., NY (a,b,g)
Olderman Mfg. Corp., Conn (b)
Olin Mathieson Chemical Corp., Metals Div., NY (b)
Parish Pressed Steel Div., Dana Corp., Pa (a,g)
Peterson Products Corp., Ill (a,b,f,g)
Phoenix Products Co., Wis (a,b,c,f,g)
Pioneer Stamped Products Co., NY (a,b,e,f,g)
Pittsburgh Steel Co., Pa (g,j)
Plume & Atwood Mfg. Co., Conn (a,b,c,f,g,l)
Polar Ware Co., Wis (a,b,f,g)
Powell Pressed Steel Co., Ohio (a,g)
Precision Extrusions, Inc., Ill (a)
Pressed Steel Co., Pa (a,b,f,g)
Pressed Steel Tank Co., Wis (a,b,c,e,f,g,h)
Queen Products Co., Inc., Ky (a,g)
Regal Ware, Inc., Wis (a,b,g)
Reichert Float & Mfg. Co., Ohio (a,b,c,d,f,j)
Republic Steel Corp., Ohio (g)
Revere Copper & Brass, Inc., NY (a,b)
Reynolds Metals Co., Va (a)
Rockwell Engineering Co., Ill (a,b,c,g)

Rockwell-Standard Corp., Stamping Div., NY (a,b,d,f,g)
Rohr Aircraft Corp., Calif (a,e,g,h)
Rolock, Inc., Conn (f)
Ryerson, Joseph T. & Sons, Inc., Ill (a,g)
Scaife Co., Pa (a,b,c,e,f,g,h)
Scovill Mfg. Co., Mill Products Div., Conn (a,b,c,f,g)
Shank Metal Products Co., NY
Simonsen Metal Products Co., Ill (a,g)
Smoot-Holman Co., Calif (g)
Southern Metal Products Co., La (a,g)
Southwestern Porcelain Steel Corp., Okla (g)
Spincraft, Inc., Wis (a,b,g)
Star Stamping Co., Mich (a,b,g)
Staver Co., Inc., NY (a,b,c,d,e,f,g,h,j)
Stirrup Metal Products Corp., NJ (a,b,c,g)
Superior Mfg. Co., Pa (g)
Superior Spinning & Stamping Co., Ohio (a,b,f,g)
Sylvania Electric Products, Inc., Parts Div., Pa (a,b,c,f,g)
Teiner, Roland Co., Inc., Mass (a,b,f,g)
Texas Instruments, Inc., Metals & Controls Div., Mass (a,b,c,e,f,g,h,j)
Textile Shield Co., Inc., Mass (a,b,g)
Thompson-Bremer & Co., Ill (a,b,c,f,g,h)
Titan Metal Mfg. Co., Pa (b)
Trenton Pipe Nipple Co., NJ (b,g)
Triangle Stamping Co., Ohio (a,b,c,d,f,g,j)
United-Carr Fastener Corp., Mass (a,b,g)
Van Huffel Tube Corp., Ohio (a,b,g)
Volkert Stampings, Inc., NY (b,f,g)
Vollrath Co., Wis (g)
Vulcan-Kidd Steel Div., H.K. Porter Co. Inc., Pa (g)
Waterbury Cos., Inc., Conn (a,b,g)
Waterbury Pressed Metal Co., Conn (a,b,f,g)
Waterman Industries, Inc., Calif (a,b,g)
Wayne Foundry & Stamping Co., Mich (a,b,e,g,h)
Wesbar Stamping Corp., Wis (a,b,c,g)
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY (a,b,c,e,f,g)
Wilson-Hurd Mfg. Co., Inc., Wis (a)
Wisconsin Tool & Stamping Co., Ill (a,b,g)
Wolverine Tube Div., Calumet & Hecla, Inc., Mich (a)
Worcester Pressed Steel Co., Mass (a,b,c,e,f,g,h,j)
Worcester Stamped Metal Co., Mass (a,b,f,g,h,j)
Wuest Bros., Inc., Ky (a,b,c,f,g)
Wycoff Steel Co., Pa (g)
Youngstown Kitchens Div., American Standard Co., Ohio (a,g)
Youngstown Mfg., Inc., Ohio (a,g)

## Drop Forgings

(see Forgings)

## Ductile Iron

(see Iron)

## Electrodes, Welding

(see Filler Metals)

## Electroless Coatings

(see Immersion Coatings)

## Electroplated Coatings

(Electroplaters; see also Preplated Metals)

Abalon Precision Mfg. Corp., NY
Accurate Anodizing Corp., Ill
Acme Plating Co., Ohio
Ainsworth Precision Castings Co., Div. of Harsco Corp., Mich
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY
Allied Research Products, Inc, Md
Aluminum Billets, Inc., Ohio
American Emblem Co., Inc., NY
American Nickeloid Co., Ill
American Platinum & Silver Div., Engelhard Industries, Inc., NY
—Ad p 159
American Smelting & Refining Co., NY
Apollo Metal Works, Ill
Atlantic Brass Works, Inc., Ill
Atlantic Steel Co., Ga
Auld, D.L. Co., Ohio
Bart Mfg. Corp., NJ
Bethlehem Steel Co., Pa
Bishop, J. & Co. Platinum Works, Pa
Boyles Galvanizing & Plating Co., Tex
Brown Lipe Chapin Div., General Motors Corp., NY
Brewer-Titchener Corp., NY
Brooks & Perkins, Inc., Mich
Chromium Corp. of America, NY
City Plating Works, Inc., Conn
Cohan Epner Co., Inc., NY
Colonial Alloys Co., Pa
Columbus Dental Mfg. Co., Ohio
Commercial Screw Products Co., Ohio
Conforming Matrix Corp., Ohio
Continental Die Casting Corp., Mich
Croname, Inc., Ill
Designers Metal Corp., Ill
Diamond Alkali Co., Ohio
Diversey Corp., Metal Industries Div., Ill
Doehler-Jarvis Div., National Lead Co., Ohio
Dollin Corp., NJ
Du-Wel Metal Products, Inc., Mich
Eaton Mfg. Co., Reliance Div., Ohio
Edna Lite Optical Co., Inc., NY
Electric Autolite Co., Ohio
Electric Materials Co., Pa
Electrolizing Corp., Ohio
Elmet Div., North American Phillips Co., Inc., Me
Fox Co., Ohio
General Chain & Mfg. Corp., Ohio
General Findings & Supply Co., Industrial Div., Mass
Grand Rapids Brass Co., Mich
Hardy Mfg. Corp., Ind
Harshaw Chemical Co., Ohio
Hilfinger Corp., Ohio
Hull, R.O. & Co., Inc., Ohio
Indium Corp. of America, NY
Industrial Chromium Corp., Mass
Jervis Corp., Mich
K. & L. Plating Co., Pa
Kees, F.D. Mfg. Co., Neb
La France Precision Casting Co., Pa
Lakeland Industries, Minn
Lea Mfg. Co., Conn
Litho-Strip Corp., M.M. Young Div., Ill
Lundquist Tool & Mfg Co., Inc., Mass
MacDermid, Inc., Conn
Marlane Development Co., Inc., NY
Master Chrome Service, Inc., Ohio
McGean Chemical Co., Ohio
Mechanical Plating Co., Ill
Medico Industries, Inc., Pa
Merrimac Brass, Mass
Metal Finishers, Inc., Md
Metal & Thermit Corp., NJ
Metaplast Process, Inc., NY
Michigan Chrome & Chemical Co., Mich
Modern Plating Corp., Ill
National Malleable & Steel Castings Co., Ohio
New Jersey Metals Co., NJ
New Jersey Zinc Co., NY
Norgren-Stemac, Inc., Colo
Nylok Corp., NJ
Olean Electro Plating Co., NY
Ormond Mfg. Co., Inc., NJ
Penn Metal Co., Inc., W. Va
Pittsburgh Steel Co., Pa
Plume & Atwood Mfg. Co., Conn
Promat Div., Poor & Co., Ill
Reed & Prince Mfg. Co., Mass
Republic Steel Corp., Ohio
Rustproofing & Metal Finishing Corp., Mass
Ryerson, Joseph T. & Son, Inc., Ill
St. Eloi Corp., Ohio
St. Louis Diecasting Corp., Mo
Seal-Peel, Inc., Mich
Sifco Metachemical, Inc., Ohio
Sommer Metalcraft Corp., Ind
Southern Metal Products Co., La
Spencer Nahm Co., Calif
Steel Protection & Chemical Co., Ind
Stevens, Frederic B., Inc., Mich
Stirrup Metal Products Corp., NJ
Sylvania Electric Products, Inc., Parts Div., Pa
Texas Instruments, Inc., Metals & Controls Div., Mass
Tiarco Corp., NJ
Trenton Pipe Nipple Co., NJ
Tubular Rivet & Stud Co., Mass
United Refining & Smelting Co., Ill
United-Carr Fastener Corp., Mass
Vanamatic Co., Ohio
Van der Horst Corp., NY
Van Valkenburg, L.D. Co., Mass
WLS Stamping Co., Ohio
Waldman, Joseph & Sons, Epoxy Products Div., NJ
Wayne Foundry & Stamping Co., Mich
Wesbar Stamping Corp., Wis
Western Coating Co., Mich
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY
Williams Gold Refining Co., Inc., NY
Woodstock Div., Electric Auto-Lite Co., Ill
Worcester Wire Works Div., National-Standard Co., Mass
Worth Co., Wis
Wright Metalcoaters, NJ
Wyandotte Chemicals Corp., Mich
Zeller Corp., Ohio

## Embossed Metals

(incl. rigidized)

Aluminum Co. of America, Pa (a)
American Nickeloid Co., Ind. (a,b,g,j)
Ardmore Products, Inc., NJ (a,b,c,d,e,f,g,h,j)
Atlantic Steel Co., Ga (a,b,g)
Auld, D.L. Co., Ohio (a,b)
Biersach & Niedermeyer Co., Wis (a,b,g)
Clad-Rex Corp., Ill
Colonial Alloys Co., Pa (a)
Cooley, W.J. & Co., Tenn (a,b,c,g)
Copper & Brass Sales, Inc., Mich (a)
Croname Inc., Ill (a,b,f,g,j)
Electric Steel Foundry Co., Ore (a,b,c,g)
Fairmont Aluminum Co., Va (a)
Falstrom Co., NJ (a,b,e,f,g,h)
Grammes, L.F. & Sons, Inc., Pa (a,b,g)
Grigolelt Co., Ill (a,g)
Hawkridge Bros. Co., Mass (a)
Haydon Corp., NY (a,g)
Kaiser Aluminum & Chemical Sales, Inc., Ill (a)
Langsenkamp, F.H. Co., Ind (a)
Mahon, R.C. Co., Mich (a)
McKinney Mfg. Co., Pa (a,b,e,f,g)
Metal Goods Corp., Mo (a)
Morse, Fred W Co., RI (a,b,c,g)
Olin Mathieson Chemical Corp., Metals Div., NY (a)
Pittsburgh Steel Co., Pa (g)
Premier Metal Works, Inc., Ill (a,b,f,g)
Republic Steel Corp., Ohio (g)
Revere Copper & Brass, Inc., NY (a)
Reynolds Aluminum Supply Co., Ga (a)
Reynolds Metal Co., Ky (a)
Rigidized Metals Corp., NY (a,b,f,g,h)
Rockwell Engineering Co., Ill (a,b,c,g)
Ryerson, Joseph T. & Son, Inc., Ill (a)
Sager Metal Strip Co., Ill (a)
Sharon Steel Corp., Pa (g)
Southern Aluminum Finishing Co., Inc., Ga (a)
Southwestern Porcelain Steel Corp., Okla (g)
Sun Steel Co., Ill (a,g,h)
Wesbar Stamping Corp., Wis (a,b,c,g)
Whitehead Metal Products Co., Inc., NY (a,b,f,g)
Wilson-Hurd Mfg. Co., Inc., Wis (a)

## Emulsion Coatings

(see Organic Coatings)

## Enamels

(see Organic Coatings)

## Epoxies

Adhesive Products Corp., NY (z)
Aerojet-General Corp., Structural Materials Div., Calif (y,ee)
Alcylite Plastics & Chemical Corp., Calif (p)
Amercoat Corp., Calif (ee)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

**American Metaseal Corp., NJ (x,ee)**
American-Marietta Co., Adhesive, Resin & Chemical Div., Wash (p,y)
**Angier Adhesives Div., Interchemical Corp., Mass (x)**
Aries Laboratories, Inc., Conn (p,x,y)
Armstrong Products Co., Ind (x)
**Atlas Mineral Products Co., Pa (x)**
**Biggs, Carl H. Co., Inc., Calif (t,x,y)**
Bisonite Co., Inc., NY (x)
Booty Resineers Div., American-Marietta Co., Ohio (y)
Borden Chemical Div., Borden Co., NY (p)
Cadillac Plastic & Chemical Co., Mich (p,x)
Chemical Coatings & Engineering Co., Inc., Pa (p,x)
Chemical Development Corp., Mass (p, x)
Chemicals and Plastics Div., Food Machinery & Chemical Corp., NY (p,y)
**Ciba Co., Inc., Plastics Div., Pa**
(p,x)—Ad pp 278-279
Clinton Co., Ill (x,y)
Coast Pro-Seal & Mfg. Co., Calif (x)
Colonial Kolonite Co., Ill (bb,cc)
Comco Plastics, Inc., NY (bb,cc,dd,ee)
Continental-Diamond Fibre Corp., Del (bb,cc,dd,ee)
Co-Polymer Chemicals Inc., Mich (x)
Cordo Chemical Corp., Conn (x,y)
Cordo Molding Products, Inc., Conn (y)
Curbell, Inc., NY (bb,cc,ee)
Dayton Rubber Co., Ohio (x,y)
Dennis Chemical Co., Mo (y)
Devcon Corp., Mass (x,y)
Dow Chemical Co., Plastics Div., Mich (p)
Dyna-Therm Chemical Corp., Calif (p)
Electro Chemical Engineering & Mfg. Co., Pa (t,cc)
Electrofilm, Inc., Calif (t)
Electronic Production & Development, Inc., Chemical Div., Calif (x,y)
Emerson & Cuming, Inc., Mass (p,u, x,bb)
Fiber Glass Industries, Inc., NY (x,y, cc)
Fibercast Div., Youngstown Sheet & Tube Co., Okla (ee)
Formica Corp., Sub. of American Cyanamid Co., Ohio (cc,ee)
Foss Mfg. Co., Id (x)
Fry Plastics International, Calif (p,x)
Fuller, H.B. Co., Minn (x)
Furane Plastics, Inc., Calif (x,y)
Galigher Co., Utah (p,s,x)
General Electric Co., Laminated Products Dept., Ohio (bb,cc,ee)
General Plastics Mfg. Co., Wash (x)
Glass Reinforced Plastics Corp., Ohio (bb,ee)
Glo-Brite Products, Inc., Ill (u)
Hardman, H.V. Co., Inc, NJ (x)
Hauger-Beegle Asso., Inc., Ill (t,x)
Hiller Aircraft Corp, Adhesive Engineering Div., Calif (t,u,x)
Hysol Corp., NY (p,x,y,bb,cc,dd,ee)
Insulation Mfrs. Corp., Ill (x)
Jones-Dabney Co., Div. of Devoe & Raynolds Co., Inc., Ky (p,x)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Kish Industries, Inc., Mich (x)
Kurz, Kasch, Inc., Ohio (y)
Maloney, F.H. Co., Tex (x,y)
Marblette Corp., NY (x,y,bb)
Mesa Plastics Co., Calif (p,y,bb,cc)
Mica Corp., Calif (cc)
Mica Insulator Div., Minnesota Mining & Mfg. Co., NY (cc)
Micarta Div., Westinghouse Electric Corp., SC (x,y)
Miller-Stephenson Chemical Co., Inc., Conn (p,y,bb)
Narmco Industries, Inc., Narmco Materials Div., Calif (u,x,y,dd)
National Vulcanized Fibre Co., Del (cc)
New England Laminates Co., Inc., Conn (cc)
Norrich Plastics Corp., NY (bb,cc,dd, ee)
Northern Plastics Corp., Wis (cc,dd)
Ohio Adhesives Corp., Ohio (x)
Panelyte Div., St. Regis Paper Co., NJ (x,bb,cc,dd,ee)
Permacel, NJ (p,x,y)
Philrus Products Co., NJ (bb,cc,dd,ee)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Poly Resins, Calif (p,x)
Polygon Plastic Co., Ind (ee)
Polymer Corp., Pa (y)
Porter, William Co., Calif (cc,ee)
Pyrosil, Inc., Ohio (x,cc)
Radiation Applications, Inc., NY (x)
Raybestos-Manhattan, Inc., Plastic Products Div., Pa (x,cc)
Raybestos-Manhattan, Inc., Raybestos Div., Conn (p,x)
Reichhold Chemicals, Inc., NY (p,x)
Ren Plastics, Inc., Mich (p,s,x,y,ee)
Reynolds Chemical Products Co., Mich (p,x)
Rezolin, Inc., Calif (p,x)
Richardson Co., NY (bb,cc,ee)
Rogers Corp., Conn (y)
Roller Reinforced Plastics, Ohio (x)
Schwartz Chemical Co., Inc., NY (x)
Shell Chemical Co., NY (p)
Spaulding Fibre Co., Inc., NY (bb,cc, dd,ee)
Specialty Resins Co., Calif (x,y)
Strick Plastics Co., Pa (u,cc)
Sun Chemical Corp., Electro Technical Div., NJ (x)
Swedlow, Inc., Calif (cc)
Synthane Corp., Pa (bb,cc,dd,ee)
Taylor Fibre Co., Pa (bb,cc,dd,ee)
**Union Carbide Plastics Co., Div. of Union Carbide Corp., NY**
(p,x)—Ad p 257
U.S. Gypsum Co., Ill (x)
U.S. Polymeric Chemicals, Inc., Conn (s)
**Waldman, Joseph & Sons, Epoxy Products Div., NJ**
(x,y,cc)—Ad p 499
Williamson Adhesives, Inc., Ill (x)

## Ethyl Cellulose

Ace Plastic Co., NY (bb,cc,dd,ee)
Adhesive Products Corp., NY (x)
American Hard Rubber Co., Div. of Amerace Corp., NJ (bb,dd,ee)
American Molding Powder & Chemical Co., NY (y)
American Products Mfg. Co., Inc., La (t)
Anchor Plastics Co., Inc., NY (bb,dd, ee)
Auburn Plastics, Inc., NY (bb,dd,ee)
Bamberger, Claude P., Inc., NJ (y)
Bischoff Chemical Corp., NY (u)
Campco Div., Chicago Molded Products Corp., Ill (t,cc)
Carroll, J.B. Co., Ill (cc)
Coating Products, Inc., NJ (t,cc)
Continental-Diamond Fibre Corp., Del (ee)
Crane Plastics, Inc., Ohio (bb,dd,ee)
CrystalX Corp., Pa (bb,cc,dd,ee)
Davis, Joseph Plastics Co., NJ (t,y, bb,cc,dd,ee)
Denver Plastics, Inc., Colo (u)
Dow Chemical Co., Plastics Div., Mich (p,y,cc)
Dyna-Therm Chemical Corp., Calif (p)
General Plastics Mfg. Co., Wash (bb, cc,dd,ee)
Gering Plastics, Div. of Studebaker-Packard Corp., NJ (y,bb,dd)
Glass Laboratories, NY (bb,dd,ee)
H & R Industries, Pa (bb,cc,dd,ee)
Hercules Powder Co., Inc., Del (p)
Heyden Newport Chemical Corp., American Plastics Corp. Div., NY (bb, cc,dd,ee)
Hydrawlik Co., NJ (bb,dd)
Industrial Plastics Corp., Ind (bb,dd)
K S H Plastics, Inc., Mo (bb,cc,dd)
Lus-Trus Corp., Mich cc)
Muehlstein, H. & Co., Inc., NY (y)
Nixon Nitration Works, NJ (bb,cc)
Omni Products Corp., NY (y,bb,cc)
Perfex Plastics, Inc., Ill (bb,dd,ee)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Pyramid Plastics, Inc., Ill (bb,dd,ee)
Schwab Plastic Corp., Mich (bb,cc,dd, ee)
Simon Products Co., Ill (t)
Southern Plastics Co., SC (bb,cc,dd,ee)
Sunlites Plastics, Inc., Wis (bb,dd,ee)
Superior Plastics, Inc., Ill (bb,ee)
Western Felt Works, Ill (cc)
World Plastics, NY (bb,cc,dd,ee)

## Expanded Metals

Aluminum Co. of America, Pa (a)
Aluminum Specialty Co., Wis (a)
American Metal Products, Inc., Ohio (g)
Atlantic Steel Co., Ga (g)
Avon Tube Div., Higbie Mfg. Co., Mich (g)
Biersach & Niedermeyer Co., Wis (a, b,c,f,g)
Castle, A.M. & Co., Ill (a,g)
Clad-Rex Corp., Ill (a,g)
Colonial Alloys Co., Pa (a)
Designers Metal Corp., Ill (a,b,d,e,f, g,j)
Edgcomb Steel & Aluminum Corp., NJ (a,g)
Ellwood City Iron & Wire Co., Pa (c)
Exmet Corp., NY (a,b,c,d,e,f,g,h,j)
Evans, George Corp., Ill (a)
Flexonics Corp., Ill (g)
Hawkridge Bros. Co., Mass (a)
Haydon Corp., NY (a,g)
Hazledine, E.T. Co., Ind (g)
Houston Blow Pipe & Sheet Metal Works, Tex (g)
Ideal Can Co., Mass (g)
Kees, F.D. Mfg. Co., Neb (g)
Levinson Steel Co., Pa (a,g)
Metal Goods Corp., Mo (g)
North American Cement Co., Designers Metals Div., Ind (a,b,c,f,g,j)
Penn Metal Co., Inc., Mass (a,b,c,d, f,g,h,j)
Republic Steel Corp., Ohio (g)
Reynolds Aluminum Supply Co., Ga (a, g)
Rockwell Engineering Co., Ill (a,b,c,g)
Rolled Alloys, Inc., Mich (f)
Rolock Inc., Conn (f)
Ryerson, Joseph T. & Son, Inc., Ill (a,g)
Standard Metals Corp., Mass (f)
Trenton Pipe Nickel Co., NJ b,g)
Trojan Steel Co., W. Va (g)
U.S. Gypsum Co., Ill (a,g)
Vulcan Rail & Construction Co., NY (g)
Ward, H.H. Co., Pa (g)
Wheeling Corrugating Co., W.Va
Wheeling Steel Corp., W.Va (g)
Whitehead Metal Products Co., Inc., NY (a,f)
Whyte, Oliver Co., Inc., NY (a,g)
Wire & Iron Products, Inc., Mich (f,g)

## Extrusions

(see below; also Impact Extrusions; Tubing)

## Extrusions, Metallic

(excl. Tubing, Pipe)

Accurate Metal Weather Strip Co., Inc., NY (a,b)
Adams Engineering Co., Inc., Fla (a)
Aerolite Extrusion Co., Ohio (a)
Allegheny Ludlum Steel Corp., Pa (g)
Aluminum Co. of America, Pa (a,e)
Aluminum Billets, Inc., Ohio (a)
Aluminum Extrusions, Inc., Mich (a)
American Brass Co., Sub. of Anaconda Co., NY (b)
American Machine & Foundry Co., Cleveland Welding Div., Ohio (g,h)
American Reed Co., Inc., Mass (e)
Ampco Metal, Inc., Wis (b)
Anaconda Aluminum Co., Sub. of Anaconda Co., Ky (a)
Armco Steel Corp., Sheffield Div., Mo (g)
Arvin Industries, Inc., Ind (a)
Atlantic India Rubber Works, Inc., Ill (m)
Atlantic Steel Co., Ga (a)
Auld, D.L. Co., Ohio (a)
B & T Metals Co., Ohio (a)
Babcock & Wilcox Co., Tubular Products Div., Pa (g)
Badger Aluminum Extrusions, NY (a)
Beck, I. & Sons, Inc., NY (a,b)
Belmont Aluminum Extrusion Co., Pa (a)
Benada Aluminum Products Co., Ohio (a)
Beryllium Corp., Pa (b)
Bohn Aluminum & Brass Corp., Mich (a,b)
Bonnell, William L. Co., Inc., Ga (a)
**Bridgeport Brass Co., Conn**
(a,b,h)—Ad p 176
Brinkerhoff Brass & Bronze Works, Inc., NY (a,b)
Bristol Brass Corp., Conn (b)
Bunker Hill Co., Calif (d)
Burgess-Norton Mfg. Co., Ill (c)
Cameron Iron Works, Inc., Special Products Div., Tex (c,f,g,h)
Capitol Products Corp., Pa (a)
Castle, A.M. & Co., Ill (a)
Chase Brass & Copper Co., Sub. of Kennecott Copper Corp., Conn (a,b,f)
Clendenin Bros., Inc., Md (a,b)
Colonial Alloys Co., Pa (a)
Columbia-Geneva Steel Div., U.S. Steel Corp., Calif (g)
Columbus Bolt & Forging Co., Ohio (a,b,g)
Consolidated Fruit Jar Co., NJ (d)
Copper & Brass Sales, Inc., Mich (a, b,e)
Corson Industries, Pa (a)
Craft Mfg. Co., Ill (a,b,c,e,f,g,h,j)
Crane Plastics, Inc., Ohio (k,m)
Crown Metal Co., Wis (d)
Curtiss-Wright Corp., Metals Processing Div., NY (f,g,h)
Cyril Bath Co., Ohio (a,h)
Detroit Gasket & Mfg. Co., Extruded Metals Div., Mich (a)
Division Lead Co., Ill (d)
Dixie Aluminum Corp., Ga (a)
Dixie Bronze Co., Ala (b)
Doehler-Jarvis Div., National Lead Co., Ohio (a)
**Dow Chemical Co., Dow Metal Products Co. Div., Mich**
(e)—Ad pp 408-409
Dresser Mfg. Div., Dresser Industries, Inc., Pa (f,g)
Empire Metal Co., NY (d)
Etched Products Corp., NY (a)
Eureka Electric Products Co., Pa (b)
Fletcher Enamel Co., W. Va (a,b,c,d, e,f)
Flynn, Michael Mfg. Co., Pa (a)
Frasse, Peter A. & Co., Inc., NY (g)
Fromson Orban Co., Inc., NY (a)
Fuller, W.P. & Co., Calif (j)
Garlock Packing Co., NY (k,m)
**General Extrusions, Inc., Ohio**
(a)—Ad p 462
Harper, H. M. Co., Ill (a,b,f,g,h)
Harvey Aluminum, Calif (a,g,h)
Hawkridge Bros. Co., Mass (a)
Himmel Bros. Co., Conn (a)
Hunter Douglas Aluminum Div., Bridgeport Brass Co., Calif (a,b)
International Nickel Co., Inc., NY (f)
**Jarl Extrusions, Inc., NY**
(a)—Ad p 442
Jasco Aluminum Products Co., NY (a)

Jet Specialties Co., Inc., Calif (k)
Jones & Laughlin Steel Corp., Pa (g)
Kaiser Aluminum & Chemical Sales, Inc., Ill (a)
Kassel Export Co., Inc., NJ (g)
Kawneer Co., Mich (a)
Kelsey-Hayes Co., Mich (g)
Kroh Wagner, Ill (a)
Langsenkamp, F.H. Co., Ind (a)
Light Metals Corp., Mich (a)
Magnode Products, Inc., Ohio (a,e)
Metal Goods Corp., Mo (a)
Metal Trims, Inc., Miss (a)
Moczik Tool & Die Works, Mich (a,b)
Monarch Tool & Mfg. Co., Ky (a)
Mueller Brass Co., Mich (a,b)
National Aluminum Co., Ohio (a)
National Lead Co., NY (a,b,d)
National Metal Products Co., Pa (a,b)
National Tube Div., U.S. Steel Corp., Pa (g)
New Jersey Aluminum Extrusion Co., Inc., NJ (a)
Nuclear Metals, Inc., Mass (a,b,c,e, f,g,h)
Olin Mathieson Chemical Corp., Metals Div., NY (a)
Parish Pressed Steel Div., Dana Corp., Pa (g)
Penn Brass & Copper Co., Pa (a)
Penn Extrusion Corp., Pa (a)
Pfister Tubing Corp., NJ (a)
Phelps Dodge Copper Products Corp., NY
Pioneer Aluminum, Inc., Calif (a)
Pittsburgh Plate Glass Co., Pa (a,g)
**Precision Extrusions, Inc., Ill** (a)—Ad p 458
Raybestos-Manhattan, Inc., NJ (k,m)
Republic Metals Co., Inc., NY (d)
Republic Steel Corp., Ohio (g)
Revere Copper & Brass, Inc., NY (a, b)
Reynolds Aluminum Supply Co., Ga (a)
Reynolds Metals Co., Va (a)
Rockwell Engineering Co., Ill (a,b,c,g)
Royce Aluminum Corp., Mass (a)
Ryerson, Joseph T. & Son, Inc., Ill (a,g)
Saramar Aluminum Co., Ohio (a)
Scaife Co., Pa (b,c,f,g)
Scovill Mfg. Co., Conn (b)
Serrick Corp., John Lees Div., Ind (a,g)
Southern Aluminum Finishing Co. Inc., Ga (a)
Southern Extrusions, Inc., Ark (a)
Stainless Metals, Inc., NY (g)
Steel Industries, Inc., Ind (b,g)
Superior Industries, Inc., Ohio (a)
Supplex Co., Div. of Amerace Corp., NJ (k)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (g)
Texas Aluminum Co., Inc., Tex (a)
Textron Metals Co., Ohio (a)
Thompson Products, Inc., Light Metals Div., Ohio (a)
Thompson Products, Inc., Valve Div., Ohio (f,g)
Titan Metal Mfg. Co., Pa (b)
Titanium Metals Corp. of America, NY (h)
Toledo Stamping & Mfg. Co., Ohio (a,g)
Trim Alloys, Inc., Mass (a)
Union Steel Corp., NJ (g)
United Shoe Machinery Corp., Mass (f,g)
U.S. Extrusions Corp., NY (a)
U.S. Steel Corp., Pa (g)
U.S. Steel Supply Div., U.S. Steel Corp., Ill (g)
Universal Converting Corp., Mass (a)
Uniworld Research Corp. of America, Ohio (c)
Vulcan Metal Products, Inc., Ala (a)
Vulcan Rail & Construction Co., NY (a)
Vulcan-Kidd Steel Div., H.K. Porter Co., Inc., Pa (g)
W.F. Mfg. Co., Calif (a)
Warner Mfg. Corp., NJ (a)
**Werner, R.D. Co., Pa** (a)—Ad p 437
Wesbar Stamping Corp., Wis (a,b,c,g)
White Metal Rolling & Stamping Corp., NY (a,e)
Whitehead Metal Products Co., Inc., NY (a)
Wolverine Tube Div., Calumet & Hecla, Inc., Mich (a)
Worcester Pressed Steel Co., Mass (a, g)
Youngstown Mfg., Inc., Ohio (a)

## Extrusions, Nonmetallic

(excl. Tubing, Pipe)

Ace Plastic Co., NY (k)
Allegheny Plastics, Inc., Pa (k)
Allied Resinous Products, Inc., Ohio (k)
Amco Plastic Pipe Co., Calif (k)
American Agile Corp., Ohio (k)
American Hard Rubber Co., Div. of Amerace Corp., NJ (k,l,m)
American Molding Co., Calif (k)
American Plastics Corp., NY (k)
Anchor Plastics Co., Inc., NY (k)
Anesite Co., Ill (l)
Atlas Mineral Products Co., Pa (k)
**Auburn Mfg. Co., Conn** (k,m)—Ad p 450
Auburn Plastics, Inc., NY (k,m)
Automotive Rubber Co., Inc., Mich (m)
Beck, I. & Sons, Inc., NY (m)
Bond International, Inc., Mich (m)
Borden Co., Borden Chemical Div., NY (k)
Bowling Green Rubber Co., Ohio (m)
Brown Rubber Co., Inc., Ind (m)
Button Corp. of America, NJ (k)
Byers, A.M. Co., Pa (k)
Cadillac Plastic & Chemical Co., Mich (k)
Cambridge-Panelyte Molded Plastics Co., Div. of St. Regis Paper Co., Ohio (k)
Campco Div., Chicago Molded Products Corp., Ill (k)
Canfield, H.O. Co., va
Carlon Products Corp., Ohio (k)
Carolina Industrial Plastics Div., Essex Wire Corp., NC (k)
Cellupiastic Corp., NJ (k)
Chardon Rubber Co., Ohio (k)
Colonial Plastics Mfg. Co., Div. of Van Dorn Iron Works Co., Ohio (k)
**Conneaut Rubber & Plastics Co., Div. of U.S. Stoneware Co., Ohio** (k,m)—Ad p 447
Connecticut Hard Rubber Co., Conn (m)
Continental Rubber Works, Pa (m)
Contour Extrusion Co., NY (k)
**Crane Plastics, Inc., Ohio** (k,m)—Ad p 464
Crescent Plastics, Inc., Ind (k)
Davis, Joseph Plastics Co., NJ (k)
Detroit Macoid Corp., Mich (k,m)
Dryden Rubber Div., Sheller Mfg. Co., Ill (m)
Eclipse Plastic Industries, Inc., Fla (k)
Electric Autolite Co., Ohio (k)
Eljay Corp., Md (l)
Enflo Corp., NJ (l)
Extruders, Inc., Calif (k)
Faultless Rubber Co., Ohio (m)
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (m)
Frost Rubber Co., Ill (m)
Fry Plastics International, Calif (k)
Galigher Co., Utah (k)
Garlock Packing Co., NY (k,m)
Geauga Industries Co., Ohio (k,m)
General American Transportation Corp., Ill (k)
General American Transportation Corp., Plastics Div., Ill (k)
General Electric Co., Chemical & Metallurgical Div., Ill (k)
General Gasket, Inc., Conn (m)
General Plastics Corp., Ind (k)
Gering Plastics, Div. of Studebaker-Packard Corp., NJ (k)
Gilman Bros. Co., Conn (k)
Glass Laboratories, Inc., NY (k)
Glass Reinforced Plastics Corp., Ohio (l)
Glastic Corp., Ohio (l)
Goodrich, B.F. Industrial Products Co., Ohio (k)
Gossett and Hill Co., Ill (k)
Gotham Plastics Corp., NY (k)
H & R Industries, Pa (k,m)
Hall Mfg. Co., NJ (k)
Hartwell, H.N. & Sons, Inc., Mass (k)
Haveg Industries, Inc., Del (l)
Hawkeye Rubber Mfg. Co., Iowa (m)
Hitemp Wires, Inc., NY (k)
Hungerford Plastics Corp., NJ (k,m)
Hydrawlik Co., NJ (k,m)
Industrial Plastics Corp., Ind (k)
Industrial Products Div., General Tire & Rubber Co., Ind (k)
Insulation Mfrs. Corp., Ill (k)
Irvington Varnish & Insulation Div., Minnesota Mining & Mfg. Co., NJ (k)
Jet Specialties Co., Inc., Calif (k)
Johnson Plastic Corp., Ohio (k,m)
Johnson Rubber Co., Ohio (m)
Jordan-Rogers Co., Calif (k)
Joymont Plastics, Inc., Ohio (k)
Judsen Rubber Works, Inc., Ill (m)
K S H Plastics, Inc., Mo (k)
Kaykor Industries, Inc., NJ (k)
Keystone Plastics, Inc., NJ (k)
Kraloy Plastic Pipe Co., Inc., Calif (k)
Lavelle Rubber Co., Ill (m)
Luminous Resins, Inc., Ill (k)
Lus-Trus Corp., Mich (k)
Luzerne Rubber Co., NJ (k,l)
Madin Plastics Inc., NJ (k)
Maloney, F.H. Co., Tex (k,m)
Martin Rubber Co., Inc., NJ (m)
Mayon Plastics, Minn (k)
Mechanical Rubber Products Co., NY (l)
Meyer, J. & Sons, Inc., Pa (k)
Mid-States Rubber Products, Inc., Ind (m)
Midwest Plastic Products Co., Ill (k)
Minnesota Rubber Co., Minn (m)
Minnesota Rubber & Gasket Co., Minn (m)
Moldex, NY (m)
Moore, Samuel & Co., Ohio (k)
**Moxness Products, Inc., Wis** (m)—Ad p 460
**Mueller Brass Co., Mich** (k)—Ad p 455
Multiple Extrusions, Inc., Minn (m)
Munray Products Div., Fanner Mfg. Co., Ohio (k)
National Gasket & Washer Mfg. Co., Inc., NY (k,l,m)
National Lock Co., Ill (k)
National Vulcanized Fibre Co., Del (k)
New England Tape Co., Div. of United-Carr Fastener Corp., Mass (k)
Panelyte Div., St. Regis Paper Co., NJ (k)
Parker, Stearns & Co., Inc., NY (m)
Pawling Rubber Corp., NY (k,l)
Pennsylvania Fluorocarbon Co., Inc., Pa (k)
Perfex Plastics, Inc., Ill (k,m)
Pipco International Corp., Sub. of Plastiglide Mfg. Corp., Calif (k)
Plastex Co., Ohio (k)
Plastic Engineering, Inc., Ohio (k)
Plastic Packaging Co., Ill (k)
Plastiglide Mfg. Corp., Calif (k)
Plymouth Cordage Co., Mass (k)
Polyform Plastics Corp., NY (k)
Polygon Plastic Co., Ind (l)
Polymer Corp. of Pennsylvania, Sub. of Polymer Corp., Pa (k)
Polyplastic Products, Inc., NJ (k)
Prince Rubber & Plastics Co., Inc., NY (k,l)
Pyramid Plastics, Inc., Ill (k)
Raybestos-Manhattan, Inc., NJ (l,m)
Reliance Plastic & Chemical Corp., NJ (k)
Resistoflex Corp., NJ (k)
Rogers Corp., Conn (m)
Rowland Products, Inc., Conn (k)
Schaefer-Hausner Corp., NY (k)
Schwab Plastic Corp., Mich (k,m)
Seamless Rubber Co., Conn (m)
Shamban, W.S. & Co., Ind (k)
Sheffield Plastics Co., Mass (k)
Sheller Mfg. Corp., Mich (k,l,m)
Sierra Engineering Co., Calif (m)
Southern Plastics Co., SC (k,m)
Sparta Mfg. Co., Div. of U.S. Ceramic Tile Co., Ohio (k)
Stalwart Rubber Co., Ohio (m)
Standard Products Co., Mich (m)
Stockwell Rubber Co., Inc., Pa (k,m)
Sun Rubber Co., Ohio (m)
Sunlites Plastics, Inc., Wis (k)
Superior Plastics, Inc., Ill (k)
Supplex Co., Div. of American Hard Rubber Co., NJ (k,m)
Taunton Div., Haveg Industries, Inc., Mass (k,m)
Technical Specialties Co., NY (m)
Textron Metals Co., Ohio (k)
Thermoid Div., H.K. Porter Co., Pa (k,m)
Thombert, Inc., Iowa (k)

### KEY

**MATERIALS**

a—Aluminum and its alloys
b—Copper and its alloys
c—Iron and its alloys (except steel)
d—Lead and its alloys
e—Magnesium and its alloys
f—Nickel and its alloys
g—Steels
h—Titanium and its alloys
j—Zinc and its alloys
k—Thermoplastics
l—Thermosetting plastics
m—Elastomers

**BASIC FORMS**

n—Anodes
o—Bar
p—Base resins, polymers or gums
q—Billets
r—Custom formed parts (incl. specialties)
s—Fibers
t—Film
u—Foams (component materials or products)
v—Foil
w—Ingot
x—Laminating, casting resins
y—Molding compounds
z—Plate
aa—Powder
bb—Rod
cc—Sheet
dd—Strip
ee—Tubing
ff—Wire

**Tri-Point Mfg. & Developing Co., NY (k)**
**United Shoe Machinery Corp., Mass (k,m)**
U.S. Gasket Plastics Div., Garlock Packing Co., NJ (k,l)
**U.S. Rubber Co., Mechanical Goods Div., Ind (k)**
**U.S. Stoneware Co., Ohio (k,l,m)**
**Victory Plastics Co., Mass (k)**
**Vogt Mfg. Co., NY (k)**
**Vulcanized Rubber & Plastics Co., Pa (m)**
Western Felt Works, Ill (l,m)
**Western Plastics Corp., Neb (k)**
Western Textile Products Co., Mo (k,m)
**Westlake Plastics Co., Pa (k)**
William Brand-Rex Div., American Enka Corp., Mass (k)
**Williams - Bowman Rubber Co., Ill** (k,l)—Ad p 276
World Plastics, NY (k)
Yale Rubber Mfg. Co., Mich (m)
**Yardley Plastics Co., Ohio** (k)—Ad p 466

## Fabrics, Nonwoven Synthetic

Albany Felt Co., NY
**American Felt Co., Conn** —Ad p 312
Beckmann, Inc., NY
Booth Felt Co., Inc., NY
Cadillac Plastic & Chemical Co., Mich
Carborundum Co., Refractories Div., NJ
Chicopee Mills, Inc., NY
Chicopee Mills, Inc., Lumite Div., NY
**Continental Felt Co., NY** —Ad p 322
Dexter, C.H. & Sons, Inc., Conn
Electrofilm Inc., Calif
**Felters Co., Mass** —Ad p 310
Ferro Corp., Fiber Glass Div., Tenn
Filpaco Industries, Inc., Ill
Foss Mfg. Co., Id
Gustin-Bacon Mfg. Co., Mo
Kendall Co., Fiber Products Div., Mass
Masland Duraleather Co., Pa
National Felt Co., Mass
Noone Industrial Fabrics Div., Kenwood Mills, NY
Quaker City Felt Co., Pa
Russell Mfg. Co., Conn
Snyder, M.L. & Son, Inc., Pa
Star Woolen Co., NY
Stevens, J.P. & Co., Inc., NY
Tallman-McCluskey Fabrics Co., Mo
**Troy Blanket Mills, NY** —Ad p 327
U.S. Plywood Corp., NY
Wellington Sears Co., NY
Wood Conversion Co., Minn

## Fabrics, Woven

(coated)

Albany Felt Co., NY
Aldan Rubber Co., Pa
Alpha Wire Corp., NY
Andrews-Alderfer Div., Kendall Co., Ohio
Cadillac Plastic & Chemical Co., Mich
Chicago-Allis Mfg. Corp., Ill
Chicopee Mills, Inc., Lumite Div., NY
Connecticut Hard Rubber Co., Conn
Continental-Diamond Fibre Corp., Del
**Cordo Chemical Corp., Conn** —Ad p 269
**du Pont de Nemours, E.I. & Co., Inc., Del** —Ad p 315
**Fabricon Products Div., Eagle-Picher Co., Mich** —Ad p 275
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass
Flexible Tubing Corp., Minn
Foss Mfg. Co., Id
General Asbestos Gasket Mfg. Corp., Mo
General Plastics Corp., NJ
Goodrich, B.F. Industrial Products Co., Ohio
Kaufman Glass Co., Del
Narmco Industries, Inc., Narmco Materials Div., Calif
National Gasket & Washer Mfg. Co., Inc., NY
Prince Rubbber & Plastic Products Co., Inc., NY
**Reeves Bros., Inc., Vulcan Rubber Products Div., NY** —Ad p 318
Russell Mfg. Co., Conn
**Sparta Mfg. Co., Div. of U.S. Ceramic Tile Co., Ohio**
Twitchell, E.W., Inc., Pa
Wasco Products, Inc., Mass
Wisconsin Gasket & Mfg. Co., Wis

## Fabrics, Woven

(uncoated)

Aetna Felt Co., Inc., NY
Albany Felt Co., NY
Alox Mfg Co., Mo
Alpha Wire Corp., NY
Atlantic Bag Co., NY
Booth Felt Co., Inc., NY
Cadillac Plastic & Chemical Co., Mich
Chicopee Mills, Inc., Lumite Div., NY
Electrofilm, Inc., Calif
Ferro Corp., Fiber Glass Div., Tenn
Filpaco Industries, Inc., Ill
Foss Mfg. Co., Id
Franklin Cotton Mill Co., Ohio
General Asbestos Gasket Mfg. Corp., Mo
Kendall Co., Fiber Products Div., Mass
National Gasket & Washer Mfg. Co., Inc., NY
Noone Industrial Fabrics Div., Kenwood Mills, NY
Russell Mfg Co., Conn
Sherwatt Equipment & Mfg. Co., Inc., NY
Stevens, J.P. & Co., Inc., NY
Supreme Industrial Products Co., Ill
Tallman-McCluskey Fabrics Co., Mo
Thompson, H.I. Fiber Glass Co., Calif
Turner Halsey Co., NY
Twitchell, E.W., Inc., Pa
U.S. Rubber Co., NY
U.S. Rubber Co., Textile Div., NY
Vulcan Rubber Products Div., Reeves Bros., Inc., NY
Wellington Sears Co., NY

## Fasteners

(see Mechanical Fasteners)

## Felts, Synthetic

(see Fabrics, Nonwoven)

## Felts, Wool

Aetna Felt Co., Inc., NY
Albany Felt Co., NY
**American Felt Co., Conn** —Ad p 312
Armstrong Cork Co., Pa
Artex Felt Co., NY
Auburn Mfg. Co., Conn
Bacon Felt Co., Mass
Beckmann, Inc., NY
Booth Felt Co., Inc., NY
Boston Felt Co., Mass
Carey, Philip Mfg. Co., Ohio
Central Felt & Fabrics Corp., NY
Coated Abrasive Products, Inc., Ohio
**Continental Felt Co., NY** —Ad p 322
**Felters Co., Mass** —Ad p 310
Fidelity Felt & Mfg. Co., NY
Filpaco Industries, Inc., Ill
General Gasket, Inc., Conn
Hall, C P. Co., NY
Johns-Manville Corp., NY
Mechanical Felt & Textiles Co., NJ
National Felt Co., Mass
National Gasket & Washer Mfg. Co., Inc., NY
Noone Industrial Fabrics Div., Kenwood Mills, NY
Quaker City Felt Co., Pa
Reynolds Aluminum Supply Co., Ga
Standard Asbestos Mfg. Co., Ill
Standard Felt Co., Calif
Supreme Industrial Products Co., Ill
Wellington Sears Co., NY
Western Felt Works, Ill
Wisconsin Gasket & Mfg. Co., Wis
Wood Conversion Co., Minn

## Ferrites

(see Ceramics)

## Fibers, Synthetic

(see specific polymer)

## Filler Metals, Welding

(electrodes, rods, etc.)

Abalon Precision Mfg. Corp., NY
Acme Stamping & Wire Forming Co., Pa
Alloy Rods Co., Pa
All-State Welding Alloys Co., Inc., NY
Alofs Mfg. Co., Mich
American Brass Co., Sub. of Anaconda Co., NY
American Manganese Steel Div., American Brake Shoe Co., Ill
American Products Corp., Ill
Ampco Metal, Inc., Wis
Arcos Corp., Pa
Atlas Foundry Co., Ohio
**Bridgeport Brass Co., Conn** —Ad p 176
Champion Rivet Co., Ohio
Crucible Steel Co. of America, Pa
Dana Corp., Auburn Div., Ind
Electric Steel Foundry Co., Ore
Electronic Parts Mfg. Co., Inc., NJ
Eutectic Welding Alloys Corp., NY
General Dynamics Corp., Liquid Carbonic Div., Ill
Harnischfeger Corp., Wis
Hayden Wire Works, Inc., Mass
Haynes Stellite Co., Div. of Union Carbide Corp., Ind
Ideal Can Co., Mass
Ingersoll Products Div., Borg-Warner Corp., Ill
International Nickel Co., Inc., NY
Jervis Corp., Mich
Johnson, A. & Co., Inc., NY
K S M Products, Inc., NJ
Kaiser Aluminum & Chemical Sales, Inc., Ill
Lincoln Electric Co., Ohio
Linde Co., Div. of Union Carbide Corp., NY
Lukens Steel Co., Pa
Magnesium Co. of America, Ind
Magnesium Products of Milwaukee, Inc., Wis
Magnesium Elektron, Inc., NY
Manganese Steel Forge Co., Pa
Marquette Mfg. Co., Inc., Minn
McDowell Mfg. Co., Pa
Metal Goods Corp., Mo
Metal & Thermit Corp., NJ
Midwest Stamping & Mfg. Co., Ohio
Morrisville Foundry Co., Inc., Vt
Narragansett Boiler Works, Inc., RI
Noland Tank & Galvanizing Co., Tenn
Page Steel & Wire Div., American Chain & Cable Co., Pa
Rockwell Engineering Co., Ill
Somerset Foundry & Machine Co., Pa
Southern Metal Products Co., La
Titan Metal Mfg. Co., Pa
Victor Equipment Co., Calif
**Waimet Alloys Co., Mich** —Ad p 82
Wall Colmonoy Corp., Stainless Process Div., Mich
Waterman Industries, Inc., Calif
Wesbar Stamping Corp., Wis
Whitehead Metal Products Co., Inc., NY

## Film

(see specific plastic or rubber)

## Fluorocarbon Plastics

aaRBee Plastic Co., Calif (y)
Acme Resin Corp., Ill (p)
Allegheny Plastics, Inc., Pa (bb,cc,dd,ee)
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY (y)
Auburn Plastic Engineering, Ill (t,bb,cc,dd,ee)
Automotive Rubber Co., Inc., Mich (y,cc)
Bamberger, Claude P., Inc., NJ (y)
Belding Corticelli Industries, NY (y)
Cadillac Plastic & Chemical Co., Mich (t,bb,cc,dd,ee)
Chemical Coatings and Engineering Co., Inc., Pa (x)
Chicago Gasket Co., Ill (t,bb,cc,dd,ee)
Colonial Kolonite Co., Ill (bb,cc,dd,ee)
Corsco Plastics, Inc., NY (bb,cc,dd,ee)
Commercial Plastics & Supply Corp., NY (bb,cc,dd,ee)
Conneaut Rubber and Plastics Co., Div. of U.S. Stoneware Co., Ohio (bb,cc,dd,ee)
Continental-Diamond Fibre Corp., Del (bb,cc,dd,ee)
Cosmo Plastics Co., Ohio (u)
Crane Packing Co., Ill (t,bb,cc,dd,ee)
CrystalX Corp., Pa (t,bb,cc,dd,ee)
Curbell, Inc., NY (bb,cc,dd,ee)
**Dixon Corp., RI** (y,bb,cc,dd,ee)—Ad p 434
Dodge Fibers Corp., NY (s,t,cc,dd)
du Pont de Nemours, E.I. & Co., Inc., Del (p,s,t,y)
Electro Chemical Engineering & Mfg. Co., Pa (t,cc)
Enflo Corp., NJ (t,bb,cc,dd,ee)
Fluorocarbon Co., Calif (p,t,bb,cc,dd,ee)
Fluoro-Plastics, Inc., Div. of Flexrock Co., Pa (bb,cc,dd,ee)
Galigher Co., Utah (bb,cc,dd,ee)
Garlock Packing Co., NY (y,bb,cc,dd,ee)
General Gasket, Inc., Conn (t,cc)
General Plastics Corp., NJ (t,x)
General Plastics Mfg. Co., Wash (bb,cc,dd,ee)
H & R Industries, Pa (bb,cc,dd,ee)
Halogen Insulator & Seal Corp., Ill (bb,cc,dd,ee)
Haveg Industries, Inc., Del (bb,cc,ee)
Hitemp Wires, Inc., NY (ee)
Insulation Mfrs. Corp., Ill (t,bb,cc,dd,ee)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Kurz Kasch, Inc., Ohio (y)
Maloney, F.H. Co., Tex (y)
Minnesota Mining & Mfg. Co., Minn (y)
Minnesota Mining and Mfg. Co., Chemical Div., Minn (p,y)
Norrich Plastics Corp., NY (bb,ee)
Pennsylvania Fluorocarbon Co., Inc., Pa (bb)
Permacel, NJ (t,cc,ee)
**Polymer Corp. of Pennsylvania, Sub. of Polymer Corp., Pa** (t,bb,cc,dd,ee)—Ad p 230
Prince Rubber & Plastics Co., Inc., NY (bb,cc,ee)
Radiation Applications, Inc., NY (bb,cc,dd,ff)
**Raybestos - Manhattan, Inc., Plastics Products Div., Pa** (bb,cc,ee)—Ad p 268
Resistoflex Corp., NJ (bb,cc,ee)
Russell Mfg. Co., Conn (s)
Sanford Plastics Corp., NY (bb,ee)

Shamban, W.S. & Co., Calif (p,t,x, y,bb,cc,dd,ee)
Sparta Mfg. Co., Div. of U.S. Ceramic Tile Co., Ohio (t,y,bb,cc,dd,ee)
Staver Co., Inc., NY (cc,dd)
Thombert, Inc., Iowa (bb,cc,dd,ee)
Tri-Point Mfg. & Developing Co., NY (bb)
U.S. Gasket Plastics Div., Garlock Packing Co., NJ (t,bb,cc,dd,ee)
U.S. Stoneware Co., Ohio (ee)
Vulcan Rubber Products Div., Reeves Bros. Inc., NY (bb,dd,ee)
Westlake Plastics Co., Pa (t,y,bb,cc, dd,ee)

## Fluorocarbon Rubber

(fluoroelastomers)

Automotive Rubber Co., Inc., Mich (cc,dd)
Belko Corp., Md (y)
Bond International, Inc., Mich (y,ee)
Castle Rubber Co., Pa (y,bb,cc,dd,ee)
Chemical Coatings and Engineering Co., Pa (x,y)
Chicago-Allis Mfg. Corp., Ill (p)
**Colonial Rubber Co., Div. of U.S. Stoneware Co., Ohio** (y,cc,dd)—Ad p 441
Connecticut Hard Rubber Co., Conn (cc,dd)
Continental Rubber Works, Pa (bb,cc, dd,ee)
Dayton Rubber Co., Ohio (y,bb,cc,dd,ee)
Dodge Fibers Corp., NY (s,t,cc,dd)
Dow Corning Corp., Mich (p)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (y,ee)
du Pont de Nemours, E.I. & Co., Inc., Del (cc)
Electro Chemical Engineering & Mfg. Co., Pa (t,cc)
Flexible Tubing Corp., Conn (ee)
Garlock Packing Co., NY (y,cc)
Hitemp Wires, Inc., NY (ee)
Hooker Chemical Corp., NY (p)
Johns-Manville Corp., Dutch Brand Div. NY (cc)
Maloney, F.H. Co., Tex (y)
Minnesota Mining & Mfg. Co., Minn (p)
Minnesota Mining and Mfg. Co., Chemical Div., Minn (p,y)
**Moxness Products, Inc., Wis** (cc)—Ad p 460
Norrich Plastics Corp., NY (bb,dd,ee)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
**Rogers Corp., Conn** (u,y)—Ad p 261
Russell Mfg. Co., Conn (s)
Trostel, Albert Packing, Ltd., Wis (y)
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (p,y,cc)
Western Felt Co., Ill (y,cc,dd,ee)
Westlake Plastics Co., Pa (bb,cc,dd)

## Foams

(see specific plastic or rubber)

## Foil

(see specific metal)

## Forgings

(see also Cold Headed Parts)

Abegg & Reinhold Co., Calif (g)
Accurate Brass Corp., NY (b)
Albert Pipe Supply Co., Inc., NY (c,g)
Alco Products, Inc., NY (g)
Allegheny Ludlum Steel Corp., Pa (g)
Aluminium Ltd. Sales, Inc., NY (a)
**Aluminum Co. of America, Pa** (a,e)—Ad pp 423-424
Amalgamated Steel Corp., Ohio (g)
American Brass Co., Sub. of Anaconda Co., NY (b)
American Car & Foundry Div., ACF Industries, Inc., NY (g)
American Chain & Cable Co., Pa (g)
American Forge & Mfg. Co., Pa (g)
American Manganese Bronze Co., Pa (b)
American Metal Products Co., Mich (a,g)
American Steel Foundries, Ill (g)
Amforge Div., American Brake Shoe Co., Ill (a,g)
Ampco Metal, Inc., Wis (b)
Anti-Corrosive Metal Products Co., Inc., NY (g)
Armco Steel Corp., Sheffield Div., Mo (g)
Atlas Drop Forge Co., Mich (f,g,h)
Auld, D.L. Co., Ohio (a)
Avins Industrial Products Corp., NY (b)
Baldt Anchor, Chain & Forge Div., Boston Metals Co., Pa (a,b,g)
Baldwin-Lima-Hamilton Corp., Pa (g,h)
Bay City Forge Co., Pa (g)
Bethlehem Steel Co., Pa (g)
Billings & Spencer Co., Conn (a,b,g,h)
Bingham Herbrand Corp., Herbrand Div., Ohio (g)
Blakeslee Forging Co., Conn (a,b,c,d, f,g,h)
Bohn Aluminum & Brass Corp., Mich (a,b)
Braeburn Alloy Steel Corp., Pa (g)
Brewer-Titchener Corp., NY (a,g)
**Bridgeport Brass Co., Conn** (a,b,f)—Ad p 176
Bristol Brass Corp., Conn (b)
California Drop Forge Co., Calif (g,h)
**Cameron Iron Works, Inc., Special Products Div., Tex** (c,f,g,h)—Ad p 439
Canton Forge & Axle Works, Poor & Co., Ohio (f,g)
Carbo Tool & Die Co., Ohio (c,f)
Carpenter Steel Co., Pa (g)
Champion Rivet Co., Ohio (b,c,g)
Chase Brass & Copper Co., Sub. of Kennecott Copper Corp., Conn (a,b)
Chicago Extruded Metals Co., Ill (b)
Cincinnati Forging Co., Ohio (b)
Clapp, E.D. Mfg. Co., Inc., NY (b,c, f,g)
Cleveland Cap Screw Co., Ohio (a,b, f,g,h)
Cleveland City Forge Co., Ohio (a, c,f,g,h)
Colonial Steel Div., Vanadium-Alloys Steel Co., Pa (g)
Columbia-Geneva Steel Div., U.S. Steel Corp., Calif (g)
Columbus Bolt & Forging Co., Ohio (g)
Commercial Shearing & Stamping Co., Ohio (g)
Composite Forgings, Inc., Mich (g)
Consolidated Industries Inc., Conn (a, b,e,f,g,h)
Copper & Brass Sales, Inc., Mich (a,b)
Cored Forging Div., Bridgeport Brass Co., Conn (a,b)
Crucible Steel Co. of America, Pa (c,f,g)
Crucible Steel Co. of America, Titanium and Vacuum Metals Product Div., Pa (b,c,f,g,h)
Curtiss-Wright Corp., Metals Processing Div., NY (a,b,f,g)
Custom Tool and Mfg. Co., Minn (c,f, g,h)
Cyril Bath Co., Ohio (a,g)
Dirilyte Co. of America, Inc., Ind (a,b,e)
Doehler-Jarvis Div., National Lead Co., Ohio (a)
Edgcomb Steel & Aluminum Corp., NJ (g)
Edgewater Steel Co., Pa (g,h)
Electric Autolite Co., Ohio (c)
Electric Materials Co., Pa (b)
Electric Steel Foundry Co., Ore (f,g)
Endicott Forging & Mfg. Co., Inc., NY (b,f,g,h)
Eureka Electric Products Co., Pa (a, b,g)
Fairmount Tool & Forging, Inc., Sub. of Houdaille Industries, Inc., Ohio (g)
Finkl, A. & Sons Co., Ill (g)
Frasse, Peter A. & Co., Inc., NY (a,g)
Fromson Orban Co., Inc., NY (a)
Garden State Forge Co., NJ (a,b,c,f, g,h)
General Drop Forge Corp., NY (g)
Giant Grip Mfg. Co., Wis (a,g,h)
Greene, G.G. Corp., Pa (g)
Harrisburg Steel Co., NY (g)
Harvey Aluminum, Calif (a,e,g)
Heppenstall Co., Pa (g,h)
Hobbs, Clinton E. Co., Mass (c,g)
Hunter-Douglas Aluminum Div., Bridgeport Brass Co., Calif (a,b)
Huron Forge & Machine Co., Mich (a,b,g)
Illinois Forge, Inc., Ill (g)
Illinois Iron & Bolt Co., Ill (g)
Indiana Forge & Machine Co., Ind (g)
Interstate Drop Forge Co., Wis (f,g)
Irwin-Sensenich Corp., Pa (g)
Isaacson Iron Works, Wash (g)
Janney Cylinder Co., Pa (b)
Jessop Steel Co., Pa (g)
**Kaiser Aluminum & Chemical Sales, Inc., Ill** (a)—Ad p 419
Kelsey-Hayes Co., Mich (g,h)
Keystone Forging Co., Pa (g)
Kovar, John R. Mfg. Co., Inc., Minn (g)
Kropp Forge Co., Ill (g,h)
Ladish Co., Wis (a,b,c,e,f,g,h)
Larson, Charles E. & Sons, Inc., Ill (a,b,c,g)
Larson Tool & Stamping Co., Mass (a,b,c,e,f,g,h,j)
Latrobe Steel Co., Pa (g)
**Lenape Hydraulic Pressing & Forging Co., Pa** (a,b,g)—Ad p 462
Lindell Drop Forge Co., Mich (g)
Machinery Forging Co., Ohio (g)
Mallory, P.R. & Co., Inc., Ind (b)
Manganese Steel Forge Co., Pa (g)
McCarter Iron Works, Inc., Pa (g)
McInnes Steel Co., Pa (f,g,h)
McNally Pittsburg Mfg. Co., Kan (g)
Melling Forging Co., Mich (f)
Midvale-Heppenstall Co., Pa (c,f,g)
Milwaukee Forge & Machine Co., Wis (g)
Montague Machine Co., Mass (g)
Moore Dry Dock Co., Calif (g)
**Mueller Brass Co., Mich** (a,b)—Ad p 455
Murray, A.B. Co., Inc., NJ (a,b,f,g)
Murray Tube Works, Inc., NJ (a,b,g)
National Forge & Ordnance Co., Pa (g)
National Lead Co., NY (a,b,h)
National Supply Co., Pa (g)
National Tube Div., U.S. Steel Corp., Pa, (g)
Nurenross, C.S. & Sons Co., Ill (g)
Ohio Forge & Machine Corp., Ohio (c,f,g)
Olderman Mfg. Corp., Conn (b)
Olds Alloys Co., Calif (b)
Pacific States Steel Corp., Calif (g)
Park Drop Forge Co., Ohio (g)
Pattin Mfg. Co., Ohio (g)
Pencoyd Steel & Forge Corp., Pa (c,g)
Peninsular Steel Co., Mich (g)
Pettibone Mulliken Corp., Ill (g)
Philadelphia Bronze & Brass Corp., Pa (a,b,f,h)
Phoenix Mfg. Co., Ill (g)
Pittsburgh Forgings Co., Pa (a,f,g)
Porter, H.K., Inc., Mass (g)
Porter, H.K., Inc., Forge & Fittings Div., Ohio (a,g)
Rankin Forge Co., Pa (c,g)
Republic Steel Corp., Ohio (g)
Revere Copper & Brass, Inc., NY (a,b)
**Rhode Island Tool Co., RI** (a,b,c,f,g)—Ad p 450
Rockford Bolt & Steel Co., Ill (g)
Rockwell Engineering Co., Ill (a,b,c,g)
Rome Mfg. Div., Revere Copper & Brass, Inc., NY (a,b)
Ryerson, Joseph T. & Son, Inc., Ill (a,g)
St. Pierre Chain Corp., Mass (a,f,g)
Scovill Mfg. Co., Mill Products Div., Conn (a,b)
Seltzer, George H. & Co., Pa (g)
Sherman & Reilly, Inc., Tenn (a,g)
Skookum Co., Inc., Ore (g)
Smith-Armstrong Forge, Inc., Ohio (g)
Standard Forge & Axle Co., Inc., Ala (g)
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa (g)
Star Heel Plate Co., Inc., NJ (g)
Steel, R. & Sons, Inc., NY (f,g)
Steel Improvement and Forge Co., Ohio (a,g)
Struthers Wells Corp., NY (f,g)
Taylor Forge & Pipe Works, Ill (a,c, f,g,h)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (g)
Thompson Products, Inc., Valve Div., Ohio (f,g)
Titan Metal Mfg. Co., Pa (a,b)
Tool & Mfg. Co., Inc., Pa (g)
Transue & Williams Steel Forging Corp., Ohio (b,c,f,g,h)
Tube Turns, Div. of Chemetron Corp., Ky (a,b,c,e,f,g,h)
Union Forging Co., NY (g)
United Forge Co., Mich (c,g)
United Shoe Machinery Corp., Mass (a)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

U.S. Steel Corp., Pa (g)
Universal-Cyclops Steel Corp., Pa (f,g
Uniworld Research Corp. of America Ohio (c)
Vanadium-Alloys Steel Co., Pa (g)
Vulcan-Kidd Steel Div., H.K. Porter Co., Inc., Pa (g)
Walker Forge, Inc., Wis (g)
Weatherhead Co., Ind (a,b,g,h)
Weber-Knapp Co., NY (a)
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (a,b,c,f,g,h)
Wilcox Forging Corp., Pa. (e,f,g,h)
Wilde Drop Forge & Tool Co., Inc., Mo (g)
Wilde Tool Co., Inc., Kan (g)
Williams, J.H. & Co., NY (a,b,e,f,g,h)
Wyman-Gordon Co., Mass (a,e,f,g,h)
Zeller Corp., Ohio (g)
Ziv Steel & Wire Co., Ill (g)

## Forsterite

(see Ceramics)

## Furanes

Adhesive Products Corp., NY (x)
Alcylite Plastics & Chemical Corp., Calif (p)
Atlas Mineral Products Co., Pa (p,x)
Durez Plastics Div., Hooker Chemical Corp., NY (p)
Electro Chemical Engineering & Mfg. Co., Pa (cc)
Foss Mfg. Co., Id (x)
Furane Plastics, Inc., Calif (p,x)
Haveg Industries, Inc., Del (p,bb,cc,ee)
Knight, Maurice A., Ohio (p,x)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Reichhold Chemicals, Inc., NY (p)
U.S. Stoneware Co., Ohio (y)

## Galvanized Metals

(see Precoated Metals)

## Galvanizers

Acme Galvanizing Co., Calif
Advance Galvanizing Co., Calif
Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich
American Smelting & Refining Co., NY
American Tinning & Galvanizing Co., Pa
Armco Steel Corp., Ohio
Armor Galvanizing Works, Inc., Calif
Atlantic Steel Co., Ga
Atlas Galvanizing Co., Calif
Bessemer Galvanizing Works, Ala
Bethlehem Steel Co., Pa
Boyles Galvanizing & Plating Co., Tex
Buffalo Steel Corp., NY
Byers, A.M. Co., Pa
Clayton & Lambert Mfg. Co., Ky
Clifton Conduit Corp., Md
Columbian Steel Tank Co., Mo
Continental-Emsco Co., Calif
Debevoise Co., NY
Designers Metal Corp., Ill
Detroit Brass & Malleable Co., Mich
Dow Chemical Co., Tex
Empire Metal Co., NY
Enterprise Galvanizing Co., Pa
Fanner Mfg. Co., Ohio
Farrelloy Co., Pa
Fenestra, Inc., Mich
General Chain & Mfg. Corp., Ohio
Green-Walker Galvanizing Co., Inc., La
Gregory, Thomas Galvanizing Works, NY
Hanlon-Gregory Galvanizing Co., Pa
Haywiik Galvanizing, Inc., La
Hill, James Mfg. Co., RI
Illinois Edison Porcelain Div., McGraw-Edison Co., Ill
Independent Galvanizing Co., NJ
Joslyn Mfg. & Supply Co., Ill
Joslyn Pacific Co., Calif
Kent County Galvanizing Co., RI
Kinkead Industries, Inc., Ill
Kobel, W.R. Sheet Metal Products, Utah
Koven, L.O. & Bro., Inc., NJ
Lawson, F.H. Co., Ohio
Lehigh Structural Steel Co., Pa
Lewis Bolt & Nut Co., Minn
Line Material Industries, McGraw-Edison Co., Pa
Los Angeles Galvanizing Co., Calif
Malleable Iron Fittings Co., Conn
Maze, W.H. Co., Ill
Metal Coating Corp., Ill
Metallizing Co. of Los Angeles, Inc., Calif
Metalplate Co., Inc., Ala
Missouri Rolling Mill Corp., Miss
National Galvanizing Co., Pa
National Gasket & Washer Mfg. Co., Inc., NY
New Jersey Zinc Co., NY
Noland Tank & Galvanizing Co,, Tenn
Northwestern Steel & Wire Co., Ill
Nowery J. Smith Bolt & Supply Co., Tex
Nylok Corp., NJ
Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa
Penn Metal Co., Inc., W.Va
Pittsburgh Steel Co., Pa
Pratt, William E. Foundry Div., Joslyn Mfg. & Supply Co., Ill
Promat Div., Poor & Co., Ill
Reed & Prince Mfg. Co., Mass
Republic Steel Corp., Ohio
Riverside Foundry & Galvanizing Co., Mich
Roebling's, John A. Sons Div., Colorado Fuel & Iron Corp., NJ
Rohnco, Inc., Ill
Ryerson, Joseph T. & Son, Inc., Ill
San Francisco Galvanizing Works, Calif
Sawhill Tubular Products, Inc., Pa
Scaife Co., Pa
Schlueter Mfg. Co., Mo
Sealube Co., Mass
Sharon Steel Corp., Pa
Sherman & Reilly, Inc., Tenn
Smith, N.J. Bolt Co., Tex
Southern Galvanizing Co., Md
Southern Metal Products Co., La
Spencer Nahm Co., Calif
Spring City Foundry Co., Pa
Stevens, Frederic B., Inc., Mich
Superior-Pacific Galvanizing Co., Calif
Trenton Pipe Nipple Co., NJ
WLS Stamping Co., Ohio
Wessels Co., Mich
Wilcox-Crittenden Div., North & Judd Mfg. Co., Conn
Witt Cornice Co., Galvanizing Div., Ohio
Wood, John Co., Ill
Worcester Wire Works Div., National-Standard Co., Mass
Young & Greenawalt, Ind

## Germanium

African Metals Corp., NY (w)
American Metal Climax, Inc., NY (o,w,aa)
American Zinc Sales Co., Mo (q)
Belmont Smelting & Refining Works, Inc., NY (aa)
Eagle-Picher Co., Ohio (w,aa)
Hardy, Charles, Inc., NY (aa)
New Jersey Metals Co., NJ (o)
Parker Metal Goods Co., Mass (bb)
Sylvania Electric Products, Inc., Chemical & Metallurgical Div., Pa (w)
Ullmann, Inc., Wis (o,ee)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)

## Glass, Alumino-Silicate

Bassichis Co., Ohio (aa)
Bausch & Lomb Optical Co., NY (r)
Bird, Richard H. Co. Inc., Mass (r)
**Corning Glass Works, NY** (r,aa,bb,ee)—Ad p 319
Fischer & Porter Co., Pa (r)
Kaufman Glass Co., Del (z,bb,cc,ee)
Kimble Glass Co., Sub. of Owens-Illinois Glass Co., Ohio (r,aa,bb,ee)
**Kopp Glass, Inc., Pa** (r)—Ad p 309
Lancaster Glass Corp., Ohio (r)
Pittsburgh Plate Glass Co., Pa (s)
Russell Mfg. Co., Conn (r,s)

## Glass, Borosilicate

Anchor Hocking Glass Corp., Ohio (r)
Applied Instruments, Inc., NY (z,bb,cc,ee)
Bassichis Co., Ohio (aa)
Bausch & Lomb Optical Co., NY (r)
Bird, Richard H. Co., Mass (r)
**Corning Glass Works, NY** (r,z,aa,bb,cc,ee)—Ad p 319
Fischer & Porter Co., Pa (r)
Fish-Schurman Corp., NY (r)
Friedrich & Dimmock, Inc., NJ (r,s)
Gustin-Bacon Mfg. Co., Mo (r,s)
Johns-Manville Corp., NY (s)
Kaufman Glass Co., Del (z,bb,cc,ee)
Kimble Glass Co., Sub. of Owens-Illinois Glass Co., Ohio (r,aa,bb,ee)
**Kopp Glass, Inc., Pa** (r)—Ad p 309
Lancaster Glass Corp., Ohio (r)
Mansol Ceramics Co., NJ (r,aa)
Marsco Mfg. Co., Ill (r)
Modiglass Fibers, Inc., NJ (s)
Penberthy Instrument Co., Wash (r)
Pittsburgh Corning Corp., Pa (u)
Pittsburgh Plate Glass Co., Pa (s)
Pittsburgh Plate Glass Co., Fiber Glass Div., Pa (s)
Russell Mfg. Co., Conn (s)
Semon Bache & Co., NY (z,cc,ee)
Shull Bros. Glass Co., NJ (r,ee)
Thompson, H.I. Fiber Glass Co., Calif (s)

## Glass, Lead Alkali Silicate

Bassichis Co., Ohio (aa)
Bausch & Lamb Optical Co., NY (r)
**Corning Glass Works, NY** (r,aa,bb,ee)—Ad p 319
Fischer & Porter Co., Pa (r)
Kaufman Glass Co., Del (z,bb,cc,ee)
Kimble Glass Co., Sub. of Owens-Illinois Glass Co., Ohio (r,aa,bb,ee)
**Kopp Glass, Inc., Pa** (r)—Ad p 309
Lancaster Glass Corp., Ohio (r)
Mansol Ceramics Co., NJ (r,aa)
Pemberthy Instrument Co., Wash (r,z)
Semon Bache & Co., NY (z,cc,ee)

## Glass, 96% Silica

Aerojet-General Corp., Structural Materials Div., Calif (r,u)
Amersil Quartz Div., Engelhard Industries, Inc., NJ (s,z,aa,bb,cc,ee)
Applied Instruments, Inc., NY (z,cc,ee)
Bassichis Co., Ohio (aa)
Bausch & Lomb Optical Co., NY (r)
**Corning Glass Works, NY** (r,z,aa,bb,cc,ee)—Ad p 319
Fischer & Porter Co., Pa (r)
Johns-Manville Corp., NY (s)
Kaufman Glass Co., Del (z,bb,cc,ee)
Marsco Mfg. Co., Ill (r)
Russell Mfg. Co., Conn (r,s)
Saunders, Alexander & Co., Inc., NY (aa)
Thompson, H.I. Fiber Glass Co., Calif (s)

## Glass, Silica

Aerojet-General Corp., Structural Materials Div., Calif (r,u)
Applied Instruments, Inc., NY (z,cc,ee)
Bassichis Co., Ohio (aa)
Bausch & Lomb Optical Co., NY (r)
**Corning Glass Works, NY** (r,aa,cc)—Ad p 319
Fischer & Porter Co., Pa (r)
Friedrich & Dimmock, Inc., NJ (r)
Johns-Manville Corp., NY (s)
Kaufman Glass Co., Del (z,bb,cc,ee)
McGean Chemical Co., Ohio
Modiglass Fibers, Inc., NJ (s)
Pittsburgh Corning Corp., Pa (u)
Pyrosil, Inc., Ohio (r,z,aa,bb,cc,ee)
Semon Bache & Co., NY (z,cc,ee)
Thermal American Fused Quartz Co., NJ (r,z,bb,cc,ee)
Thompson, H.I. Fiber Glass Co., Calif (s)

## Glass, Soda-Lime

Anchor Hocking Glass Co., Ohio (r)
Applied Instruments, Inc., NY (z,bb,cc,ee)
Bassichis Co., Ohio (aa)
Bausch & Lomb Optical Co., NY (r,s)
**Corning Glass Works, NY** (r,aa,bb,ee)—Ad p 319
Erie Scientific Corp., NY (cc)
Fischer & Porter Co., Pa (r)
Friedrich & Dimmock, Inc., NJ (r,s,bb,ee)
Kaufman Glass Co., Del (z,bb,cc,ee)
Kimble Glass Co., Sub. of Owens-Illinois Glass Co., Ohio (r,aa,bb,ee)
**Kopp Glass, Inc., Pa** (r)—Ad p 309
Lancaster Glass Corp., Ohio (r)
Mansol Ceramics Co., NJ (r,aa)
Modiglass Fibers, Inc., NJ (s)
Pittsburgh Plate Glass Co., Pa (z,cc)
Semon Bache & Co., NY (z,cc,ee)
Shull Bros. Glass Corp., NJ (r,bb,ee)
Thompson, H.I. Fiber Glass Co., Calif (s)

## Glass Coatings

(see Inorganic Coatings)

## Glass for Plastics Reinforcement

American Polyglas Corp., NJ
Bassichis Co., Ohio
Coast Mfg. & Supply Co., Calif
Electrofilm, Inc., Calif
Exeter Mfg. Co., NY
Ferro Corp., Ohio
**Ferro Corp., Fiber Glass Div., Tenn** —Ad p 321
Flexfirm Products, Calif
Foss Mfg. Co., Id
General Plastics Corp., NJ
Glass Textiles Div., Johns-Manville Corp., Ohio
Miller-Stephenson Chemical Co., Inc., Conn
Modiglass Fibers, Inc., NJ
Owens-Corning Fiberglas Corp., Ohio
**Pittsburgh Plate Glass Co., Fiber Glass Div., Pa** —Ad p 311
Pyrosil, Inc., Ohio
Ren Plastics, Inc., Mich
Rezolin, Inc., Calif
Riegel Paper Corp., NY
Russell Mfg. Co., Conn
Standard Insulation Co., Plastics Div., NJ
Stevens, J.P. & Co., Inc., NY
Tallman-McCluskey Fabrics Co., Mo
Thompson, H.I. Fiber Glass Co., Calif
Union Carbide Metals Co., Div. of Union Carbide Corp., NY

## Gold and Its Alloys

Advance Stamping Co., Mich (dd)
Alpha Metals, Inc., NJ (t)
American Metal Climax, Inc., NY (w,aa)
American Platinum & Silver Div., Engelhard Industries, Inc., NY (n,o,v,z,bb,cc,dd,ee,ff)

American Platinum Works, NJ (z)
American Silver Co., NY (v,dd,ee,ff)
American Smelting & Refining Co., NY (o)
Anaconda Co., NY (o)
Anchor Metal Co., Inc., NY (w)
Baker & Co., Inc., NJ (n,o,v,w,z,bb,cc,dd)
Bart Mfg. Corp., NJ (aa)
Bishop, J. & Co. Platinum Works, Pa (v,ee,ff)
Composite Industrial Metals, Inc., RI (p)
Deringer Metallurgical Corp., Ill (cc,dd,ee,ff)
Eastern Smelting & Refining Corp., Mass (n,o,v,w,z,aa,bb,cc,dd,ee,ff)
Goldsmith Bros. Div., National Lead Co., Ill (n,o,v,w,z,aa,bb,cc,dd,ff)
Hagstoz, T.B. & Son, Pa (n,cc,dd,ff)
Handy & Harman, NY (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Hanovia Chemical & Mfg. Co., NJ (aa)
Hardy, Charles, Inc., NY (aa)
Hastings & Co., Inc., Pa (v)
Hayden Wire Works, Inc., Mass (ff)
Horton-Angell Co., Mass (n,o,bb,cc,dd,ee,ff)
Improved Seamless Wire Co., RI (bb,cc,dd,ee,ff)
Lakeland Industries, Minn (z)
Leach & Garner Co., Industrial Div., Mass (n,o,v,z,bb,cc,dd,ee,ff)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (n,o,v,z,bb,dd,ee,ff)
Metals Disintegrating Co., Inc., NJ (aa)
Metz Refining Co., NJ (n,o,q,z,aa,bb,cc,dd,ee,ff)
Nesor Alloy Products Co., NJ (dd,ff)
Ney, J.M. Co., Industrial Div., Conn (v,z,bb,cc,dd,ee,ff)
Norwalk Powdered Metals, Inc., Conn (aa)
Peerless Roll Leaf Co., Div. of Howe Sound Co., NJ (v,dd)
Riegel Paper Corp., NY
**Sel-Rex Corp., NJ** (n,aa)—Ad p 356
Standard Metals Corp., Mass (n,o,v,z,bb,cc,dd,ee,ff)
**Technic, Inc., RI** (aa)—Ad p 352
Texas Instruments, Inc., Metals & Controls Div., Mass (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Western Gold & Platinum Co., Sub. of Wilbur B. Driver Co., Calif (aa,cc,dd,ff)
Wildberg Bros. Smelting & Refining Co., Calif (n,o,v,w,z,aa,bb,cc,dd,ff)
Williams Gold Refining Co., Inc., NY (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)

## Graphite

(see Carbon)

## Gray Iron

(see Iron)

## GR-S Rubber

(see Styrene-Butadiene Rubber)

## Hard Facing Alloys

Air Reduction Sales Co., Div. of Air Reduction Co., Inc., NY
Alloy Rods Co., Pa
Alloy Surfaces Co., Inc., Del
All-State Welding Alloys Co., Inc., NY
American Brake Shoe Co., NY
American Manganese Steel Div., American Brake Shoe Co., Ill
American Smelting & Refining Co., NY
Champion Rivet Co., Ohio
Cleveland Hard Facing Co., Inc., Ohio
Crucible Steel Co. of America, Pa
Electric Steel Foundry Co., Ore
Fansteel Metallurgical Corp., Ill
General Electric Co., NY
Harnischfeger Corp., Wis
Hayden Wire Works, Inc., Mass
Haynes Stellite Co., Div. of Union Carbide Corp., Ind
Hobart Bros. Co., Ohio
Janney Cylinder Co., Pa
Kennametal, Inc., Pa
Kinkead Industries, Inc., Ill
Lincoln Electric Co., Ohio
Lincoln Iron Works, Vt
Linde Co., Div. of Union Carbide Corp., NY
Marquette Mfg. Co., Inc., Minn
McKay Co., Pa
Metal Finishers, Inc., Md
Metal & Thermit Corp., NJ
Metal-Cladding, Inc., NY
Metallizing Co. of Los Angeles Inc., Calif
Metallizing Engineering Co., Inc., NY
Moore Drydock Co., Calif
Morrisville Foundry Co., Inc., Vt
Overmyer Mould Co., Inc., Ind
Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa
Republic Steel Corp., Ohio
Sommer Metalcraft Corp., Ind
Stevens, Frederic B., Inc., Mich
Stoody Co., Calif
Tiarco Corp., NJ
Uniworld Research Corp. of America, Ohio
Vanadium-Alloys Steel Co., Pa
Victor Equipment Co., Calif
Wall Colmonoy Corp., Stainless Process Div., Mich

## Hard Surfaces for Metals

(see Diffusion Coatings; Hard Facing Alloys)

## High Pressure Laminates

(see Laminates)

## Hot Melt Coatings

(see Organic Coatings)

## Hypalon

(see Chlorosulfonated Polyethylene Rubber)

## Immersion Coatings, Chemical

(Incl. Electroless)

Allied Research Products, Inc., Md
Amchem Products, Inc., Pa
Automotive Rubber Co., Inc., Mich
Biddle Screw Products Co., Ind
Birchwood Chemical Co., Minn
Carboline Co., Mo
Chemical Development Corp., Mass
Dollin Corp., NJ
Electro Chemical Engineering & Mfg. Co., Pa
Engineering Products & Specialties, Inc., RI
Hughson Chemical Co., Div. of Lord Mfg. Co., Pa
Industrial Chromium Corp., Mass
Jervis Corp., Mich
**Kanigen Div., General American Transportation Corp., Ill** —Ad p 355
Lewco, Ohio
Lithcote Corp., Ill
MacDermid, Inc., Conn
Magnesium Co. of America, Ind
Marlane Development Co., Inc., NY
Merix Chemical Co., Ill
Metal Finishers, Inc., Md
Metal & Thermit Corp., NJ
Metal-Cladding, Inc., NY
Mitchell-Bradford Chemical Co., Conn
Modern Plating Corp., Ill
National Lock Co., Ill
Neilson Chemical Co., Mich
Nylok Corp., NJ
Octagon Process, Inc., NY
Parker Rust Proof Co., Mich
Plume & Atwood Mfg. Co., Conn
Promat Div., Poor & Co., Ill
Reynolds Chemical Products Co., Mich
Rustproofing & Metal Finishing Corp., Mass
St. Eloi Corp., Ohio
Stevens, Frederic B., Inc., Mich
Tuff Clad, Inc., Ohio
Turco Products, Inc., Calif
Union Carbide Metals Co., Div. of Union Carbide Corp., NY
WLS Stamping Co., Ohio
Wright Metalcoaters, NJ

## Impact Extrusions

(cold extrusions)

Allied Products Corp., Mich (g)
Almco Steel Products Corp., Ind (b,g)
**Aluminum Co. of America, Pa** (a)—Ad pp 423-424
Bridgeport Brass Co., Conn (a)
Cliff Mfg. Co., Ohio (a)
Curtiss-Wright Corp., NY (g)
Cyril Bath Co., Ohio (g)
Division Lead Co., Ill (d)
Dow Chemical Co., Dow Metal Products Co. Div. Mich (e)
Fletcher Enamel Co., W.Va (a,b,c,d,e,f)
Fromson Orban Co., Inc., NY (a)
Harvey Aluminum, Calif (a)
Heintz Mfg. Co., Pa (g)
Hunter-Douglas Aluminum Div., Bridgeport Brass Co., Calif (a)
Impact Extrusions, Inc., Ind (a)
Impax, Inc., Mo (a,b,e,j)
Jervis Corp., Mich (a)
Ladish Co., Wis (a,b,c,e,f,g,h)
Leake Engineering Co., Mich (a,b,d,g)
Magline, Inc., Mich (e)
Magnesium Co. of America, Ind (a,e)
**Mueller Brass Co., Mich** (a,b,g)—Ad p 455
National Impacted Metal Corp., Miss (a,b,e,j)
Republic Steel Corp., Ohio (g)
Rockwell-Standard Corp., Stamping Div., NY (a,g)
Rome Mfg. Div., Revere Copper & Brass, Inc., NY (a,b)
Sherman & Reilly, Inc., Tenn (e,f,g)
Sun Tube Corp., NJ (a,b,e)
Thompson Products, Light Metals Div., Ohio (a)
Townsend Co., Engineered Fasteners Div., Pa (a,b,g)
United Shoe Machinery Corp., Mass (a)
Westinghouse Electric Corp., Materials Mfg. Corp., Pa (b,f,g)
Wirz, A.H., Inc., Pa (a,b,d,j)
Worcester Pressed Steel Co., Mass (a)

## Impregnated or Compressed Wood

(see Wood)

## Impregnation Coatings

(see Organic Coatings)

## Indium and Its Alloys

Alpha Metals, Inc., NJ (o,q,t,w,bb,cc,dd)
American Silver Co., NY (v,dd,ee,ff)
American Smelting & Refining Co., NY (n,o,q,v,w,bb,cc,dd,ff)
Anaconda Co., NY (aa)
Belmont Smelting & Refining Works, Inc., NY (o)
**Cerro de Pasco Sales Corp., NY** (o,w)—Ad p 178
Division Lead Co., Ill (o,v,cc,ff)
Empire Metal Co., NY (n,o,q,w,bb,ff)
Federated Metals Div., American Smelting and Refining Co., NY (o,q,v,w,bb,cc,dd,ff)
Glidden Co., Chemical Divs., Metals Dept., Ind (aa)
Goldsmith Bros. Div., National Lead Co., Ill (o,q)
Handy & Harman, NY (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Hardy, Charles, Inc. NY (aa)
**Indium Corp. of America, NY** (n,o,q,v,w,z,aa,bb,cc,dd,ff) — Ad p 172
International Minerals and Metals Corp., NY (w)
Kelsey-Hayes Co., Utica Metals Div., NY (w)
Nesor Alloy Products Co., NJ (dd,ff)
**Sel-Rex Corp., NJ** (aa)—Ad p 356
Texas Instruments, Inc., Metals & Controls Div., Mass (dd)
United Refining & Smelting Co., Ill (n,o,q,w,z,bb,cc,dd,ff)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Western Gold & Platinum Co., Sub. of Wilbur B. Driver Co., Calif (dd, ff)
Williams Gold Refining Co., Inc., NY (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)

## Ingots

(see specific metal)

## Injection Moldings

(see Moldings)

## Inorganic Coatings, Ceramic

(formulations)

Bisonite Co. Inc., NY
California Metal Enameling Co., Calif
Centralab Div., Globe Union, Inc., Wis
Chicago Vitreous Corp., Div. of Eagle-Picher Co., Ill
Continental Coatings Corp., Ohio
Cooley, W.J. & Co., Tenn
Dennis Chemical Co., Mo
Douglas & Sturgess, Calif
du Pont de Nemours, E.I. & Co., Inc., Del
Dyna-Therm Chemical Corp., Calif
Earl Paint Corp., NY
Electrolizing Co., Ill
France, J.H. Refractories Co., Pa
Harshaw Chemical Co., Ohio
Hayden Wire Works, Inc., Mass
Hitemp Wires, Inc., NY
Hommel, O Co., Pa
Ingram-Richardson, Inc., Ind
Kraus Research Labs, Md
Laboratory Equipment Corp., Mich
Linde Co., Div. of Union Carbide Corp., NY
Lithium Corp. of America Inc., Minn
Metal & Thermit Corp., NJ
Metallizing Engineering Co., Inc., NY
**Norton Co., Mass**
—Ad p 348
Refractory & Insulation Corp., NY
Sauereisen Cements Co., Pa
Solar Aircraft Co., Calif
Thermal Refractories Corp., NJ
Zirconium Corp. of America, Ohio
Zophar Mill, Inc., NY

## Inorganic Coatings, Ceramic

(coaters)

American Emblem Co., Inc., NY
Bevan Co., Calif
Bisonite Co., Inc., NY
Brooks & Perkins, Inc., Mich
California Metal Enameling Co., Calif
Centralab Div., Globe Union Inc., Wis
Continental Coatings Corp., Ohio
Cooley, W.J. & Co., Tenn
Dyna-Therm Chemical Corp., Calif
Electrofilm, Inc., Calif
Electrolizing Co., Ill
Emerson & Cuming, Inc., Mass
Enamel Products Co., Ohio
Erie Ceramic Arts Co., Pa
Fletcher Enamel Co., W.Va
Galigher Co., Utah
Hayden Wire Works, Inc., Mass
Ingram-Richardson, Inc., Ind
Lancaster Glass Corp., Ohio
Linde Co., Div. of Union Carbide Corp., NY
Metal-Cladding, Inc., NY
Metallizing Co. of Los Angeles, Inc., Calif
Metaplast Process, Inc., NY
**Norton Co., Mass**
—Ad p 348
Russell Mfg. Co., Conn
St. Eloi Corp., Ohio
Solar Aircraft Co., Calif
**Swedlow, Inc., Calif**
—Ad p 263
Sylvester & Co., Ohio
Union Carbide Metals Co., Div. of Union Carbide Corp., NY
Zirconium Corp. of America, Ohio

## Inorganic Coatings, Porcelain or Glass

(formulations)

American Metal Products Co., Mich
Bettinger Corp., Mass
California Metal Enameling Co., Calif
Chemical Coatings and Engineering Co., Pa
Chicago Vitreous Corp., Div. of Eagle-Picher Co., Ill
Dennis Chemical Co., Mo
Du-Co Ceramics Co., Pa
du Pont de Nemours, E.I. & Co., Inc., Del
Dyna-Therm Chemical Corp., Calif
Erie Ceramic Arts Co., Pa
Ferro Corp., Ohio
Harshaw Chemical Co., Ohio
Hitemp Wires, Inc., NY
Hommel, O. Co., Pa
Independence Stove & Mfg. Co., Mo
Ingram-Richardson, Inc., Ind
Lithium Corp. of America Inc., Minn
Metal-Cladding Inc., NY
Pemco Corp., Md
Pierce & Stevens Chemical Corp., NY
Sauereisen Cements Co., Pa
Wyandotte Chemicals Corp., Mich

## Inorganic Coatings, Porcelain or Glass

(enamelers)

AllianceWall Div., AllianceWare, Inc., Ohio
American Valve & Enameling Corp., Ind
Applied Instruments, Inc., NY
Barrows Porcelain Enamel Corp., Ohio
Bettinger Corp., Mass
Bevan Co., Calif
California Metal Enameling Co., Calif
Cleveland Porcelain Enameling Co., Ohio
Emerson & Cuming, Inc., Mass
Enamel Products Co., Ohio
Erie Ceramic Arts Co., Pa
Erie Enameling Co., Pa
Ervite Co., Pa
Ferro Enameling Co., Calif
Fletcher Enamel Co., W.Va
Geuder, Paeschke & Frey Co., Wis
Heintz Mfg. Co., Pa
Independence Stove & Mfg. Co., Mo
Ingersoll Products Div., Borg-Warner Corp., Ill
Ingram-Richardson, Inc., Ind
Ingram-Richardson Mfg. Co., Pa
Kawneer Co., Mich
Lansdale Porcelain Enamel Corp., Pa
Metal & Thermit Corp., NJ
Metal-Cladding, Inc., NY
Monarch Aluminum Mfg. Co., Ohio
National Metal Products Co., Pa
Penn Fibre & Specialty Co., Inc., Pa
Philadelphia Enameling Works, Inc., Pa
Pittsburgh Plate Glass Co., Pa
Porcelain Enamel Finishers, Ill
Smith, A.O. Corp., Wis
Smoot-Holman Co., Calif
Southwestern Porcelain Steel Corp., Okla
**Swedlow, Inc., Calif**
—Ad p 263
Temco, Inc., Tenn
Vollrath Co., Wis

## Inorganic Fibers

(except Asbestos, Ceramic, Glass, Carbon; see these categories)

Allied Chemical Corp., Plastics & Coal Chemicals Div., NY
Baldwin-Ehret-Hill, Inc., NJ
Carborundum Co., NY
Carey, Philip Mfg. Co., Ohio
Celotex Corp., Ill
Chemore Corp., NY
Eagle-Picher Co., Ohio
Electrofilm Inc., Calif
Gustin-Bacon Mfg. Co., Mo
Johns-Manville Corp., NY
Modiglass Fibers, Inc., NJ
Standard Asbestos Mfg. Co., Ill
Thermal Refractories Corp., NJ
Union Carbide Metals Co., Div. of Union Carbide Corp., NY

## Intermetallic Compounds

(see Ceramics; Refractories)

## Investment Castings

(see castings)

## Iron, Alloy

(castings)

Acme Foundry & Machine Co., Okla
Adirondack Steel Casting Co., NY
Advance Foundry Co., Ohio
Albion Malleable Iron Co., Mich
Alloy Precision Castings Co., Ohio
Almont Mfg. Co., Mich
Alten Foundry & Machine Works, Inc., Ohio
American Brake Shoe Co., NY
American Cast Iron Pipe Co., Ala
American Foundries Co., Mich
Apex Foundry, Inc., Mich
Apex Steel Corp., Ltd., Calif
Arzt, T.L. Foundry Co., Ill
Atlantic Foundry Co., Ohio
Banner Iron Works, Mo
Barber Iron Work, Inc., La
Bay City Foundry Co., Mich
Beaver Valley Alloy Foundry Co., Pa
Belle City Malleable Iron, Racine Steel Castings Co., Wis
Beloit Foundry Co., Ill
Bethlehem Steel Co., Pa
Bierman-Everett Foundry Co., NJ
Bignall Co., NY
Bonnot Co., Ohio
Brom Machine & Foundry Co., Minn
Butler Engine & Foundry Co., Inc., Pa
Cadillac Malleable Iron Co., Mich
Calumet Div., Calumet & Hecla, Inc., Mich
Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich
Carondelet Foundry Co., Mo
Casting Service Corp. of Michigan Mich
Chambersburg Engineering Co., Pa
Chemung Foundry Corp., NY
Chicago Hardware Foundry Co., Ill
Cleveland Foundry & Mfg. Co., Inc., Tenn
Crawford & Doherty Foundry Co., Ore
Curtiss-Wright Corp., NY
Dalton Foundries, Inc., Ind
Darling Valve & Mfg. Co., Pa
Dayton Foundry, Calif
Deuscher, H.P. Co., Ohio
Duriron Co., Inc., Ohio
Ehrsam, J.B. & Sons Mfg. Co., Kan
Electric Steel Foundry Co., Ore
Electron Corp., Colo
Elk Engineering Works, Inc., Pa
Elkhart Iron Works, Mich
Engineered Castings Div., American Brake Shoe Co., NY
Enterprise Wheel & Car Corp., Va
Florence Pipe Foundry & Machine Co., NJ
Flynn & Emrich Co., Md
Forest City Foundries Co., Ohio
Frederick Iron & Steel, Inc., Md
Fremont Casting Co., Mass
G. & C. Foundry Co., Ohio
Gale Mfg. Co., Mich
General Electric Co., Foundry Dept., NY
Gillett & Eaton, Inc., Minn
Goslin Birmingham Mfg. Co., Inc., Ala
Grafton Foundry Co., Wis
Grede Foundries, Inc., Wis
Green Bay Foundry & Machine Works, Wis
Greenlee Foundry Co., Ill
Grimm Foundry Co., Inc., NJ
Gunite Foundries Corp., Ill
H & H Foundry Machine Co., Pa
Hamilton Foundry & Machine Co., Ohio
Hansell-Elcock, Ill
Helmick Foundry-Machine Co., W.Va
Hewitt, John Foundry Co., NJ
Howard Foundry Co., Ill
Irwin-Sensenich Corp., Pa
Janney Cylinder Co., Pa
Keen Foundry Co., Inc., Ind
Kingsport Foundry & Mfg. Corp., Tenn
Kolcast Industries Div., Thompson Products, Inc., Ohio
Kramer Bros Foundry Co., Ohio
Kutztown Foundry & Machine Corp., Pa
Lake Erie Foundry Co., NY
Lang-Scharmann & Co., Wis
Lawton, C.A. Co., Wis
Liberty Foundry Co., Mo
Lincoln Foundry Corp., Calif
Link-Belt Co., Ill
Littlestown Hardware & Foundry Co., Inc., Pa
Lodi Iron Works, Inc., Calif
Long Beach Iron Works, Calif
Macaulay, H.C. Foundry Co., Calif
Mackintosh-Hemphill Div., E.W. Bliss Co., Pa
Manufacturers Iron Foundry, Inc., Conn
McLanahan & Stone Corp., Pa
**Meehanite Metal Corp., NY**
—Ad p 461
Mercast Mfg. Corp., Calif
Metropolitan Iron Foundry, NY
Midwestern Foundries, Inc., Ind
Montague Machine Co., Mass
National Malleable & Steel Castings Co., Ohio
Neenah Foundry Co., Wis
North Wales Foundry Co., Inc., Pa
Oak Hill Foundry & Machine Works, Ohio
Oakland Foundry & Machine Co., Mich
Oil City Iron Works, Tex
Overmyer Mould Co., Inc., Ind
Parker-Street Castings Co., Ohio
Perkins, Henry Co., Mass
Pittsburgh Foundry & Machine Co., Pa
Pohiman Foundry Co., Inc., NY
Posey Iron Works, Inc., Pa
Potts, C. & G. & Co., Ind
Prescott Co., Mich
Pusey & Jones Corp., Del
Quaker Alloy Casting Co., Pa
Republic Steel Corp., Ohio
Richmond Foundry & Mfg. Co., Inc., Va
Ridge Foundry, Calif
Riverside Foundry & Galvanizing Co., Mich
Rosedale Foundry & Machine Co., Pa
Ross-Meehan Foundries, Tenn
Ryerson, Joseph T. & Son, Inc., Ill
St. Marys Foundry Co., Ohio
Schaefer-Goodnow Foundries, Inc., Pa
Schneider, Bowman Co., Inc., Pa
Scudder, E.J. Foundry & Machine Co., NJ
Shakopee Foundry Co., Minn
Shartle Div., Black-Clawson Co., Ohio
Sheffield Foundry Co., Ill
Shenango Furnace Co., Centrifugally Cast Products Div., Ohio
Sibley Machine & Foundry Corp., Ind
Sioux City Foundry & Boiler Co., Iowa
Sonith Foundries Div., Food Machinery & Chemical Corp., Ind
Sorbo-Mat Process Engineers, Mo

Sparta Foundry Div., Muskegon Piston Ring Co., Mich
Springfield Foundry Co., Mass
Spuck Iron & Foundry Co., Mo
Star Heel Plate Co., Inc., NJ
Stuart Foundry Co., Mich
Superior Foundry, Inc., Ohio
Taylor & Co., Inc., NY
Taylor & Boggis Foundry, Ohio
Taylor-Wharton Co., Div. of Harsco Corp., NJ
Texas Foundries, Inc., Tex
Tower Grove Foundry, Mo
Union Iron Works, Wash
United Shoe Machinery Corp., Mass
U.S. Pipe & Foundry Co., Ala
Uniworld Research Corp. of America, Ohio
Valley Iron Works, Minn
Wall Colmonoy Corp., Stainless Process Div., Mich
Washington Iron Works, Wash
Waterman Industries, Inc., Calif
West Point Foundry & Machine Co., Div. of Batson-Cook Co., Ga
Zenith Foundry Co., Wis

## Iron, Gray

(castings)

ACF Industries, Inc., NY
Acco Steel Casting Div., American Chain & Cable Co., Inc., Pa
Acme Foundry & Machine Co., Kan
Acme Foundry & Machine Co., Okla
Advance Foundry Co., Ohio
Albert Lea Foundry-Queen Products Div., King-Seeley Corp., Minn
Allegheny Foundry Co., Pa
Allis-Chalmers Mfg. Co., Wis
Alloy Precision Castings Co., Ohio
Almont Mfg. Co., Mich
Alten Foundry & Machine Works, Inc., Ohio
American Brake Shoe Co., NY
American Cast Iron Pipe Co., Ala
American Foundries Co., Mich
American Foundry Co., Inc., Ind
American Laundry Machinery Co., NY
Apex Foundry, Inc., Mich
Apex Steel Corp., Ltd., Calif
Appleton Electric Co., Ill
Arneson Foundry Co., Wis
Arzt, T.L. Foundry Co., Ill
Atlantic Foundry Co., Ohio
Atlas Foundry Co., Ohio
Atlas Foundry & Mfg. Co., Calif
Auburn Foundry, Inc., Ind
Avco Mfg. Corp., New Idea Div., NY
Banner Iron Works, Mo
Barber Iron Works Inc., La
Barnett Foundry & Machine Co., NJ
Bay City Foundry Co., Mich
Becker, L.A. Foundry Co., Mo
Bellaire Stove Co., Ohio
Belle City Malleable Iron, Racine Steel Castings Co., Wis
Beloit Foundry Co., Ill
Bethlehem Steel Co., Pa
Bierman-Everett Foundry Co., NJ
Bignall Co., NY
Black-Clawson Co., Ohio
Bond, Charles Co., Pa
Bonnot Co., Ohio
Brake Shoe & Castings Div., American Brake Shoe Co., NY
Bruce Foundry and Mfg. Co., Mich
Butler Engine & Foundry Co., Inc., Pa
Calumet Div., Calumet & Hecla, Inc., Mich
Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich
Carondelet Foundry Co., Mo
Casting Service Corp. of Michigan, Mich
Central Specialty Div., King-Seeley Corp., Mich
Chambersburg Engineering Co., Pa.
Chemung Foundry Corp., NY
Chicago Hardware Foundry Co., Ill
Cincinnati Foundry Co., Ohio
Cleveland Foundry & Mfg. Co., Inc., Tenn
Columbiana Pump Co., Ohio
Compton Foundry, Calif
Continental Gin Co., Ala
Cooper-Bessemer Corp., Ohio
Crawford & Doherty Foundry Co., Ore
Dalton Foundries, Inc., Ind
Dana Corp., Auburn Div., Ind
Darling Valve & Mfg. Co., Pa
Dayton Malleable Iron Co., Ohio
Decatur Casting Co., Ind
De Laval Steam Turbine Co., NJ
Detroit Brass & Malleable Co., Mich
Deuscher, H.P. Co., Ohio
Dexter Foundry Div., Philco Corp., Iowa
Dodge Mfg. Co., Ind
Dostal Foundry & Machine Co., Mich
Eaton Mfg. Co., Foundry Div., Mich
Ehrsam, J.B. & Sons Mfg. Co., Kan
Electron Corp., Colo
Elk Engineering Works, Inc., Pa
Elkhart Foundry & Machine Co., Inc., Ind
Elkhart Iron Works, Mich
Empire Pattern and Foundry Co., Okla
Engineered Castings Div., American Brake Shoe Co., NY
Enterprise Wheel & Car Corp., Va
Fearon Foundry Co., Ill
Florence Pipe Foundry & Machine Co., NJ
Florin Foundry & Mfg. Co., Pa
Flynn & Emrich Co., Md
Forest City Foundries Co., Ohio
Frederick Iron & Steel, Inc., Md
Fremont Casting Co., Mass
Fulton Foundry & Machine Co., Inc., Ohio
G. & C. Foundry Co., Ohio
Gale Mfg. Co., Mich
Gartland-Haswell Foundry, Inc., Ohio
General Electric Co., Foundry Dept., NY
General Foundry & Mfg. Co., Mich
General Iron Works Co., Colo
General Motors Corp., Central Foundry Div., Mich
Georgia Iron Works, Ga
Gillett & Eaton, Inc., Minn
Glamorgan Pipe & Foundry Co., Va
Goslin-Birmingham Mfg. Co., Inc., Ala
Gowanda Furnaces, Inc., NY
Grafton Foundry Co., Wis
Grede Foundries, Inc., Wis
Green Bay Foundry & Machine Works, Wis
Greenlee Foundry Co., Ill
Grimm Foundry Co., Inc., NJ
Gunite Foundries Corp., Ill
H & H Foundry Machine Co., Pa
Hamilton Foundry & Machine Co., Ohio
Hansell-Elcock, Ill
Hardinge Mfg. Co., Pa
Headford Bros. & Hitchins Foundry Co., Iowa
Helmick Foundry-Machine Co., W.Va
Hewitt, John Foundry Co., NJ
Hodgson Foundry Co., Ill
Howard Foundry Co., Ill
Independence Stove & Mfg. Co., Mo
Industrial & Furnace Car Div., Irwin-Sensenich Corp., Pa
International Harvester Co., Ill
Janney Cylinder Co., Pa
Johnstone Foundries, Inc., Pa
Kanawha Mfg. Co., W.Va
Kansas City Hay Press Co., Mo
Katelman Foundry & Mfg. Co., Iowa
Keen Foundry Co., Inc., Ind
Kelly Foundry Co., Pa
Kingsport Foundry & Mfg. Corp., Tenn
Koehring Co., Wis
Kramer Bros. Foundry Co., Ohio
Kutztown Foundry & Machine Corp., Pa
Lake Erie Foundry Co., NY
Lakeside Malleable Casting Co., Wis
Lang-Scharmann & Co., Wis
Lawton, C.A. Co., Wis
Le Baron, E.L. Foundry, Mass
Lehigh, Inc., Pa
Letukas Foundry Inc., Ind
Lewistown Foundry & Machine Co., Pa
Liberty Foundry Co., Mo
Lincoln Foundry Corp., Calif
Lincoln Iron Works, Vt
Link-Belt Co., Ind
Littite Foundries, Inc., Mich
Littlestown Hardware & Foundry Co., Inc., Pa
Lodge Mfg. Co., Tenn
Lodi Iron Works, Inc., Calif
Long Beach Iron Works, Calif
Macaulay, H.C. Foundry Co., Calif
Madison Foundry Co., Ohio
Magirl Foundry & Furnace Co., Ill
Manufacturers Iron Foundry, Inc., Conn
McCarter Iron Works, Inc., Pa
McLanahan & Stone Corp., Pa
**Meehanite Metal Corp., NY**
—Ad p 461
Mercast Mfg. Corp., Calif
Metropolitan Iron Foundry, NY
Midwestern Foundries, Inc., Ind
Milwaukee Malleable & Grey Iron Works, Wis
Montague Machine Co., Mass
Morrisville Foundry Co., Inc., Vt
National Grey Iron Foundry, Ill
National Malleable & Steel Castings Co., Ohio
National Supply Co., Pa
Neenah Foundry Co., Wis
Noble & Wood Machine Co., NY
North Wales Foundry Co., Inc., Pa
Oak Hill Foundry & Machine Works, Ohio
Oakland Foundry & Machine Co., Mich
Oil City Iron Works, Tex
Overmyer Mould Co., Inc., Ind
Palmyra Foundry Co., Inc., NJ
Parker-Street Castings Co., Ohio
Pequonnock Foundry, Inc., Conn
Perkins, Henry Co., Mass
Pittsburgh Foundry & Machine Co., Pa
Pohlman Foundry Co., Inc., NY
Posey Iron Works, Inc., Pa
Potts, C. & G. & Co., Ind
Prescott Co., Mich
Pusey & Jones Corp., Del
Refinery Castings Co., Tex
Republic Steel Corp., Ohio
Richmond Foundry & Mfg. Co., Inc., Va
Ridge Foundry, Calif
Riverside Foundry Co., Pa
Riverside Foundry & Galvanizing Co., Mich
Rockwell Engineering Co., Ill
Rodney Hunt Machine Co., Mass
Rosedale Foundry & Machine Co., Pa
Ross-Meehan Foundries, Tenn
Ryerson, Joseph T. & Son, Inc., Ill
St. Marys Foundry Co., Ohio
San Francisco Iron Foundry, Calif
Savannah Machine & Foundry Co., Foundry Div., Ga
Schaefer-Goodnow Foundries, Inc., Pa
Schneider, Bowman Co., Inc., Pa
Scudder, E.J. Foundry & Machine Co., NJ
Selma Foundry & Machine Co., Ala
Shakopee Foundry Co., Minn
Shartle Div., Black-Clawson Co., Ohio
Sheffield Foundry Co., Ill
Shenango Furnace Co., Centrifugally Cast Products Div., Ohio
Sibley Machine & Foundry Corp., Ind
Sioux City Foundry & Boiler Co., Iowa
Somerset Foundry & Machine Co., Pa
Sonith Foundries Div., Food Machinery & Chemical Corp., Ind
Sorting-Mat Process Engineers, Mo
Southern Car & Mfg. Co., Inc., Ala
Sparta Foundry Div., Muskegon Piston Ring Co., Mich
Spencer's, I.S. Sons, Inc., Conn
Spring City Foundry Co., Pa
Springer's Foundry Co., Inc., Ind
Springfield Foundry Co., Mass
Spuck Iron & Foundry Co., Mo
Star Heel Plate Co., Inc., NJ
Stearns-Roger Mfg. Co., Colo
Sterling Foundry Co., Ill
Sterrit-Thomas Foundry Co., Pa
Stuart Foundry Co., Mich
Superior Foundry, Inc., Ohio
Swayne-Robinson & Co., Ind
Swett, A.L. Iron Works, NY
Taylor & Co., Inc., NY
Taylor & Boggis Foundry, Ohio
Terre Haute Malleable & Mfg. Corp., Ind
Texas Foundries, Inc., Tex
Tower Grove Foundry, Mo
Union Iron Works, Wash
United Shoe Machinery Corp., Mass
U.S. Pipe & Foundry Co., Ala
Utica General Jobbing Foundry, Inc., NY
Valley Iron Works, Minn
Vulcan Foundry Co., Calif
Vulcan Rail & Construction Co., NY
Washington Iron Works, Wash
Waterman Industries, Inc., Calif
Werner Foundry & Machine Co., Pa
West Point Foundry & Machine Co., Div. of Batson-Cook Co., Ga
Western Foundry & Machine Works, Inc., Kan
Western Iron & Foundry Co., Inc., Kan
Westinghouse Electric Corp., Materials Mfg. Dept., Pa
Wheland Co., Tenn
Wollaston Foundry Corp., Mass

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Woodruff & Edwards, Inc., Ill
Yale & Towne Mfg. Co., Ill
Zellner Foundry Co., Ohio
Zenith Foundry Co., Wis

## Iron, Ingot

Alten Foundry & Machine Works, Inc., Ohio (o)
Armco Steel Corp., Ohio (o,q,z,bb,cc, dd)
Cannon-Muskegon Corp., Mich (w)
Crucible Steel Co. of America, Pa (w)
Crucible Steel Co. of America, Titanium & Vacuum Metal Products Div., Pa (o,q,z,bb,cc,dd,ff)
Foote Mineral Co., Pa (aa)
Hayden Wire Works, Inc., Mass (o, bb,ee,ff)
Metallizing Co. of Los Angeles, Inc., Calif (ff)
National Moldite Co., NY (aa)
National-U.S. Radiator Corp., Plastic Metals Div., NY (aa)
Nesor Alloy Products Co., NJ (ff)
Norrich Plastics Corp., Screw Machine Products Div., NY (o,bb,ee)
Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa (ff)
Rathbone Corp., Mass (o,bb)
Republic Steel Corp., Ohio (w,aa)
Shenango Furnace Co., Centrifugally Cast Products Div., Ohio (o,ee)
Star Heel Plate Co., Inc., NJ (bb)
Superior Tube Co., Pa (ee)
Sylvania Electric Products, Inc., Parts Div., Pa (ff)
Tube Methods Inc., Pa (ee)

## Iron, Malleable

(castings)

Acco Steel Casting Div., American Chain & Cable Co., Inc., Pa
Acme Steel & Malleable Iron Works, NY
Albion Malleable Iron Co., Mich
Alloy Precision Castings Co., Ohio
American Chain & Cable Co., Pa
American Malleable Castings Co., Ohio
American Steel and Wire Div., U.S. Steel Corp., Ohio
Appleton Electric Co., Ill
Auto Specialties Mfg. Co., Mich
Badger Malleable & Mfg. Co., Wis
Belle City Malleable Iron, Racine Steel Castings Co., Wis
Cadillac Malliable Iron Co., Mich
Chicago Malleable Castings Co., Ill
Connecticut Malleable Castings Co., Conn
Dana Corp., Auburn Div., Ind
Dayton Malleable Iron Co., Ohio
Detroit Brass & Malleable Co., Mich
Eastern Malleable Iron Co., Del
General Electric Co., Foundry Dept., NY
General Motors Corp., Central Foundry Div., Mich
Hodgson Foundry Co., Ill
Iowa Malleable Iron Co., Iowa
Jamestown Malleable Iron Corp., NY
Laconia Malleable Iron Co., NH
Lake City Malleable Co., Ohio
Lakeside Malleable Castings Co., Wis
Lancaster Malleable Castings Co., Pa
Lehigh, Inc., Pa
Lincoln Foundry Corp., Calif
Link-Belt Co., Ind
McCarter Iron Works, Inc., Pa
Meadville Malleable Iron Co., Pa
Meeker Foundry Co., NJ
Metropolitan Iron Foundry, NY
Milwaukee Malleable & Grey Iron Works, Wis
Molin: Iron Works, Ill
Muncie Malleable Foundry Co., Ind
National Malleable & Steel Castings Co., Ohio
Northern Malleable Iron Co., Minn
Pennsylvania Malleable Iron Corp., Pa
Prescott Co., Mich
Rockwell Engineering Co., Ill
St. Louis Malleable Castings Co., Mo
Sorbo-Mat Process Engineers, Mo
Star Heel Plate Co., Inc., NJ
Superior Steel & Malleable Castings Co., Mich
Terre Haute Malleable & Mfg. Corp., Ind
Texas Foundries Inc., Tex
United Shoe Machinery Corp., Mass
U.S. Challenge & Challenge Co., Ill
Vulcan Rail & Construction Co., NY
West Virginia Malleable Iron Co., W.Va
Westmoreland Malleable Iron Co., NY

## Iron, Malleable Pearlitic

(castings)

Albion Malleable Iron Co., Mich
Auto Specialties Mfg. Co., Mich
Badger Malleable & Mfg. Co., Wis
Belle City Malleable Iron Co., Wis
Cadillac Malliable Iron Co., Mich
Canton Malleable Iron Co., Ohio
Chain Belt Co., Wis
Crane Co., Metals Div., Pa
Dalton Foundries, Inc., Ind
Dayton Malleable Iron Co., G.H.R. Div., Ohio
Eastern Malleable Iron Co., Del
Erie Malleable Iron Co., Pa
Federal Malleable Co., Wis
General Motors Corp., Central Foundry Div., Mich
I-F Mfg. Co., Ohio
Jamestown Malleable Iron Corp., NY
Laconia Malleable Iron Co., NH
Lakeside Malleable Casting Co., Wis
Lehigh Foundries Co., Div. of Lehigh Inc., Pa
Link-Belt Co., Ill
Meadville Malleable Iron Co., Pa
Milwaukee Malleable & Grey Iron Works, Wis
Moline Malleable Iron Co., Ill
National Malleable & Steel Castings Co., Ohio
Northern Malleable Iron Co., Minn
Peoria Malleable Casting Co., Ill
Pratt, William E. Mfg. Co., Ill
St. Louis Malleable Casting Co., Mo
Texas Foundries, Inc., Tex
Wagner Malleable Iron Co., Ill
Webster Mfg., Inc., Ohio

## Iron, Nodular or Ductile

(castings)

Acme Foundry & Machine Co., Okla
Adirondack Steel Casting Co., NY
Advance Foundry Co., Ohio
Alloy Precision Castings Co., Ohio
Alten Foundry & Machine Works Inc., Ohio
American Brake Shoe Co., NY
American Cast Iron Pipe Co., Ala
Apex Foundry, Inc., Mich
Artz, T. L. Foundry Co., Ill
Atlantic Foundry Co., Ohio
Bay City Foundry Co., Mich
Beloit Foundry Co., Ill
Bethlehem Steel Co., Pa
Black-Clawson Co., Ohio
Bonnot Co., Ohio
Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich
Chambersburg Engineering Co., Pa
Chicago Hardware Foundry Co., Ill
Crawford & Doherty Foundry Co., Ore
Curtiss-Wright Corp., Metals Processing Div., NY
Dayton Foundry, Calif
Deuscher, H.P. Co., Ohio
Dodge Steel Co., Pa
Ductile Iron Foundry, Inc., Conn
Electron Corp., Colo
Engineered Castings Div., American Brake Shoe Co., NY
Goslin Birmingham Mfg. Co., Inc., Ala
Grede Foundries, Inc., Wis
Gunite Foundries Corp., Ill
Hamilton Foundry & Machine Co., Ohio
Hansell-Elcock, Ill
Hodgson Foundry Co., Ill
Howard Foundry Co., Ill
Jamestown Malleable Iron Corp., NY
Janney Cylinder Co., Pa
Kutztown Foundry & Machine Corp., Pa
Lincoln Foundry Corp., Calif
Macauley, H.C. Foundry Co., Calif
**Meehanite Metal Corp., NY**
—Ad p 461
Mercast Mfg. Corp., Calif
Montague Machine Co., Mass
Neenah Foundry Co., Wis
Oil City Iron Works, Tex
Pohlman Foundry Co., Inc., NY
Pratt, William E. Foundry Div., Joslyn Mfg. & Supply Co., Ill
Rosedale Foundry & Machine Co., Pa
Ross-Meehan Foundries, Tenn
Sandy Hill Iron & Brass Works, NY
Savannah Machine & Foundry Co., Foundry Div., Ga
Shenango Furnace Co., Centrifugally Cast Products Div., Ohio
Sioux City Foundry & Boiler Co., Iowa
Southern Car & Mfg. Co., Inc., Ala
Stuart Foundry Co., Mich
Taylor-Wharton Co., Div. of Harsco Corp., NJ
Texas Foundries, Inc., Tex
United Shoe Machinery Corp., Mass

## Iron, Powders

Alan Wood Steel Co., Pa
Alloy Metal Powders, Inc., Iowa
Antara Chemicals, Div. of General Aniline & Film Corp., NY
Belmont Smelting & Refining Works, Inc., NY
Crane Co., Metals Div., Pa
Easton Metal Powder Co., Div. of American Mannex Corp., Pa
Ekstrand & Tholand, NY
Foote Mineral Co., Pa
Globe Steel Abrasive Co., Ohio
Hardy, Charles, Inc., NY
**Hoeganaes Sponge Iron Corp., NJ**
—Ad p 462
Johnson, A. & Co., Inc., NY
Magnetic Powders, Inc., Pa
National Moldite Co., NJ
National-U.S. Radiator Corp., Plastic Metals Div., NY
Norwalk Powdered Metals, Inc., Conn
**Pyron Corp., NY**
—Ad p 432
Republic Steel Corp., Ohio
Shakopee Foundry Co., Minn
Sorbo-Mat Process Engineers, Mo
Steel Shot Producers, Inc., Pa
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
Uniworld Research Corp. of America, Ohio

## Iron, Wrought

Albert Pipe Supply Co., Inc., NY (ee)
American Silver Co., NY (v,dd)
Byers, A.M., Pa (o,q,z,ee)
Dormont Mfg. Co., Pa (ee)
Gary Steel Products Corp., Va (o,z,bb)
Lockhart Iron & Steel Co., Pa (o, q,bb,dd)
National Electric Div., H.K. Porter Co., Pa (ee)
Rathbone Corp., Mass (o,bb)
Ryerson, Joseph T. & Son, Inc., Ill (ee)
Shaw-Kendall Engineering Co., Ohio (ee)
Titanium & Vacuum Metal Products Div., Crucible Steel Co. of America, Pa (o,q,z,bb,cc,dd,ff)
Vulcan Rail & Construction Co., NY (o,dd,ee)

## Isocyanates

(see Urethanes)

## Isoprene - Isobutylene Rubber

Adhesive Products Corp., NY (x)
Armstrong Cork Co., Pa (bb,cc,dd)
Atlas Mineral Products Co., Pa (cc)
Automotive Rubber Co., Inc., Mich (cc,dd)
Belko Corp., Md (y)
Bond International, Inc., Mich (y,ee)
Brown Rubber Co., Inc., Ind (u)
Castle Rubber Co., Pa (y,bb,cc,dd,ee)
Chicago-Allis Mfg. Corp., Ill (p)
Continental Rubber Works, Pa (bb,cc, dd,ee)
Dayton Rubber Co., Ohio (y,bb,cc,dd, ee)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (y,ee)
Electro Chemical Engineering & Mfg. Co., Pa (t,cc)
**Enjay Chemical Co. Div., Humble Oil & Refining Co., NY**
(p)—Ad pp 266-267
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (y,cc,ee)
Garlock Packing Co., NY (y,cc)
Geauga Industries Co., Ohio (y,bb,dd)
**Goshen Rubber Co., Inc., Ind**
(y)—Ad p 438
Hewitt-Robins, Inc., Conn (cc,ee)
Maloney, F.H. Co., Tex (y)
Martin Rubber Co., Inc., NJ (y,dd,ee)
Mid-States Rubber Products, Inc., Ind (y)
National Gasket & Washer Mfg. Co., Inc., NY (bb,cc,dd,ee)
Naugatuck Chemical Div., U.S. Rubber Co., Conn (x)
Paeco Rubber Co., Inc., Ohio (y,dd,ee)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
Parker, Stearns & Co., Inc., NY (y, bb,cc,dd,ee)
Pawling Rubber Corp., NY (bb,dd,ee)
Polymer Chemical Co., Ohio (x)
Rand Rubber Co., NY (t,cc)
Raybestos-Manhattan, Inc., Plastic Products Div., Pa (x)
Republic Rubber Div., Lee Rubber & Tire Corp., Ohio (p,y,ee)
Roberts Toledo Rubber Co., Ohio (ee)
Rogers Corp., Conn (cc,dd)
Roth Rubber Co., Ill (y,cc)
Sheller Mfg. Corp., Mich (u)
Standard Products Co., Mich (y)
Stockwell Rubber Co., Inc., Pa (y, cc,dd)
Technical Specialties Co., NY (dd)
Trostel, Albert Packing, Ltd., Wis (y)
**U.S. Rubber Co., Kem-Blo Dept., Conn**
(u)—Ad p 250
Vulcan Rubber Products Div., Reeves Bros. Inc., NY (p,y,cc)
Vulcanized Rubber & Plastics Co., Pa (y)
Western Felt Works, Ill (y,cc,dd,ee)
Williams-Bowman Rubber Co., Ill (y,bb,cc,dd,ee)

## Lacquers

(see Organic Coatings)

## Laminates

(see below; also Pre-Impregnated Materials)

## Laminates, High Pressure, Plastics or Rubber

(sheet, rod or tube; incl. clad laminates)

Acme Specialties, Inc., Pa (k,l,m)
Aerojet-General Corp., Structural Materials Div., Calif (l)
Allied Resinous Products, Inc., Ohio (k)

American Agile Corp., Ohio (k)
**American Brakeblok Div., American Brake Shoe Co., Mich (k)**
American Hard Rubber Co., Div. of Amerace Corp., NJ (k,l)
American Polyglas Corp., NJ (l)
**Apex Reinforced Plastics Div., White Sewing Machine Corp., Ohio (l)**
Artmor Plastics Corp., Md (l)
**Auburn Plastic Engineering, Ill (k)**
**Baer, N.S. Co., NJ (l)**
Bolta Products Div., General Tire & Rubber Co., Mass (k)
Brinkerhoff Brass & Bronze Works, Inc., NY (l)
**Cadillac Plastic & Chemical Co., Mich (l)**
**Calfibe Co., Inc., Calif (l)**
**Castle Rubber Co., Pa (m)**
**Coating Products, Inc., NJ (l)**
**Colonial Art Co., Inc., Mass (k)**
**Conneaut Rubber and Plastics Co., Div. of U.S. Stoneware Co., Ohio (k,l,m)**
**Connecticut Hard Rubber Co., Conn (m)**
**Conolite Div., Continental Can Co., Del (l)**
**Consoweld Corp., Wis (l)**
**Continental Rubber Works, Pa (m)**
**Continental-Diamond Fibre Corp., Del (k,l)**
**Curbell, Inc., NY (l)**
**Davidson Rubber Co., Mass (m)**
**Davis, Joseph Plastics Co., NJ (k)**
Delta Plastics Co., NJ (l)
**Dryden Rubber Div., Sheller Mfg. Corp., Ill (m)**
Dumont Corp., Ill (k,l,m)
**Everlite Corp., Wash (l)**
Fabricon Products Div., Eagle-Picher Co., Mich (l)
**Farley & Loetscher Mfg. Co., Plastics Div., Iowa**
(l)—Ad p 276
**Formica Corp., Sub. of American Cyanamid Co., Ohio (l)**
**Gatke Corp., Ill (l)**
General Electric Co., Laminated Products Dept., Ohio (l)
**General Plastics Corp., NJ (k,l)**
**General Tire & Rubber Co., Ind (l)**
**H & R Industries, Pa (k)**
Halogen Insulator & Seal Corp., Ill (l)
**Hartwell, H.N. & Son, Inc., Mass (k)**
**Haskelite Mfg. Corp., Mich (l)**
**Haveg Industries, Inc., Del (l)**
**Home Rubber Co., NJ (m)**
**Insulation Mfrs. Corp., Ill (k)**
**Iten Fibre Co., Ohio (l)**
**Johns-Manville Corp., NY (k,l)**
**Kaykor Industries, Inc., Div. of Kaye-Tex Mfg. Corp., NJ (k)**
Kerrco, Neb (k,l)
**Lewis, J.P. Co., Plastic Products Div., NY (l)**
**Luminous Resins, Inc., Ill (k)**
**Maloney, F.H. Co., Tex (l)**
**Marblette Corp., NY (l)**
**Mechanical Rubber Products Co., NY (l)**
**Mica Corp., Calif (l)**
**Mica Insulator Div., Minnesota Mining & Mfg. Co., NY (l)**
**Micarta Div., Westinghouse Electric Corp., SC (l)**
Moxness Products, Inc., Wis (l,m)
**National Vulcanized Fibre Co., Del**
(l)—Ad p 249
**New England Laminates Co., Inc., Conn**
(l)—Ad p 281
**Northern Plastics Corp., Wis (l)**
**Panelyte Div., St. Regis Paper Co., NJ (l)**
**Penn Fibre & Specialty Co., Inc., Pa (l)**
**Permali, Inc., Pa**
(l)—Ad p 431
**Philrus Products Co., NJ (k,l)**
**Porter, William Co., Calif (l)**
**Reinhold Engineering & Plastics Co., Inc., Calif (l)**
**Ren Plastics, Inc., Mich (l)**
**Replac Corp., Ohio (k,l,m)**
**Richardson Co., NY (l)**
**Reflin Co., Calif (l)**
**Rogers Corp., Conn (l)**
**Ryerson, Joseph T. & Son, Inc., Ill (l)**
**Seiberling Rubber Co., Plastics Div., Ohio (k,m)**
**Shamban, W.S. & Co., Ind (k)**
**Sillcocks Miller Co., NJ (k)**
**Spaulding Fibre Co., Inc., NY**
(l)—Ad p 255
**Standard Insulation Co., NJ (l)**
**Sun Steel Co., Ill (k)**
**Swedlow, Inc., Calif**
(k,l)—Ad p 263
**Synthane Corp., Pa**
(l)—Ad p 234
**Taylor Fibre Co., Pa**
(l)—Ad p 246
**Thermoid Div., H.K. Porter Co., Pa (k,m)**
**Thombert, Inc., Iowa (l)**
**U. S. Gasket Plastics Div., Garlock Packing Co., NJ (k)**
**Vulcan Rubber Products Div., Reeves Bros. Inc., NY (m)**
**Vulcanized Rubber & Plastics Co., Pa (m)**
**Westlake Plastics Co., Pa (l)**

## Laminates, Low Pressure, Plastics or Rubber

**(sheet, rod or tube; incl. clad laminates)**

**Acme Specialties, Inc., Pa (k,l,m)**
Aerojet-General Corp., Structural Materials Div., Calif (l)
**Allegheny Plastics, Inc., Pa (k)**
**Allied Resinous Products, Inc., Ohio (k)**
**Aisynite Co. of America, Calif (l)**
**American Agile Corp., Ohio (k)**
American Brake Shoe Co., NY (k)
American Insulator Corp., Pa (l)
American Polyglas Corp., NJ (l)
**Apex Reinforced Plastics Div., White Sewing Machine Corp., Ohio (m)**
Artmor Plastics Corp., Md (l)
**Atlas Powder Co., Chemicals Div., Del**
(k)—Ad p 262
**Auburn Plastic Engineering, Ill (l)**
**Baer, N.S. Co., NJ (l)**
**Biggs, Carl H. Co., Inc., Calif (l)**
**Blank, Arthur & Co., Inc., Mass (k)**
Brinkerhoff Brass & Bronze Works, Inc., NY (l)
**Cadillac Plastic & Chemical Co., Mich (k,l)**
**Calfibe Co., Inc., Calif (l)**
**Carroll, J.B. Co., Ill (k)**
**Castle Rubber Co., Pa (m)**
**Clad-Rex Corp., Ill (k)**
**Coating Products, Inc., NJ (l)**
**Connecticut Hard Rubber Co., Conn (m)**
Consolidated Molded Products Corp., Pa (l)
**Continental Can Co., NY (l)**
**Continental Rubber Works, Pa (m)**
**Continental-Diamond Fibre Corp., Del (k,l)**
**Corite Products Inc., Ill (l)**
**Corrulux Div., L.O.F. Glass Fibers Co., Tex (l)**
Delta Plastics Co., NJ (l)
**Dumont Corp., Calif**
(k,l,m)—Ad p 428
**Dura Plastics of New York, Inc., NY (k)**
**Eljay Corp., Md (k,l)**
**Emerson & Cuming, Inc., Mass (k,l,m)**
**Everlite Corp., Wash (l)**
Fiber Glass Industries, Inc., NY (l)
Fiberglass Ohio Inc., Ohio (l)
**Filon Plastics Corp., Calif (l)**
Foss Mfg. Co., Id (l)
**Frost Rubber Co., Ill (m)**
Fry Plastics International, Calif (k)
General Plastics Corp., Ind (k)
General Plastics Corp., NJ (k,l)
Gering Plastics, Div. of Studebaker-Packard Corp., NJ (k)
**Glastic Corp., Ohio**
(l)—Ad p 256
**Haskelite Mfg. Corp., Mich (l)**
**Haveg Industries, Inc., Del (l)**
**Hays Mfg. Co., Pa (l)**
**Heil Process Equipment Corp., Ohio (l)**
**Home Rubber Co., NJ (m)**
**Insulation Mfrs. Corp., Ill (k)**
**Kaykor Industries, Inc., NJ (k)**
Kerrco, Neb (k,l)
Kevinite Div., Swedlow, Inc., Ohio (l)
**Koch, H. & Sons, Calif (l)**
**Laminated Plas-Tex Corp., Ohio (k)**
**Lamtex Industries, Inc., NY (l)**
**Lewis, G.B. Co., Wis**
(l)—Ad p 432
**Lun Laminates, Inc., NY (l)**
**Mechanical Rubber Products Co., NY (l)**
**Mica Corp., Calif (l)**
**Mica Insulator Co., NY (l)**
**Micarta Div., Westinghouse Electric Corp., SC (l)**
**Minnesota Mining & Mfg. Co., Reinforced Plastics Div., Minn**
(l)—Ad pp 258-259
National Vulcanized Fibre Co., Del (l)
New England Laminates Co., Inc., Conn (l)
**Penn Fibre & Specialty Co., Inc., Pa (l)**
Permali, Inc., Pa (l)
**Perry Plastics Inc., Pa (k,l)**
**Philrus Products Co., NJ (k,l)**
Polygon Plastic Co., Ind (l)
**Porter, William Co., Calif (l)**
**Precision Paper Tube Co., Ill (l)**
**Rand Rubber Co., NY (k,l)**
**Reinhold Engineering & Plastics Co., Inc., Calif (l)**
**Reflin Co., Calif (l)**
**Ren Plastic, Inc., Mich (l)**
**Replac Corp., Ohio (l,m)**
Resolite Corp., Pa (l)
Riverside Plastics Corp., NY (l)
**Rowland Products, Inc., Conn (k)**
**Rubatex Div., Great American Industries, Inc., Va (u)**
**Rubber Corp. of America, NY (k)**
**Russell Reinforced Plastics Corp., NY (l)**
**Schorl Process Div., Ferro-Co Corp., NY (l)**
**Scranton Plastic Laminating Corp., Pa (k)**
Sealview Plastics, Inc., Pa (l)
**Sewell Mfg. Co., Mich (k)**
**Shamban, W.S. & Co., Ind (k)**
**Sierra Electric Corp., Calif (l)**
**Sillcocks Miller Co., NJ (k)**
**Southern Plastics Co., SC (k)**
**Sparta Mfg. Co., Div. of U.S. Ceramic Tile Co., Ohio (k)**
**Standard Insulation Co., NJ (l)**
**Stockwell Rubber Co., Inc., Pa (k,m)**
**Strick Plastics Co., Pa (m,k,l)**
**Swedlow, Inc., Calif (k,l)**
**U.S. Rubber Co., NY (k)**
**Urrite Plastics Fabricators, Calif (k)**
**Vulcan Rubber Products Div., Reeves Bros. Inc., NY (m)**
**Vulcanized Rubber & Plastics Co., Pa (m)**
**Westlake Plastics Co., Pa (l)**
Winner Mfg. Co., Inc., NJ (l)
**Woodall Industries, Inc., Mich (k,l)**
**Youngstown Sheet & Tube Co., Ohio (l)**
**Zenith Plastics Co., Sub. of Minnesota Mining & Mfg. Co., Calif (l)**

## Laminates, High or Low Pressure, Plastics or Rubber—Moldings

**(incl. clad laminates)**

**Admiral Corp., Molded Products Div., Ill (l)**
Aerojet-General Corp., Structural Materials Div., Calif (l)
**Allied Resinous Products, Inc., Ohio (k)**
**American Agile Corp., Ohio (k)**
**American Brakeblok Div., American Brake Shoe Co., Mich (k)**
**Apex Reinforced Plastics Div., White Sewing Machine Corp., Ohio (l)**
**Arrowhead Products, Calif (l,m)**
**Artmor Plastics Corp., Md (l)**
**Baer, N.S. Co., NJ (l)**
Brunswick Corp., Defense Products Div., Mich (l)
**Byers, A.M. Co., Pa (k)**
**Cadillac Plastic & Chemical Co., Mich (k,l)**
**Calfibe Co., Inc., Calif (l)**
**Camfield Fiberglass Plastics, Inc., Mich (l)**
**Carroll, J.B. Co., Ill (k)**
**Castle Rubber Co., Pa (m)**
**Colonial Art Co., Inc., Mass (k)**
**Colonial Rubber Co., Div. of U.S. Stoneware Co., Ohio (k,m)**

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Continental Rubber Works, Pa (m)
**Continental-Diamond Fibre Corp., Del (k,l)**
**Corite Products, Inc., Ill (l)**
**Curtiss-Wright Corp., Utica Div., Mich (l)**
Dumont Corp., Calif (k,l,m)
**Eljay Corp., Md (l)**
Englander Co., Inc., Industrial Products Div., Md (l)
**Fiber Glass Industries, Inc., NY (l)**
**Formica Corp., Sub. of American Cyanamid Co., Ohio (l)**
Foss Mfg. Co., Id (l)
**Frost Rubber Co., Ill (m)**
Fry Plastics International, Calif (l)
**Galigher Co., Utah (k)**
**Gatke Corp., Ill (l)**
**General American Transportation Corp., Ill (l)**
**General Electric Co., Plastics Dept., Ill (l)**
**General Tire & Rubber Co., Ind (k)**
Gering Plastics Div., Studebaker-Packard Corp., NJ (k)
**Glass Reinforced Plastics Corp., Ohio (l)**
**Glastic Corp., Ohio**
(l)—Ad p 256
Greene, Tweed & Co., Pa (k,l,m)
**H & R Industries, Pa (k)**
**Haskelite Mfg. Corp., Mich (l)**
**Haveg Industries, Inc., Del (l)**
Hawley Products Co., Ill (l)
**Hays Mfg. Co., Pa (l)**
**Hewitt-Robins, Inc., Conn (m)**
**Home Rubber Co., NJ (m)**
Industrial Products Div., General Tire & Rubber Co., Ind (k)
Insulation Mfrs. Corp., Ill (k)
Kaykor Industries, Inc., Div. of Kaye-Tex Mfg. Corp., NJ (k)
Kerrco, Neb (k,l)
Knight, Maurice A., Ohio (l)
Lamtex Industries, Inc., NY (l)
Lone Star Plastics Co., Inc., Tex (l)
Lunn Laminates, Inc., NY (k,l)
Maloney, F.H. Co., Tex (l)
Marion Div., General Tire & Rubber Co., Ind (l)
Masterglas Div., Gisholt Machine Co., Wis (l)
Mechanical Rubber Products Co., NY (l)
Mica Corp., Calif (l)
**Mica Insulator Div., Minnesota Mining & Mfg. Co., NY (l)**
Micarta Div., Westinghouse Electric Corp., SC (l)
**Minnesota Mining & Mfg. Co., Reinforced Plastics Div., Minn**
(l)—Ad pp 258-259
Molded Fiber Glass Co., Ohio (l)
**National Vulcanized Fibre Co., Del**
(l)—Ad p 249
**New England Laminates Co., Inc., Conn**
(l)—Ad p 281
Northwest Plastics Industries, Inc., Minn (l)
**Panelyte Div., St. Regis Paper Co., NJ**
(l)—Ad p 444
Penn Fibre & Specialty Co., Inc., Pa (k)
**Permali, Inc., Pa**
(l)—Ad p 431
Plymouth Industrial Products, Inc., Wis (k)
Porter, William Co., Calif (l)
REF Mfg. Corp., NY (l)
Reinhold Engineering & Plastics Co., Inc., Calif (l)
Ren Plastic, Inc., Mich (l)
Replac Corp., Ohio (k,l,m)
Resolite Corp., Pa (l)
Richardson Co., Ill (l)
Riverside Plastics Corp., NY (l)
Russell Reinforced Plastics Corp., NY (l)
Shamban, W.S. & Co., Ind (k)
Sierra Electric Corp., Calif (k)
**Spaulding Fibre Co., Inc., NY**
(l)—Ad p 255
Standard Insulation Co., NJ (l)
Stockwell Rubber Co., Inc., Pa (k,m)
Strick Plastics Co., Pa (k,l,m)
Structural Fibers, Inc., Ohio (l)
Sun Rubber Co., Ohio (m)
**Swedlow, Inc., Calif**
(k,l)—Ad p 263
**Synthane Corp., Pa**
(l)—Ad p 234
**Taylor Fibre Co., Pa**
(l)—Ad p 246
Thermoid Div., H.K. Porter Co., Pa (l)
Thompson, H.I. Fiber Glass Co., Calif (l)
Toledo Industrial Rubber Co., (l)
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (m)
Waterbury Cos., Inc., Conn (l)
Winner Mfg. Co., Inc., NJ (l)
Wittman, Lawrence & Co., NY (k,l)
Woodall Industries, Inc., Mich (k,l)
Zenith Plastics Co., Sub. of Minnesota Mining & Mfg. Co., Calif (l)

## Laminates, Metal-Metal

(incl. "bimetals"; key letters refer to base metal)

Aerojet-General Corp., Structural Materials Div., Calif (a,g,h)
Al-Fin Div., Arthur Tickle Engineering Works, Inc., NY (a,e)
Almco Steel Products Corp., Ind (g)
American Cast Iron Pipe Co., Ala (c,g)
American Silver Co., Inc., NY (b,c,f,g)
Baker & Co., Inc., NJ (b,f)
Brunswick Corp., Defense Products Div., Mich (a)
Chace, W.M. Co., Mich (a,b,c,e,f,g,h,i)
Composite Industrial Metals, Inc., RI (a,b,c,d,e,f,g,h,j)
Copperweld Steel Co., Ohio (g)
Eastern Brass & Copper Co., NY (a)
Eastern Smelting & Refining Corp., Mass (b)
Gar Precision Parts, Inc., Conn (b,f)
General Findings & Supply Co., Industrial Div., Mass (b,f)
General Plate Div., Metals & Controls Corp., Mass (a,b,c,e,f,g,h,j)
Haydon Corp., NY (a,g)
Horton-Angell Co., Mass (b,f)
Improved Seamless Wire Co., RI (b,c,f)
Knapp Mills, Inc., NY (b,g)
Laminated Shim Co., Conn (a,b,g)
Leach & Garner Co., Industrial Div., Mass (b,f)
**Makepeace, D.E. Div., Engelhard Industries, Inc., Mass**
(b,c,f,g)—Ad p 158
Nuclear Metals, Inc., Mass (a,b,c,e,f,g,h)
Presswork, Inc., Mich (b,d)
Revere Copper & Brass, Inc., Foil Div., NY (a)
Rockwell Engineering Co., Ill (a,b,c,g)
Rockwell-Standard Corp., Stamping Div., NY (a,b,f,g)
Standard Metals Corp., Mass (a,b,c,f,g)
Staver Co., Inc., NY (a,b)
Sylvania Electric Products, Inc., NY (b,f)
Wilson, H.A. Co., Div. of Engelhard Industries, Inc., NJ (b,f,g)
Wisconsin Gasket & Mfg. Co., Ohio (b,g)

## Laminates, Metal-Organic

(key letters refer to base metal)

Aerojet-General Corp., Structural Materials Div., Calif (a,g,h)
AllianceWall Div., AllianceWare, Inc., Ohio (a,g)
American Nickeloid Co., Ill (a,g)
Arvin Industries, Inc., Ind (a,e,g)
Benjamin Electric Mfg. Co., Ill (g)
**Clad-Rex Corp., Ill**
(a,g)—Ad p 413
Coated Coil Corp., NY (a,g)
Cochran Foil Co., Ky (a)
Dumont Corp., Calif (a)
Enamel Products Co., Ohio (a,c)
Enamelstrip Corp., Sub. of National Steel Corp., Pa (a,b,c,f,g,j)
Gomar Mfg. Co., Inc., NJ (a)
Haydon Corp., NY (a,g)
Hood Rubber Co., Div. of B.F. Goodrich Chemical Co., Mass (a,g)
Kaiser Aluminum & Chemical Sales Inc., Ill (a)
Maloney, F.H. Co., Tex (g)
Met-L-Wood Corp., Ill (a,b,d,f,g)
New England Laminates Co., Inc., Conn (g)
Sun Steel Co., Ill (a,e,g)
Young, M.M. Div., Litho-Strip Corp., Ill (a,g)

## Laminates, Wood-Metal

Brunswick Corp., Defense Products Div., Mich
Gamble Brothers, Inc., Special Products Div., Ky
**Haskelite Mfg. Corp., Mich**
**Keller Products, Inc., NH**
**Laminated Veneers Co., NY**
Met-L-Wood Corp., Ill
**Technical Ply-Woods Sales, Ill**
**U.S. Plywood Corp., NY**

## Laminating Resins

(see specific plastic or rubber)

## Lead and Its Alloys

Advance Stamping Co., Mich (dd)
Alpha Metals, Inc., NJ (n,o,v,w,z,aa,bb,cc,dd)
American Metal Climax, Inc., NY (n,o,w,aa,bb)
American Nickel Alloy Mfg. Corp., NY (w)
American Smelting & Refining Co., NY (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Bar-Ray Products, NY (v,z,cc)
Bearium Metals Corp., NY (w)
Belmont Smelting & Refining Works, Inc., NY (n,o,v,w,z,aa,cc,ff)
Bunker Hill Co., Calif (n,o,w,z,bb,cc,dd,ee,ff)
**Cerro de Pasco Sales Corp., NY**
(w)—Ad p 178
Chicago Smelting & Refining Corp., Ill (w)
Crown Metal Co., Wis (n,o,q,w,bb,cc,dd,ee,ff)
Designers Metal Corp., Ill (cc)
Dietzel Lead Burning Co., Pa (n,o,z,cc)
Division Lead Co., Ill (n,o,v,w,z,aa,cc,dd,ee,ff)
Dixie Lead Co., Tex (n,o,q,w,aa,cc)
Eagle-Picher Co., Ohio (aa)
Empire Metal Co., NY (n,o,q,v,w,z,bb,cc,dd,ee,ff)
Evans Metal Co., Ga (w,cc,ee)
Federated Metals Div., American Smelting & Refining Co., NY (n,o,w,cc,ee,ff)
Fox Products Co., Pa (n)
Glidden Co., Ind (aa)
**Glidden Co., Chemical Divs., Metals Dept., Ind**
(aa)—Ad p 429
Greenback Industries, Inc., Mich (aa)
Hardy, Charles, Inc., NY (aa)
Harshaw Chemical Co., Ohio (n)
Hayden Wire Works, Inc., Mass (ff)
Hayman, Michael & Co., NY (o,w)
Heil Process Equipment Corp., Ohio (n)
Hi-Grade Alloy Corp., Ill (n,o,v,w,z,bb,cc,ee,ff)
Indium Corp. of America, NY (v,cc,dd,ff)
Johnston Foil Div., Standard Packaging Corp., Mo (v,cc)
Kassel Export Co., Inc., NJ (v)
Kinkead Industries, Inc., Ill (cc,dd)
Kirk, Morris P. & Son, Calif (n,o,q,w,z,aa,bb,cc,dd)
Lavin, R. & Sons, Inc., Ill (n,w)
McGean Chemical Co., Ohio (n,o,aa,bb,dd)
Metal & Thermit Corp., NJ (n)
Metallizing Co. of Los Angeles, Inc., (ff)
Metals Disintegrating Co., Inc., NJ (aa)
National Lead Co., NY (n,o,q,w,z,aa,bb,cc,dd,ee,ff)
National Lead Construction Co., Inc., NJ (n,o,w,z,cc,ee,ff)
Nesor Alloy Products Co., NJ (ff)
New England Smelting Works, Inc., Mass (o,w)
Oatey, L.R. Co., Ohio (o,w,cc,dd)
Olds Alloy Co., Calif (q,w)
Peerless Alloy Co., Colo (n,o,q,w,z,bb,cc)
Peerless Roll Leaf Co., Div. of Howe Sound Co., NJ (v,dd)
Pittsburgh Smelting & Refining Co., Pa (o,w,cc)
Presswork, Inc., Mich (o,cc)
Republic Lead Equipment Co., Ohio (n)
Republic Metals Co., Inc., NY (n,o,q,v,w,z,cc,ee,ff)
Revere Copper & Brass, Inc., Foil Div., NY (v)
River Smelting & Refining Co., Ohio (o,w)
Rotometals, Calif (o,w,bb,cc,dd,ee,ff)
St. Joseph Lead Co., NY (w)
Sall, George Metals Co., Inc., Pa (w)
Staver Co., Inc., NY (v,cc,dd)
Stevens, Frederic B., Inc., Mich (n)
Texas Instruments, Inc., Metals & Controls Div., Mass (dd)
Udylite Corp., Mich (n)
U.S. Smelting, Refining & Mining Co., NY (w)
U.S. Stoneware Co., Ohio (n)
Waltham Foundry Co., Mass (w)

## Leather and Leather Parts

Alexander Bros. Belting Co., NJ
Alexander, E.P. & Son, Mass
**Auburn Mfg. Co., Conn**
—Ad p 450
Bond, Charles Co., Pa
Charlotte Leather Belting Co., NC
Chicago Rawhide Mfg. Co., Ill
Chicago-Allis Mfg. Corp., Ill
Donovan, F.C., Inc., Mass
Excelsior Leather Washer Mfg. Co., Inc., Ill
Foss Mfg. Co., Id
Garlock Packing Co., NY
General Gasket, Inc., Conn
Gibb, Walton Leather Co., Pa
Glenn, Joseph & Sons, Inc., Pa
Graton & Knight Co., Mass
Haffner Bros. Co., Ohio
Hay, James E. Co., Inc., Mass
Houghton, E.F. & Co., Pa
**International Packings Corp., NH**
—Ad p 416
Mechanical Leathers, Inc., Pa
Michigan Leather Products Co., Mich
National Gasket & Washer Mfg. Co., Inc., NY
Norwich Leather Co., Conn
Page Belting Co., NH
Penn Fibre & Specialty Co., Inc., Pa
Porter, William Co., Calif
Rhoads, J.E. & Sons, Del
Schachner Leather & Belting Co., Charlotte Leather Belting Co. Div., NC
Shingle Leather Co., NJ
Silcocks Miller Co., NJ
Southern Belting & Transmission Co., Ga
Standard Washer & Mat, Inc., Conn
Staver Co., Inc., NY

Truche Leather Co., Mass
**Warren Belting Co., Mass**
**Winworth Co., Inc., NJ**

## Lignum Vitae

(see Wood)

## Lithium

**American Potash & Chemical Corp., Calif (w)**
Belmont Smelting & Refining Works, Inc., NY (o,aa)
**Foote Mineral Co., Pa (w)**
**Hardy, Charles, Inc., NY (aa)**
**Kawecki Chemical Co., NY (w)**
Lithium Corp. of America, Inc., Minn (w,bb,ff)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)

## Low Pressure Laminates

(see Laminates)

## Magnesium and Its Alloys

Alabama Metallurgical Corp., Ala (w)
**Aluminum Co. of America, Pa (n,o,q,z,bb,cc,dd)**
**Aluminum & Magnesium, Inc., Ohio (w)**
**American Silver Co., NY (v,dd)**
**American Smelting & Refining Co., NY (n,w)**
**Apex Smelting Co., Ill (n,w)**
**Arcos Corp., Pa (ff)**
**Armet Alloys, Inc., Ohio (n,w)**
Belmont Smelting & Refining Works, Inc., NY (w)
Brooks & Perkins, Inc., Mich (z,cc,dd)
**Copper & Brass Sales, Inc., Mich (o, z,bb,cc,dd,ee,ff)**
**Designers Metal Corp., Ill (cc)**
**Dow Chemical Co., Dow Metal Products Co., Div., Mich**
(n,o,q,w,z,aa,bb,cc,dd,ee,ff)—Ad pp 408-409
**Federated Metals Div., American Smelting & Refining Co., NY (n,w)**
**Hardy, Charles, Inc., NY (aa)**
**King Laboratories, Inc., NY (w,aa)**
**Kinkead Industries, Inc., Ill (cc,dd)**
**Light Metals, Inc., Ind (n)**
**Magline, Inc., Mich (o,z,bb,cc,ee,ff)**
**Magna Mfg. Co., Inc., NJ (aa)**
**Magnesium Elektron, Inc., NY (n, w,bb)**
**Magnode Products, Inc., Ohio (n,o,bb, dd,ee)**
**Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (o,ee)**
**McGean Chemical Co., Ohio (aa)**
**Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)**
**Norrich Plastics Corp., NY (o,bb)**
**Nuclear Metals, Inc., Mass (bb,dd,ee)**
**Peerless Roll Leaf Co., Div. of Howe Sound Co., NJ (v,dd)**
**Purdy, A.R. Co., Inc., NJ (o,z,bb,cc, ee,ff)**
**Reade Mfg. Co., Inc., NJ (aa)**
**Standard Magnesium Corp., Okla (n,q, w)**
**Tube Distributors Co., Inc., NY (ee)**
**Ullmann, Inc., Wis (o,ee)**
**U.S. Magnesium Div., Transition Metals & Chemicals, Inc., NY (aa)**
**Utica General Jobbing Foundry, Inc., NY (o)**
**Vanadium Corp. of America, NY (w)**
**Waltham Foundry Co., Mass (w)**
White Metal Rolling & Stamping Corp., NY (n,o,q,z,bb,cc,dd,ee,ff)

## Manganese and Its Alloys

**Amalgamated Steel Corp., Ohio (o,bb)**
**American Nickel Alloy Mfg. Corp., NY (w)**
**Anaconda Co., NY (n,v,cc)**
**Belmont Smelting & Refining Works, Inc., NY (w,aa)**
**Chicago Development Corp., Md (o,v, z,bb,cc,dd,ee,ff)**
Crane Co., Metals Div., Pa (aa)
**Foote Mineral Co., Pa (aa)**
**Hardy, Charles, Inc., NY (aa)**
**Hayden Wire Works, Inc., Mass (ff)**
**Hommel, O. Co., Pa (aa)**
**Lavin, R. & Sons, Inc., Ill (w)**
Metals Disintegrating Co., Inc., NJ (aa)
**National Paint & Manganese Co., Va (aa)**
**National-U.S. Radiator Corp., Plastic Metals Div., NY (aa)**
**New Jersey Zinc Co., NY (w)**
**Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)**
**Pioneer Aluminum, Inc., Calif (z)**
**Taylor-Wharton Co., Div. of Harsco Corp., NJ (z,bb,ff)**
**Tube Distributors Co., Inc., NY (ee)**
**Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)**
**Utica General Jobbing Foundry, Inc., NY (aa)**
**Vanadium Corp. of America, NY (w)**

## Manganese Bronze

(see Copper)

## Mechanical Fasteners

**Abalon Precision Mfg. Corp., NY**
**Acme Machine Products Div., Serrick Corp., Ind**
**Acme Stamping & Wire Forming Co., Pa**
**Albany Products Co., Inc., Conn**
**Allen Mfg. Co., Conn**
**Allmetal Screw Products Co., Inc., NY**
**Alofs Mfg. Co., Mich**
**Aluminum Co. of America, Pa**
**American Screw Co., Conn**
**American Steel and Wire Div., U.S. Steel Corp., Ohio**
**Anti-Corrosive Metal Products Co., Inc., NY**
**Atlantic Steel Co., Ga**
**Automatic Nut Co., Pa**
**Automotive Rubber Co., Inc., Mich**
**Aviation Developments, Inc., Calif**
**Bethlehem Steel Co., Pa**
**Blake & Johnson Co., Conn**
**Boots Aircraft Nut Corp., Conn**
**Bostitch, Inc., RI**
**C. E. M. Co., Conn**
**Camloc Fastener Corp., NJ**
**Central Screw Co., Ill**
**Champion Rivet Co., Ohio**
**Chicago Rivet & Machine Co., Ill**
**Chicago Screw Co., Div. of Standard Screw Co., Ill**
**Cleveland Cap Screw Co., Ohio**
**Columbia-Geneva Steel Div., U.S. Steel Corp., Calif.**
**Consolidated Fruit Jar Co., NJ**
**Continental Screw Co., Mass**
**Delron Co., Inc., Calif**
**Dimco-Gray Co., Ohio**
**Driv-Lok Sales Corp., Ill**
**Elastic Stop Nut Corp. of America, NJ**
**Electric Steel Foundry Co., Ore**
**Erie Bolt & Nut Co., Pa**
**Falstrom Co., NJ**
**Fastex Div., Illinois Tool Works, Ill**
**General American Transportation Corp., Ill**
**General Chain & Mfg. Corp., Ohio**
**Gries Reproducer Corp., NY**
**Grip Nut Co., Ind**
—Ad p 498
**Groov-Pin Corp., NJ**
**Harper, H.M. Co., Ill**
**Hartford Machine Screw Co., Div. of Standard Screw Co., Conn**
**Hassall, John, Inc., NY**
**Heli-Coil Corp., Conn**
**Hennefelt Precision Products, Ohio**
**Hi-Shear Rivet Tool Co., Calif**
**Holo-Krome Screw Corp., Conn**
**Huck Mfg. Co., Mich**
**Ideal Can Co., Mass**
**Jaques Co., Mass**
**Jervis Corp., Mich**
**K S M Products, Inc., NJ**
**Kinkead Industries, Inc., Ill**
**Klincher Locknut Corp., Ind**
**Langsenkamp, F.H. Co., Ind**
**Lincoln Iron Works, Vt**
**Lundquist Tool & Mfg. Co., Inc., Mass**
**MacLean-Fogg Lock Nut Co., Ill**
—Ad p 494
**Magnesium Co. of America, Ind**
**Magnesium Products of Milwaukee, Inc., Wis**
**Metal Goods Corp., Mo**
**Miracle Adhesives Corp., NY**
**Morrisville Foundry Co., Inc., Vt**
**National Lock Co., Fastener Div., Ill**
**National Machine Products Co., Mich**
**Navan Products, Inc., Sub. of North American Aviation Inc., Calif**
**Nelson Stud Welding Div., Gregory Industries, Inc., Ohio**
**Nutt-Shel Co., Calif**
**Nylok-Detroit, Mich**
**Ohio Nut & Bolt Co., Ohio**
**Palnut Co., NJ**
**Parker-Kalon Div., General American Transportation Corp., NJ**
**Penn Engineering & Mfg. Corp., Pa**
**Plastiglide Mfg. Corp., Calif**
**Plume & Atwood Mfg. Co., Conn**
**Prestole Corp, Ohio**
**Red Devil Mfg. Co., Ill**
**Reynolds Aluminum Supply Co., Ga**
**Rhode Island Tool Co., RI**
**Rockwell Engineering Co., Ill**
**Rolled Alloys, Inc., Mich**
**Russell, Burdsall & Ward Bolt & Nut Co., NY**
—Ad p 501
**Set Screw & Mfg. Co., Ill**
—Ad p 496
**Shakeproof Div., Illinois Tool Works, Ill**
**Sharon Steel Corp., Pa**
**Shur-Lok Corp., Calif**
**Sillcocks Miller Co., NJ**
**Simmons Fastener Corp., NY**
—Ad p 497
**Simonsen Metal Products Co., Ill**
**Snyder Mfg. Co., Inc., Ohio**
**Southco Div., South Chester Corp., Pa**
**Southern Screw Co., NC**
**Special Screw Products Co., Ohio**
**Standard Locknut & Lockwasher, Inc., Ind**
**Standard Pressed Steel Co., Pa**
**Star Expansion Industries Corp., NY**
**Star Stainless Screw Co., NJ**
**Sterling Bolt Co., Ill**
**Tennessee Coal and Iron Div., U.S. Steel Corp., Ala**
**Thompson-Bremer & Co., Ill**
**Thomson, Judson L. Mfg. Co., Mass**
**Tinnerman Products, Inc., Ohio**
**Townsend Co., Engineered Fasteners Div., Pa**
**Tubular Rivet & Stud Co., Mass**
**United Shoe Machinery Corp., Mass**
**United-Carr Fastener Corp., Mass**
**Velcro Sales Corp., NY**
**Waldes Kohinoor, Inc., NY**
**Waterbury Pressed Metal Co., Conn**
**Waterman Industries, Inc., Calif**
**Weckesser Co., Ill**
**Wesbar Stamping Corp., Wis**
**Western Automatic Machine Screw Co., Div. of Standard Screw Co., Ohio**
**Whitehead Metal Products Co., Inc., NY**
**Wilson, H.A. Div., Engelhard Industries, Inc., NJ**
**Worth Co., Wis**

## Melamines

**Adhesive Products Corp., NY (x)**
**Alcylite Plastics & Chemical Corp., Calif (p,y)**
**Allied Chemical Corp., Plastics & Coal Chemicals Div., NY (p,y)**
**American Cyanamid Co., Plastics & Resins Div., NY**
(p,x,y)—Ad pp 251-254
**American-Marietta Co., Adhesive, Resin & Chemical Div., Wash (p)**
**Baer, N.S Co., NJ (bb,cc,dd,ee)**
**Booty Resineers Div., American-Marietta Co., Ohio (p)**
**Cadillac Plastic & Chemical Co., Mich (bb,cc,dd,ee)**
**Catalin Corp. of America, NY (p,x)**
**Colonial Kolonite Co., Ill (bb,cc,ee)**
**Comco Plastics, Inc., NY (bb,cc,dd, ee)**
**Continental-Diamond Fibre Corp., Del (bb,cc,dd,ee)**
**Curbell, Inc., NY (bb,cc,dd,ee)**
**Dapol Plastics, Inc., Mass (y)**
**Delta Plastics Co., NJ (bb,cc,dd,ee)**

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Dyna-Therm Chemical Corp., Calif (p)
**Farley & Loetscher Mfg. Co., Plastics Div., Iowa (cc)**
Fiberite Corp., Minn (y)
**Formica Corp., Sub. of American Cyanamid Co., Ohio (bb,cc,ee)**
General Electric Co., Laminated Products Dept., Ohio (bb,cc,ee)
**Grigoleit Co., Ill (p,s)**
**Haskelite Mfg. Corp., Mich (cc,dd)**
Iten Fibre Co., Ohio (bb,cc,dd,ee)
**Kaufman Glass Co., Del (bb,cc,dd,ee)**
Kurz Kasch, Inc., Ohio (y)
**Laminated Plastex Corp., Ohio (x,cc)**
**Mica Insulator Div., Minnesota Mining & Mfg. Co., NY (bb,cc)**
**Monsanto Chemical Co., Plastics Div., Mass (p,x)**
**Muehlstein, H. & Co., Inc., NY (p,y)**
National Vulcanized Fibre Co., Del (bb,cc,dd,ee)
**Northern Plastics Corp., Wis (cc,dd)**
Omni Products Corp., NY (y)
**Panelyte Div., St. Regis Paper Co., NJ (x,bb,cc,dd,ee)**
**Penn Fibre & Specialty Co., Inc., Pa (bb,cc,dd,ee)**
**Philrus Products Co., NJ (bb,cc,dd,ee)**
Reichhold Chemical, Inc., NY (p,x)
Richardson Co., NY (bb,cc,ee)
Sierra Electric Corp., Calif (y)
Spaulding Fibre Co., Inc., NY (bb, cc,dd,ee)
Synthane Corp., Pa (bb,cc,dd,ee)
Taylor Fibre Co., Pa (bb,cc,dd,ee)
**Texas Glass Fiber Corp., Tex (y)**
**U.S. Polymeric Chemical, Inc., Conn (s)**
Westlake Plastics Co., Pa (bb,cc,dd,ee)

## Metal Powder Parts

(Metal Compacts)

**Allied Products Corp., Mich (c)**
**Aluminum Co. of America, Pa (a)**
**American Brake Shoe Co., NY (a,b,c, f,g,)**
**American Nickel Alloy Mfg. Corp., NY (f)**
**American Powdered Metals, Inc., Conn (b,c)**
**American Sinteel Corp., NY (b,c,d,g)**
**American Sinterings Div., Engineered Plastics, Inc., Conn (b,c,f,g,j)**
Amplex Div., Chrysler Corp., Mich (b,c,f,g)
**Arnold Engineering Co., Ill (c,f)**
**Arrow Sintered Products Co., Ill (b, c,g)**
**Asco Sintering Corp., Calif (a,b,c,d,f,g)**
**Atlas Brass Foundry, Calif (b,c)**
**Bassick Co., Conn (a,b,c,f,g)**
**Bendix Aviation Corp., NJ (a,b,c,f,g)**
**Boston Gear Works, Mass (a,b,c,f,g)**
**Bound Brook Oil-Less Bearing Co., NJ (b,c,f)**
**Brockway Pressed Metals, Inc., Pa (a, b,c,f,g)**
Bunting Brass & Bronze Co., Ohio (b,c)
**Burgess-Norton Mfg. Co., Ill (a,b,c,f, g)**
**Ceromet, Inc., Calif (b,c,f,g)**
Chicago Development Corp., Md (h)
**Chicago Powdered Metals Products Co., Ill (a,b,c,f,g)**
**Cleveland Graphite Bronze Co., Ohio (a,b,c,f,g)**
Compacted Metals Corp., Ill (b,c,f,g)
**CrystalX Corp., Pa (bb,cc,dd,ee)**
Delco Moraine Div., General Motors Corp., Ohio (b,c,f,g)
**Diamond Mfg. Co., Pa (a,b,f,g)**
**Dixon Sintaloy, Inc., Conn (b,c,f,g,h,j)**
**Eaton Mfg. Co., Powdered Metals Div., Mich (b,c,d,f,g,j)**
**Eberhart Steel Products, Powdered Metals Div., Ind (b,c)**
**Engineered Plastics & American Sinterings, Inc., Conn (b,c,f,g)**
**Ferro Powdered Metals, Inc., Ind (b, c,f,g)**
**General Metals Powder Co., Ohio (b, c,d,j)**
**General Powdered Metal Products, Inc., Holly Corp., Conn (a,b,c,f,g)**
**General Sintering Corp., Ill (a,b,c,f,g)**
Gibson Electric Co., Pa (a,b,c,f)
**Haller, Inc., Mich (b,c,g)**
**Indar Corp., Ind (a,b,c,f,g)**
**Indiana Steel Products Co., Ind (a, b,c,f,g)**
**International Powder Metallurgy Co., Inc., Pa (a,b,c,d,f,g,j)**
**Johnson Bronze, Pa (b,c)**
Keystone Carbon Co., Pa (b,c,f,g)
**Kwikset Powdered Metal Products, Calif (b,c,d,f,g)**
**Lux Clock Mfg. Co., Inc., Conn (a, b,c,f,g)**
Magnetic Core Corp., NY (c)
Mallory, P.R. & Co., Inc., Ind (g)
Merriman Bros., Inc., Mass (b,c,f,g)
Metal Powder Products, Inc., Ohio (b, c,g)
**Metals Disintegrating Co., Inc., NJ** (a,b,c,f,h,j)—Ad p 456
Micro Metallic Corp., NY (a,b,c,f,g)
Micro-Metals Co., Calif (a,b,c,e,f)
**Midwest Sintered Products Corp., Ill (b,c)**
**Mueller Brass Co., Mich** (a,b,c,f,g)—Ad p 455
National Molded Products, Inc., Pa (a,b,c,f,g)
National Moldite Co., NJ (c)
**Norwalk Powdered Metals, Inc., Conn (b,c,f,g,j)**
Nuclear Metals, Inc., Mass (a,b,c,e,f, g,h)
Pacific Sintered Metals Co., Calif (b, c)
Parker White Metal Co., Pa (b,c,f,g)
Picco, Inc., Calif (c)
Powder Metals Products Co., Pa (a, b,c,f,g)
Powdercraft Corp., SC (a,b,c,f,g)
Precision Metal Products Co., Pa (b,c)
Presmet Corp., Mass (b,c,f,g,j)
Pure Carbon Co., Inc., Pa (c)
Raybestos Div., Raybestos-Manhattan, Inc., Conn (a,b,c,e,f,h)
Reese Metal Products Corp., Pa (b,c,g)
Republic Steel Corp., Ohio (c)
Russell Mfg. Co., Conn (b)
St. Marys Carbon Co., Pa (b,c,f)
Schwarzkopf Development Corp., NY (a,b,c,e,f)
Sintercast Div., Chromalloy Corp., NY (a,b,c,f,g)
Sintered Metals, Inc., Mass (b,c)
Sparta Foundry Div., Muskegon Piston Ring Co., Mich (b,c)
Star Heel Plate Co., Inc., NJ (c)
Superior Carbon Products, Inc., Ohio (b,c,f,g)
**Supermet Div., Globe Industries, Inc., Ohio** (c,f,g)—Ad p 464
Torrington Co., Conn (a,b,f,g)
United Sintered Alloys, NY (a,b,c,f,g)
U.S. Graphite Co., Div. of Wickes Corp., Mich (b,c,d,f,g,j)
Uniworld Research Corp. of America, Ohio (c,f)
Veremere, E.A., Inc., Calif (a,b,c,f,g)
Wakefield Bearing Corp., Mass (b,c, f,g,h,j)
**Wellman, S.K. Co., Ohio (b,c)**
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (a,b,c,f,g,h)
**Yale & Towne Mfg. Co., Powdered Metal Products Div., Ill (b,c)**

## Metallic Coatings

**(see Diffusion Coatings; Immersion Coatings; Galvanizers; Electroplaters; Hard Facing Alloys; Preplated Metals; Metallized Coatings)**

## Metallized Coatings—Spray Metallizers

Alloy Products Corp., Wis
American Metal Products Co., Mich
**Applied Instruments, Inc., NY**
**Bisonite Co., Inc., NY**
**Continental Boiler & Sheet Iron Works, Mo**
Elmet Div., North American Phillips Co., Inc., Me
**Farwell Metal Fabricating, Minn**
**Flood City Brass & Electric Co., Pa**
**Hayden Wire Works, Inc., Mass**
**Haynes Stellite Co., Div. of Union Carbide Corp., Ind**
**Jema-American, Inc., NJ**
Linde Co., Div. of Union Carbide Corp., NY
**McGregor-Michigan Corp., Mich**
**Metal-Cladding, Inc., NY**
**Metallizing Co. of America, Ill**
**Metallizing Co. of Los Angeles, Inc., Calif**
**Metallizing Engineering Co., Inc., NY** —Ad pp 351, 360
Metalweld, Inc., Pa
Moore Dry Dock Co., Calif
New Jersey Zinc Co., NY
Parker White Metal Co., Pa
Sandy Hill Iron & Brass Works, NY
Schori Process Div., Ferro-Co Corp., NY
Schwartz Chemical Co., Inc., NY
Southern Galvanizing Co., Md
Superior Plating, Inc., Minn
Tickle, Arthur Engineering Works, Inc., NY
Wall Colmonoy Corp., Stainless Process Div., Mich
Waterbury Cos., Inc., Conn
Zeller Corp., Ohio

## Metallized Coatings—Vacuum Metallizers

**Adams Plastic Products, Ohio**
**American Metal Climax, Inc., NY**
American Metal Products Co., Mich
**Amos Molded Plastics Div., Ames-Thompson Corp., Ind**
**Applied Instruments, Inc., NY**
**Bee Chemical Co., Ill**
**Closures, Inc., Conn**
**Coating Products, Inc., NJ** —Ad p 359
Cohan Epner Co., Inc., NY
Consolidated Vacuum Corp., NY
**Cruver Mfg. Co., Ill**
**Davis Products Corp., NY**
**Dobeckmun Co., Div. of Dow Chemical Co., Ohio**
**Electrolizing Co., Ill**
Electronic Parts Mfg. Co., Inc., NJ
**Erie Resistor Corp., Plastics Div., Pa**
**Eyelet Specialty Div., International Silver Co., Conn**
**Gomar Mfg. Co., Inc., NJ**
**Hastings & Co., Inc., Pa**
**High Vacuum Equipment Corp., Mass**
Industrial Paint Div., Glidden Co., Ohio
**International Optical Co., Inc., NY**
**Jema-American, Inc., NJ**
**Kinney Mfg. Div., N.Y. Air Brake Co., Mass**
**Libbey - Owens - Ford Glass Co., Liberty Mirror Div., Pa** —Ad p 358
**Metallizing Co. of America, Ill**
**Metaplast Process, Inc., NY**
Optical Coating Laboratory, Inc., Calif
**Owens-Illinois Glass Co., Closure & Plastics Div., Ohio**
Poly-Kote, Inc., Mass
**St. Eloi Corp., Ohio**
**Schwartz Chemical Co., Inc., NY**
**Shelby Instrument Co., Calif**
Stokes, F.J. Corp., Pa
**Superior Plastics, Inc., Ill**
**Swedlow, Inc., Calif** —Ad p 263
Sylvania Electric Products, Inc., NY

## Metallized Coatings—Metallizing Wire

**Acco Steel Casting Div., American Chain & Cable Co., Inc., Pa**
**Alloy Metal Wire Co., Inc., Pa**
**Alphaloy Corp., Div. of Alpha Metals, Inc., Ill**
Belmont Smelting & Refining Works, Inc., NY
Carpenter Steel Co., Webb Wire Div., NJ
Colonial Alloys Co., Pa
Crucible Steel Co. of America, Pa
Electronic Parts Mfg. Co., Inc., NJ
Elmet Div., North American Phillips Co., Inc., Me
Empire Metal Co., NY
Hayden Wire Works, Inc., Mass
Mariane Development Co., Inc., NY
Metal Goods Corp., Mo
Metallizing Co. of America, Ill
Metallizing Co. of Los Angeles, Inc., Calif
**Metallizing Engineering Co., Inc., NY** —Ad pp 351, 360
**Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa**
Roebling's, John A. Sons Div., Colorado Fuel & Iron Corp., NJ
Rotometals, Calif
Sandvik Steel, Inc., NJ
Stainless and Strip Div., Jones & Laughlin Steel Corp., Mich
Superior Mfg. Co., Pa
United Refining & Smelting Co., Ill
uniworld Research Corp. of America, Ohio
Vanadium-Alloys Steel Co., Pa
White Metal Rolling & Stamping Corp., NY
Wright Metalcoaters, NJ

## Methyl Methacrylate

(see Acrylic Plastics)

## Mica

**Asheville-Schoonmaker Mica Co., Va (r,z,aa,cc,ee)**
**Beryl Ores Co., Colo (r,aa,cc)**
**Concord Mica Corp., NH (aa)**
**Continental-Diamond Fibre Corp., Del (r,z,cc,ee)**
**Edgar Plastic Kaolin Co., Fla (aa)**
**Farnam Mfg. Co., NC (r)**
**Foote Mineral Co., Pa (aa)**
**Franklin Mineral Products Co., NC (aa)**
Funkhouser Mills, Div. of Ruberoid Co., Md (aa)
**General Electric Co., NY (r)**
**Hall, C.P. Co., Ohio (aa)**
**Haveg Industries, Inc., Del** (bb,cc)—Ad pp 425-426
**Hayden Mica Co., Inc., Mass (aa)**
Industrial Mica Corp., NJ (cc)
**Insulation Mfrs. Corp., Ill (r,cc,ee)**
Kassel Export Co., Inc., NJ (bb,ee)
**McGean Chemical Co., Ohio (aa)**
**Mica Fabricating Co., NJ (r,aa,cc)**
**Mica Insulator Div., Minnesota Mining & Mfg. Co., NY (z,cc,ee)**
**Micacraft Products, Inc., NJ (r,cc)**
**Mycalex Corp. of America, NJ** (r,z,aa,bb,cc,dd)—Ad pp 323-326
**Peerless Products Industries, Ill (r)**
**Richmond Mica Corp., Va (aa)**
**Smith Chemical & Color Co., Inc., NY (aa)**
Sylvania Electric Products, Inc., Parts Div., Pa (r)

Synthetic Mica Co., Div. of Mycalex Corp. of America, NJ (aa)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
U.S. Mica Co., Inc., Ill (r)

## Mineral Wool

(see Inorganic Fibers)

## Molding Compounds

(see specific plastic or rubber)

## Moldings, Blow

Adams Plastic Products, Ohio (k)
American Can Co., Plastics Div., NY (k)
American Hard Rubber Co., Div. of Amerace Corp., NJ (l)
Amos Molded Plastics Div., Amos-Thompson Corp., Ind (k)
Artmor Plastics Corp., Md (k)
Brown Rubber Co., Inc., Ind (m)
Cadillac Plastic & Chemical Co., Mich (k)
CrystalX Corp., Pa (k)
Davis, Joseph Plastics Co., NJ (k)
Eclipse Plastic Industries, Inc., Fla (k)
Foster Grant Co., Mass (k)
General Plastics Corp., Ind (k)
General Plastics Mfg. Co., Wash (k,m)
Hohwieler Rubber Co., Inc., Pa (m)
Johnson Rubber Co., Ohio (m)
Lee Rubber & Tire Corp., Pa (m)
Lus-Trus Corp., Mich (k)
Luzerne Rubber Co., NJ (l)
Madin Plastics Inc., NJ (k)
Naige Co., Inc., NY (k)
Newth Rubber Co., RI (m)
Owens-Illinois Glass Co., Closure & Plastics Div., Ohio (k)
Plax Corp., Conn (k)
Rogers Corp., Conn (m)
Schwab Plastic Corp., Mich (k,m)
Seamless Rubber Co., Conn (m)
Shamban, W.S. & Co., Calif (k)
Sheller Mfg. Corp., Mich (l,m)
Shoe Form Co., Inc., DeWitt Plastics Div., NY (k)
Stockwell Rubber Co., Inc., Pa (m)
Stokes Molded Products Div., Electric Storage Battery Co., NJ (l)
Sun Rubber Co., Ohio (m)
Swedlow Inc., Calif (k,l)
Tuff Clad, Inc., Ohio (k)
Universal Unlimited, Inc., NY (k)
Wasco Products, Inc., Mass (k)
Western Felt Works, Ill (l,m)
Westlake Plastics Co., Pa (k)
Whyte Mfg. Co., Inc., NY (k,m)
Woodall Industries Inc., Mich (k)

## Moldings, Cold

Acushnet Process Co., Mass (m)—Ad p 448
American Hard Rubber Co., Div. of Amerace Corp., NJ (l)
American Insulator Corp., Pa (l)
Apex Reinforced Plastics Div., White Sewing Machine Corp., Ohio (l)
Biggs, Carl H. Co., Inc., Calif (l)
Califbe, Co., Inc., Calif (j)
Ceilcote Co., Ohio (l)
Dryden Rubber Div., Sheller Mfg. Co., Ill (m)
Dumont Corp., Calif (l)
Enflo Corp., NJ (l)
Foss Mfg. Co., Id (l)
Garfield Mfg. Co., NJ (l)
Garlock Packing Co., NY (k,m)
Halex Corp., Mich (k)
Heil Process Equipment Corp., Ohio (l)
Hohwieler Rubber Co., Inc., Pa (m)
Modern Industrial Plastics Div., Duriron Co., Ohio (l)
Raybestos Div., Raybestos-Manhattan, Inc., Conn (l)
Rostone Corp., Ind (l)
Seamless Rubber Co., Conn (m)
Schori Process Div., Ferro-Co Corp., NY (l)
Sparta Mfg. Co., Div. of U.S. Ceramic Tile Co., Ohio (k)
U.S. Gasket Plastics Div., Garlock Packing Co., NJ (l)
Warminster Fiberglass Co., Div. of Fischer & Porter Co., Pa (l)

## Moldings, Compression

Acadia Synthetic Products Div., Western Felt Works, Ill (m)—Ad p 412
Ackerman Plastic Molding Div., Consolidated Iron-Steel Mfg. Co., Ohio (l)
Acushnet Process Co., Mass (m)—Ad p 448
Admiral Corp., Molded Products Div., Ill (l)
Aerojet-General Corp., Structural Materials Div., Calif (l)
Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich (l)
Alcylite Plastics & Chemical Corp., Calif (l)
Allegheny Plastics, Inc., Pa (k)
Allied Resinous Products, Inc., Ohio (k)
American Agile Corp., Ohio (k)
American Hard Rubber Co., Div. of Amerace Corp., NJ (k,l,m)
American Insulator Corp., Pa (l)
American Plastics Corp., NY (l)
American Sinterings Div., Engineered Plastics, Inc., Conn (l)
Anderson Assoc., Inc., Ohio (l)
Apex Reinforced Plastics Div., White Sewing Machine Corp., Ohio (l)
Aries Laboratories, Inc., Conn (l)
Armstrong Cork Co., Pa (l)
Artmor Plastics Corp., Md (k)
Atlantic India Rubber Works, Inc., Ill (m)
Auburn Mfg. Co., Conn (k,m)—Ad p 450
Auburn Plastics, Inc., NY (k,l)
Automotive Rubber Co., Inc., Mich (m)
Bangor Plastics Inc., Mich (l)
Beck, I. & Sons, Inc., NY (k)
Belko Corp., Md (m)
Boonton Molding Co., NJ (k)
Bolta Products Div., General Tire & Rubber Co., Mass (l)
Button Corp. of America, NJ (l)
Cadillac Plastic & Chemical Co., Mich (k)
Camfield Fiberglass Plastics, Inc., Mich (l)
Canfield, H.O. Co., Va (l,m)
Capac Mfg. Corp., Mich (l,m)
Chemtrol, Calif (k)
Chicago Gasket Co., Ill (l)
Chicago Molded Products Corp., Ill (l)
Chicago Molded Products Corp., Custom Molding Div., Ill (l)
Chicago Rawhide Mfg Co., Ill (k,m)
Chicago-Allis Mfg. Corp., Ill (m)
Colonial Rubber Co., Div. of U.S. Stoneware Co., Ohio (k,m)—Ad p 441
Colt's Plastics Co., Inc., Conn (l,m)
Conneaut Rubber & Plastics Co., Div., of U.S. Stoneware Co., Ohio (k,l,m)
Connecticut Hard Rubber Co., Conn (m)
Consolidated Molded Products Corp., Pa (l)
Continental Rubber Works, Pa (m)
Continental-Diamond Fibre Corp., Del (k,l)
Crane Packing Co., Ill (k)
Curtiss-Wright Corp., Plastics Div., NY (l)
Curtiss-Wright Corp., Utica Div., Mich (l)
Davidson Rubber Co., Mass (l,m)
Dayton Rubber Co., Ohio (m)
Delta Plastics Co., NJ (l)
Dimco-Gray Co., Ohio (l)
Disogrin Industries, Inc., NY (m)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (k)
Dumont Corp., Calif (l)
Duriron Co., Inc., Ohio (l)
Electronic Production & Development, Inc., Chemical Div., Calif (l)
Enflo Corp., NJ (l)
Fabricon Products Div., Eagle-Picher Co., Mich (l)
Faultless Rubber Co., Ohio (m)
Fiber Glass Industries, Inc., NY (l)
Fibercast Div., Youngstown Sheet & Tube Co., Okla (l)
Fiberglass Ohio Inc., Ohio (l)
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (l,m)
Firestone Tire & Rubber Co., Ohio (m)
Garfield Mfg. Co., NJ (l)
Garlock Packing Co., NY (k,m)
Gatke Corp., Ill (l)
Geauga Industries Co., Ohio (m)
General American Transportation Corp., Ill (k,l)
General American Transportation Corp., Plastics Div., Ill (k,l)—Ad p 411
General Electric Co., Chemical & Metallurgical Div., Ill (l)
General Electric Co., Plastics Dept., Ill (l,m)
General Gasket, Inc., Conn (m)
General Industries Co., Molded Plastic Div., Ohio (l)
Glass Reinforced Plastics Corp., Ohio (l)
Glastic Corp., Ohio (l)
Goodrich, B.F. Industrial Products Co., Ohio (k)
Goshen Rubber Co., Inc., Ind (m)—Ad p 438
Greene, Tweed & Co., Pa (k,l,m)
Grimes Mfg. Co., Plastic Research Products Div., Ohio (l)
Halogen Insulator & Seal Corp., Ill (l)
Havog Industries, Inc., Del (l)—Ad pp 425-426
Hawkeye Rubber Mfg. Co., Iowa (m)
Hawley Products Co., Ill (l) (m)
Hays Mfg. Co., Pa (l)
Hohwieler Rubber Co., Inc., Pa (m)
Industrial Molded Products Co., Inc., Ill (l)
Industrial Products Div., General Tire & Rubber Co., Ind (m)
Insulation Products Co., Pa (l)
International Packings Corp., NH (m)—Ad p 416
Jersey Plastic & Die Casting Co., NJ (l)
Johnson Rubber Co., Ohio (m)
Judsen Rubber Works, Inc., Ill (m)
Kerrco, Neb (k,l)
Kirkhill Rubber Co., Calif (m)
Kuhn & Jacob Molding & Tool Co., NJ (l)
Kurz Kasch, Inc., Ohio (l)
Lamtex Industries, Inc., NY (l)
Lavelle Rubber Co., Ill (m)
Lee Rubber & Tire Corp., Pa (m)
Lewis, G.B. Co., Wis (l)—Ad p 432
Lone Star Plastics Co., Inc., Tex (l)
Loranger Mfg. Corp., Pa (l)
Lunn Laminates, Inc., NY (l)
Luzerne Rubber Co., NJ (k,l)
Mack Molding Co., NJ (l)
Maloney, F.H. Co., Tex (l,m)
Martin Rubber Co., Inc., NJ (m)
Mesa Plastics Co., Calif (l)
Micarta Div., Westinghouse Electric Corp., SC (k,l,m)
Mid-States Rubber Products, Inc., Ind (m)
Midwest Molding & Mfg. Co., Ill (l)
Midwest Rubber Co., Mich (m)
Minneapolis Plastic Molders, Inc., Minn (l)
Minnesota Rubber Co., Minn (m)
Modern Industrial Plastics Div., Duriron Co., Ohio (l)
Modern Plastics Corp., Mich (l)
Molded Fiber Glass Co., Ohio (l)
Morrell, George Corp., Mich (l)
Moxness Products, Inc., Wis (l,m)—Ad p 460
National Lock Co., Ill (l)
Newth Rubber Co., RI (m)
Owens-Illinois Glass Co., Closure & Plastics Div., Ohio (l)
Pacific Moulded Products Corp., Calif (m)
Paeco Rubber Co., Inc., Ohio (k,l,m)
Panelyte Div., St. Regis Paper Co., NJ (l)
Parker Appliance Co., Rubber Products Div., Ohio (m)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (m)
Parker, Stearns & Co., Inc., NY (m)
Perry Plastics, Inc., Pa (k,l)
Plastic Masters, Inc., Mich (l)
Plastic Products Corp., Ohio (l)
Plasticrafters, Inc., Ill (l)
Precision Rubber Products Corp., Ohio (m)
Raybestos-Manhattan, Inc., NJ (l,m)

### KEY

**MATERIALS**

a—Aluminum and its alloys
b—Copper and its alloys
c—Iron and its alloys (except steel)
d—Lead and its alloys
e—Magnesium and its alloys
f—Nickel and its alloys
g—Steels
h—Titanium and its alloys
j—Zinc and its alloys
k—Thermoplastics
l—Thermosetting plastics
m—Elastomers

**BASIC FORMS**

n—Anodes
o—Bar
p—Base resins, polymers or gums
q—Billets
r—Custom formed parts (incl. specialties)
s—Fibers
t—Film
u—Foams (component materials or products)
v—Foil
w—Ingot
x—Laminating, casting resins
y—Molding compounds
z—Plate
aa—Powder
bb—Rod
cc—Sheet
dd—Strip
ee—Tubing
ff—Wire

Regal Plastic Co., Mo (l)
Reinhold Engineering & Plastics Co., Inc., Calif (l)
Resistoflex Corp., NJ (k)
Richardson Co., NY (l)
Riverside Plastics Corp., NY (l)
Roberts Toledo Rubber Co., Ohio (m)
Rogers Corp., Conn (l,m)
Rogers, V.F. Plastic Molding, Colo (l,m)
Romar Plastics, Inc., Ill (l)
Rostone Corp., Ind (l)
Roth Rubber Co., Ill (l,m)
Russell Reinforced Plastics Corp., NY (l)
St. Clair Rubber Co., Mich (m)
Sealview Plastics, Inc., Pa (l)
Shamban, W.S. & Co., Calif (k)
Shaw Insulator Co., NJ (l)
Sheller Mfg. Corp., Mich (k,l,m)
Sierra Electric Corp., Calif (l)
Sierra Engineering Co., Calif (m)
Sillcocks Miller Co., NJ (k)
Southern Plastics Co., SC (l)
Sparta Mfg. Co., Div. of U.S. Ceramic Tile Co., Ohio (k)
Spencer Rubber Co., Conn (m)
Stalwart Rubber Co., Ohio (m)
Standard Plastics Co., Mass (l)
Stillman Rubber Co., Calif (m)
Stockwell Rubber Co., Inc., Pa (k,l,m)
Stokes Molded Products Div., Electric Storage Battery Co., NJ (l)
Stowe-Woodward, Inc., Mass (m)
Structural Fibers, Inc., Ohio (l)
Sun Rubber Co., Ohio (m)
Swedish Crucible Steel Co., Mich (k)
Swedlow, Inc., Calif (l)
Sylvania Electric Products, Inc., Parts Div., Pa (l)
Synthane Corp., Pa (l)
Taunton Div., Haveg Industries, Inc., Mass (k,l,m)
Texstar Plastics Div., Texstar Corp., Tex (k,l)
Thermoid Div., H.K. Porter Co., Pa (l)
Tingley Rubber Corp., NJ (m)
Toledo Industrial Rubber Co., Ohio (l,m)
Toyad Corp., Pa (k,m)
Trostel, Albert Packing, Ltd., Wis (m)
Tyer Rubber Co., Mass (m)
U.S. Gasket Plastics Div., Garlock Packing Co., NJ (k,l)
U.S. Rubber Co., Mechanical Goods Div., Ind (l)
U.S. Stoneware Co., NY (k,l)
Vulcanized Rubber & Plastics Co., Pa (m)
Waldman, Joseph & Sons, Epoxy Products Div., NJ (l)
Warminster Fiberglass Co., Div. of Fischer & Porter Co., Pa (l)
Waterbury Cos., Inc., Conn (l)
Weshar Stamping Corp., Wis (m)
Western Felt Works, Ill (l,m)
Westlake Plastics Co., Pa (k)
Whitco, Inc., Ill (l)
**Williams - Bowman Rubber Co., Ill**
(l,m)—Ad p 276
Wittman, Lawrence & Co., NY (l)
Woodall Industries, Inc., Mich (k,l)
Wyatt Industries Inc., Plastic & Rubber Div., Tex (l,m)
Yale Rubber Mfg. Co., Mich (m)
Zenith Plastics Co., Calif (l)

## Moldings, Injection

aaRBee Plastic Co., Calif (k)
**Acushnet Process Co., Mass** (m)—Ad p 448
Adams Plastic Products, Ohio (k)
Admiral Corp., Molded Products Div., Ill (k)
Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich (k)
American Agile Corp., Ohio (k)
American Can Co., Plastics Div., NY (k)
American Hard Rubber Co., Div. of Amerace Corp., NJ (k,m)
American Insulator Corp., Pa (k,m)
American Plastics Corp., NY (k)
Amos Molded Plastics Div., Amos-Thompson Corp., Ind (k)
Anderson Assoc., Inc., Ohio (k)
Anthes Div., Gleason Corp., Iowa (k,l)
Armstrong Cork Co., Pa (k)
**Auburn Mfg. Co., Conn** (k,m)—Ad p 450
Auburn Plastics, Inc., NY (k,m)
Auburn Rubber Co., Inc., Ind (k)
Belke Corp., Md (m)
Bolta Products Div., General Tire & Rubber Co., Mass (k)
Booker & Wallestad, Inc., Minn (k)
Boonton Molding Co., NJ (k)
Bridgeport Moulded Products, Inc., Conn (k)
Buckeye Molding Co., Ohio (k)
Burwood Products Co., Mich (k)
Byrd Plastics, Inc., Pa (k)
Cambridge-Panelyte Molded Plastics Co., Div. of St. Regis Paper Co., Ohio (k)
Campro Co., Ohio (k)
Canfield, H.O. Co., Va (l,m)
Carlon Products Corp., Ohio (k)
Celluplastic Corp., NJ (k)
Chemtrol, Calif (k)
Chicago Molded Products Corp., Ill (k)
Chicago Molded Products Corp., Custom Molding Div., Ill (k)
Chicago-Allis Mfg. Corp., Ill (m)
Clover Industries, Inc., NY (k)
Colonial Plastics Mfg. Co., Div. of Van Dorn Iron Works Co., Ohio (k)
Colt's Plastics Co., Inc., Conn (k)
Comet Metal Products Co., Inc., NY (k)
Commercial Plastics Co., Ill (k)
Commercial Plastics Co., Associated Plastic Div., Mich (k)
Conneaut Rubber & Plastics Co., Div. of U.S. Stoneware Co., Ohio (k,l,m)
Consolidated Molded Products Corp., Pa (k)
Continental Rubber Works, Pa (m)
Continental-Diamond Fibre Corp., Del (k)
Cosmo Plastics Co., Ohio (k)
Cruver Mfg. Co., Ill (k)
CrystalX Corp., Pa (k)
Curtiss-Wright Corp., Plastics Div., NY (k)
Danielson Mfg. Co., Conn (k)
Dapol Plastics, Inc., Mass (k,l)
Dayton Rogers Mfg. Co., Minn (k,l)
Delta Plastics Co., NJ (k)
Denver Plastics, Inc., Colo (k)
Detroit Macoid Corp., Mich (k,m)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (k,m)
Electronic Production & Development, Inc., Chemical Div., Calif (k)
Engineered Nylon Products Div., Kennatrack Corp., Ind (k)
Erie Resistor Corp., Plastics Div., Pa (k)
Fabricon Products Div., Eagle-Picher Co., Mich (k)
Federal Tool Corp., Ill (k)
Fiberglass Ohio Inc., Ohio (l)
Foster Grant Co., Mass (k)
Franklin Plastics, Inc., Pa (k)
Fry Plastics International, Calif (k)
Galigher Co., Utah (k,l)
Garlock Packing Co., NY (k)
Geauga Industries Co., Ohio (m)
General American Transportation Corp., Ill (k)
**General American Transportation Corp., Plastics Div., Ill** (k)—Ad p 411
General Electric Co., Chemical & Metallurgical Div., Ill (k)
General Electric Co., Plastics Dept., Ill (k)
General Industries Co., Molded Plastic Div., Ohio (k)
Glass Laboratories, Inc., NY (k)
Goodrich, B.F. Industrial Products Co., Ohio (k)
Gossett and Hill Co., Ill (k)
Gotham Plastics Corp., NY (k)
Gries Reproducer Corp., NY (k)
H & R Industries, Pa (k)
Hauser Products, Inc., Ill (l)
Hewitt-Robins, Inc., Conn (m)
Hungerford Plastics Corp., NJ (k,m)
Industrial Molded Products Co., Inc., Ill (k)
Industrial Products Div., General Tire & Rubber Co., Ind (k)
Jamison Plastic Corp., NY (k)
Jersey Plastic & Die Casting Co., NJ (k)
Jet Specialties Co., Inc., Calif (k)
Johnson Plastic Corp., Ohio (k,m)
Judsen Rubber Works, Inc., Ill (m)
Keolya Plastics, Inc., Ill (k)
Kerrco, Neb (k,l)
Kirk, F.J. Co., Inc., Mass (k)
Lancaster Glass Corp., Ohio (k)
Lee Rubber & Tire Corp., Pa (m)
Lincoln Molded Plastics, Inc., Ohio (k)
Lone Star Plastics Co., Inc., Tex (k)
Loranger Mfg. Corp., Pa (k)
Luminous Resins, Inc., Ill (k)
Luzerne Rubber Co., NJ (k)
Mack Molding Co., NJ (k)
Madin Plastics Inc., NJ (k)
Mallory, P.R. Plastics, Inc., Ill (k)
Maloney, F.H. Co., Tex (k)
Michigan Plastic Products, Inc., Mich (k)
Midwest Molding & Mfg. Co., Ill (k)
Minneapolis Plastic Molders, Inc., Minn (k)
Minnesota Plastics Corp., Minn (k,m)
Minnesota Rubber Co., Minn (m)
Modern Industrial Plastics Div., Durion Co., Ohio (k)
Modern Plastics Corp., Mich (k)
**Moxness Products, Inc., Wis** (k)—Ad p 460
**Mueller Brass Co., Mich** (k)—Ad p 455
Nalge Co., Inc., NY (k)
National Lock Co., Ill (k)
Norgren-Stemac, Inc., Colo (k)
Nosco Plastics Co., Pa (k)
Nylon Molded Products Corp., Ohio (k)
Nyloncraft, Inc., Ind (k)
Ohio Rubber Co., Ohio (k)
O'Sullivan Rubber Corp., Va (k)
Owens-Illinois Glass Co., Closure & Plastics Div., Ohio (k)
Paeco Rubber Co., Inc., Ohio (k,l,m)
Panelyte Div., St. Regis Paper Co., NJ (k)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (m)
Pee Wee Molding Corp., NY (k)
Peoria Plastic Co., Ill (k)
Perfex Plastics, Inc., Ill (k)
Perry Plastics, Inc., Pa (k,l)
Pipco International Corp., Sub. of Plastiglide Mfg. Corp., Calif (k)
Plastic Engineering, Inc., Ohio (k)
Plastic Masters, Inc., Mich (k)
Plasticrafters, Inc., Ill (k,m)
Plastiglide Mfg. Corp., Calif (k)
Plax Corp., Conn (k)
Plymouth Industrial Products, Wis (k)
Porter, William Co., Calif (k)
Precision Plastics Co., Pa (k)
Prince Rubber & Plastics Products, Inc., NY (k,l)
**Pyramid Products Co., Inc., Ohio** (k)—Ad p 458
Pyro Plastics Corp., NJ (k)
Quinn-Berry Corp., Pa (k)
Raybestos-Manhattan, Inc., NJ (m)
Roberts Toledo Rubber Co., Ohio (m)
Rogers, V.F. Plastic Molding, Colo (k)
Romar Plastics, Inc., Ill (k)
St. Clair Rubber Co., Mich (m)
Sanford Plastics Corp., NY (k)
Santay Corp., Ill (k)
Saran Lined Pipe Co., Div. of Michigan Pipe Co., Mich (k)
Schaefer-Hausner Corp., NY (k)
Schwab Plastic Corp., Mich (k)
Shamban, W.S. & Co., Calif (k)
Shaw Insulator Co., NJ (k)
Sheller Mfg. Corp., Mich (k,l,m)
Sierra Electric Corp., Calif (k)
Sillcocks Miller Co., NJ (k)
Sinko Mfg. & Tool Co., Ill (k)
Standard Plastics Co., Mass (k)
Sterling Molders, Inc., NY (k)
Stockwell Rubber Co., Inc., Pa (m)
Stokes Molded Products, Div. of Electric Storage Battery Co., NJ (l)
Superior Plastics, Inc., Ill (k)
Sylvania Electric Products, Inc., Parts Div., Pa (k)
Taunton Div., Haveg Industries, Inc., Mass (k)
Tingley Rubber Corp., NJ (k)
Toledo Industrial Rubber Co., Ohio (l,m)
Tri-State Plastic Molding Co., Ky (k)
Tube Turns Plastics, Inc., Ky (k)
U.S. Gasket Plastics Div., Garlock Packing Co., NJ (k)
U.S. Rubber Co., Mechanical Goods Div., Ind (k)
United-Carr Fastener Corp., Mass (k,l)
Vulcanized Rubber & Plastics Co., Pa (k,m)
Wagner Plastic Corp., NJ (k)
Waterbury Cos., Inc., Conn (k)
Western Felt Works, Ill (l,m)
Westlake Plastics Co., Pa (k)
Whyte Mfg. Co., Inc., NY (k,m)
Worcester Moulded Plastics Co., Mass (k)
Zenith Plastics Co., Calif (l)

## Moldings, Reinforced Plastics

(see Laminates)

## Moldings, Sheet

(sheet formed parts)

Aerojet-General Corp., Structural Materials Div., Calif (l)
Allied Resinous Products, Inc., Ohio (k)
American Agile Corp., Ohio (k)
American Hard Rubber Co., Div. of Amerace Corp., NJ (k,l)
American Plastics Corp., NY (k)
American Polyglas Corp., NJ (l)
Amos Molded Plastics Div., Amos-Thompson Corp., Ind (k)
Artmor Plastics Corp., Md (k)
Auburn Rubber Co., Inc., Ind (k)
Blank, Arthur & Co., Inc., Mass (k)
Borkland Mfg. Co., Ind (k)
Brown Rubber Co., Inc., Ind (m)
Cadillac Plastic & Chemical Co., Mich (k,l)
Cambridge-Panelyte Molded Plastics Co., Div. of St. Regis Paper Co., Ohio (k)
Canfield, H.O. Co., Va (l,m)
Carolina Industrial Plastics Div., Essex Wire Corp., NC (k)
Carroll, J.B. Co., Ill (k)
Chicago-Allis Mfg. Corp., Ill (m)
Cincinnati Industries Inc., Ohio (k)
Colonial Art Co., Inc., Mass (k)
**Colonial Rubber Co., Div. of U.S. Stoneware Co., Ohio** (k,m)—Ad p 441
Connecticut Hard Rubber Co., Conn (m)
Consolidated Molded Products Corp., Pa (k)
Continental Rubber Works, Pa (m)
Continental-Diamond Fibre Corp., Del (k,l)
CrystalX Corp., Pa (k)
Curbell, Inc., NY (k)
Duplican Corp., Mass (k)
Dryden Rubber Div., Sheller Mfg. Co., Ill (m)
Dura Plastics of New York, Inc., NY (k)
Enflo Corp., NJ (l)
Fabricon Products Div., Eagle-Picher Co., Mich (l)
Falge Engineering Corp., Md (k)
Federal Tool Corp., Ill (k)
Fiber Glass Industries, Inc., NY (l)
Formica Corp., Sub. of American Cyanamid Co., Ohio (l)

Foster Grant Co., Mass (k)
Fry Plastics International, Calif (k)
Galigher Co., Utah (k)
Garlock Packing Co., NY (k,m)
General American Transportation Corp., Ill (k)
**General American Transportation Corp., Plastics Div., Ill**
(k)—Ad p 411
General Electric Co., Chemical & Metallurgical Div., Ill (m)
General Plastics Corp., Ind (k)
General Plastics Mfg. Co., Wash (k,m)
General Tire & Rubber Co., Ind (l)
Glastic Corp., Ohio (l)
H & R Industries, Pa (k)
**Haveg Industries, Inc., Del**
(l)—Ad pp 425-426
Hays Mfg. Co., Pa (l)
Heil Process Equipment Corp., Ohio (k,l,m)
Hewitt-Robins, Inc., Conn (m)
Hohwieler Rubber Co., Inc., Pa (m)
Klise Mfg. Co., Mich (k)
Lone Star Plastics Co., Inc., Tex (k)
Luminous Resins, Inc., Ill (k)
Lunn Laminates, Inc., NY (k,l)
Lus-Trus Corp., Mich (k)
Luzerne Rubber Co., NJ (k,l)
Madin Plastics Inc., NJ (k)
Marbiette Corp., NY (l)
Mica Insulator Co., NY (l)
Micarta Div., Westinghouse Electric Corp., SC (k,l)
Midwest Plastic Products Co., Ill (k)
Minnesota Mining & Mfg. Co., Minn (l)
Nalge Co., Inc., NY (k)
National Vulcanized Fibre Co., Del (l)
Newth Rubber Co., RI (m)
Nopco Chemical Co., NJ (l)
O'Sullivan Rubber Corp., Va (k)
Panelyte Div., St. Regis Paper Co., NJ (k)
Plastic Products Corp., Ohio (k)
Pyro Plastics Corp., NJ (k)
Pyrosil, Inc., Ohio (l)
Quelcor, Inc., Pa (k)
Regal Plastic Co., Mo (k)
Reinhold Engineering & Plastics Co., Inc., Calif (l)
Rogers Corp., Conn (l,m)
St. Clair Rubber Co., Mich (m)
Schori Process Div., Ferro-Co Corp., NY (l)
Sealview Plastics, Inc., Pa (k)
Seamless Rubber Co., Conn (m)
Shamban, W.S. & Co., Ind (k)
Shoe Form Co., Inc., DeWitt Plastics Div., NY (k)
Sierra Electric Corp., Calif (k,l)
Silicocks Miller Co., NJ (k)
Snyder Mfg. Co., Inc., Ohio (k)
Sparta Mfg. Co., Div. of U.S. Ceramic Tile Co., Ohio (k)
Strick Plastic Co., Pa (k,m)
Superior Plastics, Inc., Ill (k)
Swedlow, Inc., Calif (k,l)
Synthane Corp., Pa (l)
Taunton Div., Haveg Industries, Inc., Mass (m)
Texstar Plastics Div., Texstar Corp., Tex (k,l)
Toyad Corp., Pa (k)
Tuff Clad, Inc., Ohio (k)
U.S. Gasket Plastics Div., Garlock Packing Co., NJ (k,l)
U.S. Rubber Co., Mechanical Goods Div., Ind (k)
Universal Unlimited, Inc., NY (k)
Valley-National Corp., Conn (k)
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (m)
Western Felt Works, Ill (l,m)
Westlake Plastics Co., Pa (k)
**Williams-Bowman Rubber Co., Ill**
(l,m)—Ad p 276
Woodall Industries, Inc., Mich (k)

## Moldings, Slush

(plastics and rubber)

American Agile Corp., Ohio (k)
Automotive Rubber Co., Inc., Mich (m)
Boonton Molding Co., NJ (m)
Borden Co., Borden Chemical Div., NY (k)
Chicago-Allis Mfg. Corp., Ill (m)
Dennis Chemical Co., Mo (k)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (k)
Dumont Corp., Calif (l)
Hungerford Plastics Corp., NJ (k,m)
Madin Plastics Inc., NJ (k)
Munray Products Div., Fanner Mfg. Co., Ohio (k,l,m)
Pyrosil, Inc., Ohio (l)
Quelcor, Inc., Pa (k)
Sheller Mfg. Corp., Mich (k,l,m)
Steere Enterprises, Inc., Ohio (m)
Tuff Clad, Inc., Ohio (k)
U.S. Stoneware Co., Ohio (k)
Western Textile Products Co., Mo (k,m)

## Moldings, Transfer

Accurate Molding Corp., NY (l)
**Acushnet Process Co., Mass**
(m)—Ad p 448
Admiral Corp., Molded Products Div., Ill (l)
Aerojet-General Corp., Structural Materials Div., Calif (l)
Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich (l)
Alcylite Plastics & Chemical Corp., Calif (l)
American Hard Rubber Co., Div. of Amerace Corp., NJ (k,l)
American Insulator Corp., Pa (l)
American Plastics Corp., NY (l)
American Sinterings Div., Engineered Plastics, Inc., Conn (l)
**Auburn Mfg. Co., Conn**
(k)—Ad p 450
Auburn Plastics, Inc., NY (l)
Automotive Rubber Co., Inc., Mich (m)
Bangor Plastics, Inc., Mich (l)
Belko Corp., Md (m)
Biwax Corp., Ill (l)
Bond International, Inc., Mich (m)
Booker & Wallestad, Inc., Minn (l)
Boonton Molding Co., NJ (k)
Bridgeport Moulded Products, Inc., Conn (l)
Canfield, H.O. Co., Va (l,m)
Capac Mfg. Corp., Mich (l,m)
Chicago Molded Products Corp., Ill (l)
Chicago Molded Products Corp., Custom Molding Div., Ill (l)
Chicago Rawhide Mfg. Co., Ill (k,m)
Chicago-Allis Mfg. Corp., Ill (m)
Cincinnati Industries Inc., Ohio (k,l)
**Colonial Rubber Co., Div. of U.S. Stoneware Co., Ohio**
(k,m)—Ad p 441
Colt's Plastics Co., Inc., Conn (l)
Consolidated Molded Products Corp., Pa (l)
Continental Rubber Works, Pa (m)
Dayton Rogers Mfg. Co., Minn (k,l)
Dayton Rubber Co., Ohio (m)
Dayton Rubber Co., Molded Products Div., Mich (l)
Delta Plastics Co., NJ (l)
Dimco-Gray Co., Ohio (l)
Disogrin Industries, Inc., NY (m)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (k)
Electronic Production & Development, Inc., Chemical Div., Calif (l)
Faultless Rubber Co., Ohio (m)
Fiberglass Ohio Inc., Ohio (l)
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (m)
Formica Corp., Sub. of American Cyanamid Co., Ohio (k)
Galigher Co., Utah (m)
Garfield Mfg. Co., NJ (l)
Garlock Packing Co., NY (k,m)
General American Transportation Corp., Ill (k,l)
**General American Transportation Corp., Plastics Div., Ill**
(l)—Ad p 411
General Electric Co., Chemical & Metallurgical Div., Ill (l)
General Electric Co., Plastics Dept., Ill (l,m)
General Industries Co., Molded Plastic Div., Ohio (l)
Goodrich, B.F. Industrial Products Co., Ohio (k)
Grimes Mfg. Co., Plastic Research Products Div., Ohio (l)
**Haveg Industries, Inc., Del**
(l)—Ad pp 425-426
Hawkeye Rubber Mfg. Co., Iowa (m)
Hohwieler Rubber Co., Inc., Pa (m)
Houghton, E.F. & Co., Pa (m)
Industrial Molded Products Co., Inc., Ill (l)
Insulation Products Co., Pa (l)
Johnson Rubber Co., Ohio (m)
Judsen Rubber Works, Inc., Ill (m)
Kerrco, Neb (k,l)
Kurz Kasch, Inc., Ohio (l)
Lee Rubber & Tire Corp., Pa (m)
Lone Star Plastics Co., Inc., Tex (l)
Loranger Mfg. Corp., Pa (l)
Luzerne Rubber Co., NJ (k,l)
Mack Molding Co., NJ (l)
Marion Div., General Tire & Rubber Co., Ind (l)
Martin Rubber Co., Inc., NJ (m)
Mesa Plastics Co., Calif (l)
Mid-States Rubber Products, Inc., Ind (m)
Midwest Molding & Mfg. Co., Ill (l)
Minnesota Rubber Co., Minn (l,m)
**Moxness Products, Inc., Wis**
(l,m)—Ad p 460
National Lock Co., Ill (l)
Paeco Rubber Co., Inc., Ohio (k,l,m)
Panelyte Div., St. Regis Paper Co., NJ (l)
Parker Appliance Co., Rubber Products Div., Ohio (m)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (m)
Perry Plastics, Inc., Pa (l)
Plastic Research Products Co., Div. of Grimes Mfg. Co., Ohio (l)
Plasticrafters, Inc., Ill (l)
Porter, William Co., Calif (l)
Precision Rubber Products Corp., Ohio (m)
Raybestos-Manhattan, Inc., NJ (m)
Reinhold Engineering & Plastics Co., Inc., Calif (l)
Resistoflex Corp., NJ (k)
Richardson Co., NY (l)
Rogers, V.F. Plastic Molding, Colo (l,m)
Romar Plastics, Inc., Ill (l)
Rostone Corp., Ind (l)
Roth Rubber Co., Ill (m)
St. Clair Rubber Co., Mich (m)
Seamless Rubber Co., Conn (m)
Shaw Insulator Co., NJ (l)
Sheller Mfg. Corp., Mich (k,l,m)
Sierra Electric Corp., Calif (l)
Sierra Engineering Co., Calif (m)
Southern Plastics Co., SC (l)
Standard Plastics Co., Mass (l)
Stockwell Rubber Co., Inc., Pa (m)
Stokes Molded Products, Div. of Electric Storage Battery Co., NJ (l)
Stowe-Woodward, Inc., Mass (m)
Sun Rubber Co., Ohio (m)
Sylvania Electric Products, Inc., Parts Div., Pa (l)
Taunton Div., Haveg Industries, Inc., Mass (k,l,m)
Tingley Rubber Corp., NJ (m)
Toledo Industrial Rubber Co., Ohio (l,m)
Trostel, Albert Packing, Ltd., Wis (m)
U.S. Rubber Co., Mechanical Goods Div., Ind (l)
Vulcanized Rubber & Plastics Co., Pa (m)
Waldman, Joseph & Sons, Epoxy Products Div., NJ (l)
Waterbury Cos. Inc., Conn (l)
Western Felt Works, Ill (l,m)
Whitso, Inc., Ill (l)
**Williams-Bowman Rubber Co., Ill**
(l,m)—Ad p 276
Wyatt Industries Inc., Plastic & Rubber Div., Tex (l,m)

**KEY**

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

## Molybdenum and Its Alloys

Alloy Metal Products, Inc., Iowa (o,w)
Alpha Metals, Inc., NJ (cc,dd)
Amalgamated Steel Corp., Ohio (o,bb)
American Metal Climax, Inc., NY (o,q,z,aa,bb,cc,dd)
American Nickel Alloy Mfg. Corp., NY (w,aa)
American Silver Co., NY (v,dd,ee,ff)
Associated Engineering & Mfg. Corp., NJ (n,o,aa,bb,cc,dd,ee,ff)
Belmont Smelting & Refining Works, Inc., NY (o,w,aa)
Bridgeport Brass Co., Conn (ee)
Cleveland Tungsten Inc., Ohio (aa,bb,ee)

Climax Molybdenum Div., American Metal Climax, Inc., NY (o,q,w,z,bb, cc,dd)
Crucible Steel Co. of America, Titanium & Vacuum Metals Product Div., Pa (o,q,w,z,cc,dd)
Damascus Tube Co., Pa (ee)
Electronic Parts Mfg. Co., Inc., NJ (z,bb,cc,ee,ff)
Elmet Div., North American Phillips Co., Inc., Me (o,w,z,aa,bb,cc,dd,ff)
**Fanstee! Metallurgical Corp., Ill** (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff) — Ad p 174
Firth Sterling, Inc., Pa (q)
General Electric Co., Lamp Metals & Components Dept., Ohio (o,q,w,aa,bb, cc,dd,ff)
Hamilton Watch Co, Precision Metals Div., Pa (v,dd,ff)
Hardy, Charles, Inc., NY (aa)
Harvey Aluminum, Calif (o,bb)
Hayden Wire Works, Inc., Mass (aa,ff)
Johnston & Funk Titanium Corp., Ohio (bb,ff)
Kassel Export Co., Inc., NJ (v,bb,dd, ee,ff)
Mallory, P.R. & Co., Inc., Ind (aa, bb)
Mallory-Schwarzkopf Metals, Inc., NY (o,v,w,z,bb,cc,dd,ee,ff)
Metal & Thermit Corp., NJ (w)
Metallizing Co. of Los Angeles, Inc., Calif (ff)
Metallizing Engineering Co., Inc., NY (ff)
Molybdenum Corp. of America, Pa (o,w,z,aa,bb,cc,dd)
**National-Standard Co., Mich** (ff)—Ad p 421
North American Phillips Co., Inc., Me (aa)
Nuclear Metals, Inc., Mass (w,ee)
Oregon Metallurgical Corp., Ore (w)
Reduction & Refining Co., NJ (q,w,aa, bb,ff)
Rodney Metals, Inc., Mass (v,dd)
Shieldalloy Corp., NJ (aa)
**Stauffer Chemical Co., NY** (q)—Ad p 163
Stauffer-Temescal Co., Calif (q,w)
**Sylvania Electric Products, Inc., Chemical & Metallurgical Div., Pa** (n,w,aa,bb,ff)—Ad p 153
Tube Distributors Co., Inc., NY (ee)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
Universal-Cyclops Steel Corp., Pa (o,q, z,cc)
Utica General Jobbing Foundry, Inc., NY (aa)
**Wah Chang Corp., NY** (n,aa,bb,ff)—Ad p 164
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,v,w,z,bb, cc,dd,ee)

## Monel

(see Nickel)

## Neoprene

(see Chloroprene Rubber)

## Nickel and Its Alloys

**Advance Stamping Co., Miuh (dd)**
Allied Research Products, Inc., Md (n)
Alloy Metal Powders, Inc., NY (aa)
Alloy Metal Products, Inc., Iowa (o, w)
Amalgamated Steel Corp., Ohio (o,bb)
American Metal Climax, Inc., NY (aa)
**American Nickel Alloy Mfg. Corp.,NY** (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
American Silver Co., NY (v,dd,ee,ff)
American Smelting & Refining Co., NY (n,w)
Arcos Corp., Pa (ff)
Auld, D.L. Co., Ohio (n)
Austenal Co., Div. of Howe Sound Co., NY (w)
Bart Mfg. Corp., NJ (aa)
Belmont Smelting & Refining Works, Inc., NY (n,o,w,aa)
Biddle Screw Products Co., Ind (o, bb,ee)
Bishop, J. & Co. Platinum Works, Pa (ee,ff)
Bridgeport Brass Co., Conn (bb,cc,dd, ee,ff)
**Brinkerhoff Brass & Bronze Works, Inc., NY (cc,dd)**
Brush Beryllium Co., Ohio (w)
Cannon-Muskegon Corp., Mich (o,v,w, cc,dd,ff)
Carpenter Steel Co., Webb Wire Div., NJ (ff)
**Central Fabricators, Inc., Ohio** (z, bb,cc,ee)
Chase Brass & Copper Co., Inc., Sub. of Kennecott Copper Corp., Conn (o,bb,cc,ee)
Chicago Steel Service Co., Ill (o,q,z, bb,cc,dd,ee,ff)
Chromium Corp. of America, NY (v)
Craft Metal Spinning Co., Ill (cc)
Crane Co., Metals Div., Pa (aa)
**Crucible Steel Co. of America, Titanium and Vacuum Metal Products Div., Pa** (o,q,v,z,bb,cc,dd,ee,ff)
Damascus Tube Co., Pa (ee)
Designers Metal Corp., Ill (cc)
Dixon Sintaloy, Inc., Conn (o)
Dormont Mfg. Co., Pa (ee)
**Driver, Wilbur B. Co., NJ** (v,bb,dd,ff)—Ad p 185
Driver-Harris Co., NJ (v,bb,dd,ff)
Electronic Parts Mfg. Co., Inc., NJ (bb,dd,ee,ff)
**Elgin National Watch Co., Abrasives Div., Ill** (o,bb,dd,ff)
Erskine Precision Wire Corp., Pa (ff)
Federated Metals Div., American Smelting & Refining Co., NY (n)
Foote Mineral Co., Pa (w,aa)
Fox Products Co., Pa (n)
Fromson Orban Co., Inc., NY (ee)
General Electric Co., Metallurgical Products Dept., Mich (q,w,aa,bb,cc, dd)
General Plate Div., Metals & Controls Corp., Mass (v,cc,dd)
**Gibson Electric Co., Pa.** (bb,dd,ff)—Ad p 466
Grand Rapids Brass Co., Mich (z)
Hamilton Watch Co., Precision Metals Div., Pa (v,w,bb,dd)
Hardy, Charles, Inc., NY (aa)
Harshaw Chemical Co., Ohio (n)
Hayden Wire Works, Inc., Mass (aa,ff)
Haynes Stellite Co., Div. of Union Carbide Corp., Ind (o,q,v,w,z,aa,bb, cc,dd,ee,ff)
Horton-Angell Co., Mass (n,o,bb,cc, ee,ff)
**Hoskins Mfg. Co., Mich** (bb,dd,ff)—Ad p 177
International Nickel Co., Inc., NY (n,z,bb,cc,dd,ee,ff)
Jelliff, C.O. Mfg. Corp., Conn (ff)
K. & L. Plating Co., Pa (z)
Kanthal Corp., Conn (bb,dd,ff)
Kelsey-Hayes Co., Mich (o,q,z,cc)
Kelsey-Hayes Co., Metals Div., NY (o,q,v,w,z,bb,cc,dd,ff)
Kinkead Industries, Inc., Ill (cc,dd)
Lakeland Industries, Minn (z)
Lavin, R. & Sons, Inc., Ill (w)
Leach & Garner Co., Industrial Div., Mass (w,cc,dd,ee,ff)
McGean Chemical Co., Ohio (n,o,bb,dd)
Metal Forming Corp., Div. of Vanadium-Alloys Co., Ind (ee)
Metal Goods Corp., Mo (o,z,bb,cc,dd, ee,ff)
Metal Hybrides, Inc., Mass (aa)
Metallizing Co. of Los Angeles, Inc., Calif (ff)
Metallizing Engineering Co., Inc., NY (ff)
Metals Disintegrating Co., Inc., NJ (aa)
Michigan Seamless Tube Co., Mich (ee)
Modern Plating Corp., Ill (n)
National Lead Co., NY (q,w)
**National-Standard Co., Mich** (ff)—Ad p 421
National-U.S. Radiator Corp., Plastic Metals Div., NY (aa)
Nesor Alloy Products Co., NJ (ff)
New England Brass Co., Mass (cc,dd)
New Jersey Metals Co., NJ (n,q,w)
**New Jersey Zinc Co., NY** (aa)—Ad pp 452-453
Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)
Norrich Plastics Corp., Screw Machine Products Div., NY (o,bb,ee)
Norwalk Powdered Metals, Inc., Conn (aa)
Nuclear Metals, Inc., Mass (w,bb,dd, ee)
Precision Tube Co., Inc., Pa (ee)
Pyron Corp., NY (aa)
Rathbone Corp., Mass (o,bb)
Republic Steel Corp., Steel & Tubes Div., Ohio (ee)
Rigidized Metals Corp., NY (cc,dd)
**Riverside-Alloy Metal Div., H.K. Porter Co., Inc., NJ** (bb,dd,ff)—Ad p 160
Rolock, Inc., Conn (ff)
Sandusky Foundry & Machine Co., Ohio (ee)
**Sel-Rex Corp., NJ** (n,aa)—Ad p 356
**Seymour Mfg. Co., Conn** (n)—Ad p 178
Shenango Furnace Co., Centrifugally Cast Products Div., Ohio (ee)
Sherwatt Equipment & Mfg. Co., Inc., NY (ff)
Shieldalloy Corp., NJ (aa)
Sierra Metals Corp., Sub. of American-Marietta Co., Ill (w)
**Somers Brass Co., Inc., Conn** (v,dd)—Ad p 162
Standard Metals Corp., Mass (ee)
Stauffer-Temescal Co., Calif (o,q,w,z, bb,cc,dd,ee,ff)
Stevens, Frederic B., Inc., Mich (n)
Superior Steel Corp., Pa (dd)
Superior Tube Co., Pa (ee)
Sylvania Electric Products, Inc., Parts Div., Pa (ff)
Techalloy Co., Inc., Pa (o,v,bb,cc,dd, ff)
Trent Tube Co., Sub. of Crucible Steel Co. of America, Pa (ee)
Tube Distributors Co., Inc., NY (ee)
Tube Methods Inc., Pa (ee)
Tube Reducing Corp., NJ (ee)
Udylite Corp., Mich (n)
Ullmann, Inc., Wis (o,ee)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
United Wire & Supply Corp., RI (ff)
Universal-Cyclops Steel Corp., Pa (o, q,z,bb,cc,dd,ff)
Utica General Jobbing Foundry, Inc., NY (aa)
Utility Mfg. Co., Mass (bb)
Vanadium-Alloys Steel Co., Pa (aa)
**Waimet Alloys Co., Mich** (w)—Ad p 82
Wall Colmonoy Corp., Stainless Process Div., Mich (w,aa,bb)
Wall Tube & Metal Products Co., Tenn (ee)
Wallingford Steel Co., Conn (dd,ee)
Waterbury Rolling Mills, Inc., Conn (dd)
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,v,w,z,bb,cc, dd,ee)
Whitehead Metal Products Co., Inc., NY (o,q,z,bb,cc,dd,ee,ff)
Wilson, H.A. Co., Div. of Engelhard Industries, Inc., NJ (bb,dd)
Wisconsin Centrifugal Foundry, Inc., Wis (ee)
Youngstown Welding & Engineering Co., Ohio (ee)

## Nickel Silver

(see Copper)

## Nitrides

(see Refractories)

## Nitrile Rubber

(see Acrylonitrile-Butadiene Rubber)

## Nodular Iron

(see Iron)

## Nylon

(see Polyamides)

## Organic Coatings

(formulations — lacquers, enamels, etc; see also Precoated Metals)

Abalon Precision Mfg. Corp., NY
Acheson Colloids Co., Mich
Acme Plating Co., Ohio
Acme Stamping & Wire Forming Co., Pa
Alcylite Plastics & Chemical Corp., Calif
AllianceWall Div., AllianceWare, Inc., Ohio
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY
**Allied Research Products, Inc., Md** —Ad p 358
Alpha-Molykote Corp., Conn
Aluminum Co. of America, Pa
Amercoat Corp., Calif
American Cynamid Co., Plastics & Resins Div., NY
American Solder & Flux Co., Pa
American-Marietta Co., Ill
Armitage, J.L. & Co., NJ
Ashtabula Mfg. Co., Ohio
Atlas Mineral Products Co., Pa
Auld, D.L. Co., Ohio
Automotive Rubber Co., Inc., Mich
Avondale Co., Ill
B.B. Chemical Co., Bostik Dept., Mass.
Babbitt Chemical Co., Inc., Mass
Barrett Varnish Co., Ill
Bee Chemical Co., Ill
Berry Bros., Mich
Biggs, Carl H. Co., Inc., Calif
Bisonite Co., Inc., NY
Boatwright Paint & Varnish Works, Inc., Ga
Borden Chemical Div., Borden Co., NY
Bradley Paint Co., Pa
Bradley & Vrooman Co., Ill
Brandt, Charles T., Inc., Md
Burwood Products Co., Mich
Capitol Chemical Co., Ill
Carboline Co., Mo
Ceilcote Co., Ohio
**Cellusuede Products, Inc., Ill** (flock)—Ad p 363
Chemical Coatings Corp., Conn
Chemical Coatings & Engineering Co., Inc., Pa
Chemical Development Corp., Mass
Chemical Process Co., Calif
Chemical Products Corp., RI
Clinton Co., Ill
Commercial Chemical Co., Ohio
Co-Polymer Chemicals Inc., Mich
Cordo Chemical Corp., Conn
Davis Products Corp., NY
Day, James B. & Co., Ill
Dayton Rubber Co., Ohio
Debevoise Co., NY
Dennis Chemical Co., Mo
Designers Metal Corp., Ill
De Soto Paint & Varnish Co., Tex
Dirilyte Co. of America, Inc., Ind
Doehler-Jarvis Div., National Lead Co., Ohio
Dollin Corp., NJ

Douglas & Sturgess, Calif
du Pont de Nemours, E. I. & Co., Inc., Del
Duralac Chemical Corp., NJ
Dyna-Therm Chemical Corp., Calif
Earl Paint Corp., NY
Egan & Hausman Co., Inc., NY
Egyptian Lacquer Mfg. Co., NJ
Electro Chemical Engineering & Mfg Co., Pa
Electrofilm, Inc., Calif
Electronic Production & Development, Inc., Chemical Div., Calif
Enamelstrip Corp., Sub. of National Steel Corp., Pa
**Enthone, Inc., Conn**
—Ad p 350
Everlite Corp., Wash
Fidelity Chemical Products Corp., NJ
Flexrock Co., Pa
Forbes Finishes Div., Pittsburgh Plate Glass Co., Ohio
Foss Mfg. Co., Id
Fox Co., Ohio
Furane Plastics Inc., Calif
Gates Engineering Co., Del
General Electric Co., Chemical Materials Dept., Mass
General Plastics Corp., NJ
General Plastics Mfg. Co., Wash
Globe Paint Works, Inc., Pa
Goodyear Tire & Rubber Co., Chemical Div., Ohio
Graphite Products Corp., Ohio
Grand Rapids Varnish Corp., Mich
Grems Mfg. Co., Ore
Hardman, H.V. Co., Inc., NJ
Haveg Industries, Inc., Del
Hilo Varnish Corp., Industrial Finishes Div., Mass
Horn, A.C. Co., Inc., Div. of Sun Chemical Corp., NY
Hughson Chemical Co., Div. of Lord Mfg. Co., Pa
Hysol Corp., NY
Industrial Metal Protectives Inc., Ohio
Industrial Paint Div., Glidden Co., Ohio
Industrial Polychemical Service, Calif
Interchemical Corp., Finishes Div., NJ
Jamestown Finishes, NY
Jasper Lacquer Co., Inc., Ind
Jema-American, Inc., NJ
Jervis Corp., Mich
Johnson, S.C. & Son, Inc., Wis
Jones-Dabney Co., Div. of Devoe & Raynolds Co., Inc., Ky
Keystone Refining Co., Inc., Pa
Kish Industries, Inc., Mich
Knight, Maurice A., Ohio
Lacquer & Chemical Corp., NY
Lacquer Products, Inc., Ohio
Lakewood Metal Products, Inc., Conn
Landau, J. & Co., Inc., NJ
Lithcote Corp., Ill
Lowe Bros. Co., Ohio
**Maas & Waldstein Co., NJ**
—Ad p 353
Magic Chemical Co., Mass
Magnesium Co. of America, Ind
Marblette Corp., NY
Masonite Corp., Ill
McDougall Butler Co., Inc., NY
McGee Chemical Co., Inc., Pa
Mearl Corp., NY
Merix Chemical Co., Ill
**Metal & Thermit Corp., NJ**
—Ad p 357
Micarta Div., Westinghouse Electric Corp., SC
Michigan Chrome & Chemical Co., Mich
Midland Industrial Finishes Co., Ill
Minnesota Paints, Inc., Minn
Mirro Aluminum Co., Wis
Mobay Chemical Co., Pa
Mobile Paint Mfg. Co., Inc., Ala
Modern Plating Corp., Ill
Mono-Seal Products Div., Downer, Hunnewell, Inc., Mass
Monsanto Chemical Co., Organic Chemicals Div., Mo
Munray Products Div., Fanner Mfg. Co., Ohio
Narmco Industries, Inc., Narmco Materials Div., Calif
National Mfg. Corp., NY
Naugatuck Chemical Div., U.S. Rubber Co., Conn
Navan Products, Inc., Sub. of North American Aviation, Inc., Calif
New Jersey Zinc Co., NY
Nikolas, G.J. & Co., Inc., Ill
Nukem Products Corp., NY
Octagon Process, Inc., NY
Owens-Illinois Glass Co., Closure & Plastics Div., Ohio
Paramount Paint & Lacquer Co., Calif
Parker Paint Mfg. Corp., Ind
Pecora, Inc., Pa
Penn Metal Co., Inc., W.Va
Perry-Austen Mfg. Co., NY
Peterson, D.J. Co., Wis
Philadelphia Enameling Works, Inc., Pa
Pierce, F.O. Co., NY
Pierce & Stevens Chemical Corp., NY
Pittsburgh Plate Glass Co., Pa
Pittsburgh Steel Co., Pa
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif
Plume & Atwood Mfg. Co., Conn
Polymer Corp., Pa
Polymer Industries Inc., Conn
Powell Pressed Steel Co., Ohio
Pratt & Lambert, Inc., NY
Promat Div., Poor & Co., Ill
Queen Products Co., Inc., Ky
Quelcor, Inc., Pa
Radiant Color Co., Calif
Radiation Applications, Inc., NY
Raffi and Swanson, Inc., Mass
Randolph Products Co., NJ
Raybestos-Manhattan, Inc., NJ
Raybestos-Manhattan, Inc., Adhesives Div., Conn
Reynolds Aluminum Supply Co., Ga
Reynolds Chemical Products Co., Mich
Riegel Paper Corp., NY
Rinshed-Mason Co., Mich
Rodney Metals, Inc., Mass
Rosco Laboratories, NY
Rubber Corp. of America, NY
Rust-Oleum Corp., Ill
Sanford Process Co., Inc., Calif
Saran Protective Coatings Co., Mich
Sauereisen Cements Co., Pa
Schori Process Div., Ferro-co Corp., NY
Schwartz Chemical Co., Inc., NY
Seal-Peel, Inc., Mich
Sealube Co., Mass
Seaporcel Metals, Inc., NY
Sherwin-Williams Co., Ohio
Sierra Engineering Co., Calif
Simonsen Metal Products Co., Ill
Spraylat Corp, NY
Stanley Chemical Co., Conn
Steel Protection & Chemical Co., Ind
Steelcote Mfg. Co., Mo
Subox, Inc., NJ
Sun Steel Co., Ill
Superior Plastics, Inc., Ill
Textileather Div., General Tire & Rubber Co., Ohio
Thompson and Co., Pa
Tousey Varnish Co., Ill
Tubular Rivet & Stud Co., Mass
Tuff Clad, Inc., Ohio
Union Chemical Corp., NJ
Union Paste Co., Mass
United Shoe Machinery Corp., Mass
U.S. Stoneware Co., Ohio
Waterbury Cos., Inc., Conn
Watson-Standard Co., Pa
Wesbar Stamping Corp., Wis
Western Coating Co., Mich
Westinghouse Electric Corp., Pa
Worth Co., Wis
Zeller Corp., Ohio
Zolatone Process, Inc., Calif

## Organic Coatings

(coaters)

Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich
Aldan Rubber Co., Pa
Alloy Products Corp., Wis
Aluminum Co. of America, Pa
Aluminum Specialty Co., Wis
American Emblem Co., Inc., NY
American Hard Rubber Co., Div. of Amerace Corp., NJ
Arbonite Corp., Pa
Ashtabula Mfg. Co., Ohio
Atlas Mineral Products Co., Pa
Auld, D.L. Co., Ohio
Automotive Rubber Co., Inc., Mich
Avondale Co., Ill
Bee Chemical Co., Ill
Biggs, Carl H. Co., Inc., Calif
Bishopric Products Co., Ohio
Bisonite Co., Inc., NY
Boatwright Paint & Varnish Works, Inc., Ga
Bradley Paint Co., Pa
Brandt, Charles T., Inc., Md
Caspers Tin Plate Co., Ill
Chemical Development Corp., Mass
Coated Coil Corp., NY
Cohan Epner Co., Inc., NY
Colonial Alloys Co., Pa
Cordo Chemical Corp., Conn
Croname, Inc., Ill
Day, James B. & Co., Ill
Debevoise Co., NY
Dirilyte Co. of America, Inc., Ind
Dolin Metal Products, Inc., NY
Dollin Corp., NJ
Douglas & Sturgess, Calif
Dyna-Therm Chemical Corp., Calif
Earl Paint Corp., NY
Electro Chemical Engineering & Mfg. Co., Pa
Electro Technical Div., Sun Chemical Corp., NJ
Electrofilm, Inc., Calif
Emerson & Cuming, Inc., Mass
Enamelstrip Corp., Sub. of National Steel Corp., Pa
Everlite Corp., Wash
Eyelet Specialty Div., International Silver Co., Conn
Falstrom Co., NJ
Farwell Metal Fabricating, Minn
Fletcher Enamel Co., W.Va
Forbes Finishes Div., Pittsburgh Plate Glass Co., Ohio
Foss Mfg. Co., Id
Fuller, H.B. Co., Minn
Gates Engineering Co., Del
General Plastics Corp., NJ
Globe Paint Works, Inc., Pa
Gomar Mfg. Co., Inc., NJ
Goodrich, B.F. Industrial Products Co., Ohio
Grand Rapids Brass Co., Mich
Grand Rapids Varnish Corp., Mich
H & R Industries, Pa
Hartglas Co., Ohio
Haveg Industries, Inc., Del
Hayden Wire Works, Inc., Mass
Hilo Varnish Corp., Industrial Finishes Div., Mass
Hughson Chemical Co., Div. of Lord Mfg. Co., Pa
Industrial Metal Protectives, Inc., Ohio
Industrial Paint Div., Glidden Co., Ohio
Jamison Plastic Corp., NY
Jervis Corp., Mich
Johnson, S.C & Son, Inc., Wis
Kelley Mfg. Co., Tex
Kickhaefer Mfg. Co., Wis
King, Alfred B., Co., Conn
Lakewood Metal Products, Inc., Conn
Lacquer & Chemical Corp., NY
Lithcote Corp., Ill
Lowe Bros. Co., Ohio
Ludlow Plastics Mass
Luzerne Rubber Co., NJ
**Maas & Waldstein Co., NJ**
—Ad p 353
Magic Chemical Co., Mass
Merix Chemical Co., Ill
Metal-Cladding, Inc., NY
Metalweld, Inc., Protective Coating Div., Pa
Met-L-Wood Corp., Ill
Michigan Chrome & Chemical Co., Mich
Miller-Stephenson Chemical Co., Inc., Conn
Minnesota Mining & Mfg. Co., Adhesives, Coatings & Sealers Div., Mich
Modern Plating Corp., Ill
Morton Mfg. Co., Ill
Munray Products Div., Fanner Mfg. Co., Ohio
Montague Machine Co., Mass
Narmco Industries, Inc., Narmco Materials Div., Calif
National Lock Co., Ill
National Metal Products Co., Pa
Nikolas, G.J. & Co., Inc., Ill
Norgren-Stemac, Inc., Colo
Pecora, Inc., Pa
Peterson, D.J. Co., Wis
Polacoat, Inc., Ohio
Polymer Corp., Pa
Quelcor, Inc., Pa
Radiant Color Co., Calif
Radiation Applications, Inc., NY
Raffi and Swanson, Inc., Mass
Respro Div., General Tire & Rubber Co., RI

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Riegel Paper Corp., NY
Rust-Oleum Corp., Ill
Rustproofing & Metal Finishing Corp., Mass
Schori Process Div., Ferro-co Corp., NY
Schwartz Chemical Co., Inc., NY
Smith-Victor Corp., Ind
Smoot-Holman Co., Calif
Steelcote Mfg. Co., Mo
Stirrup Metal Products Corp., NJ
Sun Steel Co., Ill
Superior Plastics, Inc., Ill
Textileather Div., General Tire & Rubber Co., Ohio
Toyad Corp., Pa
Tuff Clad, Inc., Ohio
Union Chemical Corp., NJ
U.S. Stoneware Co., Ohio
United-Carr Fastener Corp., Mass
Wayne Chemical Products Co., Mich
Woodstock Div., Electric Auto-Lite Co., Ill
Worth Co., Wis
Zolatone Process, Inc., Calif
Zophar Mills, Inc., NY

## Organic Coatings —Claddings

(see also Laminates, Metal-Organic)

American Hard Rubber Co., Div. of Amerace Corp., NJ
Arvin Industries, Inc., Ind
Automotive Rubber Co., Inc., Mich
Chemical Products Corp., RI
Clad-Rex Corp., Ill
Electro Chemical Engineering & Mfg. Co., Pa
Lithcote Corp., Ill
Metal-Cladding, Inc., NY
Nukem Products Corp., NY
O'Sullivan Rubber Corp., Plastics Div., Va
Penn Metal Co., Inc., W.Va
Polymer Corp., Pa
Quelcor, Inc., Pa
Radiation Applications, Inc., NY
Seiberling Rubber Co., Plastics Div., Ohio
Sun Steel Co., Ill
Tuff Clad, Inc., Ohio
Watson-Standard Co., Pa

## Organic Coatings —Prepainted Metals

Abalon Precision Mfg. Corp., NY
Aluminum Co. of America, Pa
Bridgeport Brass Co., Conn
Caspers Tin Plate Co., Ill
Clad-Rex Corp., Ill
Coated Coil Corp., NY
Cooley, W.J. & Co., Tenn
Dow Chemical Co., Mich
Enamelstrip Corp., Sub. of National Steel Corp., Pa
Fairmont Aluminum Co., W.Va
Falstrom Co., NJ
Fryling Mfg. Co., Pa
Hoofer Mfg. Co., Ill
Kaiser Aluminum & Chemical Sales Inc., Ill
Kees, F.D. Mfg. Co., Neb
Kinkead Industries, Inc., Ill
Lundquist Tool & Mfg. Co., Inc., Mass
Mahon, R.C. Co., Mich
National Metal Products Co., Pa
Penn Metal Co., Inc., W.Va
Philadelphia Steel & Wire Corp., Pa
Pittsburgh Steel Co., Pa
Republic Steel Corp., Ohio
Reynolds Aluminum Supply Co., Ga
Reynolds Metals Co., Va
Rigidized Metals Corp., NY
Rodney Metals, Inc., Mass
Roll Coater, Inc., Ind
Security Sash & Screen Co., Mich
Sharon Steel Corp., Pa
Silicocks Miller Co., NJ
Stainless and Strip Div., Jones & Laughlin Steel Corp., Ohio
Sun Steel Co., Ill
Thomas Strip Div., Pittsburgh Steel Co., Pa

## Organic Coatings, Strippable

Adhesive Products Corp., NY
Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich
Amercoat Corp., Calif
American Latex Products Corp., Calif
Angier Adhesives Div., Interchemical Corp., Mass
Atlas Mineral Products Co., Pa
Avondale Co., Ill
Babbitt Chemical Co., Inc., Mass
Bee Chemical Co., Ill
Belding Corticelli Industries, NY
Better Finishes & Coatings, Inc., NJ
Bischoff Chemical Corp., NY
Bisonite Co., Inc., NY
Blaco Mfg. Co., Ohio
Borden Chemical Div., Borden Co., NY
Bradley & Vrooman Co., Ill
Carboline Co., Mo
Chemical Coatings & Engineering Co., Inc., Pa
Chemical Development Corp., Mass
Chemical Products Corp., RI
Daubert Chemical Co., Ill
Dennis Chemical Co., Mo
De Soto Paint & Varnish Co., Tex
Dip Seal Plastics, Inc., Ill
Diversey Corp., Metal Industries Div., Ill
Dow Chemical Co., Plastics Div., Mich
du Pont de Nemours, E. I. & Co., Inc., Del
Earl Paint Corp., NY
Fidelity Chemical Products Corp., NJ
Fine Organics, Inc., NY
Frost Paint & Oil Corp., Minn
George, P.D. Co., Mo
Globe Imperial Corp., Plastic-Seal Div., Ill
Houghton, E.F. & Co., Pa
Hughes Glue Co., Mich
Hughson Chemical Co., Div. of Lord Mfg. Co., Pa
Industrial Paint Div., Glidden Co., Ohio
Interchemical Corp., Finishes Div., NJ
Jamestown Finishes, NY
Johnson, S.C & Son, Inc., Wis
Kinkead Industries, Inc. Ill
Koster-Keunen Mfg. Co. Inc. NY
Lacquer & Chemical Corp., NY
Lacquer Products, Inc., Ohio
Landau, J. & Co., Inc., NJ
Maas & Waldstein Co., NJ
Magic Chemical Co., Mass
Metal & Thermit Corp., NJ
Micarta Div., Westinghouse Electric Corp., SC
Michelman Chemicals, Inc., Ohio
Midland Adhesive & Chemical Corp., Mich
Minnesota Mining & Mfg. Co., Adhesives, Coatings & Sealers Div., Mich
Minnesota Paints, Inc., Minn
Modern Plating Corp., Ill
Morningstar-Paisley, Inc., NY
Munray Products Div., Fanner Mfg. Co., Ohio
Nikolas, G.J. & Co., Inc., Ill
Nukem Products Corp., NY
Octagon Process, Inc., NY
Parker Paint Mfg. Corp., Ind
Pecora, Inc., Pa
Pennsalt Chemicals Corp., Pa
Pierce & Stevens Chemical Corp., NY
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif
Plume & Atwood Mfg. Co., Conn
Poly Resins, Calif
Polyken Sales Div., Kendall Co., Ill
Polymer Chemical Co., Ohio
Polymer Industries, Inc., Conn
Protective Treatments, Inc., Ohio
Puritan Co., Inc., NY
Pyramid Plastics, Inc., Ill
Quelcor, Inc., Pa
Radiation Applications, Inc., NY
Reynolds Chemical Products Co., Mich
Schwartz Chemical Co., Inc., NY
Seal-Peel, Inc., Mich
Serwell Products Co., Ohio
Sierra Engineering Co., Calif
Spraylat Corp., NY
Sun Steel Co., Ill
Thompson and Co., Pa
Turco Products, Inc., Calif
Union Chemical Corp., NJ
Union Paste Co., Mass
U.S. Rubber Co., NY
U.S. Stoneware Co., Ohio
Valvoline Oil Co., Div. of Ashland Oil & Refining Co., Pa
Watson-Standard Co., Pa
Wayne Chemical Products Co., Mich
Western Coating Co., Mich
Whitfield Chemical Co., Mich
Xylos Rubber Co., Ohio
Zophar Mills, Inc., NY

## Oxide Coatings

(see Conversion Coatings)

## Oxides

(see Ceramics; Refractories)

## Paints

(see Organic Coatings)

## Papers

(cellulose, inorganic, synthetic; for industrial use)

Allied Chemical Corp., Plastics & Coal Chemicals Div., NY
Auburn Mfg. Co., Conn
Avery Label Co., Decorative Products Div., Ohio
Consolidated Water Power & Paper Co., Wis
Dexter, C.H. & Sons, Inc., Conn
Filpaco Industries, Inc., Ill
Fox Edge Co., Inc., Mass
General Gasket, Inc., Conn
Georgia-Pacific Corp., Ore
Gomar Mfg. Co., Inc., NJ
Hollingsworth & Vose Co., Mass
Insulation Mfrs. Corp., Ill
Johns-Manville Corp., NY
**Knowlton Bros., Inc., NY**
—Ad p 320
Mica Fabricating Co., NJ
Mosinee Paper Mills Co., Wis
National Gasket & Washer Mfg. Co., Inc., NY
Nicolet Industries, Inc., NY
Owens-Illinois Glass Co., Paper Products Div., Ohio
Panelyte Div., St. Regis Paper Co., NJ
Plymouth Cordage Co., Mass
Precision Paper Tube Co., Ill
Raybestos-Manhattan, Inc., NJ
Riegel Paper Corp., NY
Rogers Corp., Conn
Spaulding Fibre Co., Inc., NY
Spruce Pine Mica Co., Inc., NC
Standard Asbestos Mfg. Co., Ill
Standard Washer & Mat, Inc., Conn
Twitchell, E. W., Inc., Pa
Upson Co., NY
Vellumoid Co., Mass
Victor Mfg. & Gasket Co., Ill
West Virginia Pulp & Paper Co., NY
Wisconsin Gasket & Mfg. Co., Wis

## Perforated Materials

Acme Precision Products, Inc., Ohio (a,b,g,h)
Aluminum Co. of America, Pa (a)
American Metal Products, Inc., Ohio (g)
American Nickel Alloy Mfg. Corp., NY (f)
Atlantic Steel Co., Ga (a,b,g)
BLC Porous Materials Co., Calif (a, b,e,f,g,j,k,l,m)
Biersach & Niedermeyer Co., Wis (a, b,c,f,g)
Blaco Mfg. Co., Ohio (b,g)
Bohn Aluminum & Brass Co., Mich (a)
Brockway Pressed Metals, Inc., Pa (b, c)
Burgess-Norton Mfg. Co., Ill (c)
California Perforated Screen Co., Calif (a,b,c,f,g,j)
Caspers Tin Plate Co., Ill (g)
Chase Brass & Copper Co., Sub. of Kennecott Copper Corp., Conn (b)
Clad-Rex Corp., Ill (a,g)
Clark Perforating Co., Mich (a,b,c,d, f,g,j,k,l,m)
Clendenin Bros., Inc., Md (a,b)
Colonial Alloys Co., Pa (a)
Colorado Fuel & Iron Corp., Colo (g)
Cross Engineering Co., Pa (a,g)
Diamond Mfg. Co., Pa (a,b,c,d,e,f,g,h, j)
Division Lead Co., Ill (d)
Duplex Mfg. Corp., Ark (g)
Edgcomb Steel & Aluminum Corp., NJ (a,g)
Ellwood City Iron & Wire Co., Pa (c)
Emerson-Sack-Warner Corp., Mass (a, b,f,g)
Erdle Perforating Co., Inc., NY (a, b,c,d,f,g,j,k,l)
Etched Products Corp., NY (a)
Falstrom Co., NJ (a,b,e,g)
Fletcher Enamel Co., W.Va (a,b,c,d,e, f)
Fox Products Co., Pa (c)
General Alloys Co., Mass (a,b,f)
Greene, G.G. Corp., Pa (g)
Grigoleit Co., Ill (a,g)
**Harrington & King Perforating Co., Inc., Ill**
(a,b,c,d,e,f,g,h,j,k,l,m)—Ad p 440
Hawkridge Bros. Co., Mass (a)
Hendrick Mfg. Co., Pa (a,b,c,d,e,f,g,h, j)
Houston Blow Pipe & Sheet Metal Works, Tex (a,b,g)
Ideal Can Co., Mass (g)
Industrial & Furnace Car Div., Irwin-Sensenich Corp., Pa (g)
Kees, F.D. Mfg. Co., Neb (g)
Levinson Steel Co., Pa (g)
Madin Plastics, Inc., NJ (k)
Manganese Steel Forge Co., Pa (g)
McCarter Iron Works, Inc., Pa (g)
McNally Pittsburgh Mfg. Co., Kan (a, g)
Meico Wire Products, Calif (a)
Morton Mfg. Co., Ill (a,g)
Mundt, Charles & Sons, NJ (a,b,c,d, e,f,g,h,j,k,l,m)
National Galvanizing Co., Pa (g)
National Lead Construction Co., Inc., NJ (d)
**National-Standard Co., Mich**
(a,b,f,g,h)—Ad p 421
Norwalk Powdered Metals, Inc., Conn (b)
Parker Metal Goods Co., Mass (g)
**Perforating Industries, Inc., NJ**
(k,l)—Ad p 450
Republic Steel Corp., Ohio (g)
Reynolds Metals Co., Va (a)
Rigidized Metals Corp., NY (a,b,f, g,h,j)
Rockwell Engineering Co., Ill (a,b,c,g)
Ryerson, Joseph T. & Son, Inc., Ill (a,g)

Servwell Products Co., Ohio (b,g)
Silicocks Miller Co., NJ (a,b)
Stainless Metals, Inc., NY (g)
Standard Stamping & Perforating Co., Ill (a,b,g,k,l,m)
Thompson Pipe & Steel Co., Colo (g)
Toepfer & Sons., Inc., Wis (a,b,c,e,f,g,h,j)
Weibar Stamping Corp., Wis (a)
Whitehead Metal Products Co., Inc., NY (a,b,f)
Whyte, Oliver Co., Inc., NY (a,g)
Wire & Iron Products, Inc., Mich (f,g)
Wrought Washer Mfg. Co., Wis (g)

## Permanent Mold Castings

(see Castings)

## Phenolics

**Ace Plastic Co., NY (bb,cc,dd)**
Adhesive Products Corp., NY (x)
Alcylite Plastics & Chemical Corp., Calif (p,x,y)
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY (p,y)
American-Marietta Co., Adhesive, Resin & Chemical Div., Wash (p)
Anderson Assoc., Inc., Ohio (y)
Archer-Daniels-Midland Co., Minn (y)
Atlas Mineral Products Co., Pa (x)
Auburn Plastic Engineering, Ill (bb,cc)
Baer, N.S. Co., NJ (bb,cc,dd,ee)
Bisonite Co., Inc., NY (x)
Blank, Arthur & Co., Inc., Mass (cc)
Booty Resineers Div., American-Marietta Co., Ohio (p)
Borden Chemical Div., Borden Co., NY (p)
Cadillac Plastic & Chemical Co., Mich (bb,cc,dd,ee)
Calfibe Co., Inc., Calif (cc,ee)
Catalin Corp. of America, NY (p,x)
Chemical Process Co., Calif (x)
Coast Mfg. & Supply Co., Calif (y)
Colonial Kolonite Co., Ill (bb,cc,ee)
Comco Plastics, Inc., NY (bb,cc,dd,ee)
Commercial Plastics & Supply Corp., NY (bb,cc,dd,ee)
Continental-Diamond Fibre Corp., Del (bb,cc,dd,ee)
Cordo Chemical Corp., Conn (y)
Cordo Molding Products, Inc., Conn (y)
CrystalX Corp., Pa (bb,cc,dd,ee)
Curbell, Inc., NY (bb,cc,dd,ee)
Delta Plastics Co., NJ (bb,cc,dd,ee)
Douglas & Sturgess, Calif (x,y)
Dunnican Assoc., NJ (p,y)
**Durez Plastics Div., Hooker Chemical Corp., NY** (p,x,y)—Ad pp 232-233
Dyna-Therm Chemical Corp., Calif (p)
Electrofilm, Inc., Calif (t)
Eljay Corp., Md (bb,cc,dd,ee)
Farley & Loetscher Mfg. Co., Plastics Div., Iowa (cc)
**Fiberite Corp., Minn** (y)—Ad p 281
Fiber Glass Industries, Inc., NY (x,cc)
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (p,x,y)
Formica Corp., Sub. of American Cyanamid Co., Ohio (bb,cc,dd,ee)
Foss Mfg. Co., Id (x)
Galigher Co., Utah (bb,cc,dd,ee)
General Electric Co., Chemical Materials Dept., Mass (p,x,y)
General Electric Co., Laminated Products Dept., Ohio (bb,cc,ee)
**General Plastics Mfg. Co., Wash (bb,cc,dd,ee)**
Grigoleit Co., Ill (p,s)
Haveg Industries, Inc., Del (p,bb,cc,ee)
Hercules Powder Co., Inc., Del (p)
Hiller Aircraft Corp., Adhesive Engineering Div., Calif (u)
Iten Fibre Co., Ohio (bb,cc,dd,ee)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Lewis, J.P. Co., Plastic Products Div., NY (cc)
Kish Industries, Inc., Mich (u,x)
Kurz Kasch, Inc., Ohio (y)
Laminated Plastex Corp., Ohio (x,cc)
Maloney, F.H. Co., Tex (x,y,bb,cc,dd,ee)
Marbiette Corp., NY (p,u,x,y,bb,cc,ee)
Mica Insulator Div., Minnesota Mining & Mfg. Co., NY (bb,cc,ee)
Micarta Div., Westinghouse Electric Corp., SC (p,x)
Monsanto Chemical Co., Plastics Div., Mass (p,x)
Narmco Industries, Inc., Narmco Materials Div., Calif (u,x,y,dd)
National Moldite Co., NJ (y)
National Vulcanized Fibre Co., Del (bb,cc,dd,ee)
New England Laminates Co., Inc., Conn (cc)
Nopco Chemical Co., NJ (p)
Norrich Plastics Corp., NY (bb,cc,dd,ee)
Northern Plastics Corp., Wis (cc,dd)
Omni Products Corp., NY (y)
Panelyte Div., St. Regis Paper Co., NJ (x,bb,cc,dd,ee)
Penn Fibre & Specialty Co., Inc., Pa (bb,cc,dd,ee)
Permali, Inc., Pa (bb,cc,dd)
Philrus Products Co., NJ (bb,cc,dd,ee)
**Plastics Engineering Co., Wis** (p,x,y,aa)—Ad p 270
Poly Resins, Calif (p,x)
Precision Paper Tube Co., Ill (ee)
Pyrosil Inc., Ohio (x,cc)
Raybestos Div., Raybestos-Manhattan, Inc., Conn (p,x)
Raybestos-Manhattan, Inc., Adhesives Div., Conn (p,x)
Raybestos - Manhattan, Inc., Plastic Products Div., Pa (p,x,y)
Reichhold Chemicals, Inc., NY (p,x,y)
Rezolin, Inc., Calif (p,u,x)
Richardson Co., NY (bb,cc,ee)
**Rogers Corp., Conn** (y)—Ad p 261
Schenectady Varnish Co., Inc., NY (p,x)
Schwab Plastic Corp., Mich (bb,cc,dd,ee)
Sierra Electric Corp., Calif (y)
Spaulding Fibre Co., Inc., NY (bb,cc,dd,ee)
Spencer Rubber Co., Conn (u)
Strick Plastics Co., Pa (u,cc)
Sun Chemical Corp., Electro Technical Div., NJ (x)
Swedlow, Inc., Calif (cc)
Synco Resins, Inc., Conn (p,x)
Synthane Corp., Pa (bb,cc,dd,ee)
Taylor Fibre Co., Pa (bb,cc,dd,ee)
Texas Glass Fiber Corp., Tex (y)
Thombert, Inc., Iowa (bb,cc,dd,ee)
**Union Carbide Plastics Co., Div. of Union Carbide Corp., NY** (p,u,x,y)—Ad p 257
U.S. Polymeric Chemicals, Inc., Conn (s)
Varcum Chemical Corp., NY (p)
Watertown Mfg. Co., Conn (p,y)
Westlake Plastics Co., Pa (bb,cc,dd,ee)
Wilmington Fibre Specialty Co., Del (bb,cc,ee)

## Phosphate Coatings

(see Conversion Coatings)

## Phosphor Bronze

(see Copper)

## Pipe

(see Tubing)

## Plaster Mold Castings

(see Castings)

## Plastics

(see specific material and form)

## Plate

(see specific metal)

## Plated Coatings

(see Electroplated Coatings; Preplated Metals)

## Platinum and Platinum Group Alloys

American Metal Climax, Inc., NY (aa)
American Platinum & Silver Div., Engelhard Industries, Inc., NY (n,v,z,aa,bb,cc,dd,ee,ff)
American Platinum Works, NJ (z)
American Silver Co., NY (v,dd,ee,ff)
Anaconda Co., NY (n,v,cc)
**Baker & Co., Inc., NJ (n,o,v,w,z,aa,bb,cc,dd)**
Bishop, J. & Co. Platinum Works, Pa (n,v,z,bb,cc,dd,ee,ff)
Deringer Metallurgical Corp., Ill (cc,dd,ee,ff)
Eastern Smelting & Refining Corp., Mass (n,o,v,w,z,aa,bb,cc,dd,ee,ff)
Electronic Parts Mfg. Co., Inc., NJ (ff)
**Gibson Electric Co., Pa** (bb,dd,ff)—Ad p 466
Goldsmith Bros. Div., National Lead Co., Ill (n,o,v,w,z,bb,cc,dd,ff)
Hagstoz, T.B. & Son, Pa (n,cc,dd,ff)
Hamilton Watch Co., Precision Metals Div., Pa (ff)
Handy & Harman, NY (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Hanovia Chemical & Mfg. Co., NJ (aa)
Hardy, Charles, Inc., Mass (aa)
Hayden Wire Works, Inc., Mass (ff)
Hudsar, Inc., NJ (w)
**International Nickel Co., Inc., Platinum Metals Div., NY** —Ad pp 182-183
Leach & Garner Co., Industrial Div., Mass (n,o,v,bb,cc,dd,ee,ff)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (o,dd,ee,ff)
Metz Refining Co., NJ (n,o,q,z,aa,bb,cc,dd,ee,ff)
Nesor Alloy Products Co., NJ (dd,ff)
Ney, J.M. Co., Industrial Div., Conn (z,bb,cc,dd,ff)
Nuclear Metals, Inc., Mass (w)
**Sel-Rex Corp., NJ** (n,aa)—Ad p 356
Standard Metals Corp., Mass (cc,dd,ff)
Texas Instruments, Inc., Metals & Controls Div., Mass (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
**Technic, Inc., RI** (aa)—Ad p 352
Western Gold & Platinum Co., Sub. of Wilbur B. Driver Co., Calif (aa,cc,dd,ff)
Wildberg Bros. Smelting & Refining Co., Calif (n,o,v,w,z,aa,bb,cc,dd,ff)
Williams Gold Refining Co., Inc., NY (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Wilson H.A. Div., Engelhard Industries, Inc., NJ (ff)

## Plywood

(see Wood)

## Polyamides

(nylon)

Ace Plastics Co., NY (bb,dd)
Adhesive Products Corp., NY (x)
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY (p,s,y)
American Hard Rubber Co., Div. of Amerace Corp., NJ (bb,dd,ee)
American Molding Powder & Chemical Co., NY (y)
Anchor Plastics Co., Inc., NY (bb,dd,ee)
Anderson Asso., Inc., Ohio (y)
Auburn Plastic Engineering, Ill (t,bb,cc,ee)
Bamberger, Claude P., Inc., NJ (y)
Belding Corticelli Industries, NY (p,x,y)
Cadillac Plastic & Chemical Co., Mich (f,bb,cc,dd,ee)
Catalin Corp. of America, NY (y)
Chemical Coatings & Engineering Co., Inc., Pa (x)
Chippewa Plastics Co., Wis (t)
Colonial Kolonite Co., Ill (bb,cc,dd,ee)
Commercial Plastics & Supply Corp., NY (bb,cc,dd)
Conneaut Rubber and Plastics Co., Div. of U.S. Stoneware Co., Ohio (bb,cc,dd,ee)
Cosmo Plastics Co., Ohio (u)
CrystalX Corp., Pa (t,bb,cc,dd,ee)
Danielson Mfg. Co., Conn (bb,cc,dd,ee)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

du Pont de Nemours, E. I. & Co., Inc., Del (p,s,y)
Dyna-Therm Chemical Corp., Calif (p)
Emerson & Cuming, Inc., Mass (p,u,x)
Fiberfil, Inc., Ind (y)
Firestone Plastics Co., Pa (s)
Flexible Tubing Corp., Conn (ee)
Fluoro-Plastics, Inc., Div. of Flexrock Co., Pa (bb,cc)
Foster Grant Co., Mass (p,t,y,ee)
Fox Edge Co., Inc., Mass (s)
Fry Plastics International, Calif (bb, cc)
General Mills Inc., Chemical Div., Ill (p)
General Plastics Corp., NJ (t,x)
General Plastics Mfg. Co., Wash (bb, cc,dd,ee)
Glass Laboratories, NY (bb,dd,ee)
H & R Industries, Pa (t,bb,cc,dd,ee)
Hauger-Beegle Asso., Inc., Ill (t)
Hyde Co., A.L., NJ (bb,cc)
Industrial Rayon Corp., NY (s)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Lus-Trus Corp., Mich (cc,ee)
Moore, Samuel & Co., Ohio (ee)
Muehlstein, H. & Co., Inc., NY (y)
Narmco Industries, Inc., Narmco Materials Div., Calif (x,y)
National Vulcanized Fibre Co., Del (bb,dd,ee)
Plast-Ad Mfg. Co., Ind (bb,cc,dd,ee)
**Polymer Corp. of Pennsylvania, Sub. of Polymer Corp., Pa**
(t,bb,cc,dd,ee)—Ad p 230
Prince Rubber & Plastics Co., Inc., NY (bb,ee)
Raybestos - Manhattan, Inc., Plastic Products Div., Pa (x)
Reichhold Chemicals, Inc., NY (p)
Schwab Plastic Corp., Mich (bb,cc,dd, ee)
Shamban, W.S. & Co., Calif (t,bb,cc, dd,ee)
Southern Plastics Co., SC (bb,cc,dd, ee)
Spencer Chemical Co., Mo (p,x,y)
Sunlites Plastics, Inc., Wis (bb,dd,ee)
Thombert, Inc., Iowa (bb,cc,dd,ee)
U. S. Gasket Plastics Div., Garlock Packing Co., NJ (t,bb,cc,dd,ee)
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (bb,dd,ee)
Western Plastics Corp., Neb (bb,dd,ee)
Westlake Plastics Co., Pa (t,bb,cc,dd, ee)

## Polycarbonate Plastics

Commercial Plastics & Supply Corp., NY (bb,cc,dd,ee)
Fiberfil, Inc., Ind (y)
General Electric Co., NY (p,y)
General Electric Co., Chemical Materials Dept., Mass (p,t,y)
Glass Laboratories Inc., NY (bb,dd,ee)
Mobay Chemical Co., Pa (p,t,y)
Pennsylvania Fluorocarbon Co., Inc., Pa (ee)
Polymer Corp., Pa (y)
Polymer Corp. of Pennsylvania, Sub. of Polymer Corp., Pa (bb,cc,dd,ee)
Southern Plastics Co., SC (bb,cc,dd,ee)
Visking Co., Div. of Union Carbide Corp., Ill (t)

## Polyesters

Adhesive Products Corp., NY (x)
Aerojet-General Corp., Structural Materials Div., Calif (y)
Alcylite Plastics & Chemical Corp., Calif (p)
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY (p,y)
Alsynite Co. of America, Calif (cc)
**American Cynamid Co., Plastics & Resins Div., NY**
(x)—Ad pp 251-254
American Metaseal Corp., NJ (p)
American Products Mfg. Co., Inc., La (p)
Archer-Daniels-Midland Co., Minn (p)
Atlas Mineral Products Co., Pa (x)
**Atlas Powder Co., Chemicals Div., Del**
(p,x,y)—Ad p 262
Auburn Plastic Engineering, Ill (t,bb, cc,ee)
Avery Label Co., Decorative Products Div., Ohio (t)
Boonton Molding Co., NJ (x)
Brown Rubber Co., Inc., Ind (u)
Burkart, F. Mfg. Co., Div. of Textron Inc., Mo (u)
Cadillac Plastic & Chemical Co., Mich (t,x,cc)
Califbe Co., Inc., Calif (cc,ee)
Cast Optics Corp., NJ (cc)
**Celanese Plastics Co. Div., Celanese Corp. of America, NJ**
(p)—Ad pp 271-274
Chemical Process Co., Calif (p,x,y)
**Coating Products, Inc., NJ**
(t,cc)—Ad p 359
Colonial Kolonite Co., Ill (cc)
Columbia - Geneva Steel Div., U.S. Steel Corp., Calif (ee)
Continental-Diamond Fibre Corp., Del (bb,cc,dd,ee)
Cordo Chemical Corp., Conn (x,y)
Cordo Molding Products, Inc., Conn (y)
CrystalX Corp., Pa (t,bb,cc,dd,ee)
Curbell, Inc., NY (f)
Dayton Rubber Co., Ohio (x,y)
**Dobeckmun Co., Div. of Dow Chemical Co., Ohio (x)**
Douglas & Sturgess, Calif (x,y) (s,t)
du Pont de Nemours, E. I. & Co., Inc., Del (s,t)
**Durez Plastics Div., Hooker Chemical Corp., NY**
(p,x,y)—Ad pp 232-233
Everlite Corp., Wash (cc)
Fiber Glass Industries, Inc., NY (x,y, cc)
Fiberglass Ohio Inc., Ohio (cc)
Flexfirm Products, Calif (s,y)
Flexible Tubing Corp., Conn (ee)
Foam Products, Inc., Pa (u)
Foamade Industries, Mich (u)
Foss Mfg. Co., Id (x)
Fry Plastics International, Calif (p,x)
Gallgher Co., Utah (p,s,x)
General Electric Co., NY (x)
General Plastics Mfg. Co., Wash (x, cc)
General Tire & Rubber Co., Chemical Div., Ohio (p)
Glass Reinforced Plastics Corp., Ohio (bb,ee)
Glastic Corp., Ohio (y,bb,cc)
Goodrich, B.F. Co., Sponge Products Div., Conn (u)
Goodyear Tire & Rubber Co., Chemical Div., Ohio (p)
Hall, C.P. Co., Ohio (p)
Haskelite Mfg. Corp., Mich (cc,dd)
Hastings & Co., Inc., Pa (t)
Haveg Industries, Inc., Del (cc)
Hays Mfg. Co., Pa (y,cc)
**Industrial Paint Div., Glidden Co., Ohio**
(p,x)—Ad p 248
Insulation Mfrs. Corp., Ill (cc,dd)
Interchemical Corp., NY (p,x,y)
Interchemical Corp., Finishes Div., NJ (p,x)
Johns-Manville Corp., NY (cc)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Kish Industries, Inc., Mich (x)
Laminated Plastex Corp., Ohio (x,cc)
Lewis, G.B. Co., Wis (bb)
Luminous Resins, Inc., Ill (y)
Maloney, F.H. Co., Tex (x,y)
Micarta Div., Westinghouse Electric Corp., SC (p,y)
Minnesota Mining & Mfg. Co., Minn (s)
Mobay Chemical Co., Mo (p)
Muehlstein, H. & Co., Inc., NY (p)
Narmco Industries, Inc., Narmco Materials Div., Calif (x,y,dd)
National Vulcanized Fibre Co., Del (cc,dd)
Naugatuck Chemical Div., U.S. Rubber Co., Conn (p,u,x,y)
Nopco Chemical Co., NJ (p)
Omni Products Corp., NY (p)
Ormond Mfg. Co., Inc., NJ (cc,dd)
Panelyte Div., St. Regis Paper Co., NJ (x,y,cc)
Peiron Corp., Ill (p,x,y)
Penn Fibre & Specialty Co., Inc., Pa (cc)
Philrus Products Co., NJ (bb,cc,dd)
Pittsburgh Plate Glass Co., Pa (p,u, x,y)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Plumb Chemical Corp., Pa (y)
Polycast Corp., Conn (cc)
Polygon Plastic Co., Ind (bb,ee)
Porter, William Co., Calif (ee)
Precision Paper Tube Co., Ill (ee)
Prince Rubber & Plastics Co., Inc., NY (cc)
Reichhold Chemicals, Inc., NY (p,u,x)
Robertson, H.H. Co., Pa (p)
Rohm & Haas Co., Pa (x,y)
Roller Reinforced Plastics, Ohio (x,y)
Rubber Corp. of America, NY (u)
Schorl Process Div., Ferro-Co Corp., NY (cc,ee)
Schwab Plastic Corp., Mich (u)
Schwartz Chemical Co., Inc., NY (x)
Sheller Mfg. Corp., Mich (u)
Specialty Resins Co., Calif (p,x)
Strick Plastics Co., Pa (u,cc,dd)
Sun Chemical Corp., Electro Technical Div., NJ (p,x)
Swedlow, Inc., Calif (cc)
Thalco, Calif (p)
United Shoe Machinery Corp., Mass (x)
U.S. Polymeric Chemicals, Inc., Conn (s)
U.S. Rubber Co., NY (p,u,x)
Varflex Corp., NY (ee)
Wasco Products, Inc., Mass (cc)
Williamson Adhesives, Inc., Ill (y)
Witco Chemical Co., Ill (p,u)
Woodall Industries, Inc., Mich (y)
Zenith Plastics Co., Sub. of Minnesota Mining & Mfg. Co., Calif (u)

## Polyethylenes

aaRBee Plastic Co., Calif (y)
Ace Plastic Co., NY (bb,cc,dd,ee)
Adhesive Products Corp., NY (x)
Advance Screw Products Co., Inc., Wis (bb)
Aladdin Transparent Packaging Corp., NY (t,ee)
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY (p,y)
Allied Resinous Products, Inc., Ohio (y,bb,cc,dd,ee)
Alpha Wire Corp., NY (ee)
American Agile Corp., Ohio (bb,cc,dd, ee)
American Hard Rubber Co., Div. of Amerace Corp., NY (bb,dd)
American Molding Powder & Chemical Co., NY (y)
Anchor Plastics Co., Inc., NY (bb,dd, ee)
Anderson Asso., Inc., Ohio (y)
Anesit Co., Ill (ee)
Auburn Plastic Engineering, Ill (t,bb, cc,ee)
Auburn Plastics Inc., NY (bb,cc,dd,ee)
Bamberger, Claude P., Inc., NJ (p,y)
Blacher, B., NY (t)
Blank, Arthur & Co., Inc., Mass (t)
Blossom Mfg. Co., Inc., NY (t,cc)
Bolta Products Div., General Tire & Rubber Co., Mass (s)
Cadillac Plastic & Chemical Co., Mich (t,bb,cc,dd,ee)
**Campco Div., Chicago Molded Products Corp., Ill**
(t,cc)—Ad p 243
Carroll, J.B. Co., Ill (cc)
Catalin Corp. of America, NY (y)
**Celanese Plastics Co., Div. of Celanese Corp. of America, NJ**
(p,t,y,cc)—Ad pp 271-274
Celluplastic Corp., NJ (bb,ee)
Chester Packaging Div., St. Regis Paper Co., NY (t,cc)
Chippewa Plastics Co., Wis (t,ee)
Clopay Corp., Ohio (t,cc)
Clover Industries, Inc., NY (y)
Colonial Kolonite Co., Ill (bb,cc,ee)
Commercial Plastics & Supply Corp., NY (bb,cc,dd,ee)
Conneaut Rubber & Plastics Co., Div. of U.S. Stoneware Co., Ohio (t,bb, cc,dd,ee)
Contour Extrusion Co., NY (t,bb,cc,dd, ee)
Copper and Brass Sales, Inc., Mich (ee)
Cosmo Plastics Co., Ohio (u)
Crane Plastics, Inc., Ohio (bb,dd,ee)
Crescent Plastics, Inc., Ind (ee)
CrystalX Corp., Pa (t,bb,cc,dd,ee)
Curbell, Inc., NY (s,bb,cc,dd,ee)
Danielson Mfg. Co., Conn (bb)
Dapol Plastics, Inc., Mass (y)
Davis, Joseph Plastics Co., NJ (t,y, bb,cc,dd,ee)
Denver Plastics, Inc., Colo (t,u,bb,cc, dd,ee)
Designers Metal Corp., Ill (cc)
Dobeckmun Co., Div. of Dow Chemical Co., Ohio (x)
Dow Chemical Co., Plastics Div., Mich (p,t,y)
du Pont de Nemours, E. I. & Co., Inc., Del (p,y)
Dura-Lee Corp., Kan (t)
Durable Formed Products, Inc., NY (cc,ee)
Durethene Corp., Ill (t)
Eastman Chemical Products, Inc., Sub. of Eastman Kodak Co., NY (p,u,y)
Eclipse Plastic Industries, Inc., Fla (bb,cc,dd,ee)
Extruders, Inc., Calif (t)
Firestone Plastics Co., Pa (s,t)
Flexible Packaging Div., Continental Can Co., Inc., Ohio (t,cc)
Foamade Industries, Mich (u,cc,dd)
Foss Mfg. Co., Id (t)
Foster Grant Co., Mass (t)
Fox Edge Co., Inc., Mass (s)
Gallgher Co., Utah (bb,cc,dd,ee)
Garlock Packing Co., NY (y)
Geauga Industries Co., Ohio (bb,dd)
General Electric Co., NY (t)
General Gasket, Inc., Conn (t,cc)
General Plastics Corp., Ind (cc)
General Plastics Mfg. Co., Wash (cc)
General Tire & Rubber Co., Ind (t,cc)
Genesee Laboratory, Inc., NY (ee)
Gering Plastics, Div. of Studebaker-Packard Corp., NJ (t,y,bb,dd,ee)
Glass Laboratories, NY (bb,dd,ee)
Goodrich-Gulf Chemicals, Inc., Ohio (p)
Grace, W.R. & Co., Polymer Chemicals Div., NJ (p,y)
Grigoleit Co., Ill (p,s)
H & R Industries, Pa (t,bb,cc,dd,ee)
Hastings & Co., Inc., Pa (t)
Hercules Powder Co., Inc., Del (p,y)
Heyden Newport Chemical Corp., American Plastics Corp. Div., NY (bb,cc,ee)
Hydrawlik Co., NJ (bb,dd)
Industrial Plastics Corp., Ind (bb,dd)
Insulation Mfrs. Corp., Ill (cc,ee)
Jet Specialties Co., Inc., Calif (bb,cc, dd,ee)
KSH Plastics, Inc., Mo (bb,cc,dd)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Kaykor Industries, Inc., Div. of Kaye-Tex Mfg. Corp., NJ (cc)
Koppers Co., Inc., Plastics Div., Pa (p,y)
Kuss, R.L. & Co., Inc., Ohio (t)
Ludlow Plastics, Mass (t)
Luminous Resins, Inc., Ill (y)
Lus-Trus Corp., Mich (cc,ee)
Maloney, F.H. Co., Tex (y)
Manufacturers Corp., Ohio (ee)
Mason Envelope Co., Inc., NY (t)
Mayon Plastics, Minn (ee)
Midwest Plastic Products Co., Ill (t, cc)

Monsanto Chemical Co., Plastics Div., Mass (p,y)
Moore, Samuel & Co.,Ohio (ee)
Muehlstein, H & Co., Inc., NY (y)
Murray, A.B. Co., Inc., NJ (ee)
Naige Co., Inc., NY (ee)
National Gasket & Washer Mfg. Co., Inc., NY (bb,cc,dd,ee)
National Tube Div., U.S. Steel Corp., Pa (ee)
New England Tape Co., Div. of United-Carr Fastener Corp., Mass (dd)
Olin Mathieson Chemical Corp., Packaging Div., NY (t,ee)
Omni Products Corp., NY (y)
Ormond Mfg. Co., Inc., NJ (cc,dd)
Pacific Coast Foil Co., Calif (t)
Panelyte Div., St. Regis Paper Co., NJ (t,cc,ee)
Penn Fibre & Specialty Co., Inc., Pa (bb,cc,dd,ee)
Perfex Plastics, Inc., Ill (bb,dd,ee)
Phillips Chemical Co., Okla (p)
Plastic Compounding Corp., Sub. of Plastiglide Mfg. Co., Calif (y)
Plastic Materials, Inc., NY (y)
Plastic Packaging Co., Ill (t)
Plax Corp., Conn (t,cc)
Polo Plastics Co., Wis (t)
Polymer Corp., Pa (y)
Polyplastic Products, Inc., NJ (t,cc)
Precision Paper Tube Co., Ill (cc)
Presto Plastic Products Co., Inc., NY (t,cc)
Prince Rubber & Plastics Co., Inc., NY (bb,cc,dd,ee)
Pyramid Industries, Inc., Pa (ee)
Pyramid Plastics, Inc., Ill (dd,ee)
Reed Plastics Corp., Mass (y)
Reliance Plastic & Chemical Corp., NJ (t,bb,dd)
Reynolds Aluminum Supply Co., Ga (t)
Reynolds Metals Co., Va (t,cc)
Ross & Roberts, Inc., Conn (t)
Rubber & Plastics Compound Co., Inc., NY (t)
Russell Mfg. Co., Conn (s)
Ryerson, Joseph T. & Son, Inc., Ill (ee)
Schwab Plastic Corp., Mich (u,bb,cc, dd,ee)
Scranton Plastic Laminating Corp., Pa (cc)
Seiberling Rubber Co., Plastics Div., Ohio (bb,cc)
Shaw-Kendall Engineering Co., Ohio (ee)
Sheller Mfg. Corp., Mich (u)
Simon Products Co., Ill (t)
Snyder Mfg. Co., Inc., Ohio (t,cc)
Southern Plastics Co., SC (bb,cc,dd,ee)
Spencer Chemical Co., Mo (p,x,y)
Staver Co., Inc., NY (cc,dd)
Sunlites Plastics, Inc., Wis (bb,dd,ee)
Superior Mfg. Co., Pa (dd)
Superior Plastics, Inc., Ill (bb,cc,dd, ee)
Supplex Co., Div. of Amerace Corp., NJ (y,dd,ee)
Technical Tape Corp., NY (t,cc,ee)
Thombert, Inc., Iowa (cc,ee)
Triangle Conduit & Cable Co., Inc., NJ (ee)
Toyad Corp., Pa (u)—Ad p 260
Union Carbide Plastics Co., Div. of Union Carbide Corp., NY (p,y)—Ad p 257
U.S. Industrial Chemicals Co., Div. of National Distillers & Chemical Corp., NY (p,x,y)
U.S. Stoneware Co., NY (y)
Varflex Corp., NY (ee)
Visking Co., Div. of Union Carbide Corp., Ill (t)
Vogt Mfg. Corp., NY (bb,dd)
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (s,bb,dd,ee)
Western Felt Works, Ill (cc)
Western Plastics Corp., Neb (bb,dd,ee)
Western Plastics Corp., Wash (ee)
Westlake Plastics Co., Pa (t,bb,cc,dd, ee)
William Brand-Rex Div., American Enka Corp., Mass (ee)
Woodall Industries, Inc., Mich (cc)
World Plastics, NY (bb,cc,dd,ee)

## Polypropylene

Avi Sun Corp., Pa (y)—Ad pp 244-245
Campco Div., Chicago Molded Products Corp., Ill (t,cc)—Ad p 243
Catalin Corp. of America, NY (y)
Chemore Corp., NY (p,s,y)
Chippewa Plastics Co., Wis (t)
Conneaut Rubber and Plastics Co., Div. of U. S. Stoneware Co., Ohio (bb,cc,dd,ee)
Crane Plastics, Inc., Ohio (bb,dd,ee)
Eastman Chemical Products, Inc., Sub. of Eastman Kodak Co., NY (p,y)
Enjay Chemical Co. Div., Humble Oil & Refining Co., NY (y)
Hercules Powder Co., Del (y)
Industrial Rayon Corp., NY (s)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Ludlow Plastics, Mass (t)
Madin Plastics Inc., NJ (y,cc)
Naige Co., Inc., NY (ee)
Spencer Chemical Co., Mo (y)
Texas Eastman Co., Div. of Eastman Kodak Co., Tex (y)
Visking Co., Div. of Union Carbide Corp., Ill (t)

## Polystyrenes

(Incl. copolymers and modifications)

aaRite Plastic Co., Calif (y)
Ace Plastic Co., NY (bb,cc,dd,ee)
Adhesive Products Corp., NY (x)
Ambassador Plastics & Mfg. Corp., Ill (u)
American Cyanamid Co., Plastics & Resins Div., NY (y)
American Hard Rubber Co., Div. of Amerace Corp., NJ (bb,cc,dd,ee)
Anchor Plastics Co., Inc., NY (bb,dd, ee)
Anderson Asso., Inc., Ohio (y)
Anesit Co., Ill (ee)
Auburn Plastic Engineering, Ill (bb,cc, ee)
Auburn Plastics, Inc., NY (bb,cc,dd, ee)
Bamberger, Claude P., Inc., NJ (p,y)
Blank, Arthur & Co., Inc., Mass (cc)
Bolta Products Div., General Tire & Rubber Co., Mass (t,cc)
Cadillac Plastic & Chemical Co., Mich (bb,cc,dd,ee)
Campco Div., Chicago Molded Products Corp., Ill (t,cc)—Ad p 243
Catalin Corp. of America, NY (y)
Chemical Development Corp., Mass (p)
Coating Products, Inc., NJ (t,cc)
Colonial Kolonite Co., Ill (bb,cc,ee)
Commercial Plastics & Supply Corp., NY (bb,cc,dd)
Conneaut Rubber & Plastics Co., Div. of U.S. Stoneware Co., Ohio (bb, cc,dd,ee)
Cosmo Plastics Co., Ohio (u)
Crane Plastics, Inc., Ohio (bb,dd,ee)
Crescent Plastics, Inc., Ind (ee)
CrystalX Corp., Pa (t,bb,cc,dd,ee)
Curbell, Inc., NY (bb,cc,ee)
Dapol Plastics, Inc., Mass (y)
Denver Plastics, Inc., Colo (u)
Dewey & Almy Chemical Co., Div. of W.R. Grace Co., Mass (p)
Dobeckmun Co., Div. of Dow Chemical Co., Ohio (x)
Dow Chemical Co., Plastics Div., Mich (p,t,u,y)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (y)
Dumont Corp., Calif (u)
Dura Plastics of New York, Inc., NY (bb,cc)
Dyna-Therm Chemical Corp., Calif (p)
Eclipse Plastic Industries, Inc., Fla (bb,cc,dd,ee)
Emerson & Cuming, Inc., Mass (u,x,bb)
Fiberfil, Inc., Ind (y)
Foam Products, Inc., Pa
Foster Grant Co., Mass (p,s,y,cc)
Fry Plastics International, Calif (cc)
Galigher Co., Utah (bb,cc,dd,ee)
General Plastics Corp., Ind (cc)
General Plastics Mfg. Co., Wash (bb, cc,dd,ee)
Gering Plastics, Div. of Studebaker-Packard Corp., NJ (y,bb,dd,ee)
Glass Laboratories, NY (bb,dd,ee)
Glo-Brite Products, Inc., Ill (u,y,cc)
Goodyear Tire & Rubber Co., Ohio (y)
H & R Industries, Pa (bb,cc,dd,ee)
Haskelite Mfg Corp., Mich (u)
Hayden Wire Works, Inc., Mass (x)
Heyden Newport Chemical Corp., American Plastics Corp. Div., NY (bb, cc,dd,ee)
Industrial Plastics Corp., Ind (bb,dd)
KSH Plastics Inc., Mo (bb,cc,dd)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Kaykor Industries, Inc., NJ (cc)
Koppers Co., Plastics Div., Pa (p,u,y)—Ad pp 264-265
Laminated Plastex Corp., Ohio (x,cc)
Lone Star Plastics Co., Inc., Tex (u)
Luminous Resins, Inc., Ill (y)
Lus-Trus Corp., Mich (cc,ee)
Maloney, F.H. Co., Tex (x,y)
Manufacturers Corp., Ohio (ee)
Marbon Chemical Div., Borg-Warner Corp., Ind (p,y)
Midwest Plastic Products Co., Ill (t, cc)
Monsanto Chemical Co., Mass (p,y)
Muehlstein, H. & Co., Inc., NY (p,y)
Murray, A.B. Co., Inc., NJ (ee)
Naugatuck Chemical Div., U.S. Rubber Co., Conn (p,y)
Nesbitt Industries, Inc., Ill (u)
Nixon Nitration Works, NJ (cc)
Northwest Plastics Industries, Inc., Wash (u)
Omni Products Corp., NY (y)
O'Sullivan Rubber Corp., Plastics Div., Va (t,cc)
Panelyte Div., St. Regis Paper Co., NJ (u,bb,cc)
Perfex Plastics, Inc., Ill (bb,dd,ee)
Plastic Materials, Inc., NY (y)
Plax Corp., Conn (t,cc)
Polymer Corp. of Pennsylvania, Sub. of Polymer Corp., Pa (bb,cc)
Precision Paper Tube Co., Ill (ee)
Prince Rubber & Plastics Co., Inc., NY (bb,cc,ee)
Pyramid Plastics, Inc., Ill (dd,ee)
Reed Plastics Corp., Mass (y)
Schwab Plastic Corp., Mich (u,bb,cc, dd,ee)
Scranton Plastic Laminating Corp., Pa (cc)
Seiberling Rubber Co., Plastics Div., Ohio (bb,cc)
Sheffield Plastics Co., Mass (cc)
Sheller Mfg. Corp., Mich (u)
Snyder Mfg. Co., Inc., Ohio (t,cc)
Southern Plastics Co., SC (bb,cc,dd,ee)
Sterling Models, Pa (u)
Strick Plastics Co., Pa (u)
Sunlites Plastics, Inc., Wis (bb,dd,ee)
Superior Plastics, Inc., Ill (bb,cc,dd, ee)
Toyad Corp., Pa (u)—Ad p 260
Union Carbide Plastics Co., Div. of Union Carbide Corp., NY (p,y)—Ad p 257
United Shoe Machinery Corp., Mass (p,u)
Visking Co., Div. of Union Carbide Corp., Ill (t)
Western Felt Works, Ill (cc)
Western Plastics Corp., Neb (bb,dd,ee)
Western Plastics Corp., Wash (ee)
Westlake Plastics Co., Pa (t,y,bb,cc, dd,ee)
William Brand-Rex Div., American Enka Corp., Mass (bb,cc)
Woodall Industries, Inc., Mich (cc)
Worcester Moulded Plastics Co., Mass (u)
World Plastics, NY (bb,cc,dd,ee)

## Polysulfide Rubber

Adhesive Products Corp., NY (x)
Armstrong Cork Co., Pa (bb,cc,dd)
Beiko Corp., Md (y)
Bond International, Inc., Mich (y,ee)
Castle Rubber Co., Pa (y,bb,cc,dd,ee)
Chemical Coatings & Engineering Co., Inc., Pa (x,y)
Chicago-Allis Mfg. Corp., Ill (p)
Coast Pro-Seal Mfg. Co., Calif (y)
Dayton Rubber Co., Ohio (y,bb,cc,dd, ee)
Garlock Packing Co., NY (y,cc)
Hiller Aircraft Corp., Adhesive Engineering Div., Calif (x)
Home Rubber Co., NJ (y,bb,cc,dd)
Maloney, F.H. Co., Tex (y)
Moxness Products, Inc., Wis (bb,cc, dd,ee)
Paeco Rubber Co., Inc., Ohio (y,dd,ee)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
Parker, Stearns & Co., Inc., NY (y, bb,cc,dd,ee)

### KEY

**MATERIALS**

a—Aluminum and its alloys
b—Copper and its alloys
c—Iron and its alloys (except steel)
d—Lead and its alloys
e—Magnesium and its alloys
f—Nickel and its alloys
g—Steels
h—Titanium and its alloys
j—Zinc and its alloys
k—Thermoplastics
l—Thermosetting plastics
m—Elastomers

**BASIC FORMS**

n—Anodes
o—Bar
p—Base resins, polymers or gums
q—Billets
r—Custom formed parts (incl. specialties)
s—Fibers
t—Film
u—Foams (component materials or products)
v—Foil
w—Ingot
x—Laminating, casting resins
y—Molding compounds
z—Plate
aa—Powder
bb—Rod
cc—Sheet
dd—Strip
ee—Tubing
ff—Wire

Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Polymer Industries Inc., Conn (x)
Raybestos-Manhattan, Inc., Plastic Products Div., Pa (x)
Thiokol Chemical Corp., NJ (p,x,y)
Toyad Corp., Pa (u)
Trostel, Albert Packing, Ltd., Wis (y)
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (p,y,cc)
Vulcanized Rubber & Plastics Co., Pa (y)
Western Felt Works, Ill (y,cc,dd,ee)
Williams-Bowman Rubber Co., Ill (y,bb,cc,dd,ee)

## Polyvinyl Alcohols

(see Vinyls)

## Polyvinyl Chloride and Copolymers

(see Vinyls)

## Porcelain

(see Ceramics)

## Porcelain Enamels

(see Inorganic Coatings)

## Powdered Metals

(see Iron Powders or specific metal)

## Precoated Metals —Aluminized

American Chain & Cable Co., Pa (g)
Armco Steel Corp., Ohio (g)
Bethlehem Steel Co., Pa (g)
Biersach & Niedermeyer Co., Wis (a)
Brasco Mfg. Co., Ill (g)
Clad-Rex Corp., Ill (a,g)
Colonial Alloys Co., Pa. (a)
Enamel Products Co., Ohio (g)
Gillett & Eaton, Inc., Minn (c)
Grigoleit Co., Ill (a)
Ideal Can Co., Mass (g)
Jackson Steel Products, Inc., NY (g)
Kassel Export Co., Inc., NJ (c,g)
Kees, F.D. Mfg. Co., Neb (g)
Mayville Metal Products Co., Wis (g)
National Galvanizing Co., Pa (g)
Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa (g)
Rome Mfg. Div., Revere Copper & Brass, Inc., NY (g)
Sager Metal Strip Co., Ill (a)
Sun Steel Co., Ill (g)
Tickle, Arthur Engineering Works, Inc., NY (c,g)
Whitehead Metal Products Co., Inc., NY (g)
Whyte, Oliver Co., Inc., Mass (g)

## Precoated Metals —Galvanized

Albert Pipe Supply Co., Inc., NY (g)
Anderson-Bolling Mfg. Co., Mich (g)
Armco Steel Corp., Ohio (g)
Associated Spring Corp., Wallace Barnes Div., Conn (g)
Atlantic Steel Co., Ga (g)
Bethlehem Steel Co., Pa (c,g)
Biersach & Niedermeyer Co., Wis (g)
Bignall Co., NY (c)
Brasco Mfg. Co., Ill (g)
Brewer-Titchener, Corp., NY (g)
Byers, A.M. Co., Pa (c)
Castle, A.M. & Co., Ill (a,g)
Clad-Rex Corp., Ill (g)
Columbia - Geneva Steel Div., U.S. Steel Corp., Calif (g)
Conner Mfg. Co., Ky (g)
Continental Nu-Steel Metal Products Div., Continental Wire & Iron Works, Ill (g)
Continental Steel Corp., Ind (g)
Edgcomb Steel & Aluminum Corp., NJ (g)
Empire-Reeves Steel Div., Universal-Cyclops Steel Corp., Pa (g)
Enterprise Galvanizing Co., Pa (g)
Grand Sheet Metal Products Co., Consumer Products Div., Ill (c)
Granite City Steel Co., Ill (g)
Hobbs, Clinton E. Co., Mass (c,g)
Ideal Can Co., Mass (g)
Jackson Steel Products, Inc., NY (g)
Kelley Mfg. Co., Tex (g)
Koehler Mfg. Co., Mass (c,g)
Levinson Steel Co., Pa (g)
Mahon, R.C. Co., Mich (g)
Mayville Metal Products Co., Wis (g)
McNally Pittsburg Mfg. Co., Kan (g)
National Galvanizing Co., Pa (g)
National Tube Div., U.S. Steel Corp., Pa (g)
New York Iron Roofing & Corrugating Co., Inc., NJ (g)
Newport Steel Corp., Ky (g)
Nikoh Tube Co., Ill (g)
Northwestern Steel & Wire Co., Ill (g)
Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa (g)
**Republic Steel Corp., Ohio** (g)—Ad pp 84-85
Riverside Foundry & Galvanizing Co., Mich (c,g)
Roebling's John A. Sons Div., Colorado Fuel & Iron Corp., NJ (g)
Rome Mfg. Div., Revere Copper & Brass, Inc., NY (g)
Ryerson, Joseph T. & Son, Inc., Ill (g)
Sharon Steel Corp., Pa (g)
Sherman & Reilly, Inc., Tenn (e,f,g)
Solar Steel Corp., Ohio (g)
Southern Galvanizing Co., Md (g)
Southern Metal Products Co., La (g)
Stainless and Strip Div., Jones & Laughlin Steel Corp., Ohio (g)
Stenman, Bror F., Mass (g)
Sun Steel Co., Ill (g)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (g)
Thomas Strip Div., Pittsburgh Steel Co., Pa (g)
U. S. Steel Corp., Pa (g)
U.S. Steel Supply Div., U.S. Steel Corp., Ill (g)
Vulcan Rail & Construction Co., NY (g)
Weirton Steel Co., Div. of National Steel Corp., W. Va (g)
Wesbar Stamping Corp., Wis (c,g)
Wheeling Steel Corp., W.Va (g)
Witt Cornice Co., Galvanizing Div., Ohio (g)
Worcester Wire Works Div., National-Standard Co., Mass (g)
Youngstown Kitchens Div., American Standard Co., Ohio (a,g)
Youngstown Sheet & Tube Co., Ohio (g)

## Precoated Metals —Lead or Terne-Coated

Acme Stamping & Wire Forming Co., Pa (a,b,g)
Anderson-Bolling Mfg. Co., Mich (g)
Armco Steel Corp., Ohio (c,g)
Biersach & Niedermeyer Co., Wis (g)
Brasco Mfg. Co., Ill (g)
Cartwright, R. Tube Products Co., Mich (g)
Caspers Tin Plate Co., Ill (g)
Columbia - Geneva Steel Div., U.S. Steel Corp., Calif (g)
Composite Industrial Metals, Inc., RI (a,b,c,d,e,f,g,h,j)
Empire-Reeves Steel Div., Universal-Cyclops Steel Corp., Pa (g)
Follansbee Steel Corp., Sheet Metal Specialty Div., W.Va (g)
Hayden Wire Works, Inc., Mass (d)
Higbie Mfg. Co., Mich (g)
Houston Blow Pipe & Sheet Metal Works, Tex (g)
Ideal Can Co., Mass (g)
Langsenkamp, F.H. Co., Ind (b)
National Lead Construction Co., Inc., NJ (d)
New Haven Copper Co., Conn (b)
Nikoh Tube Co., Ill (g)
Philadelphia Steel & Wire Corp., Pa (g)
Presswork, Inc., Mich (b,g)
Reactive Metals, Inc., Ohio (g)
**Republic Steel Corp., Ohio** (g)—Ad pp 84-85
Revere Copper & Brass, Inc., NY (b)
Rome Mfg. Co., Revere Copper & Brass, Inc., NY (g)
Ryerson, Joseph T. & Son, Inc., (g)
Sharon Steel Corp., Pa (g)
Solar Steel Corp., Ohio (g)
Steel Protection & Chemical Co., Ind (a,b,c,f,g)
Sun Steel Co., Ill (g)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (g)
Thomas Strip Div., Pittsburgh Steel Co., Pa (g)
U.S. Steel Supply Div., U.S. Steel Corp., Ill (g)
Wayne Foundry & Stamping Co., Mich (g)
Weirton Steel Co., Div. of National Steel Corp., W. Va (g)
Wesbar Stamping Corp., Wis (c,g)
Wheeling Steel Corp., W.Va (g)
Whitehead Metal Products Co., Inc., NY (b,g)
Wisconsin Tool & Stamping Co., Ill (g)
Wright Metalcoaters, NJ (a,b,c,e,f,g)
Youngstown Kitchens Div., American Standard Co., Ohio (a,g)

## Precoated Metals —Tin-Coated

Acme Stamping & Wire Forming Co., Pa (a,b,g)
American Silver Co., NY (a,b,e,f,g)
Anderson-Bolling Mfg. Co., Mich (g)
Association Spring Corp., Wallace Barnes Steel Div., Conn (g)
Bethlehem Steel Co., Pa (g)
Brasco Mfg. Co., Ill (g)
Caspers Tin Plate Co., Ill (g)
Columbia - Geneva Steel Div., U.S. Steel Corp., Calif (g)
Composite Industrial Metals, Inc., RI (a,b,c,d,e,f,g,j)
Conner Mfg. Co., Ky (g)
Granite City Steel Co., Ill (g)
Inland Steel Co., Ill (g)
Kaiser Steel Corp., Calif (g)
Koehler Mfg. Co., Mass (c,g)
Lundquist Tool & Mfg. Co., Inc., Mass (a,g)
Olean Electro Plating Co., NY
Philadelphia Steel & Wire Corp., Pa (g)
**Republic Steel Corp., Ohio** (g)—Ad pp 84-85
Riverside Foundry Co., Pa (c)
Smithers Tool & Machine Products, Inc., NY (g)
Solar Steel Corp., Ohio (g)
Somers Brass Co. Inc., Conn (b,f)
Stainless and Strip Div., Jones & Laughlin Steel Corp., Ohio (g)
Steel Protection & Chemical Co., Ind (a,b,c,f,g)
Sun Steel Co., Ill (g)
U. S. Steel Corp., Pa (g)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (g)
Wabash Metal Products Co., Inc., Ind (g)
Weirton Steel Co., Div. of National Steel Corp., W.Va (g)
Wheeling Steel Corp., W.Va (g)
Wisconsin Tool & Stamping Co., Ill (g)
Wright Metalcoaters, NJ (a,b,c,e,f,g)
Youngstown Sheet & Tube Co., Ohio (g)

## Pre-Impregnated Materials for Plastic Laminates

American Plastics Corp., NY (l)
Apex Reinforced Plastics Div., White Sewing Machine Corp., Ohio (l)
Cincinnati Industries Inc., Ohio (k)
Coast Mfg. & Supply Co., Calif (l)
**Cordo Chemical Corp., Conn** (k,l,m)—Ad p 269
**Cordo Molding Products, Inc., Conn** (l)—Ad p 269
Eljay Corp., Md (k,l)
Emerson & Cuming, Inc., Mass (k,l,m)
**Fabricon Products Div., Eagle-Picher Co., Mich** (l)—Ad p 275
**Firmaline Products of Crompton & Knowles, NJ** (k,l)—Ad p 457
Flexfirm Products, Calif (k,l)
Flexible Tubing Corp., Conn (k)
**Glastic Corp., Ohio** (l)—Ad p 256
Haveg Industries Inc., Del (l)
Luminous Resins Inc., Ill (k)
Maloney, F.H. Co., Tex (l)
Micarta Div., Westinghouse Electric Corp., SC (l)
Minnesota Mining & Mfg. Co., Minn (l)
**Minnesota Mining & Mfg. Co., Reinforced Plastics Div., Minn** (l)—Ad pp 258-259
Modiglass Fibers, Inc., NJ (k,l)
Narmco Industries, Inc., Narmco Materials Div., Calif (l)
New England Laminates Co., Conn (l)
Panelyte Div., St. Regis Paper Co NJ (l)
Raybestos Div., Raybestos-Manhattan, Inc., Conn (l)
Riegel Paper Corp., NY (k,l)
Rogers Corp., Conn (l)
Russell Mfg. Co., Conn (l)
Spaulding Fibre Co., Inc., NY (l)
Standard Insulation Co., Plastics Div., NJ (l)
Sun Chemical Corp., Electro Technical Div., (k,l,m)
Swedlow, Inc., Calif (l)
U.S. Polymeric Chemicals, Inc., Conn (l,m)

## Prepainted Metals

(see Organic Coatings)

## Preplated Metals

(chromium, nickel)

Acme Stamping & Wire Forming Co., Pa (a,b,g)
Aluminum Co. of America, Pa (a)
American Nickeloid Co., Ill (a,b,g,j)
American Silver Co., Inc., NY (b,f,g)
Apollo Metal Works, Ill (b,c,g,j)
Benjamin Electric Mfg. Co., Ill (g)
Chromalloy Corp., NY (g)
Enamelstrip Corp., Sub. of National Steel Corp., Pa (a,b,c,f,g,h,j)
Fromson Orban Co., Inc., NY (a)
Grand Sheet Metal Products Co., Consumer Products Div., Ill (a,b,c,e,f,g,h,j)
Grigoleit Co., Ill (a,g)
Hayden Wire Works, Inc., Mass (a,b,f,j)
Haydon Corp., NY (g)
Kassel Export Co., Inc., NJ (g)
Kroh Wagner, Ill (a,g)
Metal Trims, Inc., Miss (a)
Pittsburgh Steel Co., Pa (b,d,f,j)
**Republic Steel Corp., Ohio** (g)—Ad pp 84-85
Rigidized Metals Corp., NY (a,g)

Roebling's John A. Sons Div., Colorado Fuel & Iron Corp., NJ (g)
Sheldon, M. L. & Co., Inc., NY (f)
Sun Steel Co., Ill (g)
Sylvania Electric Products, Inc., Parts Div., Pa (a,b,c,f,g)
Thomas Strip Div., Pittsburgh Steel Co., Pa (b,f,j)
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY (g)
Worcester Wire Works Div., National-Standard Co., Mass (g)
Wright Metalcoaters, NJ (a,b,c,e,f,g)

## Pressure Sensitive Tapes

(see tapes)

## Protein Plastics

Adhesive Products Corp., NY (x)
American Hard Rubber Co., Div. of Amerace Corp., NJ (bb,cc,dd,ee)
American Plastics Corp., NY (bb,cc)
Borden Co., Borden Chemical Div., NY (p)
Chemical Process Co., Calif (x)
Heyden Newport Chemical Corp., American Plastics Corp. Div., NY (bb, cc,dd)
National Casein Sales, Ill (p)
Reichhold Chemicals, Inc., NY (p)

## Quartz

(see Ceramics)

## Rare Earth Metals

American Metallurgical Products Co., Pa
Davison Chemical Co., Div. of W. R. Grace & Co., Md
Foote Mineral Co., Pa
Heavy Minerals Co., Tenn
Lindsay Chemical Div., American Potash & Chemical Corp., Ill
Maywood Chemical Works, NJ
Michigan Chemical Corp., Rare Earths & Thorium Div., Mich
Molybdenum Corp. of America, Pa
Research Chemicals Div., Nuclear Corp. of America, Calif
Union Carbide Metals Co., Div. of Union Carbide Corp., NY
United Mineral & Chemical Corp., NY

## Refractories, Aluminide

Commercialores, SC (aa)
Coors Porcelain Co., Colo (r,bb,ee)
Du-Co Ceramics Co., Pa (r,z,bb,ee)
Engineered Ceramics Mfg. Co., Ill (r,z,bb,ee)
Ironton Fire Brick Co., Ohio (r)
Louthan Mfg. Co. Div., Ferro Corp., Ohio (r,z,bb,cc,ee)

## Refractories, Boride

Carborundum Co., Refractories Div., NJ (r,bb,ee)
Electro Refractories & Abrasives Corp., NY (aa)
Firth Sterling, Inc., Pa (r)
Norton Co., Mass (r,aa)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)

## Refractories, Carbide

Carborundum Co., Refractories Div., NJ (r,u,aa,bb,ee)
Continental Coatings Corp., Ohio (aa)
Engineered Ceramics Mfg. Co., Ill (r,z,bb,ee)
Firth Sterling, Inc., Pa (r)
Norton Co., Mass (r,z,aa,bb,ee)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)

## Refractories, Nitride

Carborundum Co., Refractories Div., NJ (r,bb,ee)
Norton Co., Mass (r,aa)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (s)

## Refractories, Oxide

**Beryllium Corp., Pa**
(r)—Ad p 157
**Brush Beryllium Co., Ohio**
(r)—Ad p 171
Carborundum Co., Refractories Div., NJ (r,s,aa,bb,ee)
Continental Coatings Corp., Ohio (aa)
Corning Glass Works, NY (r,aa)
Du-Co Ceramics Co., Pa (r,z,aa,bb,ee)
Eagle-Picher Co., Ohio (s)
Electrical Refractories Co., Ohio (r,ee)
Electro Refractories & Abrasives Corp., NY (r)
Emerson & Cuming, Inc., Mass (u,cc)
Engineered Ceramics Mfg. Co., Ill (r, z,bb,ee)
General Refractories Co., Pa (r,aa)
Laboratory Equipment Corp., Mich (r, bb,ee)
Monsanto Chemical Co., Inorganic Chemicals Div., Mo (aa)
Morganite, Inc., NY (aa,bb,ee)
Norton Co., Mass (r,z,aa,bb,ee)
Refractory Specialties Co., Pa (r)
Research Chemicals Div., Nuclear Corp. of America, Calif (aa,bb)
Saxonburg Ceramics, Inc., Pa (r,bb, cc,ee)
Thermal Refractories Corp., NJ (r,z, bb,cc,ee)
Thompson, H.I. Fiber Glass Co., Calif (s)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
Zirconium Corp. of America, Ohio (r, u,z,aa,bb,ee)

## Refractories, Silicide

Du-Co Ceramics Co., Pa (r,z,bb,ee)
Eagle-Picher Co., Ohio (s)
Electrical Refractories Co., Ohio (r)
Engineered Ceramics Mfg. Co., Ill (r,z,bb,ee)
General Ceramics Div., Indiana General Corp., NJ (r)
Ironton Fire Brick Co., Ohio (r)
Louthan Mfg. Co. Div., Ferro Corp., Ohio (r,z,bb,cc,ee)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
Western Gold & Platinum Co., Sub. of Wilbur B. Driver Co., Calif (r, z,bb,cc)

## Reinforced Plastics

(see Laminates)

## Rhenium

Chase Brass & Copper Co., Sub. of Kennecott Copper Corp., Conn (aa, bb,dd,ff)
Hardy, Charles, Inc., NY (aa)
Mallory, P.R. & Co., Inc., Ind (bb)
Nuclear Metals, Inc., Mass (w,bb)
University of Tennessee, Dept of Chemistry, Tenn (aa)

## Rock Wool

(see Inorganic Fibers)

## Rod

(see specific material)

## Rods, Welding

(see Filler Metals)

## Roll Formed Parts

Abalon Precision Mfg. Corp., NY (a, b,c,g)
Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich (g)
**Alloy Products Corp., Wis**
(a,f,g,h)—Ad p 408
Aluminum Co. of America, Pa (a)
American Brass Co., Sub. of Anaconda Co., NY (b)
American Car & Foundry Div., ACF Industries, Inc., NY (a,e,g)
American Nickel Alloy Mfg. Corp., NY (f)
American Pipe & Construction Co., Northwest Div., Ore (g)
American Welding and Mfg. Co., Ohio (a,f,g,h)
Ampco Metal, Inc., Wis (b)
Arrow Metal Products Corp., NJ (a)
Beck, I. & Sons, Inc., NY (a,b,g)
Bethlehem Steel Co., Pa (g)
Biersach & Niedermeyer Co., Wis (a, b,c,g)
Binkley Co., Mo (g)
Brown Lipe Chapin Div., General Motors Corp., NY (a,g)
Brush Beryllium Co., Ohio (b)
Bunker Hill Co., Calif (d)
Burkhardt Steel Co., Colo (c,g)
Byers, A.M. Co., Pa (c)
Carbo Tool & Die Co., Ohio (c)
Chicago Screw Co., Div. of Standard Screw Co., Ill (a,b,c,f,g)
Coast Pro-Seal & Mfg. Co., Calif (a, b,f,g,h,j)
Craft Mfg. Co., Ill (f,g)
Crucible Steel Co. of America, Pa (g,h)
Crucible Steel Co. of America, Titanium & Vacuum Metal Products Div., Pa (h)
Dahlin, C.A. Co., Ill (a,b,e,f,g,h,j)
Day Co., Minn (a,g)
Division Lead Co., Ill (d)
Dow Chemical Co., Dow Metal Products Co. Div., Mich (e)
Dresser Mfg. Div., Dresser Industries, Inc., Pa (a,f,g,h)
Eaton Mfg. Co., Reliance Div., Ohio (g)
Edgewater Steel Co., Pa (g,h)
Ellwood City Iron & Wire Co., Pa (c)
Emerson-Sack-Warner Corp., Mass (a, b,f,g)
Enamel Products Co., Ohio (c)
Fabristeel Products, Inc., Mich (g)
Falstrom Co., NJ (a,b,e,g,h)
Fitzgibbons Boiler Co., Inc., NY (c)
Fletcher Enamel Co., W. Va (a,b,c,d,e, f,g)
Grigoleit Co., Ill (a,g)
Haydon Corp., NY (a,g)
Ideal Can Co., Mass (a,b,g)
Inland Steel Co., Ill (g)
Irwin-Sensenich Corp., Pa (g)
Jackson Steel Products, Inc., NY (a, b,f,g,j)
Kaiser Steel Corp., Calif (g)
Kelley Mfg. Co., Tex (a,b,g)
Kelsey-Hayes Co., Mich (g)
Kroh Wagner, Ill (a,b)
Leach & Garner Co., Industrial Div., Mass (b,f)
Le Tourneau, R.G., Inc., Tex (g)
Lock Joint Tube Co., Inc., Ind (g)
Magnesium Co. of America, Ind (a,e)
Magnesium Products of Milwaukee, Inc., Wis (a,e)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (a,b,c,e,f,g,h)
Manufacturers & Fabricators, Inc., Ohio (f,g)
McLanahan & Stone Corp., Pa (g)
Merrimac Brass, Mass (b,f)
Metal Forming Corp., Div. of Vanadium-Alloys Steel Co., Ind (a,b,f,g)
Midvale-Heppenstall Co., Pa (c,f,g)
Mirro Aluminum Co., Wis (a)
Morse, Fred W. Co., RI (a,b,c,g,j)
Morton Mfg. Co., Ill (a,g)
National Aluminum Co., Ohio (a,g)
National Metal Products Co., Pa (a, b,g,j)
National Screw & Mfg. Co., Ohio (b,g)
Nikoh Tube Co., Ill (g)
Nippert Electric Products Co., Ohio (h)
Parish Pressed Steel Div., Dana Corp., Pa (g)
Pfister Tubing Corp., NJ (a)
Posey Iron Works, Inc., Pa (g)
Pyramid Mouldings, Inc., Ill (a,b,c,g)
Regal Ware, Inc., Wis (a,b,g)
Revere Copper & Brass, Inc., Ill (a,b, c,f,g,j)
Reynolds Aluminum Supply Co., Ga (a)
Rockwell Engineering Co., Ill (a,b,c,g)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Rohr Aircraft Corp., Calif (a)
Roll Formed Products Co., Ohio (a, b,g,h)
Ryerson, Joseph T. & Son, Inc., Ill (a,g)
Sager Metal Strip Co., Ill (a,b,c,j)
Security Cos., Mich (a)
Security Sash & Screen Co., Mich (a)
Serrick Corp., John Lees Div., Ind (a,g)
Stainless and Strip Div., Jones & Laughlin Steel Corp., Ohio (g)
Standard Pressed Steel Co., Pa (b,g)
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa (g)
Stanwood Corp., Ill (g)
Sylvania Electric Products, Inc., Parts Div., Pa (b,f,g)
Textron Metals Co., Ohio (a)
Thompson Pipe & Steel Co., Colo (a,b, c,d,e,f,g)
U.S. Graphite Co., Div. of Wickes Corp., Mich (aa)
Vanadium-Alloys Steel Co., Pa (g)
Vulcan Mfg. Co., Ohio (a,b,c,f,g)
Wal-Mar Corp., Ill (a,b,c,e,g)
Werner, R.D. Co., Pa (a,b,g,j)
Western Automatic Machine Screw Co., Div. of Standard Screw Co., Ohio (a,b,c,f,g)
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY (a,b,c,e,f,g)
Wyatt Metal & Boiler Works, Inc., Tex (a,b,c,e,f,g)

## Rubber, Natural

Adhesive Products Corp., NY (x)
American Hard Rubber Co., Div. of Amerace Corp., NY (bb,cc,dd)
American Rubber Products Corp., Ind (u,bb,cc,dd,ee)
Atlas Mineral Products Co., Pa (cc)
Auburn Rubber Co., Inc., Ind (cc)
Automotive Rubber Co., Inc., Mich (cc, dd)
Belko Corp., Md (y)
Bond International, Inc., Mich (y,ee)
Broadway Rubber Corp., Ky (u,cc)
Brown Rubber Co., Inc., Ind (u)
Capac Mfg. Corp., Mich (y,cc)
Castle Rubber Co., Pa (y,bb,cc,dd,ee)
Chicago-Allis Mfg. Corp., Ill (p)
Colonial Rubber Co., Div. of U.S. Stoneware Co., Ohio (y)
Continental Rubber Works, Pa (bb,cc, dd,ee)
Coyne & Paddock, Inc., NY (cc)
Dayton Rubber Co., Ohio (u,y,bb,cc,dd, ee)
Douglas & Sturgess, Calif (x,y)
Johns-Manville Corp., Dutch Brand Div., Ill (u,y,cc,dd)
Faultless Rubber Co., Ohio (u,y,bb,ee)
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (s,u,y,cc,ee)
Flexible Tubing Corp., Conn (ee)
Foam Products, Inc., Pa (u)
Foamade Industries, Mich (u)
Garlock Packing Co., NY (y,bb,cc,dd, ee)
Geauga Industries Co., Ohio (y,bb,dd)
Goodrich, B.F. Chemical Co., Sponge Products Div., Conn (u)
Goshen Rubber Co., Inc., Ind (y)
Hardman, H.V. Co., Inc., NJ (x)
Hayes Adhesive Co., Inc., Mo (y)
Hewitt-Robins, Inc., Conn (cc,ee)
Home Rubber Co., NJ (y,bb,cc,dd,ee)
Johns-Manville Corp., NY (cc)
Luzerne Rubber Co., NJ (bb,cc,dd,ee)
Maloney, F.H. Co., Tex (y)
Martin Rubber Co., Inc., NJ (y,dd,eee)
Mid-States Rubber Products, Inc., Ind (y)
Morningstar-Paisley, Inc., NY (y)
National Gasket & Washer Mfg. Co., Inc., NY (bb,cc,dd,ee)
Naugatuck Chemical Div., U.S. Rubber Co., Conn (u,x,y)
Paeco Rubber Co., Inc., Ohio (y)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
Parker, Stearns & Co., Inc., NY (y, bb,cc,dd,ee)
Pawling Rubber Corp., NY (bb,dd,ee)
Polymer Chemical Co., Ohio (x,y)
Rand Rubber Co., NY (p,t,cc)
Raybestos-Manhattan, Inc., NJ (bb, cc,dd)
Raybestos-Manhattan, Inc., Plastic Products Div., Pa (x)
Republic Rubber Div., Lee Rubber & Tire Corp., Ohio (p,y,bb,cc,dd,ee)
Roberts Toledo Rubber Co., Ohio (ee)
Rogers Corp., Conn (y,cc,dd)
Roth Rubber Co., Ill (y,cc)
Rubatex Div., Great American Industries, Inc., Va (u)
Rubber Corp. of America, NY (u)
Russell Mfg. Co., Conn (s)
Sheller Mfg. Corp., Mich (u)
Snyder, M.L. & Son, Inc., Pa (ee)
Standard Products Co., Mich (y)
Stockwell Rubber Co., Inc., Pa (u,y, bb,cc,dd)
Technical Specialties Co., NY (dd)
Toyad Corp., Pa (t,u)
Trostel, Albert Packing, Ltd., Wis (y)
U.S. Rubber Co., Kem-Blo Dept., Conn (u)—Ad p 250
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (p,y,cc)
Vulcanized Rubber & Plastics Co., Pa (y)
Western Felt Works, Ill (y,cc,dd,ee)
Williams-Bowman Rubber Co., Ill (y,bb,cc,dd,ee)

## Rubber, Synthetic

(see specific material)

## Sand Castings

(see Castings)

## Sandwich Materials

(key letters refer to core materials)
Aerojet-General Corp., Structural Materials Div., Calif (a,g)
Allegheny Ludlum Steel Corp., Pa (g)
Almco Steel Products Corp., Ind (g)
Aluminum Co. of America, Pa (a)
Antara Chemicals, Div. of General Aniline & Film Corp., NY (c)
Apex Reinforced Plastics Div., White Sewing Machine Corp., Ohio (l)
Artmor Plastics Corp., Md (a,k,l,m)
Bar-Ray Products, NY (d)
Bridgeport Brass Co., Conn (g)
Brunswick Corp., Defense Products Div., Mich (a,l)
Busch, J.C. Co., NY (a,c)
Cincinnati Industries Inc., Ohio (k)
Composite Industrial Metals, Inc., RI (a,b,c,d,e,f,g,h,j)
Continental Rubber Works, Pa (m)
Dow Chemical Corp., Plastics Div., Mich (k)
Douglas Aircraft Co., Inc., Aircumb Div., Calif (l)
Dumont Corp., Calif (a,k,m)
General Findings & Supply Co., Industrial Div., Mass (b,f)
General Tire & Rubber Co., Ind (l)
Glo-Brite Products, Inc., Ill (l)
H & R Industries, Pa (k)
Hardy Mfg. Corp., Ind (g)
Haskelite Mfg. Corp., Mich (k,l,m)
Hawkeye Rubber Mfg. Co., Iowa (g,m)
Hexcel Products, Inc., Calif (a,g)
Kassel Export Co., Inc., NJ (g)
Leach & Garner Co., Industrial Div., Mass (b,f)
Lukens Steel Co., Pa (a,b,e,f,g,h)
Luminous Resins, Inc., Ill (k)
Lunn Laminates, Inc., NY (l)
Mechanical Rubber Products Co., NY (l)
Minnesota Mining & Mfg. Co., Minn (l)
Mobay Chemical Co., Pa (k)
National Moldite Co., NJ (c)
National Vulcanized Fibre Co., Del (l)
Northwest Plastics Industries, Inc., Wash (l)
Nuclear Metals, Inc., Mass (a,b,c,e,f, g,h)
Permacel, NJ (l)
Presswork, Inc., Mich (b,d)
Replac Corp., Ohio (k,l,m)
Riegel Paper Corp., NY (k,l)
Rogers Corp., Conn (l,m)
Rohr Aircraft Corp., Calif (f,g)
Russell Mfg. Co., Conn (b)
Russell Reinforced Plastics Corp., NY (l)
Solar Aircraft Co., Calif (g,h)
Standard Insulation Co., NJ (l)
Standard Metals Corp., Mass (c,f)
Superior Steel Div., Copperweld Steel Co., Pa (g)
Swedlow, Inc., Calif (a,f,g,h)
Thermoid Div., H.K. Porter Co., Pa (l)
Thompson, H. I. Fiber Glass Co., Calif (g)
Toyad Corp., Pa (k)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
U.S. Polymeric Chemicals, Inc., Conn (l)
West Haven Foundry Co., Conn (a,b)
Wittman, Lawrence & Co., NY (k,l)
Zenith Plastics Co., Calif (l)

## Screw Machine Parts

Abalon Precision Mfg. Corp., NY (a, b,c,g)
Abbott Products, Inc., NY (a,b,c,d,e, f,g,h,j)
Advance Screw Products Co., Inc., Wis (a,b,c,g)
Affiliated Screw Products Co., Ill (a, b,c,d,e,f,g,h,j)
Albany Products Co., Inc., Conn. (b,f)
Allied Machine Products Co., Mich (a,b,g)
Allied Metal Products Co., Mass (a, b,c,g)
Allied Products Corp., Mich (g)
Allmetal Screw Products Co., Inc., NY (f,g,h)
Aluminum Co. of America, Pa (a)
American Electrical Products Co., Ohio (a,b,f,g)
American Fabricated Products Co., Ind (a,b,f,g)
American Sanitary Mfg. Co., Ill (b)
American Screw Products Co., Mich (a,b,g)
Ampco Metal, Inc., Wis (b)
Anti-Corrosive Metal Products Co., Inc., NY (g)
Approved Mfg. Co., Inc., Mich (b,g)
Argosy Products, Inc., Ohio (a,b,g)
Ashby Mfg. Co., Mo (b,f,g)
Atkins Saw Div., Borg-Warner Corp., Ind (g)
Auburn Spark Plug Co., Inc., NY (a, b,c,d,f,g,h)
Auel Industries, Pa (a,b,g)
Autel Electronics Co., Precision Machine & Welding Div., NJ (a,b,c,e, g,h)
Automatic Metal Products Corp., Mich (b,f,g,h)
Babson Dow Mfg. Co., Mass (a,b,c, f,g)
Balas Collet Mfg. Co., Ohio (a,b,f,g)
Baldwin Mfg. Co., Conn (a,b,c,d,f, g,h,j)
Barton Products Corp., Wis (a,b,c,e, f,g)
Bayley Products, Inc., Mich (a,b,g)
Beacon Metal Mfg. Co., NY (a,b,c,e, f,g,h,j)
Beck Products Corp., Mich (a,b,f,g)
Bethandale Corp., Ohio (a,b,f,g)
Bethlehem Steel Co., Pa (g)
Bickford F.H. Co., Ohio (a,b,g)
Biddle Screw Products Co., Ind (a,b, c,d,e,f,g,h)
Blacher Bros., Inc., RI (a,b,g)
Boehm Screw Products Co., Mich (a, b,f,g)
Boots Aircraft Nut Corp., Conn (a, b,f,g)
Brown Corp., NY (g)
Buchmann Spark Wheel Corp., NY (a, b,c,e,f,g)
Buckeye Brass & Mfg. Co., Ohio (b)
Burgess-Norton Mfg. Co., Ill (c)
C & G Screw Machine Products Co., Ind (a,b,g)
Carleton Screw Products Co., Minn (a, b,g)
Cartwright, R. Tube Products Co., Mich (a,b,g)
Central Screw Products Co., Mich (a, b,f,g)
Chapman Machine Co., Inc., Conn (a, b,f,g)
Chardon Metal Products Co., Ohio (a, b,f,g)
Chicago Screw Co., Div. of Standard Screw Co., Ill (a,b,c,f,g)
Clendenin Bros., Inc., Md (b)
Cleveland Cap Screw Co., Ohio (a,b, f,g,h)
Collis Co., Iowa (a,b,f,g)
Columbus Dental Mfg. Co., Ohio (a, b,c,g)
Columbus Jack Corp., Ohio (a,c,g)
Columbus Production Mfg. Co., Ohio (a,b,g)
Comerford Mfg. Co., Inc., Conn (a,b, c,e,f,g,h,j)
Condamatic Co., Inc., Mich (a,g,h)
Conn Perry Mfg. Co., Mich (b,g)
Connecticut Mfg. Co., Conn (b,f,g)
Control Parts Corp., NY (a,b,c,d,e,f, g,h,j)
Couch-Uthe Co., Ohio (b,f,g)
Curtis Products Co., Conn (a,b,c,f,g)
Curtis Screw Co., Inc., NY (a,b,f,g)
Davis & Hemphill, Md (a,b,c)
Dawlen Corp., Mich (a,b,c,f)
Decatur Automatic Co., Ill (a,b,f,g)
Deerfield Mfg. Co., Ohio (a,b,f,g)
Defiance Screw Machine Products Div., Serrick Corp., Ohio (g)
Delo Screw Products Co., Ohio (a, b,f,g)
Delron Co., Inc., Calif (a,g)
Dependable Automatic Screw Co., Conn (a,b,c,d,e,f,g,h,j)
Dixon Corp., RI (k)
Drexel Screw Products Co., Ill (a,b, c,d,f,g,k)
Duffin Mfg. Co., Ohio (a,b,g,h)
Duro Screw & Mfg. Co., NJ (a,b, f,g,h)
Eastern Machine & Screw Corp., Conn (a,g)
Eby, Hugh H. Co., Pa (a,b,f)
Economy Machine Products Co., Ill (a,b,f,g)
Electric Auto-Lite Co., Ohio (a,b,c,g)
Electric Materials Co., Pa (b)
Electronic Parts Mfg. Co., Inc., NJ (c,f,g)
Elsby, J.S., Inc., Wis (a,b,f,g)
Enoch Mfg. Co., Ore (a,b,c,e,g,j)
Essential Bar Products Co., Mich (a, b,f,g)
Eureka Electric Products Co., Pa (a,b)
Everard Tap & Die Corp., NY (a,b,c, f,g)
Fairchild Screw Products, Inc., Conn (a,b,f,g)
Falls Machine Co., Ohio (a,b,g)
Federal Screw Works, Mich (a,b,f,g)
Femco Mfg. Co., Inc., Mich (g)
Fischer Special Mfg. Co., Ohio (a,b)
Fordsell Machine Products Co., Mich (a,b,f,g)
Frisby, R.J. Mfg. Co., Ill (a,b,g)
G & G Mfg. Co., Ill (a,b,f,g)
G & Z Automatic Products Co., Mich (a,b,g)
Gantner Screw Products Co., Inc., Ohio (a,b,f,g)

General Engineering Works, Ill (a,e,f,g)
General Findings & Supply Co., Industrial Div., Mass (a,b,c,f,g)
General Screw Products Corp., NY (a,b,f,g)
Grass, M.J. Machine Products Co., NY (a,b,f,g)
Greer Stop Nut Co., Ill (a,b,c,e,f,g,h,j)
Gregg Metal Products Inc., Wis (a,b,f,g)
Gross Willard N., Inc., NJ (a,b,f,g)
H & H Screw Products, Inc., NY (a,b,f,g,h)
H & H Screw Products Mfg. Co., RI (a,b,f,g)
H & K Machine Service Co., Inc., Mo (a,b,g)
Haber, Ill (a,b,c,f)
Hack, J.H. Mfg. Co., Mich (a,b,f,g)
Hardy Mfg. Corp., Ind (a,b,g)
Harvey Aluminum, Calif (a,g)
Harvin & Co., NJ (a,b,f,g)
Harwood Screw Products, Inc., Ohio (a,b,g)
Held, O.P., Inc., NY (a,b,c,g)
Heller, A.B. Screw Products, Inc., Mich (a,b,g)
Henefelt Precision Products, Ohio (a,b,f,g)
Hercules Fastener Co., Ill (a,c,f,g,j)
Herker Screw Products, Inc., Wis (a,b,g)
Herman Machine & Tool Co., Ohio (a,b,f,g)
Hershey Metal Products, Inc., Conn (a,b,f,g,h)
Holt Products Co., Mich (a,g)
Hoofer Mfg. Co., Ill (a,c)
Hoyt, Charles D. Co., Inc., Ind (a,b,f,g)
Huck Mfg. Co., Mich (a)
Hudson Screw Machine Products Co., Ill (a,b,c,e,f,g,h,j)
Hunt Screw & Mfg. Co., Ill (a,b,f,g,h)
Huron Automatic Screw Co., Mich (a,b,g)
Hy-Level Screw Products Co., Ohio (a,b,g)
Ideal Metal Products Co., Ill (a,b,f,g)
Imsande Screw Products Co., Ohio (a,b)
Industrial Precision Products, Ill (a,b,c)
Inland Mfg. Co., Neb (a,b,c,d,e,f,g,h,j)
Instrument Parts Corp., NY (a,b,c,f,g)
Instrument Specialties Co., Inc., NJ (b)
Jaques Co., Mass (a,b,e,f,g,h)
Jolens Metal Products Co., NJ (a,b,f,g)
Jordan Machine Products, Inc., Mich (a,b,f,g)
Kay-Bee Machine Products Co., Wis (a,b,g)
Kennedy Automatic Products, Inc., Mich (a,b,g)
Kenosha Automatic Products Co., Wis (a,b,g)
Kerr-Lakeside Industries, Inc., Ohio (a,b,f,g)
Kewaunee Engineering Corp., Wis (c)
Klincher Locknut Corp., Ind (a,b,c,f,g)
Koehler Mfg. Co., Mass (c)
Kohn Engineering Corp., Mich (a,b,c,f,g,h)
Kramer, C.P. Co., Ill (a,f,g)
Lake Mfg. Corp., Conn (a,b,g)
Lamson Products Co., Wash (a,b,d,e,f,g,j)
Lattner Bros. Machining Co., Mich (a,b,f,g)
Latwaitis, Ernest A., NY (a,b,f,g)
Lawrenceville Screw Co., Pa (a,b,f,g)
Lincoln Machine Parts Corp., NY (a,b,f,g,h)
Lincoln Mfg. Co., Inc., Ill (a,b,f,g)
Linden & Co., Inc., RI (a,b,c,g)
Livingston-Tyler Products, Ohio (a,b,e,g)
Locke Machine Co., Ohio (a,b,e,f,g)
Loeffler, J.M. Machine Co., Pa (a,b,c)
Lorain Automatic Screw Machine Co., Inc., Ohio (a,b,g)
Lubenow, Arthur Co., Wis (a,b,f,g)
Lundberg Screw Products Co., Mich (a,b,g)
Lyndon Machine Products Co., Inc., Mich (a,b,g)
M & S Mfg. Co., Mich (a,b,g)
Machine Products Corp., Ohio (a,b,c,d,e,f,g,h,j)
Machinery Products Co. of Lancaster, Pa (a,b,f,g)
Machinery Products Corp., Ill (a,b,f,g)
Mac-It Parts Co., Pa (b,f,g)
Main Screw Machine Products, Inc., Conn (a,b,g)
Mantel Screw Products Co., Wis (a,b,f,g,h)
Marquette Metal Products Co., Ohio (a,b,f,g)
Masco Screw Products Co., Mich (a,b,f,g)
Massachusetts Screw Mfg. Co., Mass (a,b,f,g)
Maynard Mfg. Co., Mich (a,b,f,g,h)
McKinney Mfg. Co., Pa (a,b,e,f,g)
McLanahan & Stone Corp., Pa (c,g)
McMahon Bros. Machine Works, Inc., Ill (a,b,f,g,h)
Meaden Screw Products Co., Ill (a,b,f,g)
Measuregraph Co., Mo (a,b,f,g,h)
Mechanical Art Works, Inc., NJ (a,b,f,g)
Meier Screw Products & Mfg. Co., Mich (a,b,c,e,f,g)
Merit Screw Machine Products Co., Ill (a,b,f,g,h)
Merit Specialties Co., Inc., Mo (a,b,e,f,g)
Merz Machine & Tool Works, Ind (a,b,g)
Micro Products Corp., Mo (a,g)
Mid-West Screw Products Co., Mo (a,b,c,g)
Midwest Screw Products, Inc., Ohio (a,b,f,g,h)
Milford Automatics, Inc., Conn (a,b,g)
Milled Screw Products, Co., Ill (a,b,f,g)
Millers' Brass Fitting Co., Inc., NY (a,b,f,g)
Milwaukee Machine Products Co., Wis (a,b,g)
Milwaukee Stamping Co., Wis (a,g)
Mitchell & Scott Machine Co., Inc., Ind (a,b,f,g)
Modern Screw Products Co., Mo (b,f,g)
Monarch Tool & Mfg. Co., Ky (g)
Moody Machine Products Co., Inc., RI (a,b,c,f,g)
Moore, George W., Inc., Mass (a,b,g)
**Mueller Brass Co., Mich** (a,b,f)—Ad p 455
Mueller Machine Products Inc., Wis (a,b,c,d,e,f,g,j)
Napoleon Products Co., Ohio (a,g)
National Acme Co., Ohio (a,b,f,g)
National Lead Co., NY (a)
National Screw & Mfg. Co., Ohio (b,f,g)
New Britain Machine Co., Conn (a,b,g)
New Haven Screw Machine Products, Inc., Conn (a,b,f,g,h,j)
Newtown Mfg. Co., Conn (a,b,f,g,h)
Nicoud Mfg. Co., Ill (a,b,f,g)
Noera Mfg. Co., Conn (a,b,g)
Nolte Screw Machine Products Co., Ohio (a,b,c,f,g)
Northwest Automatic Products Corp., Minn (a,b,f,g)
Nutmeg Screw Machine Products Co., Conn (a,b,f,g)
Nylok Corp., NJ (a,b,c,e,g,h)
Ohio Metal Products Co., Ohio (a,b,f,g,h)
Ohio Screw Products, Inc., Ohio (a,b,f,g)
Olderman Mfg. Corp., Conn (a,b)
Olson Mfg. Co., Mass (a,b,f,g)
Ostby & Barton Co., Flightex Fabrics, Inc., RI (a,b,f,g)
Ottawa Steel Products, Inc., Mich (g)
Owen Mfg., Inc., Ill (a,b,f,g)
Pabst Engineering Equipment Co., Inc., NJ (a,b,c,e,f,g,h,j)
Pacific Screw Products Co., Calif (a,b,f,g)
Pan-American Metal Products Co., Inc., Fla (a,b,f,g)
Parker & Harper Mfg. Co., Mass (a,b,f,g)
Peck Spring Co., Conn (a,b,c,f,g)
Peerless Automatic Machine Co., Ohio (a,b,c,g)
Peerless Industries, Inc., Mich (a,b,g)
Peerless Products Industries, Ill (a,b,g)
Perry Fay Co., Ohio (a,b,g)
Philadelphia Enameling Works Inc., Pa (a,b,g)
Phillips, F.C., Inc., Mass (b,f,g)
Phillips Bros. Screw Products Co., Mich (b,f,g,h)
Piper Tool Co., Inc., Mich (g)
Pohlman, R.L. Co., Mo (a,b,g)
Polyphase Machine Co., NY (a,b,f,g,h)
Precision Machine Co., Ind (a,b,g)
Precision Piece Parts, Inc., Ind (g)
Precision Screw Products Co., Inc., Calif (a,b,f,g)
Progressive Service Co., Mo (a,b,e,f,g)
Racine Screw Co., Wis (a,b,f,g)
Rainier Metal Products Co., Ill (a,b,g)
Rasco-Veeder Co., Ill (a,b,f,g)
Ravenswood Machine Corp., Ill (a,b,f,g)
Red Devil Mfg. Co., Ill (a,b,c,d,e,f,g,h,j)
Redmer Air Devices, Ala (a,b,c,f,g)
Reliable Screw Machine Products, Ill (a,b,f,g,h)
Remler Co., Ltd., Calif (a,b,f,g)
Rex Products Co., Ohio (a,b,f,g)
Richmond Mfg. Co., Tex (a,b,f,g)
Rockwell Engineering Co., Ill (a,b,c,g)
Rosan Inc., Calif (a,g)
S & S Mfg. Co., NJ (a,b,c,e,f,g,h)
Sargent & Greenleaf, Inc., NY (a,b,g)
Scovill Mfg. Co., Mill Products Div., Conn (a,b)
Seltzer, George H. & Co., Pa (g)
Sheller Mfg. Corp., Mich (g)
Sinclair Co., Mass (a,b,g)
Skookum Co., Inc., Ore (g)
Spencer Nahm Co., Calif (a,b,f,g)
Spencer's Sons, I.S., Inc., Conn (a,b,g)
Standard Pressed Steel Co., Pa (a,b,c,e,f,g,h)
Standard Screw Products Co., Calif (a,b,g)
Star Heel Plate Co., Inc., NJ (g)
Steel Heddle Mfg. Co., Pa (a,b,c,e,f,g,h,j)
Steel Industries, Inc., Ind (a,b,g)
Steinen, Wm. Mfg. Co., NJ (a,b,c,f,g,h)
Thompson-Bremer & Co., Ill (a,b,c,f,g,h)
Thompson Products, Inc., Ohio (h)
Titan Metal Mfg. Co., Pa (a,b)
Tompkins Products, Mich (a,b,c,d,f,g,j)
Trigon Specialties Corp., Ind (a,b,c,d,e,f,g,h,j)
Ullmann, Inc., Wis (a,b,c,e,f,g,h)
Union Screw & Mfg. Co., Pa (a,b,g)
United Screw & Bolt Corp., Ill (a,b,g)
United Shoe Machinery Corp., Mass (a,b,c,f,g)
Unity Machine & Tool Corp., Pa (a,g)
Vanamatic Co., Ohio (a,b,g)
Wagner Specialty Co., Wis (a,b,c,g,j)
Wall, P. Mfg. Co., Pa (a,b,c,g)
Waldman, Joseph & Sons, Epoxy Products Div., NJ (a,b,c,f,g)
Walrod Machine Products, Ore (a,b,g)
Ward, H.H. Co., Pa (a,b,c,f,g,j)
Waterman Industries, Inc., Calif (a,b)
Weatherhead Co., Ind (a,b,c,d,e,f,g,h,j)
Weber-Knapp Co., NY (a)
Wedler Bros., Inc., Ohio (a,b,f,g)
Western Automatic Machine Screw Co., Div. of Standard Screw Co., Ohio (a,b,c,f,g)
Western Machine Co., Wis (a,b,c,f,g,j)
Wirth, Carl & Son, Inc., NY (a,b,c,d,e,f,g,h,j)
Worth Co., Wis (a,b,c,g)
Wright, Albert Screw Machine Products, Calif (a,b,f,g)
Wuest Bros., Inc., Ky (a,b,c,f,g)
Zeller Corp., Ohio (g)

## Selenium

American Metal Climax, Inc., NY (aa)
American Nickel Alloy Mfg. Corp., NY (aa)
American Smelting & Refining Co., NY (q,aa)
Anaconda Co., NY (aa)
Belmont Smelting & Refining Works, Inc., NY (aa)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

**Cerro de Pasco Sales Corp., NY** (aa)—Ad p 178
Federated Metals Div., American Smelting & Refining Co., NY (aa)
Hardy, Charles, Inc., NY (aa)
Hommel, O. Co., Pa (aa)
Kaweckl Chemical Co., NY (aa)
McGean Chemical Co., Ohio (aa)
Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)
Phelps Dodge Refining Corp., NY (aa)

## Sheet

(see specific material)

## Sheet Formed Plastics Parts

(see Moldings, Sheet)

## Sherardized Coatings

(see Diffusion Coatings)

## Silicides

(see Refractories)

## Silicon

American Nickel Alloy Mfg. Corp., NY (w,aa)
Belmont Smelting & Refining Works, Inc., NY (aa)
du Pont de Nemours, E. I. & Co., Inc., Del (w)
Foote Mineral Co., Pa (q)
Hardy, Charles, Inc., NY (aa)
Lavin, R. & Sons, Inc., Ill (w)
Monsanto Chemical Co., Inorganic Chemicals Div., Mo (q,w,bb)
National Electric Div., H.K. Porter Co., Pa (ff)
**National-Standard Co., Mich** (ff)—Ad p 421
National-U.S. Radiator Corp., Plastic Metals Div., NY (aa)
Sylvania Electric Products, Inc., Chemical & Metallurgical Div., Pa (w,bb,ee)
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
Utica General Jobbing Foundry, Inc., NY (aa)
Vanadium Corp. of America, NY (w)

## Silicon Bronze

(see Copper)

## Silicone Plastics

Adhesive Products Corp., NY (x)
Alpha Wire Corp., NY (ee)
Belko Corp., Md (y)
Bisonite Co., Inc., NY (y)
Colonial Kolonite Co., Ill (bb,cc,ee)
Comco Plastics, Inc., NY (bb,cc,dd,ee)
Continental-Diamond Fibre Corp., Del (bb,cc,dd,ee)
Cordo Chemical Corp., Conn (y)
Cordo Molding Products, Inc., Conn (y)
Curbell, Inc., NY (bb,cc,dd,ee)
Dodge Fibers Corp., NY (s)
Dow Corning Corp., Mich (p,u,x,y)
Dyna-Therm Chemical Corp., Calif (p)
Electrofilm, Inc., Calif (t)
Emerson & Cuming, Inc., Mass (u)
Flexible Tubing Corp., Conn (ee)
Formica Corp., Sub. of American Cyanamid Co., Ohio (cc,ee)
General Electric Co., Laminated Products Dept., Ohio (cc)
General Electric Co., Silicone Products Dept., NY (p,u,x,y)
General Gasket, Inc., Conn (cc)
Glass Reinforced Plastics Corp., Ohio (bb,ee)
Hall, C.P. Co., Ohio (p)
Hewitt-Robins, Inc., Conn (u,cc,ee)
Insulation Mfrs. Corp., Ill (p,y,bb,cc,dd,ee)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Kurz Kasch, Inc., Ohio (y)
Maloney, F.H. Co., Tex (y)
Mesa Plastics Co., Calif (p,y,bb,cc)
Mica Insulator Div., Minnesota Mining & Mfg. Co., NY (bb,cc)
Narmco Industries, Inc., Narmco Materials Div., Calif (x)
National Gasket & Washer Mfg. Co., Inc. NY (bb,cc,dd,ee)
National Vulcanized Fibre Co., Del (bb,cc,dd,ee)
Panelyte Div., St. Regis Paper Co., NJ (x,bb,cc,dd,ee)
Parker, Stearns & Co., Inc., NY (bb,cc,dd,ee)
Pawling Rubber Corp., NY (bb,dd,ee)
Philrus Products Co., NJ (bb,cc,dd,ee)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Prince Rubber & Plastics Co., Inc., NY (bb,cc,ee)
Raybestos-Manhattan, Inc., NJ (bb,cc,dd)
Raybestos-Manhattan, Inc., Plastic Products Div., Pa (x)
Rogers Corp., Conn (u,y,bb,cc,dd)
Roth Rubber Co., Ill (cc)
Staver Co., Inc., NY (cc,dd)
Swedlow Inc., Calif (cc)
Synthane Corp., Pa (bb,cc,dd,ee)
Taylor Fibre Co., Pa (bb,cc,dd,ee)
Toyad Corp., Pa (u)
**Union Carbide Corp., Silicones Div., NY** (p,t,x,y)—Ad p 277
U.S. Polymeric Chemicals, Inc., Conn (s)
Varflex Corp., NY (ee)
Western Felt Works, Ill (cc)
William Brand-Rex Div., American Enka Corp., Mass (ee)

## Silicone Rubber

Adhesive Products Corp., NY (x)
Alpha Wire Corp., NY (ee)
Armstrong Cork Co., Pa (bb,cc,dd)
Belko Corp., Md (y)
Bond International, Inc., Mich (y,ee)
Capac Mfg. Corp., Mich (y)
Castle Rubber Co., Pa (y,bb,cc,dd,ee)
Chicago-Allis Mfg. Corp., Ill (p)
Coast Pro-Seal & Mfg. Co., Calif (y)
**Colonial Rubber Co., Div. of U.S. Stoneware Co., Ohio** (y)—Ad p 441
Connecticut Hard Rubber Co., Conn (s,u,y,bb,cc,dd)
Continental Rubber Works, Pa (bb,cc,dd,ee)
Continental-Diamond Fibre Corp., Del (cc,dd)
Dayton Rubber Co., Ohio (y,bb,cc,dd,ee)
Delta Plastics Co., NJ (bb,cc,dd)
Dodge Fibers Corp., NY (s)
Dow Corning Corp., Mich (p,u,x,y)
Dyna-Therm Chemical Corp., Calif (p)
Flexible Tubing Corp., Conn (ee)
Garlock Packing Co., NY (y,bb,cc,dd,ee)
General Electric Co., Chemical & Metallurgical Div., Ill (cc,dd,ee)
General Electric Co., Plastics Dept., Ill (p,y,bb,cc,dd,ee)
General Electric Co., Silicone Products Dept., NY (p,u,y)
**Goshen Rubber Co., Inc., Ind** (y)—Ad p 438
**Haveg Industries, Inc., Del** (bb,cc,ee)—Ad pp 425-426
Hewitt-Robins, Inc., Conn (cc,ee)
Insulation Mfrs. Corp., Ill (cc)
Maloney, F.H. Co., Tex (y)
Mechanical Rubber Products Co., NY (t,u,bb,cc,dd)
Micarta Div., Westinghouse Electric Corp., SC (cc)
Mid-States Rubber Products, Inc., Ind (y)
Minnesota Rubber Co., Minn (ee)
**Moxness Products, Inc., Wis** (bb,cc,dd,ee)—Ad p 460
National Gasket & Washer Mfg. Co., Inc., NY (bb,cc,dd,ee)
Paeco Rubber Co., Inc., Ohio (y, dd, ee)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
Pawling Rubber Corp., NY (bb,dd,ee)
Permacel, NJ (t,u,bb,cc)
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (t)
Prince Rubber & Plastics Co., Inc., NY (bb,cc,ee)
Raybestos-Manhattan, Inc., NJ (bb,cc,dd)
Raybestos-Manhattan, Inc., Plastic Products Div., Pa (x)
Rogers Corp., Conn (u,y,cc,dd)
Roth Rubber Co., Ill (cc)
Stockwell Rubber Co., Inc., Pa (u,y,bb,cc,dd)
Swedlow, Inc., Calif (cc)
Taunton Div., Haveg Industries Inc., Mass (u,bb,cc,dd,ee)
**Toyad Corp., Pa** (u)—Ad p 260
Trostel, Albert Packing, Ltd., Wis (y)
**Union Carbide Corp., Silicones Div., NY** (p,y,cc,dd)—Ad p 277
U.S. Polymeric Chemicals, Inc., Conn (s)
U.S. Stoneware Co., Ohio (y)
Varflex Corp., NY (ee)
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (p,y,cc)
Western Felt Works, Ill (y,cc,dd,ee)
William Brand-Rex Div., American Enka Corp., Mass (ee)
Williams-Bowman Rubber Co., Ill (y,bb,cc,dd,ee)

## Silver and Its Alloys

Alloy Metal Powders, Inc., Iowa (aa)
Alpha Metals Inc., NJ (n,o,q,bb,cc,dd)
American Metal Climax, Inc., NY (w,aa)
**American Platinum & Silver Div., Engelhard Industries, Inc., NY** (n,o,q,v,w,z,aa,bb,cc,dd,ff)—Ad p 159
American Products Corp., Ill (dd,ff)
American Silver Co., NY (v,dd,ee,ff)
American Smelting & Refining Co., NY (n,o,q,bb,ee)
Anaconda Co., NY (o)
Baker & Co., Inc., NJ (n,o,v,w,z,aa,bb,cc,dd)
Belmont Smelting & Refining Works, Inc., NY (o,dd,ff)
Bunker Hill Co., Sales & Fabrication Div., Calif (o)
Cerro de Pasco Sales Corp., NY (o,w)
Composite Industrial Metals, Inc., RI (p)
Designers Metal Corp., Ill (cc)
Division Lead Co., Ill (ff)
Eastern Smelting & Refining Corp., Mass (n,o,v,w,aa,bb,cc,dd,ee,ff)
Eynon-Dakin Co., Mich (ee)
Federated Metals Div., American Smelting & Refining Co., NY (n)
Fox Products Co., Pa (n)
Fulton Gold Refiners Corp., NY (n,o,q,v,w,aa,bb,cc,dd)
**Gibson Electric Co., Pa** (aa,bb,dd,ff)—Ad p 466
Goldsmith Bros. Div., National Lead Co., Ill (n,o,v,w,z,aa,bb,cc,dd,ff)
**Handy & Harman, NY** (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)—Ad p 152
Hanovia Chemical & Mfg. Co., NJ (aa)
Hardy, Charles, Inc., NY (aa)
Hayden Wire Works, Inc., Mass (ff)
Hommel, O. Co., Pa
Horton-Angell Co., Mass (n,o,bb,cc,dd,ee,ff)
Hudsar, Inc., NJ (w)
Leach & Garner Co., Industrial Div., Mass (n,o,q,v,z,bb,cc,dd)
Lucas-Milhaupt Engineering Co., Wis (dd,ff)
Makepeace, D.E. Div., Engelhard Industries Inc., Mass (n,o,v,z,aa,bb,dd,ee,ff)
Metallizing Co. of Los Angeles, Inc., Calif (ff)
Metals Disintegrating Co., Inc., NJ (aa)
Metz Refining Co., NJ (n,o,q,z,aa,bb,cc,dd,ee)
Minimax Co., Ill (aa)
Nesor Alloy Products Co., NJ (dd,ff)
Ney, J.M. Co., Industrial Div., Conn (v,z,bb,cc,dd,ff)
Norwalk Powdered Metals, Inc., Conn (aa)
Peerless Roll Leaf Co., Div. of Howe Sound Co., NJ (v,dd)
Reade Mfg. Co., Inc., NJ (aa)
Republic Metals Co., Inc., NY (o,w)
Rigidized Metals Corp., NY (cc,dd)
Rotometals, Calif (dd,ff)
**Sel-Rex Corp., NJ** (n,aa)—Ad p 356
Sherwatt Equipment & Mfg. Co., Inc., NY (ff)
Texas Instruments, Inc., Metals & Controls Div., Mass (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Ullmann, Inc., Wis (o,ee)
United Wire & Supply Corp., RI (ff)
Vanadium-Alloys Steel Co., Pa (aa)
Western Gold & Platinum Co., Sub. of Wilbur B. Driver Co., Calif (aa,cc,dd,ff)
Wildberg Bros. Smelting & Refining Co., Calif (n,o,v,w,z,aa,bb,cc,dd,ff)
Williams Gold Refining Co., Inc., NY (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Wilson, H.A. Div., Engelhard Industries, Inc., NJ (cc)

## Slush Moldings

(see Moldings)

## Solders

Abalon Precision Mfg. Corp., NY
All-State Welding Alloys Co., Inc., NY
Alofs Mfg. Co., Mich
American Emblem Co., Inc., NY
American Metal Climax, Inc., NY
American Products Corp., Ill
American Smelting & Refining Co., NY
Anchor Metal Co., Inc., NY
Belmont Smelting & Refining Works, Inc., NY
Bishop, J. & Co. Platinum Works, Pa
Chemical Development Corp., Mass
Composite Industrial Metals, Inc., RI
Consolidated Fruit Jar Co., NJ
Division Lead Co., Ill
Dyna-Therm Chemical Corp., Calif
Empire Metal Co., NY
Eutectic Welding Alloys Corp., NY
Falstrom Co., NJ
Farrelloy Co., Pa
General Findings & Supply Co., Industrial Div., Mass
Hayden Wire Works, Inc., Mass
Ideal Can Co., Mass
Indium Corp. of America, NY
Kenmore Machine Products, Inc., NY
Kester Solder Co., Ill
Kling Metal Spinning & Stamping Co., NY
L. & R. Mfg. Co., NJ

Langsenkamp, F.H. Co., Ind
Lucas-Milhaupt Engineering Co., Wis
Lundquist Tool & Mfg. Co., Inc., Mass
Magnesium Co. of America, Ind
Magnesium Products of Milwaukee, Inc., Wis
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass
Metal Goods Corp., Mo
Metallizing Co. of Los Angeles, Inc., Calif
Midwest Stamping & Mfg. Co., Ohio
National Lead Co., NY
Ney, J.M. Co., Conn
Presswork, Inc., Mich
Ren Plastics, Inc., Mich
Republic Metals Co., Inc., NY
Reynolds Aluminum Supply Co., Ga
Rockwell Engineering Co., Ill
Rotometals, Calif
Ruby Chemical Co., Ohio
Trenton Pipe Nipple Co., NJ
United Refining & Smelting Co., Ill
United Wire & Supply Corp., RI
Waterman Industries, Inc., Calif
Wayne Chemical Products Co., Mich
West Haven Foundry Co., Conn
Whitehead Metal Products Co., Inc., NY
Wildberg Bros. Smelting & Refining Co., Calif
Williams Gold Refining Co., Inc., NY

## Spinnings

Ace Metal Spinning, Ill (a,b,c,d,e,f,g,h,j)
Acme Metal Spinning, Inc., Minn (a b,c,d,e,f,g,h,j)
Aluminum Co. of America, Pa (a)
Aluminum Goods Mfg., Wis (a)
Aluminum Specialty Co., Wis (a)
American Aluminum Co., NJ (a,b)
Anchor Metal Spinning Co., Ohio (a, b,c,d,e,f,g,h,j)
Bartlett-Thompson Co. Inc., Mass (a, b,f,g)
Bergfels, William & Co., NJ (a,b,c, f,g,j)
Biersach & Niedermeyer Co., Wis (a,g)
Broadway Mfg. Co., Wis (a,b,c,f,g)
Brooks & Perkins, Inc., Mich (a,e,h)
Clover Industries, Inc., NY (a)
Commerical Shearing & Stamping Co., Ohio (a,b,e,f,g)
Craft Mfg. Co., Ill (a,b,c,d,f,g)
Craft Metal Spinning Co., Ill (a,b,f,g)
Cyril Bath Co., Ohio (a,g)
Dahlin, C.A. Co., Ill (a,b,e,f,g,h,j)
Dow Chemical Co., Mich (e)
Emerson-Sack-Warner Corp., Mass (a, b,c,e,f,g,h,j)
Garco Mfg. Co., Inc., Ill (a,b,e,f,g,h, j)
General Alloys Co., Mass (a,b,f)
Greene, G.G. Corp., Pa (a,g)
H & H Tube & Mfg. Co., Mich (b)
Hardy Mfg. Corp., Ind (a,g)
Kelsey-Hayes Co., Mich (g)
Kenmore Machine Products, Inc., NY (b)
Kling Metal Spinning & Stamping Co., NY (a,b,c,d,e,f,g,j)
Lukens Steel Co., Pa (a,b,e,f,g,h)
Magline, Inc., Mich (e)
Magnesium Co. of America, Ind (a,e)
Magnesium Products of Milwaukee, Inc., Wis (a,e)
Manufacturers Service, Inc., Ohio (a, b,g)
Mirro Aluminum Co., Wis (a)
Morse, Fred W. Co., RI (a,b,c,g,j)
Muncie Metal Spinning, Inc., Ind (a, b,g)
Murray, A.B. Co., Inc., NJ (a,b,f,g)
Murray Tube Works, Inc., NJ (a,b,g)
Pabst Engineering Equipment Co., Inc., NJ (a,b,c,e,f,g)
Perrin, Edward C. Co., NJ (a,b,g)
Phoenix Products Co., Wis (a,b,c,d,e, f,g,h,j)
Precision Metal Spinning Co., Mich (a,b,c,e,f,g)
Premier Metal Works, Inc., Ill (a,b,g)
Regal Ware, Inc., Wis (a,b,g)
Republic Steel Corp., Ohio (g)
Revere Copper & Brass, Inc., NY (b)
Reynolds Metals Co., Va (a)
Rockwell Engineering Co., Ill (a,b,c,g)
Ryerson, Joseph T. & Son, Inc., Ill (a,g)
Seattle Boiler Works, Inc., Wash (a,g)
Smith-Victor Corp., Ind (a)
Solar Aircraft Co., Calif (g)
Spincraft, Inc., Wis (a,b,d,e,f,g,h,j)
Stainless Metals, Inc., NY (c,f,h)
Stirrup Metal Products Corp., NJ (a, b,g)
Teiner, Roland Co., Inc., Mass (a, b,e,f,g,h)
Toledo Stamping & Mfg. Co., Ohio (a,b,g,h)
Torngren, C.W. Co., Inc., Mass (a, b,c,e,f,g,h,j)
Ward, H.H. Co., Pa (a,b)
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY (a,b,c,e,f,g)

## Sprayed Coatings

(see Metallized Coatings)

## Stampings, Punchings

(see also Drawn, Pressed Parts)

Abalon Precision Mfg. Corp., NY (a, b,c,g)
Ackermann Mfg. Co., W.Va (g)
Acme Mfg. & Gasket Co., Pa (a,b, f,g)
Acme Metal Spinning, Inc., Minn (a, b,c,e,f,g,j)
Acme Stamping & Wire Forming Co., Pa (a,b,g)
Acorn Sheet Metal Mfg. Co., Inc., Ill (a,g)
Acro Metal Stamping Co., Wis (a,b, f,g)
Adams, I.G. Metalware Co., Mo (a, b,c,e,f,g,j)
Advance Stamping Co., Mich (a,b,c, d,f,g,j)
Aerolite Electronics Corp., NJ (a,b, c,g)
Ainsworth-Precision Castings Co., Div. of Harsco Corp., Mich (g)
All-Form Metal Products Co., Ohio (a,b,c,d,e,f,g,j)
Allied Products Corp., Mich (a,g)
Alloy Products Corp., Wis (a,f,g,h)
Almco Steel Products Corp., Ind (a, b,g)
Alofs Mfg. Co., Mich (a,b,g)
Alox Mfg. Co., Mo (a,b,c,f,g)
Alpha Metals, Inc., NJ (a,g)
Aluminum Co. of America, Pa (a)
Aluminum Goods Mfg., Wis (a)
Aluminum Specialty Co., Wis (a,g)
American Aluminum Co., NJ (a,b)
American Brass Co., Sub. of Anaconda Co., NY (a,b,g)
American Emblem Co., Inc., NY (a,b, g)
American Mfg. Co., Tenn (a,g)
American Sheet Metal Works, Inc., Conn (a,b,g)
American Silver Co., NY (a,b,e,f,g)
American Stamping Co., Ohio (a,b,g)
Anchor Metal Spinning Co., Ohio (a, b,c,d,e,f,g,h,j)
Anderson, O.L. Co., Inc., Mich (a, b,c,e,f,g,h,j)
Anderson-Bolling Mfg. Co. Mich (a,g)
Anthes Div., Gleason Corp., Iowa (a,g)
Anti-Corrosive Metal Products Co., Inc., NY (g)
Armor Metal Products Co., Ohio (a,g)
Art Wire & Stamping Co., NJ (a,b, c,d,f,g)
Arvin Industries, Inc., Ind (a,g)
Ashtabula Mfg. Co., Ohio (g)
Associated Spring Corp., Wallace Barnes Steel Div., Conn (g)
Atkins Saw Div., Borg-Warner Corp., Ind (g)
Atlas Metal Parts Co., Wis (a,b,c,g)
**Auburn Mfg. Co., Conn** (a,b,c,d,e,f,g)—Ad p 450
Auel Industries, Pa (a,b,f,g)
Auld, D.L. Co., Ohio (a,b,c)
Autel Electronics Co., Precision Machine & Welding Div., NJ (a,b,c,e, g,h)
Automotive Rubber Co., Inc., Mich (f,g)
Backus Novelty Co., Pa (a,b,c,f,g)
Barclay Mfg. Co., Ind (c)
Barium Steel Corp., NY (g)
Bartlett-Thompson Co., Inc., Mass (a, b,f,g)
Bay State Stamping Co., Mass (a,b,g)
Beacon Metal Mfg. Co., NY (a,b,c,d, e,f,g,h,j)
Behringer Metal Works, Inc., NJ (a, b,c,g)
Belmet Products, Inc., NY (a,b,g)
Benjamin Electric Mfg. Co., Ill (a, b,g)
Bennett Mfg. Co., NY (a,b,e,g)
Bethlehem Steel Co., Pa (g)
Biddle Screw Machine Products Co., Ind (a,b,c,d,e,f,g,h)
Biersach & Niedermeyer Co., Wis (a, b,c,g)
Bingham Herbrand Corp., Bingham Stamping Div., Ohio (g)
Blacher Bros., Inc., RI (a,b,g)
Blaco Mfg. Co., Ohio (b,g)
Blickman, S., Inc., NJ (a,b,c,g)
Boots Aircraft Nut Corp., Conn (g)
Borg-Warner Corp., Ingersoll Products Div., Ill (g)
Brandt, Charles T., Inc., Md (a,b,e, f,g)
Brewer-Titchener Corp., NY (a,g)
Brooks & Perkins, Inc., Mich (a,e,h)
Burgess-Norton Mfg. Co., Ill (c)
Carbo Tool & Die Co., Ohio (c)
Carroll Pressed Metal, Inc., Mass (a, b,f,g)
Cartwright, R. Tube Products Co., Mich (a,b,g)
Clendenin Bros., Inc., Md (a,b)
Cleveland Metal Products Co., Ohio (a,b,c,f,g)
Cleveland Pressed Products Corp., Ohio (a,b,g)
Clover Industries, Inc., NY (a)
Cly-Del Mfg. Co., Inc., Conn (a,b, f,g,j)
Columbia Metal Stamping Co., Ohio (a,g)
Columbian Steel Tank Co., Mo (g)
Columbus Dental Mfg. Co., Ohio (a, b,c,g)
Columbus Jack Corp., Ohio (a,c,g)
Comerford Mfg. Co., Inc., Conn (a, b,c,e,f,g,j)
Commercial Shearing & Stamping Co., Ohio (a,b,f,g)
Composite Industrial Metals, Inc., RI (a,b,c,d,e,f,g,h,j)
Consolidated Fruit Jar Co., NJ (a, b,c,d,g,j)
Cooley, W.J. & Co., Tenn (a,b,g)
Craft Mfg. Co., Ill (a,b,c,d,f,g)
Croname Inc., Ill (a,b,f,g,j)
Crosby Co., NY (a,b,g)
Crown Metal Co., Wis (d)
Cuyahoga Stamping Co., Ohio (a,b,g)
Cyril Bath Co., Ohio (a,e,f,g,h)
Dahlin, C.A. Co., Ill (a,b,e,f,g,j)
Dana Corp., Auburn Div., Ind (g)
Danby Mfg. Co., Mich (a,b,g)
Dare Products, Inc., Mich (g)
Day Co., Minn (a,g)
Dayton Rogers Mfg. Co., Minn (a,b,g)
Dearborn Stamping Co., Mich (g)
Defiance Metal Products Co., Ohio (a,g)
Defiance Stamping Co., Ohio (g)
Detroit Stamping Co., Mich (a,b,g)
Dirilyte Co. of America, Inc., Ind (a,b)
Division Lead Co., Ill (d)
Dixon Corp., RI (k)
Doehler-Jarvis Div., National Lead Co. Ohio (a)
Dolin Metal Products, Inc., NY (g)
Dow Chemical Co., Dow Metal Products Co. Div., Mich (e)
Dudek & Bock Spring Mfg. Co., Ill (a,g)
Duplex Mfg. Corp., Ark (a,g)
Duplican Co., Inc., Mass (a,b,c,e,f, g,h,j)
Earley, Sam C. Corp., Ohio (a,b,g)
Eastern Tool & Mfg. Co., NJ (a,b,c, g)
Eastern Tool & Stamping Co., Inc., Mass (a,b,c)
Eby, Hugh H. Co., Pa (a,b,f)
Electric Auto-Lite Co., Ohio (a,b,g)
Electric Materials Co., Pa (b)
Electronic Parts Mfg. Co., NJ (c,f,g)
Ellwood City Iron & Wire Co., Pa (c)
Emerson-Sack-Warner Corp., Mass (a, b,c,f,g)
Empire Spring Co., Ohio (a,b,g)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Empire-Reeves Steel Div., Universal-Cyclops Steel Corp., Pa (g)
Enamel Products Co., Ohio (a,c)
Etched Products Corp., NY (a,b,g)
Evans, George Corp., Ill (a)
Eureka Electric Products Co., Pa (a,b)
Everard Tap & Die Corp., NY (a, b,f,g)
Fabristeel Products, Inc., Mich (g)
Falstrom Co., NJ (a,b,e,g)
Farwell Metal Fabricating, Minn (a, b,e,f,g)
**Federal Tool Corp., Ill** (a,b,c,g,)—Ad p 436
Federal Tool & Mfg. Co., Minn (a, b,c,f,g)
Figley Die & Stamping Co., Ohio (a, b,g)
FitzSimons Mfg. Co., Mich (a,b,g)
Fletcher Enamel Co., W.Va (a,b,c,d, e,f,g)
Follansbee Steel Corp., Sheet Metal Specialty Div., W.Va (a,b,g)
Forg, Peter Mfg. Co., Mass (a,b,c,g)
Fox Co., Ohio (a,b,c,g)
Fox Products Co., Pa (c)
Fryling Mfg. Co., Pa (a,b,f,g,j)
Garco Mfg. Co., Inc., Ill (a,b,c,e,f, g,h,j)
Gary Steel Products Corp., Va (a,g)
General Alloys Co., Mass (a,b,f)
General Chain & Mfg. Corp., Ohio (g)
General Extrusions, Inc., Ohio (a)
General Findings & Supply Co., Industrial Div., Mass (a,b,c,f,g)
General Gasket, Inc., Conn (a,b,c,d,g)
Geometric Stamping Co., Ohio (a,b,g)
Gerstenslage Co., Ohio (a,g)
Geuder, Paeschke & Frey Co., Wis (a, c,f,g)
Giant Grip Mfg. Co., Wis (a,c,e,f,g,h)
Gibson Electric Co., Pa (b)
Grammes, L.F. & Sons, Inc., Pa (a,b, g)
Grand Haven Stamped Products Co., Mich (a,b,g,j)
Grand Sheet Metal Products Co., Consumer Products Div., Ill (a,b,c,e,f, g,h,j)
Greene, G.G. Corp., Pa (a,b,e,f,g,j)
Greene Mfg. Co., Wis (a,g)
Grigoleit Co., Ill (a,g)
Guarantee Specialty Mfg. Co., Ohio (a,b,c,g,j)
H.K. Metal Craft Mfg. Corp., NY (a, b,c,g,j)
H P L Mfg. Co., Ohio (a,b,g)
Haigh Mfg. Co., Mich (a,b,f)
Hardy Mfg. Corp., Ind (a,b,g)
Headly Mfg. Co., Ill (a,b,c,e,f,g,h,j)
Heypian Mfg. Co., NJ (a,b,f,g)
Hoofer Mfg. Co., Ill (a,g)
Houston Blow Pipe & Sheet Metal Works, Tex (a,b,g)
Hunter Spring Co., Div. of American Machine & Metals, Inc., Pa (a,b,f,g)
Ideal Can Co., Mass (a,b,c,g)
Indium Corp. of America, NY (d)
Indus Corp., Ind (g)
Industrial Precision Products, Ill (a, b,c,e,f,g,h,j)
Industrial Products Div., General Tire & Rubber Co., Ind
Ingram-Richardson, Inc., Ind (g)
Inshield Die & Stamping Co., Ohio (a,b,g)
Instrument Specialties Co., Inc., NJ (b)
Interlake Mfg. Co., Mich (a,g)
Irwin-Sensenich Corp., Pa (g)
Jackson Auto Radiator, Ill (a,b,g)
Jarco Metal Products, NY (a,b,g,j)
Jervis Corp., Mich (a,b,g,h)
Judd Industries, Inc., Ohio (a,b,g)
K-D Mfg. Co., Tex (g)
Kaiser Steel Corp., Calif (g)
Kees, F.D. Mfg. Co., Neb (a,b,g)
Kelley Mfg. Co., Tex (a,b,g)
Kenmore Machine Products, Inc., NY (b)
Kickhaefer Mfg. Co., Wis (a,b,g)
King Laboratories, Inc., NY (a,b,c, f,g)
Kirchhof Patent Co., Inc., NY (a,b, c,f,g,j)
Kling Metal Spinning & Stamping Co., NY (a,b,c,d,e,f,g,j)
Koehler Mfg. Co., Mass (a,b,c,d,g)
Krueger & Hudepohl, Inc., Ohio (a, b,c,f,g)
Laminated Shim Co., Conn (a,b,g)
Lansing Stamping Co., Mich (g)
Larkin Specialty Mfg. Co., Calif (a,b, g)
Larson Tool & Stamping Co., Mass (a, b,c,e,f,g,h,j)
Laystrom Mfg. Co., Ill (a,b,c,f,g,j)
Leake Engineering Co., Mich (a,b,c, d,e,f,g,h,j)
Linden & Co., Inc., RI (a,b,g)
Littleford Bros. Inc., Ohio (a,b,c,f,g)
Lukens Steel Co., Pa (a,b,e,f,g,h)
Lundquist Tool & Mfg. Co., Inc., Mass (a,b,c,e,f,g,h)
Lynn, Gary Co., Ohio (a,b,g)
Machine Products Corp., Ohio (a,b,d,f, g)
Magline, Inc., Mich (e)
Magnesium Co. of America, Ill (a,e)
Magnesium Products of Milwaukee, Inc., Wis (a,e)
Magnetic Stamping Co., Pa (a,b,g)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (b)
Maloney, F.H. Co., Tex (g)
Manganese Steel Forge Co., Pa (g)
Manufacturers Service, Inc., Ohio (a, b,g)
Mayville Metal Products Co., Wis (a, b,g)
McDowell Mfg. Co., Pa (a,b,g)
McKinney Mfg. Co., Pa (a,b,e,f,g)
McLanahan & Stone Corp., Pa (c,g)
Meico Wire Products, Calif (a)
Meiray Mfg. Co., Ill (a,b,c,d,e,f,g,h,j)
Metal Forming Corp., Div. of Vanadium-Alloys Steel Co., Pa (a,b,f,g)
Metal Parts & Stamping Co., Ohio (a,b,c,f,g,h,j)
Metallo Gasket Co., NJ (a,b,c,d,f,g,j)
Metallurgical Products Co., Pa (a,b,f, h,j)
Micacraft Products, Inc., NJ (a)
Midwest Stamping & Mfg. Co., Ohio (a,b,f,g)
Milwaukee Stamping Co., Wis (a,b,g)
Mirro Aluminum Co., Wis (a)
Misner Corp., Neb (a,b,c,g)
Monarch Tool & Mfg. Co., Ky (a,b,c, g)
Morrison Steel Products, Inc., NY (g)
Morse, Fred W. Co., RI (a,b,c,g,j)
Morton Mfg. Co., Ill (a,g)
Mueller Machine Products, Inc., Wis (a,b,c,d,f,g)
National Gasket & Washer Mfg. Co., Inc., NY (a,b,c,d,e,f,g,h,j)
National Lead Co., NY (a,c,h)
National Lock Co., Ill (a,b,c,d,g)
National Metal Products Co., Pa (a, c,g)
National Supply Co., Pa (g)
Nichols, L.O. & Son Mfg. Co., Mo (a, b,c,g)
Nigg Engineering Corp., Calif (a,b,c,g)
Noera Mfg. Co., Conn (a,b,g)
Noland Tank & Galvanizing Co., Tenn
Norcross, C.S. & Sons Co., Ill (g)
Nylok Corp., NJ (a,b,c,e,g)
Ohio Nut & Washer Co., Ohio (a,g)
Olean Electro Plating Co., NY (a,b,g)
Ormond Mfg., Co., Inc., NJ (a,b,f,j)
Pabst Engineering Equipment Co., Inc., NJ (a,b,c,e,f,g)
Paragon Spring Co., Ill (a,b,c,f,g)
Parish Pressed Steel Div., Dana Corp., Pa (a,g)
Parker, Charles Co., Conn (a,f)
Parker Metal Goods Co., Mass (a,b,g)
Peck Spring Co., Conn (a,b,c,f,g,h)
Peerless Products Industries, Ill (a, b,g)
Pemco Wheel Co., Mich (g)
Penn Fibre & Specialty Co., Inc., Pa (a,b,c,d,e,f,g,j)
Penrod, Floyd & Sons Tool & Engineering Corp., Ind (a,b,g)
Perrin, Edward C. Co., NJ (a,b,g)
Peterson Products Corp., Ill (a,b,f,g)
Philadelphia Enameling Works Inc., Pa (a,b,g)
Phoenix Iron & Steel Co., Pa (a,g)
Pioneer Stamped Products Co., NY (a, b,c,d,e,f,g,h)
Pittsburgh Forgings Co., Mich (g)
Plume & Atwood Mfg. Co., Conn (a,b,f,g)
Porter, H.K., Inc., Forge & Fittings Div., Ohio (a,g)
Powell Pressed Steel Co., Ohio (a,g)
Premier Metal Works, Inc., Ill (a,b, f,g)
Pressed Steel Co., Pa (a,b,d,f,g,j)
Presswork, Inc., Mich (a,b,c,d,f,g,j)
Prestole Corp., Ohio (a,g)
Queen Products Co., Inc., Ky (a,b,g)
Reed & Prince Mfg. Co., Mass (a,b, c,g)
Regal Ware, Inc., Wis (a,b,g)
**Reichert Float & Mfg. Co., Ohio** (a,b,c,d,f,j)—Ad p 464
Reliable Spring & Wire Forms Co., Ohio (a,b,f,g)
Republic Steel Corp., Ohio (g)
Revere Copper & Brass, Inc., NY (a, b,c,f,g,j)
Reynolds Metals Co., Va (a)
Rochester Novelty Works, Inc., NY (a,g)
Rockwell Engineering Co., Ill (a,b,c,g)
**Rockwell - Standard Corp., Stamping Div., NY** (a,b,d,f,g)—Ad p 458
Rohr Aircraft Corp., Calif (a,e,g,h)
Rolock, Inc., Conn (f)
Roth Steel Products Co., Ohio (g)
Ryerson, Joseph T. & Son, Inc., Ill (a,g)
S.T.D. Div., Pierce Industries, Inc. of Ohio, Ohio (a,g)
St. Marys Carbon Co., Pa (b)
Sargent & Greenleaf, Inc., NY (a,b,g)
Scovill Mfg. Co., Mill Products Div., Conn (a,b,c,f,g)
Security Cos., Mich (a)
Security Sash & Screen Co., Mich (a)
Serwell Products Co., Ohio (b,g)
Shakeproof Div., Illinois Tool Works, Ill (b,g)
Shank Metal Products Co., NY (a,g)
Shelby Mfg. Co., Ohio (g)
Sheller Mfg. Corp., Mich (g)
Sierra Electric Corp., Calif (b,g)
Sillcocks Miller Co., NJ (a,b,f,g)
Simonsen Metal Products Co., Ill (a, g)
Sinclair Co., Mass (b,g)
Sioux City Foundry & Boiler Co., Iowa (g)
Smithers Tool & Machine Products, Inc., NY (g)
Smith-Victor Corp., Ind (a,g)
Smoot-Holman Co., Calif (g)
Sommer Metalcraft Corp., Ind (a,g)
South River Metal Products Co., Inc., NJ (a,e,g)
Southern Car & Mfg. Co., Inc., Ala (a,b,g)
Southwestern Porcelain Steel Corp., Okla (g)
Spincraft, Inc., Wis (a,b,g)
Stainless Metals, Inc., NY (c,f,h)
Stamford Metal Specialty Co., Inc., NY (a,f,g)
Standard Forge & Axle Co., Inc., Ala (g)
Standard Nut & Bolt Co., RI (a,b,f,g)
Standard Steel Sections, Inc., NY (a, b,c,g)
Stanley Industrial Sales, Stanley Works, Conn (g)
Star Heel Plate Co., Inc., NJ (g)
Star Stamping Co., Mich (a,b,g)
Staver Co., Inc., NY (a,b,c,d,e,f,g,h,j)
Steel Heddle Mfg. Co., Pa (a,b,c,e,f,g, h,j)
Steel Industries, Inc., Ind (a,b,g)
Steinen, Wm. Mfg. Co., NJ (a,b,c,g)
Stenman, Brer F., Mass (a,g)
Stimpson, Edwin B. Co., Inc., NY (a,o,f,g,j)
Stirrup Metal Products Corp., NJ (a, b,c,g)
Superior Mfg. Co., Pa (g, j)
Superior Spinning & Stamping Co., Ohio (a,b,f,g)
Sylvania Electric Products Inc., Parts Div., Pa (a,b,c,f,g)
Textile Shield Co., Inc., Mass (a,b,g)
Thompson Products, Inc., Ohio (g)
Thompson-Bremer & Co., Ill (a,b,c,f, g,h)
Titchener, E.H. & Co., NY (a,b,f,g)
Toledo Stamping & Mfg. Co., Ohio (a,b,g,h)
Transue & Williams Steel Forging Corp., Ohio (f,g)
Triangle Stamping Co., Ohio (a,b,c,d,f, g,j)
Turner & Seymour Mfg. Co., Conn (a, b,g)
United Metal Products Corp., Mich (a,b,c,g)
United Screw & Bolt Corp., Ill (a, b,g)
United Shoe Machinery Corp., Mass (a,b,f,g,j)
U.S. Gasket & Shim Co., Ohio (a, b,c,d,e,f,g,h,j)
United-Carr Fastener Corp., Mass (a, b,g)
Unity Machine & Tool Corp., Pa (a, b,g)
Van Valkenburg, L.A. Co., Mass (a, b,c,f,g)
Variety Stamping Corp., Ohio (a,b,c,g)
Volkert Stampings, Inc., NY (b,f,g)
WLS Stamping Co., Ohio (a,b,c,d,e, f,g,h,j)
Wabash Metal Products Co., Inc., Ind (a,b,g)
Wagner, E.P. Mfg. Co., Wis (a,b,c,g, j)
Wagner Specialty Co., Wis (a,b,c,g, j)
Wall, P. Mfg. Co., Pa (a,b,g)
Wall Tube & Metal Products Co., Tenn (g)
Ward, H.H. Co., Pa (a,b,c,f,g,j)
Waterbury Buckle Co., Conn (a,g,j)
Waterbury Cos., Inc., Conn (a,b,g)
Waterbury Pressed Metal Co., Conn (a,b,f,g)
Waterman Industrial, Inc., Calif (a, b,g)
Wayne Foundry & Stamping Co., Mich (a,b,e,g,h)
Weatherhead Co., Ind (a,b,g,h)
Weber-Knapp Co., NY (a,g)
Welding Apparatus Co., Ill (a,f,g)
Wesbar Stamping Corp., Wis (a,g)
Wesco Spring Co., Ill (g)
Western Tool & Die Works, Ore (a,b, g)
Wilder Mfg. Co., Inc., Calif (a,c,g)
Williams, F.B. Co., Ill (g)
Williams, H.E. Products Co., Mo (a, b,c,g,j)
Wilson-Hurd Mfg. Co., Inc., Wis (a)
Wirth, Carl & Son, Inc., NY (a,b,c,g)
Wisconsin Gasket & Mfg. Co., Wis (a,b,g)
Wisconsin Tool & Stamping Co., Ill (a,b,d,f,g,j)
Wood, John Co., Minn (g)
Woolf Aircraft Products, Inc., Mich (a,b,g)
Worcester Pressed Steel Co., Mass (a, b,c,e,f,g,h,j)
Worcester Stamped Metal Co., Mass (a,b,e,f,g,h,j)
Worth Co., Wis (a,b,c,g)
Wrought Washer Mfg. Co., Wis (a,b, d,e,f,g,h,j)
Wuest Bros., Inc., Ky (a,b,c,f,g)
Youngstown Kitchens Div., American Standard Co., Ohio (a,g)
Youngstown Mfg., Inc., Ohio (a,g)
Youngstown Sheet and Tube Co., Ohio (g)

## Steatite

(see Ceramics)

## Steel, Carbon

Acme-Newport Steel Co., Ky (w,z,cc)
Advance Screw Products Co., Inc., Wis (o)
Advance Stamping Co., Mich (dd)
Ainsworth-Precision Castings Co., Div of Harsco Corp., Mich (ee)
Alan Wood Steel Co., Pa (q,w,z,cc,dd)
Albert Pipe Supply Co., NY (ee)
Albert Wright Screw Machine Products, Calif (bb)
Alco Products, Inc., NY (q,aa)
Allegheny Ludlum Steel Corp., Pa (dd)
Alloy Metal Powders, Inc., Iowa (aa)
Aimco Steel Products Corp., Ind (o, z,bb,cc,dd)
Amalgamated Steel Corp., Ohio (o,bb)
American Cast Iron Pipe Co., Ala (ee)
American Metal Products, Inc., Ohio (z,cc)
American Silver Co., NY (v,dd)
**American Steel and Wire Div., U. S. Steel Corp., Ohio** (o)—Ad pp 90-91
Ames, W. & Co., NJ (o)
Anchor Drawn Steel Co., Div. of Vanadium-Alloys Steel Co., Pa (bb,ff)
Aristoloy Steel Div., Copperweld Steel Co., Ohio (o,q,w)
Armco Steel Corp., Ohio (o,z,bb,cc, dd,ff)
Armco Steel Corp., Sheffield Div., Mo (o,q,w,z,bb,cc,dd,ff)
Athenia Steel Div., National Standard Co., NJ (dd)
Atlantic Steel Co., Ga (o,q,w,z,bb,cc, dd,ee,ff)
Austenal Co., Div. of Howe Sound Co., NY (w)
Babcock & Wilcox Co., Tubular Products Div., Pa (ee)
Barium Steel Corp., NY (q,w,z,ee)
Baxter Foundry & Machine Works, Inc., Id (o,z,bb,cc,dd)
Bethlehem Steel Co., Pa (o,q,z,bb, cc,dd,ee,ff)
Biddle Screw Products Co., Ind (o,bb, ee)
Bliss & Laughlin, Inc., Ill (o)
Brainard Steel Div., Sharon Steel Corp., Ohio (ee)
Burkhardt Steel Co., Colo (o,z,cc,dd, ee)
Byers, A.M. Co., Pa (o,q,w,z,cc,dd)
Cannon-Muskegon Corp., Mich (w)
Carpenter Steel Co., Webb Wire Div., NJ (ff)
Caspers Tin Plate Co., Ill (cc,dd)
Castle, A.M. & Co., Ill (o,z,bb,cc, dd,ee,ff)
Central Fabricators, Inc., Ohio (z, bb,cc,ee)
Chicago Steel Service Co., Ill (o,z, bb,cc,dd)
Clad-Rex Corp., Ill (cc)
Clark Perforating Co., Mich (cc,dd)
Clayton Mark & Co., Ill (ee)
Colonial Steel Div., Vanadium-Alloys Steel Co., Pa (o,q,w,z,bb,cc,ff)
Columbia-Geneva Steel Div., U. S. Steel Corp., Calif (o,q,z,cc,dd,ee)
Connors Steel Div., H.K. Porter Co., Inc., Ala (o,q,w,dd)
Continental Steel Corp., Ind (o,q,bb,ff)
Crucible Steel Co. of America, Pa (o,q,w,z,bb,cc,dd,ee,ff)
Crucible Steel Co. of America, Titanium & Vacuum Metal Products Div., Pa (o,q,z,bb,cc,dd,ff)
Cumberland Steel Co., Md (o)
Designers Metal Corp., Ill (cc)
Detroit Steel Corp., Portsmouth Div., Mich (q,w,bb,cc)
Dixon Sintaloy, Inc., Conn (o)
Dudek & Bock Spring Mfg. Co., Ill (dd,ff)
Eaton Mfg. Co., Reliance Div., Ohio (o,ff)
Edgcomb Steel & Aluminum Corp., NJ (o,z,cc,dd)
Elliott Bros. Steel Co., Pa (cc,dd)
Empire-Reeves Steel Div., Universal-Cyclops Steel Corp., Pa (z,cc)
Enterprise Wheel & Car Corp., Va (o, z,cc)
Eynon-Dakin Co., Mich (ee)
Finkl, A. & Sons Co., Ill (w)
Follansbee Steel Corp., W.Va (cc,dd)
Forg, Peter Mfg. Co., Mass (cc)
Fort Howard Steel & Wire Co., Wis (o)
Franklin Steel Div., Borg-Warner Corp., Pa (o)
Frasse, Peter A. & Co., Inc., NY (o,bb,cc,dd,ee,ff)
Fromson Orban Co., Inc., NY (ee)
Gary Steel Products Corp., Va (o,z,cc)
General Chain & Mfg. Corp., Ohio (ff)
General Motors Corp., Rochester Products Div., NY (ee)
Granite City Steel Co., Ill (w,z,cc)
Great Lakes Steel Corp., Div. of National Steel Corp., Mich (z,cc,dd)
Green River Steel Corp., Ky (o,q,w)
Hardy, Charles, Inc., NY (aa)
Hayden Wire Works, Inc., Mass (o, bb,ee,ff)
Haydon Corp., NY (ee)
Houston Blow Pipe & Sheet Metal Works, Tex (o,z,cc)
Inland Steel Co., Ill (o,z,cc,dd)
Inshield Die & Stamping Co., Ohio (cc)
Isaacson Iron Works, Wash (q,w)
Jackson Steel Products, Inc., NY (ee)
Jones & Laughlin Steel Corp., Pa (o, q,z,bb,cc,dd,ee,ff)
K-D Mfg. Co., Tex (o)
Kaiser Steel Corp., Calif (o,q,w,z,bb, cc,dd,ee)
Keystone Drawn Steel Co., Pa (o)
Keystone Steel & Wire Co., Ill (w, bb)
Kinkead Industries, Inc., Ill (o,z,bb, cc,dd)
Korhumel Steel and Aluminum Co., Ill (o,z,bb,cc,dd,ff)
Laclede Steel Co., Mo (o,q,w,bb,dd, ee,ff)
Larson, Charles E. & Sons, Inc., Ill (o)
La Salle Steel Co., Ill (o)
Le Tourneau, R.G., Inc., Tex (z)
Levinson Steel Co., Pa (o,z,bb,cc,dd)
Lock Joint Tube Co., Inc., Ind (ee)
Lockhart Iron & Steel Co., Pa (o,q,z, bb,cc,dd,ee)
Lockport Mfg. Co., Ill (z)
Lukens Steel Co., Pa (w,z)
Lundquist Tool & Mfg. Co., Inc., Mass (bb,cc,dd,ee,ff)
Lurla Engineering Co., Pa (z,bb,cc)
Mahon, R.C. Co., Mich (o,z,cc,dd)
Makepeace, D.E. Div., Engelhard Industries Inc., Mass (o,dd,ee)
McCarter Iron Works, Inc., Pa (o,z,bb, cc)
McGregor-Michigan Corp., Mich (z)
McInnes Steel Co., Pa (o)
McLouth Steel Corp., Mich (cc,dd)
Metal Forming Corp., Div. of Vanadium-Alloys Steel Co., Ind (ee)
Metallizing Co. of Los Angeles, Inc., Calif (ff)
Michigan Seamless Tube Co., Mich (ee)
Midvale-Heppenstall Co., Pa (w)
Modern Plating Corp., Ill (z)
Morrisville Foundry Co., Inc., Vt (z, bb,cc,dd)
Murray, A.B. Co., Inc., NJ (ee)
Narragansett Boiler Works, Inc., RI (o,z,bb,cc,ee)
National Galvanizing Co., Pa (z,bb, cc,ee)
National Lock Washer Co., NJ (ff)
National Supply Co., Pa (o,q,w)
National Tube Div., U.S. Steel Corp., Pa (ee)
National U.S. Radiator Corp., Plastic Metals Div., Pa (aa)
**National-Standard Co., Mich** (dd,ff)—Ad p 421
Nesor Alloy Products Co., NJ (ff)
New York Iron Roofing & Corrugating Co., Inc., NJ (cc)
Newman-Crosby Steel Co., RI (dd)
Nikoh Tube Co., Ill (bb,cc,dd,ee)
Norrich Plastics Corp., Screw Machine Products Div., NY (o,bb,ee)
Northwestern Steel & Wire Co., Ill (o,q,w,z,bb,ff)
Norwalk Powdered Metals, Inc., Conn (aa)
Ohio Seamless Tube Div., Copperweld Steel Co., Ohio (ee)
Ormond Mfg. Co., Inc., NJ (cc,dd,ff)
Pacific States Steel Corp., Calif (o, q,w)
Pacific Tube Co., Calif (o)
Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa (ff)
Peninsular Steel Co., Mich (o,z)
Phoenix Iron & Steel Co., Pa (z)
Phoenix Mfg. Co., Ill (o)
Pittsburgh Forgings Co., Mich (o,q)
Pittsburgh Steel Co., Pa (q,w,bb,cc, dd,ee,ff)
Precision Tube Co., Inc., Pa (ee)
Purdy, A.R. Co., Inc., NJ (o,z,bb, cc,dd,ff)
Rathbone Corp., Mass (o,bb)
Reactive Metals, Inc., Ohio (cc)
**Republic Steel Corp., Ohio** (o,q,w,z,bb,cc,dd,ee,ff)—Ad pp 84-85
Reynolds Aluminum Supply Co., Ga (cc)
Rigidized Metals Corp., NY (cc,dd)
**Riverside-Alloy Metal Div., H.K. Porter Co., Inc., NJ** (ff)—Ad p 160
Rodney Metals, Inc., Mass (v,dd)
Roebling's, John A. Sons Div., Colorado Fuel & Iron Corp., NJ (bb, dd,ff)
Rome Mfg. Div., Revere Copper & Brass Inc., NY (ee)
Rome Strip Steel Co., Inc., NY (o, z,dd,ff)
Ross-Meehan Foundries, Tenn (o)
Ryerson, Joseph T. & Son, Inc., Ill (o,q,z,bb,cc,dd,ee,ff)
St. Louis Steel Casting, Inc., Mo (o)
Sandusky Foundry & Machine Co., Ohio (ee)
**Sandvik Steel, Inc., NJ** (dd)—Ad p 83
Saran Lined Pipe Co., Div. of Michigan Pipe Co., Mich (ee)
Sawhill Tubular Products, Inc., Pa (ee)
Scudder, E.J. Foundry & Machine Co., NJ (bb,ee)
Service Steel Div., Van Pelt Corp., Mich (ee)
Sharon Steel Corp., Pa (q,w,z,cc,dd)
Sharpsville Steel Fabricators, Inc., Pa (o,z,bb,cc)
Shaw-Kendall Engineering Co., Ohio (ee)
Sherwatt Equipment & Mfg. Co., Inc., NY (ff)
Simonds Saw & Steel Co., Mass (o,cc)
Smith-Moon Steel Co., Inc., Kan (o, z,cc)
Solar Steel Corp., Ohio (o,bb,cc,dd,ee)
Sonken-Galamba Corp., Kan (z,bb,cc, ee)
**Stainless and Strip Div., Jones & Laughlin Steel Corp., Ohio** (dd)—Ad p 89
Southern Fabricating Co., Inc., Ala (ee)
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa (q,w)
Star Heel Plate Co., Inc., NJ (o,z, bb,cc,dd,ee,ff)
Sun Steel Co., Ill (o,q,z,bb,cc,dd)
Superior Drawn Steel Co., Pa (o,bb,ff)
Superior Steel Div., Copperweld Steel Co., Pa (dd)
Superior Tube Co., Pa (ee)
Sylvania Electric Products, Inc., Parts Div., Pa (ff)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (o,q,z,cc,dd)
Thomas Strip Div., Pittsburgh Steel Co., Pa (dd)
Thompson Industries, Inc., NY (bb)
Thompson Wire Co., Mass (dd)
Timken Roller Bearing Co., Steel & Tube Div., Ohio (ee)
Topeka Foundry & Iron Works Co., Inc., Kan (o,z,bb,cc,dd)
Trojan Steel Co., W.Va (o,z,bb,cc,dd)
Tube Distributors Co., Inc., NY (ee)
Tube Reducing Corp., NJ (ee)
Uddeholm Co. of America, Inc., NY (bb,dd,ee)
Udylite Corp., Mich (n)
Ullmann, Inc., Wis (o,ee)
Union Iron Works, Wash (o,z,cc,dd,ee)
Union Steel Corp., NJ (dd)
United Screw & Bolt Corp., Ill (bb, cc,dd,ff)
U.S. Challenge & Challenge Co., Ill (bb)
U.S. Gasket & Shim Co., Ohio (cc,dd)
U.S. Steel Corp., Pa (o,q,z,cc,dd)
U.S. Steel Supply Div., U.S. Steel Corp., Ill (o,z,cc,dd,ee)
Vanadium-Alloys Steel Co., Pa (o,q, w,z,aa,bb,cc,ff)

### KEY

**MATERIALS**

a—Aluminum and its alloys
b—Copper and its alloys
c—Iron and its alloys (except steel)
d—Lead and its alloys
e—Magnesium and its alloys
f—Nickel and its alloys
g—Steels
h—Titanium and its alloys
j—Zinc and its alloys
k—Thermoplastics
l—Thermosetting plastics
m—Elastomers

**BASIC FORMS**

n—Anodes
o—Bar
p—Base resins, polymers or gums
q—Billets
r—Custom formed parts (incl. specialties)
s—Fibers
t—Film
u—Foams (component materials or products)
v—Foil
w—Ingot
x—Laminating, casting resins
y—Molding compounds
z—Plate
aa—Powder
bb—Rod
cc—Sheet
dd—Strip
ee—Tubing
ff—Wire

Vulcan Rail & Construction Co., NY (o,dd,ee)
Vulcan-Kidd Steel Div., H.K. Porter Co., Inc., Pa (o,q,w,bb,ff)
Wallace Tube Co., Div. of Wallace Supplies Mfg. Co., Ill (ee)
Wal-Mar Corp., Ill (ee)
Washburn Wire Co., Phillipsdale Div., RI (q,bb,dd)
Weirton Steel Co., Div. of National Steel Corp., W.Va (cc)
Western Automatic Machine Screw Co., Div. of Standard Screw Co., Ohio (o)
Western Iron & Foundry Co., Inc., Kan (o,z,bb,cc,dd)
Wheatland Tube Co., Pa (ee)
Wickwire Bros., Inc., NY (bb,ff)
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY (w,z)
Wilson Steel & Wire Co., Ill (ff)
Wisconsin Steel Co., Div. of International Harvester Co., Ill (o,q)
Wycoff Steel Co., Pa (o,z)
Youngstown Sheet and Tube Co., Ohio (o,z,bb,cc,dd,ee,ff)

## Steel, Carbon—Castings

Acco Steel Casting Div., American Chain & Cable Co., Inc., Pa
Adirondack Steel Casting Co., NY
Advance Foundry Co., Ohio
Allied Steel Castings Co., Ill
All-Metals Precision Casting Corp., NY
Alloy Cast Steel Co., Ohio
Alloy Precision Castings Co., Ohio
Alloy Steel & Metals Co., Calif
American Cast Iron Pipe Co., Ala
American Steel Foundries, Ill
Arneson Foundry Co., Wis
Arwood Corp., NY
Atlantic Foundry Co., Ohio
Atlantic Steel Castings Co., Pa
Austenal Co., Div. of Howe Sound Co., NY
Auto Specialties Mfg. Co., Mich
Baldwin-Lima-Hamilton Corp., Pa
Bay City Electric Steel Casting Co., Mich.
Beaver Valley Alloy Foundry Co., Pa
Bethlehem Steel Co., Pa
Birdsboro Steel Foundry & Machine Co., Pa
Blaw-Knox Co., Pa
Bone Engineering Corp., Calif
Calumet Steel Castings Corp., Ind
Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich
Commercial Steel Casting Co., Ohio
Crucible Steel Casting Co., Pa
Dayton Steel Foundry Co., Ohio
Dodge Steel Co., Pa
Eastern Malleable Iron Co., Del
Electric Steel Castings Co., Ind
Electric Steel Foundry Co., Ore
Electrocast Steel Foundry Co., Ill
Empire Foundry Co., Inc., Calif
Empire Steel Castings, Inc., Pa
Engineered Castings Div., American Brake Shoe Co., NY
Falk Corp., Wis
Farrel-Birmingham Co., Inc., Conn
Federal Steel Products Corp., Tex
Fort Pitt Steel Casting Div., Pittsburgh Steel Foundry Corp., Pa
General Electric Co., Foundry Dept., NY
General Steel Castings Corp., Ill
Glover Machine Works, Ga
Goslin Birmingham Mfg. Co., Inc., Ala
Grede Foundries, Inc., Wis
Gunite Foundries Corp., Ill
Hartford Electric Steel Corp., Conn
Hica, Inc., La
Hitchiner Mfg. Co., Inc., NH
Howard Foundry Co., Ill
Hughes Tool Co., Tex
Humphrey Castings, Inc., Calif
Illinois Precise Casting Co., Ill
Kay-Brunner Steel Products, Inc., Calif
LFM Mfg. Co., Inc., Sub. of Rockwell Mfg. Co., Kan
Lebanon Steel Foundry, Pa
Lectromelt Casting Div., Akron Standard Mold Co., Ohio
Liberty Foundry Co., Mo
Lincoln Iron Works, Vt
Los Angeles Steel Casting Co., Calif
Mackintosh-Hemphill Div., E.W. Bliss Co., Pa
Manco Products, Inc., Mich
Massillon Steel Casting Co., Ohio
Mercast Mfg. Corp., Calif
Midwest Precision Castings Co., Ohio
Minneapolis Electric Steel Castings Co., Minn
Misco Precision Casting Co., Mich
Missouri Steel Castings Co., Mo
Monroe Steel Castings Co., Mich
Montague Machine Co., Mass
National Malleable & Steel Castings Co., Ohio
National Precision Casting Corp., Div. of Beryllium Corp., Pa
National Supply Co., Pa
Ohio Steel Foundry Co., Ohio
Oklahoma Steel Castings Div., American Steel & Pump Corp., Okla
Olympic Steel Works, Wash
Omaha Steel Works, Neb
Pelton Steel Casting Co., Wis
Penn Steel Castings Co., Pa
Picco, Inc., Calif
Pittsburgh Steel Foundry Corp., Pa
Posey Iron Works, Inc., Pa
Pratt & Letchworth Div., Dayton Malleable Iron Co., Inc., NY
Precision Founders, Inc., Calif
Quaker Alloy Casting Co., Pa
Quality Electric Steel Castings, Inc., Tex
Quincy Steel Casting Co., Mass
Racine Steel Castings Co., Wis
Reliance Steel Castings Co., Pa
Rockwell Engineering Co., Ill
Ross-Meehan Foundries, Tenn
Ryerson, Joseph T. & Son, Inc., Ill
St. Louis Steel Casting, Inc., Mo
Sandusky Foundry & Machine Co., Ohio
Sawbrook Steel Castings Co., Ohio
Scullin Steel Co., Mo
Sivyer Steel Casting Co., Wis
Skookum Co., Inc., Ore
Sorbo-Mat Process Engineers, Mo
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa
Star Heel Plate Co., Inc., NJ
Strong Steel Foundry Co., NY
Superior Foundry, Inc., Ohio
Superior Steel & Malleable Castings Co., Mich
Swedish Crucible Steel Co., Mich
Texas Foundries, Inc., Tex
Texas Steel Co., Tex
Thys Co., Calif
Union Iron Works, Wash
Union Spring & Mfg. Co., Pa
**Unitcast Corp., Ohio**
—Ad p 467
U.S. Pipe & Foundry Co., Ala
Utility Steel Foundry, Calif
Valley Steel Casting Co., Mich
Vascoloy-Ramet Corp., Ill
Vulcan Iron Works, Pa
Washington Iron Works, Wash
West Steel Casting Co., Ohio
Westinghouse Electric Corp., Materials Mfg. Dept., Pa
Westlectric Castings, Inc., Calif
Worthington Corp., NJ

## Steel, Heat and Corrosion Resistant

Acme Tube, Inc., NJ (ee)
Advance Stamping Co., Mich (dd)
Albert Pipe Supply Co., Inc., NY (ee)
Albraco Metals Co., NY (o,q,bb,ee,ff)
Alco Products, Inc., NY (q)
**Allegheny Ludlum Steel Corp., Pa**
(o,q,w,z,bb,cc,dd,ee,ff)—Ad p 87
Alloy Metal Powders, Inc., NY (aa)
Alloy Metal Products, Inc., Iowa (o,q,w)
Alofs Mfg. Co., Mich (dd)
American Cast Iron Pipe Co., Ala (ee)
American Silver Co., NY (v,dd,ee,ff)
**American Steel & Wire Div., U.S. Steel Corp., Ohio**
(ff)—Ad pp 90-91
Anchor Drawn Steel Co., Div. of Vanadium-Alloys Steel Co., Pa (bb,ff)
Arcos Corp., Pa (ff)
Aristoloy Steel Div., Copperweld Steel Co., Ohio (o,q)
Armco Steel Corp., Ohio (o,q,v,z,bb,cc,dd,ff)
Athenia Steel Div., National-Standard Co., NJ (dd)
Austenal Co., Div. of Howe Sound Co., NY (w)
Babcock & Wilcox Co., Tubular Products Div., Pa (ee)
Bethlehem Steel Co., Pa (o,q,z,bb,cc,dd,ee,ff)
Biddle Screw Products Co., Ind (o,bb,ee)
Bishop, J. & Co., Platinum Works, Pa (ee)
Brinkerhoff Brass & Bronze Works, Inc., NY (z,bb,cc)
Brush Beryllium Co., Ohio (v,dd)
Byers, A.M. Co., Pa (o,q,w,z,cc,dd)
Cannon-Muskegon Corp., Mich (w)
Carlson, G.O., Inc., Pa (o,z,cc)
Carpenter Steel Co., Pa (o,q,w,bb,dd,ee,ff)
Carpenter Steel Co., Alloy Tube Div., NJ (ff)
Carpenter Steel Co., Webb Wire Div., NJ (ff)
Castle, A.M. & Co., Ill (o,q,z,cc,dd,ff)
Central Fabricators, Inc., Ohio (z,bb,cc,ee)
Chromalloy Corp., NY (cc)
Colonial Steel Div., Vanadium-Alloys Steel Co., Pa (o,q,w,z,bb,cc,ff)
Columbia-Geneva Steel Div., U.S. Steel Corp., Calif (o,q,w,z,cc,dd,ee,ff)
**Crucible Steel Co. of America, Pa**
(o,q,w,z,bb,cc,dd,ee,ff)—Ad p 93
Crucible Steel Co. of America, Titanium & Vacuum Metal Products Div., Pa (o,q,z,bb,cc,dd,ff)
Curtiss-Wright Corp., Metals Processing Div., NY (ee)
Damascus Tube Co., Pa (ee)
Dixon Sintaloy, Inc., Conn (o)
Driver, Wilbur B. Co., NJ (y,bb,dd,ff)
Dudek & Bock Spring Mfg Co., Ill. (dd, ff)
Eastern Stainless Steel Corp., Md (z,cc,dd)
Eaton Mfg. Co., Reliance Div., Ohio (o,ff)
Edgcomb Steel & Aluminum Corp., NJ (o,z,cc,dd)
Electric Steel Foundry Co., Ore (o,q,w,z,bb,cc,dd,ee,ff)
Erskine Precision Wire Corp., Pa (ff)
Eynon-Dakin Co., Mich (ee)
Firth Sterling, Inc., Pa (o,q,w,bb,ff)
Frasse, Peter A. & Co., Inc., NY (o,bb,cc,dd,ee,ff)
Fromson Orban Co., Inc., NY (ee)
Gary Steel Products Corp., Va (o,z,cc)
General Electric Co., Metallurgical Products Dept., Mich (aa,bb,cc,dd)
Green River Steel Corp., Ky (o,q,w)
Hamilton Watch Co., Precision Metals Div., Pa (v,cc,dd,ff)
Hardy, Charles, Inc., NY (aa)
Hayden Wire Works, Inc., Mass (o,z,bb,dd,ee,ff)
Haydon Corp., NY (ee)
Hexcel Products, Inc., Calif (v)
**Hoeganaes Sponge Iron Corp., NJ**
(aa)—Ad p 462
Industrial Stainless Steels, Inc., Mass (o,q,z,bb,cc,dd,ee,ff)
Jessop Steel Co., Pa (o,q,z,cc,dd,ee)
Johnson, A. & Co., Inc., NY (ee)
Jones & Laughlin Steel Corp., Pa (o,q,cc,dd)
Josiyn Stainless Steels, Ill (o,q,w,bb,ff)
Kaiser Steel Corp., Calif (o,q,w,z,bb,cc,dd)
Kelsey-Hayes Co., Mich (o,q,z,cc)
Kinkead Industries, Inc., Ill (cc,dd)
Kirk & Blum Mfg Co., Ohio (z,cc)
Kolcast Industries Div., Thompson Products, Inc., Ohio (q,w)
Krueger Fabricating Co., Inc., Wis (cc)
Larson, Charles E. & Sons Inc., Ill (z)
**Latrobe Steel Co., Pa**
(o,q,w)—Ad p 95
Lockport Mfg. Co., Ill (z)
Lukens Steel Co., Pa (w,z)
Lundquist Tool & Mfg. Co., Inc., Mass (bb,cc,dd,ee,ff)
Makepeace, D.E. Div., Engelhard Industries Inc., Mass (o,dd,ee)
McCarter Iron Works, Inc., Pa (o,z,bb,cc)
McInnes Steel Co., Pa (o)
Metallizing Co. of Los Angeles, Inc., Calif (ff)
Michigan Seamless Tube Co., Mich (ee)
Midvale-Heppenstall Co., Pa (w)
**Mott Metallurgical Corp., Ill**
(porous)—Ad p 466
Murray, A.B. Co., Inc., NJ (ee)
National Electric Div., H.K. Porter Co., Inc., Pa (ee)
National Supply Co., Pa (o,q,w)
National Tube Div., U.S. Steel Corp., Pa (ee)
**National-Standard Co., Mich**
(dd,ff)—Ad p 421
New Jersey Metals Co., NJ (w)
Norrich Plastics Corp., Screw Machine Products Div., NY (o,bb,ee)
Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa (ff)
Pencoyd Steel & Forge Corp., Pa (o,q,w)
Precision Tube Co., Inc., Pa (ee)
Purdy, A.R. Co., Inc., NJ (o,z,bb,cc,dd,ff)
Rathbone Corp., Mass (o,bb)
**Republic Steel Corp., Ohio**
(o,q,w,z,bb,cc,dd,ee,ff)—Ad pp 84-85
Reynolds Aluminum Supply Co., Ga (o,z,bb,cc,dd,ee)
**Riverside-Alloy Metal Div., H.K. Porter Co., Inc., NJ**
(bb,dd,ff)—Ad p 160
Rodney Metals, Inc., Mass (v,dd)
Rolled Alloys, Inc., Mich (o,q,z,bb,cc,dd,ee,ff)
Rome Mfg. Div., Revere Copper & Brass Inc., NY (ee)
Ross-Meehan Foundries, Tenn (o)
Ryerson, Joseph T. & Son, Inc., Ill (o,q,z,bb,cc,dd,ee,ff)
St. Louis Steel Casting, Inc., Mo (n)
Sandusky Foundry & Machine Co., Ohio (ee)
**Sandvik Steel, Inc., NJ**
(dd,ee,ff)—Ad p 83
Service Steel Div., Van Pelt Corp., Mich (ee)
Seymour Mfg. Co., Conn (dd)
Sharon Steel Corp., Pa (q,w,z,cc,dd)
Sharpsville Steel Fabricators, Inc., Pa (o,z,bb,cc)
Sherwatt Equipment & Mfg. Co., Inc., NY (ff)
Simonds Saw & Steel Co., Mass (o,cc)
Smith-Moon Steel Co., Kan (o,z,cc,dd)
Solar Steel Corp., Ohio (o,z)
**Somers Brass Co., Inc., Conn**
(v,dd,)—Ad p 162
**Stainless and Strip Div., Jones & Laughlin Steel Corp., Mich**
(o,q,w,bb,cc,dd,ff)—Ad pp 96-97

**Stainless and Strip Div., Jones & Laughlin Steel Corp., Ohio** (dd)—Ad p 89
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa (q,w)
Star Heel Plate Co., Inc., NJ (z,ff)
Sun Steel Co., Ill (cc,dd)
Superior Drawn Steel Co., Pa (o, bb,ff)
Superior Mfg. Co., Pa (dd,ff)
Superior Steel Corp., Pa (dd)
Superior Steel Div., Copperweld Steel Co., Pa (dd)
Superior Tube Co., Pa (ee)
Sylvania Electric Products, Inc., Parts Div., Pa (ff)
Techalloy Co., Inc., Pa (v,bb,dd,ff)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (o,q,w,z,cc,dd,ff)
Timken Roller Bearing Co., Steel & Tube Div., Ohio (o,q,ee)
Trent Tube Co., Sub. of Crucible Steel Co. of America, Pa (ee)
Tube Distributors Co., Inc., NY (ee)
Tube Reducing Corp., NJ (ee)
Uddeholm Co. of America, Inc., NY (bb,dd)
Ulbrich Stainless Steels Corp., Conn (dd)
Ullmann, Inc., Wis (o,ee)
Union Steel Corp., NJ (dd,ee)
United Screw & Bolt Corp., Ill (bb, cc,dd,ff)
U.S. Challenge & Challenge Co., Ill (bb)
U.S. Gasket & Shim Co., Ohio (cc,dd)
U. S. Steel Corp., Pa (o,q,w,z,cc,dd, ee)
U.S. Steel Supply Div., U.S. Steel Corp., Ill (o,q,z,cc,ee)
Universal-Cyclops Steel Corp., Pa (o, q,z,bb,cc,dd,ff)
Uniworld Research Corp. of America, Ohio (o,q,v,w,z,aa,bb,cc,dd,ee,ff)
**Vanadium Corp. of America, NY** —Ad p 86
Vanadium-Alloys Steel Co., Pa (o,q,w, z,aa,bb,cc,ff)
Vulcan Rail & Construction Co., NY (o,dd,ee)
Vulcan-Kidd Steel Div., H.K. Porter Co., Inc., Pa (o,q,z,bb,ff)
**Waimet Alloys Co., Mich** (w)—Ad p 82
Wall Tube & Metal Products Co., Tenn (ee)
Wallingford Steel Co. Conn (v,dd)
Washington Steel Corp., Pa (cc,dd)
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,w,z,bb,cc,dd,ee)
Whitehead Metal Products Co., Inc., NY (z,bb,cc,dd)
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY (z)
Wisconsin Centrifugal Foundry Inc., Wis (ee)
Worcester Wire Works Div., National-Standard Co, Mass (ff)

## Steel, Heat and Corrosion Resistant—Castings

**Acco Steel Casting Div., American Chain & Cable Co., Inc., Pa**
Adirondack Steel Casting Co., NY
Aelco Foundries, Inc., Wis
Allegheny Ludlum Steel Corp., Pa
All-Metals Precision Casting Corp., NY
Alloy Engineering & Casting Co., Ill
**Alloy Precision Castings Co., Ohio**
**Alloy Steel Casting Co., Pa**
**American Brake Shoe Co., NY**
American Cast Iron Pipe Co., Ala
**American Steel Foundries, Ill**
**Apex Steel Corp., Ltd., Calif**
Arwood Corp., NY
Austenal Co., Div. of Howe Sound Co., NY
Baldwin-Lima-Hamilton Corp., Pa
**Beaver Valley Alloy Foundry Co., Pa**
Beloit Foundry Co., Ill
Bethlehem Steel Co., Pa
**Blaw-Knox Co., Pa**
**Bone Engineering Corp., Calif**
Bonney-Floyd Co., Ohio
**Brinkerhoff Brass & Bronze Works, Inc., NY**
**Calcrizing Co., Pa**
**Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich**
**Carondelet Foundry Co., Mo**
**Commercial Steel Casting Co., Ohio**
Copper Alloy Corp., NJ
**Crucible Steel Casting Co., Pa**
Curtiss-Wright Corp., Metals Processing Div., NY
Dodge Steel Co., Pa
**Donegal Steel Foundry Co., Pa**
Duraloy Co., Pa
**Duriron Co., Inc., Ohio**
**Electric Steel Foundry Co., Ore**
**Electro-Alloys Div., American Brake Shoe Co., Ohio**
**Empire Steel Castings, Inc., Pa**
Engineered Castings Div., American Brake Shoe Co., NY
**Fahralloy Co., Ill**
**Fort Pitt Steel Casting Div., Pittsburgh Steel Foundry Corp., Pa**
Frasse, Peter A. & Co., Inc., NY
**General Alloys Co., Mass**
**General Electric Co., Foundry Dept., NY**
General Electric Co., Metallurgical Products Dept., Mich
Goslin Birmingham Mfg. Co., Inc., Ala.
**Grede Foundries, Inc., Wis**
**Hanford Foundry Co., Calif**
**Hartford Electric Steel Corp., Conn**
Hica, Inc., La
**Hitchiner Mfg. Co., Inc., NH**
**Howard Foundry Co., Ill**
**Humphrey Castings, Inc., Calif**
**Illinois Precise Casting Co., Ill**
**Industrial Stainless Steels, Inc., Mass**
**Ingersoll-Rand Co., NJ**
**Janney Cylinder Co., Pa**
Johnson, A. & Co., Inc., NY
Jones & Laughlin Steel Corp., Strip Steel Div., Ohio (dd)
Kay-Brunner Steel Products, Inc., Calif
Kolcast Industries Div., Thompson Products, Inc., Ohio
LFM Mfg. Co., Inc., Sub. of Rockwell Mfg. Co., Kan
Lebanon Steel Foundry, Pa
Los Angeles Steel Casting Co., Calif
Manco Products, Inc., Mich
Massillon Steel Casting Co., Ohio
Michigan Steel Casting Co., Div. of Consolidated Foundries & Mfg. Corp., Mich
Midwest Precision Castings Co., Ohio
Minneapolis Electric Steel Castings Co., Minn.
Misco Precision Casting Co., Mich
National Malleable & Steel Castings Co., Ohio
National Precision Casting Corp., Div. of Beryllium Corp., Pa
National Supply Co., Pa
Ohio Steel Foundry Co., Ohio
Oklahoma Steel Castings Div., American Steel & Pump Corp., Okla.
Perfecto Cast, Calif
Picco, Inc., Calif
Pittsburgh Steel Foundry Corp., Pa
Precision Founders, Inc., Calif
Quaker Alloy Casting Co., Pa
Rockwell Engineering Co., Ill
Ross-Meehan Foundries, Tenn
Ryerson, Joseph T. & Son, Inc., Ill
St. Louis Steel Casting, Inc., Mo
Sandusky Foundry & Machine Co., Ohio
Sharpsville Steel Fabricators, Inc., Pa
Sivyer Steel Casting Co., Wis
Skookum Co., Inc., Ore
Sherwatt Equipment & Mfg. Co., Inc., NY (ff)
Stainless Foundry & Engineering, Inc., Wis
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa
Stanwood Corp., Ill
Star Heel Plate Co., Inc., NJ
Superior Foundry, Inc., Ohio
Symington-Gould Corp., NY
Texas Foundries, Inc., Tex
Texas Steel Co., Tex.
Thompson Products, Inc., Valve Div., Ohio
Union Iron Works, Wash
**U.S. Magnet & Alloy Corp., NJ** —Ad p 420
U.S. Pipe & Foundry Co., Ala
**Unicast Corp., Ohio** —Ad p 467
Uniworld Research Corp. of America, Ohio
Utility Steel Foundry, Calif
Vollrath Co., Contract Div., Wis
Wall Colmonoy Corp., Stainless Process Div., Mich
**West Steel Casting Co., Ohio**
Westinghouse Electric Corp., Materials Mfg. Dept., Pa
Wisconsin Centrifugal Foundry, Inc., Wis

## Steel, Low Alloy

Acme Tube, Inc., NJ (ee)
Acme-Newport Steel Co., Ky (z,cc,ee)
Advance Screw Products Co., Inc., Wis
Advance Stamping Co., Mich (dd)
Alan Wood Steel Co., Pa (z,cc,dd)
Alco Products, Inc., NY (q,aa)
**Allegheny Ludlum Steel Co., Pa** (o,q,w,z,bb,cc,dd,ee,ff)—Ad p 87
Alloy Metal Products, Inc., Iowa (o, q,w)
Alofs Mfg. Co., Mich (cc,dd,ff)
Amalgamated Steel Corp., Ohio (o, bb)
American Cast Iron Pipe Co., Ala (ee)
**American Steel & Wire Div., U.S. Steel Corp., Ohio** (o,dd)—Ad pp 90-91
Anchor Drawn Steel Co., Div. of Vanadium-Alloys Steel Co., Pa (bb, ff)
Arcos Corp., Pa (ff)
Aristoloy Steel Div., Copperweld Steel Co., Ohio (o,q)
Armco Steel Corp., Ohio (z,cc,dd)
Armco Steel Corp., Sheffield Div., Mo (o,q,w,z,bb,cc,ff)
Arrow Metal Products Corp., NJ (cc)
Atlantic Steel Co., Ga (o)
Austenal Co., Div. of Howe Sound Co.,
Babcock & Wilcox Co., Tubular Products Div., Pa (ee)
Bethlehem Steel Co., Pa (o,q,z,bb,cc, dd,ee,ff)
Biddle Screw Products Co., Ind (o,bb, ee)
Bliss & Laughlin, Inc., Ill (o)
Burkhardt Steel Co., Colo (o,z,cc,dd)
Byers, A.M. Co., Pa (o,q,w,z)
California Metal Enameling Co., Calif (cc)
Cannon-Muskegon Corp., Mich (w)
Carpenter Steel Co., Pa (o,q,w,bb,dd, ff)
Castle, A.M. & Co., Ill (o,q)
Colonial Steel Div., Vanadium-Alloys Steel Co., Pa (o,q,w,z,bb,cc,ff)
Columbia-Geneva Steel Div., U.S. Steel Corp., Calif (o,q,w,z,cc,dd,ee)
Connors Steel Div., H.K. Porter Co., Inc., Ala (o,q)
**Crucible Steel Co. of America, Pa** (o,q,w,z,bb,cc,dd,ee,ff)—Ad p 93
Crucible Steel Co. of America, Titanium & Vacuum Metals Product Div., Pa (o,q,w,bb,cc,dd)
Curtiss-Wright Corp., Metals Processing Div., NY (ee,ff)
Dixon Sintaloy, Inc., Conn (o)
Dudek & Bock Spring Mfg Co., Ill (dd,ff)
Eastern Rolling Mills, Inc., NY (cc,dd)
Empire-Reeves Steel Div., Universal-Cyclops Steel Corp., Pa (z,cc)
Enterprise Wheel & Car Corp., Va (z,cc)
Eynon-Dakin Co., Mich (ee)
Finkl, A. & Sons Co., Ill (w)
Frasse, Peter A. & Co., Inc., NY (o,z,bb,cc,dd,ee,ff)
Great Lakes Steel Corp., Div. of National Steel Corp., Mich (z,cc,dd)
Green River Steel Corp., Ky (o,q,w)
Hardy, Charles, Inc., N (aa)
Hayden Wire Works, Inc., Mass (o,bb, ff)
Haydon Corp., NY (ee)
Higbie Mfg. Co., Mich (ee)
**Hoeganaes Sponge Iron Corp., N J** (aa)—Ad p 462
Inland Steel Co., Ill (o,z,cc,dd)
Jones & Laughlin Steel Corp., Pa (o, q,z,bb,cc,dd,ee,ff)
Kaiser Steel Corp., Calif (o,q,w,z,bb, cc,dd)
Kelsey-Hayes Co., Mich (o,q,z,cc)
Keystone Drawn Steel Co., Pa (q)
Kinkead Industries, Inc., Ill (cc,dd)
Larson, Charles E. & Sons Inc., Ill (o)
La Salle Steel Co., Ill (aa)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

**Latrobe Steel Co., Pa** (o,q,w)—Ad p 95
LeTourneau, R.G., Inc., Tex (z)
Levinson Steel Co., Pa (cc)
Lincoln Steel Corp., Neb (cc)
Lukens Steel Co., Pa (w,z)
Lundquist Tool & Mfg. Co., Inc., Mass (cc,dd)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (o,dd,ee)
McInnes Steel Co., Pa (o)
Metallizing Co. of Los Angeles, Inc., Calif (ff)
Michigan Seamless Tube Co., Mich (ee)
Midvale-Heppenstall Co., Pa (w)
Murray, A.B. Co., Inc., NJ (ee)
National Tube Div., U.S. Steel Corp., Pa (ee)
**National-Standard Co., Mich** (ff)—Ad p 421
National-U.S. Radiator Corp., Plastic Metals Div., Pa (aa)
Norrich Plastics Corp., Screw Machine Products Div., NY (o,bb)
Northwestern Steel & Wire Co., Ill (o,q,w,z,bb,ff)
Ohio Seamless Tube Div., Copperweld Steel Co., Ohio (ee)
Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa (ff)
Pencoyd Steel & Forge Corp., Pa (o,q,w)
Peninsular Steel Co., Mich (o,q,z)
Pittsburgh Forgings Co., Mich (o,q)
Rathbone Corp., Mass (o,bb)
Reliance Div., Eaton Mfg. Co., Ohio (o,ff)
**Republic Steel Corp., Ohio** (o,q,w,z,bb,cc,dd,ee,ff)—Ad pp 82-83
Revere Copper & Brass, Inc., NY (ee)
Rome Mfg. Div., Revere Copper & Brass, Inc., NY (ee)
Ross-Meehan Foundries, Tenn (o)
Ryerson, Joseph T. & Son, Inc., Ill (o,z,bb,cc,dd)
St. Louis Steel Casting, Inc., Mo (n)
Sandusky Foundry & Machine Co., Ohio (ee)
**Sandvik Steel, Inc., NJ** (dd)—Ad p 83
Sawhill Tubular Products, Inc., Pa (ee)
Scudder, E.J. Foundry & Machine Co., NJ (bb,ee)
Service Steel Div., Van Pelt Corp., Mich (ee)
Sharon Steel Corp., Pa (q,w,z,cc,dd)
Sharpsville Steel Fabricators, Inc., Pa (o,z,bb,cc)
Simonds Saw & Steel Co., Mass (o,cc)
Smith-Moon Steel Co., Inc., Kan (o,z,cc)
Solar Steel Corp., Ohio (o,z)
**Stainless and Strip Div., Jones & Loughlin Steel Corp., Ohio** (dd)—Ad p 89
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa (q,w)
Star Heel Plate Co., Inc., NJ (ee,ff)
Sun Steel Co., Ill (o,q,z,bb,cc,dd)
Superior Drawn Steel Co., Pa (o,bb,ff)
Superior Tube Co., Pa (ee)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (o,q,w,z,cc,dd,ee)
Thomas Strip Div., Pittsburgh Steel Co., Pa (dd)
Thompson Wire Co., Mass (dd)
Timken Roller Bearing Co., Steel & Tube Div., Ohio (o,q,ee)
Tube Distributors Co., Inc., NY (ee)
Tube Reducing Corp., NJ (ee)
Uddeholm Co. of America, Inc., NY (bb)
Ullmann, Inc., Wis (o,ee)
Union Iron Works, Wash (cc)
Union Steel Corp., NJ (dd)
United Screw & Bolt Corp., Ill (bb,cc,dd,ff)
**U. S. Steel Corp., Pa** (o,q,w,z,cc,dd)—Ad pp 84-85
U.S. Steel Supply Div., U.S. Steel Corp., Ill (o,z,cc,dd,ee)
Vanadium-Alloys Steel Co., Pa (o,q,w,z,aa,bb,cc,ff)
Washburn Wire Co., Phillipsdale Div., RI (q,bb,dd)
Weirton Steel Co., Div. of National Steel Corp., W.Va (cc)
Western Automatic Machine Screw Co., Div. of Standard Screw Co., Ohio (o)
Wheelock, Lovejoy & Co., Inc., Mass (o,q,bb)
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY (w,z)
Wilder Mfg. Co., Inc., Calif (o,z,cc)
Wyckoff Steel Co., Pa (o,z)
Youngstown Sheet and Tube Co., Ohio (o,z,cc,dd,ee)

## Steel, Low Alloy —Castings

Acco Steel Casting Div., American Chain & Cable Co., Inc., Pa
Adirondack Steel Casting Co., NY
Advance Foundry Co., Ohio
Allied Steel Castings Co., Ill
All-Metals Precision Casting Corp., NY
Alloy Cast Steel Co., Ohio
Alloy Precision Castings Co., Ohio
Alloy Steel & Metals Co., Calif
American Cast Iron Pipe Co., Ala
American Manganese Steel Div., American Brake Shoe Co., Ill
American Steel Foundries, Ill
Arwood Corp., NY
Atlantic Foundry Co., Ohio
Atlantic Steel Castings Co., Pa
Austenal Co., Div. of Howe Sound Co., NY
Auto Specialties Mfg. Co., Mich
Baldwin-Lima-Hamilton Corp., Pa
Bay City Electric Steel Casting Co., Mich
Beaver Valley Alloy Foundry Co., Pa
Bethlehem Steel Co., Pa
Birdsboro Steel Foundry & Machine Co., Pa
Blaw-Knox Co., Pa
Bone Engineering Corp., Calif
Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich
Carondelet Foundry Co., Mo
Commercial Steel Casting Co., Ohio
Crucible Steel Casting Co., Pa
Dayton Steel Foundry Co., Ohio
Dodge Steel Co., Pa
Electric Steel Castings Co., Ind
Electric Steel Foundry Co., Ore
Electrocast Steel Foundry Co., Ill
Empire Foundry Co., Inc., Calif
Empire Steel Castings, Inc., Pa
Federal Steel Products Corp., Tex
General Electric Co., Foundry Dept., NY
General Steel Castings Corp., Ill
Glover Machine Works, Ga
Goslin Birmingham Mfg. Co., Inc., Ala
Grafton Foundry Co., Wis
Grede Foundries, Inc., Wis
Gunite Foundries Corp., Ill
Hartford Electric Steel Corp., Conn
Hica, Inc., La
Hitchiner Mfg. Co., Inc., NH
Howard Foundry Co., Ill
Hughes Tool Co., Tex
Humphrey Castings, Inc., Calif
Illinois Precise Casting Co., Ill
Kay-Brunner Steel Products, Inc., Calif
Kolcast Industries Div., Thompson Products, Inc., Ohio
Lebanon Steel Foundry, Pa
Lectromelt Casting Div., Akron Standard Mold Co., Ohio
Los Angeles Steel Casting Co., Calif
Mackintosh-Hemphill Div., E.W. Bliss Co., Pa
Massillon Steel Casting Co., Ohio
Mercast Mfg. Corp., Calif
Metropolitan Iron Foundry, NY
Midwest Precision Castings Co., Ohio
Minneapolis Electric Steel Castings Co., Minn
Misco Precision Casting Co., Mich
Missouri Steel Castings Co., Mo
Monroe Steel Castings Co., Mich
National Malleable & Steel Castings Co., Ohio
National Precision Casting Corp., Div. of Beryllium Corp., Pa
National Supply Co., Pa
Ohio Steel Foundry Co., Ohio
Oklahoma Steel Castings Div., American Steel & Pump Corp., Okla
Olympic Steel Works, Wash
Omaha Steel Works, Neb
Pelton Steel Casting Co., Wis
Picco, Inc., Calif
Pittsburgh Steel Foundry Corp., Pa
Posey Iron Works Inc., Pa
Pratt & Letchworth Div., Dayton Malleable Iron Co., Inc., NY
Precision Founders, Inc., Calif
Quaker Alloy Casting Co., Pa
Quality Electric Steel Castings, Inc., Tex
Racine Steel Castings Co., Belle City Malleable Div., Wis
Reliance Steel Castings Co., Pa
Rockwell Engineering Co., Ill
Ross-Meehan Foundries, Tenn
Ryerson, Joseph T. & Son, Inc., Ill
St. Louis Steel Casting, Inc., Mo
Sandusky Foundry & Machine Co., Ohio
Sawbrook Steel Castings Co., Ohio
Scudder, E.J. Foundry & Machine Co., NJ
Sharpsville Steel Fabricators, Inc., Pa
Sivyer Steel Casting Co., Wis
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa
Star Heel Plate Co., Inc., NJ
Strong Steel Foundry Co., NY
Superior Foundry, Inc., Ohio
Swedish Crucible Steel Co., Mich
Taylor-Wharton Co., Div. of Harsco Corp., NJ
Texas Foundries, Inc., Tex
Texas Steel Co., Tex
Union Iron Works, Wash
Union Spring & Mfg. Co., Pa
**Unitcast Corp., Ohio** —Ad p 467
United Shoe Machinery Corp., Mass
U. S. Magnet & Alloy Corp., NJ
U.S. Pipe & Foundry Co., Ala
Utility Steel Foundry, Calif
Valley Steel Casting Co., Mich
Vulcan Iron Works, Pa
Washington Iron Works, Wash
West Steel Casting Co., Ohio
Westinghouse Electric Corp., Materials Mfg. Dept., Pa
Westlectric Castings, Inc., Calif
Worthington Corp., NJ

## Steel, Specialty

(electrical, magnet, nitriding, etc.)

Acme-Newport Steel Co., Ky (cc)
Adirondack Steel Casting Co., NY
**Allegheny Ludlum Steel Corp., Pa** (o,q,z,bb,ff)—Ad p 87
Alloy Metal Powders, Inc., NY (aa)
Amalgamated Steel Corp., Ohio (o,bb)
American Silver Co., Inc., NY (v, bb, ee,ff)
Armco Steel Corp., Ohio (o,q,v,z,bb,cc,dd,ee,ff)
Arnold Engineering Co., Ill (dd)
Atlantic Steel Co., Ga (o)
Austenal Co., Div. of Howe Sound Co., NY (w)
Bethlehem Steel Co., Pa (o,q)
Biddle Screw Products Co., Ind (o,bb,ee)
Brush Beryllium Co., Ohio (v,dd)
Byers, A. M. Co., Pa (q,z)
Cannon-Muskegon Corp., Mich (w,ff)
Carpenter Steel Co., Pa (o,q,w,bb,dd,ee)
Chicago Development Corp., Md (aa)
Colonial Steel Div., Vanadium-Alloys Steel Co., Pa (o,q,w,z,bb,cc,ff)
Crucible Steel Co. of America, Pa (o,q,w,z,bb,cc)
Crucible Steel Co. of America, Titanium & Vacuum Metal Products Div., Pa (o,q,z,bb,cc,dd,ff)
Edgcomb Steel & Aluminum Corp., NJ (o,cc,dd)
Firth Sterling Inc., Pa (o,q,w,bb,ff)
Green River Steel Corp., Ky (o,q,w)
Hamilton Watch Co., Precision Metals Div., Pa (v,cc,dd,ff)
**Hoeganaes Sponge Iron Corp., NJ** (aa)—Ad p 462
Inland Steel Co., Ill (cc)
Johnston & Funk Titanium Corp., Ohio (w,bb,ff)
Jones & Laughlin Steel Corp., Pa (o,z,cc)
Kassel Export Co., Inc., NJ (dd,ff)
Kelsey-Hayes Co., Metals Div., NY (o,q,w,z,bb,cc,dd,ff)
Larson Tool & Stamping Co., Mass (o)
La Salle Steel Co., Mo (o)
Latrobe Steel Co., Pa (o,q,w)
Lukens Steel Co., Pa (w,z)
Manganese Steel Forge Co., Pa (o,z,bb,cc,dd,ff)
McInnes Steel Co., Pa (o)
Midvale-Heppenstall Co., Pa (q,w)
National Supply Co., Pa (o,q,w)
National-Standard Co., Mich (dd,ff)
Reactive Metals, Inc., Ohio (cc)
Republic Steel Corp., Ohio (o,q,w,z,bb,cc,dd,ee)
Ryerson, Joseph T. & Son, Inc., Ill (z)
**Sandvik Steel, Inc., NJ** (o,bb,dd)—Ad p 83
Sharon Steel Corp., Pa (cc)
Simonds Saw and Steel Co., Mass (cc,dd)
Stauffer-Temescal Co., Calif (o,q,w,z,bb,cc,dd,ff)
Stulz-Sickles Co., NJ (o,q,z,bb)
Superior Steel Corp., Pa (dd)
Sylvania Electric Products Inc., Parts Div., Pa (ff)
Timken Roller Bearing Co., Steel & Tube Div., Ohio (o,q,ee)
Ullmann, Inc., Wis (o,ee)
Universal-Cyclops Steel Corp., Pa (o,q,z,bb,cc,dd,ff)
Vanadium-Alloys Steel Co., Pa (o,q,w,z,aa,bb,cc,ff)
Vascoloy-Ramet Corp., Ill
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,v,w,z,bb,cc,dd,ee)

## Steel, Specialty —Castings

Acco Steel Casting Div., American Chain & Cable Co., Inc., Pa
Allegheny Ludlum Steel Corp., Pa
All-Metals Precision Casting Corp., NY
Alloy Precision Castings Co., Ohio
American Brake Shoe Co., NY
American Steel Foundries, Ill
Arwood Corp., NY
Austenal Co., Div. of Howe Sound Co., NY
Baldwin-Lima-Hamilton Corp., Pa
Beaver Valley Alloy Foundry Co., Pa
Bethlehem Steel Co., Pa
Blaw-Knox Co., Pa
Bone Engineering Corp., Calif
Campbell, Wyant & Cannon Foundry Co., Div. of Textron, Inc., Mich
Carondelet Foundry Co., Mo
Crobalt, Inc., Mich
Crucible Steel Casting Co., Pa
Curtiss-Wright Corp., Metals Processing Div., NY
Electric Steel Foundry Co., Ore
General Electric Co., Foundry Dept., NY
General Steel Castings Corp., Ill
Grede Foundries, Inc., Wis
Hica, Inc., La
Howard Foundry Co., Ill.

Humphrey Castings, Inc., Calif
Janney Cylinder Co., Pa
Johnston & Funk Titanium Corp., Ohio
Kay-Brunner Steel Products, Inc., Calif
Kolcast Industries, Div., Thompson Products, Inc., Ohio
LFM Mfg. Co., Sub. of Rockwell Mfg. Co., Kan
Lebanon Steel Foundry, Pa
Los Angeles Steel Casting Co., Calif
Manco Products, Inc., Mich
Mercast Mfg. Corp., Calif
Midwest Precision Castings Co., Ohio
Misco Precision Casting Co., Mich
Missouri Steel Castings Co., Mo
National Precision Casting Corp., Div. of Beryllium Corp., Pa
National Supply Co., Pa
Ohio Steel Foundry Co., Ohio
Overmyer Mould Co., Inc., Ind
Perfecto Cast, Calif
Picco, Inc., Calif
Precision Founders, Inc., Calif
Quaker Alloy Casting Co., Pa
Quality Electric Steel Castings, Inc., Tex
Rockwell Engineering Co., Ill
Ryerson, Joseph T. & Son, Inc., Ill
Standard Steel Works Div., Baldwin-Lima-Hamilton Corp., Pa
Star Heel Plate Co., Inc., NJ
Stulz-Sickles Co., NJ
Swedish Crucible Steel Co., Mich
Taylor-Wharton Co., Div. of Harsco Corp., NJ
Texas Foundries, Inc., Tex
United Shoe Machinery Corp., Mass
U.S. Magnet & Alloy Corp., NJ
U.S. Pipe & Foundry Co., Ala
Uniworld Research Corp. of America, Ohio
Utility Steel Foundry, Calif
Vanadium-Alloys Steel Co., Pa
Wall Colmonoy Corp., Stainless Process Div., Mich
Washington Iron Works, Wash
West Steel Casting Co., Ohio
Westinghouse Electric Corp., Materials Mfg. Dept., Pa
Wisconsin Centrifugal Foundry, Inc., Wis

## Steel, Tool and Die

Able Tool & Engineering Co., Ill (z)
Advance Stamping Co., Mich (o,z,bb)
Albraco Metals Corp., NY (o,q,bb)
**Allegheny Ludlum Steel Corp., Pa** (o,q,z,bb,ff)—Ad p 87
Alofs Mfg. Co., Mich (o,z,bb)
Amalgamated Steel Corp., Ohio (o,bb)
American Brake Shoe Co., NY (aa)
Anchor Drawn Steel Co., Div. of Vanadium Alloys Steel Co., Pa (bb,ff)
Austenal Co., Div. of Howe Sound Co., NY (w)
Bethlehem Steel Co., Pa (o,q)
Biddle Screw Products Co., Ind (o,bb,ee)
Braeburn Alloy Steel Corp., Pa (o,q)
Cannon-Muskegon Corp., Mich (w)
Carpenter Steel Co., Pa (o,q,w,bb,dd,ff)
Columbia Tool Steel Co., Ill (o,q,w,bb)
**Crucible Steel Co. of America, Pa** (o,q,w,z,bb,cc,dd,ff)—Ad p 93
Crucible Steel Co. of America, Titanium & Vacuum Metal Products Div., Pa (o,q,w,z,bb,cc,dd,ff)
Delaware Tool Steel Corp., Del (o)
Edgcomb Steel & Aluminum Corp., NJ (o,q,w,bb)
Finkl, A. & Sons Co., Ill (w)
Firth Sterling, Inc., Pa (o,q,w,bb,ff)
Forg, Peter Mfg. Co., Mass (cc)
Frasse, Peter A. & Co., Inc., NY (o)
Green River Steel Corp., Ky (o,q,w)
Hardy, Charles, Inc., NY (aa)
Hayden Wire Works, Inc., Mass (o,z,bb)
Heller Tool Co., Ohio (o)
Inshield Die & Stamping Co., Ohio (o)
Jessup Steel Co., Pa (o,q,z,cc,dd)
Jones & Laughlin Steel Corp., Pa (o,z,bb)
Kinkead Industries, Inc., Ill (o,z,bb)
Larson, Charles E. & Sons, Inc., Ill (o)
**Latrobe Steel Co., Pa** (o,q,w)—Ad p 95
Lundquist Tool & Mfg. Co., Inc., Mass (o,z,bb)
Midvale-Heppenstall Co., Pa (q,w)
Morrisville Foundry Co., Inc., Vt (bb)
National Supply Co., Pa (o,q,w)
Norrich Plastics Corp., Screw Machine Products Div., NY (o,bb,ee)
Norwalk Powdered Metals, Inc., Conn (aa)
Ormond Mfg., Co., Inc., NJ (cc,dd,ff)
Pencoyd Steel & Forge Corp., Pa (o,q,w)
Peninsular Steel Co., Mich (o,q,z)
Pittsburgh Tool Steel Wire Co., Pa (o,bb)
Republic Steel Corp., Ohio (o,q)
Ross-Meehan Foundries, Tenn (o)
Ryerson, Joseph T. & Son, Inc., Ill (o,bb,cc)
Simonds Saw & Steel Co., Mass (o,cc)
Solar Steel Corp., Ohio (o,bb)
Superior Tube Co., Pa (ee)
Timken Roller Bearing Co., Steel & Tube Div., Ohio (o,q)
Uddeholm Co. of America, Inc., NY (o,q) q,z,bb,cc,dd,ff)
Universal-Cyclops Steel Corp., Pa (o,q,w,z,aa,bb,cc,ff)
Vanadium-Alloys Steel Co., Pa (o,q,w,z,aa,bb,cc,ff)
Vulcan-Kidd Steel Div., H.K. Porter Co. Inc., Pa (o,q,w,bb,ff)
**Waimet Alloys Co., Mich** (w)—Ad p 82
Wheelock, Lovejoy & Co., Inc., Mass (o,q,bb)
Wilder Mfg. Co., Inc., Calif (o,bb)
Ziv Steel & Wire Co., Ill (o,q)

## Steel, Tool and Die —Castings

Albraco Metals Corp., NY
Allegheny Ludlum Steel Corp., Pa
All-Metals Precision Casting Corp., NY
Alloy Precision Casting Co., Ohio
American Foundry & Machine Div., Eimco Corp., Utah
Apex Steel Corp., Ltd., Calif
Arwood Corp., NY
Atlantic Steel Castings Co., Pa
Austenal Co., Div of Howe Sound Co., NY
Bay City Electric Steel Casting Co., Mich
Beaver Valley Alloy Foundry Co., Pa
Bone Engineering Corp., Calif
Carondelet Foundry Co., Mo
Crucible Steel Co. of America, Pa
Crucible Steel Casting Co., Pa
Curtiss-Wright Corp., Metals Processing Div., NY
Empire Steel Castings, Inc., Pa
General Electric Co., Foundry Dept., NY
Hica, Inc., La
Hitchiner Mfg. Co., Inc., NH
Howard Foundry Co., Ill
Illinois Precise Casting Co., Ill
Kolcast Industries Div., Thompson Products Inc., Ohio
LFM Mfg. Co., Sub. of Rockwell Mfg. Co., Kan
Lebanon Steel Foundry, Pa
Manco Products, Inc., Mich
Midwest Precision Castings Co., Ohio
Misco Precision Casting Co., Mich
Missouri Steel Castings Co., Mo
National Precision Casting Corp., Div. of Beryllium Corp., Pa
National Supply Co., Pa
Precision Founders, Inc., Calif
Quaker Alloy Casting Co., Pa
Rockwell Engineering Co., Ill
Ross-Meehan Foundries, Tenn
Star Heel Plate Co., Inc., NJ
Swedish Crucible Steel Co., Mich
Vanadium-Alloys Steel Co., Pa
Westinghouse Electric Corp., Materials Mfg. Dept., Pa

## Strip

(see specific material)

## Strippable Coatings

(see Organic Coatings)

## Styrene

(see Polystyrene)

## Styrene-Butadiene Rubber

Adhesive Products Corp., NY (x)
American Hard Rubber Co., Div. of Amerace Corp., NJ (bb,cc,dd,ee)
American Synthetic Rubber Corp., NY (p)
Anderson Assoc., Inc., Ohio (y)
Auburn Plastics, Inc., NY (bb,cc,dd)
Auburn Rubber Co., Inc., Ind (cc)
Automotive Rubber Co., Inc., Mich (cc,dd)
Belko Corp., Md (y)
Bond International, Inc., Mich (y,ee)
Borden Co., Borden Chemical Div., NY (p)
Capac Mfg. Corp., Mich (y,cc)
Castle Rubber Co., Pa (y,bb,cc,dd,ee)
Chicago-Allis Mfg. Corp., Ill (p)
Continental Rubber Works, Pa (bb,cc,dd,ee)
Copolymer Rubber and Chemical Corp., La (p)
Dayton Rubber Co., Ohio (y,bb,cc,dd,ee)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (y,ee)
Dyna-Therm Chemical Corp., Calif (p)
Electrofilm, Inc., Calif (t)
Faultless Rubber Co., Ohio (u,y,bb,ee)
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (u,y,cc,ee)
Firestone Tire & Rubber Co., Ohio (p)
Garlock Packing Co., NY (y,bb,cc,dd,ee)
Geauga Industries Co., Ohio (y,bb,dd)
General Tire & Rubber Co., Chemical Div., Ohio (p)
Goodrich, B.F. Chemical Co., Ohio (p,cc)
Goodrich-Gulf Chemicals Inc., Ohio (p)
Goodyear Tire & Rubber Co., Chemical Div., Ohio (p)
**Goshen Rubber Co., Inc., Ind** (y)—Ad p 438
Heresite & Chemical Co., Wis (p)
Hewitt-Robins, Inc., Conn (cc,ee)
Home Rubber Co., NJ (y,bb,cc,dd)
Koppers Co., Inc., Pa (p)
Maloney, F.H. Co., Tex (y)
Marbon Chemical Div., Borg-Warner Corp., Ind (p,u,x,y)
Martin Rubber Co., Inc., NJ (y,dd,ee)
Mid-States Rubber Products, Inc., Ind (y)
Naugatuck Chemical Div., U.S. Rubber Co., Conn (p,u,x,y)
Paeco Rubber Co., Inc., Ohio (y,dd,ee)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
Parker, Stearns & Co., Inc., NY (cc,dd)
Phillips Chemical Co., Okla (p)
Polymer Chemical Co., Ohio (x)
Republic Rubber Div., Lee Rubber & Tire Corp., Ohio (p,y,cc,dd,ee)
Roberts Toledo Rubber Co., Ohio (ee)
Roth Rubber Co., Ill (y,cc)
Rubatex Div., Great American Industries Inc., Va (u)
Rubber Corp. of America, NY (m)
Shell Chemical Co., NY (p)
Sheller Mfg. Corp., Mich (u)
Southern Plastics Co., SC (bb,cc,dd,ee)
Stockwell Rubber Co., Inc., Pa (y,bb,cc,dd)
Technical Specialties Co., NY (dd)
Texas-U.S. Chemical Co., Tex (p)
**Toyad Corp., Pa** (u)—Ad p 260
Trostel, Albert Packing, Ltd., Wis (y)
United Rubber & Chemical Co., Tex (p)
U.S. Rubber Co., NY (p)
**U.S. Rubber Co., Kem-Blo Dept., Conn** (u)—Ad p 250
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (p,y,cc)
Vulcanized Rubber & Plastics Co., Pa (y)

### KEY

**MATERIALS**

a—Aluminum and its alloys
b—Copper and its alloys
c—Iron and its alloys (except steel)
d—Lead and its alloys
e—Magnesium and its alloys
f—Nickel and its alloys
g—Steels
h—Titanium and its alloys
j—Zinc and its alloys
k—Thermoplastics
l—Thermosetting plastics
m—Elastomers

**BASIC FORMS**

n—Anodes
o—Bar
p—Base resins, polymers or gums
q—Billets
r—Custom formed parts (incl. specialties)
s—Fibers
t—Film
u—Foams (component materials or products)
v—Foil
w—Ingot
x—Laminating, casting resins
y—Molding compounds
z—Plate
aa—Powder
bb—Rod
cc—Sheet
dd—Strip
ee—Tubing
ff—Wire

Western Felt Works, Ill (y,cc,dd,ee)
**Westlake Plastics Co., Pa (t,bb,cc, dd)**
Williams-Bowman Rubber Co., Ill (y, bb,cc)

## Superalloys

(see Nickel; Cobalt; Chromium)

## Synthetic Fibers

(see specific polymer)

## Tantalum and its Alloys

**Alpha Metals, Inc., NJ (v,cc,dd)**
**American Silver Co., NY (v,dd,ee,ff)**
Belmont Smelting & Refining Works, Inc., NY (aa)
Bishop, J. & Co. Platinum Works, Pa (ee)
Bridgeport Brass Co., Conn (ee)
Damascus Tube Co., Pa (ee)
**Fansteel Metallurgical Corp., Ill**
(n,o,q,v,w,z,aa,bb,cc,dd,ee,ff) — Ad p 174
Firth Sterling Inc., Pa (q,aa)
**Foote Mineral Co., Pa (aa)**
**Hamilton Watch Co., Precision Metals Div., Pa (v,dd)**
**Hardy, Charles, Inc., NY (aa)**
Harvey Aluminum, Calif (o,bb)
**Haynes Stellite Co., Div. of Union Carbide Corp.,** Ind (o,bb,cc,dd,ee,ff)
Hoskins Mfg. Co., Mich (ff)
**Johnston & Funk Titanium Corp., Ohio (bb,ff)**
**Kawecki Chemical Co., NY (n,o,q,v, w,z,aa,bb,cc,dd,ee,ff)**
**Kennametal, Inc., Pa**
(o,v,aa,dd,ff)—Ad p 306
**Makepeace, D.E. Div., Engelhard Industries,** Inc., Mass (dd)
**Mallory-Schwarzkopf Metals, Inc., NY (o,v,w,z,bb,cc,dd,ee,ff)**
**National Research Corp., Mass (v, w,aa,bb,cc,ee,ff)**
Nuclear Metals, Inc., Mass (w,bb,dd, ee)
**Oregon Metallurgical Corp., Ore (w)**
Rodney Metals, Inc., Mass (v,dd)
**Shieldalloy Corp., NJ (aa)**
Stauffer-Temescal Co., Calif (o,q,v,w, z,bb,cc,dd,ee,ff)
**Superior Tube Co., Pa**
(ee)—Ad pp 414-415
Texas Instruments, Inc., Metals & Controls Div., Mass (v,dd,ff)
**Union Carbide Metals Co., Div. of Union Carbide Corp., NY**
(w,aa)—Ad p 181
Universal Cyclops Steel Corp., Pa (o, q,z,cc)
**Wah Chang Corp., NY**
(v,aa,bb,dd,ff)—Ad p 164
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,v,w,z,bb, cc,dd,ee)

## Tapes, Adhesive

**American Tape Co., Mich**
Armstrong Cork Co., Pa
Avery Label Co., Decorative Products Div., Ohio
**Angier Adhesives Div., Interchemical Corp., Mass**
Atlantic Bag Co., NY
**Beck, I. & Sons, Inc., NY**
**Coating Products, Inc., NJ**
—Ad p 359
**Connecticut Hard Rubber Co., Conn**
**Cycleweld Div., Chrysler Corp., Mich**
Durable Rubber Products Co., Ill
**Dutch Brand Div., Johns-Manville Corp., Ill**
**Electro Technical Div., Sun Chemical Corp., NJ**
**Enflo Corp., NJ**
**Foamade Industries, Mich**
Foss Mfg. Co., Id
**Hampton Mfg. Co., NY**
**Hiller Aircraft Corp., Adhesive Engineering Div., Calif**
**Insulation Mfrs. Corp., Ill**
**Interchemical Corp., NY**
Interchemical Corp., Finishes Div., NJ
**Johns-Manville Corp., NY**
**Kinkead Industries, Inc., Ill**
**Lundquist Tool & Mfg. Co., Inc., Mass**
**Magnesium Co. of America, Ind**
**Moxness Products, Inc., Wis**
—Ad p 460
**Mystik Adhesive Products, Inc., Ill**
Narmco Industries, Inc., Narmco Materials Div., Calif
**Nicolet Industries, Inc., NY**
Permacel, NJ
Presstite Div., American-Marietta Co., Mo
**Respro Div., General Tire & Rubber Co., RI**
Reynolds Aluminum Supply Co., Ga
**Rubber & Plastics Compound Co., Inc., NY**
**Superior Plastics, Inc., Ill**
**Technical Tape Corp., NY**

## Teflon

(see Fluorocarbons)

## Terne Plate

(see Precoated Metals)

## Tetrafluoroethylene

(see Fluorocarbon)

## Tin and Its Alloys

African Metals Corp., NY (w)
Allied Research Products, Inc., Md (n)
**Alpha Metals, Inc., NJ (n,o,q,v,w,aa, bb,cc,dd)**
**American Metal Climax, Inc., NY (w,aa)**
**American Smelting & Refining Co., NY (n,o,w)**
Anchor Metal Co., Inc., NY (w,aa)
Arcos Corp., Pa (ff)
Belmont Smelting & Refining Works, Inc., NY (n,o,v,w,aa,cc,dd,ff)
**Caspers Tin Plate Co., Ill (cc,dd)**
**Cerro de Pasco Sales Corp., NY**
(w)—Ad p 178
**Crown Metal Co., Wis (n,ee,ff)**
**Division Lead Co., Ill (o,v,w,cc,dd,ee, ff)**
**Dixon Sintaloy, Inc., Conn (o)**
**Empire Metal Co., NY (n,o,q,w,bb,ff)**
**Farrelloy Co., Pa (aa,ff)**
**Glidden Co., Chemical Divs., Metals Dept., Ind**
(aa)—Ad p 429
**Greenback Industries, Inc., Mich (aa)**
**Hardy, Charles, Inc., NY (aa)**
**Harshaw Chemical Co., Ohio (n)**
**Hayden Wire Works, Inc., Mass (ff)**
**Hi-Grade Alloy Corp., Ill (n,o,v,w,ee)**
**Hodgson Foundry Co., Ill (n)**
Indium Corp. of America, NY (dd,ff)
Johnston Foil Div., Standard Packaging Corp., Mo (v,cc)
**Korhumel Steel and Aluminum Co., Ill (z,dd)**
**McGean Chemical Co., Ohio (n,o,aa)**
**Metal & Thermit Corp., NJ (n,w,aa)**
Metallizing Engineering Co., Inc., NY (ff)
**Metallizing Co. of Los Angeles, Inc., Calif (ff)**
**Metals Disintegrating Co., Inc., NJ**
(aa)—Ad p 456
**Modern Plating Corp., Ill (n)**
**National Lead Co., NY (n,o,q,w,z,aa, bb,cc,dd,ee)**
**Nesor Alloy Products Co., NJ (ff)**
Norwalk Powdered Metals, Inc., Conn (aa)
**Pittsburgh Smelting & Refining Co., Pa (o,w)**
Presswork, Inc., Mich (cc)
**Republic Metals Co., Inc., NY (n,o, v,w,cc,ee,ff)**
Revere Copper & Brass, Inc., NY (v)
**Revere Copper & Brass, Inc., Foil Div., NY (v)**
**River Smelting & Refining Co., Ohio (o)**
**Rotometals, Calif (o,v,w,aa)**
**Sall, George Metals Co., Inc., Pa (w)**
Sherwatt Equipment & Mfg. Co., Inc., NY (ff)
**Stevens, Frederic B., Inc., Mich (n)**
**Udylite Corp., Mich (n)**
United Refining & Smelting Co., Ill (n,o,q,w,z,bb,cc,dd,ff)

## Tinplate

(see Precoated Metals)

## Titanium and Its Alloys

**Alpha Metals, Inc., NJ (v)**
American Silver Co., NY (v,dd,ee,ff)
Belmont Smelting & Refining Works, Inc., NY (aa)
Bishop, J. & Co. Platinum Works, Pa (ee)
Bridgeport Brass Co., Conn (ee)
**Central Fabricators, Inc., Ohio (z,bb, cc,ee)**
Chicago Development Corp., Md (o,v,z, aa,bb,cc,dd,ff)
**Crucible Steel Co. of America, Pa**
(o,q,w,z,bb,cc,dd,ee,ff)—Ad p 93
**Crucible Steel Co. of America, Titanium & Vacuum Metal Products Div., Pa (o,q,v,z,bb,cc,dd,ee,ff)**
Damascus Tube Co., Pa (ee)
Driver-Harris Co., NJ (v,dd)
du Pont de Nemours, E. I. & Co., Inc., Del (w)
**Electric Steel Foundry Co., Ore (o, q,w,bb,ee)**
**Foote Mineral Co., Pa (o,bb)**
General Electric Co., Metallurgical Products Dept., Mich (q,w,aa,bb,cc, dd)
Hardy, Charles, Inc., NY (aa)
Harvey Aluminum, Calif (o,q,w,bb,ee)
Hexcel Products, Inc., Calif (v)
Hoskins Mfg. Co., Mich (ff)
**Johnston & Funk Titanium Corp., Ohio (bb,ff)**
Kennametal, Inc., Pa (aa,bb,ee)
**King Laboratories, Inc., NY (w,aa)**
**Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (o,dd)**
**Mallory, P.R. & Co., Inc., Ind (o,q, bb,cc,dd,ee)**
Metal Forming Corp. Div., Vanadium-Alloys Steel Co., Ind (ee)
**Metal Hydrides, Inc., Mass (aa)**
**Metal & Thermit Corp., NJ (w)**
Metals Disintegrating Co., Inc., NJ (aa)
**Michigan Seamless Tube Co., Mich (ee)**
**National Lead Co., NY (o,q,w,z,bb,cc, dd,ee,ff)**
**Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)**
Nuclear Metals, Inc., Mass (w,bb,dd, ee)
Oregon Metallurgical Corp., Ore (w,ee)
**Pioneer Aluminum, Inc., Calif (z)**
Reactive Metals, Inc., Ohio (o,q,w,z, bb,cc,dd,ee,ff)
**Republic Steel Corp., Ohio**
(o,q,v,w,z,aa,cc,dd,ee,ff) — Ad pp 84-85
Rigidized Metals Corp., NY (cc,dd)
**Superior Steel Corp., Pa (dd)**
Superior Tube Co., Pa (ee)
**Techalloy Co., Inc., Pa (dd,ff)**
Texas Instruments, Inc., Metals & Controls Div., Mass (v,cc,dd)
**Titanium Metals Corp. of America, NY**
(o,q,v,z,aa,bb,cc,dd,ee,ff)
**Trent Tube Co., Sub. of Crucible Steel Co. of America, Pa (ee)**
**Tube Distributors Co., Inc., NY (ee)**
**Tube Reducing Corp., NJ (ee)**
**Ullmann, Inc., Wis (o,ee)**
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
**United International Research, Inc., NY (aa)**
Vanadium Corp. of America, NY (w)
**Worcester Wire Works Div., National-Standard Co., Mass (ff)**
**Youngstown Welding & Engineering Co., Ohio (ee)**

## Tool Steels

(see Steel)

## Transfer Moldings

(see Moldings)

## Trifluorochloroethylene

(see Fluorocarbon)

## Tubing, Pipe

**Ace Plastic Co., NY (k,l)**
Acme Tube, Inc., NJ (a,b)
**Acme-Newport Steel Co., Ky (g)**
Aerojet-General Corp., Structural Materials Div., Calif (l)
**Albert Pipe Supply Co., Inc., NY (a,g,k)**
**Albright Son & Co., Pa (g)**
Allegheny Ludlum Steel Corp., Pa (g)
**Allied Tube Corp., Pa (a,g)**
Aluminum Co. of America, Pa (a,e)
**Amco Plastic Pipe Co., Calif (k)**
**American Agile Corp., Ohio (k)**
American Brass Co., Sub. of Anaconda Co., NY (b)
**American Cast Iron Pipe Co., Ala**
(c,f,g)—Ad p 410
American Metal Products Co., Mich (a,g)
**American Molding Co., Calif (k)**
**American Nickel Alloy Mfg. Corp., NY (f)**
**American Pipe & Construction Co., Ore (g)**
**American Plastics Corp., NY (k)**
**American Reed Co., Inc., Mass (a)**
**American Smelting & Refining Co., NY (d)**
American Silver Co., NY (b,f,g,h)
**Ampco Metal, Inc., Wis (b)**
Anaconda Metal Hose Div., American Brass Co., Sub. of Anaconda Co., Conn (a,b,g,k)
Anchor Plastics Corp., NY (k)
**Apex Reinforced Plastics Div., White Sewing Machine Corp., Ohio (l)**
**Armco Steel Corp., Ohio (g)**
**Arvin Industries, Inc., Ohio (a,g)**
**Atlantic India Rubber Works, Inc., Ill (m)**
**Atlantic Steel Co., Ga (a,g)**
**Atlas Mineral Products Co., Pa (k)**
**Auburn Plastic Engineering, Ill (k)**
Avins Industrial Products Corp., NY (c)
**Avon Tube Div., Higbie Mfg. Co., Mich (g)**
Babcock & Wilcox Co., Tubular Products Div., Pa (g)

Badger Aluminum Extrusions, NY (a)
Barium Steel Corp., NY (g)
Benada Aluminum Products Co., Ohio (a)
Bethlehem Steel Co., Pa (g)
Bishop, J. & Co. Platinum Works, Pa (f,g)
Bohn Aluminum & Brass Corp., Mich (a)
Bond International, Inc., Mich (y,ee)
Borden Co., Borden Chemical Div., NY (k)
Brainard Steel Div., Sharon Steel Corp., Ohio (g)
**Bridgeport Brass Co., Conn** (a,b,f,h)—Ad p 176
Brinkerhoff Brass & Bronze Works, Inc., NY (a,b,f,g)
Broadway Mfg. Co., Wis (c,f,g)
Bundy Tubing Co., Mich (f,g)
Bunker Hill Co., Calif (d)
Burkhardt Steel Co., Colo (g)
**Busada Mfg. Co., NY** (c,g)—Ad p 442
Byers, A. M. Co., Pa (c,k)
Cadillac Plastic & Chemical Co., Mich (k,l,m)
Califlex Co., Inc., Calif (k)
Carlon Products Corp., Ohio (k)
Carolina Industrial Plastics Div., Essex Wire Corp., NC (k)
Carpenter Steel Co., Pa (f,g,h)
Carpenter Steel Co., Alloy Tube Div., NJ (g)
Cartwright, R. Tube Products Co., Mich (a,b,e,f,g)
Celluplastic Corp., NJ (k)
Channel Master Corp., NY (a)
Chase Brass & Copper Co., Sub. of Kennecott Copper Corp., Conn (b)
Chicago Gasket Co., Ill (k)
Clayton Mark & Co., Ill (g)
Cleveland Steel Specialty Co., Inc., Ohio (g)
Clifton Conduit Corp., Md (g)
Colonial Alloys Co., Pa (a)
Colonial Plastics Mfg. Co., Div. of Van Dorn Iron Works Co., Ohio (k)
Colorado Fuel and Iron Corp., Colo (g)
Columbia-Geneva Steel Div., U. S. Steel Corp., Calif (g)
Conneaut Rubber & Plastics Co., Div. of U.S. Stoneware Co., Ohio (k,m)
Continental Copper & Steel Industries, Inc., NY (a,b,c,e,f,g,h)
Continental Rubber Works, Pa (m)
Continuous Cast Products Dept., American Smelting & Refining Co., NJ (b)
Copper and Brass Sales, Inc., Mich (a,b,e)
Cornell and Underhill, Inc., NJ (a,c,g)
Corson Industries, Pa (a)
Crane Co., Ill (k)
Crane Plastics, Inc., Ohio (k,m)
Crescent Plastics, Inc., Ind (k)
Crucible Steel Co. of America, Pa (f,g,h)
Crucible Steel Co. of America, Titanium & Vacuum Metals Products Div., Pa (f,g,h)
CrystalX Corp., Pa (k)
Curbell, Inc., NY (k,l,m)
Curtiss-Wright Corp., Metals Processing Div., NY (g,h)
Damascus Tube Co., Pa (f,g,h)
Daubert Chemical Co., Ill (m)
Defiance Metal Products Co., Ohio (g)
Detroit Float & Stamping Co., Mich (b)
Division Lead Co., Ill (d)
Dixie Aluminum Corp., Ga (a)
Dixie Plastics Mfg. Co., La (k)
Dixon Corp., RI (k)
Dormont Mfg. Co., Pa (a,b,c,e)
Dow Chemical Co., Dow Metal Products Co. Div., Mich (e)
Drawn Metal Tube Co., Conn (b)
Dryden Rubber Div., Sheller Mfg. Co., Ill (m)
Easton Plastic Products Co., Inc., Pa (k)
Eclipse Plastic Industries, Inc., Fla (k)
Edgcomb Steel & Aluminum Corp., NJ (a)
Electric Steel Foundry Co., Ore (g,h)
Electronic Parts Mfg. Co., Inc., NJ (b,f)
Ellwood City Iron & Wire Co., Pa (c)
Emerson-Sack-Warner Corp., Mass (a, b,f,g)
Empire Metal Co., NY (d)
Ethylene Chemical Corp., NJ (l)
Evans Metal Co., Ga (d)
Eynon-Dakin Co., Mich (a,b,c,f,g)
Fibercast Co., Div., of Youngstown Sheet and Tube Co., Okla (l)
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (m)
FitzSimons Mfg. Co., Mich (g)
Flexaust Co., Div. of Callahan Mining Co., Inc., NY (m)
Flexonics Corp., Ill (g)
Florence Pipe Foundry & Machine Co., NJ (c)
Formed Tubes, Inc., Mich (g)
Fox Products Co., Pa (a)
Franklin Plastics, Inc., Pa (k)
Frasse, Peter A. & Co., Inc., NY (a,g)
Fromson Orban Co., Inc., NY (a,b,f,g)
Fry Plastics International, Calif (k)
Garlock Packing Co., NY (k)
Gates Rubber Co., Colo (k)
Geauga Industries Co., Ohio (m)
General American Transportation Corp., Plastics Div., Ill
General Extrusions, Inc., Ohio (a)
**General Motors Corp., Rochester Products Div., NY** (g)—Ad p 435
Genesee Laboratories, Inc., NY (k)
Gering Plastics, Div. of Studebaker-Packard Corp., NJ (k)
Glass Laboratories, NY (k)
Goodrich, B.F., Industrial Products Co., Ohio (k)
H & H Tube & Mfg. Co., Mich (b)
H-P Products, Inc., Ohio (g)
Hall Mfg. Co., NJ (k)
Hartwell, H.N. & Son, Inc., Mass (k)
Harvey Aluminum, Calif (a,h)
Hawkridge Bros. Co., Mass (a)
Haydon Corp., NY (a,g)
Haynes Stellite Co., Div. of Union Carbide Corp., Ind (f)
Hays Mfg. Co., Pa (l)
Hazledine, E.T. Co., Ind (g)
Heil Process Equipment Corp., Ohio (k)
Hi-Grade Alloy Corp., Ill (d)
Houston Blow Pipe & Sheet Metal Works, Tex (a,b,g)
Hungerford Plastics Corp., NJ (k)
**Hussey, C.G. & Co., Div. of Copper Range Co., Pa** (b)—Ad p 180
Hydrawlik Co., NJ (k,m)
Imco Container Corp., Mo (k)
Industrial Pipe & Supply Co., Ill (g)
Industrial Plastic Fittings Co., Ohio (k)
Industrial Synthetics Corp., NJ (k)
International Nickel Co., Inc., NY (f)
Jackson Steel Products, Inc., NY (a, b,g)
Jarl Extrusions, Inc., NY (a)
Jessop Steel Co., Pa (g)
Jet Specialties Co., Inc., Calif (k)
Johnson Metal Hose, Inc., Conn (b,f)
Johnson Plastic Corp., Ohio (k,m)
Johnson Rubber Co., Ohio (m)
Jones & Laughlin Steel Corp., Pa (g)
Jordan-Rogers Co., Calif (k)
Judsen Rubber Works, Inc., Ill (m)
K S H Plastics, Inc., Mo (k)
Kaiser Aluminum & Chemical Sales Inc., Ill (a)
Kaiser Steel Corp., Calif (g)
Kaufman Glass Co., Del (k,l)
Kenmore Machine Products, Inc., NY (b)
Kensico Tube Co., NY (b)
Kleiner Metal Specialties, Inc., NJ (g)
Koehler Mfg. Co., Mass (g)
Kralov Plastic Pipe Co., Inc., Calif (k)
Laclede Steel Co., Mo (g)
Lamtex Industries, Inc., NY (l)
Langsenkamp, F.H. Co., Ind (a,b)
Leach & Garner Co., Mass (b,f)
Lee Rubber & Tire Corp., Pa (m)
Lewin-Mathes Co., Mo (b)
Lewis & Saunders, NH (a,b,g)
Linderme Tube Co., Ohio (a,b)
Lock Joint Tube Co., Inc., Ind (g)
Lunn Laminates, Inc., NY (l)
Lus-Trus Corp., Mich (k)
Luzerne Rubber Co., NJ (k,l)
MacKenzie-Walton Co., RI (b)
Magline Inc., Mich (a,e)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (a,b,e,g)
Manufacturers Corp., Ohio (k)
Manufacturers & Fabricators, Inc., Ohio (f)
Mechanical Rubber Products Co., NY (l)
Meier Screw Products & Mfg. Co., Mich (a,b,c,e,g)
Melco Wire Products, Calif (a)
Metal Forming Corp., Div. of Vanadium-Alloys Co., Ind (a,b,f,g)
Metal Goods Corp., Mo (a,b,f,g)
Midland Pipe & Supply Co., Ill (b,c,g)
Midvale-Heppenstall Co., Pa (g)
Minnesota Mining & Mfg. Co., Minn (k,l)
Missouri Boiler & Sheet Works, Mo (g)
Moore Drydock Co., Calif (g)
Morse, Fred W. Co., RI (a)
Moxness Products, Inc., Wis (m)
**Mueller Brass Co., Mich** (b)—Ad p 455
Murray, A.B. Co., Inc., NJ (a,b,f,g)
Naige Co., Inc., NY (k)
Narragansett Boiler Works, Inc., RI (g)
National Copper & Smelting Co., Ohio (b)
National Electric Div., H.K. Porter Co., Pa (g)
National Galvanizing Co., Pa (g)
National Gasket & Washer Mfg. Co., Inc., NY (k,l,m)
National Lead Co., NY (a,b,d)
National Lead Construction Co., Inc., NJ (d)
National Supply Co., Pa (g).
National Tube Div., U.S. Steel Corp., Pa (g)
National Tube Div., U.S. Steel Corp., Pa (k)
National Vulcanized Fibre Co., Del (k,l)
New England Tape Co., Div. of United-Carr Fastener Corp., Mass (k)
Newage Industries, Inc., Pa (k)
Nikon Tube Co., Ill (g)
Noera Mfg. Co., Conn (b,g)
Nuclear Metals, Inc., Mass (a,b,c,e, f,g,h)
Ohio Seamless Tube Div., Copperweld Steel Co., Ohio (g)
Ohio Steel Foundry Co., Ohio (f)
Olds Alloys Co., Calif (b,d,f)
Olin Mathieson Chemical Corp., Metals Div., NY (a)
Oregon Metallurgical Corp., Ore (h)
Pabst Engineering Equipment Co., Inc., NJ (a,b,c,e,f,g,h,j)
Panelyte Div., St. Regis Paper Co., NY (k,l)
Parker Metal Goods Co., Mass (a,g)
Parker, Stearns & Co., Inc., NY (m)
Parker-Street Castings Co., Ohio (c)
Pencoyd Steel & Forge Corp., Pa (c,g)
Penn Brass & Copper Co., Pa (b)
Penn Extrusion Corp., Pa (a)
Perfex Plastics, Inc., Ill (k)
Pfister Tubing Corp., NJ (a)
Philadelphia Bronze & Brass Corp., Pa (b)
Philrus Products Co., NJ (l)
Phoenix Iron & Steel Co., Pa (g)
Pittsburgh Steel Co., Pa (g)
Pittsburgh Tube Co., Pa (g)
Plastex Co., Ohio
Plastic Pipe & Tube Corp., Calif (k)
Plastic Process Co., Inc., Calif (k)
Plymouth Cordage Co., Mass (k)
Polyform Plastics Corp., NY (k)
Polymer Corp. of Pennsylvania, Sub. of Polymer Corp., Pa (k)
Porter, William Co., Calif (l)
Precision Extrusions, Inc., Ill (a)
Precision Tube Co., Inc., Pa (a,b,f,g)
Pressed Steel Co., Pa (f)
Prince Rubber Co., Inc., NY (k,l)
Pyramid Moldings, Inc., Ill (g)
Pyramid Plastics, Inc., Ill (k,m)
Raybestos-Manhattan, Inc., NJ (m)
Reading Tube Corp., NY (b)
Reflin Co., Calif (l)
Reinhold Engineering & Plastics Co., Calif (k)
Reliance Plastic & Chemical Corp., NJ (k)
Ren Plastics, Inc., Mich (l)
Replac Corp., Ohio (k,l,m)
Republic Steel Corp., Ohio (g)
Republic Steel Corp., Steel & Tubes Div., Ohio (f,g,h)

## KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Resistoflex Corp., NJ (k)
Revere Copper & Brass, Inc., NY (a,b,g)
Reynolds Aluminum Supply Co., Ga (a,g,b)
Reynolds Metals Co., Va (a)
Rigidized Metals Corp., NY (a,g)
Rockwell Engineering Co., Ill (a,b,c,g)
Rolled Alloys, Inc., Mich (f,g)
Rolock, Inc., Conn (f)
Rome Mfg. Div., Revere Copper & Brass, Inc., NY (g)
Rome Turney Radiator Co., NY (a,b,g)
Roth Steel Products Co., Ohio (g)
Rotometals, Calif (d)
Rowland Products, Inc., Conn (k)
Ryerson, Joseph T. & Son, Inc., Ill (a,g)
Sandusky Foundry & Machine Co., Ohio (b,f,g)
Sandvik Steel, Inc., NJ (g)
Sanford Plastics Corp., NY (k)
Saran Lined Pipe Co., Div. of Michigan Pipe Co., Mich (g)
Sawhill Tubular Products, Inc., Pa (f,g)
Schwab Plastics Corp., Mich (k,m)
Scovill Mfg. Co., Mill Products Div., Conn (b)
Service Steel Co., Mich (g)
Shamban, W.S. & Co., Ind (k)
Shaw-Kendall Engineering Co., Ohio (a,b,c,f,g)
Sheffield Plastics Co., Mass (k)
Sheldon, M L. & Co., Inc., NY (f)
Shenango Furnace Co., Centrifugally Cast Products Div., Ohio (b,c,f)
Shoe Form Co., DeWitt Plastics Div., NY (k)
Sierra Electric Corp., Calif (k)
Skyline Industries, Pa (k)
Small Tube Products, Inc., Conn (b)
Snyder, M.L. & Son, Inc., Pa (k)
Solar Steel Corp., Ohio (g)
South River Metal Products Co., Inc., NJ (a,e)
Southern Aluminum Finishing Co., Inc., Ga (a)
Southern Fabricating Co., Inc., Ala (g)
Southern Plastics Co., SC (k,m)
Southwestern Plastic Pipe Co., Tex (k)
Sparta Mfg. Co., Div. of U.S. Ceramic Tile Co., Ohio (k)
Spiral-Glas Pipe Co., NJ (k,l,m)
Spuck Iron & Foundry Co., Mo (g)
Standard Metals Corp., Mass (b,f)
Standard Products Co., Mich (m)
Standard Tube Co., Mich (g)
Star Heel Plate Co., Inc., NJ (g)
Stockwell Rubber Co., Inc., Pa (k,m)
Stokes Molded Products, Div., Electric Storage Battery Co., NJ (k)
Summerill Tubing Co. Div., Columbia Steel & Shafting Co., Pa (g)
Sunlite Plastics, Inc., Wis (k)
**Superior Tube Co., Pa** (c,f,g,h)—Ad pp 414-415
Supplex Co., Div. of Amerace Corp., NJ (k,m)
Surprenant Mfg. Co., Mass (k)
Swepco Tube Corp., NJ (f)
Synthane Corp., Pa (l)
Taunton Div., Haveg Industries, Inc., Mass (m)
Taylor Fibre Co., Pa (l)
Technical Specialties Co., NY (m)
Tennessee Coal and Iron Div., U.S. Steel Corp., Ala (g)
Texas Aluminum Co., Tex (a)
Thermoid Div., H. K. Porter Co., Pa (k,l,m)
Thompson Pipe & Steel Co., Colo (c,f,g)
Timken Roller Bearing Co., Ohio (g)
Titanium Metals Corp. of America, NY (h)
Tompkins Products, Mich (a)
Trent Tube Co., Sub. of Crucible Steel Co. of America, Pa (f,g,h)
Trenton Pipe Nipple Co., NJ (b,g)
Triangle Conduit & Cable Co., Inc., NJ (b,k)
Trim Alloys, Inc., Mass (a)
Tube Distributors Co., Inc., NY (c,e,f,g,h)
Tube Methods, Inc., Pa (c,f,g)
Tube Reducing Corp., NJ (f,g,h)
Tuff Clad, Inc., Ohio (k)
Udylite Corp., Mich (k)
Uniform Tubes, Inc., Pa (a,b,f,g)
Union Steel Corp., NJ (g)
U.S. Flexible Tubing Co., Ill (g)
U.S. Gasket Plastics Div., Garlock Packing Co., NJ (k,l)
U.S. Rubber Co., Mechanical Goods Div., Ind (k)
U.S. Steel Corp., Pa (g)
U.S. Steel Supply Div., U.S. Steel Corp., Ill (g)
U.S. Stoneware Co., Ohio (k)
U.S. Valve & Mfg. Co., Calif (g)
United Wire & Supply Corp., RI (a,b)
Universal Converting Corp., Mass (a)
Urrite Plastics Fabricators, Calif (k)
Vanadium-Alloys Steel Co., Pa (f,g)
Vanamatic Co., Ohio (g)
Van Huffel Tube Corp., Ohio (a,b,g)
Van Pelt Corp., Service Steel Div., Mich (f,g,h)
Viking Copper Tube Co., Ohio (b)
Viplax Products Corp., NJ (k)
Vogt Mfg. Corp., NY (k)
Vulcan Metal Products, Inc., Ala (a)
Vulcan Rail & Construction Co., NY (a,c,g)
Wall Tube & Metal Products Co., Tenn (b,f,g)
Wallace Tube Co., Div. of Wallace Supplies Mfg. Co., (a,b,g)
Wallingford Steel Co., Conn (g)
Wal-Mar Corp., Ill (a,b,c,e,g)
Waterman Industries, Inc., Calif (a,b)
Weiskittel, Harry C. Co., Inc., Md (c)
Welding Apparatus Co., Ill (a,f)
Wells, A.H. & Co., Inc., Conn (b)
Western Felt Works, Ill (l,m)
Western Textile Products Co., Mo (k,m)
Westlake Plastics Co., Pa (k,l,m)
Wheatland Tube Co., Pa (g)
Wheeling Steel Corp., Va (g)
White Metal Rolling & Stamping Corp., NY (a,e)
Whitehead Metal Products Co., Inc., NY (a,b,f,g)
William Brand-Rex Div., American Enka Corp., Mass (k)
**Williams-Bowman Rubber Co., Ill** (l,m)—Ad p 276
**Wolverine Tube Div., Calumet & Hecla, Inc., Mich** (a,b,g)—Ad p 445
Woolf Aircraft Products, Inc., Mich (a,b,f,g)
World Plastics, NY (k)
Yardley Plastics Co., Ohio (k)
Youngstown Mfg., Inc., Ohio (a)
Youngstown Sheet and Tube Co., Ohio (g)
Youngstown Welding & Engineering Co., Ohio (a,f,h)

## Tungsten

American Metal Climax, Inc., NY (aa)
American Nickel Alloy Mfg. Corp., NY (w,aa)
Associated Engineering & Mfg. Corp., NJ (o,aa,bb,cc,dd,ff)
Belmont Smelting & Refining Works, NY (aa)
Cleveland Tungsten, Inc., Ohio (aa, bb)
Electronic Parts Mfg. Co., Inc., NJ (bb,cc,ee,ff)
Elmet Div., North American Philips Co. Inc., Me (o,w,aa,bb,ff)
**Fansteel Metallurgical Corp., Ill** (n,o,q,v,w,z,aa,bb,cc,dd,ee,ff) — Ad p 174
Firth Sterling Inc., Pa (q,aa,bb)
Fromson Orban Co., Inc., NY (ff)
General Electric Co., Lamp Metals & Components Dept., Ohio (o,q,w, aa,bb,cc,dd,ff)
**Gibson Electric Co., Pa** (aa)—Ad p 466
Hardy, Charles, Inc., NY (aa)
Harvey Aluminum, Calif (o,bb)
Hayden Wire Works, Inc., Mass (ff)
Kassel Export Co., Inc., NJ (v,bb, dd,ff)
**Kennametal, Inc., Pa** (o,bb)—Ad p 306
Kinkead Industries, Inc., Ill (o)
Mallory-Schwarzkopf Metals, Inc., NY (o,v,w,z,bb,cc,dd,ee,ff)
Molybdenum Corp. of America, Pa (o, w,z,aa,bb,cc,dd)
Nuclear Metals, Inc., Mass (w,bb, dd,ff)
Oregon Metallurgical Corp., Ore (w)
Reduction & Refining Co., NJ (q,w,aa, bb,ff)
Shieldalloy Corp., NJ (aa)
**Stauffer Chemical Co., NY** (q)—Ad p 163
Stauffer-Temescal Co., Calif (w)
**Sylvania Electric Products, Inc., Chemical & Metallurgical Div., Pa** (w,aa,bb,ff)—Ad p 153
Union Carbide Metals Co., Div. of Union Carbide Corp., NY (aa)
Universal-Cyclops Steel Corp., Pa (o, q,z,cc)
**Wah Chang Corp., NY** (n,aa,bb,cc,ff)—Ad p 164
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,v,w,z,bb,cc, dd,ee)

## Upset Forgings

(see Forgings)

## Ureas

Adhesive Products Corp., NY (x)
Alcylite Plastics & Chemical Corp., Calif (p,x,y)
Allied Chemical Corp., Plastics & Coal Chemicals Div., NY (p,y)
**American Cyanamid Co., Plastics & Resins Div., NY** (p,u)—Ad pp 251-254
American Viscose Corp., Pa (y)
American-Marietta Co., Adhesive, Resin & Chemical Div., Wash (p)
Archer-Daniels-Midland Co., Minn (p)
Booty Resineers Div., American-Marietta Co., Ohio (p)
Borden Co., Borden Chemical Div., NY (p)
Catalin Corp. of America, NY (p,x)
Chemical Process Co., Calif (x)
Chemore Corp., NY (p,y)
Colton Chemical Co., Div. of Air Reduction Co., Inc., Ohio (u)
Dunnican Asso., NJ (y)
Dyna-Therm Chemical Corp., Calif (p)
Gordon Chemicals, Inc., Del (y)
Grigolelt Co., Ill (p,s)
Kurz Kasch, Inc., Ohio (y)
Luminous Resins, Inc., Ill (y)
Mica Insulator Div., Minnesota Minins & Mfg. Co., NY (bb,cc)
Monsanto Chemical Co., Plastics Div., Mass (p)
Muehlstein, H. & Co., Inc., NY (p,y)
Nopco Chemical Co., NJ (p)
Omni Products Corp., NY (p)
Reichhold Chemicals, Inc., NY (p,x)
Sierra Electric Corp., Calif (y)
Specialty Resins Co., Calif (p)
Sylvan Plastics, Inc., Pa (y)
Synco Resins, Inc., Conn (p)
Texas Glass Fiber Corp., Tex (y)

## Urethane Elastomers

Acushnet Process Co., Mass (y)
Adhesive Products Corp., NY (x)
American Latex Products Co., Calif
American Rubber Products Corp., Ind (u,cc,dd)
B.B. Chemical Co., Bostik Dept., Mass (u)
Bond International, Inc., Mich (y,ee)
Brown Rubber Co., Inc., Ind (u)
Castle Rubber Co., Pa (y,bb,cc,dd,ee)
Chemical Coatings & Engineering Co., Inc., Pa (p,u,x,y)
Chicago-Allis Mfg. Corp., Ill (p)
Coast Pro-Seal & Mfg. Co., Calif (y)
Continental Rubber Works, Pa (bb,cc, dd,ee)
Dayton Rubber Co., Ohio (p,u,x,y,bb, cc,dd,ee)
Disogrin Industries, Inc., NY (bb,cc)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (y,ee)
du Pont de Nemours, E. I. & Co., Inc., Del (w)
Dyna-Therm Chemical Corp., Calif (p,x)
Faultless Rubber Co., Ohio (u)
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (u)
Flexible Tubing Corp., Conn (ee)
Foam Products, Inc., Pa (u)
Foamade Industries, Mich (u,x,y,cc,dd)
General Electric Co., Plastics Dept., Ill (u)
General Plastics Mfg. Co., Wash (u,cc)
General Tire & Rubber Co., Chemical Div., Ohio (p)
Goodrich, B.F. Chemical Co., Ohio (p)
Hewitt-Robins, Inc., Conn (u,cc)
Hudson Cush-N-Foam Corp., NJ (u, bb,cc)
Isocyanate Products, Inc., Del (p,u)
Maco Industries, Inc., Ill (bb,cc,dd,ee)
Maloney, F.H. Co., Tex (x,y)
Marblette Corp., NY
Mobay Chemical Co., Pa (p,u,x,y)
Naugatuck Chemical Div., U.S. Rubber Co., Conn (p,u,x,y)
Parker Seal Co., Div. of Parker-Hannifin Corp., Calif (u)
Pelron Corp., Ill (p,u,x,y)
Plas-Kem Corp., Div. of Dyna-Therm Chemical Corp., Calif (x)
Prince Rubber & Plastics Co., Inc., NY (bb)
Reynolds Chemical Products Co., Mich (p,u,x)
Schwab Plastics Corp., Mich (u)
Scott Paper Co., Foam Div., Pa (u)
Sheller Mfg. Corp., Mich (u)
Sterling Alderfer Co., Ohio (u,dd)
Stockwell Rubber Co., Inc., Pa (u,cc)
Taunton Div., Haveg Industries, Inc., Mass (u)
Technical Specialties Co., NY (dd)
Thermoid Div., H. K. Porter Co., Pa (u)
Thiokol Chemical Corp., NJ (p,y)
Thombert, Inc., Iowa (bb,cc)
Toyad Corp., Pa (t,u)
Trostel, Albert Packing, Ltd., Wis (y)
United Shoe Machinery Corp., Mass (p,u)
U.S. Rubber Co., NY (p)
Vulcan Rubber Products Div., Reeves Bros., Inc., NY (p,y,cc)
Western Felt Works, Ill (y,cc,dd,ee)
Witco Chemical Co., Ill (p,u)

## Urethane Foams

Adhesive Products Corp., NY (x)
Aerojet-General Corp., Structural Materials Div., Calif (u)
American Latex Products Corp., Calif
American Rubber Products Corp., Ind (u,cc,dd)
Aries Laboratories, Inc., Conn (u)
Atlas Mineral Products Co., Pa (u)
Atlas Powder Co., Del (u)
B.B. Chemical Co., Bostik Dept., Mass (u)
Burkart, F. Mfg. Co., Div. of Textron Inc., Mo (u)
Cadillac Plastic & Chemical Co., Mich (x,y,bb,cc,dd)
Carolina Industrial Plastics Div., Essex Wire Corp., NC (u)
Chemical Coatings & Engineering Co., Inc., Pa (p,u,x,y)
Columbus Coated Fabrics Corp., Ohio (u)

**Crest Chemical Industries Corp., NY (u)**
CrystalX Corp., Pa (u)
Dayton Rubber Co., Ohio (p,u,x,y,bb, cc,dd,ee)
**Disogrin Industries, Inc., NY (bb,cc)**
**Dryden Rubber Div., Sheller Mfg. Corp., Ill (u,y)**
du Pont de Nemours, E. I. & Co., Inc., Del (u)
Durez Plastics Div., Hooker Chemical Corp., NY (u)
Dyna-Therm Chemical Corp., Calif (p)
**Electro Chemical Engineering & Mfg. Co., Pa (u, cc)**
**Englander Co., Inc., Industrial Products Div., Md (u)**
Firestone Rubber & Latex Products Co., Div. of Firestone Tire & Rubber Co., Mass (u)
Foam Products, Inc., Pa (u)
**Foamade Industries, Mich (u,x,y,cc,dd)**
Foss Mfg. Co., Id (u)
Fry Plastics International, Calif (u)
**Furane Plastics, Inc., Calif (x,y)**
**General Plastics Mfg. Co., Wash (u, cc)**
General Tire & Rubber Co., Ind (u)
General Tire & Rubber Co., Chemical Div., Ohio (p)
Goodrich, B.F. Chemical Co., Sponge Products Div., Conn (u)
**Hadley Bros.-Uhl Co., Mo (u)**
Hewitt-Robins, Inc., Conn (u,cc)
Industrial Paint Div., Glidden Co., Ohio (p,u)
**Interchemical Corp., Finishes Div., NJ (u)**
**Isocyanate Products, Inc., Del (p,u)**
Luminous Resins, Inc., Ill (y)
Maco Industries, Inc., Ill (bb,cc,dd,ee)
**Maloney, F.H. Co., Tex (y)**
Marion Div., General Tire & Rubber Co., Ind (u)
Mobay Chemical Co., Pa (p,u,x,y)
**Nesbitt Industries, Inc., Ill (u)**
Nopco Chemical Co., NJ (u,cc)
Paeco Rubber Co., Inc., Ohio (y,dd, ee)
**Pelron Corp., Ill (p,x,y)**
Plas-Kem Corp., Div. of Dyna-Therm Corp., Calif (x)
Polytron Corp., Calif (p,u)
Quelcor, Inc., Pa (u)
**Reichhold Chemicals, Inc., NY (u)**
Richardson Co., NY (bb,cc,ee)
**Russell Reinforced Plastics Corp., NY (u)**
**Schenectady Varnish Co., Inc., NY (p)**
**Schwab Plastic Corp., Mich (u)**
Scott Paper Co., Foam Div., Pa (u)
**Sheller Mfg. Corp., Mich (u)**
**Southern Plastics Co., NC (bb,cc,dd, ee)**
Sterling Alderfer Co., Ohio (u,dd)
**Strick Plastics Co., Pa (u)**
**Thiokol Chemical Corp., NJ (p,u,x,y)**
**Toyad Corp., Pa** (u)—Ad p 260
**United Shoe Machinery Corp., Mass (t,u)**
**U.S. Rubber Co., Conn (p,u,x,y)**
William Brand-Rex Div., American Enka Corp., Mass (ee)
**Witco Chemical Co., Ill (p,u)**
**Woodall Industries, Inc., Mich (u)**

## Vacuum Formed Parts

(see Moldings, Sheet)

## Vacuum Metallizing

(see Metallized Coatings)

## Vanadium

American Metal Climax, Inc., NY (o)
**American Nickel Alloy Mfg. Corp., NY (w)**
Belmont Smelting & Refining Works, Inc., NY (aa)
Bridgeport Brass Co., Conn (ee)
**Chicago Development Corp., Md (aa)**
**Hardy, Charles, Inc., NY (aa)**
**Magnesium Elektron, Inc., NY (w,aa)**
**National-Standard Co., Mich** (ff)—Ad p 421
Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)
**Nuclear Metals, Inc., Mass (w,bb,ee)**
Oregon Metallurgical Corp., Ore (v,w)
**Shieldalloy Corp., NY (aa)**
Texas Instruments, Inc., Metals & Controls Div., Mass (v)
**Union Carbide Metals Co., Div. of Union Carbide Corp., NY** (w,z,aa,bb)—Ad p 181
Vanadium Corp. of America, NY (o,v,z,bb,cc,dd,ee,ff)
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,v,w,z,bb,cc,dd, ee)

## Varnishes

(see Organic Coatings)

## Vinyls

(Polyvinyl chloride and copolymers)
Adhesive Products Corp., NY (p,x,y)
Air Reduction Chemical Co., Div. of Air Reduction Co., Inc., NY (p)
Albany Novelty Mfg. Co., Mass (cc)
Albert Pipe Supply Co., Inc., NY (ee)
Alpha Plastics, Inc., NJ (bb,ee)
Alpha Wire Corp., NY (cc,ee)
Amercoat Corp., Calif (cc,ee)
American Hard Rubber Co., Div. of Amerace Corp., NJ (y,bb,cc,dd,ee)
American Products Mfg. Co., La (p,t, cc)
Atlas Mineral Products Co., Pa (cc,ee)
Auburn Plastics, Inc., NY (y,bb,cc,dd, ee)
Automotive Rubber Co., Inc., Mich (u,y,cc,dd)
Avery Label Co., Decorative Products Div., Ohio (u)
Blacher, B., NY (t)
Blossom Mfg. Co., NY (t,cc,dd)
Bolta Products Div., General Tire & Rubber Co., Mass (s,t,bb,cc,ee)
Borden Chemical Co., Div. of Borden Co., NY (p,ee)
Byers, A.M. Co., Pa (ee)
Cadillac Plastic & Chemical Co., Mich (t,cc,ee)
Carolina Industrial Plastics Div., Essex Wire Corp., NC (u,ee)
Carroll, J.B. Co., Ill (x,cc)
Chemical Products Corp., RI (u,y)
Chemore Corp., NY (p,s,y)
Colonial Plastics Mfg. Co., Div. of Van Dorn Iron Works, Ohio (bb,cc, dd,ee)
Columbus Coated Fabrics Corp., Ohio (t)
Comco Plastics, Inc., NY (cc,dd,ee)
Commercial Plastics & Supply Corp., NY (cc,ee)
Conneaut Rubber and Plastics Co., Div. of U.S. Stoneware Co., Ohio (t,bb,cc,dd,ee)
Cordo Chemical Corp., Conn (t,x,y)
Crane Plastics, Inc., Ohio (bb,dd,ee)
Crest Chemical Industries Corp., NY (u)
CrystalX Corp., Pa (t,bb,cc,dd,ee)
Curbell, Inc., NY (cc,ee)
Dennis Chemical Co., Mo (u,x,y)
Diamond Alkali Co., Ohio (p)
Dobeckmun Co., Div. of Dow Chemical Co., Ohio (x)
Douglas & Sturgess, Calif (p,x,y)
Dow Chemical Co., Plastics Div., Mich (p)
Dryden Rubber Div., Sheller Mfg. Corp., Ill (y,ee)
Dura Plastics of New York, Inc., NY (x,bb,cc,dd,ee)
Electric Steel Foundry Co., Ore (bb, cc,dd,ee)
Elm Coated Fabrics Co., Inc., NY (t,
Escambia Chemical Corp., NY (p)
Firestone Plastics Co., Pa (s,t)
Flexible Tubing Corp., Conn (ee)
Fry Plastics International, Calif (t, u,cc,dd,ee)
Galigher Co., Utah (bb,cc,dd,ee)
Geauga Industries Co., Ohio (p,bb,dd, ee)
General Tire & Rubber Co., Chemical Div., Ohio (p)
General Tire & Rubber Co., Textileather Div., Ohio (t)
Genesee Laboratory, Inc., NY (bb,dd, ee)
Gering Plastics Div., Studebaker-Packard Corp., NJ (y,bb,dd,ee)
Glass Laboratories, Inc., NY (dd)
Goodrich, B.F. Co., Sponge Products Div., Conn (u)
Goodrich Chemical Co., Ohio (p,u,x, y)
Goodrich, B.F. Industrial Products Co., Ohio (t,bb,cc,dd,ee)
Goodyear Tire & Rubber Co., Ohio (p,x)
Great American Industries, Inc., Rubatex Div., Va (u)
Hauger-Beegle Asso., Inc., Ill (t)
Heyden Newport Chemical Corp., American Plastics Corp. Div., NY (bb, ee)
Hydrawlik, NJ (bb,ee)
Industrial Plastics Corp., Ind (bb,dd, ee)
Insulation Mfrs. Corp., Ill (ee)
Interchemical Corp., Finishes Div., NJ (u)
K-S-H Plastics, Inc., Mo (bb,cc,dd, ee)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Kaykor Industries, Inc., Div. of Kaye-Tex Mfg. Corp., NJ (bb,cc,dd)
Kuss, R.L. & Co., Inc., Ohio (t, cc)
Lus-Trus Corp., Mich (bb,cc,dd,ee)
Mannesmann-Easton Plastic Products Co., Inc., Pa (bb,ee)
Masland Duraleather Co., Pa (t,cc)
Mayon Plastics, Minn (bb,ee)
Mono-Sol Corp., Ind (u)
Monsanto Chemical Co., Organic Chemicals Div., Mo (p)
Monsanto Chemical Co., Plastics Div., Mass (p,t,u,x,y,cc)
Morningstar-Paisley, Inc., NY (p)
Nalge Co., Inc., NY (ee)
National Gasket & Washer Mfg. Co., Inc., NY (cc,dd,ee)
National Tube Div., U.S. Steel Corp., Pa (ee)
Naugatuck Chemical Div., U.S. Rubber Co., Conn (p,u,x,y)
New England Tape Co., Div. of United-Carr Fastener Corp., Mass (bb,dd,ee)
Newage Industries, Inc., Pa (ee)
Nixon Nitration Works, NJ (cc)
O'Sullivan Rubber Corp., Va (t)
Pawling Rubber Corp., NY (bb,dd,ee)
Perfex Plastics, Inc., Ill (bb,dd,ee)
Plas Kem Corp., Div. of Dyna-Therm Chemical Corp., Calif (u,x,y)
Plast-Ad Mfg. Co., Ind (bb,cc,dd,ee)
Polo Plastics Co., Wis (t,u,cc)
Poly Resins, Calif (p,x)
Polymer Corp., Pa (p)
Premier Thermo Plastics Co., Ky (u, y)
Prince Rubber & Plastics Co., Inc., NY (bb,cc,dd,ee)
Pyramid Plastics, Inc., Ill (bb,dd,ee)
Pyrosil, Inc., Ohio (cc)
Quelcor, Inc., Pa (u,x,y,cc)
Reichhold Chemicals, Inc., NY (p)
Reliance Plastic & Chemical Corp., NJ (bb,cc,dd,ee)
Republic Rubber Div., Lee Rubber and Tire Corp., Ohio (dd,ee)
Reynolds Chemical Products Co., Mich (u,x,y)
Reynolds Metals Co., Va (t,x,cc)
Ross & Roberts, Inc., Conn (t,cc)
Rubber Corp. of America, NY (p,t,x, y,cc)
Rubber & Plastics Compound Co., Inc., NY (cc)
Scranton Plastic Laminating Corp., Pa (t,x,cc,dd)
Seaman Products, Calif (t)
Seiberling Rubber Co., Plastics Div., Ohio (t,u,cc)
Sheffield Plastics, Inc., Mass (ee)
Southern Plastics Co., SC (bb,cc,dd, ee)
Stockwell Rubber Co., Inc., Pa (bb, cc,ee)
Structural Products Div., National Starch & Chemical Corp., NY (p)
Sun Steel Co., Ill (t,x,cc,dd)
Sunlite Plastics, Inc., Wis (bb,dd,ee)
Superior Plastics, Inc., Ill (bb,cc,dd, ee)
Supplex Co., Div. of Amerace Corp., NJ (y,bb,dd,ee)

### KEY

**MATERIALS**

**a**—Aluminum and its alloys
**b**—Copper and its alloys
**c**—Iron and its alloys (except steel)
**d**—Lead and its alloys
**e**—Magnesium and its alloys
**f**—Nickel and its alloys
**g**—Steels
**h**—Titanium and its alloys
**j**—Zinc and its alloys
**k**—Thermoplastics
**l**—Thermosetting plastics
**m**—Elastomers

**BASIC FORMS**

**n**—Anodes
**o**—Bar
**p**—Base resins, polymers or gums
**q**—Billets
**r**—Custom formed parts (incl. specialties)
**s**—Fibers
**t**—Film
**u**—Foams (component materials or products)
**v**—Foil
**w**—Ingot
**x**—Laminating, casting resins
**y**—Molding compounds
**z**—Plate
**aa**—Powder
**bb**—Rod
**cc**—Sheet
**dd**—Strip
**ee**—Tubing
**ff**—Wire

Taunton Div., Haveg Industries, Inc., Mass (ee)
**Toyad Corp., Pa** (u)—Ad p 260
Tuff Clad, Inc., Ohio (x,cc)
**Union Carbide Plastics Co., Div. of Union Carbide Corp., NY** (p,s,t,u,y,cc)—Ad p 257
U.S. Rubber Co., NY (p,y)
U.S. Stoneware Co., Ohio (bb,cc,dd,ee)
Varflex Corp., NY (ee)
Watson-Standard Co., Pa (u,y)
Western Textile Products Co., Mo (ee)
Whirlclad Div., Polymer Corp., Pa (p)
Whitehead Metal Products Co., Inc., NY (bb,cc,dd,ee)
William Brand-Rex Div., American Enka Corp., Mass (bb,dd,ee)

## Vinyls

(Saran; polyvinyl alcohol, butyral and formal)
Air Reduction Chemical Co., Div. of Air Reduction Co., Inc., NY (p,s)
American Hard Rubber Co., Div. of Amerace Corp., NJ (bb,cc,dd,ee)
Automotive Rubber Co., Inc., Mich (cc,dd)
Avery Label Co., Decorative Products Div., Ohio (u)
Bolta Products Div., General Tire & Rubber Co., Mass (s)
Borden Chemical Co., Div. of Borden Co., NY (p)
Cadillac Plastic & Chemical Co., Mich (t)
Dobeckmun Co., Div. of Dow Chemical Co., Ohio (x)
Dow Chemical Co., Plastics Div., Mich (p,t,y,bb,cc,dd,ee)
du Pont de Nemours, E. I. & Co., Inc., Del (p,t,x)
Franklin Glue Co., Ohio (p)
Fry Plastics International, Calif (t,u,cc,dd,ee)
Heyden Newport Chemical Corp., American Plastics Corp. Div., NY (bb,ee)
Kaufman Glass Co., Del (bb,cc,dd,ee)
Kuss, R. L. & Co., Inc., Ohio (s,t,cc)
Lus-Trus Corp., Mich (bb,dd,ee)
Mono-Sol Corp., Ind (t)
Monsanto Chemical Co., Plastics Div., Mass (t)
Plas Kem Corp., Div. of Dyna-Therm Corp., Calif (u,x,y)
Plast-Ad Mfg. Co., Ind (cc)
Prince Rubber & Plastics Co., Inc., NY (ee)
Pyramid Plastics, Inc., Ill (bb,cc,dd,ee)
Resistoflex Corp., NJ (cc,ee)
Reynolds Metals Co., Va (t,x,cc)
Saran Lined Pipe Co., Div. of Michigan Pipe Co., Mich (bb,cc,ee)
Seaman Products, Calif (t)
Shawinigan Resins Corp., Mass (p,y)
Stockwell Rubber Co., Inc., Pa (bb,cc,ee)
Structural Products Div., National Starch & Chemical Corp., NY (p)
**Union Carbide Plastics Co., Div. of Union Carbide Corp., NY** (p)—Ad p 257
Whitehead Metal Products Co., Inc., NY (ee)

## Vulcanized Fibre

**Ace Plastic Co., NY (bb,cc)**
**Baer, N.S. Co., NJ (bb,cc,dd,ee)**
**Colonial Kolonite Co., Ill (bb,cc,ee)**
Comco Plastics, Inc., NY (bb,cc,dd,ee)
Commercial Plastics & Supply Corp., NY (bb,cc)
**Continental-Diamond Fibre Corp., Del (bb,cc,dd,ee)**
**Coyne & Paddock, Inc., NY (cc)**
Curbell, Inc., NY (bb,cc,ee)
**Dobeckmun Co., Div. of Dow Chemical Co., Ohio (x)**
**Electrofilm, Inc., Calif (t)**
**Insulation Mfrs. Corp., Ill (bb,cc,dd,ee)**
**Item Fibre Co., Ohio (s,bb,cc,dd,ee)**
**Laminated Plastex Corp., Ohio (x,cc)**
**National Gasket & Washer Mfg. Co., Inc., NY (bb,cc,dd,ee)**
**National Vulcanized Fibre Co., Del** (bb,cc,dd,ee)—Ad p 249
**Penn Fibre & Specialty Co., Inc., Pa (bb,cc,dd,ee)**
**Philrus Products Co., NJ (bb,cc,dd,ee)**
**Spaulding Fibre Co., Inc., NY** (bb,cc,dd,ee)—Ad p 255
**Staver Co., Inc., NY (cc,dd)**
**Taylor Fibre Co., Pa** (bb,cc,dd)—Ad p 246
**Thombert, Inc., Iowa (cc,dd)**
**Westlake Plastics Co., Pa (bb,cc,dd,ee)**
**Wilmington Fibre Specialty Co., Del** (bb,cc,dd,ee)

## Welding Rods and Electrodes

(see Filler Metals)

## Weldments

**Abalon Precision Mfg. Corp., NY (a,b,c,g)**
**Acme Precision Products, Inc., Ohio (a,f,g)**
**Acorn Sheet Metal Mfg. Co., Inc., Ill** (a,g)
**Adams, I.G. Metalware Co., Mo (g)**
**Aerojet-General Corp., Structural Materials Div., Calif** (a,b,c,d,e,f,g,h)
**Albert Pipe Supply Co., Inc., NY (g)**
**Alco Products, Inc., NY (a,b,f,g)**
**Allis-Chalmers Mfg. Co., Wis. (a,f,g)**
**Alloy Products Corp., Wis** (a,f,g,h)
**Almco Steel Products Corp., Ind (a,b,c,g)**
**Aluminum Co. of America, Pa (a)**
**Amalgamated Steel Corp., Ohio (g)**
**American Brake Shoe Co., NY (b)**
**American Car & Foundry Div., ACF Industries, Inc., NY (a,e,g)**
**American Cast Iron Pipe Co., Ala (g)**
**American Machine & Foundry Co., Cleveland Welding Div., Ohio (a,c,f,g,h)**
**American Metal Products Co., Mich** (a,g)
**American Pipe & Construction Co., Ore (a,g)**
**American Sheet Metal Works, Inc., Conn (a,g)**
**American Welding and Mfg. Co., Ohio** (a,f,g,h)
**Ampco Metal, Inc., Wis (b)**
**Anderson, O.L. Co., Inc., Mich (a,b,c,d,g)**
**Armor Metal Products Co., Ohio (a,g)**
**Atlas Steel Construction Co., NY (a,b,c,g)**
**Automotive Rubber Co., Inc., Mich (a,c,e,g)**
Baldwin-Lima-Hamilton Corp., Pa (a,g)
**Barclay Mfg. Co., Ind (c)**
**Beatty Machine & Mfg. Co., Ind (g)**
**Behringer Metal Works, Inc., NJ (a,g)**
**Beloit Iron Works, Wis (c,g)**
**Bergen Point Iron Works, NY (a,b,c,f,g,h)**
Bethlehem Steel Co., Pa (g)
**Biersach & Niedermeyer Co., Wis (a,b,c,g)**
**Blaw-Knox Co., Pa (a,g)**
**Blickman, S. Inc., NJ (a,b,c,f,h)**
**Brandt, Charles T Inc., Md (a,b,e,f,g)**
**Brinkerhoff Brass & Bronze Works, Inc., NY (a,b,c,f,g)**
**Brooks & Perkins, Inc., Mich** (a,e,g,h)—Ad p 457
**Burkhardt Steel Co., Colo (c,g)**
**Butler Mfg. Co., Mo (a,g)**
**Caldwell, W.E. Co., Ky (a,g)**
**Central Fabricators, Inc., Ohio (a,b,c,f,g,h)**
**Clarksville Foundry & Machine Works, Tenn (a,c)**
**Cleveland Steel Specialty Co., Ohio (g)**
**Combined Industries Co., NY (a,b,c,e,f)**
**Combustion Engineering, Inc., Ill (a,b,g)**
**Commercial Shearing & Stamping Co., Ohio (g)**
**Continental Copper & Steel Industries Inc., NY (a,b,c,e,f,g,h)**
**Cornell and Underhill, Inc., NJ (a,g)**
**Darby Corp., Kan (a,f,g)**
**Dare Products, Inc., Mich (g)**
**Day Co., Minn (a,g)**
**Dixie Bronze Co., Ala (b)**
**Dolin Metal Products, Inc., NY (g)**
Dow Chemical Co., Dow Metal Products Co. Div., Mich (e)
**Downington Iron Works, Pa (c,g)**
**Dravo Corp., Pa (a,g)**
**Dresser Mfg. Div., Dresser Industries, Inc., Pa (g)**
**Electric Steel Foundry Co., Ore (g)**
**Emerson-Sack-Warner Corp., Mass (a,f,g)**
**Enterprise Wheel & Car Corp., Va (a,g)**
Evans, George Corp., Ill (g)
**Everard Tap & Die Corp., NY** (a,g)
**Falk Corp., Wis (g)**
**Falstrom Co., NJ (a,b,c,d,e,f,g,h,j)**
**Farwell Metal Fabricating, Minn (a,c,e,f,g)**
Federal Machine and Welder Co., Ohio (g)
**Fitzgibbons Boiler Co., Inc., NY (c)**
**Foster Wheeler Corp., NY (a,f,g)**
**Gary Steel Products Corp., Va (a,g)**
General Alloys Co., Mass (a,b,f)
**General American Transportation Corp., Ill** (a,c,g)
**General American Transportation Corp., Plate & Welding Div., Ill** (a,c,g)
**General Cable Corp., NY (g)**
**Glasby J.P. Mfg. Co., Inc., NJ** (a,c,e,f,g)
**Goslin Birmingham Mfg. Co., Inc., Ala** (b,f,g)
**Graver Tank & Mfg. Co. Div., Union Tank Car Co., Ind** (a,f,g)
**Greene, G.G. Corp., Pa (g)**
**Hardy, Mfg. Corp., Ind (g)**
**Hazledine, E.T. Co., Ind (g)**
**Hibben & Co., Ill (a,g)**
**Hicks Corp., Mass (a,b,g)**
**Hobbs, Clinton E. Co., Mass (c,g)**
**Houston Blow Pipe & Sheet Metal Works, Tex (a,b,g)**
**Ideal Can Co., Mass (a,c,g)**
**Indus Corp., Ind (a,g)**
**Industrial Equipment Co., Ohio (a,g)**
**Industrial Pipe & Supply Co., Ill (g)**
**Industrial Precision Products, Ill (a,c)**
**Ingalls Iron Works Co., Ala (c,g)**
**Ingersoll Products Div., Borg-Warner Corp., Ill (g)**
**Inland Mfg. Co., Neb (g)**
**Interlake Mfg. Co., Mich (g)**
**International Nickel Co., Inc., NY (f)**
**Irvington Form & Tank Corp., NY (a,b,g)**
Irwin-Sensenich Corp., Pa (g)
Jervis Corp., Mich (a,g)
**K-D Mfg. Co., Tex (c,g)**
**Kaiser Steel Corp., Calif (g)**
Kelsey-Hayes Co., Mich (g)
**Kewaunee Engineering Corp., Wis (c)**
**King, Alfred B. Co., Conn (a,b,c,d,f,g)**
**King Fifth Wheel Co., Pa (g)**
Kirk & Blum Mfg. Co., Ohio (g)
**Koven, L.O. & Bro., Inc., NJ (a,g)**
**Krueger Fabricating Co., Inc., Wis (a,b,c,e,g)**
**LFM Mfg. Co., Inc., Sub. of Rockwell Mfg. Co., Kan (g)**
**Langsenkamp, F.H. Co., Ind (a,b)**
**Larkin Specialty Mfg. Co., Calif (a,b,g)**
**Lawrence, L. Co., Inc., NJ** (a,b,c,e,f,g,h,j)
**Leader Iron Works, Inc., Ill (a,b,c,f,g)**
**Levinson Steel Co., Pa (g)**
**Lincoln Steel Corp., Neb (g)**
**Littleford Bros. Inc., Ohio** (a,c,f,g)
**Lockport Steel Fabricators, Inc., Ill** (a,f,g)
Loeffler, J.M. Machine Co., Pa (a,b,c)
Lukens Steel Co., Pa (a,b,e,f,g,h)
**Machine Products Corp., Ohio (a,b,c,f,g)**
**Magline, Inc., Mich (a,e)**
**Magnesium Co. of America, Ind (a,e)**
**Mahon, R.C. Co., Mich (a,g)**
**Manganese Steel Forge Co., Pa (g)**
**Manufacturers & Fabricators, Inc., Ohio (f,g)**
**Manufacturers Service, Inc., Ohio (a,b,g)**
**Mayville Metal Products Co., Wis (g)**
McDowell-Wellman Cos., Ohio (g)
**McGregor-Michigan Corp., Mich (c,f,g)**
**McLanahan & Stone Corp., Pa (g)**
**McNally Pittsburg Mfg. Co., Kan (a,c,g)**
**Midvale-Heppenstall Co., Pa (g)**
**Midwest Piping Co., Inc., Mich (g)**
**Missouri Boiler & Sheet Works, Mo (g)**
**Moore Dry Dock Co., Calif (g)**
**Morrisville Foundry Co., Inc., Vt (g)**
**Morse, Fred W. Co., RI** (a,b,c,g,j)
**Murray, A.B. Co., Inc., NJ** (a,b,f,g)
**Murray Tube Works Inc., NJ (g)**
**Narragansett Boiler Works, Inc., RI (g)**
**National Lead Construction Co., Inc., NJ (d)**
**National Metal Products Co., Pa** (a,c,g)
**National Screw & Mfg. Co., Ohio (g)**
**National Steel & Shipbuilding Corp., Calif** (a,g)
**National Tank Co., Okla (a,g)**
**Nigg Engineering Corp., Calif** (a,c,g)
**Olean Electro Plating Co., NY (g)**
**Pabst Engineering Equipment Co., Inc., NJ** (a,c,f,g)
**Parish Pressed Steel Div., Dana Corp., Pa (g)**
**Patterson Foundry & Machine Co., Ohio (a,g)**
**Pennsylvania Engineering Corp., Pa (g)**
**Penrod, Floyd & Sons Tool & Engineering Corp., Ind (g)**
**Pfaudler Co., NY (a,f,g)**
Philadelphia Bronze & Brass Corp., Pa (b)
**Phoenix Iron & Steel Co., Pa (g)**
**Portland Co., Me (a,f,g)**
**Posey Iron Works, Inc., Pa (g)**
**Pressed Steel Tank Co., Wis (a,f,g)**
**Progressive Service Co., Mo (g)**
**Pusey & Jones Corp., Del** (a,b,c,e,f,g)
**Queen Products Co., Inc., Ky (a,g)**
**Rankin Forge Co., Pa (c,g)**
Republic Steel Corp., Ohio (g)
**Reynolds Metals Co., Va (a)**
Rockwell Engineering Co., Ill (a,b,c,g)
**Rockwell-Standard Corp., Stamping Div., NY** (a,b,f,g)—Ad p 458
**Rolock, Inc., Conn (f,g)**
**Rose Iron Works, Ohio (a,b,c,f,g,h)**
**Sandy Hill Iron & Brass Works, NY (b,g)**
**Scaife Co., Pa (a,b,c,f,g)**
**Seattle Boiler Works, Inc., Wash (a,f,g)**
**Shank Metal Products Co., NY (a,g)**
**Sherman & Reilly, Inc., Tenn (a,e,f,g)**

Shriver, T. & Co., Inc., NJ (a,g)
Sinclair Co., Mass (b,c,g)
Sioux City Foundry & Boiler Co., Iowa (g)
Smith, A.O. Corp., Wis (a,g)
South River Metal Products Co., Inc., NJ (a,e,g)
Southern Car & Mfg. Co., Inc., Ala (a,g)
Southwestern Porcelain Steel Corp., Okla (g)
Spincraft, Inc., Wis (a,f,g)
Spring City Foundry Co., Pa (c)
Spuck Iron & Foundry Co., Mo (g)
Stacey Mfg. Co., Ohio (a,g)
Stainless Metals, Inc., NY (c,f,h)
Stalker Corp., Mich (f,g,h)
Standard Steel Sections, Inc., NY (a,c,g)
Stanwood Corp., Ill (g)
Star Heel Plate Co., Inc., NJ (g)
Steel, R. & Sons, Inc., NY (g)
Steel Fabricators Co., Ohio (a,c,e,f,g,h)
Stover Steel Tank & Mfg. Co., Ill (d,f,g)
Struthers Wells Corp., NY (a,f,g,h)
Sylvania Electric Products, Inc., Parts Div., Pa (b,c,f,g)
Texas Foundries, Inc., Tex (g)
Thompson Pipe & Steel Co., Colo (a,b,c,d,e,g,h)
Thys Co., Calif (g)
Toledo Stamping & Mfg. Co., Ohio (g)
Torngren, C.W. Co., Inc., Mass (a,b,c,f,g,h)
Trane Co., Wis (g)
Trojan Steel Co., W.Va (g)
Union Iron Works, Wash (g)
Union Tank Car Co., Ill (a,f,g)
United Shoe Machinery Corp., Mass (a,b,c,e,f,g)
U.S. Valve & Mfg. Co., Calif (g)
Variety Stamping Corp., Ohio (c,g)
Victor Steel Products Corp., NY (g)
Vulcan Mfg., Ohio (a,b,c,e,f,g,h)
Wal-Mar Corp., Ill (a,c,e,g)
Ward, H.H. Co., Pa (a,b,c,f,g,j)
Warren Brothers Roads Co., Mass (a,c,d,e,f,g,j)
Waterman Industries, Inc., Calif (a,g)
Werner, R.D. Co., Inc., NY
West Point Foundry & Machine Co., Ga (c)
Western Foundry & Machine Works, Inc., Kan (g)
Wheeler, C.H. Mfg. Co., Wheelerweld Div., Pa (b,c,f,g)
Whyte, Oliver Co., Inc., NY (a,c,g)
Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp., NY (a,b,c,f,g)
Wilder Mfg. Co., Inc., Calif (c,g)
Willamette Iron and Steel Co., Ore (f,g)
Wisconsin Centrifugal Foundry, Inc., Wis (h)
Woolf Aircraft Products, Inc., Mich (a,c,g)
Wyatt Metal & Boiler Works, Inc., Tex (a,b,c,e,f,g)
Youngstown Kitchens Div., American Standard Co., Ohio (a,g)
Youngstown Welding & Engineering Co., Ohio (a,f,h)

## Wire

Abalon Precision Mfg. Corp., NY (a,b,c,g)
Ace Wire Spring & Form Co., Inc., Pa (g)
Acme Stamping & Wire Forming Co., Pa (a,b,g)
Acme Steel Products Div., Acme Steel Co., Ill (g)
Aerojet-General Corp., Structural Materials Div., Calif (g,h)
Alabama Wire Co., Inc., Ala (a)
Allegheny Ludlum Steel Corp., Pa (g)
All-State Welding Alloys Co., Inc., NY (a)
Almco Steel Products Corp., Ind (g)
Alofs Mfg. Co., Mich (a,g)
Alpha Wire Corp., NY (b)
Aluminum Co. of America, Pa (a)
American Chain & Cable Co., Pa (g)
American Electric Cable Co., Mass (b,c,g)
American Nickel Alloy Mfg. Corp., NY (f)
American Reed Co., Inc., Mass (c)
American Silver Co., NY (b,f,g,h)
American Smelting & Refining Co., NY
American Steel and Wire Div., U. S. Steel Corp., Ohio (b,g)
Anchor Drawn Steel Co., Div. of Vanadium-Alloys Steel Co., Pa (g)
Arcos Corp., Pa (a,b,e,f,h)
Armco Steel Corp., Ohio (g)
Associated Spring Corp., Wallace Barnes Steel Div. Conn (g)
Athenia Steel Div., National-Standard Co., NJ (g)
Atlantic Bag Co., NY (g)
Atlantic Steel Co., Ga (g)
Baker Platinum Div., Engelhard Industries, Inc., NJ (a,b,f,g,h)
Belmont Smelting & Refining Works, Inc., NY (d,j)
Beryllium Corp., Pa (b)
Bethlehem Steel Co., Pa (g)
Bishop, J. & Co. Platinum Works, Pa (f)
Bridgeport Brass Co., Conn (a,b,f)
Bristol Brass Corp., Conn (b)
Cambridge Wire Cloth Co., Md (a,b,c,e,f,g,h)
Carol Cable Co., Div. of Crescent Co., Inc., RI (b)
Carpenter Steel Co., Pa (g)
Carpenter Steel Co., Webb Wire Div., NJ (g)
Chase Brass & Copper Co., Sub. of Kennecott Copper Corp., Conn (a,b,f)
Chicago Development Corp., Md (h)
Clendenin Bros., Inc., Md (a,b)
Colonial Alloys Co., Pa (a)
Colonial Steel Div., Vanadium-Alloys Steel Co., Pa (g)
Colorado Fuel and Iron Corp., Colo (g)
Colorado Fuel & Iron Corp., Pacific Coast Div., Calif (g)
Columbia-Geneva Steel Div., U.S. Steel Corp., Calif (b,g)
Comerford Mfg. Co., Inc., Conn (a,b,c,e,f,g,h,j)
Continental Steel Corp., Ind (g)
Copper and Brass Sales, Inc., Mich (a,b,e)
Crown Metal Co., Wis (d)
Crucible Steel Co. of America, Pa (f,g,h)
Crucible Steel Co. of America, Titanium & Vacuum Metal Products Div., Pa (h)
Curtiss-Wright Corp., Metals Processing Div., NY (g)
Dare Products, Inc., Mich (b,g)
Detroit Steel Corp., Portsmouth Div., Mich (g)
Division Lead Co., Ill (d)
Dow Chemical Co., Magnesium Div., Mich (e)
Driver, Wilbur B. Co., NJ (b,f)
Driver-Harris Co., NJ (f)
Dudek & Bock Spring Mfg. Co., Ill (a,b,g)
Eaton Mfg. Co., Reliance Div., Ohio (a,b,e,g)
Edgcomb Steel & Aluminum Corp., NJ (a,g)
Electric Auto-Lite Co., Ohio (a,b)
Electric Steel Foundry Co., Ore (g)
Electronic Parts Mfg. Co., NJ (b,f)
Elgin National Watch Co., Ill (f)
Empire Metal Co., NY (d)
Erskine Precision Wire Corp., Pa (b,f,g)
Essex Industrial Products Div., Essex Wire Corp., Ind (a,b)
Essex Wire Corp., Magnet Wire Div., Ind (a,b)
Frasse, Peter A. & Co., Inc., NY (a,g)
Fromson Orban Co., Inc., NY (a)
General Alloys Co., Mass (a,b,f,g)
General Cable Corp., NY (a,b)
General Chain & Mfg. Corp., Ohio (g)
General Findings & Supply Co., Industrial Div., Mass (a,b,c,f,g)
Greene, G.G. Corp., Pa (g)
Hawkridge Bros. Co., Mass (a,h)
Hayden Wire Works, Inc., Mass (a,b,c,d,f,g,j)
Haynes Stellite Co., Div. of Union Carbide Corp., Ind (f)
Hazledine, E.T. Co., Ind (g)
HI-Grade Alloy Corp., Ill (d)
Hoskins Mfg. Co., Mich (f,h)
Hudson Wire Co., NY (a,b,j)
Indiana Steel & Wire Co., Inc., Ind (g)
Indium Corp. of America, NY (d)
International Nickel Co., Inc., NY (f)
Jarco Metal Products, NY (g)
Jelliff, C.O. Mfg. Corp., Conn (f)
Johnson Steel and Wire Co., Inc., Mass (g)
Jones & Laughlin Steel Corp., Pa (g)
Kaiser Aluminum & Chemical Sales, Inc., Ill (a)
Kanthal Corp., Conn (c,f)
Kassel Export Co., Inc., NJ (a,b,c,g)
Kelsey-Hayes Co., Metals Div., NY (f)
Keystone Steel & Wire Co., Ill (g)
Laclede Steel Co., Mo (g)
Langsenkamp, F.H. Co., Ind (b)
La Salle Steel Co., Mo (g)
Leach & Garner Co., Mass (b,f)
Lincoln Steel Corp., Neb (g)
**Little Falls Alloys, Inc., NJ** (a,b,h)—Ad p 440
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (a,b,e,g)
Manganese Steel Forge Co., Pa (g)
Matthiessen & Hegeler Zinc Co., Ill (j)
Meico Wire Products, Calif (a)
Metal Goods Corp., Mo (a,b,f)
Metallizing Co. of Los Angeles, Inc., Calif (a,b,c,d,f,g,j)
Mid-States Steel & Wire Co., Ind (g)
Mid-West Wire Products Co., Inc., Mich (g)
National Electric Div., H.K. Porter Co., Pa (a)
National Lead Co., NY (d,h)
National Lock Washer Co., NJ (g)
**National-Standard Co., Mich** (b,c,f,g,h,j)—Ad p 421
Nesor Alloy Products Co., NJ (a,b,c,d,f,g,j)
New England Electrical Works, Inc., NH (b)
Nichols Wire & Aluminum Co., Iowa (a)
Northwestern Steel & Wire Co., Ill (g)
Okonite Co., Sub. of Kennecott Copper Corp., NJ (b)
Olin Mathieson Chemical Corp., Metals Div., NY (a)
**Page Steel & Wire Div., American Chain & Cable Co., Inc., Pa** (g)—Ad p 446
Peerless Wire Goods Co., Inc., Ind (g)
Philadelphia Steel & Wire Corp., Pa (g)
Pittsburgh Steel Co., Pa (g)
Reactive Metals, Inc., Ohio (h)
Republic Steel Corp., Ohio (g)
Revere Copper & Brass Inc., NY (b)
Reynolds Aluminum Supply Co., Ga (a)
Reynolds Metals Co., Va (a)
Riverside-Alloy Metal Div., H. K. Porter Co., Inc., NJ (b,f,g)
Roebling's John A. Sons Div., Colorado Fuel & Iron Corp., NJ (a,b,g)
Rolled Alloys, Inc., Mich (f)
Rolock, Inc., Conn (f)
Ryerson, Joseph T. & Son, Inc., Ill (a,g)
Sandvik Steel, Inc., NJ (g)
Scovill Mfg. Co., Mill Products Div., Conn (b)
Seneca Wire & Mfg. Co., Ohio (g)
Sherman & Reilly, Inc., Tenn (g)
Simonsen Metal Products Co., Ill (a)
South River Metal Products Co., Inc., NJ (a)
Southern Metal Products Co., La (g)
Standard Metals Corp., Mass (b,f)
Star Heel Plate Co., Inc., NJ (a,b,g)
Stulz-Sickles Co., NJ (g)
Superior Mfg. Co., Pa (g)
Surprenant Mfg. Co., Mass (b)
Sylvania Electric Products, Inc., Parts Div., Pa (b,c,f,g)
Techalloy Co., Inc., Pa (f,g,h)
Tennessee Coal and Iron Div., U. S. Steel Corp., Ala (b,g)
Titan Metal Mfg. Co., Pa (b)
Triangle Conduit & Cable Co., Inc., NJ (a,b)
U. S. Steel Corp., Pa (g)

### KEY

**MATERIALS**

a—Aluminum and its alloys
b—Copper and its alloys
c—Iron and its alloys (except steel)
d—Lead and its alloys
e—Magnesium aid its alloys
f—Nickel and its alloys
g—Steels
h—Titanium and its alloys
j—Zinc and its alloys
k—Thermoplastics
l—Thermosetting plastics
m—Elastomers

**BASIC FORMS**

n—Anodes
o—Bar
p—Base resins, polymers or gums
q—Billets
r—Custom formed parts (incl. specialties)
s—Fibers
t—Film
u—Foams (component materials or products)
v—Foil
w—Ingot
x—Laminating, Casting resins
y—Molding compounds
z—Plate
aa—Powder
bb—Rod
cc—Sheet
dd—Strip
ee—Tubing
ff—Wire

United Wire & Supply Corp., RI (a, b)
Uniworld Research Corp. of America, Ohio (c)
Utility Mfg. Co., Mass (a,b,g)
Vanadium-Alloys Steel Co., Pa (g)
Wal-Mar Corp., Ill (a,b,c,e,g)
Washburn Wire Corp., Phillipsdale Div., RI (g)
Washington Mfg. Co., Inc., Iowa (g)
Wesco Spring Co., Ill (g)
White Metal Rolling & Stamping Corp., NY (a,e)
Whitehead Metal Products Co., Inc., NY (a,b,f,g)
Whyte, Oliver Co., Inc., NY (a,g)
Wickwire Brothers, Inc., NY (g)
Wilson Steel & Wire Co., Ill (g)
Worcester Wire Works Div., National-Standard Co., Mass (g,h)
Youngstown Sheet and Tube Co., Ohio (g)

## Wire Cloth

(incl. parts)

Alabama Wire Co., Inc., Ala (a)
American Brass Co., Sub. of Anaconda Co., NY (b)
American Steel and Wire Div., U. S. Steel Corp., Ohio (g)
Arcos Corp., Pa (e,h)
Biersach & Niedermeyer Co., Wis (a, g)
Bishop, J. & Co. Platinum Works, Pa (g)
Buffalo Wire Works Co., Inc., NY (a,b,c,f,g)
Cambridge Wire Cloth Co., Md (a,b, c,d,f,g,h,j)
Chase Brass & Copper Co., Sub. of Kennecott Copper Corp., Conn (a,b,f)
Cleveland Wire Cloth & Mfg. Co., Ohio (a,b,c,f,g,h,j)
Cole-Roscoe Mfg. Co., Conn (b,f,g,h)
Colorado Fuel & Iron Corp., Pacific Coast Div., Calif (g)
Columbia-Geneva Steel Div., U.S. Steel Corp., Calif (g)
Electric Steel Foundry Co., Ore (g)
General Alloys Co., Mass (f)
General Cable Corp., NY (a,b)
Gilbert & Bennett Mfg. Co., Conn (a,g)
Green Bay Foundry & Machine Works, Wis (b,f)
Hewitt-Robins Inc., Conn (g)
Jelliff, C.O. Mfg. Corp., Conn (a,b,c, f,g)
Johnston & Funk Titanium Corp., Ohio (g,h)
Kassel Export Co., Inc., NJ (a,b,f)
Kenmore Machine Products, Inc., NY (f)
Manganese Steel Forge Co., Pa (a,b,c, f)
Metal Goods Corp., Mo (g)
Michigan Wire Cloth Co., Mich (a, b,f,g)
Mid-States Steel & Wire Co., Ind (g)
**National-Standard Co., Mich** (a,b,c,f,g,h,j)—Ad p 421
**Newark Wire Cloth Co., NJ** (a,b,c,f,g,h)—Ad p 454
Pequot Wire Cloth Co., Div. of Hudson Wire Co., Conn (a,b,f,g)
Phoenix Mfg. Co., Ill (g)
Reynolds Wire Div., National-Standard Co., Ill (a,b,c,d,f,g,h,j)
Rolock, Inc., Conn (a,b,f,g)
Rotometals, Calif (a,f)
Seymour Mfg. Co., Conn (b)
Sherman & Reilly, Inc., Tenn (g)
Sherwatt Equipment & Mfg. Co., Inc., NY (a,b,c,e,f,g,h,j)
Sinclair Co., Mass (b,g)
Star Heel Plate Co., Inc., NJ (g)
Star Wire Screen & Iron Works, Inc., Calif (a,b,c,f,g)
Taylor-Wharton Co., Div. of Harsco Corp., NJ (g)
Tennessee Coal and Iron Div., U. S. Steel Corp., Ala (g)
Tyler, W.S. Co., Ohio (a,b,c,f,g)
Unique Wire Weaving Co., Inc., NJ (a,b,c,e,f,g,h)
U. S. Steel Corp., Pa (g)
Uniworld Research Corp. of America, Ohio (c)
Wesbar Stamping Corp., Wis (c,g)
Whitehead Metal Products Co., Inc., NY (a,b,f)
Wickwire Bros., Inc., NY (a,b,g)
Wright, G.F. Steel & Wire Co., Mass (a,b,f,g)

## Wire Forms and Parts

(except cloth)

Abalon Precision Mfg. Corp., NY (a, b,c,g)
Ace Wire Spring & Form Co., Inc., Pa (g)
Acme Stamping & Wire Forming Co., Pa (a,b,g)
All-Form Metal Products Co., Ohio (a,b,c,f,g)
Alox Mfg. Co., Mo (a,b,c,f,g)
Aluminum Co. of America, Pa (a)
American Mfg. Co., Tenn (a,g)
American Metal Products Co., Mich (a,g)
American Reed Co., Inc., Mass (c)
Anthes Div., Gleason Corp., Iowa (g)
Armco Steel Corp., Ohio (g)
**Art Wire & Stamping Co., NJ** (a,b,c,e,f,g,h,j)—Ad p 437
Associated Spring Corp., Wallace Barnes Steel Div., Conn (g)
Automotive Rubber Co., Inc., Mich (f, g)
Bethlehem Steel Co., Pa (g)
Blacher Bros., Inc., RI (b,g)
Blaco Mfg. Co., Ohio (g)
Buffalo Wire Works Co., NY (a,b,f,g)
Cambridge Wire Cloth Co., Md (a,b, f,g)
Cartwright, R. Tube Products Co., Mich (b)
Clendenin Bros. Inc., Md (a,b,g)
Cleveland Metal Products Co., Ohio (a,b,f,g)
Colorado Fuel and Iron Corp., Colo (g)
Colorado Fuel & Iron Corp., Pacific Coast Div., Calif (g)
Columbus Dental Mfg. Co., Ohio (g)
Comerford Mfg. Co., Inc., Conn (a,b, c,e,f,g)
Dare Products, Inc., Mich (g)
Dudek & Bock Spring Mfg Co., Ill (a,b,g)
Eastern Tool & Mfg. Co., NJ (a,b,g)
Electronic Parts Mfg. Co., Inc., NJ (b,f)
Elgin National Watch Co., Ill (f)
Empire Spring Co., Ohio (g)
Farwell Metal Fabricating, Minn (a, b,c,e,f,g)
Figley Die & Stamping Co., Ohio (g)
General Alloys Co., Mass (a,b,f)
General Cable Corp., NY (a)
General Chain & Mfg. Corp., Ohio (g)
General Findings & Supply Co., Industrial Div., Mass (a,b,c,f,g)
Grammes, L.F. & Sons, Inc., Pa (a, b,g)
Greene, G.G. Corp., Pa (g)
Hayden Wire Works, Inc., Mass (g)
Hodges, William & Co., Inc., Pa (g)
Hunter Spring Co., Div. of American Machine & Metals, Inc., Pa (a,b,f, g)
Industrial Precision Products, Ill (a, b,c,e,f,g,h,j)
Judd Industries, Inc., Ohio (a,g)
King Laboratories, Inc., NY (a,f,g)
Kilse Mfg. Co., Mich (b,g)
Laclede Steel Co., Mo (g)
Larkin Specialty Mfg. Co., Calif (a, b,f,g)
Leach & Garner Co., Industrial Div., Mass (a,b,f)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (a,b,e,g)
Meico Wire Products, Calif (a)
Metal Textile Corp., NJ (a,b,c,f,g,h,k)
Mid-West Wire Products Co., Inc., Mich (g)
Morse, Fred W. Co., RI (a,b,g)
Newark Wire Cloth Co., NJ (a,b,f,g,h)
Northwestern Steel & Wire Co., Ill (g)
Ormond Mfg. Co., Inc., NJ (a,b,c,f, g,h)
Parker Metal Goods Co., Mass (a,b,c, g)
Penrod, Floyd & Sons Tool & Engineering Corp., Ind (g)
Pittsburgh Steel Co., Pa (g)
Reliable Spring & Wire Forms Co., Ohio (a,b,e,f)
Republic Steel Corp., Ohio (g)
Reynolds Wire Div., National-Standard Co., Ill (a,b,e,f)
Riverside-Alloy Metal Div., H.K. Porter Co., Inc., NJ (b,f,g)
Robertson Steel & Iron Co., Ohio (a, b,g)
Rockford Bolt & Steel Co., Ill (g)
Roebling's, John A. Sons Div., Colorado Fuel & Iron Corp., NJ (g)
Rolock Inc., Conn (a,b,f,g)
Scovill Mfg. Co., Mill Products Div., Conn (a,b,c,f,g)
Serwell Products Co., Ohio (f)
Simonsen Metal Products Co., Ill (a)
Star Heel Plate Co., Inc., NJ (g)
Steel Heddle Mfg. Co., Pa (a,b,c,e,f, g)
Superior Mfg. Co., Pa (a,c,g,j)
Sylvania Electric Products, Inc., Parts Div., Pa (a,b,c,d,f,g)
Titchener, E.H. & Co., NY (a)
Turner & Seymour Mfg. Co., Conn (a, b,g)
United Wire & Supply Corp., RI (a,b)
U.S. Steel Supply Div., U.S. Steel Corp., Ill (g)
Wal-Mar Corp., Ill (a,b,c,g)
Ward, H.H. Co., Pa (a,b,c,f,g,j)
Washington Mfg. Co., Iowa (g)
Waterbury Buckle Co., Conn (a,b,g)
Wesco Spring Co., Ill (g)
Whyte, Oliver Co., Inc., Mass (g)
Wilder Mfg. Co., Inc., Calif (a,b,g)
Wire and Iron Products, Inc., Mich (a,b,c,f,g)
Wood, John Co., Minn (g)
Worth Co., Wis (a,b,e,g)

## Wood—Balsa

Balsa Equador Lumber Corp., NY
Bogert & Hopper, Inc., NY
Emery, George D. Co., NY
Foss Mfg. Co., Id
Gamble Brothers, Inc., Special Products Div., Ky
General Veneer Mfg. Co., Calif
International Balsa Corp., NJ
Monteath, J.H. Co., NY
Pollack, Robert Co., Calif
Sterling Models, Pa
Technical Ply-Woods Sales, Ill
Testor Chemical Co., Ill

## Wood—Composition Board

Allied Chemical Corp., Plastics & Coal Chemicals Div., NY
Armstrong Cork Co., Pa
Artyle Industries, Inc., Ohio
Balsa Equador Lumber Corp., NY
Celotex Corp., Ill
Diamond Lumber Co., Ore
Gamble Brothers, Inc., Special Products Div., Ky
Georgia-Pacific Corp., Ore
Hardboard Div., Evans Products Co., Ore
Johns-Manville Corp., NY
Long-Bell Div., International Paper Co., Wash
Masonite Corp., Ill
National Starch & Chemical Corp., Structural Products Div., NY
Reynolds Aluminum Supply Co., Ga
Roddis Plywood Corp., Wis
Simpson Timber Co., Wash
Technical Ply-Woods Sales, Ill
U. S. Gypsum Co., Ill
Wal-Mar Corp., Ill
West Virginia Pulp & Paper Co., NY
Weyerhaeuser Timber Co., Silvatek Products Div., Wash

## Wood—Impregnated and/or Compressed

American Polyglas Corp., NJ
Armstrong Cork Co., Pa
Diamond Lumber Co., Ore
Everlite Corp., Wash
Fibron Products, Inc., NY
Formica Corp., Sub. of American Cyanamid Co., Ohio
Gamble Brothers, Inc., Special Products Div., Ky
Georgia-Pacific Corp., Ore
Hardboard Div., Evans Products Co., Ore
Micarta Div., Westinghouse Electric Corp., SC
Parkwood Laminates, Inc., Mass
Permali, Inc., Pa
Ren Plastics Inc., Mich
Reynolds Aluminum Supply Co., Ga
Simpson Timber Co., Wash
Technical Ply-Woods Sales, Ill
West Virginia Pulp & Paper Co., NY
Wood Conversion Co., Minn

## Wood—Lignum Vitae

Lignum-Vitae Products Corp., NJ

## Wood—Plywood

American Plywood Div., Curtis Cos., Inc., Wis
Artyle Industries, Inc., Ohio
Balsa Equador Lumber Corp., NY
Darlington Veneer Co., SC
Delta Plywood Corp., Ark
Diamond Lumber Co., Ore
Gamble Brothers, Inc., Ky
Georgia-Pacific Corp., Ore
Long-Bell Div., International Paper Co., Wash
Nu-Ply Corp., Minn
Puget Sound Plywood, Inc., Wash
Reynolds Aluminum Supply Co., Ga
Roddis Plywood Corp., Wis
Simpson Timber Co., Wash
Technical Ply-Woods Sales, Ill
Timber Products Co., Ore
U. S. Plywood Corp., NY
West Virginia Pulp & Paper Co., NY

## Wool Felts

(see Felts)

## Wrought Iron

(see Iron)

## Zinc and Its Alloys

Advance Stamping Co., Mich (dd)
Allied Research Products, Inc., Md (n)
Alpha Metals, Inc., NJ (v)
American Metal Climax, Inc., NY (o,w)

American Nickel Alloy Mfg. Corp., NY (q,w)
American Silver Co., NY (v,dd)
American Smelting & Refining Co., NY (n,v,w)
American Zinc Sales Co., Mo (n,o,q,w,z)
Anchor Metal Co., Inc., NY (w)
Apex Smelting Co., Ill (w)
Belmont Smelting & Refining Works, Inc., NY (n,o,v,w,z,aa,bb,cc,dd,ff)
Bunker Hill Co., Calif (n,o,z,cc,dd)
Cerro de Pasco Sales Corp., NY (w)
Chicago Smelting & Refining Corp., Ill (w)
Clark Perforating Co., Mich (cc)
Dixon Sintaloy, Inc., Conn (o)
Duane Specialties, Ltd., NJ (w)
Eagle-Picher Co., Ohio (g,aa)
Empire Metal Co., NY (n,o,q,v,w,z,bb,cc,dd,ff)
Federated Metals Div., American Smelting & Refining Co., NY (n,w)
Fox Products Co., Pa (n)
General Smelting Co., Pa (n,w,aa)
Hardy, Charles, Inc., NY (aa)
Harshaw Chemical Co., Ohio (n)
Hayden Wire Works, Inc., Mass (ff)
Hi-Grade Alloy Corp., Ill (n,o)
Hodgson Foundry Co., Ill (n)
Hull, R.O. & Co., Inc., Ohio (n)
Illinois Smelting & Refining Co., Ill (o,w,z,aa,bb,cc,dd)
Illinois Zinc Co., Div. of Hydrometals, Inc., Ill (w,z,bb,cc,dd)
International Minerals and Metals Corp., NY (w)
Jordan Co., Ill (w)
Kirk, Morris P. & Son, Calif (n)
Lavin, R. & Sons, Inc., Ill (n,w)
Matthiessen & Hegeler Zinc Co., Ill (n,o,q,v,w,z,aa,bb,cc,dd)
McGean Chemical Co., Ohio (n,o,aa)
Metallizing Engineering Co., Inc., NY (ff)
Metallizing Co. of Los Angeles, Inc., Calif (ff)
Metals Disintegrating Co., Inc., NJ (aa)
Modern Plating Corp., Ill (n)
National Galvanizing Co., Pa (w)
National Lead Co., NY (n,o,q,w,z,bb,cc,dd,ee)
Nesor Alloy Products Co., NJ (ff)
New England Smelting Works, Inc., Mass (o,w)
New Jersey Metals Co., NJ (n)
**New Jersey Zinc Co., NY** (n,w,z,aa,dd)—Ad pp 452-453
Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (v,w)
Peerless Alloy Co., Colo (o,w)
Pittsburgh Smelting & Refining Co., Pa (w)
Republic Metals Co., Inc., NY (n,o,w)
Rotometals, Calif (n,o,w,aa,bb,cc,dd,ff)
St. Joseph Lead Co., NY (w)
Sall, George Metals Co., Inc., Pa (n,w)
Security Sash & Screen Co., Mich (cc)
Stevens, Frederic B., Inc., Mich (n)
Udylite Corp., Mich (n)
U. S. Reduction Co., Ind (w)
U. S. Smelting, Refining & Mining Co. NY (w)
Wall Colmonoy Corp., Mich (aa)
White Metal Rolling & Stamping Corp., NY (o,bb,ff)
Whitehead Metal Products Co., Inc., NY (cc,dd,ee)

## Zirconium and Its Alloys

Allegheny Ludlum Steel Corp., Pa (o,q,v,w,z,bb,cc,dd,ee,ff)
American Silver Co., NY (v,dd,ee,ff)
Arcos Corp., Pa (ff)
Babcock & Wilcox Co., Tubular Products Div., Pa (ee)
Belmont Smelting & Refining Works, Inc., NY (aa)
Bishop, J. & Co. Platinum Works, Pa (ee)
Bridgeport Brass Co., Conn (ee)
Brooks & Perkins, Inc., Mich
Carborundum Co., NY (o,q,r,v,w,z,bb,cc,dd,ee,ff)
**Carborundum Metals Co., NY** (o,q,v,w,z,aa,bb,cc,dd,ee,ff)
Carpenter Steel Co., Alloy Tube Div., NY (ee)
Chase Brass & Copper Co., Sub. of Kennecott Copper Corp., Conn (ee)
Columbia National Corp., Pa (w)
Crucible Steel Co. of America, Pa (ee)
Damascus Tube Co., Pa (ee)
Electric Steel Foundry Co., Ore (o,q,w,bb,ee)
Foote Mineral Co., Pa (o,v,aa,bb,cc,ff)
General Electric Co., Metallurgical Products Dept., Mich (q,w,aa,bb,cc,dd)
Hamilton Watch Co., Precision Metals Div., Pa (v,bb,cc,ff)
Hardy, Charles, Inc., NY (aa)
Harvey Aluminum, Calif (o,q,v,w,z,bb,cc,dd,ee,ff)
Hayden Wire Works, Inc. Mass (aa)
Johnston & Funk Titanium Corp., Ohio (bb,ff)
King Laboratories, Inc., NY (aa)
Makepeace, D.E. Div., Engelhard Industries, Inc., Mass (a,dd,ee,ff)
Metal Forming Corp. Div., Vanadium-Alloys Steel Co., Pa (ee)
Metal Hydrides, Inc., Mass (aa)
Metallizing Co. of Los Angeles, Inc., Calif (cc,ff)
Michigan Seamless Tube Co., Mich (ee)
National Lead Co., NY (o,q,w,z,bb,cc,dd)
Niagara Falls Smelting & Refining Div., Continental Copper & Steel Industries, Inc., NY (w)
Nuclear Metals, Inc., Mass (w,bb,dd,ee,ff)
Oregon Metallurgical Corp., Ore (w,ee)
Reactive Metals, Inc., Ohio (o,q,v,w,z,bb,cc,dd,ee,ff)
Republic Steel Corp., Steel & Tubes Div., Ohio (ee)
Rodney Metals, Inc., Mass (v)
Superior Steel Corp., Pa (dd)
**Superior Tube Co., Pa** (ee)—Ad pp 414-415
Texas Instruments, Inc., Metals & Controls Div., Mass (v,cc,dd,ee,ff)
Trent Tube Co., Sub. of Crucible Steel Co. of America, Pa (ee)
Tube Reducing Corp., NJ (ee)
**Wah Chang Corp., NY** (w)—Ad p 164
Westinghouse Electric Corp., Materials Mfg. Dept., Pa (o,q,w,z,bb,cc,dd,ee)
**Zirconium Metals Corp., Sub. of National Lead Co., NY** —Ad p 430

# Addresses of Suppliers

## a

A & A Die Casting Co., 12901 S Western Ave., Gardena, Calif.
ACF Industries, Inc., 30 Church St., New York 8, N.Y.
American Car & Foundry Div., 750 3d Ave., New York 17, N.Y.
aaRBee Plastic Co., 4505 W Jefferson Blvd., Los Angeles 16, Calif.
Abalon Precision Mfg. Corp., 540 Casanova St., New York 59, N.Y.
Abbott Ball Co., 1074 New Britain Ave., Hartford 10, Conn.
Abbott Products, Inc., 150-50 12th Ave., Whitestone 57, N.Y.
Abco Aluminum & Brass Works, 5235 Griggs Rd., Houston 21, Tex.
Abegg & Reinhold Co., 2533 E 26th St., Los Angeles 58, Calif.
Able Tool & Engineering Co., 865 N Sangamon St., Chicago 22, Ill.
Accurate Anodizing Corp., 4100 W Lake St., Chicago 24, Ill.
Accurate Die Casting Co., 3089 E 80th St., Cleveland 4, Ohio
Accurate Metal Weather Strip Co., Inc., 725 S Fulton Ave., Mt. Vernon, N.Y.
Accurate Molding Corp., 35-20 48th Ave., Long Island City 1, N.Y.
Ace Metal Spinning, 4922 S Western Ave., Chicago 9, Ill.
Ace Plastic Co., 91-30 Van Wyck Expy., Jamaica 35, N.Y.
Ace Wire Spring & Form Co., Inc., Tunnel Way, McKees Rocks, Pa.
Acheson Colloids Co., 1635 Washington, Pt. Huron, Mich.
Ackermann Mfg. Co., 1134-40 Market St., Wheeling, W. Va.
Acme Aluminum Foundry Co., 6831 S Bell Ave., Chicago, Ill.

Acme Foundry & Machine Co., Coffeyville, Kan.
Acme Foundry & Machine Co., 400 E Erisco, Blackwell, Okla.
Acme Galvanizing Co., 1733 17th St., Oakland 7, Calif.
Acme Mfg. & Gasket Co., 738-40 N 41st St., Philadelphia 4, Pa.
Acme Metal Spinning, Inc., 98 43rd Ave., NE, Minneapolis 21, Minn.
Acme Plating Co., 1563 E 21st St., Cleveland 14, Ohio
Acme Precision Products, Inc., 215 N Findlay St., Dayton 3, Ohio
Acme Resin Corp., 1401 Circle Ave., Forest Park, Ill.
Acme Specialties, Inc., 4326 N American St., Philadelphia 40, Pa.
Acme Stamping & Wire Forming Co., 201-209 Corliss St., Pittsburgh 20, Pa.
Acme Steel Co., Acme Steel Products Div., 135th St. & Perry Ave., Chicago 27, Ill.
Acme Steel & Malleable Iron Works, Buffalo 7, N.Y.
Acme Tube, Inc., 212 Colt St., Irvington 11, N.J.
Acme-Newport Steel Co., 9th & Lowell Sts., Newport, Ky.
Acorn Sheet Metal Mfg. Co., Inc., 4605 W 21st St., Chicago 50, Ill.
Acro Metal Stamping Co., 332 E Reservoir, Milwaukee 12, Wis.
**Acushnet Process Co. (Ad p 448)**
Belleville Ave., New Bedford, Mass.
Adams Engineering Co., Inc., 19300 Biscayne Blvd., Miami, Fla.
Adams, I. G., Metalware Co., 2947 Delmar Pl., St. Louis, Mo.
Adams Plastic Products, Finlay & Providence Sts., Cincinnati, Ohio
Adhesive Products Corp., 1660 Boone Ave., New York 60, N.Y.
Adirondack Steel Casting Co., Watervliet, N.Y.
Admiral Corp., Molded Prods. Div., P.O. Box 338, West Chicago, Ill.
Advance Aluminum Castings Corp., 2742 W 36th Place, Chicago 32, Ill.
Advance Foundry Co., 107 Seminary Ave., Dayton, Ohio
Advance Galvanizing Co., 5332 Alcoa Ave., Los Angeles 58, Calif.
Advance Pressure Castings, Inc., 20 Wythe Ave., Brooklyn 11, N.Y.
Advance Screw Products Co., Inc., 3767 S Kinnickinnic Ave., Milwaukee 7, Wis.
Advance Stamping Co., 12025 Dixie Ave., Detroit 39, Mich.
Advance Tool & Die Casting Co., 3760 N Holton St., Milwaukee 12, Wis.
Aelco Foundries, Inc., 1980 S 4th St., Milwaukee 4, Wis.
Aerojet-General Corp., Structural Materials Div., 6352 N. Irwindale St., Azusa, Calif.
Aerolite Electronics Corp., 2207 Summit Ave., Union City, N.J.
Aerolite Extrusion Co., 4605 Lake Park, Youngstown, Ohio
Aetna Felt Co., Inc., 204 Centre St., New York 13, N.Y.
Aetna Steel Co., P.O. Box 2090, Jacksonville 3, Fla.
Affiliated Screw Products Co., 3800 Wesley Terrace, Schiller Park, Ill.
African Metals Corp., 25 Broad, New York 4, N.Y.
Air Reduction Co., Inc., 150 E 42nd St., New York 17, N.Y.
Air Reduction Chemical Co. Div., 150 E 42nd St., New York, N.Y.
Air Reduction Sales Co., 150 E 42nd St., New York 17, N.Y.
Colton Chemical Co., 1747 Chester Ave., Cleveland 14 Ohio
Akron Porcelain Co., 2723 Cory Ave., Akron 14, Ohio
Akron Standard Mold Co., Lecromelt Casting Div., Houston St., Barberton, Ohio
Alabama Metallurgical Corp., P.O. Box 38, Selma, Ala.
Alabama Wire Co., Inc., Terrace St., Florence, Ala.
Aladdin Transparent Packaging Corp., 608 Main St., Westbury, N.Y.
Alan Wood Steel Co., Wood Rd., Conshohocken, Pa.
Albany Car Wheel Co., Inc., 185 Broadway, Menends, N.Y.
Albany Felt Co., Broadway, Albany 1, N.Y.
Albany Novelty Mfg. Co., 107 W Canton St., Boston 18, Mass.
Albany Products Co., Inc., 351 Connecticut Ave., South Norwalk, Conn
Albert Lea Foundry Co., 910 Marshall Ave., Albert Lea, Minn.
Albert Pipe Supply Co., Inc., 101 Varick Ave., Brooklyn 37, N.Y.
Albion Malleable Iron Co., 601 N Albion St., Albion, Mich.
Albraco Metals Corp., 649 Van Sinderen Ave., Brooklyn 7, N.Y.
Albright Son & Co., 123 N Front St., Allentown, Pa.
Alcasco Foundry, 14823 Loomis Ave., Harvey, Ill.
Alchemize Corp., 625 S Kolmar Ave., Chicago 24, Ill.
Alco Products, Inc., 30 Church St., New York, N.Y.
Alcylite Plastics & Chemical Corp., 23874 N Pine St., Newhall, Calif.
Aldan Rubber Co., Tioga & Salmon Sts., Philadelphia 34, Pa.
Alexander Bros. Belting Co., Franklin & Suffolk, Worcester, Mass.
Alexander, E. P. & Son, Clifton Heights, Pa.
Allegheny Foundry Co., 915 Bingham St., Pittsburgh 33, Pa.
**Allegheny Ludlum Steel Corp. (Ad p 87)**
Oliver Bldg., Pittsburgh 22, Pa.
Allegheny Plastics, Inc., Rt. 51 & Thorn Run Rd., Coraopolis, Pa.
Allen Mfg. Co., Drawer 570, Hartford 1, Conn
Allen-Stevens Corp., 33-53 62nd St., Woodside 77, N.Y.
All-Form Metal Products Co., 13000 Athens Ave., Cleveland 7, Ohio
AllianceWare, Inc., AllianceWall Div., Box 809, Alliance, Ohio
Allied Chemical Corp., 61 Broadway, New York 6, N.Y.
Plastics & Coal Chemicals Div., 40 Rector St., New York 6, N.Y.
**Solvay Process Div. (Ad p 349)**
61 Broadway, New York 6, N.Y.
Allied Machine Products Co., 6174 Concord Ave., Detroit 11, Mich.
Allied Metal Products Co., 81 Prescott St., Worcester 6, Mass.
Allied Products Corp., 12677 Burt Rd., Detroit 23, Mich.
**Allied Research Products, Inc. (Ad p 358)**
4004 W Monument St., Baltimore 5, Md.
Allied Resinous Products, Inc., Clark & Whitney Sts., Conneaut, Ohio
Allied Steel Castings Co., 1225 W 120th St., Chicago 43, Ill.
Allied Tube Corp., Bristol & Bath Sts., Philadelphia 37, Pa.
Allis-Chalmers Mfg. Co., 501 N 3rd St., La Crosse, Wis.
Allmetal Screw Products Co., Inc., 821 Stewart Ave., Garden City, N.Y.
All-Metals Precision Casting Corp., 22 School St., Yonkers, N.Y.
Alloy Cast Steel Co., Rose Ave., Marion, Ohio
Alloy Engineering & Casting Co., 1700 W Washington St., Champaign, Ill.
Alloy Metal Powders, Inc., 238 Eagle St., Brooklyn, N.Y.
Alloy Metal Products Inc., 2333 Rockingham Rd., Davenport, Iowa
Alloy Metal Wire Co., Inc., Moore Station, Prospect Park, Pa.
Alloy Precision Castings Co., 3857 W 150th St., Cleveland 11, Ohio
Alloy Products Corp., 1045 Perkins Ave., Waukesha, Wis.
Alloy Rods Co., Lincoln Hwy. W, York, Pa.
Alloy Steel Casting Co., County Line Rd., Southampton, Pa.
Alloy Steel & Metals Co., 1848 E 55th St., Los Angeles 58, Calif.
Alloy Surfaces Co., Inc., 100 S Justison St., Wilmington 1, Del.
Alloys & Chemicals Mfg. Co., Inc., 4365 Bradley Rd., SW, Cleveland 9, Ohio
All-State Welding Alloys Co., Inc., 249 Ferris Ave., White Plains, N.Y.
Almco Steel Products Corp., Wabash Ave., Bluffton, Ind.
Almont Mfg. Co., 335 E 3rd St., Imlay City, Mich.
Alofs Mfg. Co., 345 32nd St. SW, Grand Rapids 8, Mich.
Alox Mfg. Co., 6160 Maple Ave., St. Louis 14, Mo.
Alpha Metals, Inc., 56 Water St., Jersey City, N.J.
Alphaloy Corp. Div., 2250 S Lumber St., Chicago, Ill.
Alpha Plastics, Inc., 78 Okner Pkwy., Livingston, N.J.
Alpha Wire Corp., 200 Varick St., New York 14, N.Y
Alpha-Molykote Corp., 65 Harvard Ave., Stamford, Conn.
Alsynite Co. of America, 4654 De Soto St., San Diego 9, Calif.
Alten Foundry & Machine Works, Inc., 2000 W Wheeling St., Lancaster, Ohio
Aluminium Ltd. Sales, Inc., 630 5th Ave., New York 20, N.Y.
Aluminum Alloys Corp., 6650 W Walton Ave., Detroit 10, Mich.
Aluminum Billets, Inc., 3786 Oakwood Ave., Youngstown, Ohio
Aluminum Casting & Engineering Co., 2039 S Lenox St., Milwaukee 7, Wis.
**Aluminum Co. of America (Ad pp 423-424)**
1501 Alcoa Bldg., Pittsburgh 19, Pa.
Industrial Foil Div., 1655-E Alcoa Bldg., Pittsburgh 19, Pa.
Aluminum Extrusions, Inc., 815 Shepherd St., Charlotte, Mich.
Aluminum Finishing Corp., 1012 E 21st St., Indianapolis 2, Ind.
Aluminum Foils Co., P.O. Box 540, Jackson, Tenn.
Aluminum Goods Mfg., Manitowoc, Wis.
Aluminum Industries, Inc., 3670 Werk Rd., Cincinnati, Ohio
Aluminum & Magnesium, Inc., 1 Huron St., Sandusky, Ohio
Aluminum Permanent Mold Co., 1054 Front Ave., NW, Grand Rapids 4, Mich.
Aluminum Specialty Co., 16th & Wollmer Sts., Manitowoc, Wis.
Amalgamated Steel Corp., 7835 Broadway Ave., Cleveland 5, Ohio
Ambassador Plastics & Mfg. Corp., 308 W Erie, Chicago 10, Ill.
Ambrit Industries, Inc., 1288 Los Angeles St., Glendale 4, Calif.
Amchem Products, Inc., Ambler, Pa.
Amco Plastic Pipe Co., 2002 Davis St., San Leandro, Calif.
Amerace Corp., 200 W 42nd St., New York, N.Y.
American Hard Rubber Co. Div., Ace Rd., Butler, N.J.
Supplex Co. Div., 225 North Ave., Garwood, N.J.
Amercoat Corp., 4809 Firestone Blvd., South Gate, Calif.
American Agile Corp., 5461 Dunham Rd., Maple Heights, Ohio
American Aluminum Co., 230 Sheffield St., Mountainside, N.J.
American Aluminum Casting Co., 300 Colt St., Irvington 11, N.J.
American Asbestos Textile Corp., Stanbridge St., Norristown, Pa.
American Brake Shoe Co., 530 5th Ave., New York 36, N.Y.
American Brakeblok Div., 900 W Maple Rd., Troy, Mich.
American Manganese Steel Div., 389 E 14th St., Chicago Heights, Ill.
Amforge Div., 1220 W 119th St., Chicago 43, Ill.
Brake Shoe & Castings Div., 230 Park Ave., New York, N.Y.
Electro-Alloys Div., Taylor St. & Abbe Rd., Elyria, Ohio
Engineered Castings Div., Mountain Read Rd. & NYCRR, Rochester 11, N.Y.
Light Metals Dept., Railroad Ave., Mahwah, N.J.
National Bearing Div., 717 Grant Bldg., Pittsburgh 19, Pa.
American Can Co., Plastics Div., 100 Park Ave., New York, N.Y.
**American Cast Iron Pipe Co. (Ad p 410)**
2930 16th St. N, Birmingham, Ala.
American Chain & Cable Co., Inc., Reading, Pa.
Acco Steel Casting Div., Tulpehocken St., Reading, Pa.
American Chain Div., 454 E. Princess St., York, Pa.
**Page Steel & Wire Div. (Ad p 446)**
Box 692, Monessen, Pa.
American Crucible Products Co., 1319 Oberlin Ave., Lorain, Ohio
American Cyanamid Co., 30 Rockefeller Plaza, New York 20, N.Y.
Formica Corp. Sub., 4614 Spring Grove Ave., Cincinnati 32, Ohio
**Plastics & Resins Div. (Ad pp 251-254)**
30 Rockefeller Plaza, New York 20, N.Y.
American Electric Cable Co., 181 Appleton St., Holyoke, Mass.
American Electrical Products Co., P.O. Box 200, 653 Lida St., Mansfield, Ohio
American Emblem Co., Inc., P.O. Box 116, Utica 1, N.Y.
American Enka Corp., William Brand-Rex Div., 31 Sudbury Rd., Concord, Mass.
American Fabricated Products Co., 1420 E 20th St., Indianapolis 7, Ind.
**American Felt Co. (Ad p 312)**
Glenville, Conn.
American Forge & Mfg. Co., P.O. Box 20, McKees Rocks, Pa.
American Foundries Co., 330 2nd St., Milan, Mich.
American Foundry Co., Inc., 1100 S Fibles Ave., Indianapolis 21, Ind.
American Insulator Corp., New Freedom, Pa.
American Latex Products Corp., 3341 W El Segundo Blvd., Hawthorne, Calif.
American Laundry Machinery Co., Rochester, N.Y.
American Lava Corp., Cherokee Blvd. & Mfrs. Rd., Chattanooga 5, Tenn.
American Light Alloys, Inc., 1265 McBride Ave., Little Falls, N.J.
American Machine & Foundry Co., Cleveland Welding Div., W 117th St., Cleveland 11, Ohio
American Machine & Metals Inc., Hunter Spring Co. Div., 1 Spring Ave., Lansdale, Pa.
American Malleable Castings Co., Marion, Ohio
American Manganese Bronze Co., Rhawn & Torresdale Aves., Philadelphia 36, Pa.

Addresses of Suppliers

American Mannex Corp., Easton Metal Powder Co. Div., 900 Line St., Easton, Pa.
American Mfg. Co., 124 Chestnut, Chattanooga 2, Tenn.
American Metal Climax, Inc., 1270 Ave. of the Americas, New York 20, N.Y.
**Amco Div. (Ad pp 165-168)**
61 Broadway, New York 6, N.Y.
Climax Molybdenum Div., 500 Fifth Ave., New York 36, N.Y.
American Metal Products Co., 5959 Linsdale Ave., Detroit 4, Mich.
American Metal Products, Inc., 4500 W Mitchell Ave., Cincinnati 32, Ohio
American Metallurgical Products Co., P.O. Box 11068, Pittsburgh 37, Pa.
American Metaseal Corp., 607 65th St., West New York, N.J.
American Molding Co., 2002 Davis St., San Leandro, Calif.
American Molding Powder & Chemical Co., 703 Bedford Ave., Brooklyn 8, N.Y.
American Nickel Alloy Mfg. Corp., 30 Vesey St., New York 7, N.Y.
American Nickeloid Co., 2nd & West Sts., Peru, Ill.
American Pipe & Construction Co., Northwest Div., 518 N E Columbia Blvd., Portland 11, Ore.
American Plastics Corp., 342 Madison Ave., New York 17, N.Y.
American Platinum Works, Newark 5, N.J.
American Polyglas Corp., Broad & 14th Sts., Carlstadt, N.J.
American Potash & Chemical Corp., 3000 W 6th St., Los Angeles 54, Calif.
Lindsay Chemical Div., 258 Ann St., West Chicago, Ill.
American Powdered Metals, Inc., 7-9 Philip Pl., North Haven, Conn.
American Products Corp., 525 S Dearborn St., Chicago 5, Ill.
American Products Mfg. Co., Inc., 8127-33 Oleander St., New Orleans 18, La.
American Reed Co., Inc., 2 S Broadway, Lawrence, Mass.
American Rubber Products Corp., 315 Brighton St., LaPorte, Ind.
American Sanitary Mfg. Co., Box 111, Abingdon, Ill.
American Screw Co., W Main St., Willimantic, Conn.
American Screw Products Co., 5943 Martin Ave., P. O. Box 96, Detroit 10, Mich.
American Sealants Co., 103 Woodbine St., Hartford 6, Conn.
American Sheet Metal Works, Inc., 16 Jefferson St., Waterbury 20, Conn.
American Silver Co., Inc., 36-07 Prince St., Flushing 54, N.Y.
American Sinteel Corp., 1019 Saw Mill River Rd., Yonkers, N.Y.
American Smelting & Refining Co., 120 Broadway, New York 5, N.Y.
**Continuous Cast Products Div. (Ad pp 432-433)**
1160 State St., Barber, N.J.
**Federated Metals Div. (Ad p 173)**
120 Broadway, New York 5, N.Y.
**Lake Asbestos of Quebec, Ltd., Sub. (Ad pp 316-317)**
120 Broadway, New York 5, N.Y.
American Solder & Flux Co., 19th & Willard Sts., Philadelphia 40, Pa.
American Stamping Co., 26650 Lakeland Blvd., Cleveland 32, Ohio
American Standard Co., Youngstown Kitchens Div., Ellsworth Ave., Salem, Ohio
American Steel Foundries, Prudential Plaza, Chicago 1, Ill.
American Steel & Pump Corp., Oklahoma Steel Castings Div., 1200 N Peoria Ave., Tulsa, Okla.
American Synthetic Rubber Corp., 500 5th Ave., New York 36, N.Y.
American Tape Co., 4058 Beaufait Ave., Detroit 7, Mich.
American Tinning & Galvanizing Co., 552 W 12th St., Erie, Pa.
American Valve & Enameling Corp., 2855 S Holt Rd., Indianapolis 41, Ind.
**American Viscose Corp. (Ad p 313)**
1617 Pennsylvania Blvd., Philadelphia 3, Pa.
American Welding and Mfg. Co., 100 Dietz Rd., Warren, Ohio
American Zinc Sales Co., 1522 Paul Brown Bldg., St. Louis 1, Mo.
American-Marietta Co., 101 E Ontario St., Chicago 11, Ill.
Adhesive, Resin & Chemical Div., 3400 13th Ave., SW, Seattle 4, Wash.
Booty Resineers Div., 42 S 3rd St., Newark, Ohio
Presstite Div., 3738 Chouteau Ave., St. Louis, Mo.
Sierra Metals Corp. Sub., 12th St. & W Strong Ave., Wheeling, Ill.
Ames, W. & Co., 417 Communipaw Ave., Jersey City 4, N.J.
Amos-Thompson Corp., Amos Molded Plastics Div., Edinburg, Ind.
Ampco Metal, Inc., 1753 S 38th St., Milwaukee 46, Wis.
Anaconda Co., 25 Broadway, New York 4, N.Y.
American Brass Co., 25 Broadway, New York 4, N.Y.
Anaconda Metal Hose Div., 698 S Main St., Waterbury 20, Conn.
Anaconda Aluminum Co., P.O. Box 1654, Louisville 1, Ky.
Anchor Hocking Glass Corp., Lancaster, Ohio
Anchor Metal Co., Inc., 966 Meeker Ave., Brooklyn 22, N.Y.
Anchor Metal Spinning Co., 46 Fluhart Ave., Dayton 8, Ohio
Anchor Plastics Co., 36-36 36th St., Long Island City 6, N.Y.
Anderson, O.L. Co., Inc., 1347 E Fort St., Detroit 7, Mich.
Anderson Assoc., Inc., 1702 Wayne St., Toledo 1, Ohio
Anderson-Bolling Mfg. Co., Grand Haven, Mich.
Anesite Co., 3575 Touhy Ave., Chicago 45, Ill.
Anti-Corrosive Metal Products Co., Inc., Castleton-on-Hudson, N.Y.
Apex Foundry, Inc., 633 Lycaste Ave., Detroit 14, Mich.
Apex Smelting Co., 2537 W Taylor St., Chicago 12, Ill.
Apex Steel Corp., Ltd., 6920 E Slauson, Los Angeles 22, Calif.
Apollo Metal Works, 6852 S Oak Park Ave., Chicago, Ill.
Appleton Electric Co., 1701 W Wellington Ave., Chicago 13, Ill.
Applied Instruments, Inc., 25 Will Pl., Brooklyn 7, N.Y.
Approved Mfg. Co., Inc., 30?990 W 8th Mile Rd., Farmington, Mich.
Arabol Mfg. Co., 110 E 42nd St., New York 17, N.Y.
Arbonite Corp., 900 N Main St., Doylestown, Pa.
Archer-Daniels-Midland Co., 700 Investors Bldg., Minneapolis, Minn.
Arcos Corp., 1500 S 60th St., Philadelphia 43, Pa.
Ardmore Products, Inc., 194 Aldene Rd., Roselle, N.J.
Argosy Products, Inc., 7504 Carnegie Ave., Cleveland 3, Ohio
Aries Laboratories, Inc., 225 Greenwich Ave., Stamford, Conn.
Arkansas Foundry Co., 1423 E 6th St., Box 231, Little Rock, Ark.
Armco Steel Corp., 703 Curtis St., Middletown, Ohio
Fabricating Div., Middletown, Ohio
Sheffield Div., Sheffield Sta., Kansas City 25, Mo.
Armet Alloys, Inc., 4338 Bradley Rd., Cleveland 9, Ohio
Armitage, J. L. & Co., 245 Thomas St., Newark, N.J.
Armor Galvanizing Works, Inc., 580 Market St., San Francisco 4, Calif.
Armor Metal Products Co., 3408 Beekman, Cincinnati 23, Ohio
Armour & Co., Adhesive Div., 1355 W 31st St., Chicago, Ill.
Armstrong Cork Co., West Liberty St., Lancaster, Pa.
Armstrong Products Co., P.O. Box 1-MM, Warsaw, Ind.
Arneson Foundry Co., 3303 66th St., Kenosha, Wis.
Arnold Engineering Co., P.O. Box G, Marengo, Ill.
Arrow Metal Products Corp., 3rd Ave., Haskell, N.J.
Arrow Sintered Products Co., 1900 S Kostner Ave., Chicago 23, Ill.
Arrowhead Products, 2300 Curry St., Long Beach 5, Calif.
**Art Wire & Stamping Co. (Ad p 437)**
227 High St., Newark 2, N.J.
Artex Felt Co., 62 W 39th St., New York 18, N.Y.
Artmor Plastics Corp., 1003 Oldtown Rd., Cumberland, Md.
Artus Corp., 201 S Dean St., Englewood, N.J.
Artyle Industries, Inc., Box 28, Eaton, Ohio
Arvin Industries, Inc., 13th St., Columbus, Ind.
Arwood Corp., 321 W 44th St., New York 36, N.Y.
Arzt, T. L. Foundry Co., 4020 W Schubert Ave., Chicago 39, Ill.
Asbestos Corp. of America, 31 North Ave., Garwood, N. J.
Asbestos Textile Co., Inc., 165 W Wacker Drive, Chicago 1, Ill.
Asco Sintering Corp., 7799 Telegraph Rd., Los Angeles 22, Calif
Ashby Mfg. Co., 1601 Woodson Rd., St. Louis 11, Mo.
Asheville-Schoonmaker Mica Co., 900 Jefferson Ave., Newport News, Va.
Ashland Oil & Refining Co., Valvoline Oil Co. Div., 3rd Ave., Freedom, Pa
Ashtabula Mfg. Co., W 30th St., Ashtabula, Ohio
Associated Engineering & Mfg. Corp., 210 Stonehouse Rd., Glen Ridge, N. J.
Associated Spring Corp., Wallace Barnes Steel Div., 18 Main St., Bristol, Conn.
Atlantic Bag Co., 435 S 5th St., Brooklyn 11, N.Y.
Atlantic Brass Works, Inc., 2600 W Addison St., Chicago 18, Ill.
**Atlantic Casting Engineering Corp. (Ad p 438)**
810 Bloomfield Ave., Clifton, N.J.
Atlantic Foundry Co., 182 Beaver St., Akron 4, Ohio
Atlantic India Rubber Works, Inc., 569 W Polk St., Chicago 7, Ill.
Atlantic Powdered Metals, Inc., 38 Park Row, New York 38, N.Y.
Atlantic Steel Co., P.O. Box 1714, Atlanta 1, Ga.
Atlantic Steel Castings Co., 6th & Lloyd Sts., Chester, Pa.
Atlas Brass Foundry, 1901 Santa Fe Ave., Los Angeles 21, Calif.
Atlas Drop Forge Co., 209 W Mt. Hope Ave., Lansing, Mich.
Atlas Foundry Co., 3600 W 69th St., Cleveland 2, Ohio
Atlas Foundry & Machine Co., 3012 S Wilkeson St., Tacoma, Wash.
Atlas Foundry & Mfg. Co., 3701 Collins Ave., Richmond, Calif.
Atlas Galvanizing Co., 2639 Leonis Blvd., Los Angeles 11, Calif.
Atlas Metal Parts Co., 3232 N 31st St., Milwaukee 16, Wis.
Atlas Mineral Products Co., 161 Weber St., Mertztown, Pa.
**Atlas Powder Co., Chemicals Div. (Ad p 262)**
Wilmington 99, Del.
Atlas Steel Construction Co., 20 Vesey St., New York 7, N.Y.
Auburn Foundry, Inc., W 11th St., Auburn, Ind.
**Auburn Mfg. Co. (Ad p 430)**
20 Stack St., Middletown, Conn.
Auburn Plastic Engineering, 4916 S Loomis St., Chicago 9, Ill.
Auburn Plastics, Inc., 48 Canoga St., Auburn, N.Y.
Auburn Rubber Co., Inc., W 11th St., Auburn, Ind.
Auburn Spark Plug Co., Inc., Special Products Div., 89 York St., Auburn, N.Y.
Auel Industries, Herminie, Pa.
Auld, D. L. Co., 5th Ave. & 5th St., Columbus, Ohio
Aurora Metal Co., 614 W Park Ave., Aurora, Ill.
Aurora Refining Co., P.O. Box 88, Aurora, Ill.
Autel Electronics Co., Precision Machine & Welding Div., 1122 E St. George Ave., Linden, N.J.
Auto Specialties Mfg. Co., 643 Graves St., St. Joseph, Mich.
Automatic Nut Co., Lebanon, Pa.
Automotive Rubber Co., Inc., 12594 Beech Rd., Detroit, Mich.
Avco Mfg. Corp., 420 Lexington Ave., New York, N.Y.
New Idea Div., 420 Lexington Ave., New York, N.Y.
Avery Label Co., Decorative Products Div., 2123 E 9th St., Cleveland 15, Ohio
Aviation Developments, Inc., 210 S Victory Blvd., Burbank, Calif.
Avins Industrial Products Corp., 50 Broadway, New York 4, N.Y.
**AviSun Corp. (Ad pp 244-245)**
1608 Walnut St., Philadelphia 3, Pa.
Avondale Co., 260 Happ Rd., Northfield, Ill.
Avril, G. A. Co., Este Ave. & B&O R.R., Cincinnati, Ohio

## b

**B. B. Chemical Co., Bostik Dept. (Ad p 496)**
784 Memorial Dr., Cambridge 39, Mass.
B & T Metals Co., 425 W Town St., Columbus 16, Ohio
Babbitt Chemical Co., Inc., 38 Prospect, New Bedford, Mass.
Babcock & Wilcox Co., Tubular Products Div., Beaver Falls, Pa.
Babson Dow Mfg. Co., 64 Fulda St., Roxbury, Boston 19, Mass.
Backus Novelty Co., 411 Water St., Smethport, Pa.
Bacon Felt Co., 427 W Water St., Taunton, Mass.
Badger Aluminum Extrusions, 950 Georgia Ave., Brooklyn 7, N.Y.
Badger Die Casting Corp., 201 W Oklahoma Ave., Milwaukee 7, Wis.

***In contacting suppliers, please mention the Materials Selector Issue***

Badger Malleable & Mfg., Co., 223 N Chicago Ave., South Milwaukee, Wis.
Baer, N.S. Co., 1-11 Montgomery St., Hillside 5, N.J.
Baer Bros. Bronze Powder Co., Inc., Nickerson Rd., Ashland, Mass.
Baker & Co., Inc., 113 Astor St., Newark 2, N.J.
Balas Collet Mfg. Co., 1557 E 27th St., Cleveland 14, Ohio
Baldwin Mfg. Co., 140 Homer St., Waterbury 20, Conn.
Baldwin-Ehret-Hill, Inc., 500 Breunig Ave., Trenton 3, N.J.
Baldwin-Lima-Hamilton Corp., Philadelphia, Pa.
Standard Steel Works Div., Burnham, Pa.
Balsa Ecuador Lumber Corp., 500 5th Ave., New York, N.Y.
Bamberger, Claude P. Inc., 1 Mt. Vernon St., Ridgefield Park, N.J.
Bangor Plastics Inc., Washington St., Bangor, Mich.
Banner Iron Works, 1920 S Kingshighway, St. Louis 10, Mo.
Barber Iron Works, Inc., 301 W 61st St., P.O. Box 6318, Shreveport, La.
Barclay Mfg. Co., 1013 S Council St., Muncie, Ind.
Barium Steel Corp., 25 Broad St., New York 4, N.Y.
Barnard Foundry Co., Inc., 9 Roseland St., Springfield 7, Mass.
Barnett Foundry & Machine Co., Irvington, N.J.
Bar-Ray Products, 209 25th St., Brooklyn 32, N.Y.
Barrett Varnish Co., 1532 S 50th Court, Cicero 50, Ill.
Barrows Porcelain Enamel Corp., Langdon Farm Rd. & Penn R.R., Cincinnati 17, Ohio
Bart Mfg. Corp., 135 Manchester Pl., Newark 4, N.J.
Barth Smelting Corp., 99-129 Chapel St., Newark 5, N.J.
Bartlett-Thompson Co., Inc., 26 Water St., Wakefield, Mass.
Barton Products Corp., P.O. Box 305, West Bend, Wis.
Bassichis Co., 2323 W 3rd St., Cleveland 12, Ohio
Bassick Co., Howard Ave., Bridgeport, Conn.
Batson-Cook Co., West Point Foundry & Machine Co. Div., West Point, Ga.
Bausch & Lomb Optical Co., 98461 Bausch St., Rochester 2, N.Y.
Baxter Foundry & Machine Works, Inc., P.O. Box 1016, Boise, Id.
Bay City Electric Steel Casting Co., Trumbull St., Bay City, Mich.
Bay City Forge Co., 1802 Cranberry St., Erie, Pa.
Bay City Foundry Co., 400 Webster St., Bay City, Mich.
Bay Porous Material Co., 753 Loma Verde, Palo Alto, Calif.
Bay State Refining Co., Inc., 8 Montgomery St., Chicopee Falls, Mass.
Bay State Stamping Co., 372 Chandler St., Worcester, Mass.
Bay State Tool & Machine Co., 412 Albany, Springfield 4, Mass.
Bayley Products, Inc., 19155 Glendale Ave., Detroit 5, Mich.
Beacon Metal Mfg. Co., 1127 Atlantic Ave., Brooklyn 16, N.Y.
Bead Chain Mfg. Co., 110 Mountain Grove St., Bridgeport 5, Conn.
Bean, Morris & Co., Hyde Rd., Yellow Springs, Ohio
Bearium Metals Corp., 190 Mill St., Rochester, N.Y.
Beatty Machine & Mfg. Co., 940 150th St., Hammond, Ind.
Beaver Valley Alloy Foundry Co., Atlantic Ave., Monaco, Pa.
Beck, I. & Sons, Inc., 256 Mott St., New York 12, N.Y.
Beck Products Corp., 12255 E 8th Mile Rd., Detroit 5, Mich.
Becker Bros. Carbon Co., 3450 S Laramie Ave., Cicero 50, Ill.
Becker, L. A. Foundry Co., 1201 Hwy. 66, St. Louis 15, Mo.
Beckmann, Inc., 120 Baxter St., New York 13, N.Y.
Bee Chemical Co., 12933 S Stony Island Ave., Chicago 33, Ill.
Behringer Metal Works, Inc., 108 Jabez St., Newark 5, N.J.
Belding Corticelli Industries, 1407 Broadway, New York 18, N.Y.
Belko Corp., Kingsville, Md.
Bellaire Stove Co., 19th & Union Sts., Bellaire, Ohio
Belle City Malleable Iron Co., Racine Steel Castings Div., 1442 Forest St., Racine, Wis.
Belmet Products, Inc., 503 Morgan Ave., New York 22, N.Y.
Belmont Aluminum Extrusion Co., 1228 Belmont Ave., Philadelphia 4, Pa.
Belmont Smelting & Refining Works, 330 Belmont Ave., Brooklyn 7, N.Y.
Beloit Foundry Co., 445 Gardner St., South Beloit, Ill.
Beloit Iron Works, Rock River, Beloit, Wis.
Benada Aluminum Products Co., 37 James St., Girard, Ohio
Bendix Aviation Corp., Teterboro, N.J.
Bendix Foundries Div., Teterboro, N.J.
Eclipse-Pioneer Div., Teterboro, N.J.
Benjamin Electric Mfg. Co., Northwest Hwy., Des Plaines, Ill.
Bennett Mfg. Co., 41 Mechanic, Alden, N.Y.
Bergen Point Iron Works, 233 Broadway, New York 7, N.Y.
Bergfels, William & Co., 10 Orchard St., Newark 2, N.J.
Berry Bros., 211 Leib St., Detroit 7, Mich.
Beryl Ores Co., 12900 W 10G Ave., Arvada, Colo.
**Beryllium Corp. (Ad p 187)**
P.O. Box 1462, Reading, Pa.
National Precision Casting Corp. Div., P.O. Box 396, Paoli, Pa.
Bessemer Galvanizing Works, Bessemer, Ala.
Bethandale Corp., 24040 Lakeland Blvd., Cleveland 23, Ohio
Bethlehem Steel Co., 701 E 3rd St., Bethlehem, Pa.
Better Finishes & Coatings, Inc., 270 Doremus Ave., Newark, N.J.
Bettinger Corp., Gore St., Waltham, Mass.
Bevan Co., 400 N Arden Dr., El Monte, Calif.
Bickford, F. H., Co., 1529 S Broadway, Dayton 8, Ohio
Biddle Screw Products Co., S Main, Sheridan, Ind.
Bierman-Everett Foundry Co., 135 S 20th St., Irvington, N.J.
Biersach & Niedermeyer Co., 1937 N Hubbard St., Milwaukee 12, Wis.
Biggs, Carl H. Co., Inc., 1547 14th St., Santa Monica, Calif.
Bignall Co., 28 Wasson St., Buffalo 10, N.Y.
Billings & Spencer Co., 1 Laurel St., Hartford 1, Conn.
Bingham-Herbrand Corp., Herbrand Div., Lake & Stone Sts., Fremont, Ohio
Binkley Co., 100 Elm St., Warrenton, Mo.
Birchwood Chemical Co., 4500 W 44th St., Minneapolis 24, Minn.
Bird, Richard H. Co. Inc., 1 Spruce St., Waltham 54, Mass.
Birdsboro Steel Foundry & Machine Co., Birdsboro, Pa.
Bischoff Chemical Corp., 220 Miller Rd., Hicksville, N.Y.
Bishop, J. & Co. Platinum Works, E King St., Malvern, Pa.
Bishopric Products Co., 4413 Este Ave., Cincinnati 32, Ohio
Bisonite Co., Inc., P.O. Box 84, Kenmore Sta., Buffalo 17, N.Y.
Biwax Corp., 3445 Howard St., Skokie, Ill.
Blacher, B., 752 Broadway, New York 3, N.Y.
Blacher Bros., Inc., 299 Carpenter St., Providence 9, R.I.
Black Bear Co., Inc., 44-45 23rd St., Long Island City 1, N.Y.
Black-Clawson Co., 1700 Grand Ave., Middletown, Ohio
Shartle Div., 2nd & Vine Sts., Hamilton, Ohio
Blaco Mfg. Co., 6541 Euclid Ave., Cleveland 3, Ohio
Blake & Johnson Co., Waterville 48, Conn.
Blakeslee Forging Co., Plant Pl., Plantsville, Conn.
Blank, Arthur & Co., Inc., 33 Cummington St., Boston 15, Mass.
Blaw-Knox Co., 300 6th Ave., Pittsburgh 23, Pa.
Blickman, S., Inc., 536 Gregory Ave., Weehawken, N.J.
Bliss, E. W. Co., Mackintosh-Hemphill Div., 901 Bingham St., Pittsburgh, Pa.
Bliss & Laughlin, Inc., 281 E 155th St., Harvey, Ill.
Blossom Mfg. Co., Inc., 2337 McDonald Ave., Brooklyn, N.Y.
Boatwright Paint & Varnish Works, Inc., P.O. Box 306, Norcross, Ga.
Boehm Screw Products Co., 7100 W Jefferson, Detroit 17, Mich.
Bogert & Hopper, Inc., 105 W 31st St., New York, N.Y.
Bohn Aluminum & Brass Corp., 1400 Lafayette Bldg., Detroit 26, Mich.
Bond, Charles Co., 617-623 Arch St., Philadelphia 6, Pa.
Bond International, Inc., 783 S Deacon, Detroit 17, Mich.
Bone Engineering Corp., 701 W Broadway, Glendale 4, Calif.
Bonnell, William L. Co., Inc. Newman, Ga.
Bonney-Floyd Co., 611 Marion Rd., Columbus 7, Ohio
Bonnot Co., 722 Mulberry Rd., SE, Canton 2, Ohio
Booker & Wallestad, Inc., 3336 Gorham Ave., Minneapolis 26, Minn.
Boonton Molding Co., 326 Myrtle Ave., Boonton, N.J.
Booth Felt Co., Inc., 569 18th St., Brooklyn 15, N.Y.
Boots Aircraft Nut Corp., Newtown Tpke., Norwalk, Conn.
Borden Co., Borden Chemical Co. Div., 350 Madison Ave., New York 17, N.Y.
Borg-Warner Corp., 310 S Michigan Ave., Chicago, Ill.
Atkins Saw Div., 402 S Illinois St., Indianapolis, Ind.
Franklin Steel Div., Franklin, Pa.
Ingersoll Products Div., 1000 W 120th St., Chicago 43, Ill.
**Marbon Chemical Div. (Ad pp 235-242)**
7165 Chicago Ave., Gary, Ind.
Borkland Mfg. Co., 803 Quarry Rd. at 900 Wabash Rd., Marion, Ind.
Bostitch, Inc., Briggs Dr., East Greenwich, R.I.
Boston Felt Co., 210 South St., Boston 11, Mass.
Boston Gear Works, 14 Hayward St., Quincy 71, Mass.
Boston Metals Co., Baldt Anchor, Chain & Forge Div., 6th & Butler Sts., Chester, Pa.
Both, O.A. Corp., 100 Nickerson Rd., Ashland, Mass.
Bound Brook Oil-Less Bearing Co., Bound Brook, N.J.
Bowling Green Rubber Co., 4143 Monroe St., Toledo 13, Ohio
Boyles Galvanizing & Plating Co., P.O. Box 187, Hurst, Texas
Bradley Paint Co., 608 W Crawford Ave., Connellsville, Pa.
Bradley & Vrooman Co., 2629 S Dearborn St., Chicago 16, Ill.
Braeburn Alloy Steel Corp., Braeburn, Pa.
Brandt, Charles T. Inc., 1700 Ridgely St., Baltimore 30, Md.
Brasco Mfg. Co., Harvey, Ill.
Brewer-Titchener Corp., 111 Port Watson St., Cortland, N.Y.
**Bridgeport Brass Co. (Ad p 176)**
30 Grand St., Bridgeport 2, Conn.
Cored Forging Div., P.O. Box 119, South Norwalk, Conn.
Hunter-Douglas Aluminum Div., 3016 Kansas Ave., Riverside, Calif.
Bridgeport Moulded Products, Inc., 105 Meadow St., Fairfield, Conn.
Bridgeport Rolling Mills Co., Bridgeport, Conn.
Briel Industries, Inc., 2232 E Market St., New Albany, Ind.
Briggs-Shaffner Co., 500 Brookstown Ave., Winston-Salem, N.C.
Brinkerhoff Brass & Bronze Works, Inc., 57½ Dey St., New York 7, N.Y.
Bristol Brass Corp., 580 Broad St., Bristol, Conn.
Accurate Brass Corp. Sub., Pine & Emmett Sts., Bristol, Conn.
Broadway Mfg. Co., P.O. Box 252, Springdale Rd., Waukesha, Wis.
Broadway Rubber Corp., 728 S 13th St., Louisville, Ky.
Brockway Pressed Metals, Inc., 921 Clark St., Brockway, Pa.
Brom Machine & Foundry Co., 3565 6th St., Winona, Minn.
Bronze & Steel Die Casting Co., Plano, Ill.
**Brooks & Perkins, Inc. (Ad p 457)**
1950 W Fort St., Detroit 16, Mich.
Brown Corp., 213 Bellevue Ave., Syracuse 1, N.Y.
Brown Rubber Co., Inc., P.O. Box 1000, Lafayette, Ind.
Bruce Foundry & Mfg. Co., 4040 S Evans St., Tecumseh, Mich.
Brunswick Corp., Marion, Va.
Defense Products Div., 1700 Messler St., Muskegon, Mich.
**Brush Beryllium Co. (Ad p 171)**
4301 Perkins Ave., Cleveland 3, Ohio
Pennrold Div., 501 Crescent Ave., Reading, Pa.
Buchmann Spark-Wheel Corp., 4-20 47th Ave., Long Island City 1, N.Y.
Buckeye Brass & Mfg. Co., 6410 Hawthorne Ave., Cleveland 3, Ohio
Buckeye Iron & Brass Works, 324 E 3rd St., Dayton 1, Ohio
Buckeye Molding Co., 213 S 3rd St., Miamisburg, Ohio
Buffalo Steel Corp., Tonawanda, N.Y.
Buffalo Wire Works Co., 320 Terrace, Buffalo 2, N.Y.
Bullock, W.J. Inc., P.O. Box 539, Fairfield, Ala.
Bundy Tubing Co., 8109 E Jefferson, Detroit 14, Mich.
Bunker Hill Co., 660 Market St., San Francisco 4, Calif.
Bunting Brass & Bronze Co., 715 Spencer, Toledo 1, Ohio
Burgess-Norton Mfg. Co., 737 Peyton St., Geneva, Ill.
Burkhardt Steel Co., 869 S Broadway, Denver 9, Colo.
Burwood Products Co., Airport Dr., Traverse City, Mich.
**Busada Mfg. Corp. (Ad p 442)**
32-21 Downing St., Flushing, N.Y.
Busch, J.C. Co., 17 W 54th St., New York 19, N.Y.
Butler Engine & Foundry Co., Inc., 151 S Monroe, Butler, Pa.
Butler Mfg. Co., 7309 E 13th St., Kansas City, Mo.

Addresses of Suppliers

Button Corp. of America, 49 Dickerson St., Newark 9, N.J.
Byers, A. M., 1810 Clark Bldg., Pittsburgh 22, Pa.
Byrd Plastics, Inc., 2953 W 12th St., Erie, Pa.

## C

C. E. M. Co., 3 School St., Danielson, Conn.
CFI Corp., Cottage Pl., Mineola, N.Y.
C & G Screw Machine Products Co., P.O. Box 308, Carmel, Ind.
Cadillac Malleable Iron Co., 10th St., Cadillac, Mich.
Cadillac Plastic & Chemical Co., 15111 2nd Ave., Detroit, Mich.
Caldwell, W. E. Co., 2020 Brook St., Louisville 8, Ky.
Calfibe Co., Inc., P.O. Box 832, Redlands, Calif.
California Drop Forge Co., 1033 Alhambra Ave., Los Angeles 12, Calif.
California Metal Enameling Co., 6904 E Slauson Ave., Los Angeles 22, Calif.
California Perforated Screen Co., 345-347 Folsom St., San Francisco 5, Calif.
Callahan Zinc-Lead Co., Inc., Flexaust Div., 100 Park Ave., New York 17, N.Y.
Calorizing Co., P.O. Box 8742, Pittsburgh 21, Pa.
Calumet & Hecla, Inc., 13 Calumet Ave., Detroit 9, Mich.
Calumet Div., 11 Calumet Ave., Calumet, Mich.
**Wolverine Tube Div. (Ad p 445)**
1439 Central Ave., Detroit 9, Mich.
Calumet Steel Castings Corp., 1636 Summer St., Hammond, Ind.
Cambridge Wire Cloth Co., Cambridge, Md.
Camcar Screw & Mfg. Co., 600 18th Ave., Rockford, Ill.
**Cameron Iron Works, Inc., Special Products Div. (Ad p 439)**
P.O. Box 1212, Houston 1, Tex.
Camfield Fiberglass Plastics, Inc., N Centennial St., Zeeland, Mich.
Camloc Fastener Corp., 22 Spring Valley Rd., Paramus, N.J.
Campro Co., 3131 Alliance Rd., NE, Canton 1, Ohio
Canfield, H.O. Co., Box 529, Clifton Forge, Va.
Cannon-Muskegon Corp., 2875 Lincoln St., Muskegon, Mich.
Canton Malleable Iron Co., 2408 13th NE, Canton, Ohio
Capac Mfg. Corp., Capac, Mich.
Capitol Chemical Co., 4501 W Haddon Ave., Chicago 51, Ill.
Capitol Products Corp., Mechanicsburg, Pa.
Carbo Tool & Die Co., 219 Howland St., Fremont, Ohio
Carboline Co., 32 Hanley Ct., St. Louis 17, Mo.
Carbone Corp., 400 Myrtle Ave., Boonton, N.J.
Carborundum Co., Niagara Falls, N.Y.
Refractories Div., Perth Amboy, N.J.
Carborundum Metals Co., P.O. Box 32, Akron, N.Y.
Carey, Philip Mfg. Co., 320 S Wayne Ave., Lockland, Cincinnati 15, Ohio
Carleton Screw Products Co., 2424 Hiawatha Ave S, Minneapolis 4, Minn.
Carlon Products Corp., 10225 Meech Ave., Cleveland 5, Ohio
Carlson, G.O. Inc., Thorndale, Pa.
Carolina Asbestos Co., Davidson, N.C.
Carondelet Foundry Co., 2101 S Kingshighway, St. Louis 10, Mo.
Carpenter Steel Co., 101 W Bern St., Reading, Pa.
Alloy Tube Div., Springfield Rd., Union, N.J.
Webb Wire Div., 17 Liberty St., New Brunswick, N.J.
Carroll, J.B. Co., 319 N Albany Ave., Chicago 12, Ill.
Carroll Pressed Metal, Inc., 133 Dewey St., Worcester 10, Mass.
Cartwright, R. Tube Products Co., 609 St. Jean Ave., Detroit 14, Mich.
Case, J. I. Co., 702 State St., Racine, Wis.
Caspers Tin Plate Co., 4100 W 42nd Pl., Chicago 32, Ill.
Cast Optics Corp., Room 8, 123 Newman St., Hackensack, N.J.
Castalloy Co., Inc., W Central St., Natick, Mass.
Casting Engineers, Inc., 2323 N Bosworth, Chicago, Ill.
Casting Service Corp. of Michigan, Mathien Ave., Bridgman, Mich.
Castle, A M. & Co., 3400 N Wolf Rd., Franklin Park, Ill.
Castle Rubber Co., P.O. Box 589, Butler, Pa.
Catalin Corp. of America, 1 Park Ave., New York 16, N.Y.
Ceilcote Co., 4832 Ridge Rd., Cleveland 9, Ohio
**Celanese Corp. of America. Celanese Plastics Co. Div. (Ad pp 271-274)**
744 Broad St., Newark 2, N.J.
Cellufplastic Corp., 50 Ave. L, Newark 5, N.J.
**Cellusuede Products, Inc. (Ad p 363)**
511 N Madison St., Rockford, Ill.
Celotex Corp., 120 S LaSalle St., Chicago 3, Ill.
Central Fabricators, Inc., 408 Poplar St., Cincinnati, Ohio
Central Felt & Fabrics Corp., 24 W 25th St., New York 10, N.Y.
Central Screw Co., 3501 S Shields, Chicago 9, Ill.
Central Screw Products Co., 264 Walker St., Detroit 7, Mich.
Centrifugal Casting Co., 3245 Cherry Ave., Long Beach 7, Calif.
Centrifugal Casting Co., 147 W 42nd St., New York 36, N.Y.
Centrifugal Casting Machine Co., P.O. Box 947, Tulsa 1, Okla.
Centr-O-Cast & Engineering Co., 45 South St. & St. Jean Ave., Detroit 14, Mich.
Century Die Casting Co., 2629 W Fletcher St., Chicago 18, Ill.
Ceromet, Inc., 16233 Gale Ave., Industry, Calif.
**Cerro de Pasco Sales Corp. (Ad p 178)**
300 Park Ave., New York 22, N.Y.
Lewin-Mathes Div., 1111 Chouteau Ave., St. Louis 2, Mo.
Chace, W.M. Co., 1600 Beard Ave., Detroit 9, Mich.
Chain Belt Co., 4701 W Greenfield Ave., Milwaukee 1, Wis.
Chambersburg Engineering Co., Derbyshire St., Chambersburg, Pa.
Champion Rivet Co., Harvard Ave. & E 108th St., Cleveland 5, Ohio
Chandler Products Corp., 1491 Chardon Rd., Cleveland 17, Ohio
Channel Master Corp., Ellenville, N.Y.
Chapman Machine Co., Inc., 41 Main St., Terryville, Conn.
Chardon Metal Products Co., Mill St., Chardon, Ohio
Chardon Rubber Co., 6th & Washington Aves., Chardon, Ohio
Charlotte Leather Belting Co., 209 E 12th St., Charlotte 1, N.C.
Char-Lynn Co., Diecasting Div., 2842 26th Ave. S, Minneapolis 6, Minn.
Chattanooga Aluminum Foundry, Inc., 2000 Chestnut St., Chattanooga 8, Tenn.
Chemetron Corp., Tube Turns Div., 224 E Broadway, Louisville 1, Ky.
**Chemical Corp. (Ad p 360)**
67 Waltham Ave., Springfield 9, Mass.
Chemical Coatings Corp., Dividend Rd., Rocky Hill, Conn.
Chemical Coatings & Engineering Co., Inc., 221 Brooke St., Media, Pa.
Chemical Development Corp., Endicott St., Danvers, Mass.
Chemical Process Co., 1901 Spring St., Redwood City, Calif.
Chemical Products Corp., King Philip Rd., East Providence 14, R.I.
Chemore Corp., 2 Broadway, New York 4, N.Y.
Chemtrol, 404 W St. Anne Pl., Santa Ana, Calif.
Chemung Foundry Corp., Elmira, N.Y.
Chicago Aluminum Castings, 2647 Ogden Ave., Chicago, Ill.
Chicago Bridge & Iron Co., 332 S Michigan Ave., Chicago 4, Ill.
Chicago Development Corp., 5810 47th Ave., Riverdale, Md.
Chicago Extruded Metals Co., 1642 S 54th Ave., Cicero 9, Ill.
Chicago Gasket Co., 1271 W North Ave., Chicago 22, Ill.
Chicago Hardware Foundry Co., 2600 Commonwealth Ave., North Chicago, Ill.
Chicago Malleable Castings Co., 1225 W 120th St., Chicago 43, Ill.
Chicago Molded Products Corp., 1050 N Kolmar Ave., Chicago 35, Ill.
**Campco Div. (Ad p 343)**
2736 N Normandy Ave., Chicago 35, Ill.
Custom Molding Div., 1020 N Kolmar Ave., Chicago 51, Ill.
Chicago Powdered Metal Products Co., Schiller Park, Ill.
Chicago Rawhide Mfg. Co., 1301 Elston Ave., Chicago 22, Ill.
Chicago Rivet & Machine Co., 950 S 25th Ave., Bellwood, Ill.
Chicago Rubber Co., Inc., 653 Market St., Waukegan, Ill.
Chicago Smelting & Refining Corp., 3701 S Kedzie Ave., Chicago 32, Ill.
Chicago Steel Service Co., 4444 S Kildare Ave., Chicago 32, Ill.
Chicago Thrift-Etching Corp., 1555 N Sheffield Ave., Chicago 22, Ill.
Chicago White Metal Casting, Inc., 5239 W Grand Ave., Chicago 39, Ill.
Chicago-Allis Mfg. Corp., 113-125 N Green St., Chicago 7, Ill.
Chicopee Mills, Inc., 47 Worth St., New York 13, N.Y.
Lumite Div., 47 Worth St., New York 13, N.Y.
Chippewa Plastics Co., 1701 1st Ave., Chippewa Falls, Wis.
Chromalloy Corp., 450 Tarrytown Rd., White Plains, N.Y.
Elyria Foundry Div., Elyria, Ohio
Sintercast Div., 134 Woodworth Ave., Yonkers 2, N.Y.
Chromium Corp. of America, 100 Park Ave., New York 17, N.Y.
Chromizing Corp., 4609 Staunton Ave., Los Angeles 58, Calif.
Chrysler Corp., P.O. Box 1687, Detroit 31, Mich.
Amplex Div., P.O. Box 2718, Detroit 31, Mich.
Cycleweld Div., 5437 W Jefferson, Trenton, Mich.
Ciba Co., Inc., 622 Greenwich St., New York 14, N.Y.
**Plastics Div. (Ad pp 278-279)**
Kimberton, Pa.
Cincinnati Forging Co., 5604 Booster Pike, Cincinnati, Ohio
Cincinnati Foundry Co., 238 W Mitchell Ave., Cincinnati 32, Ohio
Cincinnati Industries Inc., 515 Station Ave., Cincinnati 15, Ohio
City Plating Works, Inc., 905 Honeyspot Rd., Stratford, Conn.
**Clad-Rex Corp. (Ad p 413)**
2101 S. Indiana, Chicago 16, Ill.
Clapp, E. D. Mfg. Co., Inc., 505 Genesee St., Auburn, N.Y.
Clark Bros. Bolt Co., Milldale, Conn.
Clark Perforating Co., 15875 Allen Rd., Milan, Mich.
Clarksville Foundry & Machine Works, Commerce & Spring Sts., Clarksville, Tenn.
Clayton & Lambert Mfg. Co., 1701 Dixie Hwy., Louisville 10, Ky.
Clayton Mark & Co., 1900 Dempster St., Evanston, Ill.
Clendenin Bros., Inc., 4309 Erdman Ave., Baltimore 13, Md.
Cleveland Cap Screw Co., 4444 Lee Rd., Cleveland 28, Ohio
Cleveland City Forge Co., 1621 Euclid Ave., Cleveland 15, Ohio
Cleveland Electro Metals Co., 2391 W 38th St., Cleveland 13, Ohio
Cleveland Foundry & Mfg. Co., Inc., 685 6th St., NE, Cleveland, Tenn.
Cleveland Graphite Bronze Co., 17044 St. Clair Ave., Cleveland 10, Ohio
Cleveland Hard Facing Co., Inc., 3047 Stillson Ave., Cleveland 5, Ohio
Cleveland Metal Products Co., Washington & Center Sts., Cleveland 13, Ohio
Cleveland Porcelain Enameling Co., 3190 E 65th St., Cleveland 27, Ohio
Cleveland Pressed Products Corp., 6712 Union Ave., Cleveland 5, Ohio
Cleveland Steel Specialty Co., Inc., 3765 E 91st St., Cleveland 5, Ohio
Cleveland Tungsten, Inc., 10200 Meech Ave., Cleveland 5, Ohio
Cleveland Wire Cloth & Mfg. Co., 3573 E 78th St., Cleveland 5, Ohio
Cliff Mfg. Co., 30240 Lakeland Blvd., Wickliffe, Ohio
Clifton Conduit Corp., 3300 Eastbourne Ave., Baltimore 24, Md.
Clinton Co., 1216 Elston Ave., Chicago 22, Ill.
Clinton Metal Products Co., 1076 W Locust St., Wilmington, Ohio
Clopay Corp., Clopay Sq., Cincinnati 14, Ohio
Closures, Inc., 46 State St., Waterbury, Conn.
Clover Industries, Inc., 578-588 Young St., Tonawanda, N.Y.
Cly-Del Mfg. Co., Inc., Box 1367, Waterbury, Conn.
Coast Mfg. & Supply Co., P.O. Box 71, Livermore, Calif.
Coast Pro-Seal & Mfg. Co., 2235 Beverly Blvd., Los Angeles 57, Calif.
Coated Abrasive Products, Inc., 30208 Lakeland Blvd., Wickliffe, Ohio
Coated Coil Corp., 513 W 30th St., New York 1, N.Y.
**Coating Products, Inc. (Ad p 359)**
101 W Forest Ave., Englewood, N.J.
Cochran Foil Co., 1430 S 13th St., Louisville, Ky.

***In contacting suppliers, please mention the Materials Selector Issue***

Cochrane Foundry, Inc., Box 749, York, Pa.
Cohan Epner Co., Inc., 142 W 14th St., New York 11, N.Y.
Coil Anodizers, Inc., 1250 Keating Ave., Muskegon, Mich.
Cole-Roscoe Mfg. Co., 55 Bates Ct., South Norwalk, Conn.
Colils Co., Clinton, Iowa
Colonial Alloys Co., Ridge Ave. & Crawford St., Philadelphia 29, Pa.
Colonial Art Co., Inc., Crane Ave., Westfield, Mass.
Colonial Kolonite Co., 2232 Armitage Ave., Chicago 47, Ill.
Colonial Plastics Mfg. Co., 2685 E 79th St., Cleveland 4, Ohio
Colorado Fuel & Iron Corp., Continental Oil Bldg., Denver 2, Colo.
Pacific Coast Div., 1080 19th Ave., Oakland 6, Calif.
Roebling's, John A. Sons Div., 640 S Broad St., Trenton 2, N.J.
Wickwire Spencer Steel Div., 575 Madison Ave., New York 22, N.Y.
Colt's Plastics Co., Inc., P.O. Box 96, North Grosvenordale, Conn.
Columbia Metal Stamping Co., 11900 Harvard Ave., Cleveland 5, Ohio
Columbia Steel & Shafting Co., Summerill Tubing Co. Div., P.O. Box 1557, Pittsburgh 30, Pa.
Columbia Tool Steel Co., Lincoln Hwy. & State St., Chicago Heights, Ill.
Columbian Bronze Corp., 216 N Main St., Freeport, N.Y.
Columbian Steel Tank Co., 1509 W 12th St., Kansas City 1, Mo.
Columbiana Pump Co., Columbiana, Ohio
Columbia-National Corp., 1 Gateway Center, Pittsburgh 22, Pa.
Columbus Bolt & Forging Co., 291 Marconi Blvd., Columbus 15, Ohio
Columbus Coated Fabrics Corp., 7th & Grant Aves., Columbus 16, Ohio
Columbus Dental Mfg. Co., 634 Wager St., Columbus 6, Ohio
Columbus Jack Corp., 2200 S Third St., Columbus 7, Ohio
Columbus Production Mfg. Co., 1559 McKinley, Columbia, Ohio
Combined Industries Co., P.O. Drawer 431, Catskill, N.Y.
Combustion Engineering, Inc., 1318 N Branch St., Chicago 22, Ill.
Comco Plastics, Inc., 98-34 Jamaica Ave., Richmond Hill, N.Y.
Comerford Mfg. Co., Inc., 81 Farmington Ave., Bristol, Conn.
Comet Metal Products Co., Inc., 91-04 132nd St., Richmond Hill 18, N.Y.
Commercial Chemical Co., 1021 Summer St., Cincinnati 4, Ohio
Commercial Iron Works, 2424 Porter, Los Angeles, Calif.
Commercial Plastics Co., 2810 W North Ave., Chicago 47, Ill.
Associated Plastic Div., 400 E Hines St., Midland, Mich.
Commercial Plastics & Supply Corp., 630 Broadway, New York 12, N.Y.
Commercial Screw Products Co., 15105 Darwin Ave., Cleveland 10, Ohio
Commercial Shearing & Stamping Co., 1775 Logan Ave., Youngstown, Ohio
Commercial Steel Casting Co., Cheney Ave., Marion, Ohio
Commercialores, Inc., Box 90, Clover, S.C.
Compacted Metals Corp., 99 Greenwood Ave., Waukegan, Ill.
Composite Forgings, Inc., 2300 W Jefferson Ave., Detroit 16, Mich.
Composite Industrial Metals, Inc., 235 Georgia Ave., Providence 5, R.I.
Compton Foundry, Compton, Calif.
Concord Mica Corp., 26 Crescent, Penacook, N.H.
Condamatic Co., Inc., 2700 E 9 Mile Rd., Hazel Park, Mich.
Conforming Matrix Corp., 12th & Woodruff Sts., Toledo 2, Ohio
Conn Perry Mfg. Co., 4341 Horatio Ave., Detroit 10, Mich.
Conneaut Die Casting Co., 618 Sandusky St., Conneaut, Ohio
Connecticut Hard Rubber Co., 407 East St., New Haven 9, Conn.
Connecticut Malleable Castings Co., New Haven 6, Conn.
Connecticut Mfg. Co., 115 Benedict St., Waterbury 20, Conn.
Connell Asbestos Mfg. Co., 117 Martense St., Brooklyn 26, N.Y.
Conner Mfg. Co., 828 S 17th St., Louisville, Ky.
Consolidated Foundries & Mfg. Corp., Michigan Steel Casting Co. Div., 1999 Guoin St., Detroit 7, Mich.
Consolidated Fruit Jar Co., 62 Water St., P.O. Box 109, New Brunswick, N.J.
Consolidated Industries, Inc., Manville Rd., West Cheshire, Conn.
Consolidated Iron-Steel Mfg. Co., Ackerman Plastic Molding Div., 986 E 200th St., Cleveland 19, Ohio
Consolidated Molded Products Corp., 1940 Thomas St., Scranton, Pa.
Consolidated Vacuum Corp., 1775 Mt. Read Blvd., Rochester 3, N.Y.
Consolidated Water Power & Paper Co., Wisconsin Rapids, Wis.
Consoweld Corp., 700 Hooker St., Wisconsin Rapids, Wis.
Continental Boiler & Sheet Iron Works, 5603 W Park Ave., St. Louis, Mo.
Continental Can Co., 100 E 42nd St., New York 17, N.Y.
Conolite Div., 205 W 14th St., Wilmington, Del.
Flexible Packaging Div., Mount Vernon, Ohio
Continental Coatings Corp., 17706 Miles Ave., Cleveland, Ohio
Continental Copper & Steel Industries, Inc., 345 Madison Ave., New York 17, N.Y.
Niagara Falls Smelting & Refining Div., 2200-2214 Elmwood Ave., Buffalo 23, N.Y.
Continental Die Casting Corp., 9615 Grinnell Ave., Detroit 13, Mich.

**Continental Felt Co. (Ad p 322)**
26 W 15th St., New York 11, N.Y.

Continental Gin Co., Birmingham, Ala.
Continental Rubber Works, 1985 Liberty St., Erie 6, Pa.
Continental Screw Co., 459 Mt. Pleasant St., New Bedford, Mass.
Continental Steel Corp., 1109 S Main St., Kokomo, Ind.
Continental Wire & Iron Works, Continental Nu-Steel Metal Products Div., 1249 S Ashland Ave., Chicago 8, Ill.
Continental-Diamond Fibre Corp., Newark, Del.
Continental-Emsco Co., P.O. Box 2098, Terminal Annex, Los Angeles 54, Calif.
Contour Extrusion Co., 517 Fayette Ave., Mamaroneck, N.Y.
Control Parts Corp., 530 Burnside Ave., Inwood 96, L.I., N.Y.
Conversion Chemical Corp., 98 E Main St., Rockville, Conn.
Cooley, W.J. & Co., P.O. Box 1471, 107 Hernando, Memphis, Tenn.
Cooper Alloy Corp., Bloy St. & Ramsey Ave., Hillside 5, N.J.
Cooper, Peter Corp., Palmer St., Gowanda, N.Y.
Cooper-Bessemer Corp., Mt. Vernon, Ohio
Coors Porcelain Co., 600 9th St., Golden, Colo.
Co-Polymer Chemicals Inc., 12350 Merriman Rd., Livonia, Mich.
Copolymer Rubber and Chemical Corp., P.O. Box 2591, Baton Rouge 1, La.
Copper and Brass Sales, Inc., 6555 E Davison St., Detroit 12, Mich.

**Copper Range Co., Hussey, C.G. & Co. Div. (Ad p 180)**
2850 2nd Ave., Pittsburgh 19, Pa.

Copperweld Steel Co., Warren, Ohio
Aristoloy Steel Div., Mahoning Ave. Ext., Warren, Ohio
Ohio Seamless Tube Div., Shelby, Ohio
Superior Steel Div., Superior St., Carnegie, Pa.

**Cordo Chemical Corp. (Ad p 269)**
34 Smith St., Norwalk, Conn

**Cordo Molding Products, Inc. (Ad p 269)**
34 Smith St., Norwalk, Conn.

Corite Products, Inc., 6553 W George St., Chicago 34, Ill.
Cornell and Underhill, Inc., 1310 Jefferson St., Hoboken, N.J.

**Corning Glass Works (Ad p 319)**
Corning, N. Y.

Corson Industries, 1228 Belmont Ave., Philadelphia 4, Pa.
Cosmo Plastics Co., 3239 W 14th St., Cleveland 9, Ohio
Couch-Uthe Co., 140 S Olive St., Elyria, Ohio
Coyne & Paddock, Inc., 40-09 21st St., Long Island City 1, N.Y.
Craft Mfg. Co., 2301 Davis St., North Chicago, Ill.
Craft Metal Spinning Co., 302 E Main St., Dundee, Ill.
Craftint Mfg. Co., 1615 Collamer Ave., Cleveland 10, Ohio
Crane Co., 836 S Michigan Ave., Chicago 5, Ill.
Metals Div., 4461 Bridge St., Johnstown, Pa.
Crane Packing Co., 6400 Oakton St., Morton Grove, Ill.

**Crane Plastics, Inc. (Ad p 464)**
500 Hutton Pl., Columbus 15, Ohio

Crawford & Doherty Foundry Co., 4604 SE 17th Ave., Portland, Ore.
Crescent Bronze Powder Co., 116 W Illinois St., Chicago 10, Ill.
Crescent Co., Inc., Carol Cable Co. Div., 90 Middle St., Pawtucket, R.I.
Crescent Plastics, Inc., 955 Diamond Ave., Evansville 7, Ind.
Crest Chemical Industries Corp., 132-34 32nd Ave., Flushing, N.Y.
Crobalt, Inc., 2800 S State St., Ann Arbor, Mich.
Croname, Inc., 6275 Howard St., Chicago 48, Ill.
Crosby Co., 183 Pratt St., Buffalo 4, N.Y.
Cross Engineering Co., Carbondale, Pa.
Crown Metal Co., 121 E Washington St., Milwaukee 4, Wis.
Crown Non-Ferrous Foundry, Inc. Concord Ave., Chester, Pa.

**Crucible Steel Co. of America (Ad p 93)**
P.O. Box 2518, Pittsburgh 30, Pa.
Titanium and Vacuum Metal Products Div., P.O. Box 2518, Pittsburgh 30, Pa.
Trent Tube Co., P.O. Box 2518, Pittsburgh 30, Pa.

Crucible Steel Casting Co., Union Ave. & Penn R.R., Lansdowne, Pa.
Cruver Mfg. Co., 2460 W Jackson, Chicago 12, Ill.
CrystalX Corp., W Lenni Rd., Lenni Mills, Pa.
Cumberland Steel Co., 101 Williams St., Cumberland, Md.
Curbell, Inc., 777 Hertel Ave., Buffalo 7, N.Y.
Curtis Cos., Inc., American Plywood Div., New London, Wis.
Curtis Products Co., 7 Cherry Ave., Waterbury 4, Conn.
Curtis Screw Co., Inc., 19 Gull St., Buffalo 13, N.Y.
Curtiss-Wright Corp., 304 Valley Blvd., Wood-Ridge, N.J.
Metals Processing Div., 706 Northland Ave., Buffalo 15, N.Y.
Plastics Div., 50 Rockefeller Plaza, New York, N.Y.
Utica Div., 50500 Mound Rd., Utica, Mich.
Custom Tool and Mfg. Co., 2201 N 2nd St., Minneapolis 11, Minn.
Cuyahoga Stamping Co., 10201 Harvard Ave., Cleveland 5, Ohio
Cyril Bath Co., 32342 Aurora Rd., Solon, Ohio

# d

DK Mfg. Co., Cobra Metal Hose Div., 5059 S Kedzie Ave., Chicago 32, Ill.
Dacar Chemical Products Co., 1007 McCartney St., Pittsburgh, Pa.
Dahlin, C. A. Co., 2727 Clybourn Ave., Chicago 14, Ill.
Dalton Foundries, Inc., Lincoln & Jefferson Sts., Warsaw, Ind.
Damascus Tube Co., P.O. Box 71, Greenville, Pa.
Dana Corp., Bennett Rd. & Sylvania Ave., Toledo 1, Ohio
Auburn Div., Auburn, Ind.
Parish Pressed Steel Div., Box 1422, Reading, Pa.
Danby Mfg. Co., Portland, Mich.
Danielson Mfg. Co., Lee St., Danielson, Conn.
Dapol Plastics, Inc., 53 Northboro St., Worcester 4, Mass.
Darby Corp., 1st & Walker Sts., Kansas City 15, Kan.
Dare Products, Inc., 860 Betterly Rd., Battle Creek, Mich.
Darling, L. A., Midwest Foundry Co. Div., 66-76 Clark St., Coldwater, Mich.
Darling Valve & Mfg. Co., Walnut & Marshall Sts., Williamsport, Pa.
Darlington Veneer Co., 4th St., Darlington, S.C.
Daubert Chemical Co., 333 N Michigan Ave., Chicago, Ill.
Davidson Rubber Co., 50 Brighton St., Charlestown 29, Mass.
Davis & Hemphill, 2000 Furnace Ave., Elkridge 27, Md.
Davis, Joseph Plastics Co., Kearny, N.J.
Davis Products Corp., 601 39th St., Brooklyn 32, N.Y.
Dawlen Corp., 1911 Fargo Rd., Jackson, Mich.
Day Co., 810 3rd Ave., NE, Minneapolis 13, Minn.
Day, James B. & Co., 1872 Clybourn Ave., Chicago 14, Ill.
Dayton Bronze Bearing Co., 111 Front St., Dayton 2, Ohio
Dayton Foundry, 11803 Industrial Ave., Hollydale, Calif.
Dayton Malleable Iron Co., P.O. Box 980, Dayton 1, Ohio
G. H. R. Div., 400 Detrick St., Dayton 1, Ohio
Ironton Malleable Div., Ironton, Ohio
Meta-Mold Aluminum Co., 525 E Hamilton Rd., Cedarburg, Wis.
Ohio Malleable Div., Box 88, Sta. A, Columbus, Ohio
Pratt & Letchworth Div., 189 Tonawanda St., Buffalo 7, N.Y.
Dayton Rogers Mfg. Co., 2824 13th Ave., S, Minneapolis 7, Minn.
Dayton Rubber Co., Dayton 1, Ohio
Molded Products Div., P.O. Box 209, Three Rivers, Mich.
Dayton Steel Foundry Co., 1366 Miami Chapel Rd., Dayton 1, Ohio
Dearborn Stamping Co., 10501 Haggerty Ave., Dearborn, Mich.
Debevoise Co., 74 20th St., Brooklyn 32, N.Y.
Decatur Automatic Co., P.O. Box 26, Warrensburg, Ill.
Decatur Casting Co., 822 Dayton Ave., Decatur, Ind.

Addresses of Suppliers

Decrow Engineering Corp., Main St., Middleport, N.Y.
Deerfield Mfg. Co., 4th Ave., Mason, Ohio
Defiance Metal Products Co., 21 Seneca St., Defiance, Ohio
Defiance Stamping Co., Perry & German Sts., Defiance, Ohio
De Laval Steam Turbine Co., 853 Nottingham Way, Trenton 2, N.J.
Delaware Tool Steel Corp., 34th & Market Sts., Wilmington, Del.
Delo Screw Products Co., 38 S Franklin St., Delaware, Ohio
Delron Co., Inc., 5224 Southern Ave., South Gate, Calif.
Delta Plastics Co., 776 Creek Rd., Bellmawr, N.J.
Delta Plywood Corp., Cotton Plant, Ark.
Dennis Chemical Co., 2701 Papin St., St. Louis 3, Mo.
Denver Plastics, Inc., 15200 W Colfax Ave., Golden, Colo.
Dependable Automatic Screw Co., 282 S Lenard St., Waterbury 20, Conn.
Derby Castings Co., 593 N Main St., Seymour, Conn.
Deringer Metallurgical Corp., 8131 Monticello Ave., Skokie, Ill.
De Sanno Foundry & Machine Co., 1919 Peralta St., Oakland 7, Calif.
Designers Metal Corp., 469 E 159th St., Harvey, Ill.
De Soto Paint & Varnish Co., P.O. Box 186, Garland, Tex.
Detrex Chemical Industries, Inc., Box 501, R P K Annex 32, Detroit, Mich.
Detroit Brass & Malleable Co., 2968 7th St., Wyandotte, Mich.
Detroit Float & Stamping Co., 625 Monroe St., Detroit, Mich.
Detroit Gasket & Mfg. Co., Extruded Metals Div., 12640 Burt Rd., Detroit 23, Mich.
Detroit Macoid Corp., 12340 Cloverdale, Detroit 4, Mich.
Detroit Stamping Co., 350 Midland St., Detroit 3, Mich.
Detroit Steel Corp., Portsmouth Div., Detroit 9, Mich.
Deuscher, H.P. Co., 7th & Hanover Sts., Hamilton, Ohio
Devcon Corp., Danvers, Mass.
Devoe & Raynolds Co., Inc., Jones-Dabney Co. Div., 1481 S 11th St., Louisville 8, Ky.
Dexter, C.H. & Sons, Inc., Windsor Locks, Conn.
Diamond Alkali Co., 300 Union Commerce Bldg., Cleveland 14, Ohio
Diamond Lumber Co., 323 Pittock Block, Portland 5, Ore.
Diamond Mfg. Co., W 8th St., Wyoming, Pa.
Diamonite Products Mfg. Co., Shreve, Ohio
Die Cast Products, Inc., 621 W Rosecrans Ave., Gardena, Calif.
Diecast Corp., 522-524 Hupp Ave., Jackson, Mich.
Dietzel Lead Burning Co., Narrows Run Rd., Coraopolis, Pa.
Dimco-Gray Co., 207 E 6th St., Dayton 2, Ohio
Dip Seal Plastics, Inc., 2311 23rd Ave., Rockford, Ill.
Dirilyte Co. of America, Inc., 1142 S Main St., Kokomo, Ind.
Dhogrin Industries, Inc., 510 S Fulton Ave., Mount Vernon, N.Y.
Diversey Corp., Metal Industries Div., 1820 Roscoe St., Chicago 13, Ill.
Division Lead Co., 7742 W 61st Pl., Summit, Ill.
Dixie Aluminum Corp., 304 E 2nd Ave., Rome, Ga.
Dixie Bronze Co., P.O. Box 1148, Birmingham 1, Ala.
Dixie Galvanizing & Tank Co., 1901 McQuade St., Jacksonville, Fla.
Dixie Lead Co., Sargent Rd., Box 8625, Dallas 16, Tex.
Dixie Plastics Mfg. Co., 3017 N Galves St., New Orleans, La.
Dixon Corp., Burnside St., Bristol, R.I.
**Dixon Sintaloy, Inc. (Ad p 434)**
535 Hope St., Stamford Conn.
Dodge Fibers Corp., John St., Hoosick Falls, N.Y.
Dodge Mfg. Corp., 500 S Union St., Mishawaka, Ind.
Dodge Steel Co., 6501 State Rd., Philadelphia 35, Pa.
Dolin Metal Products, Inc., 315 Lexington Ave., Brooklyn 16, N.Y.
Dollin Corp., 650 S 21st St., Irvington 11, N.J.
Donegal Steel Foundry Co., 601 E Market St., Marietta, Pa.
Donovan, F. C. Inc., 192 South St., Boston, Mass.
Dormont Mfg. Co., 5607 Butler St., Pittsburgh 1, Pa.
Dostal Foundry & Machine Co., Box 180, Pontiac, Mich.
Douglas Aircraft Co., Inc., Aircomb Div., 1720 Pico Blvd., Santa Monica Calif.
Douglas & Sturgess, 475 Bryant St., San Francisco 7, Calif.
Dow Chemical Co., Midland, Mich.
Dobeckmun Co. Div., 3301 Monroe Ave., Cleveland 13, Ohio
**Dow Metal Products Co. Div. (Ad pp 408-409)**
Midland Mich.
Plastics Div., Midland, Mich.
Dow Corning Corp., Midland, Mich.
Downer, Hunnewell, Inc., Mono-Seal Products Div., 44 Garden St., Everett 49, Mass.
Downington Iron Works, 161 Wallace St., Downington, Pa.
Dravo Corp., 102 5th Ave., Pittsburgh 22, Pa.
Drawn Metal Tube Co., 101 Elm St., Thomaston, Conn.
Dresser Industries, Inc., Dresser Mfg. Div., 43 Fisher Ave., Bradford, Pa.
Dresser Operations, Inc., Clark Bros. Co. Div., Lincoln Ave. & 5th St., Olean, N.Y.
Drexel Screw Products Co., 6200 S Oakley Ave., Chicago 36, Ill.
**Driver, Wilbur B. Co. (Ad p 185)**
1875 McCarter Hwy., Newark 4, N.J.
Western Gold & Platinum Co. Sub., 525 Harbor Blvd., Belmont, Calif.
Driver-Harris Co., 201 Middlesex St., Harrison, N.J.
Driv-Lok Sales Corp, 777 Park Ave., Sycamore, Ill.
Duane Specialties, Ltd., 2 Johnson St., Newark 5, N.J.
Du-Co Ceramics Co., Box 278, Saxonburg, Pa.
Ductile Iron Foundry, Inc., Honeyspot Rd. Extension, Stratford, Conn.
Dudek & Bock Spring Mfg. Co., 4014 W Grand Ave., Chicago 51, Ill.
Duffin Mfg. Co., 2307 Leavitt Rd., Lorain, Ohio
Du-Lite Chemical Corp., Middletown, Conn.
Duluth Brass Works Co., 5002 Ramsey St., Duluth 7, Minn.
**Dumont Corp. (Ad p 428)**
607 Irwin St., San Rafael, Calif.
Dunnican Assoc., 352 Plymouth Rd., Union, N.J.
Duplex Mfg. Corp., P.O. Box 418, Fort Smith, Ark.
Duplican Co., Inc., 1221 Turnpike Rd., Westboro, Mass.
**du Pont de Nemours, E. I. & Co., Inc. (Ad pp 231, 315)**
Wilmington 98, Del.
Dura Plastics of New York, Inc., 303 5th Ave., New York 16, N.Y.
Durable Formed Products, Inc., 74 Varick St., New York 13, N.Y.
Durable Rubber Products Co., 609 W Lake St., Chicago 6, Ill.
Duralac Chemical Corp., 84 Lister Ave., Newark 5, N.J.
Dura-Lee Corp., 1102 S Mill, Kansas City, Kan.
**Duraloy Co. (Ad p 417)**
Bridge St., Scottdale, Pa.
Durethene Corp., 1859 S 55th Ave., Chicago 50, Ill.
Duriron Co., Inc., 450 N Findlay St., Dayton, Ohio
Modern Industrial Plastics Div., Box 1019, Dayton 1, Ohio
Duro Screw & Mfg. Co., 1064 Springfield Rd., Union, N.J.
Du-Wel Metal Products, Inc., P.O. Box 307 Bangor Mich
Dyna-Therm Chemical Corp., 3813 Hoke St., Culver City, Calif.
Plas-Kem Corp. Div., 100 W Alameda St., Burbank, Calif.

## e

Eagle-Picher Co., American Bldg., Cincinnati 1, Ohio
Chicago Vitreous Corp. Div., 1425 S 55th Ct., Cicero 50, Ill.
**Fabricon Products Div. (Ad p 275)**
1721 W Pleasant Ave., River Rouge 18, Mich.
Earl Paint Corp., 240 Genesee St., Utica 2, N.Y.
Earley, Sam C. Corp., 3230 Monroe St., Toledo 6, Ohio
East Birmingham Bronze Foundry Co., 831 N 36th Way, Birmingham 4, Ala.
Eastern Brass & Copper Co., 1122 E 180th St., New York 60, N.Y.
Eastern Machine Screw Corp., Truman & Barclay Sts., New Haven 6, Conn
Eastern Malleable Iron Co., P.O. Box 349, Wilmington 99, Del.
Eastern Rolling Mills, Inc., 1122 E 180th St., New York 60, N.Y.
Eastern Smelting & Refining Corp., 109 W Brookline St., Boston 18, Mass.
Eastern Stainless Steel Corp., P.O. Box 1975, Baltimore 3, Md.
Eastern Tool & Mfg. Co., 1 Montgomery St., Belleville 9, N.J.
Eastern Tool & Stamping Co., Inc., 110 Ballard St., Saugus, Mass.
Eastman Kodak Co., 343 State St., Rochester 4, N.Y.
**Eastman Chemical Products, Inc. Sub. (Ad p 494)**
260 Madison Ave., New York 16, N.Y.
Texas Eastman Co. Div., Longview, Tex.
Easton Plastic Products Co., Inc., 900 Line St., Easton, Pa.
Eaton Mfg. Co., 9711 French Rd., Detroit, Mich.
**Foundry Div. (Ad p 459)**
700 E Huron, Vassar, Mich.
Powdered Metals Div., 325 Jay St., Coldwater, Mich.
Reliance Div., 25 Charles Ave., Massillon, Ohio
Eberhart Steel Products, Powdered Metals Div., 317 E Jefferson Blvd., Mishawaka, Ind.
Eby, Hugh H. Co., 4701 Germantown Ave., Philadelphia 20, Pa.
Eclipse Plastic Industries, Inc., Box 430, Sarasota, Fla.
Economy Machine Products Co., 5214 W Lawrence Ave., Chicago 30, Ill.
Edgar Plastic Kaolin Co., Materdyne Ave., Edgar, Fla.
Edgcomb Steel & Aluminum Corp., Hillside Ave., N.J.
Edgewater Steel Co., Box 478, Pittsburgh, Pa.
Edna Lite Optical Co., Inc., 200 N Water St., Peekskill, N.Y.
Egan & Hausman Co., Inc., 9-02 43rd Rd., Long Island City 1, N.Y.
Egyptian Lacquer Mfg. Co., P.O. Box 444, Newark 1, N.J.
Ehrsam, J. B. & Sons Mfg. Co., Enterprise, Kan.
Eimco Corp., American Foundry & Machine Div., P.O. Box 300, Salt Lake City 10, Utah
Ekstrand & Tholand, 420 Lexington Ave., New York 17, N.Y.
Elastic Stop Nut Corp. of America, 2330 Vauxhall Rd., Union, N.J.
Elastomer Chemical Corp., 212 Wright St., Newark 7, N.J.
Elchinger, Charles F., 916 Magazine St., New Orleans 12, La.
Elco Tool and Screw Corp., 1800 Broadway, Rockford, Ill.
Electric Autolite Co., Champlain & Mulberry Sts., Toledo 1, Ohio
Ceramic Div., Fostoria, Ohio
Woodstock Div., 501 Clay St., Woodstock, Ill.
Electric Materials Co., Clay & Washington Sts., North East, Pa.
Electric Steel Castings Co., 1045 Main St. Speedway, Indianapolis 24, Ind.
Electric Steel Foundry Co., 2141 NW 25th Ave., Portland 10, Ore.
Electric Storage Battery Co., Stokes Molded Products Div., Taylor St. & Webster, Trenton 4, N.J.
Electrical Refractories Co., East Palestine, Ohio
Electro Chemical Engineering & Mfg. Co., 750 Broad St., Emmaus, Pa.
Electro Refractories & Abrasives Corp., Willett Rd., Lackawanna 18, N.Y.
Electrocast Steel Foundry Co., 4701 W 15th Pl., Cicero 50, Ill.
Electrofilm, Inc., 7116 Laurel Canyon Blvd., North Hollywood, Calif.
Electrolizing Co., 1505 East End Ave., Chicago Heights, Ill.
Electron Corp., 651 Rio Grande Ave., Littleton, Colo.
Electronic Parts Mfg. Co., Inc., 508 25th St., Union City, N.J.
Electronic Production & Development, Inc., Chemical Div., 501 N Prairie Ave., Hawthorne, Calif.
Elgin National Watch Co., 107 National St., Elgin, Ill.
Eljay Corp., 2900 Herbert St., Baltimore 16, Md.
Elk Engineering Works, Inc., 220 Stackpole St., St. Marys, Pa.
Elkhart Foundry & Machine Co., Inc., 220-330 S Elkhart Ave., Elkhart, Ind.
Elkhart Iron Works, 1217-33 Broad St., St. Joseph, Mich.
Elliott Bros. Steel Co., 902-914 N Cedar St., New Castle, Pa.
Ellwood City Iron & Wire Co., 416 Pittsburgh Circle, Ellwood City, Pa.
Elm Coated Fabrics Co., Inc., 261 5th Ave., New York 16, N.Y.
Elsby, J.S. Inc., 3223 W Burnham St., Milwaukee 15, Wis.
Emerson & Cuming, Inc., 869 Washington St., Canton, Mass.
Emerson-Sack-Warner Corp., 85 Washington St., Somerville, Mass.
Emery, George D. Co., 220 11th Ave., New York, N.Y.
Emmaus Foundry & Machine Co., 4th & Furnace Sts., Emmaus, Pa.
Empire Foundry Co., Inc., 429 3rd St., Oakland 7, Calif.
Empire Metal Co., 820 E Water St., Syracuse 3, N.Y.

***In contacting suppliers, please mention the Materials Selector Issue***

Empire Pattern and Foundry Co., P.O. Box 1647, Tulsa 1, Okla.
Empire Spring Co., 210 S Albe St., Elyria, Ohio
Empire Steel Castings, Inc., P.O. Box 139, Reading, Pa.
Enamel Products Co., 341 Eddy Rd., Cleveland 8, Ohio
Endicott Forging & Mfg. Co., Inc., 1901 North St., Endicott, N.Y.
Enflo Corp., Fellowship Rd. & Rt. #73, Maple Shade, N.J.
Engelhard Industries, Inc., 904 Passaic Ave., East Newark, N.J.

**American Platinum & Silver Div. (Ad pp 158-159, 493)**
231 New Jersey R.R. Ave., Newark 5, N.J.

**Amersil Quartz Div. (Ad pp 158-159)**
685 Ramsey Ave., Hillside, N.J.

Baker Platinum Div., 113 Astor St., Newark, N.J.

**Makepeace, D.E. Div. (Ad pp 158-159)**
Pine & Durham Sts., Attleboro, Mass.

Wilson, H. A. Div., 2655 U.S. Rte. 22, Union, N.J.

Engineered Ceramics Mfg. Co., 1435 W Fulton St., Chicago 7, Ill.
Engineered Plastics, Inc., American Sinterings Div., P.O. Drawer P, Watertown, Conn.
Engineered Precision Casting Co., Highway 79, P.O. Box 68, Matawan, N.J.
Engineering Products & Specialties, Inc., Dunnel Lane, Pawtucket, R.I.
Englander Co., Inc., Industrial Products Div., 227 N. Warwick Ave., Baltimore 23, Md.
Enoch Mfg. Co., P.O. Box 5201, Portland 16, Ore.
Enterprise Galvanizing Co., 2507 E Cumberland St., Philadelphia 25, Pa.
Enterprise Wheel & Car Corp., P.O. Box 151, Bristol, Va.
**Enthone, Inc. (Ad p 350)**
442 Elm St., New Haven 8, Conn.
Erdle Perforating Co., Inc., 171 York St., Rochester 11, N.Y.
Erie Bolt & Nut Co., 1325 Liberty St., Erie, Pa.
Erie Bronze Co., 19th & Chestnut Sts., Erie, Pa.
Erie Casting Co., 1534 German St., Erie, Pa.
Erie Ceramic Arts Co., 3120 W 22nd St., Erie, Pa.
Erie Enameling Co., 1400 W 20th St., Erie 4, Pa.
Erie Malleable Iron Co., 680 W 12th St., Erie, Pa
Erie Resistor Corp., Plastics Div., 644 W 12th St., Erie, Pa.
Erie Scientific Corp., 693 Seneca St., Buffalo 10, N.Y.
Erskine Precision Wire Corp., 210 S Broad St., Emporium, Pa.
Ervite Corp., 4000 W Ridge Rd., Erie, Pa.
Escambia Chemical Corp., 261 Madison Ave., New York 16, N.Y.
Essential Bar Products Co., 2526 Brooklyn Road, Jackson, Mich.
Essex Wire Corp., 1601 Wall St., Fort Wayne, Ind.
Carolina Industrial Plastics Div., Mount Airy, N.C.
Essex Industrial Products Div., 2601 S Adams, Marion, Ind.
Magnet Wire Div., 1601 Wall St., Fort Wayne, Ind.
Est Co., Inc., Grafton, Wis.
Etched Products Corp., 1100 Brook Ave., New York 56, N.Y.
Ethylene Chemical Corp., 245 Broad St., Summit, N.J.
Eureka Electric Products Co., Clay St., North East, Pa.
Eutectic Welding Alloys Corp., 40-40 172nd St., Flushing 58, N.Y.
Evans, George Corp., 121 37th St., Moline, Ill.
Evans Metal Co., 740 Lambert Dr. NE, Atlanta 5, Ga.
Evans Products Co., Hardboard Div., P.O. Box 651, Corvallis, Ore.
Everard Tap & Die Corp., 215 E 144th St., New York 51, N.Y.
Everlite Corp., 1218 E Cherry St., Seattle 22, Wash.
**Exalco Mfg. Co. (Ad p 420)**
46 Sheldon Rd., Berea, Ohio
Excelsior Leather Washer Mfg. Co., Inc., 720 Chestnut St., Rockford, Ill.
Exeter Mfg. Co., 1451 Broadway, New York 36, N.Y.
Exmet Corp., 127 Marbledale Rd., Tuckahoe, N.Y.
Extruders, Inc., 3232 W El Segundo Blvd., Hawthorne, Calif.
Eynon-Dakin Co., 9900 Freeland Ave. Detroit 27, Mich.

# f

Fabristeel Products, Inc., 21500 W 8 Mile Rd., Detroit 41, Mich.
Fahralloy Co., 149th St. & Loomis St., Harvey, Ill.
Fairbanks, Morse & Co., Beloit, Wis.
Fairchild Screw Products, Inc., White St., Winsted, Conn.
Fairfield Aluminum Castings Co., 603 N 8th St., Fairfield, Iowa
**Fairmont Aluminum Co. (Ad p 161)**
Fairmont, W Va.
Faige Engineering Corp., 4733 Elm St., Bethesda 14, Md.
Falk Corp., Box 492, Milwaukee 1, Wis.
Falls Machine Co., 1625 Massillon Rd., Akron 12, Ohio
Falstrom Co., 70 Falstrom Ct., Passaic, N.J.
Fanner Mfg. Co., Brookside Park, Cleveland 9, Ohio
Munray Products Div., 12400 Crossburn Ave., Cleveland 11, Ohio
**Fansteel Metallurgical Corp. (Ad pp 174-175)**
North Chicago, Ill.
**Farley & Loetscher Mfg. Co., Plastics Div. (Ad p 276)**
7th & White, Dubuque, Iowa
Farnam Mfg. Co., 2000 Sweeten Creek Rd., Asheville, N.C.
Farrel-Birmingham Co., Inc., 25 Main St., Ansonia, Conn.
Farrelloy Co., 1243-45 N 26th St., Philadelphia 21, Pa.
Farwell Metal Fabricating, 77 W Fairfield Ave., St. Paul 7, Minn.
Faultless Rubber Co., Ashland, Ohio
Fearon Foundry Co., 1420 W Kinzie St., Chicago 22, Ill.
Federal Die Casting Co., 2226 N Elston, Chicago, Ill.
Federal Machine and Welder Co., 1745 Overland Ave. NE, Warren, Ohio
Federal Malleable Co., 805 S 72nd St., Milwaukee, Wis.
Federal Screw Works, Congdon St., Chelsea, Mich.
Federal Steel Products Corp., 415 N St. Charles St., Houston 3, Tex.
**Federal Tool Corp. (Ad p 436)**
3600 W Pratt Blvd., Chicago 45, Ill.
Federal Tool Mfg. Co., 3600 Alabama Ave., Minneapolis 16, Minn.
Felt Products Mfg. Co., 7450 N McCormick Blvd., Skokie, Ill.
**Felters Co. (Ad p 310)**
220 South St., Boston 11, Mass.
Femco Mfg. Co., Inc., 22845 Hoover Rd., Detroit 5, Mich.
Fenestra, Inc., 2250 E Grand Blvd., Detroit 11, Mich.
Ferro Corp., 4150 E 56th St., Cleveland 5, Ohio
**Fiber Glass Div. (Ad p 321)**
Fiber Glass Rd., Nashville 11, Tenn.
Louthan Mfg. Co. Div. P.O. Box 781, East Liverpool, Ohio
Ferro Enameling Co., 1100 57th Ave., Oakland 21, Calif.
Ferro Powdered Metals, Inc., Box 312, Salem, Ind.
Ferro-Co Corp., Schorl Process Div., 8-11 43rd Rd., Long Island City 1, N.Y.
Ferroxcube Corp. of America, E Bridge St., Saugerties, N.Y.
Fiber Glass Industries, Inc., Amsterdam, N.Y.
Fiberfil, Inc., Fox Farm Road, Warsaw, Ind.
Fiberglass Ohio Inc., 9603 Clinton Rd., Cleveland 9, Ohio
**Fiberite Corp. (Ad p 281)**
516 W 4th, Winona, Minn.
Fibron Products, Inc., 500 Fibron Bldg., 45 Mechanic St., Buffalo 2, N.Y.
Fidelity Chemical Products Corp., 470 Frelinghuysen Ave., Newark 12, N.J.
Fidelity Felt & Mfg. Co., 22 W 15th St., New York 11, N.Y.
Figley Die & Stamping Co., 401 Agnes St., Defiance, Ohio
Filon Plastics Corp., 333 N Van Ness Ave., Hawthorne, Calif.
Filpaco Industries, Inc., 2426 S Michigan Ave., Chicago 16, Ill.
Fine Organics, Inc., 209-211 E 19th St., New York, N.Y.
Finkl, A. & Sons Co., 2011 Southport Ave., Chicago 14, Ill.
Firestone Plastics Co., P.O. Box 690, Pottstown, Pa.
Firestone Tire & Rubber Co., 1200 Firestone Pkwy., Akron 17, Ohio
Firestone Rubber & Latex Products Co., Div., 1 Firestone Ave., Fall River, Mass.
World Bestos Div., 1112 S 25th St., New Castle, Ind.
**Firmaline Products of Crompton & Knowles (Ad p 457)**
7 Pierce Ave., Midland Park, N.J.
Firth Sterling, Inc., 3113 Forbes Ave., Pittsburgh, Pa.
Fischer Casting Co., Inc., P.O. Box M, Dunellen, N.J.
Fischer & Porter Co., 510 Jacksonville Rd., Warminster, Pa.
Warminster Fiberglass Co. Div., County Line & Warminster Rd., Warminster, Pa.
Fischer Special Mfg. Co., 450 Morgan St., Cincinnati 20, Ohio
Fish-Schurman Corp., 70 Portman Rd., New Rochelle, N.Y.
Fitchburg Foundry, Inc., Benson St., Fitchburg, Mass.
Fitzgibbons Boiler Co., Inc., Oswego, N.Y.
FitzSimons Mfg. Co., 3775 E Outer Drive, Detroit 34, Mich.
Fletcher Enamel Co., P.O. Box 67, Dunbar, W. Va.
Flexfirm Products, 2300 N Chico Ave., El Monte, Calif.
Flexible Tubing Corp., Guilford, Conn.
Flexonics Corp., 1315 S 3rd Ave., Maywood, Ill.
Flexrock Co., 36th & Filbert Sts., Philadelphia 1, Pa.
Fluoro-Plastics Inc. Div., 36th & Filbert Sts., Philadelphia 1, Pa.
Flood City Brass & Electric Co., Messenger & Elder Sts., Johnstown, Pa.
Florence Pipe Foundry & Machine Co., Front St., Florence, N.J.
Florin Foundry & Mfg. Co., Florin, Pa.
Fluorocarbon Co., 1754 S Clementine St., Anaheim, Calif.
Flynn & Emrich Co., 301 Holliday St., Baltimore 2, Md.
Flynn, Michael Mfg. Co., 700 E Godfrey Ave., Philadelphia 24, Pa.
Foam Products, Inc., P.O. Box 27, Manchester, Pa.
Foamade Industries, 14851 W 11 Mile Rd., Oak Park 37, Mich.
Foamalum Corp., 508 Water St., Peru, Ill.
Follansbee Steel Corp., Sheet Metal Specialty Div., P.O. Box 567, Follansbee, W. Va.
Food Machinery & Chemical Corp., 161 E 42nd St., New York 17, N.Y.
Chemicals & Plastics Div., 161 E 42nd St., New York 17, N.Y.
F M C Organic Chemicals Div., 161 E 42nd St., New York 17, N.Y.
Sonith Foundries Div., 50 Shelby St., Indianapolis 6, Ind.
Foote Mineral Co., 18 W Chelten Ave., Philadelphia 44, Pa.
Fordsell Machine Products Co., 4433 E 8 Mile Rd., Warren, Mich.
Forest City Foundries Co., 2500 W 27th St., Cleveland 13, Ohio
Forg, Peter Mfg. Co., Park St., Somerville 43, Mass.
Formed Tubes, Inc., Prairie & Albert Sts., Sturgis, Mich.
Fort Howard Steel & Wire Co., 200 9th St., Green Bay, Wis.
Fort Worth Steel & Machinery Co., 3504 Jackson St., Fort Worth, Tex.
Foss Mfg. Co., P.O. Box 553, Twin Falls, Id.
Foster Aluminum Alloy Products Corp., Pearl St., Forestville, N.Y.
Foster Grant Co., 289 N Main St., Leominster, Mass.
Foster Wheeler Corp., 165 Broadway, New York, N.Y.
Fox Co., 3400 Beekman St., Cincinnati, Ohio
Fox Edge Co., Inc., 1995 Middlesex St., Lowell, Mass.
Fox Products Co., 4720 N 18th St., Philadelphia 41, Pa.
France, J. H. Refractories Co., 710 France Rd., Snow Shoe, Pa.
Franklin Cotton Mill Co., 1106 Central Pkwy., Cincinnati 10, Ohio
Franklin Glue Co., 119 Chestnut St., Columbus 15, Ohio
Franklin Mineral Products Co., P.O. Box 28, Franklin, N.C.
Franklin Plastics, Inc., 315 Grant St., Franklin, Pa.
**Frasse, Peter A. & Co., Inc. (Ad p 179)**
17 Grand St., New York 13, N.Y.
Frederick Iron & Steel, Inc., 7th & East Sts., Frederick, Md.
Fremont Casting Co., 105 Fremont St., Worcester, Mass.
Frenchtown Porcelain Co., Frenchtown, N.J.
Friedrich & Dimmock, Inc., Lincoln Ave., Millville, N.J.
Frisby, R. J. Mfg. Co., 246 N Western Ave., Chicago 12, Ill.
Fromson Orban Co., Inc., 261 Madison Ave., New York, N.Y.
**Frontier Bronze Corp. (Ad p 178)**
4870 Packard Road, Niagara Falls, N.Y.
Frost Paint & Oil Corp., 1203 NE Tyler, Minneapolis, Minn.
Frost Rubber Co., 1407 N Dayton St., Chicago 22, Ill.
Fry Plastics International, 8601 S Figueroa, Los Angeles 3, Calif.
Fryling Mfg. Co., 531 W 11th St., Erie, Pa.
Fuller, H. B. Co., 255 Eagle, St. Paul 2, Minn.
Fuller, W. P. & Co., 301 Mission St., San Francisco, Calif.
Fullerton Mfg. Co., 343 E Santa Fe Ave., Fullerton, Calif.
Fulton Foundry & Machine Co., Inc., Cleveland, Ohio

Addresses of Suppliers

Fulton Gold Refiners Corp., 71 Fulton St., New York 38, N.Y.
Furane Plastics, Inc., 4516 Brazil St., Los Angeles 39, Calif.

# g

G. & C. Foundry Co., W Monroe & Olds St., Sandusky, Ohio
G & G Mfg. Co., 3223 W Fillmore St., Chicago 24, Ill.
G & Z Automatic Products Co., 2434 Brooklyn Rd., Jackson, Mich.
Gale Mfg. Co., 115 N Albion St., Albion, Mich.
Gallgher Co., 545 W 8th St., P.O. Box 209, Salt Lake City 10, Utah
Gamble Bros., Inc., Special Products Div., 4601 Allmond Ave., Louisville 9, Ky.
Gantner Screw Products Co., Inc., 20 S Walnut St., Springfield, Ohio
Gar Precision Parts, Inc., 190 Henry St., Stamford, Conn.
Garco Mfg. Co., Inc., 744 N Ada St., Chicago 22, Ill.
Garden State Forge Co., 1501 Jersey St., South Plainfield, N.J.
Garfield Mfg. Co., 10 Midland Ave., Wallington, N.J.
Garlock Packing Co., 402 Main St., Palmyra, N.Y.
U.S. Gasket Plastics Div., 600 N 10th St., Camden 1, N.J.
Gartland Foundry Co., 4th & Grant Sts., Terre Haute, Ind.
Gartland-Haswell Foundry, Inc., 430 W Park St., Sidney, Ohio
Gary Lynn Co., 926 York St., Cincinnati 14, Ohio
Gary Steel Products Corp., P.O. Box 449, Lynchburg, Va.
Gates Engineering Co., 100 S West St., Wilmington 99, Del.
Gates Rubber Co., 999 S Broadway, Denver, Colo.
Gatke Corp., Engineering Div., 228 N LaSalle St., Chicago 1, Ill.
Geauga Industries Co., Middlefield, Ohio
General Alloys Co., 405 W 1st St., South Boston, Mass.
General Aluminum Mfg. Co., 3027 E 55th St., Cleveland 27, Ohio
General American Transportation Corp., 135 S LaSalle St., Chicago 3, Ill.
**Kanigen Div. (Ad p 355)**
135 S LaSalle St., Chicago 3, Ill.
Parker-Kalon Div., 1 Peekay Dr., Clifton, N.J.
**Plastics Div. (Ad p 411)**
135 S LaSalle St., Chicago 3, Ill.
Plate & Welding Div., 135 S LaSalle St., Chicago 3, Ill.
General Aniline & Film Corp., Antara Chemicals Div., 435 Hudson St., New York 14, N.Y.
General Asbestos Gasket Mfg. Corp., 1721 S 7th St., St. Louis 4, Mo.
General Cable Corp., 420 Lexington Ave., New York 17, N.Y.
General Chain & Mfg. Corp., 3182 Beekman St., Cincinnati 23, Ohio
General Drop Forge Corp., 1738 Elmwood Ave., Buffalo, N.Y.
General Dynamics Corp., Liquid Carbonic Div., 135 S LaSalle St., Chicago 3, Ill.
General Electric Co., 1 River Rd., Schenectady 5, N.Y.
Chemical Materials Dept., 1 Plastics Ave., Pittsfield, Mass.
Chemical & Metallurgical Div., 2200 N 22nd St., Decatur, Ill.
Foundry Dept., 1 River Rd., (Bldg. 96), Schenectady, N.Y.
Insulating Materials Dept., 23 River Rd., Schenectady 5, N.Y.
Laminated Products Dept., Coshocton, Ohio
Lamp Wire & Phosphors Dept., 21800 Tungsten Rd., Cleveland 17, Ohio
Metallurgical Products Dept., P.O. Box 237, Roosevelt Park Annex, Detroit 32, Mich.
Plastics Dept., N 22nd St., Decatur, Ill.
Silicone Products Dept., Waterford, N.Y.
General Engineering Works, 4701 W Division St., Chicago 51, Ill.
**General Extrusions, Inc. (Ad p 462)**
4040 Lake Park Rd., Youngstown 12, Ohio
General Findings & Supply Co., Industrial Div., School & Pearl Sts., Attleboro, Mass.
General Foundry & Mfg. Co., Flint, Mich.
General Gasket, Inc., Middletown, Conn.
General Industries Co., Molded Plastic Div., Taylor & Olive Sts., Elyria, Ohio
General Iron Works Co., P.O. Box 2490, Denver 1, Colo.
General Malleable Corp., 706 E Main St., Waukesha, Wis.
General Metals Corp., 550 85th Ave., Oakland, Calif.
General Metals Powder Co., 130 Filnor Ave., Akron 5, Ohio
General Mills, Inc., Chemical Div., S Kensington Rd., Kankakee, Ill.
General Motors Corp., General Motors Bldg., Detroit, Mich.
Brown Lipe Chapin Div., GM Circle, Town Line Rd., Syracuse 1, N.Y.
Central Foundry Div., 37 Florence St., Saginaw, Mich.
Fabricast Div., 3rd & Monon, Bedford, Ind.
Moraine Products Div., 1420 Wisconsin Blvd, Dayton 1, Ohio
**Rochester Products Div. (Ad p 435)**
1000 Lexington Ave., Rochester 3, N.Y.
General Plastics Corp., 1400 N Washington St., Marion, Ind.
General Plastics Corp., 165 3rd Ave., Paterson, N.J.
General Plastics Mfg. Co., 3481 S 35th St., Tacoma 9, Wash.
General Powdered Metal Products, Inc., Holly Corp., 523 West Ave., Norwalk, Conn.
General Refractories Co., 1520 Locust St., Philadelphia 2, Pa.
General Screw Products Corp., 1190 Brooks Ave., Rochester 19, N.Y.
General Sintering Corp., 1830 N 32 Ave., Melrose Park, Ill.
General Smelting Co., 2901 E Westmoreland St., Philadelphia, Pa.
General Steel Castings Corp., 1417 State St., Granite City, Ill.
General Tire & Rubber Co., 1700 Factory Ave., Marion, Ind.
Bolta Products Div., 70 Garden St., Lawrence, Mass.
Chemical Div., 1485 Archwood, Akron 9, Ohio
Industrial Products Div., Wabash, Ind.
Marion Div., Marion, Ind.
Respro Div., 530 Wellington Ave., Cranston 10, R.I.
Textileather Div., 607 Madison Ave., Toledo 8, Ohio
General Veneer Mfg. Co., 8652 Otis, South Gate, Calif.
Genesee Laboratory, Inc., 16 Garden St., Auburn, N.Y.
Geometric Stamping Co., 1111 E 200th St., Cleveland 17, Ohio
George, P. D. Co., 5100 N 2nd St., St. Louis, Mo.
Georgia Iron Works, Augusta, Ga.
Georgia-Pacific Corp., Equitable Bldg., Portland, Ore.
Gerstenslager Co., E Bowman St., Wooster, Ohio
Geuder, Paeschke & Frey Co., 324 N 15th St., Milwaukee 1, Wis.
Giant Grip Mfg. Co., 113 Osceola St., Oshkosh, Wis.
Gibb Walton Leather Co., 54th & Grays Ferry Ave., Philadelphia 43, Pa.
**Gibson Electric Co. (Ad p 466)**
Box 545, Delmont, Pa.
Gibson & Kirk Co., Warner & Bayard St., Baltimore 30, Md.
Gilbert & Bennett Mfg. Co., Georgetown, Conn.
Gilbert Brass Foundry Co., 5036 Farlin Ave., St. Louis 15, Mo.
Gillett & Eaton, Inc., 847 Doughty, Lake City, Minn.
Gilman Bros. Co., Gilman, Conn.
Gisholt Machine Co., Masterglas Div., 1245 E Washington Ave., Madison 10, Wis.
Gladding, McBean & Co., Technical Ceramic Div., 1551 S Primrose Ave., Monrovia, Calif.
Glamorgan Pipe and Foundry Co., P.O. Drawer 740, Lynchburg, Va.
Glasby, J. P. Mfg. Co., Inc., 1 Montgomery St., Belleville 9, N.J.
Glaskyd, Inc., Eckel Rd., Perrysburg, Ohio
Glass Laboratories, 863 65th St., Brooklyn 20, N.Y.
Glass Reinforced Plastics Corp., 405 W Sophia, Maumee, Ohio
**Glastic Corp. (Ad p 256)**
4321 Glenridge Rd., Cleveland 21, Ohio
Gleason Corp., Anthes Div., 20th St. & Ave. M, Fort Madison, Iowa
Glenn, Joseph & Sons, Inc., Clifton Hts., Pa.
Glidden Co., 1717 Summer St., Hammond, Ind.
**Chemical Divs., Metals Dept. (Ad p 429)**
1717 Summer St., Hammond, Ind.
**Industrial Paint Div. (Ad p 248)**
900 Union Commerce Bldg., Cleveland 14, Ohio
Globe Imperial Corp., Plastic-Seal Div., 2038 Kishwaukee, Rockford, Ill.
**Globe Industries, Inc., Supermet Div. (Ad p 464)**
1466 Cincinnati St., Dayton 8, Ohio
Globe Paint Works, Inc., P.O. Box 36, Williamsport, Pa.
Globe Steel Abrasive Co., 238 1st Ave., Mansfield, Ohio
**Globe Union, Inc., Centralab Div. (Ad p 449)**
946 E Keefe Ave., Milwaukee 1, Wis.
Glo-Brite Products, Inc., 6415 N California Ave., Chicago 45, Ill.
Glover Machine Works, Butler St., Marietta, Ga.
Gluntz Brass & Aluminum Foundry Co., 10815 Harvard Ave., Cleveland 5, Ohio
Gold Leaf & Metallic Powders, Inc., 145 Nassau St., New York, N.Y.
Gomar Mfg. Co., Inc., 1501 W Blancke St., Linden, N.J.
Goodrich, B.F. Chemical Co., 3135 Euclid Ave., Cleveland 15, Ohio
Hood Rubber Co. Div., 99 Nichols Ave., Watertown, Mass.
Sponge Products Div., Shelton, Conn.
Goodrich, B.F. Industrial Products Co., 500 S Main St., Akron, Ohio
Goodrich-Gulf Chemicals, Inc., 1717 E 9th St., Cleveland 14, Ohio
Goodyear Tire & Rubber Co., 1144 F Market St., Akron 16, Ohio
Chemical Div., 1144 E Market St., Akron 16, Ohio
Gordon Chemicals, Inc., 500 A St., Wilmington 99, Del.
**Goshen Rubber Co., Inc. (Ad p 438)**
1525 S 19th St., Goshen, Ind.
Goslin Birmingham Mfg. Co., Inc., 3521 10th Ave. N, Birmingham 1, Ala.
Gossett and Hill Co., 7185 W Bloomingdale, Chicago 35, Ill.
Gotham Plastics Corp., 220 E 134 St., New York 51, N.Y.
Gowanda Furnaces, Inc., 7 Palmer St., Gowanda, N.Y.
Grace, W.R. & Co., 7 Hanover Sq., New York, N.Y.
Davison Chemical Co. Div., Baltimore 3, Md.
Dewey & Almy Chemical Co. Div., 62 Wittemore Ave., Cambridge 40, Mass.
Polymer Chemicals Div., 225 Allwood Rd., Clifton, N.J.
Grafton Foundry Co., 1003 Bridge St., Grafton, Wis.
Graham, James Co., 293 Wooster St., New Haven Conn.
Gra-Iron Foundry Corp., 501 S 12th Ave., Marshalltown, Iowa
Grammes, L.F. & Sons, Inc., 380 Union St., Allentown, Pa.
Grand Haven Stamped Products Co., Griffen & Madison Sts., Grand Haven, Mich.
Grand Rapids Brass Co., 420 50th St., SW, Grand Rapids 8, Mich.
Grand Rapids Varnish Corp., 1350 Steele St., SW, Grand Rapids, Mich.
Grand Sheet Metal Products Co., Consumer Products Div., 2055 Ruby St., Melrose Park, Ill.
Granite City Steel Co., 20th & Madison Aves., Granite City, Ill.
Graphite Metallizing Corp., 1050 Nepperhan Ave., Yonkers 3, N.Y.
Graphite Products Corp., Trumbull County, Brookfield, Ohio
**Graphite Specialties Corp. (Ad p 309)**
64th St. & Pine Ave., Niagara Falls, N.Y.
Grass, M.J. Machine Products Co., 19 Northampton St., Buffalo 9, N.Y.
Graton & Knight Co., 356 Franklin St., Worcester, Mass.
Gray-Syracuse, Inc., W Seneca St., Manlius, N.Y.
Great American Industries, Inc., Rubatex Div., Bedford, Va.
Great Lakes Carbon Corp., 18 E 48th St., New York 17, N.Y.
Grede Foundries, Inc., 1320 S 1st St., Milwaukee 1, Wis.
Green Bay Foundry & Machine Works, 401 S Broadway, Green Bay, Wis.
Green, A.P. Fire Brick Co., Mexico, Mo.
Green River Steel Corp., P.O. Drawer 637, Owensboro, Ky.
Greenback Industries, Inc., 2527 W Maple Rd., Birmingham, Mich.
Greene, G.G. Corp., Box 900, Warren, Pa.
Greene Mfg. Co., 1028 Douglas Ave., Racine, Wis.
Greene, Tweed & Co., North Wales, Pa.
Greenlee Foundry Co., 4600 W 14th St., Chicago 50, Ill.
Green-Walker Galvanizing Co., Inc., 5002 Jefferson Highway, New Orleans 21, La.
Greer Stop Nut Co., 2620 W Flournoy St., Chicago 12, Ill.

***In contacting suppliers, please mention the Materials Selector Issue***

Gregg Metal Products Inc., 1333 N 9th St., Milwaukee 5, Wis.
Gregory Industries Inc., Nelson Stud Welding Div., 28th St. & Toledo Ave., Lorain, Ohio
Gregory Thomas Galvan Works, 4900 Grand Ave., Maspeth 78, N.Y.
Grems Mfg. Co., 5635 S 6th St., Klamath Falls, Ore.
Grey, C.M. Industries, Inc., 358 Central Ave., East Orange, N.J.
Gries Reproducer Corp., 153 Beechwood Ave., New Rochelle, N.Y.
Grigoleit Co., 740 E North, Decatur, Ill.
Grimes Mfg. Co., Plastic Research Products, 200 Beech St., Urbana, Ohio
Grimm Foundry Co., Inc., Chimney Rock Rd., Bound Brook, N.J.
**Grip Nut Co. (Ad p 498)**
Broad & Maple Sts., South Whitley, Ind.
Groov-Pin Corp., 1125 Hendricks Causeway, Ridgefield, N.J.
Gross, Willard N., Inc., 224 Highland Ave., Westmont, Collingswood, N.J.
Guarantee Specialty Mfg. Co., 9651 Carr Ave., Cleveland 8, Ohio
Guilfoy Cornice Works, 1234 Howard St., San Francisco 3, Calif.
Gulton Industries, Inc., 212 Durham Ave., Metuchen, N.J.
Gunite Foundries Corp., 302 Peoples Ave., Rockford, Ill.
Gustin-Bacon Mfg. Co., 210 W 10th St., Kansas City 5, Mo.

# h

H & H Foundry Machine Co., P.O. Box 238, Jeanette, Pa.
H & H Screw Products, Inc., 570 Elk St., Buffalo 10, N.Y.
H. & H. Screw Products Mfg. Co., 1883 Mineral Spring Ave., North Providence 11, R.I.
H & H Tube & Mfg. Co., 263 N Forman, Detroit 17, Mich.
H & K Machine Service Co., Inc., 6229 Bartmer Ave., St. Louis, Mo.
H. K. Metal Craft Mfg. Corp., 3775 10th Ave., New York, N.Y.
H-P Products, Inc., 510 W Broad St., Louisville, Ohio
H & R Industries, 344 E Walnut St., Nazareth, Pa.
HPL Mfg. Co. 15210 Miles Ave., Cleveland 28, Ohio
Haber, 864 W North Ave., Chicago 22, Ill.
Hack, J.H. Mfg. Co., 7049 Lyndon Ave., Detroit 21, Mich.
Hadley Bros.-Uhl Co., 514 Calvary Ave., St. Louis 15, Mo.
Haffner Bros. Co., Hopple St. Central Pkwy., Cincinnati 25, Ohio
Hagstoz, T.B. & Son, 709 Sansom, Philadelphia 6, Pa
Haigh Mfg. Co., 225 E Grand River, Brighton, Mich.
Halex Corp., 26302 W 7 Mile Rd., Detroit 40, Mich.
Hall C.P. Co., 414 S Broadway, Akron 8, Ohio
Hall Mfg. Co., 175 Linden St., Hackensack, N.J.
Haller, Inc., 16580 Northville Rd., Northville, Mich.
Hallstead Foundry, Inc., Main St., Hallstead, Pa.
Halogen Insulator & Seal Corp., 9960 Pacific Ave., Franklin Park, Ill.
Hamilton Die Cast, Inc., 240 N B St., Hamilton, Ohio
Hamilton Foundry & Machine Co., 1551 Lincoln Ave., Hamilton, Ohio
Hamilton Watch Co., Precision Metals Div., Lancaster, Pa.
Hampden Brass & Aluminum Co., 262 Liberty St., Springfield, Mass.
Hampton Mfg. Co., 111 Cedar St., New Rochelle, N.Y.
**Handy & Harman (Ad pp 152, 495)**
82 Fulton St., New York 38, N.Y.
Hanford Foundry Co., 119 S Arrowhead Ave., San Bernardino, Calif.
Hauser Products, Inc., 4034 N Kolmar Ave., Chicago 41, Ill.
Hanlon-Gregory Galvanizing Co., 5515 Butler St., Pittsburgh 1, Pa.
Hanovia Chemical Mfg. Co., 1 Central Ave., East Newark, N.J.
Hansell-Elcock, 485 W 23rd Pl., Chicago 16, Ill.
Harbot Die Casting Corp., 52 E Centre St., Nutley, N.J.
Harcast Co., Inc., 620 E Glenolden Ave., Glenolden, Pa.
Hardinge Mfg. Co., 240 Arch St., York, Pa.
Hardman, H. V. Co., Inc., 577 Cortlandt St., Belleville 9, N.J.
Hardy, Charles, Inc., 420 Lexington Ave., New York 17, N.Y.
Hardy Mfg. Corp., W Pearl St., Union City, Ind.
Harnischfeger Corp., 4400 W National Ave., Milwaukee 46, Wis.
Harper, H.M. Co., 8200 Lehigh Ave., Morton Grove, Ill.
**Harrington & King Perforating Co., Inc. (Ad p 440)**
5671½ Fillmore St., Chicago 44, Ill.
Harris, Benjamin & Co., 11th & State Sts., Chicago Hts., Ill.
Harrisburg Steel Co., 110 E 42nd St., New York 17, N.Y.
Harsco Corp., 3200 Guardian Bldg., Detroit 26, Mich.
Ainsworth-Precision Castings Co. Div., 3200 Guardian Bldg., Detroit 26, Mich
Taylor-Wharton Co., High Bridge, N.J.
Harshaw Chemical Co., 1945 E 97th St., Cleveland 6, Ohio
Hartford Electric Steel Corp., 540 Flatbush Ave., Hartford 10, Conn.
Hartglas Co., 1302 Expressway Dr., Toledo 8, Ohio
Hartwell, H.N. & Son, Inc., Park Square Bldg., 31 St. James St., Boston 16, Mass.
Harvey Aluminum, 19200 S Western Ave., Torrance, Calif.
Harvill Corp., 6251 W Century Blvd., Los Angeles 45, Calif.
Harvin & Co., Box 83, Federal St., Kenilworth, N.J.
Harwood Screw Products, Inc., 1620 E Pleasant St., Springfield, Ohio
Haskelite Mfg. Corp., 701 Ann St., NW, Grand Rapids, Mich.
Hassall, John Inc., P.O. Box 2277, Westbury, N.Y.
Hastings & Co., Inc., 2314 Market St., Philadelphia 3, Pa.
Hauger-Beegle Asso., Inc., 900 W 49th Pl., Chicago 9, Ill.
Hauser Products, Inc., 4034 N Kolmar Ave., Chicago 41, Ill.
**Haveg Industries, Inc. (Ad pp 425-426)**
900 Greenbank Rd., Wilmington 8, Del.
Taunton Div., 336 Weir St., Taunton, Mass.
Hawkeye Rubber Mfg. Co., 915 Shaver Road NE, Cedar Rapids, Iowa
Hawkridge Bros. Co., 303 Congress St., Boston 10, Mass.
Hawley Products Co., 333 N 6th St., St. Charles, Ill.
Haws Refractories Co., 407 Main St., Johnstown, Pa.
Hay, James E. Co., Inc., 244 Smith St., Lowell, Mass.
Hayden Mica Co., Inc., Main St., Wilmington, Mass.
Hayden Wire Works, Inc., P.O. Box 146, West Springfield, Mass.
Haydon Corp., 3815 9th Ave., New York 34, N.Y.
Hayes Adhesive Co., Inc., Union Blvd. at Brown Ave., St. Louis 15, Mo.
Hayman, Michael & Co., 856 E Ferry St., Buffalo 11, N.Y.
Hays Mfg. Co., 80 W 12th St., Erie, Pa.
Haywilk Galvanizing Inc., P.O. Box 372, Harvey, La.
Hazledine, E.T. Co., 231 S 1st St., Terre Haute, Ind.
Headford Bros. & Hitchins Foundry Co., 1502 Westfield Ave., Waterloo, Iowa
Headly Mfg. Co., 4376 W Ogden Ave., Chicago 23, Ill.
Heatbath Corp., P.O. Box 78, Springfield 1, Mass.
Heavy Minerals Co., 4000 N Hawthorne St., Chattanooga, Tenn.
Heil Process Equipment Corp., 12901 Elmwood Ave., Cleveland 11, Ohio
Heintz Mfg. Co., Front St. & Olney Ave., Philadelphia 20, Pa.
Held, O.P. Inc., 761 Nepperhan Ave., Yonkers 3, N.Y.
Heli-Coil Corp., Shelter Rock Lane, Danbury, Conn.
Heller, A.B. Screw Products, Inc., 14571 Lesure Ave., Detroit 27, Mich.
Heller Tool Co., Heller Dr., Newcomerstown, Ohio
Helmick Foundry-Machine Co., P.O. Box 71, Fairmont, W. Va.
Hendrick Mfg. Co., 50 Dundaff St., Carbondale, Pa.
Henefelt Precision Products, 1630 Herald Ave., Cincinnati 12, Ohio
Henrite Products Corp., Ironton, Ohio
Heppenstall Co., 4620 Hatfield St., Pittsburgh 1, Pa.
Hercules Fastener Co., 2722 N Clybourn St., Chicago 14, Ill.
Hercules Powder Co., Inc., Delaware Trust Bldg., Wilmington 99, Del.
Heresite & Chemical Co., Manitowoc, Wis.
Herker Screw Products, Inc., 4924 N 125th St., Butler, Wis.
Herman Machine & Tool Co., Tallmadge, Ohio
Hersey Metal Products, Inc., Derby, Conn.
Hettleman, K. & Sons, Inc., 9th & Patapsco Aves., Baltimore 25, Md.
Hewitt, John Foundry Co., 15-29 Sherman Ave., East Newark, N.J.
Hewitt-Robins, Inc., 666 Glenbrook Rd., Stamford, Conn.
Hexcel Products, Inc., 2332 4th St., Berkeley, Calif.
Heyden Newport Chemical Corp., American Plastics Corp. Div., 342 Madison Ave., New York 17, N.Y.
Heypian Mfg. Co., E Michigan Ave., Kenilworth, N.J.
Hibben & Co., 9376 S Ewing Ave., Chicago, Ill.
Hica, Inc., 1431 W 59th St., Shreveport, La.
Hicks Corp., Hyde Park Ave., Boston, Mass.
Higbie Mfg. Co., Avon Tube Div., Klein Rd., Rochester, Mich.
High Vacuum Equipment Corp., 2 Churchill Rd., Hingham, Mass.
Hi-Grade Alloy Corp., 3034 E 95th St., Chicago 17, Ill.
Hilfinger Corp., 1800 Westwood Ave., Toledo 7, Ohio
Hiller Aircraft Corp., Adhesive Engineering Div., 1411 Industrial Rd., San Carlos, Calif.
Hills-McCanna Co., 3025 N Western Ave., Chicago 18, Ill.
Hilo Varnish Corp., Industrial Finishes Div., 376 3rd St., Everett 49, Mass.
Himmel Bros. Co., 1409 Dixwell Ave., Hamden, Conn.
Hi-Shear Rivet Tool Co., 2600 W 247th St., Torrance, Calif.
Hitchiner Mfg. Co., Inc., P.O. Box 350, Milford, N.H.
Hitemp Wires, Inc., 1200 Shames Dr., Westbury, N.Y.
Hobart Bros. Co., 1221 Hobart Rd., Troy, Ohio
Hobbs, Clinton E. Co., 203 Chelsea St., Everett 49, Mass.
Hodges, William & Co., Inc., 1627 N American St., Philadelphia 2, Pa.
Hodgman Rubber Co., Tripp St., Framingham, Mass.
Hodgson Foundry Co., 2012 W 13th St., Chicago 8, Ill.
**Hoeganaes Sponge Iron Corp. (Ad p 462)**
Riverton, N.J.
Hoffman Bronze & Aluminum Casting Co., 1000 Addison Rd., Cleveland 3, Ohio
Hofford Varnish Co., Inc., Broad & 14th Sts., Carlstadt, N.J.
Hohwieler Rubber Co., Inc., 32 W Bridge St., Morrisville, Pa.
Hollingsworth & Vose Co., Washington St., East Walpole, Mass.
Holo-Krome Screw Corp., P.O. Box 98, Elmwood Branch, Hartford 10, Conn.
Holt Products Co., Walnut St., Holt, Mich.
Home Rubber Co., 30 Woolverton Ave., Trenton, N.J.
Homestead Valve Mfg. Co., P.O. Box 348 Coraopolis, Pa.
Hommel, O. Co., P.O. Box 475, Pittsburgh 30, Pa.
Hoofer Mfg. Co., 544 W Lake St., Chicago 6, Ill.
Hooker Chemical Corp., 51 47th St., Niagara Falls, N.Y.
**Durez Plastics Div. (Ad pp 232-233)**
1967 Walck Rd., North Tonawanda, N.Y.
Hoover Co., Die Casting Div., 101 E Maple St., North Canton, Ohio
Horton-Angell Co., 31 Bicknell St., Attleboro, Mass.
**Hoskins Mfg. Co. (Ad p 177)**
4445 Lawton Ave., Detroit 8, Mich.
Houdaille Industries, Inc., Fairmount Tool & Forging, Inc. Sub., 10611 Quincy Ave., Cleveland 6, Ohio
Houghton, E.F. & Co., 303 W Lehigh Ave., Philadelphia 33, Pa.
Houston Blow Pipe & Sheet Metal Works, P.O. Box 1692, Houston 1, Tex.
Howard Foundry Co., 1700 N Kostner Ave., Chicago 29, Ill.
Howe Sound Co., 500 5th Ave., New York, N.Y.
Austenal Co. Div., 224 E 39th St., New York, N.Y.
Peerless Roll Leaf Co. Div., 4511 New York Ave., Union City, N.J.
Hoyt, Charles D. Co., Inc., 1118 Forest Ave., Mishawaka, Ind.
Huck Mfg. Co., 2480 Bellevue Ave., Detroit 7, Mich.
Hudsar, Inc., 567 Wilson Ave., Newark 5, N.J.
Hudson Cush-N-Foam Corp., 309 River Rd., Edgewater, N.J.
Hudson Screw Machine Products Co., 4500 W Augusta Blvd., Chicago 51, Ill.
Hudson Wire Co., Pequot Wire Cloth Co. Div., 35 Hoyt St., Norwalk, Conn.
Hughes Glue Co., 3500 St. Aubin Ave., Detroit 7, Mich.
Hughes Tool Co., 5425 Polk Ave., P.O. Box 2539, Houston 1, Tex.
Hull, R.O. & Co., Inc., 1300 Parsons Ct., Rocky River 16, Ohio

Addresses of Suppliers

**Humble Oil & Refining Co., Enjay Chemical Co. Div. (Ad pp 266-267)**
15 W 51st St., New York 19, N.Y.
Humphrey Castings, Inc., 3944 Riley St., San Diego 10, Calif.
Hungerford Plastics Corp., P.O. Box 376, Morristown, N.J.
Hunt Screw & Mfg. Co., 4117 N Kilpatric Ave., Chicago 41, Ill.
Hunter Engineering Co., 1495 Columbia Ave., Riverside, Calif.
Hunt-Spiller Mfg. Corp., 383 Dorchester Ave., Boston 82, Mass.
Huron Automatic Screw Co., P.O. Box 66, Port Huron, Mich.
Huron Forge & Machine Co., 9041 Alpine Ave., Detroit 4, Mich.
Hyde, A.L. Co., Main St., Grenloch, N.J.
Hydrawlik Co., 131-137 E 1st St., Roselle, N.J.
Hydroforming Co. of America, 7400 W Lawrence Ave., Chicago 31, Ill.
Hydrometals, Inc., Illinois Zinc Co. Div., 2959 W 47th St., Chicago 32, Ill.
Hy-Level Screw Products Co., 2615 Scranton Rd., Cleveland 13, Ohio
Hysol Corp., Olean, N.Y.

## i

I-F Mfg. Co., New Philadelphia, Ohio
Ideal Can Co., 68 Vine St., Everett 49, Mass.
Ideal Metal Products Co., 4842 W Kinzie St., Chicago 44, Ill.
Illinois Forge, Inc., Rock Falls, Ill.
Illinois Iron & Bolt Co., Carpentersville, Ill.
Illinois Precise Casting Co., 903 N Spaulding Ave., Chicago 51, Ill.
Illinois Smelting & Refining Co., 3637 S Albany Ave., Chicago 32, Ill.
Illinois Tool Works, 2511 N Keeler Ave., Chicago, Ill.
Fastex Div., 195 Algonquin Rd., Des Plaines, Ill.
Shakeproof Div., St. Charles Rd., Elgin, Ill.
Imco Container Corp., 75th & Cleveland Sts., Kansas City, Mo.
Impact Extrusions, Inc., 2102 Calumet Rd., Valparaiso, Ind.
Impax, Inc., P.O. Box 5841, Ferguson 21, Mo.
Improved Seamless Wire Co., 775 Eddy St., Providence 5, R.I.
Imsande Screw Products Co., 3517 Cardiff Ave., Cincinnati 9, Ohio
Indar Corp., Indianapolis, Ind.
Independence Stove & Mfg. Co., Hayward & Cottage Sts., Independence, Mo.
Independent Galvanizing Co., 37 Verona Ave., Newark 4, N.J.
Indiana Brass Co., Inc., P.O. Box 113, Frankfort, Ind.
Indiana Forge & Machine Co., 3468 Watling St., East Chicago, Ind.
Indiana General Corp., General Ceramics Div., Keasbey, N.J.
Indiana Steel Products Co., Valparaiso, Ind.
Indiana Steel & Wire Co., Inc., 2200 E Jackson St., Muncie, Ind.
**Indium Corp. of America (Ad p 172)**
1676 Lincoln Ave., Utica 1, N.Y.
Indus Corp., 1815 Madison Ave., Indianapolis 25, Ind.
Industrial Chromium Corp., 109 Lyman St., Holyoke, Mass.
Industrial Equipment Co., 115 Ohio St., Minster, Ohio
Industrial Metal Protectives, Inc., 401 Homestead Ave., Dayton 8, Ohio
Industrial Mica Corp., 223 S Van Brunt St., Englewood, N.J.
Industrial Molded Products Co., Inc., Hwy. 53 at U.S. 14, Palatine, Ill.
Industrial Pipe & Supply Co., 5100 W 16th St., Cicero 50, Ill.
Industrial Plastic Fittings Co., 3891 W 150th St., Cleveland 11, Ohio
Industrial Plastics Corp., 816 W Beardsley Ave., Elkart, Ind.
Industrial Polychemical Service, P.O. Box 423, Gardena, Calif.
Industrial Precision Products, 325 N Hoyne Ave., Chicago 12, Ill.
Industrial Rayon Corp., 500 5th Ave., New York 36, N.Y.
Industrial Stainless Steels, Inc., 255 Bent St., Cambridge 41, Mass.
Industrial Synthetics Corp., 225 North Ave., Garwood, N.J.
Industrial Tectonics, Inc., 3686 Jackson Rd., Ann Arbor, Mich.
Industrial-Ferguson Foundry Corp., Route 22, Union, N.J.
Ingalls Iron Works Co., 620 4th Ave., Birmingham, Ala.
Ingersoll-Rand Co., Phillipsburg, N.J.
Ingram-Richardson, Inc., 1460 Jefferson Rd., Frankfort, Ind.
Ingram-Richardson Mfg. Co., P.O. Box 191, Beaver Falls, Pa.
Inland Mfg. Co., 1108 Jackson St., Omaha 2, Neb.
Inland Steel Co., 30 W Monroe St., Chicago 3, Ill.
Inshield Die & Stamping Co., 1931 Manhattan Blvd., Toledo 8, Ohio
Inspiration Consolidated Copper Co., 25 Broadway, New York 4, N.Y.
Instrument Parts Corp., Snowden Ave. & Water St., Ossining, N.Y.
**Instrument Specialties Co., Inc. (Ad p 463)**
244 Bergen Blvd., Little Falls, N.J.
Insulation Mfrs. Corp., 565 W Washington Blvd., Chicago 6, Ill.
Insulation Products Co., P.O. Box 5679, Pittsburgh 8, Pa.
Interchemical Corp., 67 W 44th St., New York 36, N.Y.
Angier Adhesives Div., 120 Potter St., Cambridge 42, Mass.
Finishes Div., 224 McWhorter St., Newark 5, N.J.
Interlake Mfg. Co., 13595 Helen Ave., Detroit 12, Mich.
International Balsa Corp., 100 Boyd Ave., Jersey City 4, N.J.
International Harvester Co., 180 Michigan Ave., Chicago, Ill.
International Minerals and Metals Corp., 11 Broadway, New York 4, N.Y.
Wisconsin Steel Co. Div., 180 N Michigan Ave., Chicago 1, Ill.
International Nickel Co., Inc., 67 Wall St., New York 5, N.Y.
**Platinum Metals Div. (Ad pp 182-183)**
67 Wall St., New York 5, N.Y.
International Optical Co., Inc., 47 Urban Ave., Westbury, L.I., N.Y.
**International Packings Corp. (Ad p 416)**
Bristol, N.H.
International Packings Corp., Bristol, N.H.
International Paper Co., Long-Bell Div., Longview, Wash.
International Powder Metallurgy Co., Inc., 439 W Main St., Ridgway, Pa.
International Silver Co., Eyelet Specialty Div., P.O. Box 179, Wallingford, Conn.
Interstate Drop Forge Co., 4051 N 27th St., Milwaukee 16, Wis.
Investment Casting Co., 60 Brown Ave., Springfield, N.J.
Iowa Malleable Iron Co., 9th & Kirkwood Sts., Fairfield, Iowa
Ironton Fire Brick Co., Box 536, Ironton, Ohio
Irvington Form & Tank Corp., 100 William St., New York 38, N.Y.
Irwin-Sensenich Corp., P. O. Box 311, Irwin, Pa.
Industrial & Furnace Car Div., P.O. Box 311, Irwin, Pa.
Isaacson Iron Works, 8531 E Marginal Way, Seattle 14, Wash.
Isocyanate Products, Inc., 900 Wilmington Rd., New Castle, Del.
Iten Fibre Co., Box 20, Ashtabula, Ohio

## j

Jackson Auto Radiator, 1515 Altgeld St., Chicago 14, Ill.
Jackson Steel Products, Inc., 32 Rodney St., Brooklyn 11, N.Y.
James Hill Mfg. Co., 20 Gordon Ave., Providence 5, R.I.
Jamestown Finishes, 125 Blackstone Ave., Jamestown, N.Y.
Jamestown Malleable Iron Corp., 3444 Blackstone Ave., Jamestown, N.Y.
Jamison Plastic Corp., 1255 Newbridge Rd., North Bellmore, L.I., N.Y.
Janney Cylinder Co., 7401 State Rd., Philadelphia 36, Pa.
Jaques Co., 67 Batterymarch St., Boston 10, Mass.
Jarco Metal Products, Portland Ave., Westbury, L.I., N.Y.
**Jarl Extrusions, Inc. (Ad p 442)**
Linden Ave., East Rochester, N.Y.
Jasco Aluminum Products Co., New Hyde Park, N.Y.
Jasper Lacquer Co., Inc., Vine St., Jasper, Ind.
Jelliff, C.O. Mfg. Corp., Pequot Rd., Southport, Conn.
Jelrus Precision Casting Corp., 136 W 52 St., New York, N.Y.
Jema-American, Inc., 181 South St., Newark 5, N.J.
Jersey Plastic & Die Casting Co., 151 Shaw Ave., Irvington, N.J.
Jervis Corp., 2900 Wilson Ave., Grandville, Mich.
Jessop Steel Co., 500 Green St., Washington, Pa.
Jet Specialties Co., Inc., 941 N Eastern Ave., Los Angeles, Calif.
Jobbins, William F. Inc., Aurora, Ill.
Johns-Manville Corp., 22 E 40th St., New York 16, N.Y.
Dutch Brand Div., 7800 Woodlawn Ave., Chicago 19, Ill.
Glass Textiles Div., 1810 Madison Ave., Toledo 2, Ohio
Johnson, A. & Co., Inc., 21 West St., New York 6, N.Y.
Johnson Bronze, S Mill St., New Castle 6, Pa.
Johnson Metal Hose, Inc., 10 Sperry St., Waterbury 20, Conn.
Johnson Plastic Corp., Box 312, Chagrin Falls, Ohio
Johnson Rubber Co., 111 Vine St., Middlefield, Ohio
Johnson, S.C. & Son, Inc., Racine, Wis.
Johnson Steel and Wire Co., Inc., 53 Wiser Ave., Worcester, Mass.
Johnston & Funk Titanium Corp., W Kemrow Ave., Wooster, Ohio
Johnstone Foundries, Inc., P.O. Box 549, Grove City, Pa.
Joiens Metal Products Co., 224 Sussex Ave., Newark 4, N.J.
Jones & Laughlin Steel Corp., 3 Gateway Center, Pittsburgh 30, Pa.
**Stainless & Strip Div. (Ad pp 89, 96-97)**
Stainless—P.O. Box 4606, Detroit 34, Mich.; Strip—1939 Teeghly St., Youngstown 1, Ohio
Jordan Co., 51st St. & Merrimac Ave., Chicago 38, Ill.
Jordan Machine Products, Inc., 3611 St. Aubin Ave., Detroit 7, Mich.
Jordan-Rogers Co., 640 N Cypress, Orange, Calif.
Joseff-Hollywood Co., 129 E Providencia, Burbank, Calif.
Joslyn Mfg. & Supply Co., 155 N Wacker Dr., Chicago 6, Ill.
William E. Pratt Foundry Div., 155 N Wacker Dr., Chicago 6, Ill.
Joslyn Pacific Co., 5100 District Blvd., Los Angeles 11, Calif.
Joslyn Stainless Steels, 155 N Wacker Dr., Chicago 6, Ill.
Joymont Plastics, Inc., 710 S State St., Girard, Ohio
Judd Industries, Inc., 3148 W 32 St., Cleveland 9, Ohio
Judsen Rubber Works, Inc., 4107 W Kinzie St., Chicago 24, Ill.

## k

K-D Mfg. Co., 435 Shaffer St., Cleburne, Tex.
K. & L. Plating Co., 535 E Mifflin St., Lancaster, Pa.
K S H Plastics, Inc., Hwy. 30, High Ridge, Mo.
KSM Products, Inc., Yale & Woodland Aves., Merchantville 8, N.J.
**Kaiser Aluminum & Chemical Sales, Inc. (Ad p 419)**
919 Michigan Ave., Chicago 11, Ill.
Kaiser Steel Corp., Kaiser Center, 300 Lakeside Dr., Oakland 12, Calif.
Kamin Die Casting & Mfg. Co. 3315 N Knox, Chicago 41, Ill.
Kanawha Mfg. Co., Charleston, W. Va.
Kansas City Hay Press Co., 801 Weeswether Rd., Kansas City 5, Mo.
Kanthal Corp., Amelia Pl., Stamford, Conn.
Kassel Export Co., Inc., 30 Jay St., Englewood, N.J.
Katelman Foundry & Mfg. Co., 238 S 11th St., Council Bluffs, Iowa
Kaufman Glass Co., 1209-21 French St., Wilmington 99, Del.
Kawecki Chemical Co., 220 E 42nd St., New York 17, N.Y.
Kawneer Co., 1105 N Front St., Niles, Mich.
Kay-Bee Machine Products Co., 2776 S 34 St., Milwaukee 15, Wis.
Kay-Brunner Steel Products, Inc., 999 Meridian Ave., Alhambra, Calif.
Kaye-Tex Mfg. Corp., Kaykor Industries, Inc. Div., Yardville, N.J.
Keasbey & Mattison Co., Butler Ave., Ambler, Pa.
Keen Foundry Co., Inc., E Main & E Jerr Sts., Griffith, Ind.
Kees, F.D. Mfg. Co., 700 Park St., Beatrice, Neb.
Kelite Corp., Bldg. 15, 81 Industrial Rd., Berkeley Heights, N.J.
Keller Products, Inc., 37 Union, Manchester, N.H.
Kelley Mfg. Co., 4800 Clinton Dr., P.O. Box 17, Houston 1, Tex.
Kelly Foundry Co., 1704 Wharton St., Pittsburgh 3, Pa.
Kelsey-Hayes Co., 3600 Military Ave., Detroit, Mich.
Metals Div., New Hartford, N.Y.
Kendall Co., Walpole, Mass.
Andrews-Alderfer Div., 1055 Home Ave., Akron 10, Ohio
Fiber Products Div., Walpole, Mass.
Polyken Sales Div., 309 W Jackson Blvd., Chicago 6, Ill.
Kenmore Machine Products, Inc., 15 Depew Ave., Lyons, N.Y.

***In contacting suppliers, please mention the Materials Selector Issue***

**Kennametal, Inc. (Ad p 306)**
Lloyd Ave., Latrobe, Pa.
Kennatrack Corp., Engineered Nylon Products Div., 2530 By-Pass Rd., Elkhart, Ind.
Kennecott Copper Corp., 161 E 42nd St., New York, N.Y.
Chase Brass & Copper Co. Sub., Waterbury 20, Conn.
Okonite Co. Sub., 220 Passaic St., Passaic, N.J.
**Kennedy Automatic Products, Inc.,** 406 S Linden St., Marshall, Mich.
**Kenosha Automatic Products Co.,** P.O. Box 630, Kenosha, Wis.
Kensico Tube Co., Hubbell & RR Aves., Mt. Kisco, N.Y.
**Kent Castings Corp.,** 200 Garden St., Grand Rapids 7, Mich.
**Kent County Galvanizing Co.,** 15 Earlham Way, Hillsgrove 5, R.I.
**Keolyn Plastics, Inc.,** 2731 N Pulaski Rd., Chicago 39, Ill.
Kerrco, Box 4178, Lincoln 7, Neb.
**Kerr-Lakeside Industries, Inc.,** 21850 St. Clair Ave., Cleveland 17, Ohio
**Kester Solder Co.,** 4201 Wrightwood Ave., Chicago 39, Ill.
**Kewaunee Engineering Corp.,** N Main St., Kewaunee, Wis.
**Keystone Carbon Co.,** 1935 State St., St. Marys, Pa.
**Keystone Drawn Steel Co.,** Main & Bridge Sts., Spring City, Pa.
**Keystone Forging Co.,** Northumberland, Pa.
Keystone Plastics, Inc., 282 Badger Ave., Newark, N.J.
**Keystone Refining Co., Inc.,** Garden St., Philadelphia 37, Pa.
**Keystone Steel & Wire Co.,** Peoria 7, Ill.
Kickhaefer Mfg. Co., 901 S 2nd St., Milwaukee 4, Wis.
**King, Alfred B. Co., Devine St., North Haven, Conn.**
King Fifth Wheel Corp., 2915 N 2nd Ave., Philadelphia 33, Pa.
**King Laboratories, Inc.,** 127 Solar St., Syracuse 3, N.Y.
King-Seeley Corp., 720 Norris St., Ypsilanti, Mich.
Albert Lea Foundry-Queen Products Div., 902-910 E Main St., Albert Lea, Minn.
Almco Queen Products Div., 310 E Main St., Albert Lea, Minn.
Central Specialty Div., 720 Central Ave., Ypsilanti, Mich.
**Kingsport Foundry & Mfg. Corp.,** E Sullivan & Main Sts., Kingsport, Tenn.
**Kinkead Industries, Inc.,** 5860 N Pulaski Rd., Chicago 30, Ill.
Kiowa Corp., Marshalltown, Iowa
**Kirchhof Patent Co., Inc., Dietze Bldg., 60-64 Union St., Newark 5, N.J.**
**Kirk, F.J. Co., Inc.,** 140 Brook St., Clinton, Mass.
**Kirk, Morris P. & Son,** 2700 S Indiana St., Los Angeles 23, Calif.
Kirk & Blum Mfg. Co., 3215 Forrer St., Cincinnati 9, Ohio
Kirkhill Rubber Co., Brea, Calif.
**Kish Industries, Inc.,** 1301 N Turner St., Lansing 6, Mich.
**Kleiner Metal Specialties, Inc., P.O. Box 185, Dunellen, N.J.**
**Klincher Locknut Corp.,** 2153 Hillside Ave., Indianapolis 18, Ind.
**Kling Metal Spinning & Stamping Co.,** 245-247 Centre St., New York 13, N.Y.
**Klinzing, A.F. Co., Inc.,** 921 A 2nd St., Milwaukee 4, Wis.
**Klise Mfg. Co.,** 50 Cottage Grove St., Grand Rapids 2, Mich.
**Knapp Mills, Inc.,** 23-17 Borden Ave., Long Island City 1, N.Y.
Knight, Maurice A., 171 Kelly Ave., Akron 9, Ohio
**Knoedler Chemical Co.,** 651 High St., Lancaster, Pa.
**Knowlton Bros., Inc. (Ad p 320)**
215 Factory, Watertown, N.Y.
**Kobel, W.R. Sheet Metal Products,** 148 W 21st St., Ogden, Utah
**Koch, H. & Sons, P.O. Box 125, Corte Madera, Calif.**
**Koehler Mfg. Co.,** 395 Lincoln St., Marlboro, Mass.
**Koehring Co., Milwaukee, Wis.**
**Kohn Engineering Corp.,** 8830 S Telegraph Rd., Taylor Center, Mich.
**Kopp Glass, Inc. (Ad p 309)**
Swissvale, Pittsburgh 18, Pa.
Koppers Co., Inc., Koppers Bldg., Pittsburgh 19, Pa.
**Plastics Div. (Ad pp 264-265)**
Koppers Bldg., Pittsburgh 19, Pa.
**Korhumel Steel and Aluminum Co.,** 2424 Oakton St., Evanston, Ill.
**Koster-Keunen Mfg. Co., Inc., Bourne Blvd., Sayville, N.Y.**
**Kovar, John R. Mfg. Co., Inc., Bridge Square, Anoka, Minn.**
**Koven, L.O. & Brother, Inc.,** 154 Ogden Ave., Jersey City 7, N.J.
**Kralay Plastic Pipe Co., Inc.,** 4710-20 E Washington Blvd., Los Angeles 22, Calif.
**Kramer, C.P. Co.,** 9230 W Belmont Ave., Franklin Park, Ill.
**Kramer, H. Co., Ajax Metal Div.,** 46 Richmond St., Philadelphia 23, Pa.
**Kramer Bros. Foundry Co.,** 17 Dell St., Dayton 4, Ohio
**Kraus Research Labs, Cockeysville, Md.**
**Kroh Wagner, 2331 N Pulaski Rd., Chicago 39, Ill.**
**Krone, Paul Die Casting Co.,** 1811 N Kostner Ave., Chicago 39, Ill.
**Kropp Forge Co.,** 5301 W Roosevelt Rd., Chicago 50, Ill.
**Krueger Fabricating Co., Inc.,** 257 W Badger Road, Madison 5, Wis.
**Krueger & Hudepohl, Inc.,** 1041 Evans St., Cincinnati 4, Ohio
**Kuhn & Jacob Molding & Tool Co.,** 1200 Southard Ave., Trenton 8, N.J.
**Kurz Kasch, Inc.,** 1421 S Broadway, Dayton 1, Ohio
**Kuss, R.L. & Co., Inc.,** 739 Foulke Ave., Findlay, Ohio
**Kutztown Foundry & Machine Corp.,** Kutztown, Pa.
**Kwikset Powdered Metal Products,** 516 E Santa Ana St., Anaheim, Calif.

## L

**L. & R. Mfg. Co.,** 577 Elm St., Arlington, N.J.
**Laboratory Equipment Corp., Hilltop Rd. & Lakeview Ave., St. Joseph, Mich.**
**Laclede Steel Co.,** 1360 Arcade Bldg., St. Louis 1, Mo.
**Laconia Malleable Iron Co.,** 71 Water St., Laconia, N.H.
**Lacquer & Chemical Corp.,** 214 40th St., Brooklyn 32, N.Y.
**Lacquer Products, Inc.,** 9001 Kinsman Rd., Cleveland 4, Ohio
**Ladish Co.,** 5481 S Packard Ave., Cudahy, Wis.
**La France Precision Casting Co.,** 29th & McKean St., Philadelphia 45, Pa.
**Lake City Malleable Co.,** 5000 Lakeside Ave., Cleveland 14, Ohio
**Lake Erie Foundry Co.,** 143 Fillmore Ave., Buffalo 10, N.Y.
**Lake Mfg. Corp.,** 1070 East St., New Britain, Conn.
**Lakeland Industries, Isle, Minn.**
**Lakeside Bronze, Inc.,** 90 Arthur St., Buffalo 7, N.Y.
**Lakeside Malleable Casting Co.,** 1333 23rd St., Racine, Wis.
**Lakewood Metal Products, Inc.,** 39 Cherry Ave., Waterbury 20, Conn.
**Laminated Plastex Corp.,** 1427 W North St., Springfield, Ohio
**Laminated Shim Co.,** 1600 Union St., Glenbrook, Conn.
**Laminated Veneers Co.,** 102nd St. & 92nd Ave., Richmond Hill, N.Y.
**Lamson Products Co.,** 1128 Poplar Pl., Seattle 44, Wash.
**Lamson & Sessions Co.,** 5000 Tiedeman Rd., Cleveland 9, Ohio
**Lamtex Industries, Inc.,** 66 Brooklyn Ave., Westbury, L.I., N.Y.
**Lancaster Glass Corp.,** 220 W Main St., Lancaster, Ohio
**Lancaster Malleable Castings Co.,** 1170 Lititz Ave., Lancaster, Pa.
**Landau, J. & Co., Inc., Carlstadt, N.J.**
**Lang-Scharmann & Co.,** 206 W 1st St., Marshfield, Wis.
**Langsenkamp, F.H. Co.,** 229 E South St., Indianapolis, Ind.
**Langsenkamp-Wheeler Brass Works, Inc., South & Harmon Sts., Indianapolis, Ind.**
**Lansdale Porcelain Enamel Corp.,** 5th & Iron, Lansdale, Pa.
**Lansing Stamping Co.,** Box 838, 1167 S Pennsylvania Ave., Lansing 4, Mich.
**La Porte Foundry Co.,** 301 Truesdell Ave., La Porte, Ind.
**Larkin Specialty Mfg. Co.,** 915 Linden Ave., South San Francisco, Calif.
**Larson, W.O. Foundry Co.,** 799 Barchard, Grafton, Ohio
**Larson, Charles E. & Sons, Inc.,** 2645-65 N Keeler Ave., Chicago 39, Ill.
**Larson Tool & Stamping Co., Olive St., Attleboro, Mass.**
**La Salle Steel Co., P.O. Box 6800-A,** Chicago 80, Ill.
**Latrobe Die Casting Co., Latrobe, Pa.**
**Latrobe Steel Co. (Ad p 95)**
Latrobe, Pa.
**Lattimer Foundry and Machine Co., Lattimer Mines, Pa.**
**Lattner Bros. Machining Co.,** 650 E Troy, Ferndale 20, Mich.
**Latwaitis, Ernest A.,** 102-09 Remsen Pl., Howard Beach 14, N.Y.
**Lavelle Rubber Co.,** 424 N Wood St., Chicago 22, Ill.
**Lavin, R. & Sons, Inc.,** 3426 S Kedzie Ave., Chicago 23, Ill.
**Lawrence, L. Co., Inc.,** 292 Halsey St., Newark 2, N.J.
**Lawrence Copper & Bronze Co., W New Castle St., Zilenpole, Pa.**
**Lawrence Laboratory,** 1668 Euclid St., Santa Monica, Calif.
**Lawrenceville Screw Co.,** 4920 Harrison St., Pittsburgh 1, Pa.
**Lawson, F.H. Co., Evans & Whateley Sts., Cincinnati 4, Ohio**
**Lawton, C.A. Co., Broadway, DePere, Wis.**
**Laystrom Mfg. Co.,** 3900 W Palmer St., Chicago 47, Ill.
**Lea Mfg. Co.,** 16 Cherry Ave., Waterbury 20, Conn.
**Leach & Garner Co., Industrial Div., Leach & Garner Bldg., Attleboro, Mass.**
**Leader Iron Works, Inc.,** 2108 N Jasper St., Decatur, Ill.
**Leake Engineering Co., P.O. Box 715-MS, Monroe, Mich.**
**Lebanon Steel Foundry,** 1st Ave. & E Lehmen St., Lebanon, Pa.
**LeBaron, E.L. Foundry,** Box 746, Brockton, Mass.
**Lee Bros. Foundry Co., Inc., P.O. Box 231 Anniston, Ala.**
**Lee Rubber & Tire Corp., Hector St., Conshohocken, Pa.**
Republic Rubber Div., 1410 Albert, Youngstown 1, Ohio
**Leed, H.A. Co.,** 1685 Diswell Ave., Hamden, Conn.
**Lehigh, Inc.,** 1500 Lehigh Dr., Easton, Pa.
Lehigh Foundries Div., 1500 Lehigh Dr., Easton 1, Pa.
**Lehigh Structural Steel Co., Allentown, Pa.**
**Leitelt Bros., Inc.,** 7721-31 S Chicago Ave., Chicago 19, Ill.
**Lenape Hydraulic Pressing & Forging Co. (Ad p 462)**
Box 536, West Chester, Pa.
**Lester Castings Inc., Cannon & Aurora Rds., Bedford Heights, Ohio**
**LeTourneau, R. G., Inc.,** 2399 S MacArthur, Longview, Tex.
**Letukas Foundry, Inc., Upland, Ind.**
**Levinson Steel Co.,** S 20th & Wharton St., Pittsburgh 3, Pa.
**Lewco,** 3901 Carew Tower, Cincinnati 2, Ohio
**Lewis, G. B. Co. (Ad p 432)**
4026 Montgomery St., Watertown, Wis.
**Lewis, J.P. Co., Plastic Products Div., Beaver Falls, N.Y.**
**Lewis Bolt & Nut Co.,** 504 Malcolm Ave. SE, Minneapolis 14, Minn.
**Lewis & Saunders, Lakeport, N.H.**
**Lewistown Foundry & Machine Co.,** 16 Elizabeth St., Lewistown, Pa.
**Libbey - Owens - Ford Glass Co., Liberty Mirror Div. (Ad p 358)**
851 3rd Ave., Brackenridge, Pa.
**Liberty Foundry Co.,** 7600 Vulcan St., St. Louis 11, Mo.
**Light Metals Corp.,** 1211 Monroe Ave. NW, Grand Rapids, Mich.
**Light Metals, Inc.,** 1100 E 24th St., Indianapolis 5, Ind.
**Lignum-Vitae Products Corp.,** 98 Boyd Ave., Jersey City 4, N.J.
**Lincoln Electric Co.,** 22801 St. Clair Ave., Cleveland 17, Ohio
**Lincoln Foundry Corp.,** 2525 E 49th St., Los Angeles 58, Calif.
**Lincoln Iron Works,** 255 West St., Rutland, Vt.
**Lincoln Machine Parts Corp.,** 732 E 144th St., New York 54, N.Y.
**Lincoln Mfg. Co., Inc.,** 2617 W Fletcher St., Chicago 18, Ill.
**Lincoln Molded Plastics, Inc., Corwin & Clinton Sts., Circleville, Ohio**
**Lincoln Steel Corp.,** 315 W 9th St., Lincoln 1, Neb.
**Lindell Drop Forge Co.,** 2830 S Logan Blvd., Lansing 3, Mich.
**Linden & Co.,** 80 Baker St., Providence 5, R.I.
**Linderme Tube Co.,** 1500 219th St., Cleveland 17, Ohio
**Link-Belt Co.,** 1700 Prudential Plaza, Chicago 1, Ill.
**Linton Precision Casting Co.,** 917 N Nappanee St., Elkhart, Ind.
**Litemetal Dicast, Inc.,** 1927 Wildwood Ave., Jackson, Mich.
**Lithcote Corp.,** 5000 W Lake St., Melrose Park, Ill.
**Lithium Corp. of America, Inc.,** 400 2nd Ave. S., Minneapolis 1, Minn.
**Litho-Strip Corp., M. M. Young Div.,** 4800 S Kilbourn Ave., Chicago 32, Ill.
**Littite Foundries, Inc.,** 2431 Conners St., Port Huron, Mich.
**Little Falls Alloys, Inc. (Ad p 440)**
189 Caldwell Ave., Paterson, N.J.
**Littleford Bros. Inc.,** 453 E Pearl St., Cincinnati 2, Ohio
**Littlestown Hardware & Foundry Co., Inc., Charles St., Littlestown, Pa.**
**Livingston-Tyler Products,** 501 N 5th St., Hamilton, Ohio
**Lloyd & Scott Brass Foundry, Inc.,** 2206 Tatnall St., Wilmington 99, Del.
**Lock Joint Tube Co., Inc.,** 1400 Riverside Dr., South Bend 24, Ind.
**Locke Machine Co.,** Center St., Andover, Ohio

Lockhart Iron & Steel Co., River Ave., McKees Rocks, Pa.
Lockport Mfg. Co., 1102 Collins St., Joliet, Ill.
Lockport Steel Fabricators, Inc., P.O. Box 67, Lockport, Ill.
Lodge Mfg. Co., RR & 6th, South Pittsburg, Tenn.
Lodi Iron Works, Inc., 820 S Sacramento, Lodi, Calif.
Loeffler, J.M. Machine Co., P.O. Box 195, Penndel, Pa.
Loewenthal Metals Corp., 947 Cullerton St., Chicago 8, Ill.
Lone Star Plastics Co., Inc., 124 Roberts Cutoff, Fort Worth, Tex.
Long Beach Iron Works, 2100 W Anaheim St., Long Beach 13, Calif.
Long Foundry Co., Hoquiam, Wash.
Lorain Automatic Screw Machine Co., Inc., 218 Connecticut, Lorain, Ohio
Lorain Brass Co., 639 Broadway, Lorain, Ohio
Loranger Mfg. Corp., 12-38 Clark St., Warren, Pa.
Lord Mfg. Co., Hughson Chemical Co. Div., Greengarden at 12th, Erie, Pa.
Los Angeles Galvanizing Co., Vernon Branch, P.O. Box 58411, Los Angeles 58, Calif.
Los Angeles Steel Casting Co., 6100 S Boyle Ave., Los Angeles 58, Calif.
Lowe Bros. Co., 424 E 3rd St., Dayton 2, Ohio
Lubenow, Arthur Co., 2015 S Kinnickinnic Ave., Milwaukee 7, Wis.
**Lucas - Milhaupt Engineering Co. (Ad p 498)**
5051 S Lake Dr., Cudahy, Wis.
Ludlow Plastics, 145 Rosemary St., Needham Heights 94, Mass.
Ludlow Valve Mfg. Co., Inc., Hudson River at Adams St., Troy, N.Y.
Lukens Steel Co., Coatesville, Pa.
Lumen Bearing Co., 197 Lathrop St., Buffalo 12, N.Y.
Luminous Resins, Inc., 166 W Washington St., Chicago 2, Ill.
Lundberg Screw Products Co., 2101 W Willow St., Lansing 4, Mich.
Lundquist Tool & Mfg. Co., Inc., 57 Jackson St., Worcester 8, Mass.
Lunn Laminates, Inc., Oakwood & W 11th Sts., Huntington Station, N.Y.
Lurie Engineering Co., 1745 Easton Ave., Bethlehem, Pa.
Lus-Trus Corp., 804 Railroad St., Ypsilanti, Mich.
Lux Clock Mfg. Co., Inc., 95 Johnson St., Waterbury 20, Conn.
Luzerne Rubber Co., Muirhead Ave., Trenton 7, N.J.
Lynchburg Foundry Co., Castings Div., Courtland Bldg., Lynchburg, Va.
Lyndon Machine Products Co., Inc., 18564 Fitzpatrick Ave., Detroit 28, Mich.
Lynn Casting Corp., 3014 Floyd St., Burbank, Calif.

## m

M & S Mfg. Co., 220 Main St., Hudson, Mich.
**Maas & Waldstein Co. (Ad p 353)**
2121 McCarter Hwy., Newark 2, N.J.
Macaulay, H.C. Foundry Co., 811 Carlton St., Berkeley 10, Calif.
MacDermid Inc., 526 Huntingdon Ave., Waterbury 20, Conn.
Machine Products Corp., 125 Hollier Ave., Dayton, Ohio
Machinery Forging Co., 5430 Hamilton Ave., Cleveland 14, Ohio
Machinery Products Corp., 2020 N Major Ave., Chicago 39, Ill.
Machinery Products Co. of Lancaster, 317 E Fulton St., Lancaster 10, Pa.
Mac-It Parts Co., 275 E Liberty St., Lancaster, Pa.
Mack Molding Co., Wayne, N.J.
MacKenzie-Walton Co., 478 Pawtucket Ave., Pawtucket, R.I.
**MacLean-Fogg Lock Nut Co. (Ad p 494)**
5535 N Wolcott St., Chicago 40, Ill.
Maco Industries Inc., 6200 S Ashland Ave., Chicago 36, Ill.
Madin Plastics Inc., 370 North Ave., Cranford, N.J.
Madison Foundry Co., 935 Addison Rd., Cleveland 3, Ohio
Madison Kipp Corp., 201 Waubesa St., Madison 10, Wis.
Magic Chemical Co., 121 Crescent St., Brockton 2, Mass.
Magic Iron Cement Co., 5403 Bower Ave., Cleveland 27, Ohio
Magirl Foundry & Furnace Co., 413 E Oakland Ave., Bloomington, Ill.
Magline, Inc., 1960 Mercer, Pinconning, Mich.
Magna Mfg. Co., Inc., 4th Ave., Haskell, N.J.
Magnesium Co. of America, 5222 Indianapolis Blvd., East Chicago, Ill.
Magnesium Elektron, Inc., 630 5th Ave., New York 20, N.Y.
Magnesium Products of Milwaukee, Inc., 740 N Plankinton Ave., Milwaukee 3, Wis.
Magnetic Core Corp., John & Lawrence Sts., Newburgh, N.Y.
Magnetic Powders, Inc., Fairview Ave., Johnsonburg, Pa.
Magnetic Stamping Co., Fairview Ave., Johnsonburg, Pa.
Magnode Products, Inc., P.O. Box 292, Trenton, Ohio
Magnolia Metal Co., 800 McCarter Hwy., Newark 4, N.J.
Magnuson Products Corp., 50 Court St., Brooklyn 1, N.Y.
Mahon, R.C. Co., 6565 E 8 Mile Rd., Detroit 34, Mich.
Main Screw Machine Products, Inc., 58 Lafayette St., Waterbury, Conn.
Malleable Iron Fittings Co., Branford, Conn.
Mallory, P.R. & Co., Inc., 3033 E Washington St., Indianapolis 6, Ind.
Mallory, P.R. Plastics, Inc., 3670 Milwaukee Ave., Chicago 41, Ill.
Mallory-Schwarzkopf Metals, Inc., 320 Yonkers Ave., Yonkers, N.Y.
Malone Bronze Powder Works, Inc., Malone, N.Y.
Malone Metal Powders, Inc., Rte. 202, Flemington, N.J.
Maloney, F.H. Co., 2301 Texas Ave., P.O. Box 1777, Houston 1, Tex.
Malvern Brick & Tile Co., P.O. Box 415, Malvern, Ark.
Manco Products, Inc., 2401 Schaefer Rd., Melvindale, Mich.
Manganese Steel Forge Co., Richmond St. & Castor Ave., Philadelphia 34, Pa.
Manhattan Adhesives Corp., 425 Greenpoint Ave., Brooklyn 22, N.Y.
Mannesmann-Easton Plastic Products Co., Inc., 900 Line St., Easton, Pa.
Manor Die Cast Corp., P.O. Box 386, Bedford, Ohio
Mansfield Brass & Aluminum Corp., 287 N Diamond St., Mansfield, Ohio
Mansol Ceramics Co., 140 Little St., Belleville 9, N.J.
Mantel Screw Products Co., 3200 W Vliet St., Milwaukee 8, Wis.
Manufacturers Corp., 104 Ausdale Ave., Mansfield, Ohio
Manufacturers & Fabricators, Inc., Filbert St., Elyria, Ohio
Manufacturers Iron Foundry, Inc., 785 Union Ave., Bridgeport, Conn.
Manufacturers Service, Inc., 11440 Brookpark Rd., Cleveland 30, Ohio
Marblette Corp., 37-31 30th St., Long Island City 1, N.Y.
Markal Co., 3052 W Carroll Ave., Chicago 12, Ill.
Marlane Development Co., Inc., 153 E 26th St., New York 10, N.Y.
Marquette Mfg. Co., Inc., 307 E Hennepin Ave., Minneapolis, Minn.
Marquette Metal Products Co., 1145 Galewood Dr., Cleveland 10, Ohio
Marsco Mfg. Co., 2901 S Halsted St., Chicago 8, Ill.
Marshall Car Wheel & Foundry Co., Inc., 605 Greenwood Ave., Marshall, Tex.
Martin Rubber Co., Inc., Long Branch Ave., Long Branch, N.J.
Masco Screw Products Co., 12825 Ford Rd., Dearborn, Mich.
Masland Duraleather Co., Amber & Willard Sts., Philadelphia 34, Pa.
Mason Envelope Co., Inc., 536 Broadway, New York 12, N.Y.
Masonite Corp., 111 W Washington St., Chicago 2, Ill.
Massachusetts Screw Mfg. Co., 9 W 3rd St., South Boston 27, Mass.
Massillon Steel Casting Co., Box 388, Massillon, Ohio
Master Chrome Service, Inc., 5709 Herman Ave., Cleveland 2, Ohio
Matthiessen & Hegeler Zinc Co., 9th & Sterling Sts., La Salle, Ill.
May, Inc., 5803 Alice Rd., Houston 5, Tex.
Maynard Mfg. Co., 22755 Shakespeare Ave., East Detroit, Mich.
Mayon Plastics, 415 17th Ave. N, Hopkins, Minn.
Mayville Metal Products Co., 104 Highland St., Mayville, Wis.
Maywood Chemical Works, 111 W Hunter Ave., Maywood, N.J.
Maze, W.H. Co., 1207 Water St., Peru, Ill.
McCarter Iron Works, Inc., Norristown, Pa.
McCrady Refractories, Inc., P.O. Box 11566, Pittsburgh 38, Pa.
**McDanel Refractory Porcelain Co. (Ad p 308)**
510 9th Ave., Beaver Falls, Pa.
McDougall Butler Co., Inc., 2929 Main St., Buffalo 14, N.Y.
McDowell Mfg. Co., 301 Stanton Ave., Pittsburgh 9, Pa.
McDowell-Wellman Cos., 113 St. Clair Ave. NW, Cleveland 14, Ohio
McGean Chemical Co., 1040 Midland Bldg., Cleveland 15, Ohio
McGee Chemical Co., Inc., 8000 W Chester Pike, Upper Darby, Pa.
McGraw-Edison Co., 5201 W 65th St., Chicago, Ill.
Illinois Edison Porcelain Div., Macomb, Ill.
Line Material Industries Div., N Burson St., East Stroudsburg, Pa.
Mc Gregor-Michigan Corp., 5818 Rivard, Detroit 11, Mich.
McInnes Steel Co., 441 E Main St., Corry, Pa.
McKay Co., 481 McKay Bldg., Pittsburgh, Pa.
McKinney Mfg. Co., 1715 Liverpool St., Pittsburgh 33, Pa.
McLanahan & Stone Corp., 200 Wall St., Hollidaysburg, Pa.
McLouth Steel Corp., 300 S Livernois Ave., Detroit 17, Mich.
McMahon Bros. Machine Works, Inc., 3200 S 61st Court, Cicero 50, Ill.
McNally Pittsburg Mfg. Co., P.O. Drawer D., Pittsburg, Kan.
Meaden Screw Products Co., 3010 S Kilbourn Ave., Chicago 23, Ill.
Meadville Malleable Iron Co., Meadville, Pa.
Mearl Corp., 124 E 40th St., New York 16, N.Y.
Measuregraph Co., 4245 Forest Park Blvd., St. Louis 8, Mo.
Mechanical Art Works, Inc., 96-98 Monroe St., Newark 5, N.J.
Mechanical Felt & Textiles Co., 50 W 18th St., Weehawken, N.J.
Mechanical Leathers, Inc., 2204 E Butler St., Philadelphia 37, Pa.
Mechanical Plating Co., 1500-26 W Hubbard St., Chicago 22, Ill.
Mechanical Rubber Products Co., Warwick, N.Y.
Medico Industries, Inc., 11-13 Tompkins St., Pittston, Pa.
**Mechanite Metal Corp. (Ad p 461)**
714 North Ave., New Rochelle, N.Y.
Meeker Foundry Co., Newark 4, N.J.
Meier Screw Products & Mfg. Co., 19361 Sherwood Ave., Detroit, Mich.
Meico Wire Products, 4407 San Fernando Rd., Glendale 4, Calif.
Melling Forging Co., 1709 Thompson St., Lansing 3, Mich.
Melray Mfg. Co., 9511 W. River St., Schiller Park, Ill.
Mercast Mfg. Corp., 2620 1st St., La Verne, Calif.
Merit Screw Machine Products Co., Inc., 4847 W Lake St., Chicago 44, Ill.
Merit Specialties Co., Inc., 203-205 E Davis St., St. Louis 11, Mo.
Merix Chemical Co., 2234 E 75th St., Chicago 49, Ill.
Merrimac Brass, 22 High St., Merrimac, Mass.
Merriman Bros., Inc., 185 Amory St., Boston 30, Mass.
Merz Machine & Tool Works, 920 N Main St., Crown Point, Ind.
Mesa Plastics Co., 12270 Nebraska Ave., Los Angeles 25, Calif.
Metal Carbides Corp., 107 E Indianola Ave., Youngstown 5, Ohio
Metal Coating Corp., 1215 W 37th St., Chicago 9, Ill.
Metal Finishers, Inc., 78 S Franklintown Rd., Baltimore 23, Md.
Metal Goods Corp., 8800 Page Blvd., St. Louis 14, Mo.
Metal Hydrides, Inc., 12 Congress St., Beverly, Mass.
Metal Mold Magnesium Corp., 95 Hamilton St., Cedarburg, Wis.
Metal Parts & Stamping Co., 1120 Eastern Ave., Cincinnati, Ohio
Metal Powder Products, Inc., P.O. Box 189 M, Logan, Ohio
Metal Textile Corp., 647 E 1st Ave., Roselle, N.J.
Metal Trims, Inc., Livingston Rd., Jackson, Miss.
**Metal & Thermit Corp. (Ad p 357)**
Rahway, N.J.
Metal-Cladding, Inc., P.O. Box 544, North Tonawanda, N.Y.
Metallized Carbon Co., 19 S Water St., Ossining, N.Y.
Metallizing Co. of America, 3520 W Carroll Ave., Chicago 24, Ill.
Metallizing Co. of Los Angeles, Inc., 1233 S Boyle Ave., Los Angeles 23, Calif.
**Metallizing Engineering Co., Inc. (Ad pp 351, 360)**
Prospect Ave., Westbury, N.Y.
Metallurgical Products Co., 35th & Moore Sts., Philadelphia, Pa.
Metallo Gasket Co., 21 Bethany St., New Brunswick, N.J.
Metalplate Co., Inc., 757 North 44th St., Birmingham 6, Ala.
**Metals Disintegrating Co. (Ad p 456)**
P.O. Box 290, Elizabeth, N.J.
Metalweld, Inc., Protective Coating Div., Scotts Lane & Abbottsford Ave., Philadelphia, Pa.
Metaplast Process, Inc., 34-51 56th St., Woodside, N.Y.

***In contacting suppliers, please mention the Materials Selector Issue***

Met-L-Wood Corp., 6755 W 65th St., Chicago 38, Ill.

**Metropolitan Iron Foundry, 890 Metropolitan Ave., Brooklyn 11, N.Y.**

Metz Refining Co., 369 Mulberry St., Newark 2, N.J.

**Meyer, J. & Sons, Inc., 4321 N 4th St., Philadelphia 40, Pa.**

Mica Corp., 4031 Elenda St., Culver City, Calif.

**Mica Fabricating Co., 53 Central Ave., Rochelle Park, N.J.**

**Micacraft Products, Inc., 701 McCarter Hwy., Newark, N.J.**

**Micheiman Chemicals, Inc., 6316 Wiehee Rd., Cincinnati, Ohio**

Michigan Chemical Corp., Rare Earths & Thorium Div., St. Louis, Mich.

**Michigan Chrome & Chemical Co., 8615 Grinnell Ave., Detroit 13, Mich.**

Michigan Leather Products Co., 6307 E Lafayette Ave., Detroit 7, Mich.

Michigan Pipe Co., Saran Lined Pipe Co. Div., 2415 Burdette Ave., Ferndale 20, Mich.

**Michigan Plastic Products, Inc., Robbins Rd., Grand Haven, Mich.**

Michigan Seamless Tube Co., South Lyon, Mich.

Michigan Wire Cloth Co., 2100 Howard St., Detroit 16, Mich.

Mico Corp., 4031 Elenda, Culver City, Calif.

Micro Metallic Corp., 30 Sea Cliff Ave., Glen Cove, N.Y.

Micro Products Corp., 4116-18 Olive St., St. Louis 8, Mo.

Micro-Metals Co., 52 E Montecito Ave., Sierra Madre, Calif.

Midland Adhesive & Chemical Corp., 2600 Goodrich, Ferndale 20, Mich.

Midland Industrial Finishes Co., E Water St., Waukegan, Ill.

Midland Pipe & Supply Co., 2829 S 61st St., Cicero 50, Ill.

Midland Screw Corp., 3638 S Kedzie Ave., Chicago 32, Ill.

Mid-States Rubber Products, Inc., 1230 Race St., Princeton, Ind.

Mid-States Steel & Wire Co., Crawfordsville, Ind.

Midvale-Heppenstall Co., Nicetown, Philadelphia 40, Pa.

Midwest Molding & Mfg. Co., Gurnee, Ill.

Midwest Piping Co., Inc., 2nd & Barry Sts., St. Louis 4, Mich.

Midwest Plastic Products Co., 1801 Chicago Rd., Chicago Heights, Ill.

Midwest Precision Castings Co., 1070-903 Quincy Ave., Cleveland 6, Ohio

Midwest Rubber Co., 14273 E 9 Mile Rd., East Detroit, Mich.

**Mid-West Screw Products Co., 3662 Park Ave., St. Louis 10, Mo.**

**Midwest Screw Products, Inc., 1641 Colt Ave., East Cleveland 12, Ohio**

**Midwest Sintered Products Corp., 13606 S Halsted St., Chicago 27, Ill.**

**Midwest Stamping & Mfg. Co., Krauss Rd., Bowling Green, Ohio**

**Mid-West Wire Products Co., Inc., 2555 Fenkell Ave., Detroit 38, Mich.**

**Midwestern Foundries, Inc., 614 E Quincy, Garrett, Ind.**

**Milford Automatics, Inc., 1553 Boston Post Rd., Milford 15, Conn.**

**Milford Rivet & Machine Co., Milford, Conn.**

**Milled Screw Product Co., 2016-2026 W Lake St., Chicago 12, Ill.**

Miller Co., 99 Center St., Meriden, Conn.

Miller-Stephenson Chemical Co., Inc., 18 Marshall St., South Norwalk, Conn.

**Millers' Brass Fitting Co., Inc., 30 Main St., Brooklyn 1, N.Y.**

**Milwaukee Aluminum & Brass Foundry, 643 S 2nd St., Milwaukee 4, Wis.**

**Milwaukee Die Casting Co., 4134 N Holton St., Milwaukee 12, Wis.**

**Milwaukee Forge & Machine Co., 1532 E Oklahoma Ave., Milwaukee 7, Wis.**

**Milwaukee Machine Products Co., 3889 N 1st St., Milwaukee 12, Wis.**

**Milwaukee Malleable & Grey Iron Works, 2773 S 29th St., Milwaukee 46, Wis.**

**Milwaukee Stamping Co., 800-S 72nd St., Milwaukee 14, Wis.**

**Milwaukee Valve Co., 2375 S. Burrell St., Milwaukee 7, Wis.**

**Minimax Co., 5905 N Clark St., Chicago 26, Ill.**

**Minneapolis Electric Steel Castings Co., 3800 NE 5th St., Minneapolis 21, Minn.**

Minneapolis Plastic Molders, Inc., 5742 Nicollet Ave. S, Minneapolis 19, Minn.

**Minnesota Mining & Mfg. Co., 900 Bush Ave., St. Paul 6, Minn.**

**Adhesives, Coatings & Sealers Div., 411 Piquette Ave., Detroit 2, Mich.**

Chemical Div., 900 Bush Ave., St. Paul 16, Minn.

**Irvington Varnish & Insulator Div., Irvington N.J.**

**Mica Insulator Div., 797 Broadway, Schenectady 1, N.Y.**

**Reinforced Plastics Div. (Ad pp 258-259)**

900 Bush Ave., St. Paul 6, Minn.

Zenith Plastics Co. Div., Box 91, Gardena, Calif.

Minnesota Paints, Inc., 1101 S 3rd St., Minneapolis 15, Minn.

Minnesota Plastics Corp., 45 E Maryland Ave., St. Paul 3, Minn.

Minnesota Rubber Co., 3630 Wooddale Ave., Minneapolis 16, Minn.

Miracle Adhesives Corp., 250 Pettit Ave., Bellmore, L.I., N.Y.

Mirro Aluminum Co., 1512 Washington St., Manitowoc, Wis.

Misco Precision Casting Co., 116 W Gibbs, Whitehall, Mich.

Misner Corp., 940 N 23rd St., Omaha 2, Neb.

Missouri Boiler & Sheet Works, 23rd & Papin Sts., St. Louis 3, Mo.

Missouri Diecasting Co., 1411 N 17th St., St. Louis 6, Mo.

Missouri Rolling Mill Corp., 4800 Manchester Ave., St. Louis 10, Miss.

Missouri Steel Castings Co., 905 E 3rd St., Joplin, Mo.

Mitchell & Scott Machine Co., Inc., 1841 Ludlow Ave., Indianapolis 7, Ind.

Mitchell-Bradford Chemical Co., Wampus Lane, Milford, Conn.

Mobay Chemical Co., Penn Lincoln Parkway W, Pittsburgh 5, Pa.

Mobile Paint Mfg. Co., Inc., P.O. Box 1686, Mobile, Ala.

Moccasin Bushing Co., 2000 Chestnut St., Chattanooga 8, Tenn.

Moczik Tool & Die Works, 9511 Grinnell, Detroit 13, Mich.

Model Brass Co., Inc., 232-40 E Decatur St., Decatur, Ill.

Modern Brass Foundry & Mfg. Co., 157 Thurman St., Columbus 6, Ohio

Modern Plastics Corp., 489 N Shore Dr., Benton Harbor, Mich.

Modern Plating Corp., 121-129 S Hancock Ave., Freeport, Ill.

Modern Screw Products Co., 2307 N 9th St., St. Louis 6, Mo.

Modiglass Fibers, Inc., P.O. Box 86, Bremen, Ohio

Mohawk Foundries, Inc., 55 1st Ave., Berea, Ohio

**Moldcast Products, Inc., Pacific St., Newark 5, N.J.**

Molded Fiber Glass Co., 4401 Benefit Ave., Ashtabula, Ohio

**Moldex, 747 5th Ave., New York 22, N.Y.**

Moline Iron Works, 130 2nd, Moline, Ill.

**Moline Malleable Iron Co., St. Charles 5, Ill.**

Molybdenum Corp. of America, Washington, Pa.

Monarch Aluminum Mfg. Co., 9205 Detroit Ave., Cleveland 2, Ohio

**Monarch Products Co., Leake Stamping Div., 1259 E 1st St., Monroe, Mich.**

**Monarch Tool & Mfg. Co., 105 E 4th St., Covington, Ky.**

Mono-Sol Corp., 407 County Line Rd., Gary, Ind.

**Monroe Steel Castings Co., 917 W Front, Monroe, Mich.**

**Monsanto Chemical Co., 600 Monsanto Ave., Springfield, Mass.**

Inorganic Chemicals Div., 800 N Lindbergh Blvd., St. Louis 66, Mo.

Organic Chemicals Div., Lindbergh & Olive St. Rd., St. Louis 24, Mo.

Plastics Div., Springfield 2, Mass.

Montague Machine Co., 15th St., Turners Falls, Mass.

Monteath, J.H. Co., 2504 Park Ave., New York, N.Y.

Moody Machine Products Co., Inc., 42 Dudley St., Providence 5, R.I.

Moore, George W., Inc., 100 Beaver St., Waltham 54, Mass.

Moore, Samuel & Co., Mantua, Ohio

Moore Dry Dock Co., Adeline St., Oakland 23, Calif.

Morganite, Inc., 3302 48th Ave., Long Island City 1, N.Y.

Morningstar-Paisley, Inc., 630 W 51st St., New York 19, N.Y.

Morrell, George Corp., P.O. Box 155, Muskegon Heights, Mich.

Morrison Steel Products, Inc., 601 Amherst St., Buffalo 7, N.Y.

Morrisville Foundry Co., Inc., Morrisville, Vt.

Morse, Fred W. Co., 309 S Main St., Providence 3, R.I.

Morton Mfg. Co., 5125 W Lake St., Chicago 44, Ill.

Mosinee Paper Mills Co., Mosinee, Wis.

**Molt Metallurgical Corp. (Ad p 466)**

272 Huyshope Ave., Hartford, Conn.

Mount Vernon Die Casting Corp., Smithfield Ave., Stamford, Conn.

Mount Vernon Furnace & Mfg. Co., Mount Vernon, Ill.

**Moxness Products, Inc. (Ad p 460)**

1914 Indiana St., Racine, Wis.

Muehlstein, H. & Co., Inc., 60 E 42nd St., New York 17, N.Y.

**Mueller Brass Co. (Ad p 455)**

1925 Lapeer Ave., Port Huron, Mich.

Mueller Machine Products, Inc., 3807 S Packard Ave., Milwaukee 7, Wis.

Multiple Extrusions, Inc., 1150-1200 E 8th St., Winona, Minn.

Muncie Malleable Foundry Co., E Highland Ave., Muncie, Ind.

Muncie Metal Spinning, Inc., 1012 E 20th St., Muncie, Ind.

Mundt, Charles & Sons, 53 Fairmount Ave., Jersey City 4, N.J.

Murray, A.B. Co., Inc., P.O. Box 476, Elizabeth, N.J.

Murray Tube Works, Inc., P.O. Box 476, Elizabeth, N.J.

Muskegon Piston Ring Co., Sparta Foundry Div., Sparta, Mich.

**Mycalex Corp. of America (Ad pp 323-324)**

125 Clifton Blvd., Clifton, N.J.

Synthetic Mica Co. Div., 20 Passaic Ave., Caldwell, N.J.

Mystik Adhesive Products, Inc., 2635 N Kildare Ave., Chicago 39, Ill.

## n

Naige Co., Inc., P.O. Box 365, Rochester 2, N.Y.

**Napoleon Products Co., 410 Fillmore St., Napoleon, Ohio**

Narmco Industries, Inc., Narmco Materials Div., 600 Victoria St., Costa Mesa, Calif.

Narragansett Boiler Works, Inc., 614 S Main St., Providence 3, R.I.

**National Acme Co., 170 E 131st St., Cleveland 8, Ohio**

**National Aluminum Co., 1133 Alum Creek Dr., Columbus 9, Ohio**

**National Aluminum Co., Inc., 1912 Edgewood Ave., Racine, Wis.**

**National Aluminum & Brass Foundry, Inc., P.O. Box 179, Independence, Mo.**

**National Aluminum Mfg. Co., 720 Park Ave., Peoria, Ill.**

National Beryllia Corp., 4501 Dell Ave., North Bergen, N.J.

**National Brass Works, Inc., 2140 E 25th St., Los Angeles 58, Calif.**

**National Casein Co., 601 W 80th St., Chicago 20, Ill.**

**National Copper & Smelting Co., 1862 E 123rd St., Cleveland 6, Ohio**

National Die Casting Co., 3635 W Touhy Ave., Chicago 45, Ill.

**National Distillers & Chemical Corp., U. S. Industrial Chemicals Co. Div., 99 Park Ave., New York 16, N.Y.**

**National Felt Co., 76 Summer St., Boston 10, Mass.**

**National Forge & Ordnance Co., Irvine, Warren County, Pa.**

**National Galvanizing Co., Neville Island, Pittsburgh 25, Pa.**

**National Gasket & Washer Mfg. Co., Inc., 124 E 25th St., New York 10, N.Y.**

**National Grey Iron Foundry, Belvidere, Ill.**

National Impacted Metal Corp., Box 726, New Albany, Miss.

**National Lead Co., 111 Broadway, New York 6, N.Y.**

Doehler-Jarvis Div., 1945 Smead Ave., Toledo, Ohio

Goldsmith Bros. Div., 111 N Wabash Ave., Chicago 2, Ill.

Titanium Alloy Mfg. Div., 2950 Hyde Park Blvd., Niagara Falls, N.Y.

**Zirconium Metals Corp of America Sub. (Ad p 430)**

111 Broadway, New York 6, N.Y.

National Lead Construction Co., Inc., P.O. Box 133, Haddonfield, N.J.

National Lock Co., 1902 7th St., Rockford, Ill.

Fastener Div., 4500 Kishwaukee, Rockford, Ill.

**National Lock Washer Co., 40 Hermon St., Newark 5, N.J.**

**National Machine Products Co., 44225 Utica Rd., Utica, Mich.**

**National Malleable & Steel Castings Co., 10600 Quincy Ave., Cleveland 6, Ohio**

**National Mfg. Corp., 153 Fillmore Ave., Tonawanda, N.Y.**

**National Metal Products Co., 2 Gateway Center, Pittsburgh 22, Pa.**

**National Molded Products, Inc., 40 St. Marys St., St. Marys, Pa.**

**National Moldite Co., 250 South St., Newark 5, N.J.**

**National Paint & Manganese Co., Lynchburg, Va.**

**National Research Corp., 70 Memorial Dr., Cambridge 42, Mass.**

**National Screw & Mfg. Co., 2440 E 75th St., Cleveland 4, Ohio**

National Starch & Chemical Corp., Structural Products Div., 750 3rd Ave., New York 17, N.Y.

**National Steel Corp., Grant Bldg., Pittsburgh, Pa.**

Enamelstrip Corp. Sub., 20th & Hamilton Sts., Allentown, Pa.

Great Lakes Steel Corp., Detroit 29, Mich.
Weirton Steel Co., Weirton, W. Va.
National Steel & Shipbuilding Corp., Harbor Dr. & 28th St., San Diego 12, Calif.
National Supply Co., 2 Gateway Center, Pittsburgh 22, Pa.
National Tank Co., Wells & Sandspring Rd., Tulsa, Okla.
**National Vulcanized Fibre Co. (Ad p 249)**
Box 311, Wilmington 99, Del.
**National-Standard Co. (Ad p 421)**
601 N 8th St., Niles, Mich.
Athenia Steel Div., Clifton Ave., Clifton, N.J.
Reynolds Wire Div., 809 E 2nd St., Dixon, Ill.
Worcester Wire Works Div., 70 James St., Worcester, Mass.
National-U. S. Radiator Corp., Plastic Metals Div., 4459 Bridge St., Johnstown, Pa.
Neenah Foundry Co., Wisconsin Ave., Neenah, Wis.
Neilson Chemical Co., 2300 Gainsboro, Detroit (Ferndale) 20, Mich.
Nesbitt Industries, Inc., 1823 Milwaukee Ave., Chicago 47, Ill.
Nesor Alloy Products Co., 282 Halsey St., Newark, N.J.
New Britain Machine Co., South St., New Britain, Conn.
New England Brass Co., 16 Park St., Taunton, Mass.
New England Die Casting Co., 445 Front Ave., West Haven, Conn.
New England Electrical Works, Inc., 365 Main St., Lisbon, N.H.
**New England Laminates Co. (Ad p 281)**
P.O. Box 43, 481 Canal St., Stamford, Conn.
New England Smelting Works, Inc., 502 Union St., West Springfield, Mass.
New Haven Copper Co., Main St., Seymour, Conn.
New Haven Screw Machine Products, Inc., 561 Boston Post Rd., Milford, Conn.
New Jersey Aluminum Extrusion Co., Inc., Jersey Ave., New Brunswick, N.J.
New Jersey Metals Co., 712 Rockefeller St., Elizabeth 2, N.J.
**New Jersey Zinc Co. (Ad pp 452-453)**
160 Front St., New York 38, N.Y.
New Products Corp., 448 North Shore Ave., Benton Harbor, Mich.
New York Air Brake Co., Kinney Mfg. Div., 3529 Washington St., Boston 30, Mass.
New York Iron Roofing & Corrugating Co., Inc., 94 1st St., Jersey City 2, N. J.
Newage Industries, Inc., 222 York Rd., Jenkintown 3, Pa.
**Newark Wire Cloth Co. (Ad p 454)**
351 Verona Ave., Newark 4, N.J.
Newman Bros., Inc., 670 W 4th St., Cincinnati, Ohio
Newman-Crosby Steel Co., Deane St., Pawtucket, R.I.
Newport Steel Corp., 9th & Thomas Sts., Newport, Ky.
Newth Rubber Co., County Rd., Barrington, R.I.
Newton-New Haven Co., 680 3rd Ave., West Haven, Conn.
Newtown Mfg. Co., Newtown, Conn.
Ney, J.M. Co., Industrial Div., P.O. Box 990, Hartford 1, Conn.
Nichols, L.O. & Son Mfg. Co., 1525 Locust St., Kansas City 8, Mo.
Nichols Wire & Aluminum Co., 1725 Rockingham Rd., Davenport, Iowa
Nicolet Industries, Inc., 70 Pine St., New York 5, N.Y.
Nicoud Mfg. Co., 3220 Grand Ave., Chicago 51, Ill.
Nigg Engineering Corp., 545 N 2nd Ave., Covina, Calif.
Nikoh Tube Co., 5000 S Whipple St., Chicago 32, Ill.
Nikolas, G.J. & Co., Inc., 2890 Washington Blvd., Bellwood, Ill.
Nilsen Mfg. Co., Electronicast Div., 21 N Church St., Addison, Ill.
Nippert Electric Products Co., 1759 W Mound St., Columbus 23, Ohio
Nixon Nitration Works, Nixon, N.J.
Noble & Wood Machine Co., 1st St., Hoosick Falls, N.Y.
Noera Mfg. Co., 236 Grand St., Waterbury 20, Conn.
Noland Tank & Galvanizing Co., 705 Merritt Ave., Nashville 4, Tenn.
Nolte Screw Machine Products Co., 1534-36 Freeman Ave., Cincinnati 14, Ohio
Nonne Industrial Fabrics Div., Kenwood Mills, Rensselaer, N.Y.
Nopco Chemical Co., 1st & Essex Sts., Harrison, N.J.
Norcross, C.S. & Sons Co., Dean & Davis Sts., Bushnell, Ill.
Norgren-Stemac, Inc., 5400 S Delaware, Littleton, Ohio
Norrich Plastics Corp., 107-109 W 18th St., New York, N.Y.
Screw Machine Products Div., 107-109 W 18th St., New York, N.Y.
North American Asbestos Corp., Board of Trade Bldg., Chicago 4, Ill.
North American Aviation, Inc., Navan Products, Inc. Sub., 900 N Sepulveda, El Segundo, Calif.
North American Cement Co., Designers Metals Div., 650 Hoffman St., Hammond, Ind.
North American Phillips Co., Inc., Elmet Div., Lewiston, Me.
North American Refractories Co., 1012 National City-E 6th Bldg., Cleveland 14, Ohio
North & Judd Mfg. Co., Wilcox-Crittenden Div., Middletown, Conn.
North Wales Foundry Co., Inc., Wessahickon Ave., North Wales, Pa.
Northern Malleable Iron Co., 867 Forest St., St. Paul 6, Minn.
Northern Plastics Corp., 2nd & Market St., La Crosse, Wis.
Northwest Automatic Products Corp., 1770 Linden Ave., Minneapolis 3, Minn.
Northwest Chemical Co., 9310 Roselawn Ave., Detroit 4, Mich.
Northwest Plastics Industries, Inc., 2040 15th Ave. W, Seattle 99, Wash.
Northwestern Steel & Wire Co., Ave. B & Wallace St., Sterling, Ill.
**Norton Co. (Ad p 348)**
New Bond St., Worcester 6, Mass.
Norwalk Powdered Metals, Inc., P.O. Box 271, Muller Park, Norwalk, Conn.
Norwich Leather Co., 685 N Main St., Norwich, Conn.
Nosco Plastics Co., 17th & Gasgo, Erie, Pa.
Nuclear Corp. of America, Research Chemicals Div., Box 431, Burbank, Calif.
Nuclear Metals, Inc., Concord, Mass.
Nukem Products Corp., 111 Colgate Ave., Buffalo 20, N.Y.
Nu-Ply Corp., Bemidji, Minn.
Nutmeg Crucible Steel Co., Elm & Harbor Sts., Branford, Conn.
Nutmeg Screw Machine Products Co., Wolcott Rd., Wolcott, Conn.
Nutt-Shel Co., Inc., 2701 S Harbor Blvd., Santa Ana, Calif.
Nylok Corp., 611 Industrial Ave., Paramus, N.J.
Nylok-Detroit, 1100 N Woodward, Birmingham, Mich.
Nylon Molded Products Corp., Garrettsville, Ohio
Nylonicraft, Inc., 218 McKinley Hwy. W, Mishawaka, Ind.

## O

Oak Hill Foundry & Machine Works, Box 278, Oak Hill, Ohio
Oakes Bronze & Aluminum Co., Bronze Rd., Warren, Ohio
**Oakite Products, Inc. (Ad p 361)**
19 Rector St., New York 6, N.Y.
Oakland Foundry & Machine Co., 607-621 Woodward Ave., Rochester, Mich.
Oatey, L.R. Co., 10230 Berea Rd., Cleveland 2, Ohio
Octagon Process, Inc., 63 Bank St., Staten Island 1, N.Y.
Ohio Adhesives Corp., P.O. Box 466, New Philadelphia, Ohio
**Ohio Carbon Co. (Ad p 322)**
12508 Berea Rd., Cleveland 11, Ohio
Ohio Forge & Machine Corp., 3010 Woodhill Rd., Cleveland 4, Ohio
Ohio Metal Products Co., 35 N Bates St., Dayton 2, Ohio
Ohio Nut & Bolt Co., 33 1st Ave., Berea, Ohio
Ohio Nut & Washer Co., Box 66, Mingo Junction, Ohio
Ohio Precision Castings, Inc., 109 Webb St., Dayton 3, Ohio
Ohio Rubber Co., 301 Ben Hur Ave., Willoughby, Ohio
Ohio Screw Products, Inc., 818 West St., Elyria, Ohio
Ohio Steel Foundry Co., 1075 James St., Springfield, Ohio
Oil City Iron Works, P.O. Drawer 615, Corsicana, Tex.
Olderman Mfg. Corp., P.O. Box 917, Bridgeport, Conn.
Olds Alloys Co., 4481 Mason St., South Gate, Calif.
Olean Electro Plating Co., 890 N 4th St., Olean, N.Y.
Olin Mathieson Chemical Corp., 460 Park Ave., New York 22, N.Y.
**Metals Div. (Ad p 155)**
400 Park Ave., New York 22, N.Y.
Packaging Div., 655 Madison Ave., New York 21, N.Y.
Olson Mfg. Co., 100 Prescott St., Worcester 5, Mass.
Olympic Steel Works, 151 Horton St., Seattle 4, Wash.
Omaha Steel Works, 609 S 48th St., Omaha 6, Neb.
Omni Products Corp., 460 4th Ave., New York 16, N.Y.
Omni-Metal Castings, Inc., 135 11th St., Brooklyn 15, N.Y.
Optical Coating Laboratory, Inc., 2789 Giffen Ave., Santa Rosa, Calif.
Oregon Brass Works, 1127 SE 10th Ave., Portland 14, Ore.
Oregon Metallurgical Corp., P.O. Box 484, Albany, Ore.
Ormand Mfg. Co., Inc., 3325 Hudson Ave., Union City, N.J.
Ostby & Barton Co., Flightex Fabrics, Inc., 148 W River St., Providence 4, R.I.
O'Sullivan Rubber Corp., Valley Pike St., Winchester, Va.
Plastics Div., P.O. Box 603, Winchester, Pa.
Ottawa Steel Products, Inc., 745 Woodlawn Ave., Grand Haven, Mich.
Overmyer Mould Co., Inc., N Main St., Winchester, Ind.
Owen Mfg., Inc., S State Street Rd., Litchfield, Ill.
Owen Pattern Foundry & Mfg. Co., Inc., 710 W 22nd St., Norfolk 10, Va.
Owens-Corning Fiberglas Corp., 608 Madison Ave., Toledo 3, Ohio
Owens-Illinois Glass Co., Toledo, Ohio
Closure & Plastics Div., P.O. Box 1035, Toledo 1, Ohio
Kimble Glass Co. Sub., P.O. Box 1035, Telodo 1, Ohio
Paper Products Div., P.O. Box 1035, Toledo 1, Ohio

## P

Pabst Engineering Equipment Co., Inc., 676 Pennsylvania Ave., Elizabeth 3, N.J.
Pacific Brass Foundry of San Francisco, 251 2nd St., San Francisco 5, Calif.
Pacific Coast Foil Co., 500 Sansome St., San Francisco, Calif.
Pacific Foundry Co., Ltd., 3100 19th St., San Francisco, Calif.
Pacific Molded Products Corp., 905 E 59th St., Los Angeles 1, Calif.
Pacific Screw Products Co., 930 Linden Ave., South San Francisco, Calif.
Pacific Sintered Metals Co., 7728 El Manor Ave., Los Angeles, Calif.
Pacific States Steel Corp., Niles, Calif.
Pacific Tube Co., 5710 Smithway St., Los Angeles 22, Calif.
Pasco Rubber Co., Inc., 225 W Lake St., Ravenna, Ohio
Page Belting Co., Concord, N.H.
Palmyra Foundry Co., Inc., Palmyra, N.J.
Palnut Co., Glen Rd., Mountainside, N.J.
Pan-American Metal Products Co., Inc., 401 NW 71st St., Miami 38, Fla.
Panther Chemical Corp., P.O. Box 711, Ft. Worth, Texas
Paragon Die Casting Co., 5851 W Dickens Ave., Chicago 39, Ill.
Paragon Spring Co., 4613-17 W Fulton St., Chicago 44, Ill.
Paramount Die Casting Co., St. Joseph, Mich.
Paramount Paint & Lacquer Co., 3411 E 15th St., Los Angeles 23, Calif.
Park Drop Forge Co., 777 E 79th St., Cleveland 3, Ohio
Parker, Charles Co., Hanover St., Meriden, Conn.
Parker Appliance Co., Rubber Products Div., 17325 Euclid Ave., Cleveland 12, Ohio
Parker & Harper Mfg. Co., 119 Dewey St., Worcester 10, Mass.
Parker Metal Goods Co., 85 Prescott St., Worcester, Mass.
Parker Paint Mfg. Corp., Locust & Poplar Sts., Valparaiso, Ind.
Parker Rust Proof Co., 2177 E Milwaukee, Detroit 11, Mich.
Parker, Stearns & Co., Inc., 300 Sheffield Ave., Brooklyn 7, N.Y.
Parker White Metal Co., 2153 McKinley Ave., Erie, Pa.
Parker-Hannifin Corp., Parker Seal Co. Div., 10567 W Jefferson Blvd., Culver City, Calif.
Parker-Street Castings Co., Broadway & Chaincraft Rd., Cleveland 25, Ohio
Parkwood Laminates, Inc., 24 Water St., Wakefield, Mass.
Patterson Foundry & Machine Co., 41 Henene St., East Liverpool, Ohio
Pattin Mfg. Co., Box 527, Marietta, Ohio

***In contacting suppliers, please mention the Materials Selector Issue***

Paulson, Thomas & Son, Inc., 450 Union St., Brooklyn 31, N.Y
Pawling Rubber Corp., Pawling, N.Y.
Payne, F.S. Co., 75 Richdale Ave., Cambridge 40, Mass.
Peasley Products, Inc., 993 Honeyspot Rd., Stratford, Conn.
Peck Spring Co., Whiting St., Plainville, Conn.
Pecora Inc., 300-400 W Sedgley Ave., Philadelphia 40, Pa.
Pee Wee Molding Corp., 1720 Atlantic Ave., Brooklyn 13, N.Y.
Peerless Alloy Co., 1445 Osage St., Denver 4, Colo.
Peerless Automatic Machine Co., 1970 W 77th St., Cleveland 2, Ohio
Peerless Industries, Inc., P.O. Box 318, Plymouth, Mich.
Peerless Products Industries, 812-14-16 N Pulaski Rd., Chicago 51, Ill.
Peerless Wire Goods Co., Inc., 2703 Ferry St., LaFayette, Ind.
Pelron Corp., 7847 W 47th St., Lyons, Ill.
Pelton Steel Casting Co., 148 W Dewey Pl., Milwaukee 7, Wis.
Pemco Corp., Eastern & Pemco Aves., Baltimore, Md.
Pemco Wheel Co., 1872 Ravine Rd., Kalamazoo, Mich.
Penberthy Instrument Co., 4301 6th Ave. S, Seattle 8, Wash.
Pencoyd Steel & Forge Corp., 3720-40 Main St., Philadelphia 27, Pa.
Peninsular Steel Co., P.O. Box 3853, Parkgrove Sta., Detroit 5, Mich.
Penn Brass & Copper Co., 3837 W 20th St., Erie, Pa.
Penn Engineering & Mfg. Corp., Box 311, Doylestown, Pa.
Penn Extrusion Corp., 3837 W 20th St., Erie, Pa.
Penn Fibre & Specialty Co., Inc., 2024 E Westmoreland St., Philadelphia 34, Pa.
Penn Metal Co., Inc., P.O. Box 1480, Parkersburg, W. Va.
Penn Metal Co., Inc., 40 Central St., Boston 9, Mass.
Penn Steel Castings Co., Front & Penn Sts., Chester, Pa.
Pennsalt Chemicals Corp., 3 Penn Center, Philadelphia 2, Pa.
Pennsylvania Engineering Corp., P.O. Box 311, New Castle 17, Pa.
Pennsylvania Fluorocarbon Co., Inc., 1115 N 38th St., Philadelphia 4, Pa.
Pennsylvania Malleable Iron Corp., 712 S Prince St., Lancaster, Pa.
Penrod, Floyd & Sons Tool & Engineering Corp., 1208 W 2nd St., Muncie, Ind.
Peoria Malleable Casting Co., 2800 N Adams St., Peoria 1, Ill.
Peoria Plastic Co., East Peoria, Ill.
Pequonnock Foundry, Inc., 335 5th St., Bridgeport, Conn.
Pequot Wire Cloth Co., 35 Hoyt, Norwalk, Conn.
Perfecto Cast, 5660 Kearney Villa Rd., San Diego 11, Calif.
Perfex Plastics, Inc., 2632 S Dearborn, Chicago 16, Ill.

**Perforating Industries, Inc. (Ad p 450)**

606 Commerce Rd., Linden, N.J.

Perkins, Henry Co., Broad St., Bridgewater, Mass.
Permacel, U. S. Hwy. #1, New Brunswick, N.J.

**Permali, Inc. (Ad p 431)**

Box 718, Mount Pleasant, Pa.

Permold Co., 1250 W Liberty St., Medina, Ohio
Perrin, Edward C. Co., 3rd & Grant Sts., Camden 2, N.J.
Perry Fay Co., 200 Perry Court, Elyria, Ohio
Perry Plastics, Inc., 3409 W 14th St., Erie, Pa.
Perry-Austen Mfg. Co., 250 Parkinson Ave., Staten Island 5, N.Y.
Peterson, D. J. Co., Sheboygan, Wis.
Peterson Products Corp., 4848 N River Rd., Schiller Park, Ill.
Pettibone Mulliken Corp., 4700 W Division St., Chicago 51, Ill.
Pfaudler Co., West Ave. & Clark St., Rochester 3, N.Y.
Pfister Tubing Corp., 54 W Allendale Ave., Allendale, N.J.
Phelps Dodge Copper Products Corp., 300 Park Ave., New York 22, N.Y.
Phelps Dodge Refining Corp., 40 Wall St., New York, N.Y.
Pheoll Mfg. Co., Inc., 5700 W Roosevelt Rd., Chicago 50, Ill.
Philadelphia Asbestos Corp., 2010 N 10th St., Philadelphia 22, Pa.
Philadelphia Bronze & Brass Corp., 22nd & Masters Sts., Philadelphia 22, Pa.
Philadelphia Enameling Works, Inc., 254 N 13th St., Philadelphia 7, Pa.
Philadelphia Steel & Wire Corp., Penn St. & Belfield Ave., Philadelphia 44, Pa.
Philco Corp., Dexter Foundry Div., 501 N 8th St., Fairfield, Iowa
Phillips, F.C. Inc., 471 Washington St., Stoughton, Mass.
Phillips Chemical Co., Adams Bldg., Bartlesville, Okla.
Philrus Products Co., 135 Newark St., Newark 4, N.J.
Phoenix Die Casting Co., 21-23 Illinois St., Buffalo 3, N.Y.
Phoenix Iron & Steel Co., Front & Dock Sts., Harrisburg, Pa.
Phoenix Mfg. Co., Industry Ave., Joliet, Ill.
Phoenix Products Co., 4715 N 27th St., Milwaukee 9, Wis.
Picco, Inc., 1729 N Chico Ave., El Monte, Calif.
Pierce, F.O. Co., 2-33 50th Ave., Long Island City 1, N.Y.
Pierce Industries, Inc. of Ohio, S.T.D. Div., 1250 Asbestos Ave., Alliance, Ohio
Pierce & Stevens Chemical Corp., 710 Ohio St., Buffalo, N.Y.
Pioneer Aluminum Inc., 5251 W Imperial Blvd., Los Angeles 45, Calif.
Pioneer Stamped Products Co., P.O. Box 185, Roselawn Sta., Rochester 18, N.Y.
Piper Tool Co., Inc., 15930 Common Rd., Roseville, Mich.
Pittsburgh Corning Corp., 1 Gateway Center, Pittsburgh 22, Pa.
Pittsburgh Die & Casting Co., 7503 Ardmore St., Pittsburgh 18, Pa.
Pittsburgh Forgings Co., 919 Amur St., Jackson, Mich.
Pittsburgh Forgings Co., Thorn St., Coraopolis, Pa.
Pittsburgh Foundry & Machine Co., 36th St., Pittsburgh 1, Pa.
Pittsburgh Plate Glass Co., 632 Ft. Duquesne Blvd., Pittsburgh 22, Pa.

**Fiber Glass Div. (Ad p 311)**

1 Gateway Center, Pittsburgh 22, Pa.

Forbes Finishes Div., 3800 W 143rd St., Cleveland, Ohio
Pittsburgh Smelting & Refining Co., 100 W Elizabeth St., Pittsburgh 7, Pa.
Pittsburgh Steel Co., P.O. Box 118, Pittsburgh 19, Pa.
Thomas Strip Div., Grant Bldg., Pittsburgh 30, Pa.
Pittsburgh Steel Foundry Corp., P.O. Box 986, Pittsburgh 30, Pa.
Fort Pitt Steel Casting Div., 25th St., McKeesport, Pa.
Pittsburgh Tool Steel Wire Co., Monaca, Pa.
Pittsburgh Tube Co., 212 Wood St., Pittsburgh 22, Pa.
Plast-Ad Mfg. Co., 222 N Michigan St., South Bend 1, Ind.
Plastex Co., 3232 Cleveland Ave., Columbus 24, Ohio
Plastic Engineering, Inc., 8506 Lake Ave., Cleveland 2, Ohio
Plastic Masters, Inc., New Buffalo, Mich.
Plastic Materials, Inc., New South Rd., Hicksville, N.Y.
Plastic Packaging Co., 2025 W Charleston St., Chicago 47, Ill.
Plastic Pipe & Tube Corp., 224 S Mipas St., Santa Barbara, Calif.
Plastic Process Co., Inc., 10400 Aviation Blvd., Los Angeles 45, Calif.
Plastic Products Corp., 24001 Aurora Rd., Bedford Heights, Ohio.
Plasticrafters, Inc., 1829 S 55th Ave., Cicero 50, Ill.

**Plastics Engineering Co. (Ad p 270)**

1607 Geele Ave., Sheboygan, Wis.

Plastiglide Mfg. Corp., 1757 Stanford St., Santa Monica, Calif.
Pipco International Corp., 1731 Stanford St., Santa Monica, Calif.
Plastic Compounding Corp., 3122 Nebraska Ave., Santa Monica, Calif.
Plax Corp., Box 1019, Hartford, Conn.
Plumb Chemical Corp., 4837 James St., Philadelphia 37, Pa.
Plume & Atwood Mfg. Co., Thomaston, Conn.
Plymouth Cordage Co., Plymouth, Mass.
Plymouth Industrial Products, Inc., 503 Indiana Ave., Sheboygan, Wis.
Pohlman, R.L. Co., 6730 Olive St. Rd., St. Louis 5, Mo.
Pohlman Foundry Co., Inc., 205 Baitz Ave., Buffalo 6, N.Y.
Polacoat, Inc., 9752 Conklin Rd., Cincinnati 42, Ohio
Polar Ware Co., Lakeshore Rd., Sheboygan, Wis.
Pollock, Robert Co., 123 S Maryland Ave., Glendale, Calif.
Polo Plastics Co., 1718 N 1st St., Milwaukee 12, Wis.
Poly Resins, 11661 Wicks St., Sun Valley, Calif.
Polycast Corp., 69 Southfield Ave., Stamford, Conn.
Polyform Plastics Corp., 24 University Pl., New York 3, N.Y.
Polygon Plastic Co., Walkerton, Ind.
Poly-Kote, Inc., 82 Chestnut St., North Attleboro, Mass.
Polymer Chemical Co., 5920 Carthage Ave., Cincinnati 12, Ohio
Polymer Corp., 2120 Fairmont Ave., Reading, Pa.

**Polymer Corp. of Pennsylvania Sub. (Ad p 230)**

2140 Fairmont Ave., Reading, Pa.

Whirlclad Div., 125 N 4th St., Reading, Pa.

Polymer Industries Inc., Springdale, Conn.
Polyphase Machine Co., 43-22 50th St., Woodside 77, N.Y.
Polyplastic Products, Inc., 24th Ave., Paterson, N.J.
Polytron Corp., 1175 S 10th St., Richmond 4, Calif.
Poor & Co., 80 E Jackson Blvd., Chicago, Ill.
Canton Forge & Axle Works, 2025 Dueber Ave., SW, Canton 6, Ohio
Promat Div., 851 S Market St., Waukegan, Ill.
Porcelain Enamel Finishers, 3221 W 30th St., Chicago 23, Ill.
Porcelain Products, Inc., 224 N Patterson, Carey, Ohio
Portable Electric Tools, Inc., Admiral Die Castings Div., 250 W 83rd St., Chicago 20, Ill.
Porter, H.K. Inc., 74 Foley, Somerville 43, Mass.
Porter, H.K. Co., Inc., Alcoa Bldg., Pittsburgh 19, Pa.
Connors Steel Div., 5000 Powell Ave., Birmingham 6, Ala.
Forge & Fittings Div., 3270 E 79th St., Cleveland 4, Ohio
National Electric Div., Porter Bldg., Pittsburgh 19, Pa.
Refractories Div., Porter Bldg., Pittsburgh 19, Pa.

**Riverside-Alloy Metal Div. (Ad p 160)**

1 Pavillion Ave., Riverside, N.J.

Thermoid Div., Tacony & Comly Sts., Philadelphia 24, Pa.
Vulcan-Kidd Steel Div., Aliquippa, Pa.
Porter, William Co., 1007 Santa Fe Ave., Los Angeles 21, Calif.
Portland Co., 58 Fore St., Portland, Me.
Portland Iron Works, 1335 NW Northrup St., Portland 9, Ore.
Posey Iron Works, Inc., 580 S Prince St., Lancaster, Pa.
Potts, C. & G. & Co., 816 Washington Ave., Indianapolis, Ind.
Powder Metals Products Co., 500 St. Marys St., St. Marys, Pa.
Powdercraft Corp., 746 Hayne St., Spartanburg, S. C.
Powell Pressed Steel Co., Hubbard, Ohio
Pratt & Lambert, Inc., 75 Tonawanda St., Buffalo 7, N.Y.
Precision Castparts Corp., 4600 SE Harney Dr., Portland 6, Ore.

**Precision Extrusions, Inc. (Ad p 458)**

132 S Addison St., Bensenville, Ill.

Precision Founders, Inc., 414 Hester St., San Leandro, Calif.
Precision Machine Co., 1110 E 22nd St., Indianapolis 2, Ind.
Precision Metal Products Co., P.O. Box 129, Ellwood City, Pa.
Precision Metal Spinning Co., 9861 Dixie Hwy., Clarkston, Mich.
Precision Metalsmiths, Inc., 1081 E 200 St., Cleveland 17, Ohio
Precision Paper Tube Co., 2035 W Charleston St., Chicago 47, Ill.
Precision Piece Parts, Inc., 712 S Logan St., Mishawaka, Ind.
Precision Plastics Co., 4655 Stenton Ave., Philadelphia 44, Pa.
Precision Rubber Products Corp., 3110 Oakridge Dr., Dayton 7, Ohio
Precision Screw Products Co., Inc., 4764 Valley Blvd., Los Angeles 32, Calif.
Precision Tube Co., Inc., Church Rd. & Wissahickon Ave., North Wales, Pa.
Premier Metal Works, Inc., 1614 S Clinton St., Chicago 16, Ill.
Premier Thermo Plastics Co., Jeffersontown, Ky.
Prescott Co., 1610 15th St., Menominee, Mich.
Presmet Corp., 112 Harding St., Worcester 4, Mass.
Pressed Steel Co., Wilkes Barre, Pa.
Pressed Steel Tank Co., 1493 S 66th St., Milwaukee 14, Wis.
Pressure Castings, Inc., 21500 St. Clair Ave., Cleveland 19, Ohio
Presswork, Inc., 9100 Roselawn Ave., Detroit 4, Mich.
Presto Plastic Products Co., Inc., 5410 Ave. U, Brooklyn 34, N.Y.
Prestole Corp., 1345 Miami St., Toledo 5, Ohio
Prince Rubber & Plastics Co., Inc., 1675 Niagara St., Buffalo 7, N.Y.
Production Die Casting Co., P.O. Box 9456, Houston 11, Tex.
Progressive Service Co., 2745 Locust St., St. Louis 3, Mo.
Protective Treatments, Inc., 420 Dellrose Ave., Dayton, Ohio
Puget Sound Plywood, Inc., 230 E. F St., Tacoma 2, Wash.
Purdy, A. R. Co., Inc., Page Ave. & Orient Way, Lyndhurst, N.J.
Pure Carbon Co., Inc., 441 Hall Ave., St. Marys, Pa.

Puritan Co., Inc., Beach & Lyell Aves., Rochester, N.Y.
Pusey & Jones Corp., Front & Poplar Sts., Wilmington 9, Del.
Pyramid Industries, Inc., 1422 Irwin Dr., Erie, Pa.
Pyramid Mouldings, Inc., 5353 W Armstrong Ave., Chicago 46, Ill.
Pyramid Plastics, Inc., 556 W Polk St., Chicago 7, Ill.
**Pyramid Products Co., Inc. (Ad p 458)**
3967 E 93rd St., Cleveland 5, Ohio
Pyro Plastics Corp., Pyro Park, Union, N.J.
**Pyron Corp. (Ad p 432)**
Box E, LaSalle Sta., Niagara Falls, N.Y.
Pyrosil, Inc., P.O. Box 206, Cuyahoga Falls, Ohio

## q

Quaker Alloy Casting Co., Myerstown, Pa.
Quaker City Felt Co., 1734-36 Ludlow St., Philadelphia, Pa.
Quaker State Metals Co., P.O. Box 1167, Lancaster, Pa.
Quality Aluminum Casting Co., 1242 Lincoln Ave., Waukesha, Wis.
Quality Electric Steel Castings, Inc., P.O. Box 9382, Houston 11, Tex.
Queen Products Co., Inc., 13th & Rowan Sts., Louisville 3, Ky.
Quelcor, Inc., Front & Broomall Sts., Chester, Pa.
Quincy Steel Casting Co., 30 Fayette St., North Quincy 71, Mass.
Quinn-Berry Corp., 2609 W 12th St., Erie, Pa.

## r

REF Mfg. Corp., 391 Jericho Tpk., Mineola, N.Y.
Racine Screw Co., 1501 Clark St., Racine, Wis.
Radiant Color Co., 830 Isabella St., Oakland 7, Calif.
Radiation Applications, Inc., 42-30 24th St., Long Island City 1, N.Y.
Raffi and Swanson, Inc., 100 Eames St., Wilmington, Mass.
Rainier Metal Products Co., 2412 W 71st St., Chicago 29, Ill.
Rand Rubber Co., 397 Sumner Ave., Brooklyn 16, N.Y.
Randolph Products Co., 18 12th St., Carlstadt, N.J.
Rangers Die Casting Co., 10828 S Alameda St., Lynwood, Calif.
Rankin Forge Co., Rankin, Pa.
Rasco-Veeder Co., 1600 S Dearborn St., Chicago 16, Ill.
Rathbone Corp., Park St., Palmer, Mass.
Rausch Mfg. Co., Inc., 750 Pelham Blvd., St. Paul 14, Minn.
Ravenswood Machine Corp., 3325 N Knox Ave., Chicago 41, Ill.
Raybestos-Manhattan, Inc., 61 Willett St., Passaic, N.J.
**Adhesives Div. (Ad p 492)**
P.O. Box 1021, Bridgeport 2, Conn.
**Plastic Products Div. (Ad p 268)**
Manheim, Pa.
Raybestos Div., P.O. Box 1021, Bridgeport 2, Conn.
Reactive Metals, Inc., 980 Warren Ave., Niles, Ohio
Reade Mfg. Co., Inc., 135 Hoboken Ave., Jersey City 2, N.J.
Reading Tube Corp., Empire State Bldg., 350 5th Ave., New York, N.Y.
Red Devil Mfg. Co., 1412 N Ogden Ave., Chicago 10, Ill.
Redmer Air Devices, Box 247, Guntersville, Ala.
Reduction and Refining Co., Kenilworth, N.J.
Reed Plastics Corp., 116 Gold St., Worcester 8, Mass.
Reed & Prince Mfg. Co., 1 Duncan Ave., Worcester 1, Mass.
Reese Metal Products Corp., 537 Howard Ave., Lancaster, Pa.
**Reeves Bros., Inc., Vulcan Rubber Products Div. (Ad p 318)**
1071 Ave. of Americas, New York, N.Y.
Refinery Castings Co., P.O. Box 5085, Dallas 22, Tex.
Reflin Co., 5660 Kearney Villa Rd., San Diego 11, Calif.
Refractory & Insulation Corp., 120 Wall St., New York 5, N.Y.
Refractory Specialties Co., 2200 Washington Ave., Philadelphia 46, Pa.
Regal Plastic Co., 2800 E 14th St., Kansas City 27, Mo.
Regal Ware, Inc., Kewashum, Wis.
**Reichert Float & Mfg. Co. (Ad p 464)**
2242 Smead Ave., Toledo 6, Ohio
Reichhold Chemicals, Inc., 525 N Broadway, White Plains, N.Y.
Reinhold Engineering & Plastics Co., 12827 E Imperial Hwy., Norwalk, Calif.
Reliable Screw Machine Products, 4433 W Rice St., Chicago 51, Ill.
Reliable Spring & Wire Forms Co., 3167 Fulton Rd., Cleveland 9, Ohio
Reliance Foundry Co., 500-526 E Front St., Cincinnati 2, Ohio
Reliance Plastic & Chemical Corp., 110 Kearney St., Paterson 2, N.J.
Reliance Steel Castings Co., 2818 Smallman St., Pittsburgh 22, Pa.
Remler Co., Ltd., 2101 Bryant St., San Francisco 10, Calif.
Ren Plastics, Inc., 5422 S Cedar Rd., Lansing 17, Mich.
Rensselaer Valve Co., Cohoes, N.Y.
Replac Corp., 2130 St. Clair Ave., Cleveland 17, Ohio
Republic Die Casting Co., 611 Talcott Ave. St. Louis 7, Mo.
Republic Foil, Inc., 55 Triangle St., Danbury, Conn.
Republic Lead Equipment Co., 7930 Jones Rd., Cleveland 5, Ohio
Republic Metals Co., Inc., 273 Green, Brooklyn 22, N.Y.
**Republic Steel Corp. (Ad pp 84-85)**
Republic Bldg., Cleveland 1, Ohio
Steel & Tubes Div., 224 E 131st St., Cleveland 8, Ohio
Resistoflex Corp., Woodland Rd., Roseland, N.J.
Resolite Corp., P.O. Box 366, Zelienople, Pa.
Revere Copper & Brass, Inc., 230 Park Ave., New York 17, N.Y.
Foil Div., 196 Diamond St., Brooklyn 22, N.Y.
Rome Mfg. Div., Mill St., Rome, N.Y.
Rex Products Co., 1918 E 55th St., Cleveland 3, Ohio
Reynolds Aluminum Supply Co., 573 W Peachtree St., NE, Atlanta 3, Ga.
Reynolds Chemical Products Co., 1200 N Main St., Ann Arbor, Mich.
Reynolds Metals Co., P.O. Box 2346-ZA, Richmond, Va.
Foil Div., Reynolds Metals Bldg., Richmond 18, Va.
Rezolin, Inc., 1051 18th St., Santa Monica, Calif.
Rhoads, J.E. & Sons, 2100 W 11th St., Wilmington, Del.
**Rhode Island Tool Co. (Ad p 450)**
148 W River St., Providence 1, R.I.
Richardson Co., 2737 Lake St., Melrose Park, Ill.
Richmond Foundry & Mfg. Co., Inc., 1300 Hermitage Rd., Richmond 20, Va.
Richmond Mfg. Co., 312 N York St., Houston 3, Tex.
Richmond Mica Corp., 900 Jefferson Ave., Newport News, Va.
Ridge Foundry, 1554 Doolittle Dr., San Leandro, Calif.
Riegel Paper Co., 260 Madison Ave., New York 16, N.Y.
Rigidized Metals Corp., 658 Ohio St., Buffalo 3, N.Y.
Rinshed-Mason Co., Milford at Epworth, Detroit, Mich.
River Smelting & Refining Co., 4195 Bradley Rd., Cleveland 1, Ohio
Riverside Foundry Co., N Front St., Wrightsville, Pa.
Riverside Foundry & Galvanizing Co., 508 Harrison St., Kalamazoo, Mich.
Riverside Plastics Corp., 220 Miller Rd., Hicksville, N.Y.
Roberts Toledo Rubber Co., 4143 Monroe St., Toledo 13, Ohio
Robertson, H.H. Co., 2400 Farmer Bank Bldg., Pittsburgh, Pa.
Robertson Steel & Iron Co., 72 Elm St., Cincinnati 2, Ohio
Rochester Novelty Works, Inc., 485 Hague St., Rochester 6, N.Y.
Rockford Bolt & Steel Co., 126 Mill St., Rockford, Ill.
Rockwell Engineering Co., 13500 S Western Ave., Blue Island, Ill.
Rockwell Mfg. Co., LFM Mfg. Co., Inc. Sub., Atchison, Kan.
**Rockwell - Standard Corp., Stamping Div. (Ad p 458)**
1008 Oswego St., Utica 1, N.Y.
Roddis Plywood Corp., Marshfield, Wis.
Rode, Inc., R5 Green St., Woburn, Mass.
Rodney Hunt Machine Co., 46 Mill St., Orange, Mass.
Rodney Metals, Inc., 1357 Rodney French Blvd., New Bedford, Mass.
**Rogers Corp. (Ad p 261)**
Rogers, Conn.
Rogers, V.F. Plastic Molding, 4320 Fox St., Denver 16, Colo.
Rohm & Haas Co., Washington Square, Philadelphia 5, Pa.
Rohnco, Inc., 116 Limestone, Bellevue, Peoria 5, Ill.
Rohr Aircraft Corp., Foot of "H" St., Chula Vista, Calif.
Rolinco, Inc., 116 Limestone, Bellevue, Peoria 5, Ill.
Roll Coater, Inc., Box 67, Pendleton, Ind.
Roll Formed Products Co., 3762 Oakwood Ave., Youngstown, Ohio
Rolle Mfg. Corp., 3rd St. & Cannon Ave., Lansdale, Pa.
Rolled Alloys, Inc., 5309 Concord, Detroit 11, Mich.
Roller Reinforced Plastics, W 47th St., Box 192, Ashtabula, Ohio
Rolock, Inc., 1350 Kings Hwy., Fairfield, Conn.
Romar Plastics, Inc., 1311 E Main St., St. Charles, Ill.
Rome Strip Steel Co., Inc., 530 Henry St., Rome, N.Y.
Rome Turney Radiator Co., Rome, N.Y.
Rosan, Inc., 2901 W Coast Hwy., Newport Beach, Calif.
Rosco Laboratories, 29 Moore St., Brooklyn 6, N.Y.
Rose Iron Works, 1539 E 43rd St., Cleveland 3, Ohio
Rosedale Foundry & Machine Co., 1731 Prebel Ave., Pittsburgh 33, Pa.
Ross & Roberts, Inc., 1299 W Broad St., Stratford, Conn.
Ross-Meehan Foundries, 1601 Carter St., Chattanooga 1, Tenn.
Rostone Corp., Rd. 52 S, Lafayette, Ind.
Roth Rubber Co., 1854 S 54th St., Chicago 50, Ill.
Roth Steel Products Co., 1335 E 171st St., Cleveland 10, Ohio
Rotometals, 980 Harrison St., San Francisco 7, Calif.
Rowland Products, Inc., Fairview Lane, Kensington, Conn.
Royce Aluminum Corp., 704 W Water St., Taunton, Mass.
Rubber & Asbestos Corp., 225 Belleville Ave., Bloomfield, N.J.
Rubber Corp. of America, New South Rd., Hicksville, L.I., N.Y.
Rubber & Plastics Compound Co., Inc., 10 Rockefeller Plaza, New York 20, N.Y.
Ruberoid Co., 500 5th Ave., New York 36, N.Y.
Funkhouser Mills Div., P.O. Box 569, Hagerstown, Md.
Ruby Chemical Co., 68-70 McDowell St., Columbus 16, Ohio
Rupert Diecasting Co., 1655 Cleveland Ave., Kansas City 27, Mo.
**Russell, Burdsall & Ward Bolt & Nut Co. (Ad p 501)**
Midland Ave., Port Chester, N.Y.
Russell Mfg. Co., 400 E Main St., Middletown, Conn.
Russell Reinforced Plastics Corp., 521 W Hoffman Ave., Lindenhurst, N.Y.
Rust-Oleum Corp., 2425 Oakton St., Evanstown, Ill.
Rustproofing & Metal Finishing Corp., 75 Commercial Ave., Cambridge 42, Mass.
Ryerson, Joseph T. & Son, Inc., 16th & Rockwell Sts., Chicago 8, Ill.

## s

S & S Mfg. Co., 6139 Adams St., West New York, N.J.
Sager Metal Strip Co., 3649 S Racine, Chicago 9, Ill.
Saginaw Bay Industries, Inc., 242 N Water St., Bay City, Mich.
Saginaw Bearing Co., 821 S Water St., Saginaw, Mich.
St. Clair Rubber Co., 440 E Jefferson Ave., Detroit 26, Mich.
St. Eloi Corp., Box 507, Newtown Station, Cincinnati 44, Ohio
St. Joseph Lead Co., 250 Park Ave., New York 17, N.Y.
St. Louis Diecasting Corp., 4528 Oleatha Ave., St. Louis 16, Mo.
St. Louis Malleable Casting Co., 7701 N Conduit Ave., St. Louis, Mo.
St. Louis Steel Casting, Inc., 100 Mott St., St. Louis 15, Mo.
St. Marys Carbon Co., State Rd., St. Marys, Pa.
St. Marys Foundry Co., P.O. Box 248, St. Marys, Ohio
St. Pierre Chain Corp., 50 Frank St., Worcester 4, Mass.
St. Regis Paper Co., 150 E 42nd St., New York, N.Y.
Cambridge-Panelyte Molded Plastics Co. Div., Cambridge, Ohio
Chester Packaging Div., 684 Nepperhan Ave., Yonkers, N.Y.
**Panelyte Div. (Ad p 250)**
Enterprise Ave., Trenton 8, N.J.
Sall Bros. Co., 2300 Kishwaukee St., Rockford, Ill.
Sall, George Metals Co., Inc., 2255 E Butler St., Philadelphia 37, Pa.
San Francisco Galvanizing Works, 1180 Harrison St., San Francisco 3, Calif.

***In contacting suppliers, please mention the Materials Selector Issue***

San Francisco Iron Foundry, 260 Townsend St., San Francisco 7, Calif.

**Sandusky Foundry & Machine Co. (Ad p 427)**
W Market St., Sandusky, Ohio

**Sandvik Steel, Inc. (Ad p 83)**
1702 Nevins Rd., Fair Lawn, N.J.

Sandy Hill Iron & Brass Works, 27 Allen St., Hudson Falls, N.Y.

Sanford Plastics Corp., 521 Fifth Ave., New York 17, N.Y.

Sanford Process Co., Inc., 6920 S Central Ave., Los Angeles 1, Calif.

Santay Corp., 351 N Crawford Ave., Chicago 24, Ill.

Saramar Aluminum Co., 4021 Mahoning Ave., Youngstown 1, Ohio

Saran Protective Coatings Co., 2415 Burdette Ave., Detroit 20, Mich.

Sargent & Greenleaf, Inc., 24 Seneca Ave., Rochester 21, N.Y.

Sauereisen Cements Co., 1045 N Canal St., Pittsburgh 15, Pa.

Saunders, Alexander & Co., Inc., 195 Bedford St., New York 14, N.Y.

Savannah Machine and Foundry Co., Foundry Div., P.O. Box 590, Savannah, Ga.

Sawbrook Steel Castings Co., Shepherd & McWhorter Sts., Lockland, Cincinnati 15, Ohio

Sawhill Tubular Products, Inc., P.O. Box 11, Sharon, Pa.

Saxonburg Ceramics, Saxonburg, Pa.

Scaife Co., Anne St., Oakmont, Pa.

Schachner Leather & Belting Co., Charlotte Leather Belting Co. Div., P.O. Box 3205, Charlotte 3, N.C.

Schaefer-Goodnow Foundries, Inc., 2 36th St., Pittsburgh 1, Pa.

Schaefer-Hausner Corp., 527 Lexington Ave., New York 17, N.Y.

Schenectady Varnish Co., Inc., Congress St. & 9th Ave., Schenectady 3, N.Y.

Schilling Bronze Co., 202-216 E North St., Rome 2, N.Y.

Schlueter Mfg. Co., 4616 N Broadway, St. Louis 7, Mo.

Schmeller Aluminum Foundry Co., 3300 E 87th St., Cleveland 27, Ohio

Schneider, Bowman Co., Inc., 1612 Van Dyke St., Philadelphia 24, Pa.

Schultz Die Casting Co., 1810 Clinton St., Toledo 7, Ohio

Schumann, I. & Co., 4391 Bradley Rd., P.O. Box 2219, Cleveland 9, Ohio

Schwab Plastics Corp., 17310 Northlawn, Detroit, Mich.

Schwartz Chemical Co., Inc., 50-01 2nd St., Long Island City, N.Y.

Schwarzkopf Development Corp., 595 Madison Ave., New York 22, N.Y.

Scott Paper Co., Foam Div., Delaware & Broomall, Chester, Pa.

Scottdale Ozone Co., Crescent St., Scottdale, Pa.

**Scovill Mfg. Co., Mill Products Div. (Ad pp 169-170)**
99 Mill St., Waterbury 20, Conn.

Scranton Plastic Laminating Corp., 3216-18 Pittston Ave., Scranton 5, Pa.

Scudder, E.J. Foundry & Machine Co. Canal & Pearl Sts., Trenton 9, N.J.

Scullin Steel Co., 6700 Manchester Ave., St. Louis 10, Mo.

Seal-Peel, Inc., 755 Stephenson Hwy., Royal Oak 3, Mich.

Sealube Co., 14 Valley St., Wakefield, Mass.

Sealview Plastics, Inc., 1010 Ford St., West Conshohocken, Pa.

Seaman Products, 13001 Bradley Ave., Sylmar, Calif.

Seamless Rubber Co., 253 Hallock Ave., New Haven 3, Conn.

Seaporcel Metals, Inc., 28-20 Borden Ave., Long Island City, N.Y.

Seattle Boiler Works, Inc., 5237 E Marginal Way, Seattle, Wash.

Security Cos., 20096 James Couzens, Detroit 38, Mich.

Security Sash & Screen Co., 385 Midland, Detroit, Mich.

Seiberling Rubber Co., Plastics Div., Newcomerstown, Ohio

Selma Foundry & Machine Co., P.O. Box 662, Selma, Ala.

**Sel-Rex Corp. (Ad p 356)**
75 River Rd., Nutley 10, N.J.

Seltzer, George H. & Co., Ridley & B & O RR, P.O. Box 66, Folsom, Pa.

Semon Bache & Co., 636 Greenwich St., New York 14, N.Y.

Seneca Wire & Mfg. Co., Fostoria, Ohio

Sequoia Metalcraft Co., Inc., 1001 Washington St., San Carlos, Calif.

Serrick Corp., Defiance, Ohio
Acme Machine Products Div., 1300 Batavia St., Muncie, Ind.
John Lees Div., 1300 Batavia St., Muncie, Ind.
Screw Machine Products Div., 731-22 Perry, Defiance, Ohio

Service Steel Co., 1435 Franklin St., Detroit 7, Mich.

Servwell Products Co., 6541 Euclid Ave., Cleveland 3, Ohio

**Set Screw & Mfg. Co. (Ad p 496)**
149 Main St., Bartlett, Ill.

Sewell Mfg. Co., 1019 E 10 Mile Rd., Hazel Park, Mich.

**Seymour Mfg. Co. (Ad p 178)**
15 Franklin St., Seymour, Conn.

Shakopee Foundry Co., Shakopee, Minn.

Shamban, W.S. & Co., 11617 W Jefferson Blvd., Culver City, Calif.

Shank Metal Products Co., 347 Madison Ave., New York 17, N.Y.

Sharon Steel Corp., Sharon, Pa.
Brainard Steel Div., Griswold St., Warren, Ohio

Sharpsville Steel Fabricators, Inc., 6th & Main Sts., Sharpsville, Pa.

Shaw Insulator Co., 160 Colt St., Irvington 11, N.J.

Shawinigan Resins Corp., 644 Monsanto Ave., Springfield 1, Mass.

Shaw-Kendall Engineering Co., 120 S Superior St., P.O. Box 1736, Toledo 3, Ohio

Sheffield Foundry Co., 2070 Clybourn Ave., Chicago 14, Ill.

Sheffield Plastics, Inc., Salisbury Rd., Sheffield, Mass.

Shelby Instrument Co., 1701 Magnolia Ave., Long Beach, Calif.

Shelby Mfg. Co., E Russel Rd., Sidney, Ohio

Sheldon, M.L. & Co., Inc., 350 Lexington Ave., New York 16, N.Y.

Shell Chemical Co., 50 W 50th St., New York 20, N.Y.

Shelter Mfg. Corp., 8-159 General Motors Bldg., Detroit 2, Mich.
Dryden Rubber Div., 1014 S Kildare Ave., Chicago 24, Ill.

**Shenango Furnace Co., Centrifugally Cast Products Div. (Ad p 422)**
Dover, Ohio

Shenango Refractories, P.O. Box 120, New Castle, Pa.

Sherman & Reilly, Inc., 1st & Broad Sts., Chattanooga, Tenn.

Sherwatt Equipment & Mfg. Co., Inc., 47 Murray St., New York 7, N.Y.

Sherwin-Williams Co., 101 Prospect Ave., NW, Cleveland 1, Ohio

Shieldalloy Corp., West Blvd., New Field, N.J.

Shingle Leather Co., 1300 Walnut St., Camden 3, N.J.

Shoe Form Co., Inc., De Witt Plastics Div., Aurelius Ave., Auburn, N.Y.

Shriver, T. & Co., Inc., 890 Hamilton St., Harrison, N.J.

Shull Bros. Glass Co., 509 N 6th St., Millville, N.J.

Shur-Lok Corp., 879 S East St., Anaheim, Calif.

Sibley Machine & Foundry Corp., 206 E Tutt St., South Bend 23, Ind.

Sierra Electric Corp., 15100 S Figueroa St., Gardena, Calif.

Sierra Engineering Co., 123 E Montecito, Sierra Madre, Calif.

Sifco Metachemical, Inc., 935 E 63rd St., Cleveland 3, Ohio

Silicocks Miller Co., 10 W Parker Ave., Maplewood, N.J.

**Simmons Fastener Corp. (Ad p 497)**
N Broadway, Albany 1, N.Y.

Simon Products Co., 3211 W Grand St., Chicago 51, Ill.

Simonds Saw and Steel Co., 470 Main St., Fitchburg, Mass.

Simonsen Metal Products Co., 4444 W Chicago, Chicago 51, Ill.

Simpson Timber Co., 1010 White Bldg., Seattle, Wash.

Sinclair Co., 60 Appleton St., Holyoke, Mass.

Sinko Mfg. & Tool Co., 7310 W Wilson Ave., Chicago 31, Ill.

Sintered Metals, Inc., 3390 Washington St., Jamaica Plain 30, Mass.

Sioux City Foundry & Boiler Co., E 8th & Division Sts., Sioux City 2, Iowa

Sipe Metals Corp., 1720 N Elston Ave., Chicago 22, Ill.

Sivyer Steel Casting Co., 43rd & Mitchell Ave., Milwaukee 14, Wis.

Skookum Co., Inc., 8504 W Crawford St., Portland 3, Ore.

Skyline Industries, Titusville 1, Pa.

Small Tube Products, Inc., Main St., Waterbury, Conn.

Smith, A.O. Corp., 3533 N 27th St., Milwaukee 1, Wis.

Smith, A.P. Mfg. Co., 500 N Arlington Ave., East Orange, N.J.

Smith, N.J. Bolt Co., P.O. Box 7398, Houston 8, Tex.

Smith Chemical & Color Co., Inc., 55 John St., Brooklyn 1, N.Y.

Smith & Winchester Mfg. Co., South Windham, Conn.

Smith-Armstrong Forge, Inc., 1209 Marquette Rd., Cleveland 14, Ohio

Smithers Tool & Machine Products, Inc., 64 S Broadway, Red Hook, N.Y.

Smith-Moon Steel Co., Inc., Courier Bldg., Winfield, Kan.

Smith-Victor Corp., Griffith, Ind.

Smoot-Holman Co., 321 N Eucalyptus Ave., Inglewood, Calif.

Snyder Mfg. Co., Inc., 1458 5th St. NW, New Philadelphia, Ohio

Snyder, M.L. & Son, Inc., Jasper & York Sts., Philadelphia 15, Pa.

Solar Aircraft Co., 2200 Pacific Hwy., San Diego 12, Calif.

Solar Steel Corp., Union Commerce Bldg., Cleveland, Ohio

Solon Foundry, Inc., 6370 SoM Center Rd., Solon, Ohio

**Somers Brass Co., Inc. (Ad p 162)**
94 Baldwin Ave., Waterbury 20, Conn.

Somerset Foundry & Machine Co., 809-831 Edgewood Ave., Somerset, Pa.

Sommer Metalcraft Corp., 315 Poston Dr., Crawfordsville, Ind.

Sonken-Galamba Corp., 2nd & Riverview, Kansas City 18, Kan.

Sorbo-Cast Corp., New Brunswick, N.J.

Sorbo-Mat Process Engineers, 106 S Hanley St., St. Louis 5, Mo.

South Chester Corp., Southco Div., Lester, Pa.

South River Metal Products Co., Inc., 377 Turnpike, South River, N.J.

Southern Adhesives Corp., 1501 W Moore St., Richmond, Va.

Southern Aluminum Finishing Co., Inc., 1581 Huber St., NW, Atlanta 18, Ga.

Southern Asbestos Co., 1000 Seaboard Rd., Charlotte, N.C.

Southern Belting & Transmission Co., P.O. Box 4296, Atlanta 2, Ga.

Southern Car & Mfg. Co., Inc., 1831 29th Ave. N, Birmingham, Ala.

Southern Extrusions, Inc., N Washington St., Magnolia, Ark.

Southern Fabricating Co., Inc., 818 20th St., Sheffield, Ala.

Southern Galvanizing Co., 1620 Bush St., Baltimore 30, Md.

Southern Metal Products Co., 4444 N Miro St., New Orleans 17, La.

Southern Plastics Co., 408 Pendelton St., Columbia, S.C.

Southern Screw Co., P.O. Box 1360, Statesville, N.C.

Southwestern Plastic Pipe Co., P.O. Box 117, Mineral Wells, Tex.

Southwestern Porcelain Steel Corp., P.O. Box 607, Sand Springs, Okla.

**Spaulding Fibre Co., Inc. (Ad p 255)**
310 Wheeler St., Tonawanda, N.Y.

Special Screw Products Co., 100 Northfield Rd., Bedford, Ohio

Specialty Resins Co., 2801 Lynwood Rd., Lynwood, Calif.

**Speer Carbon Co. (Ad p 318)**
St. Marys, Pa.

Spencer Chemical Co., Dwight Bldg., 1004 Baltimore Ave., Kansas City 5, Mo.

Spencer Nahm Co., 765 1st Ave., San Leandro, Calif.

Spencer Rubber Co., Main & Chapel Sts., Manchester, Conn.

Spencer's Sons, I.S. Inc., 20 Fair St., Guilford, Conn.

Spincraft, Inc., 4122 W State St., Milwaukee 8, Wis.

Spiral-Glas Pipe Co., P.O. Box 1951, Old Bridge, N.J.

Spraylat Corp., 1 Park Ave., New York 16, N.Y.

Spring City Foundry Co., Hall & Main Sts., Spring City, Pa.

Spring Packing Corp., 332 S Michigan Ave., Chicago 4, Ill.

Springer's Foundry Co., Inc., 201 S 1st St., Terre Haute, Ind.

Springfield Foundry Co., 295 Pasco Rd., Indian Orchard, Mass.

Spruce Pine Mica Co., Inc., P.O. Box 450, Spruce Pine, N.C.

Spuck Iron & Foundry Co., 3145 N 14th St., St. Louis 7, Mo.

Stacey Mfg. Co., Township Ave., & Big Four RR, Cincinnati 16, Ohio

**Stackpole Carbon Co. (Ad p 320)**
St. Marys, Pa.

Stainless Foundry & Engineering, Inc., 5132 N 35th St., Milwaukee 9, Wis.

Stainless Metals, Inc., 19-42 42nd St., Long Island City 1, N.Y.

Stalker Corp., 203 Woodside Ave., Essexville, Mich.

Stalwart Rubber Co., 160 Northfield Rd., Bedford, Ohio

Stamford Metal Specialty Co., Inc., 429 W Broadway, New York 12, N.Y.

Stamford Rolling Mills Co., Inc., Springdale, Conn.

Standard Asbestos Mfg. Co., 860 W Evergreen Ave., Chicago 22, Ill.

Standard Casting Corp., 4400 W Cermak Rd., Chicago 23, Ill.

Standard Felt Co., 29-115 S Palm Ave., Alhambra, Calif.

Standard Forge & Axle Co., Inc., P.O. Box 309, Montgomery 1, Ala.

Standard Foundry Co., Southgate & Armory Sts., Worcester 10, Mass.

Standard Insulation Co., Plastics Div., 74 Paterson Ave., East Rutherford, N.J.

Standard Locknut & Lockwasher Inc., 2250-56 Valley Ave., Indianapolis 18, Ind.

Standard Magnesium Corp., 7500 E 41st St., Tulsa, Okla.

Standard Metals Corp., 262 Broad St., North Attleboro Mass.
Standard Nut & Bolt Co., Abbott St., Valley Falls, R.I.
Standard Packaging Corp., Johnston Foil Div., 6106 S Broadway, St. Louis 11, Mo.
Standard Plastics Co., 62 Water St., Attleboro, Mass.
Standard Pressed Steel Co., Box 888, Jenkintown, Pa.
Standard Products Co., 316 Fisher Bldg., Detroit, Mich.
Standard Screw Co., Wilson, Conn.
Chicago Screw Co., 2701 Washington Blvd., Bellwood, Ill.
Hartford Machine Screw Co., P.O. Box 1440, Hartford 2, Conn.
Western Automatic Machine Screw Co., 377 Woodland Ave., Elyria, Ohio
Standard Screw Products Co., 506 S Palm Ave., Alhambra, Calif.
Standard Stamping & Perforating Co., 3129 W 49th Place, Chicago 32, Ill.
Standard Steel Sections, Inc., 608 E 133rd St., New York, N.Y.
Standard Tube Co., 24400 Plymouth Rd., Detroit 39, Mich.
Standard Washer & Mat, Inc., 155 Adams St., Manchester, Conn.
Stanley Chemical Co., Berlin St., East Berlin, Conn.
Stanley Works, Stanley Industrial Sales Div., 195 Lake St., New Britain, Conn.
Stanwood Corp., 4819 Cortland, Chicago 39, Ill.
Star Expansion Industries Corp., Pleasant Hill Rd., Mountainville, N.J.
Star Heel Plate Co., Inc., 12 Thornton St., Newark 5, N.J.
Star Porcelain Co., Muirhead Ave., Trenton, N.J.
Star Stainless Screw Co., 194 Union Ave., Totowa, N.J.
Star Stamping Co., 1303 M-139, Benton Harbor, Mich.
Star Wire Screen & Iron Works Inc., 2515 San Fernando Rd., Los Angeles 65, Calif.
Star Woolen Co., Cohoes, N.Y.
State Foundry & Machine Co., Cedar Grove, Wis.
**Stauffer Chemical Co. (Ad p 163)**
380 Madison Ave., New York 17, N.Y.
Stauffer-Temescal Co., 1201 S 47th St., Richmond, Calif.
Staver Co., Inc., 49 N Saxon Ave., Bay Shore, N.Y.
Stearns-Roger Mfg. Co., P.O. Box 5370, Denver 17, Colo.
Steel Fabricators Co., 1252-B Spruce St., Cleveland 13, Ohio
Steel Heddle Mfg. Co., 2100 Wallegheny Ave., Philadelphia 32, Pa.
Steel Improvement and Forge Co., 970 E 64th St., Cleveland, Ohio
Steel Industries, Inc., 907 Louise Ave., Crawfordsville, Ind.
Steel Protection & Chemical Co., Mooresville, Ind.
Steel Shot Producers, Inc., 4389 Harrison St., Pittsburgh 1, Pa.
Steel, R. & Sons, Inc., 42-21 9th St., Long Island City 1, N.Y.
Steelcote Mfg. Co., 3418 Gratiot St., St. Louis 3, Mo.
**Steere Enterprises, Inc. (Ad p 363)**
422 S Broadway, Akron 8, Ohio
Steinen, William Mfg. Co., 43 Bruen St., Newark 5, N.J.
Stella Products Corp., 66 Okner Pky., Livingston, N.J.
Stenman, Bror F., West St., Auburn, Mass.
Sterling Alderfer Co., 3850 Granger Rd., Akron 13, Ohio
Sterling Aluminum Products, Inc., 2600 N 3rd St., St. Charles, Mo.
Sterling Bolt Co., 363 W Erie St., Chicago 6, Ill.
Sterling Brass Foundry, Inc., 1640 Sterling Ave., Elkhart, Ind.
Sterling Die Casting Co., 743 39th St., Brooklyn 32, N.Y.
Sterling Foundry Co., 8 Wallace St., Sterling, Ill.
Sterling Models, Belfield & Wister Sts., Philadelphia 44, Pa.
Sterling Molders, Inc., 277 Military Rd., Buffalo 7, N.Y.
Sterrit-Thomas Foundry Co., 32nd & Smallman St., Pittsburgh 1, Pa.
Stevens, Frederic B., Inc., 1800 18th St., Detroit, Mich.
Stevens, J.P. & Co., Inc., 1460 Broadway, New York 36, N.Y.
Steward, D.M. Mfg. Co., E 36th St., Chattanooga, Tenn.
Stewart-Warner Corp., Stewart Die Casting Div., 4535 W Fullerton Ave., Chicago 39, Ill.
Stillman Rubber Co., 5811 Marilyn Ave., Culver City, Calif.
Stillman White Foundry Co., Inc., 42 Dodge St., Providence, R.I.
Stimpson, Edwin B. Co., Inc., 70 Franklin Ave., Brooklyn 5, N.Y.
Stirrup Metal Products Corp., 215 Emmet St., Newark 5, N.J.
Stockwell Rubber Co., Inc., 1117 Shackamaxon St., Philadelphia 25, Pa.
Stokes, F.J. Corp., 5500 Tabor Rd., Philadelphia 20, Pa.
Stone Straw Corp., Stone Paper Tube Div., 900 Franklin St., NE, Washington 17, D.C.
Stoody Co., Whittier, Calif.
Stover Steel Tank & Mfg. Co., 100 S Hancock Ave., Freeport, Ill.
Stowe-Woodward, Inc., 181 Oak St., Newton 64, Mass.
Stranahan Foil Co., Inc., 100 Wesley St., South Hackensack, N.J.
Strick Plastics Co., Perkasie, Pa.
Strong Steel Foundry Co., 33 Norris St., Buffalo 7, N.Y.
Structural Fibers, Inc., 5th Ave., Chardon, Ohio
Struthers Wells Corp., 30 Rockefeller Plaza, New York 20, N.Y.
Stuart Foundry Co., 138 S Junction St., Detroit 9, Mich.
Studebaker - Packard Corp., Gering Plastics Div., N 7th St. & Monroe Ave., Kenilworth, N.J.
Stulz-Sickles Co., 929-939 Julia St., Elizabeth, N.J.
Subax, Inc., Fairmount Plant, Hackensack, N.J.
Sun Chemical Corp., 10th St. & 44th Ave., Long Island City 1, N.Y.
Electro Chemical Corp., 113 E Centre St., Nutley 10, N.J.
Horn, A.C. Co., Inc., 750 3rd Ave., New York 17, N.Y.
Sun Rubber Co., 366 Fairview Ave., Barberton, Ohio
Sun Steel Co., Special Products Div., 1700 W 74th Pl., Chicago 36, Ill.
Sun Tube Corp., 181 Long Ave., Hillside, N.J.
Sunlite Plastics, Inc., 1506 W Pierce St., Milwaukee, Wis.
Superb Light Alloys, Inc., Allen Blvd., Farmingdale, N.Y.
Superior Carbon Products, Inc., 9115 George Ave., Cleveland 5, Ohio
Superior Die Casting Co., 1001 London Rd., Cleveland 10, Ohio
Superior Drawn Steel Co., Beaver Ave., Monaca, Pa.
Superior Foundry, Inc., 3542 E 71st St., Cleveland 5, Ohio
Superior Industries, Inc., 3786 Oakwood Ave., Youngstown 9, Ohio
Superior Mfg. Co., 13th & Rockland Sts., Philadelphia 41, Pa.
Superior Plastics, Inc., 426 N Oakley Blvd., Chicago 12, Ill.
Superior Plating, Inc., 1064 10th Ave. SE, Minneapolis, Minn.
Superior Spinning & Stamping Co., 4057-63 Fitch Rd., Toledo 13, Ohio
Superior Steel Corp., Carnegie, Pa.
Superior Steel & Malleable Castings Co., Benton Harbor, Mich.
**Superior Tube Co. (Ad pp 414-415)**
Box 191, Norristown, Pa.
Superior-Pacific Galvanizing Co., 1711 E 61st St., Los Angeles 1, Calif.
Supreme Industrial Products Co., 367 N Karlov Ave., Chicago 24, Ill.
Surprenant Mfg. Co., 199 Washington St., Boston 8, Mass.
Swan Rubber Co., 436 E Mansfield St., Bucyrus, Ohio
Swayne-Robinson & Co., 210 Main St., Richmond, Ind.
Swedish Crucible Steel Co., 8801 Conant Ave., Detroit 11, Mich.
**Swedlow, Inc. (Ad p 263)**
6986 Bandini Blvd., Los Angeles, Calif.
Kevinite Div., 394 N Meridian Rd., Youngstown 9, Ohio
Swepco Tube Corp., 1 Clifton Blvd., Clifton, N.J.
Swett, A.L. Iron Works, 172 Glenwood Ave., Medina, N.Y.
Swift & Co., Adhesive Products Dept., 4115 Packers Ave., Chicago 9, Ill.
Sylvan Plastics Inc., 1617 Pennsylvania Ave., Philadelphia 3, Pa.
Sylvania Electric Products, Inc., 1740 Broadway, New York 19, N.Y.
**Chemical & Metallurgical Div. (Ad p 153)**
Towanda, Pa.
Parts Div., Warren, Pa.
Sylvester & Co., 17706 Miles Ave., Cleveland 28, Ohio
Symington-Gould Corp., Depew, N.Y.
Synco Resins, Inc., Henry St., Bethel, Conn.
**Synthane Corp. (Ad p 234)**
River Oaks, Pa.

## t

Tallman-McCluskey Fabrics Co., 236 E Monroe, Kirkwood 22, Mo.
Taylor & Co., Inc., 680 Morgan Ave., Brooklyn 22, N.Y.
Taylor & Boggis Foundry, 1290 E 53rd St., Cleveland, Ohio
**Taylor Fibre Co. (Ad p 246)**
Box 471, Norristown, Pa.
Taylor Forge & Pipe Works, P.O. Box 485, Chicago 90, Ill.
Techalloy Co., Inc., Rte. 113, Rahns 5, Pa.
**Technic, Inc. (Ad p 352)**
39 Snow St., Providence 3, R.I.
Technical Ply-Woods Sales, 6756 Crandon Ave., Chicago 49, Ill.
Technical Specialties Co., 415 Concord Ave., New York 55, N.Y.
Technical Tape Corp., 240 North Ave., New Rochelle, N.Y.
Teiner, Roland Co., Inc., 134 Tremont St., Everett 49, Mass.
Temco, Inc., 4101 Charlotte Ave., Nashville, Tenn.
Terre Haute Bronze & Brass Foundry, 1114 Sycamore St., Terre Haute, Ind.
Terre Haute Malleable & Mfg. Corp., 2030 N 19th St., Terre Haute, Ind.
Testor Chemical Co., 600 Buckbee, Rockford, Ill.
Texas Aluminum Co., Inc., 512 Mercantile Securities Bldg., Dallas, Tex.
Texas Foundries, Inc., P.O. Box 180, Lufkin, Tex.
Texas Glass Fiber Corp., 147 Island Grove Rd., Grandview, Tex.
**Texas Instruments, Inc., Metals & Controls Div. (Ad p 465)**
34 Forest St., Attleboro, Mass.
Texas Steel Co., 3901 Hemphill St., Fort Worth 9, Tex.
Texas-U.S. Chemical Co., P.O. Box 667, Port Neches, Tex.
Texstar Corp., Texstar Plastics Div., 1400 Henderson, Fort Worth 1, Tex.
Textile Shield Co., Inc., 1 Groton St., Lawrence, Mass.
Textron, Inc., 50 S Main, Providence, R.I.
Burkart, F. Mfg. Co., 4900 N 2nd St., St. Louis 7, Mo.
Campbell, Wyant & Cannon Foundry Co., Henry St., Muskegon, Mich.
Textron Metals Co., 39 James St., Girard, Ohio
Thalco, 765 S Harvard Blvd., Los Angeles, Calif.
Thatcher Glass Mfg. Co., Inc., McKee Div., Bullitt Ave., Jeannette, Pa.
Thermal American Fused Quartz Co., 15-19 Salem St., Dover, N.J.
Thermal Refractories Corp., 4501 Dell Ave., North Bergen, N.J.
Thinsheet Metals Co., 271-TR Railroad Hill St., Waterbury 20, Conn.
Thiokol Chemical Corp., 780 N Clinton Ave., Trenton 7, N.J.
Thombert, Inc., 316 E 7th St., N, Newton, Iowa
Thompson and Co., 1085 Allegheny Ave., Oakmont, Pa.
Thompson, H. I. Fiber Glass Co., 1733 Cordova St., Los Angeles 7, Calif.
Thompson Industries, Inc., Manhasset, N.Y.
Thompson Pipe & Steel Co., 3001 Larimer St., P.O. Box 2852, Denver 1, Colo.
Thompson Products, Inc., 23555 Euclid Ave., Cleveland 17, Ohio
Light Metals Div., 2269 Ashland Rd., Cleveland, Ohio
Kolcast Industries Div., P.O. Box 250, Minerva, Ohio
Valve Div., 1455 E 185th St., Cleveland 10, Ohio
Thompson, K.W. Tool Co., 20 Dexton Ave., New Hyde Park, N.Y.
Thompson Wire Co., 41 Mildred Ave., Boston 26, Mass.
Thompson-Bremer & Co., 228 N La Salle St., Chicago 1, Ill.
Thomson, Judson L. Mfg. Co., Sawyer Rd., Waltham, Mass.
Thys Co., 6900 Folsom Blvd., Sacramento 19, Calif.
Tiarco Corp., Box 766, Clark, N.J.
Tickle, Arthur Engineering Works, Inc., 21 Delevan St., Brooklyn 31, N.Y.
Al-Fin Div., 21 Delevan St., Brooklyn 31, N.Y.
Timber Products Co., P.O. Box 1032, Medford, Ore.
Timken Roller Bearing Co., Steel & Tube Div., 1835 Dueber Ave., SW Canton 6, Ohio
Tingley Rubber Corp., 903 Ross St., Rahway, N.J.
Tinnerman Products, Inc., Dept. 16, P O Box 6688, Cleveland 1, Ohio
Titan Metal Mfg. Co., Bellefonte, Pa.
Titanium Metals Corp. of America, 233 Broadway, New York 7, N.Y.
Titchener, E. H. & Co., 67 Clinton St., Binghamton, N.Y.
Toepfer & Sons, Inc., 6667 N Teutonia Ave., Milwaukee 9, Wis.
Toledo Industrial Rubber Co., 2238 Smead Ave., Toledo 6, Ohio

***In contacting suppliers, please mention the Materials Selector Issue***

Toledo Stamping & Mfg. Co., 99 Fearing Blvd., Toledo 7, Ohio
Tompkins Products, 1040 W Grand Blvd., Detroit 8, Mich.
Tool & Mfg. Co., Inc., P.O. Box 10344, Pittsburgh 34, Pa.
Topeka Foundry & Iron Works Co., Inc., 300-324 Jackson St., Topeka, Kan.
Torngren, C.W. Co., Inc., 236 Pearl St., Somerville 45, Mass.
Torrington Co., 59 Field St., Torrington, Conn.
Tousey Varnish Co., 520 W 25th St., Chicago 16, Ill.
Tower Grove Foundry, 4438 Hunt Ave., St. Louis 10, Mo.
Townsend Co., Engineered Fasteners Div., P.O. Box 71, Ellwood City, Pa.
**Tovad Corp. (Ad p 260)**
Plant Blvd., Latrobe, Pa.
Trane Co., 206 Cameron Ave., La-Crosse Wis
Transition Metals & Chemicals, Inc., U.S. Magnesium Div., Wallkill, N.Y.
Transue & Williams Steel Forging Corp., 562 W Ely St., Alliance Ohio
Trenton Brass Co., 621 Prospect St., Trenton N.J
Trenton Pipe Nipple Co., 626 Brunswick Ave., Trenton 8, N.J.
Triangle Conduit & Cable Co., Inc., P.O. Box 711, New Brunswick, N.J.
Triangle Stamping Co. 5101 Carnegie Ave., Cleveland 3, Ohio
Trigon Specialties Corp., 1005 S Lafayette Blvd., South Bend 18, Ind.
Trim Alloys, Inc., 30-40 W 3rd St., Boston 27, Mass.
Tri-Point Mfg. & Developing Co., 171 I. U. Willets Rd., Albertson, L.I., N.Y.
Tri-State Plastic Molding Co., 505 4th St., Henderson, Ky.
Trojan Steel Co., P.O. Box 2426, Charleston 29, W. Va.
Trostel, Albert Packings, Ltd., Lake Geneva, Wis.
**Troy Blanket Mills (Ad p 327)**
200 Madison Ave., New York, N.Y.
Truche Leather Co., Peabody, Mass.
True Alloys, Inc., 284 S Summit St., Detroit 9, Mich.
Tube Distributors Co., Inc., 1415 Kellum Pl., Garden City, N.Y.
Tube Methods, Inc., Depot & Rambo Sts., Bridgeport, Pa.
Tube Reducing Corp., 520 Main Ave., Wallington, N.J.
Tube Turns Plastics, Inc., 2929 Magazine St., Louisville 11, Ky.
Tubular Rivet & Stud Co., Weston Ave., Quincy 70, Mass.
Tuff Clad, Inc., W Oak St. Extension, Kent, Ohio
Turco Products, Inc., 6135 S. Central Ave., Los Angeles 1, Calif.
Turner Halsey Co., 40 Worth St., New York 13, N.Y
Turner & Seymour Mfg. Co., Lawton St., Torrington, Conn.
**Twin City Die Castings Co. (Ad p 418)**
Talmadge & 33rd Aves., SE, Minneapolis 14, Minn.
Twitchell, E. W., Inc., 2806 N 3rd St., Philadelphia 33, Pa.
Tyer Rubber Co., Andover, Mass.
Tyler, W.S. Co., 3615 Superior Ave., Cleveland 14, Ohio

## U

UBS Chemical Corp., 491 Main St., Cambridge 43, Mass.
Uddeholm Co. of America, Inc., 155 E 44th St., New York 17, N.Y.
Udylite Corp., 1651 Grand Blvd., Detroit 11, Mich.
Ulbrich Stainless Steels Corp., Old Colony Rd., Wallingford, Conn.
Ullmann, Inc., 4305 N 127th St., Butler, Wis.
Uniform Tubes, Inc., Level & School Rds., Collegeville 2, Pa.
Union Asbestos & Rubber Co., 1111 W Perry St., Bloomington, Ill.
Union Carbide Corp., 270 Park Ave., New York 17, N.Y.
Haynes Stellite Co. Div., 1020 W Park Ave., Kokomo, Ind.
Linde Co. Div., 270 Park Ave., New York 17, N.Y.
**National Carbon Co. (Ad p 307)**
270 Park Ave., New York 17, N.Y.
**Silicones Div. (Ad p 277)**
270 Park Ave., New York 17, N.Y.
Union Carbide Chemicals Co., Textile Fibers Dept., 270 Park Ave., New York 17, N.Y.
**Union Carbide Metals Co. (Ad p 181)**
270 Park Ave., New York 17, N.Y.
**Union Carbide Plastics Co. Div. (Ad p 257)**
270 Park Ave., New York 17, N.Y.
Visking Co. Div., 6733 W 65th St., Chicago 38, Ill.
Union Chemical Corp., 410 Freylinghuysen Ave., Newark 5, N.J.
Union Forging Co., 500 North St., Endicott, N.Y.
Union Iron Works, P.O. Box 2135, Spokane, Wash.
Union Paste Co., 1605 Hyde Park Ave., Hyde Park 36, Mass.
Union Screw & Mfg. Co., Box 25, Imperial, Pa.
Union Spring & Mfg. Co., 2nd Ave. & 8th St., New Kensington, Pa.
Union Steel Corp., Stanley Terrace, Union, N.J.
Union Tank Car Co., 228 N LaSalle, Chicago, Ill.
Graver Tank & Mfg. Co. Div., 4809 Tod Ave., East Chicago, Ind.
Unique Wire Weaving Co., Inc., 276 Ramset Ave., Hillside, N.J.
**Unicast Corp. (Ad p 467)**
Water Works Dr., Toledo 9, Ohio
United Carbon Products Co., 1310 N Madison St., Bay City, Mich.
United Cork Cos., 15 Central Ave., Kearney, N.J.
United Forge Co., 277 Dubois, Detroit 7, Mich.
United International Research, Inc., 38-15 30th St., Long Island City 1, N.Y.
United Metal Products Corp., 8101 Lyndon Ave., Detroit 38, Mich.
United Mineral & Chemical Corp., 16 Hudson St., New York 13, N.Y.
United Refining & Smelting Co., 2920 W Carroll Ave., Chicago 12, Ill.
United Rubber & Chemical Co., P.O. Box 149, Baytown, Tex.
United Screw & Bolt Corp., 2513 W Cullerton Ave., Chicago 8, Ill.
United Shoe Machinery Corp., 140 Federal St., Boston 7, Mass.
United Sintered Alloys, St. James, L.I., N.Y.
United Smelting & Aluminum Co., Inc., P.O. Box 1910, New Haven 9, Conn.
U.S. Bronze Powder Works, Inc., Flemington, N.J.
U.S. Ceramic Tile Co., Sparta Mfg. Co., Dover, Ohio
U.S. Challenge & Challenge Co., 1441 N Kingsburg St., Chicago 22, Ill.
U.S. Extrusions Corp., 120 Old Broadway, Garden City Park, N.Y.
U.S. Flexible Tubing Co., Bartlett, Ill.
U.S. Gasket & Shim Co., 2743 2nd St., Cuyahoga Falls, Ohio
U.S. Gypsum Co., 300 W Adams St., Chicago 6, Ill.
**U.S. Magnet & Alloy Corp. (Ad p 420)**
266 Glenwood Ave., Bloomfield, N.J.
U.S. Metal Products Co., P.O. Box 1067, Erie, Pa.
U.S. Mica Co., Inc., 1525 Circle Ave., Forest Park, Ill.
U.S. Pipe and Foundry Co., 3300 1st Ave. N, Birmingham 3, Ala.
U.S. Plywood Corp., 55 W 44th St., New York 36, N.Y.
U.S. Polymeric Chemicals, Inc., Box 546, Stamford, Conn.
U. S. Reduction Co., Chicago Ave. & Melville St., East Chicago, Ind.
U. S. Rubber Co., 1230 Ave. of the Americas, New York 20, N.Y.
Footwear Div., 2638 Pulaski Rd., Chicago 39, Ill.
**Kem-Blo Dept. (Ad p 250)**
Naugatuck, Conn.
Mechanical Goods Div., 4300 New Haven Ave., Fort Wayne, Ind.
**Naugatuck Chemical Div. (Ad p 247)**
Elm St., Naugatuck, Conn.
Textile Div., 1230 Ave. of the Americas, New York 20, N.Y.
U. S. Smelting, Refining & Mining Co., 62 William St., New York, N.Y.
U.S. Steel Corp., 525 William Penn Pl., Pittsburgh 30, Pa.
**American Steel & Wire Div. (Ad pp 90-91)**
Rockefeller Bldg., Cleveland 13, Ohio
Columbia-Geneva Steel Div., 120 Montgomery St., San Francisco 6, Calif.
**National Tube Div., 525 William Penn Pl., Pittsburgh 30, Pa.**
Tennessee Coal and Iron Div., P.O. Box 599, Fairfield, Ala.
United States Steel Supply Div., 208 S La Salle St., Chicago 4.
U. S. Stoneware Co., P.O. Box 350, Akron 9, Ohio
Alite Div., P.O. Box 119, Orrville, Ohio
**Colonial Rubber Co. Div. (Ad p 441)**
706 Oakwood St., Ravenna, Ohio
**Conneaut Rubber & Plastics Co. Div. (Ad p 447)**
P.O. Box 621, Conneaut, Ohio
U.S. Valve & Mfg. Co., 256 E Grand Ave., South San Francisco, Calif.
United Wire & Supply Corp., 1497 Elmwood Ave., Providence 7, R.I.
United-Carr Fastener Corp., 31 Ames St., Cambridge 42, Mass.
New England Tape Co. Div., 30 Tower St., Hudson, Mass.
Unity Machine & Tool Corp., 2727 E Westmoreland St., Philadelphia 34, Pa.
Universal Castings Corp., 5821 W 66th St., Chicago 38, Ill.
Universal Converting Corp., 1125 County St., New Bedford, Mass.
Universal Unlimited, Inc., Pratt Oval, Glen Cove, N.Y.
Universal-Cyclops Steel Corp., Bridgeville, Pa.
Empire-Reeves Steel Div., Bridgeville, Pa.
University of Tennessee, Dept of Chemistry, University Sta., Knoxville 16, Tenn.
Uniworld Research Corp. of America, 9802 Euclid Ave., Cleveland 6, Ohio
Upson Co., Stevens St., Lockport, N.Y.
Urrite Plastics Fabricators, 4740-2 S Durfee Rd., Pico-Rivera, Calif.
Utica Drop Forge & Tool Co., 2409-15 Whitesboro St., Utica 4, N.Y.
Utica General Jobbing Foundry, Inc., 1801 Foundry St., Utica 3, N.Y.
Utica Radiator Corp., Dwyer Ave., Utica, N.Y.
Utility Mfg. Co., 2443 Boston Rd., North Wilbraham, Mass.
Utility Steel Foundry, 3320 E Slauson, Vernon, Calif.

## V

Valley Iron Works, 81 E Water St., St. Paul 7, Minn.
Valley Steel Casting Co., Foot of 11th St., Bay City, Mich.
Valley-National Corp., Clark St., Millidale, Conn.
**Vanadium Corp. of America (Ad p 86)**
420 Lexington Ave., New York 17, N.Y.
Vanadium-Alloys Steel Co., Latrobe, Pa.
Anchor Drawn Steel Co., Latrobe, Pa.
Colonial Steel Div., Monaca, Pa.
Metal Forming Corp. Div., 1937 Sterling Ave., Elkart, Ind.
Vanamatic Co., 204 S Jefferson St., Delphos, Ohio
Van der Horst Corp., Olean, N.Y.
Van Dorn Iron Works Co., Colonial Plastics Div., 2685 E 79th St., Cleveland 4, Ohio
Van Huffell Tube Corp., Larchmont Ave., NE, Warren, Ohio
Van Pelt Corp., Service Steel Div., Box 532, Detroit 32, Mich.
Van Valkenburg, L.D. Co., Box 190, Holyoke, Mass.
Varcum Chemical Corp., P.O. Box 476, Niagara Falls, N.Y.
Varflex Corp., 512 W Court St., Rome, N.Y.
Variety Stamping Corp., 12695 Elmwood Ave., Cleveland 11, Ohio
Vascoloy-Ramet Corp., 800 Market St., Waukegan, Ill.
Veeder-Root Inc., 70 Sargeant St., Hartford 2, Conn.
Vellumoid Co., 54 Rockdale St., Worcester 6, Mass.
Velcro Sales Corp., 681 5th Ave., New York 22, N.Y.
Veremere, E.A. Inc., 11623 S Broadway, Los Angeles 61, Calif
Victor Equipment Co., 844 Folsom St., San Francisco 7, Calif.
Victor Mfg. & Gasket Co., 5750 W Roosevelt Rd., Chicago 50, Ill.
Victor Steel Products Corp., 1175 Leggett Ave., New York 59, N.Y.
Victory Plastics Co., 81 Apsley St., Hudson, Mass.
Viking Copper Tube Co., 16700 St. Clair Ave., Cleveland, Ohio
Viking Pump Co., George & Wyth Sts., Cedar Falls 1, Iowa
Viplax Products Corp., 408 E Warren St., Beverly, N.J.
Vogt Mfg. Corp., 100 Fernwood Ave., Rochester, N.Y.
Volco Brass & Copper Co., Kenilworth, N.J.
Volkert Stampings, Inc., 222-34 96th Ave., Queens Village 29, N.Y.
Vollrath Co., Contract Div., 1236 N 18th St., Sheboygan, Wis.
Vulcan Foundry Co., Oakland, Calif.
Vulcan Iron Works, 730 S Main St., Wilkes Barre, Pa.
Vulcan Mfg. Co., Box 22, Cincinnati 22, Ohio
Vulcan Metal Products, Inc., 2801 6th Ave., S, Birmingham, Ala.
Vulcan Rail & Construction Co., 59-30 54th St., Maspeth, N.Y.
Vulcanized Rubber & Plastics Co., 5 S Pennsylvania Ave., Morrisville, Pa.

## W

W. F. Mfg. Co., 1509 Gardena Ave., Glendale 4, Calif.
WLS Stamping Co., 3292 E 80th St., Cleveland 4, Ohio

Wabash Metal Products Co., Inc., P.O. Box 305, Wabash, Ind.
Wagner Malleable Iron Co., 1275 E Sangamon, Decatur, Ill.
Wagner, E.R. Mfg. Co., 4611 N 32nd St., Milwaukee 9, Wis.
Wagner Plastic Corp., Rte. 88, Lakewood, N.J.
Wagner Specialty Co., 647 Dodge St., Burlington, Wis.
**Wah Chang Corp. (Ad p 164)**
233 Broadway, New York 7, N.Y.
**Walmet Alloys Co. (Ad p 82)**
1999 Guoin St., Detroit 7, Mich.
Wakefield Bearing Corp., 45 Foundry St., Wakefield, Mass.
Waldes Kohinoor, Inc., 47-16 Austel Pl., Long Island City 1, N.Y.
**Waldman, Jos. & Sons, Epoxy Products Div. (Ad p 499)**
137 Coit St., Irvington, N.J.
Walker Forge, Inc., 2000 17th St., Racine, Wis.
**Wall Colmonoy Corp., Stainless Process Div. (Ad p 498)**
19345 John R. St., Detroit 3, Mich.
Wall, P. Mfg. Co., Erie St., Grove City, Pa.
Wall Tube & Metal Products Co., P.O. Box 330, Newport, Tenn.
Wallace Supplies Mfg. Co., Wallace Tube Co. Div., 1300 Diversey Pkwy., Chicago 14, Ill.
Wallingford Steel Co., 80 Valley St., Wallingford, Conn.
Wal-Mar Corp., 2800 Bernice Rd., Lansing, Ill.
Walrod Machine Products, 5225 SE 7th Ave., Portland 2, Ore.
Waltham Foundry Co., 71 Felton St., Waltham 54, Mass.
Ward, H.H. Co., 4th & Engle Sts., Chester, Pa.
Warner Mfg. Corp., 265 Watsessing Ave., Bloomfield, N.J.
Warren Belting Co., 33 Arctic St., Worcester 8, Mass.
Warren Bros. Roads Co., 32 Potter St., Cambridge 42, Mass.
Wasco Products, Inc., 5 Bay State Rd., Cambridge 38, Mass.
Washburn Wire Co., Phillipsdale Div., Bourne Ave., Phillipsdale, R.I.
Washington Iron Works, 1500 6th Ave., S, Seattle 4, Wash.
Washington Mfg. Co., Inc., P.O. Box 370, Washington, Iowa
Washington Steel Corp., Washington, Pa.
Waterbury Buckle Co., 952 S Main St., Waterbury 20, Conn.
Waterbury Cos., Inc., P.O. Box 1032, Waterbury, Conn.
Waterbury Pressed Metal Co., 300 Chase Ave., Waterbury 14, Conn.
Waterbury Rolling Mills, Inc., Box 550, Waterbury 20, Conn.
Waterman Industries, Inc., 515 S. G St., Exeter, Calif.
Watertown Mfg. Co., Echo Lake Rd., Watertown, Conn.
Watson-Standard Co., 225 Galveston Ave., Pittsburgh 12, Pa.
**Waukesha Foundry Co. (Ad p 451)**
Lincoln Ave., Waukesha, Wis.
Wayne Agricultural Works, Inc., Goldsboro, N.C.
Wayne Chemical Products Co., 9470 Copland Ave., Detroit 17, Mich.
Wayne Foundry & Stamping Co., 3100 Hubbard St., Detroit 10, Mich.
Weatherhead Co., 128 W Washington Blvd., Fort Wayne 1, Ind.
Weber-Knapp Co., 441 Chandler St., Jamestown, N.Y.
Webster Mfg., Inc., 1100 W Davis St., Tiffin, Ohio
Weckesser Co., 5713 Northwest Hwy., Chicago 46, Ill.
Wedler Bros., Inc., 1535 E 38th St., Cleveland 14, Ohio
Weiskittel, Harry C. Co., Inc., 4901 Pulaski Hwy., Baltimore 24, Md.
Welding Apparatus Co., 2750 W Van Buren St., Chicago 12, Ill.
Wellington Sears Co., 111 W 40th St., New York 18, N.Y.
Wellman, S.K. Co., 20 Egbert Rd., Bedford, Ohio
Wellman Bronze and Aluminum Co., 9401 Woodland Ave., Cleveland 4, Ohio
Wells, A.H. & Co., Inc., 100 E Aurora St., Waterbury, Conn.
Wells Aluminum Corp., 50 Henry St., North Liberty, Ind.
Wellsville Fire Brick Co., Wellsville, Mo.
**Werner, R.D. Co., Inc. (Ad p 437**
P.O. Box 580, Greenville, Pa.
Werner Foundry & Machine Co., 8th St. & Reading R.R., Lansdale, Pa.
Wesbar Stamping Corp., West Bend, Wis.
Wesco Spring Co., 4501 S Knox Ave., Chicago 32, Ill.
Wessels Co., 1625 E Euclid Ave., Detroit 11, Mich.
West Haven Foundry Co., 27 Kimberly Ave., West Haven, Conn.
West Irving Die Casting Co., 240 S Evergreen St., Bensenville, Ill.
West Steel Casting Co., 1679 Collamer Rd., Cleveland 10, Ohio
West Virginia Malleable Iron Co., Point Pleasant, W. Va.
West Virginia Pulp & Paper Co., 230 Park Ave., New York 17, N.Y.
Western Automatic Machine Screw Co., 377 Woodland Ave., Elyria, Ohio
Western Coating Co., Box 598, Oakridge Sta., Royal Oak 3, Mich.
Western Felt Works, 4115 W Ogden Ave., Chicago 23, Ill.
**Acadia Synthetic Products Div. (Ad p 412)**
4115 Ogden Ave., Chicago 23, Ill.
Western Foundry & Machine Works, Inc., 201 Jefferson St., Topeka, Kan.
Western Iron & Foundry Co., Inc., 702 E 2nd St., Wichita 2, Kan.
Western Machine Co., 180 W Holt Ave., Milwaukee 7, Wis.
Western Plastics Corp., 1515 W 2nd St., Hastings, Neb.
Western Plastics Corp., 3110 Ruston Way, Tacoma 2, Wash.
Western Textile Products Co., 2131 Hickory St., St. Louis 4, Mo.
Western Tool & Die Works, 421 NW 3rd Ave., Portland 9, Ore.
Westinghouse Electric Corp., 101 Liberty Ave., Gateway Center, Pittsburgh, Pa.
Materials Mfg. Dept., Blairsville, Pa.
Micarta Div., Hampton, S.C.
Westlake Plastics Co., 145 W Lenni Rd., Lenni Mills, Pa.
Westland Die Casting, Inc., 714 Roberta St., Glendale 1, Calif.
Westlectric Castings, Inc., 2040 S Camfield Ave., Los Angeles 22, Calif.
Westmoreland Malleable Iron Co., Westmoreland, N.Y.
Weyerhaeuser Timber Co., Silvatek Products Div., Tacoma Bldg., Tacoma 1, Wash.
Wheatland Tube Co., Bankers Securities Bldg., Philadelphia 7, Pa.
Wheaton Die Casting Corp., N 10th St., Millville, N.J.
Wheeler, C.H. Mfg. Co., Wheelerweld Div., Ambler, Pa.
Wheeling Corrugating Co., Wheeling, W. Va.
Wheeling Steel Corp., 1134-40 Market St., Wheeling, W. Va.
Wheelock, Lovejoy & Co., Inc., 128 Sidney St., Cambridge 39, Mass.
Wheland Co., 27th & Broad Sts., Chattanooga 20, Tenn.
Whitaker Metals Corp., 1301 Burlington St., North Kansas City 16, Mo.
White Metal Rolling & Stamping Corp., 80 Moultrie St., Brooklyn 22, N.Y.
White Sewing Machine Corp., Apex Reinforced Plastics Div., Elm & Washington Sts., Cleveland 13, Ohio
Whitehead Metal Products Co., Inc., 303 W 10th St., New York 14, N.Y.
Whitfield Chemical Co., 14225 Schaefer Hwy., Detroit 27, Mich.
Whitso, Inc., 9330 Byron St., Schiller Park, Ill.
Whyte, Oliver Co., Inc., 115 4th Ave., New York 3, N.Y.
Wickes Corp., U. S. Graphite Co. Div., 1621 Holland Ave., Saginaw, Mich.
Wickwire Bros., Inc., 189 Main St., Cortland, N.Y.
Wilcox Forging Corp., Chestnut & Allen Sts., Mechanicsburg, Pa.
Wildberg Bros. Smelting & Refining Co., 742 Market St., San Francisco 2, Calif.
Wilde Drop Forge & Tool Co., Inc., 2938 Fairmount Ave., Kansas City 8, Mo.
Wilde Tool Co., Inc., 13th & Pottawatomie St., Hiawatha, Kan.
Wilder Mfg. Co., Inc., 1143 Terven Ave., Salinas, Calif.
Willamette Iron and Steel Co., 2800 NW Front Ave., Portland 10, Ore.
Williams, A.C. Co., Ravenna, Ohio
Williams, F.B. Co., 507 E Pershing Rd., Chicago 53, Ill.
Williams, J.H. & Co., 400 Vulcan St., Buffalo 7, N.Y.
Williams Gold Refining Co., Inc., 2978 Main St., Buffalo 14, N.Y.
Williams, H.E. Products Co., 106 S Main St., Carthage, Mo.
Williams, E.A. & Son, 325 Washington Ave., Carlstadt, N.J.
**Williams-Bowman Rubber Co. (Ad p 276)**
1949 S 54th Ave., Cicero 50, Ill.
Williamson Adhesives, Inc., 8220 Kimball Ave., Skokie, Ill.
Wilmington Fibre Specialty Co., New Castle, Del.
Wilson Steel & Wire Co., 4840 S Western Ave., Chicago 9, Ill.
Wilson-Hurd Mfg. Co., Inc., Lines St., Wausau, Wis.
Winner Mfg. Co., Inc., P.O. Box 390, West Trenton, N.J.
Winsorth Co., Inc., 43 Oak St., Delawanna, N.J.
Winters Foundry & Machine Co., Inc., 4123 Mahoning Rd., Canton 5, Ohio
Wire and Iron Products, Inc., 1725 16th St., Detroit 16, Mich.
Wirth, Carl & Son, Inc., 1625 Clinton Ave. N, Rochester 17, N.Y.
Wirz, A.H. Inc., 4th & Townsend Sts., Chester, Pa.
Wisconsin Aluminum Foundry Co., Inc., Manitowoc, Wis.
Wisconsin Centrifugal Foundry, Inc., 905 E St. Paul Ave., Waukesha, Wis.
Wisconsin Gasket & Mfg. Co., Granville, Wis.
Wisconsin Porcelain Co., 120 Lincoln St., Sun Prairie, Wis.
Wisconsin Tool & Stamping Co., 9521 W Ainslie St., Schiller Park, Ill.
Witco Chemical Co., 75 E Wacker Dr., Chicago 1, Ill.
Witt Cornice Co., Galvanizing Div., 4454 Steel Pl., Cincinnati 9, Ohio
Wittman, Lawrence & Co., 1395 Marconi Blvd., Copiague, N.Y.
Wollaston Foundry Corp., 24 Hollbrook Rd., Quincy 71, Mass.
Wood, John Co., 4435 S Western Ave., Chicago, Ill.
Wood, John Co., 509 Front Ave., St. Paul 3, Minn.
Wood Conversion Co., 1st National Bank Bldg., St. Paul 1, Minn.
Woodall Industries, Inc., 7635 E McNichols Rd., Detroit 34, Mich.
Woodruff & Edwards, Inc., 119 N State St., Elgin, Ill.
Woolf Aircraft & Products, Inc., 3441 Filbert St., Wayne, Mich.
Worcester Moulded Plastics Co., 14 Hygeia St., Worcester 8, Mass.
Worcester Pressed Steel Co., 101 Barber Ave., Worcester 6, Mass.
Worcester Stamped Metal Co., 9 Hunt St., Worcester, Mass.
World Plastics, 1685 Boone Ave., New York 60, N.Y.
Worth Co., Briggs & Union St., Stevens Point, Wis.
Worthington Corp., 401 Worthington Ave., Harrison, N.J.
Wright Metalcoaters, 255 West St., South Hackensack, N.J.
Wright, Albert, Screw Machine Products, 4032 Hollis St., Oakland 8, Calif.
Wright, G.F. Steel & Wire Co., 243 Stafford St., Worcester 3, Mass.
Wrought Washer Mfg. Co., 2211 S Bay St., Milwaukee 7, Wis.
Wuest Bros., Inc., 924-936 W Hill St., Louisville 8, Ky.
Wyandotte Chemicals Corp., J.B. Ford Div., Wyandotte, Mich.
Wyatt Industries Inc., Plastic & Rubber Div., P.O. Box 3052, Houston 1, Tex.
Wyatt Metal & Boiler Works, Inc., P.O. Box 3032, Houston 1, Tex.
Wycoff Steel Co., Box 1256, Pittsburgh 30, Pa.
Wyman-Gordon Co., 105 Madison St., Worcester 1, Mass.

## x

Xylos Rubber Co., 1300 Emerlie Ave., Akron, Ohio

## y

Yale Rubber Mfg. Co., Henderson St., Sandusky, Mich.
Yale & Towne Mfg. Co., Powdered Metal Products Div., 9335 W. Belmont Ave., Franklin Park, Ill.
**Yardley Plastics Co. (Ad p 466)**
142 Parsons Ave., Columbus, Ohio
York Castings, Inc., 32 Latta Rd., Rochester 12, N.Y.
Young & Greenawalt, 5016 Hohman Ave., Hammond, Ind.
Youngstown Mfg., Inc., 66-76 S Prospect St., Youngstown, Ohio
Youngstown Sheet & Tube Co., P.O. Box 900, Youngstown 1, Ohio
Fibercast Co. Div., P.O. Box 727, Sand Springs, Okla.
Youngstown Welding & Engineering Co., 3800 Oakwood Ave., Youngstown 9, Ohio

## z

Z & H Mfg. Co., 31 Welcher Ave., Peekskill, N.Y.
Zeller Corp., Ft. Wayne Rd., Defiance, Ohio
Zellner Foundry Co., 2088 Scranton Rd., Cleveland 13, Ohio
Zenith Foundry Co., 1501 S 83rd St., West Allis 14, Wis.
Zenith Plastics Co., 1600 W 135th St., Gardena, Calif.
Zirconium Corp. of America, 31501 Solon Rd., Solon, Ohio
Ziv Steel & Wire Co., 2945 W Harrison St., Chicago 12, Ill.
Zolatone Process, Inc., 3411 E 15th St., Los Angeles 23, Calif.
Zophar Mills, Inc., 112 26th St., Brooklyn 32, N.Y

# GET YOUR OWN SELECTOR...

## *the Easy Way*




**For only $3.00 you can get your own copy of M/DE's annual reference issue — the 1961 MATERIALS SELECTOR — plus 12 monthly issues of MATERIALS in Design Engineering.**

You can see right now that M/DE's annual reference issue, the MATERIALS SELECTOR, is packed with the kind of reference data that makes selecting and specifying the right engineering materials, parts or finishes an easier, more efficient task for you. Remember, too, once you become a subscriber to M/DE you'll receive—every month—fast-reading, factual reports on important innovations and developments in metals, nonmetals, forms and finishes.

If you do not subscribe to MATERIALS in Design Engineering and want your own personal copy of the MATERIALS SELECTOR . . . fill in and mail the handy order card. We'll mail the MATERIALS SELECTOR to you, plus 12 monthly issues of MATERIALS in Design Engineering.

*Note: Subscription rates listed on the attached card are for U.S., U.S. Possessions and Canada only. Foreign subscription rates available on request.*

ADVERTISEMENT

**O.K.** Send me my own copy of M/DE's annual reference issue, the **1961 MATERIALS SELECTOR,** *and* enter my subscription to **MATERIALS in Design Engineering** for:



☐ One year—$3.00 ☐ Two years—$5.00

Name ..... Title .....

Firm Name ..... Dept. .....

Address ..... Home? ☐ Yes ☐ No

City ..... Zone .....State .....

Major products made at your plant .....

Other products made at your plant .....

In order to receive the 1961 Materials Selector free with your subscription, this card must be postmarked no later than December 31, 1960.

**NO MONEY NOW — WE'LL BILL YOU LATER**

PRINTED IN U.S.A.

A MESSAGE OF IMPORTANCE

**to:** those of you who want to do the **best job possible** in selecting and using engineering materials in product design and manufacture.


If you now subscribe to **MATERIALS in Design Engineering,** this is your opportunity to give **other** key men on your staff a chance to get this issue of the **MATERIALS SELECTOR.** Give them the card below and ask them to fill it in and mail it to us. The more engineering men in your plant know about selecting and specifying engineering materials, parts and finishes, the easier your own job becomes.

If you are not a subscriber, and have responsibilities involving the selection and application of engineering materials, fill in and mail the card below. We'll enter your subscription to M/DE at once—and send your own copy of the **1961 SELECTOR** right away. But please mail the card today. This offer is good for a limited time only.

**M/DE's Annual Reference Issue —**

***The Materials Selector:***

**Over 400 pages of Valuable Reference Data**




FIRST CLASS
PERMIT NO. 1538
NEW YORK, N. Y.

**BUSINESS REPLY MAIL**
No postage stamp necessary if mailed in the United States

POSTAGE WILL BE PAID BY —

**MATERIALS in Design Engineering**
A Reinhold Publication
430 PARK AVENUE
NEW YORK 22, N. Y.

***Detach Order Card and Mail Today. Offer Good for Limited Time Only.***

# Reader Service

Use these postage-free cards to request:

- **SUPPLIERS' FREE LITERATURE.** Current bulletins are listed with key numbers starting with this page and through page 588.
- **INFORMATION ON ADVERTISED PRODUCTS.** Products advertised in this issue are listed with key numbers starting on page 589.
- **REPRINTS OF M/DE MANUALS AND SPECIAL REPORTS.** These are available for a small charge; see end of this section, page 592.
- **SUBSCRIPTION TO M/DE.** Just check one of the blocks provided at bottom of reply card. Be sure to fill in your job title.

Simply circle the appropriate key numbers on the card and drop it in the mail. Be sure to **print** your name, title, and business address. The extra cards are for your convenience during the rest of the year.

## Suppliers' Literature

To get a fuller description of individual bulletins, consult the appropriate data section using the main contents page inside the front cover.

### IRONS AND STEELS

| | Circle Key No. |
|---|---|
| Boron stainless steel | 9 |
| Chromium-molybdenum-vanadium steel | 28 |
| Electric furnace steels | 8 |
| Galvanized steel | 31 |
| High strength steel | 16, 17 |
| High temperature steels | 25 |
| Manganese steel | 2 |
| Specialty steels | 6 |
| Spring, strip, specialty steels | 23 |
| Stainless steels | 1, 7, 9, 21, 30 |



FIRST CLASS
PERMIT NO. 1538
NEW YORK, N. Y.

**BUSINESS REPLY CARD**
No postage stamp necessary if mailed in the U. S.

POSTAGE WILL BE PAID BY —

MANAGER, READER SERVICE DEPARTMENT 11560

MATERIALS IN DESIGN ENGINEERING
430 PARK AVENUE
NEW YORK 22, N. Y.

**THIS CARD NOT GOOD AFTER SEPTEMBER 1961** 115/60

Name _____ Title _____

Firm _____

Street _____ City _____ Zone _____

State _____

Students and foreign subscribers (other than Canadian), please request literature directly from manufacturers.

| | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 26 | 51 | 76 | 101 | 126 | 151 | 176 | 201 | 226 | 251 | 276 | 301 | 326 | 351 | 376 | 401 | 426 | 451 | 476 | 501 | 526 | 551 | 576 | 601 | 626 | 651 | 676 |
| 2 | 27 | 52 | 77 | 102 | 127 | 152 | 177 | 202 | 227 | 252 | 277 | 302 | 327 | 352 | 377 | 402 | 427 | 452 | 477 | 502 | 527 | 552 | 577 | 602 | 627 | 652 | 677 |
| 3 | 28 | 53 | 78 | 103 | 128 | 153 | 178 | 203 | 228 | 253 | 278 | 303 | 328 | 353 | 378 | 403 | 428 | 453 | 478 | 503 | 528 | 553 | 578 | 603 | 628 | 653 | 678 |
| 4 | 29 | 54 | 79 | 104 | 129 | 154 | 179 | 204 | 229 | 254 | 279 | 304 | 329 | 354 | 379 | 404 | 429 | 454 | 479 | 504 | 529 | 554 | 579 | 604 | 629 | 654 | 679 |
| 5 | 30 | 55 | 80 | 105 | 130 | 155 | 180 | 205 | 230 | 255 | 280 | 305 | 330 | 355 | 380 | 405 | 430 | 455 | 480 | 505 | 530 | 555 | 580 | 605 | 630 | 655 | 680 |
| 6 | 31 | 56 | 81 | 106 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 | 531 | 556 | 581 | 606 | 631 | 656 | 681 |
| 7 | 32 | 57 | 82 | 107 | 132 | 157 | 182 | 207 | 232 | 257 | 282 | 307 | 332 | 357 | 382 | 407 | 432 | 457 | 482 | 507 | 532 | 557 | 582 | 607 | 632 | 657 | 682 |
| 8 | 33 | 58 | 83 | 108 | 133 | 158 | 183 | 208 | 233 | 258 | 283 | 308 | 333 | 358 | 383 | 408 | 433 | 458 | 483 | 508 | 533 | 558 | 583 | 608 | 633 | 658 | 683 |
| 9 | 34 | 59 | 84 | 109 | 134 | 159 | 184 | 209 | 234 | 259 | 284 | 309 | 334 | 359 | 384 | 409 | 434 | 459 | 484 | 509 | 534 | 559 | 584 | 609 | 634 | 659 | 684 |
| 10 | 35 | 60 | 85 | 110 | 135 | 160 | 185 | 210 | 235 | 260 | 285 | 310 | 335 | 360 | 385 | 410 | 435 | 460 | 485 | 510 | 535 | 560 | 585 | 610 | 635 | 660 | 685 |
| 11 | 36 | 61 | 86 | 111 | 136 | 161 | 186 | 211 | 236 | 261 | 286 | 311 | 336 | 361 | 386 | 411 | 436 | 461 | 486 | 511 | 536 | 561 | 586 | 611 | 636 | 661 | 686 |
| 12 | 37 | 62 | 87 | 112 | 137 | 162 | 187 | 212 | 237 | 262 | 287 | 312 | 337 | 362 | 387 | 412 | 437 | 462 | 487 | 512 | 537 | 562 | 587 | 612 | 637 | 662 | 687 |
| 13 | 38 | 63 | 88 | 113 | 138 | 163 | 188 | 213 | 238 | 263 | 288 | 313 | 338 | 363 | 388 | 413 | 438 | 463 | 488 | 513 | 538 | 563 | 588 | 613 | 638 | 663 | 688 |
| 14 | 39 | 64 | 89 | 114 | 139 | 164 | 189 | 214 | 239 | 264 | 289 | 314 | 339 | 364 | 389 | 414 | 439 | 464 | 489 | 514 | 539 | 564 | 589 | 614 | 639 | 664 | 689 |
| 15 | 40 | 65 | 90 | 115 | 140 | 165 | 190 | 215 | 240 | 265 | 290 | 315 | 340 | 365 | 390 | 415 | 440 | 465 | 490 | 515 | 540 | 565 | 590 | 615 | 640 | 665 | 690 |
| 16 | 41 | 66 | 91 | 116 | 141 | 166 | 191 | 216 | 241 | 266 | 291 | 316 | 341 | 366 | 391 | 416 | 441 | 466 | 491 | 516 | 541 | 566 | 591 | 616 | 641 | 666 | 691 |
| 17 | 42 | 67 | 92 | 117 | 142 | 167 | 192 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 | 617 | 642 | 667 | 692 |
| 18 | 43 | 68 | 93 | 118 | 143 | 168 | 193 | 218 | 243 | 268 | 293 | 318 | 343 | 368 | 393 | 418 | 443 | 468 | 493 | 518 | 543 | 568 | 593 | 618 | 643 | 668 | 693 |
| 19 | 44 | 69 | 94 | 119 | 144 | 169 | 194 | 219 | 244 | 269 | 294 | 319 | 344 | 369 | 394 | 419 | 444 | 469 | 494 | 519 | 544 | 569 | 594 | 619 | 644 | 669 | 694 |
| 20 | 45 | 70 | 95 | 120 | 145 | 170 | 195 | 220 | 245 | 270 | 295 | 320 | 345 | 370 | 395 | 420 | 445 | 470 | 495 | 520 | 545 | 570 | 595 | 620 | 645 | 670 | 695 |
| 21 | 46 | 71 | 96 | 121 | 146 | 171 | 196 | 221 | 246 | 271 | 296 | 321 | 346 | 371 | 396 | 421 | 446 | 471 | 496 | 521 | 546 | 571 | 596 | 621 | 646 | 671 | 696 |
| 22 | 47 | 72 | 97 | 122 | 147 | 172 | 197 | 222 | 247 | 272 | 297 | 322 | 347 | 372 | 397 | 422 | 447 | 472 | 497 | 522 | 547 | 572 | 597 | 622 | 647 | 672 | 697 |
| 23 | 48 | 73 | 98 | 123 | 148 | 173 | 198 | 223 | 248 | 273 | 298 | 323 | 348 | 373 | 398 | 423 | 448 | 473 | 498 | 523 | 548 | 573 | 598 | 623 | 648 | 673 | 698 |
| 24 | 49 | 74 | 99 | 124 | 149 | 174 | 199 | 224 | 249 | 274 | 299 | 324 | 349 | 374 | 399 | 424 | 449 | 474 | 499 | 524 | 549 | 574 | 599 | 624 | 649 | 674 | 699 |
| 25 | 50 | 75 | 100 | 125 | 150 | 175 | 200 | 225 | 250 | 275 | 300 | 325 | 350 | 375 | 400 | 425 | 450 | 475 | 500 | 525 | 550 | 575 | 600 | 625 | 650 | 675 | 700 |

I would like to subscribe to Materials in Design Engineering for ☐ 1 year $3.00 ☐ 2 years $5.00

# Reader Service


Stainless steel services ..... 5
Stainless steel specifications ..... 12
Stainless steel wire ..... 14, 27
Steel analyses ..... 15
Steel catalog ..... 24
Steel data ..... 10
Steel plate ..... 18
Steel services ..... 22
Steel strip ..... 20, 26
Superalloys ..... 29
Titanium-bearing stainless steels ..... 11
Tool steels ..... 3, 13
Wrought iron ..... 4
Zinc-coated steel ..... 19


## NONFERROUS METALS


| | Circle Key No. |
|---|---|
| Aluminum alloys, high strength | 34, 47 |
| Aluminum sheet, coils | 44 |
| Aluminum specifications | 46 |
| Beryllium | 37 |
| Beryllium Copper | 35 |
| Brass, aluminum products | 50 |
| Bronze | 40 |
| Cobalt-chromium superalloys | 53 |
| Columbium-base alloys | 65 |
| Copper alloy strip, wire, rod | 60 |
| Copper and brass products | 50 |
| Copper and copper alloys | 55 |
| Copper specifications | 32 |
| Corrosion resistant alloy | 64 |
| Electrical contacts | 43 |
| Electrical resistance alloys | 41, 49 |
| Electronic alloys | 42, 56 |
| Germanium | 63 |
| Indium alloys | 51 |
| Low melting alloys | 39 |
| Magnesium wrought products | 57 |
| Molybdenum metal | 33 |
| Nickel-base superalloys | 38 |
| Platinum, platinum group alloys | 52 |
| Refractory metals | 45 |
| Silver and its alloys | 48 |
| Tantalum | 66 |
| Tantalum-tungsten alloy | 62 |
| Tellurium copper | 36 |
| Thin strip | 61 |
| Tin | 54 |
| Zinc casting alloys | 58 |


## PLASTICS AND RUBBER


| | Circle Key No. |
|---|---|
| ABS resins | 71 |
| Acrylic, stretched | 102 |
| Butyl rubber | 90 |
| Cellular products | 105 |
| Coated fabrics | 77 |
| Electrical resins | 92 |
| Epoxy resins | 84, 91 |
| Extrusions | 95 |
| Hardener for epoxy resins | 75 |
| High temperature laminates | 103 |
| Impregnated materials | 80 |
| Laminates | 82, 85, 86, 95, 100, 104 |
| Mechanical rubber | 109 |
| Moldings, plastics | 74 |
| Molding compounds, plastics | 67, 72 |
| Nylon and acetal resins | 79 |
| Nylon insulation | 83 |
| Phenolics | 96 |
| Plastics materials | 73, 93 |
| Plastics products | 98 |
| Polyester-glass laminates | 76 |
| Polyester, molded | 69 |
| Polyester, resins | 87 |
| Polyethylene, low density | 81 |
| Polypropylene | 70 |
| Polystyrene | 107 |
| Resins, plastics | 89 |


**THIS CARD NOT GOOD AFTER SEPTEMBER 1961** 115/60

Name _____ Title _____

Firm _____

Street _____ City _____ Zone _____

State _____

Students and foreign subscribers (other than Canadian), please request literature directly from manufacturers.

| | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 26 | 51 | 76 | 101 | 126 | 151 | 176 | 201 | 226 | 251 | 276 | 301 | 326 | 351 | 376 | 401 | 426 | 451 | 476 | 501 | 526 | 551 | 576 | 601 | 626 | 651 | 676 |
| 2 | 27 | 52 | 77 | 102 | 127 | 152 | 177 | 202 | 227 | 252 | 277 | 302 | 327 | 352 | 377 | 402 | 427 | 452 | 477 | 502 | 527 | 552 | 577 | 602 | 627 | 652 | 677 |
| 3 | 28 | 53 | 78 | 103 | 128 | 153 | 178 | 203 | 228 | 253 | 278 | 303 | 328 | 353 | 378 | 403 | 428 | 453 | 478 | 503 | 528 | 553 | 578 | 603 | 628 | 653 | 678 |
| 4 | 29 | 54 | 79 | 104 | 129 | 154 | 179 | 204 | 229 | 254 | 279 | 304 | 329 | 354 | 379 | 404 | 429 | 454 | 479 | 504 | 529 | 554 | 579 | 604 | 629 | 654 | 679 |
| 5 | 30 | 55 | 80 | 105 | 130 | 155 | 180 | 205 | 230 | 255 | 280 | 305 | 330 | 355 | 380 | 405 | 430 | 455 | 480 | 505 | 530 | 555 | 580 | 605 | 630 | 655 | 680 |
| 6 | 31 | 56 | 81 | 106 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 | 531 | 556 | 581 | 606 | 631 | 656 | 681 |
| 7 | 32 | 57 | 82 | 107 | 132 | 157 | 182 | 207 | 232 | 257 | 282 | 307 | 332 | 357 | 382 | 407 | 432 | 457 | 482 | 507 | 532 | 557 | 582 | 607 | 632 | 657 | 682 |
| 8 | 33 | 58 | 83 | 108 | 133 | 158 | 183 | 208 | 233 | 258 | 283 | 308 | 333 | 358 | 383 | 408 | 433 | 458 | 483 | 508 | 533 | 558 | 583 | 608 | 633 | 658 | 683 |
| 9 | 34 | 59 | 84 | 109 | 134 | 159 | 184 | 209 | 234 | 259 | 284 | 309 | 334 | 359 | 384 | 409 | 434 | 459 | 484 | 509 | 534 | 559 | 584 | 609 | 634 | 659 | 684 |
| 10 | 35 | 60 | 85 | 110 | 135 | 160 | 185 | 210 | 235 | 260 | 285 | 310 | 335 | 360 | 385 | 410 | 435 | 460 | 485 | 510 | 535 | 560 | 585 | 610 | 635 | 660 | 685 |
| 11 | 36 | 61 | 86 | 111 | 136 | 161 | 186 | 211 | 236 | 261 | 286 | 311 | 336 | 361 | 386 | 411 | 436 | 461 | 486 | 511 | 536 | 561 | 586 | 611 | 636 | 661 | 686 |
| 12 | 37 | 62 | 87 | 112 | 137 | 162 | 187 | 212 | 237 | 262 | 287 | 312 | 337 | 362 | 387 | 412 | 437 | 462 | 487 | 512 | 537 | 562 | 587 | 612 | 637 | 662 | 687 |
| 13 | 38 | 63 | 88 | 113 | 138 | 163 | 188 | 213 | 238 | 263 | 288 | 313 | 338 | 363 | 388 | 413 | 438 | 463 | 488 | 513 | 538 | 563 | 588 | 613 | 638 | 663 | 688 |
| 14 | 39 | 64 | 89 | 114 | 139 | 164 | 189 | 214 | 239 | 264 | 289 | 314 | 339 | 364 | 389 | 414 | 439 | 464 | 489 | 514 | 539 | 564 | 589 | 614 | 639 | 664 | 689 |
| 15 | 40 | 65 | 90 | 115 | 140 | 165 | 190 | 215 | 240 | 265 | 290 | 315 | 340 | 365 | 390 | 415 | 440 | 465 | 490 | 515 | 540 | 565 | 590 | 615 | 640 | 665 | 690 |
| 16 | 41 | 66 | 91 | 116 | 141 | 166 | 191 | 216 | 241 | 266 | 291 | 316 | 341 | 366 | 391 | 416 | 441 | 466 | 491 | 516 | 541 | 566 | 591 | 616 | 641 | 666 | 691 |
| 17 | 42 | 67 | 92 | 117 | 142 | 167 | 192 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 | 617 | 642 | 667 | 692 |
| 18 | 43 | 68 | 93 | 118 | 143 | 168 | 193 | 218 | 243 | 268 | 293 | 318 | 343 | 368 | 393 | 418 | 443 | 468 | 493 | 518 | 543 | 568 | 593 | 618 | 643 | 668 | 693 |
| 19 | 44 | 69 | 94 | 119 | 144 | 169 | 194 | 219 | 244 | 269 | 294 | 319 | 344 | 369 | 394 | 419 | 444 | 469 | 494 | 519 | 544 | 569 | 594 | 619 | 644 | 669 | 694 |
| 20 | 45 | 70 | 95 | 120 | 145 | 170 | 195 | 220 | 245 | 270 | 295 | 320 | 345 | 370 | 395 | 420 | 445 | 470 | 495 | 520 | 545 | 570 | 595 | 620 | 645 | 670 | 695 |
| 21 | 46 | 71 | 96 | 121 | 146 | 171 | 196 | 221 | 246 | 271 | 296 | 321 | 346 | 371 | 396 | 421 | 446 | 471 | 496 | 521 | 546 | 571 | 596 | 621 | 646 | 671 | 696 |
| 22 | 47 | 72 | 97 | 122 | 147 | 172 | 197 | 222 | 247 | 272 | 297 | 322 | 347 | 372 | 397 | 422 | 447 | 472 | 497 | 522 | 547 | 572 | 597 | 622 | 647 | 672 | 697 |
| 23 | 48 | 73 | 98 | 123 | 148 | 173 | 198 | 223 | 248 | 273 | 298 | 323 | 348 | 373 | 398 | 423 | 448 | 473 | 498 | 523 | 548 | 573 | 598 | 623 | 648 | 673 | 698 |
| 24 | 49 | 74 | 99 | 124 | 149 | 174 | 199 | 224 | 249 | 274 | 299 | 324 | 349 | 374 | 399 | 424 | 449 | 474 | 499 | 524 | 549 | 574 | 599 | 624 | 649 | 674 | 699 |
| 25 | 50 | 75 | 100 | 125 | 150 | 175 | 200 | 225 | 250 | 275 | 300 | 325 | 350 | 375 | 400 | 425 | 450 | 475 | 500 | 525 | 550 | 575 | 600 | 625 | 650 | 675 | 700 |

I would like to subscribe to Materials in Design Engineering for ☐ 1 year $3.00 ☐ 2 years $5.00

FIRST CLASS
PERMIT NO. 1538
NEW YORK, N. Y.

**BUSINESS REPLY CARD**
No postage stamp necessary if mailed in the U. S.

POSTAGE WILL BE PAID BY—

MANAGER, READER SERVICE DEPARTMENT 11560

MATERIALS IN DESIGN ENGINEERING
430 PARK AVENUE
NEW YORK 22, N. Y.

# Reader Service


Silicones ..... 106
Synthetic rubber ..... 78, 88, 108
TFE fluorocarbon ..... 97, 99
Urea and melamine ..... 68
Urethane foams ..... 110
Vulcanized fibre ..... 101


## OTHER NONMETALLICS


| | Circle Key No. |
|---|---|
| Carbides, cemented | 128, 147 |
| Carbon and graphite | 126, 135, 137, 140, 141, 145, 148 |
| Cellophane film | 114 |
| Ceramics | 112, 117, 132 |
| Chemical cellulose | 138 |
| Chrysotile asbestos | 113 |
| Fabrics | |
| Coated | 120, 139 |
| Nonwoven | 142 |
| Felts | 111, 116, 122, 144 |
| Fused quartz | 121 |
| Glass | 130, 131 |
| Glass fiber insulation | 136 |
| Glass radiant heaters | 118 |
| Glass reinforcement for plastics | 123 |
| High temperature insulation | 124 |
| High temperature materials | 115 |
| Metallic oxides, sintered | 146 |
| Mica, glass-bonded | 134 |
| Paper | 129, 133 |
| Silicones | 119 |
| Thermal insulation | 127, 143 |
| Wood | 125 |


## FINISHES AND COATINGS


| | Circle Key No. |
|---|---|
| Butyrate lacquer | 159 |
| Chromium chemicals | 149 |
| Cleaning | |
| Metal | 170 |
| Ultrasonic | 153 |
| Coatings and processes | 168 |
| Coatings for metals | 151 |
| Coatings for plastics | 157 |
| Coloring plastics | 152 |
| Conversion coatings | |
| Aluminum | 171 |
| Chromate | 150 |
| Colored | 155 |
| Diffusion coatings | 156 |
| Dip coatings | 176 |
| Electroplating, gold | 173, 178 |
| Enamel, multicolor | 164 |
| Finishing, metal | 160 |
| Flame spray process | 166 |
| Flocked paper | 154 |
| Fusion bond finishes | 172 |
| Nickel alloy coatings | 161 |
| Paint finishes | 174 |
| Plasma arc coating | 179 |
| Plastisols, organisols | 177 |
| Plating services | 162 |
| Refractory coatings | 169 |
| Selective plating | 175 |
| Silicone coating | 167 |
| Sprayed vinyl finishes | 165 |
| TFE fluorocarbon finish | 158 |


## FORMS, SHAPES AND COMPOSITES


| | Circle Key No. |
|---|---|
| Aluminum publications | 181 |
| Bearing bronze | 185 |
| Beryllium copper parts | 217 |
| Castings | |
| Centrifugal | 240 |




FIRST CLASS
PERMIT NO. 1538
NEW YORK, N. Y.

**BUSINESS REPLY CARD**
No postage stamp necessary if mailed in the U. S.

POSTAGE WILL BE PAID BY —

MANAGER, READER SERVICE DEPARTMENT 11560

MATERIALS IN DESIGN ENGINEERING

430 PARK AVENUE

NEW YORK 22, N. Y.

THIS CARD NOT GOOD AFTER SEPTEMBER 1961 115/60

Name _____ Title _____

Firm _____

Street _____ City _____ Zone _____

State _____

Students and foreign subscribers (other than Canadian), please request literature directly from manufacturers.

| | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 26 | 51 | 76 | 101 | 126 | 151 | 176 | 201 | 226 | 251 | 276 | 301 | 326 | 351 | 376 | 401 | 426 | 451 | 476 | 501 | 526 | 551 | 576 | 601 | 626 | 651 | 676 |
| 2 | 27 | 52 | 77 | 102 | 127 | 152 | 177 | 202 | 227 | 252 | 277 | 302 | 327 | 352 | 377 | 402 | 427 | 452 | 477 | 502 | 527 | 552 | 577 | 602 | 627 | 652 | 677 |
| 3 | 28 | 53 | 78 | 103 | 128 | 153 | 178 | 203 | 228 | 253 | 278 | 303 | 328 | 353 | 378 | 403 | 428 | 453 | 478 | 503 | 528 | 553 | 578 | 603 | 628 | 653 | 678 |
| 4 | 29 | 54 | 79 | 104 | 129 | 154 | 179 | 204 | 229 | 254 | 279 | 304 | 329 | 354 | 379 | 404 | 429 | 454 | 479 | 504 | 529 | 554 | 579 | 604 | 629 | 654 | 679 |
| 5 | 30 | 55 | 80 | 105 | 130 | 155 | 180 | 205 | 230 | 255 | 280 | 305 | 330 | 355 | 380 | 405 | 430 | 455 | 480 | 505 | 530 | 555 | 580 | 605 | 630 | 655 | 680 |
| 6 | 31 | 56 | 81 | 106 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 | 531 | 556 | 581 | 606 | 631 | 656 | 681 |
| 7 | 32 | 57 | 82 | 107 | 132 | 157 | 182 | 207 | 232 | 257 | 282 | 307 | 332 | 357 | 382 | 407 | 432 | 457 | 482 | 507 | 532 | 557 | 582 | 607 | 632 | 657 | 682 |
| 8 | 33 | 58 | 83 | 108 | 133 | 158 | 183 | 208 | 233 | 258 | 283 | 308 | 333 | 358 | 383 | 408 | 433 | 458 | 483 | 508 | 533 | 558 | 583 | 608 | 633 | 658 | 683 |
| 9 | 34 | 59 | 84 | 109 | 134 | 159 | 184 | 209 | 234 | 259 | 284 | 309 | 334 | 359 | 384 | 409 | 434 | 459 | 484 | 509 | 534 | 559 | 584 | 609 | 634 | 659 | 684 |
| 10 | 35 | 60 | 85 | 110 | 135 | 160 | 185 | 210 | 235 | 260 | 285 | 310 | 335 | 360 | 385 | 410 | 435 | 460 | 485 | 510 | 535 | 560 | 585 | 610 | 635 | 660 | 685 |
| 11 | 36 | 61 | 86 | 111 | 136 | 161 | 186 | 211 | 236 | 261 | 286 | 311 | 336 | 361 | 386 | 411 | 436 | 461 | 486 | 511 | 536 | 561 | 586 | 611 | 636 | 661 | 686 |
| 12 | 37 | 62 | 87 | 112 | 137 | 162 | 187 | 212 | 237 | 262 | 287 | 312 | 337 | 362 | 387 | 412 | 437 | 462 | 487 | 512 | 537 | 562 | 587 | 612 | 637 | 662 | 687 |
| 13 | 38 | 63 | 88 | 113 | 138 | 163 | 188 | 213 | 238 | 263 | 288 | 313 | 338 | 363 | 388 | 413 | 438 | 463 | 488 | 513 | 538 | 563 | 588 | 613 | 638 | 663 | 688 |
| 14 | 39 | 64 | 89 | 114 | 139 | 164 | 189 | 214 | 239 | 264 | 289 | 314 | 339 | 364 | 389 | 414 | 439 | 464 | 489 | 514 | 539 | 564 | 589 | 614 | 639 | 664 | 689 |
| 15 | 40 | 65 | 90 | 115 | 140 | 165 | 190 | 215 | 240 | 265 | 290 | 315 | 340 | 365 | 390 | 415 | 440 | 465 | 490 | 515 | 540 | 565 | 590 | 615 | 640 | 665 | 690 |
| 16 | 41 | 66 | 91 | 116 | 141 | 166 | 191 | 216 | 241 | 266 | 291 | 316 | 341 | 366 | 391 | 416 | 441 | 466 | 491 | 516 | 541 | 566 | 591 | 616 | 641 | 666 | 691 |
| 17 | 42 | 67 | 92 | 117 | 142 | 167 | 192 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 | 617 | 642 | 667 | 692 |
| 18 | 43 | 68 | 93 | 118 | 143 | 168 | 193 | 218 | 243 | 268 | 293 | 318 | 343 | 368 | 393 | 418 | 443 | 468 | 493 | 518 | 543 | 568 | 593 | 618 | 643 | 668 | 693 |
| 19 | 44 | 69 | 94 | 119 | 144 | 169 | 194 | 219 | 244 | 269 | 294 | 319 | 344 | 369 | 394 | 419 | 444 | 469 | 494 | 519 | 544 | 569 | 594 | 619 | 644 | 669 | 694 |
| 20 | 45 | 70 | 95 | 120 | 145 | 170 | 195 | 220 | 245 | 270 | 295 | 320 | 345 | 370 | 395 | 420 | 445 | 470 | 495 | 520 | 545 | 570 | 595 | 620 | 645 | 670 | 695 |
| 21 | 46 | 71 | 96 | 121 | 146 | 171 | 196 | 221 | 246 | 271 | 296 | 321 | 346 | 371 | 396 | 421 | 446 | 471 | 496 | 521 | 546 | 571 | 596 | 621 | 646 | 671 | 696 |
| 22 | 47 | 72 | 97 | 122 | 147 | 172 | 197 | 222 | 247 | 272 | 297 | 322 | 347 | 372 | 397 | 422 | 447 | 472 | 497 | 522 | 547 | 572 | 597 | 622 | 647 | 672 | 697 |
| 23 | 48 | 73 | 98 | 123 | 148 | 173 | 198 | 223 | 248 | 273 | 298 | 323 | 348 | 373 | 398 | 423 | 448 | 473 | 498 | 523 | 548 | 573 | 598 | 623 | 648 | 673 | 698 |
| 24 | 49 | 74 | 99 | 124 | 149 | 174 | 199 | 224 | 249 | 274 | 299 | 324 | 349 | 374 | 399 | 424 | 449 | 474 | 499 | 524 | 549 | 574 | 599 | 624 | 649 | 674 | 699 |
| 25 | 50 | 75 | 100 | 125 | 150 | 175 | 200 | 225 | 250 | 275 | 300 | 325 | 350 | 375 | 400 | 425 | 450 | 475 | 500 | 525 | 550 | 575 | 600 | 625 | 650 | 675 | 700 |

I would like to subscribe to Materials in Design Engineering for ☐ 1 year $3.00 ☐ 2 years $5.00

# Reader Service


Castings (cont'd)
- Engineered ..... 213
- High alloy ..... 197, 200
- Meehanite ..... 223
- Nonferrous ..... 187, 202, 241
- Permanent mold ..... 201
- Precision die ..... 245
- Precision steel ..... 247
- Stainless steel ..... 248
- Steel ..... 246

Ceramic parts ..... 211
Clad metals ..... 244
Ductile iron parts ..... 182
Electrical contact materials ..... 208
Expanded strip-tubing ..... 191
Extrusions
- Aluminum ..... 206, 218, 234, 249
- Plastics, rubber ..... 194, 195, 251

Fabricated silicone rubber ..... 215
Fabricating magnesium ..... 198

Forgings ..... 192, 219, 220, 238
Forms, metallic and nonmetallic ..... 199
Impact extrusions ..... 227
Magnesium parts ..... 189
Metal-faced plywood ..... 224
Metal powder parts ..... 210, 231
Metal powders ..... 184, 209, 236
Molded plastics ..... 205, 235
Molded rubber ..... 180, 193
O-rings, rubber and plastics ..... 188
Perforated metal ..... 214
Perforated rubber, fabrics ..... 232
Pipe, butyrate ..... 190
Plastics-impregnated wood parts ..... 233
Porous metal components ..... 225
Reinforced plastics ..... 204, 221
Reinforced TFE parts ..... 196
Rubber parts ..... 212, 250
Silicone rubber parts ..... 226
Sponge iron ..... 216
Stampings, metallic and nonmetallic ..... 186, 203, 237, 239
Tubing ..... 207, 243
Vinyl-metal laminates ..... 242
Wire
- Cloth ..... 230
- Parts ..... 186
- Specially shaped ..... 183, 222
- Superalloy ..... 229

Zirconium metal parts ..... 228


THIS CARD NOT GOOD AFTER SEPTEMBER 1961 — 115/60

Name _____ Title _____

Firm _____

Street _____ City _____ Zone _____

State _____

Students and foreign subscribers (other than Canadian), please request literature directly from manufacturers.

| | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 26 | 51 | 76 | 101 | 126 | 151 | 176 | 201 | 226 | 251 | 276 | 301 | 326 | 351 | 376 | 401 | 426 | 451 | 476 | 501 | 526 | 551 | 576 | 601 | 626 | 651 | 676 |
| 2 | 27 | 52 | 77 | 102 | 127 | 152 | 177 | 202 | 227 | 252 | 277 | 302 | 327 | 352 | 377 | 402 | 427 | 452 | 477 | 502 | 527 | 552 | 577 | 602 | 627 | 652 | 677 |
| 3 | 28 | 53 | 78 | 103 | 128 | 153 | 178 | 203 | 228 | 253 | 278 | 303 | 328 | 353 | 378 | 403 | 428 | 453 | 478 | 503 | 528 | 553 | 578 | 603 | 628 | 653 | 678 |
| 4 | 29 | 54 | 79 | 104 | 129 | 154 | 179 | 204 | 229 | 254 | 279 | 304 | 329 | 354 | 379 | 404 | 429 | 454 | 479 | 504 | 529 | 554 | 579 | 604 | 629 | 654 | 679 |
| 5 | 30 | 55 | 80 | 105 | 130 | 155 | 180 | 205 | 230 | 255 | 280 | 305 | 330 | 355 | 380 | 405 | 430 | 455 | 480 | 505 | 530 | 555 | 580 | 605 | 630 | 655 | 680 |
| 6 | 31 | 56 | 81 | 106 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 | 531 | 556 | 581 | 606 | 631 | 656 | 681 |
| 7 | 32 | 57 | 82 | 107 | 132 | 157 | 182 | 207 | 232 | 257 | 282 | 307 | 332 | 357 | 382 | 407 | 432 | 457 | 482 | 507 | 532 | 557 | 582 | 607 | 632 | 657 | 682 |
| 8 | 33 | 58 | 83 | 108 | 133 | 158 | 183 | 208 | 233 | 258 | 283 | 308 | 333 | 358 | 383 | 408 | 433 | 458 | 483 | 508 | 533 | 558 | 583 | 608 | 633 | 658 | 683 |
| 9 | 34 | 59 | 84 | 109 | 134 | 159 | 184 | 209 | 234 | 259 | 284 | 309 | 334 | 359 | 384 | 409 | 434 | 459 | 484 | 509 | 534 | 559 | 584 | 609 | 634 | 659 | 684 |
| 10 | 35 | 60 | 85 | 110 | 135 | 160 | 185 | 210 | 235 | 260 | 285 | 310 | 335 | 360 | 385 | 410 | 435 | 460 | 485 | 510 | 535 | 560 | 585 | 610 | 635 | 660 | 685 |
| 11 | 36 | 61 | 86 | 111 | 136 | 161 | 186 | 211 | 236 | 261 | 286 | 311 | 336 | 361 | 386 | 411 | 436 | 461 | 486 | 511 | 536 | 561 | 586 | 611 | 636 | 661 | 686 |
| 12 | 37 | 62 | 87 | 112 | 137 | 162 | 187 | 212 | 237 | 262 | 287 | 312 | 337 | 362 | 387 | 412 | 437 | 462 | 487 | 512 | 537 | 562 | 587 | 612 | 637 | 662 | 687 |
| 13 | 38 | 63 | 88 | 113 | 138 | 163 | 188 | 213 | 238 | 263 | 288 | 313 | 338 | 363 | 388 | 413 | 438 | 463 | 488 | 513 | 538 | 563 | 588 | 613 | 638 | 663 | 688 |
| 14 | 39 | 64 | 89 | 114 | 139 | 164 | 189 | 214 | 239 | 264 | 289 | 314 | 339 | 364 | 389 | 414 | 439 | 464 | 489 | 514 | 539 | 564 | 589 | 614 | 639 | 664 | 689 |
| 15 | 40 | 65 | 90 | 115 | 140 | 165 | 190 | 215 | 240 | 265 | 290 | 315 | 340 | 365 | 390 | 415 | 440 | 465 | 490 | 515 | 540 | 565 | 590 | 615 | 640 | 665 | 690 |
| 16 | 41 | 66 | 91 | 116 | 141 | 166 | 191 | 216 | 241 | 266 | 291 | 316 | 341 | 366 | 391 | 416 | 441 | 466 | 491 | 516 | 541 | 566 | 591 | 616 | 641 | 666 | 691 |
| 17 | 42 | 67 | 92 | 117 | 142 | 167 | 192 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 | 617 | 642 | 667 | 692 |
| 18 | 43 | 68 | 93 | 118 | 143 | 168 | 193 | 218 | 243 | 268 | 293 | 318 | 343 | 368 | 393 | 418 | 443 | 468 | 493 | 518 | 543 | 568 | 593 | 618 | 643 | 668 | 693 |
| 19 | 44 | 69 | 94 | 119 | 144 | 169 | 194 | 219 | 244 | 269 | 294 | 319 | 344 | 369 | 394 | 419 | 444 | 469 | 494 | 519 | 544 | 569 | 594 | 619 | 644 | 669 | 694 |
| 20 | 45 | 70 | 95 | 120 | 145 | 170 | 195 | 220 | 245 | 270 | 295 | 320 | 345 | 370 | 395 | 420 | 445 | 470 | 495 | 520 | 545 | 570 | 595 | 620 | 645 | 670 | 695 |
| 21 | 46 | 71 | 96 | 121 | 146 | 171 | 196 | 221 | 246 | 271 | 296 | 321 | 346 | 371 | 396 | 421 | 446 | 471 | 496 | 521 | 546 | 571 | 596 | 621 | 646 | 671 | 696 |
| 22 | 47 | 72 | 97 | 122 | 147 | 172 | 197 | 222 | 247 | 272 | 297 | 322 | 347 | 372 | 397 | 422 | 447 | 472 | 497 | 522 | 547 | 572 | 597 | 622 | 647 | 672 | 697 |
| 23 | 48 | 73 | 98 | 123 | 148 | 173 | 198 | 223 | 248 | 273 | 298 | 323 | 348 | 373 | 398 | 423 | 448 | 473 | 498 | 523 | 548 | 573 | 598 | 623 | 648 | 673 | 698 |
| 24 | 49 | 74 | 99 | 124 | 149 | 174 | 199 | 224 | 249 | 274 | 299 | 324 | 349 | 374 | 399 | 424 | 449 | 474 | 499 | 524 | 549 | 574 | 599 | 624 | 649 | 674 | 699 |
| 25 | 50 | 75 | 100 | 125 | 150 | 175 | 200 | 225 | 250 | 275 | 300 | 325 | 350 | 375 | 400 | 425 | 450 | 475 | 500 | 525 | 550 | 575 | 600 | 625 | 650 | 675 | 700 |

I would like to subscribe to Materials in Design Engineering for ☐ 1 year $3.00 ☐ 2 years $5.00

FIRST CLASS
PERMIT NO. 1538
NEW YORK, N. Y.

**BUSINESS REPLY CARD**
No postage stamp necessary if mailed in the U. S.

POSTAGE WILL BE PAID BY —

MANAGER, READER SERVICE DEPARTMENT 11560

MATERIALS IN DESIGN ENGINEERING
430 PARK AVENUE
NEW YORK 22, N. Y.

## JOINING AND FASTENING OF MATERIALS


Circle Key No.

Adhesives ..... 255, 258, 261, 267, 268, 277
Brazing ..... 282
Brazing alloys ..... 260, 264, 288
Brazing preforms ..... 270
Epoxy pellets ..... 287
Etchant, fluorocarbon ..... 257
Fasteners
- Catalog ..... 281
- Cold headed ..... 265, 272
- Die cast, molded ..... 262
- Lock nut ..... 274
- Lock screw ..... 279
- Mechanical ..... 256, 263, 266, 273
- Rivets, blind ..... 286
- Screws, nylon ..... 289
- Self-locking nuts ..... 271
- Socket head cap screws ..... 280

Fastening analysis ..... 284
Increasing fatigue life of bolts ..... 259
Methods for joining metals ..... 285
Screw fastening aluminum ..... 278
Screw thread root design ..... 283
Sealant for metal parts ..... 254
Sealing compound ..... 253, 276
Seals and fasteners, high temperature ..... 252
Solder paste alloys ..... 275
Welding electrodes ..... 269

# Reader Service

## Information on Advertised Products

Turn to pages indicated for advertisements on these products. Note that the numbers given are page numbers, not key numbers. To find advertisements of specific companies, use the Index to Advertisers, pages 9-10.

### IRONS AND STEELS


| | Page No. |
|---|---|
| Carbon steels | 84-5, 89, 90-1 |
| Casting alloys | 82 |
| Heat and corrosion resistant steel | 82, 84-5, 86, 87, 89, 90-1, 93, 95, 96, 97 |
| Low alloy steel | 87, 89, 90-1, 93, 95 |
| Malleable iron | 442-3 |
| Metal powders | 432, 462 |
| Spring materials | 83 |
| Superalloys | 87, 95 |
| Tool and die steel | 87, 93 |


### NONFERROUS METALS


| | Page No. |
|---|---|
| Aluminum and its alloys | 161, 169, 173, 178, 179 |
| Beryllium and its alloys | 157, 171, 415 |
| Casting alloys | 173, 178, 452-3 |
| Chromium and its alloys | 181 |
| Columbium and its alloys | 164, 174, 181, 310, 415 |
| Contact materials, electrical | 158, 466 |
| Copper and its alloys | 155, 157, 162, 165-8, 169, 176, 178, 180, 463 |
| Electronics, alloys for | 177, 185 |
| Hafnium | 164 |
| Indium and its alloys | 172 |
| Low melting alloys | 178 |
| Magnesium and its alloys | 408-9 |
| Metal powders | 429, 452-3 |
| Molybdenum and its alloys | 153, 163, 164, 174 |
| Platinum metals | 182-3 |
| Silver and its alloys | 152 |
| Spring materials | 160 |
| Tantalum and its alloys | 164, 174, 181, 310, 415 |
| Tin and its alloys | 156 |
| Titanium and its alloys | 84-5, 93 |
| Tungsten and its alloys | 153, 163, 164, 174, 310 |
| Vanadium and its alloys | 181 |
| Zinc and its alloys | 154, 452-3 |
| Zirconium and its alloys | 164, 415, 430 |


### PLASTICS AND RUBBER


| | Page No. |
|---|---|
| ABS plastics | 235-42 |
| Cellular materials | 260 |
| Cellulose acetate | 243, 271-4 |
| Cellulose propionate | 271-4 |
| Diallyl phthalate | 232-3, 261 |
| Epoxies | 257, 278-9, 499 |




FIRST CLASS
PERMIT NO. 1538
NEW YORK, N. Y.

**BUSINESS REPLY CARD**
No postage stamp necessary if mailed in the U. S.

POSTAGE WILL BE PAID BY —

MANAGER, READER SERVICE DEPARTMENT 11560
MATERIALS IN DESIGN ENGINEERING
430 PARK AVENUE
NEW YORK 22, N. Y.

THIS CARD NOT GOOD AFTER SEPTEMBER 1961 115/60

Name Title

Firm

Street City Zone

State

Students and foreign subscribers (other than Canadian), please request literature directly from manufacturers.

| | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 26 | 51 | 76 | 101 | 126 | 151 | 176 | 201 | 226 | 251 | 276 | 301 | 326 | 351 | 376 | 401 | 426 | 451 | 476 | 501 | 526 | 551 | 576 | 601 | 626 | 651 | 676 |
| 2 | 27 | 52 | 77 | 102 | 127 | 152 | 177 | 202 | 227 | 252 | 277 | 302 | 327 | 352 | 377 | 402 | 427 | 452 | 477 | 502 | 527 | 552 | 577 | 602 | 627 | 652 | 677 |
| 3 | 28 | 53 | 78 | 103 | 128 | 153 | 178 | 203 | 228 | 253 | 278 | 303 | 328 | 353 | 378 | 403 | 428 | 453 | 478 | 503 | 528 | 553 | 578 | 603 | 628 | 653 | 678 |
| 4 | 29 | 54 | 79 | 104 | 129 | 154 | 179 | 204 | 229 | 254 | 279 | 304 | 329 | 354 | 379 | 404 | 429 | 454 | 479 | 504 | 529 | 554 | 579 | 604 | 629 | 654 | 679 |
| 5 | 30 | 55 | 80 | 105 | 130 | 155 | 180 | 205 | 230 | 255 | 280 | 305 | 330 | 355 | 380 | 405 | 430 | 455 | 480 | 505 | 530 | 555 | 580 | 605 | 630 | 655 | 680 |
| 6 | 31 | 56 | 81 | 106 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 | 531 | 556 | 581 | 606 | 631 | 656 | 681 |
| 7 | 32 | 57 | 82 | 107 | 132 | 157 | 182 | 207 | 232 | 257 | 282 | 307 | 332 | 357 | 382 | 407 | 432 | 457 | 482 | 507 | 532 | 557 | 582 | 607 | 632 | 657 | 682 |
| 8 | 33 | 58 | 83 | 108 | 133 | 158 | 183 | 208 | 233 | 258 | 283 | 308 | 333 | 358 | 383 | 408 | 433 | 458 | 483 | 508 | 533 | 558 | 583 | 608 | 633 | 658 | 683 |
| 9 | 34 | 59 | 84 | 109 | 134 | 159 | 184 | 209 | 234 | 259 | 284 | 309 | 334 | 359 | 384 | 409 | 434 | 459 | 484 | 509 | 534 | 559 | 584 | 609 | 634 | 659 | 684 |
| 10 | 35 | 60 | 85 | 110 | 135 | 160 | 185 | 210 | 235 | 260 | 285 | 310 | 335 | 360 | 385 | 410 | 435 | 460 | 485 | 510 | 535 | 560 | 585 | 610 | 635 | 660 | 685 |
| 11 | 36 | 61 | 86 | 111 | 136 | 161 | 186 | 211 | 236 | 261 | 286 | 311 | 336 | 361 | 386 | 411 | 436 | 461 | 486 | 511 | 536 | 561 | 586 | 611 | 636 | 661 | 686 |
| 12 | 37 | 62 | 87 | 112 | 137 | 162 | 187 | 212 | 237 | 262 | 287 | 312 | 337 | 362 | 387 | 412 | 437 | 462 | 487 | 512 | 537 | 562 | 587 | 612 | 637 | 662 | 687 |
| 13 | 38 | 63 | 88 | 113 | 138 | 163 | 188 | 213 | 238 | 263 | 288 | 313 | 338 | 363 | 388 | 413 | 438 | 463 | 488 | 513 | 538 | 563 | 588 | 613 | 638 | 663 | 688 |
| 14 | 39 | 64 | 89 | 114 | 139 | 164 | 189 | 214 | 239 | 264 | 289 | 314 | 339 | 364 | 389 | 414 | 439 | 464 | 489 | 514 | 539 | 564 | 589 | 614 | 639 | 664 | 689 |
| 15 | 40 | 65 | 90 | 115 | 140 | 165 | 190 | 215 | 240 | 265 | 290 | 315 | 340 | 365 | 390 | 415 | 440 | 465 | 490 | 515 | 540 | 565 | 590 | 615 | 640 | 665 | 690 |
| 16 | 41 | 66 | 91 | 116 | 141 | 166 | 191 | 216 | 241 | 266 | 291 | 316 | 341 | 366 | 391 | 416 | 441 | 466 | 491 | 516 | 541 | 566 | 591 | 616 | 641 | 666 | 691 |
| 17 | 42 | 67 | 92 | 117 | 142 | 167 | 192 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 | 617 | 642 | 667 | 692 |
| 18 | 43 | 68 | 93 | 118 | 143 | 168 | 193 | 218 | 243 | 268 | 293 | 318 | 343 | 368 | 393 | 418 | 443 | 468 | 493 | 518 | 543 | 568 | 593 | 618 | 643 | 668 | 693 |
| 19 | 44 | 69 | 94 | 119 | 144 | 169 | 194 | 219 | 244 | 269 | 294 | 319 | 344 | 369 | 394 | 419 | 444 | 469 | 494 | 519 | 544 | 569 | 594 | 619 | 644 | 669 | 694 |
| 20 | 45 | 70 | 95 | 120 | 145 | 170 | 195 | 220 | 245 | 270 | 295 | 320 | 345 | 370 | 395 | 420 | 445 | 470 | 495 | 520 | 545 | 570 | 595 | 620 | 645 | 670 | 695 |
| 21 | 46 | 71 | 96 | 121 | 146 | 171 | 196 | 221 | 246 | 271 | 296 | 321 | 346 | 371 | 396 | 421 | 446 | 471 | 496 | 521 | 546 | 571 | 596 | 621 | 646 | 671 | 696 |
| 22 | 47 | 72 | 97 | 122 | 147 | 172 | 197 | 222 | 247 | 272 | 297 | 322 | 347 | 372 | 397 | 422 | 447 | 472 | 497 | 522 | 547 | 572 | 597 | 622 | 647 | 672 | 697 |
| 23 | 48 | 73 | 98 | 123 | 148 | 173 | 198 | 223 | 248 | 273 | 298 | 323 | 348 | 373 | 398 | 423 | 448 | 473 | 498 | 523 | 548 | 573 | 598 | 623 | 648 | 673 | 698 |
| 24 | 49 | 74 | 99 | 124 | 149 | 174 | 199 | 224 | 249 | 274 | 299 | 324 | 349 | 374 | 399 | 424 | 449 | 474 | 499 | 524 | 549 | 574 | 599 | 624 | 649 | 674 | 699 |
| 25 | 50 | 75 | 100 | 125 | 150 | 175 | 200 | 225 | 250 | 275 | 300 | 325 | 350 | 375 | 400 | 425 | 450 | 475 | 500 | 525 | 550 | 575 | 600 | 625 | 650 | 675 | 700 |

I would like to subscribe to Materials in Design Engineering for ☐ 1 year $3.00 ☐ 2 years $5.00

# Reader Service


Fluorocarbons ... 230, 261, 268, 434, 460
Foams
  Plastics ... 264-5
  Rubber ... 250
Laminates
  Metallized ... 263
  Plastics ... 234, 246, 249, 255, 256, 263, 276, 281, 431
Melamine ... 251
Phenolics ... 232-3, 257, 261, 270, 281
Polyamides (nylon) ... 230
Polyester film ... 359
Polyesters ... 232-3, 248, 254, 262, 271-4
Polyethylenes ... 243, 257, 271-4
Polypropylene ... 243, 244-5
Polystyrenes ... 243, 257, 264-5
Premix plastics ... 256, 258-9, 269, 275, 457
Reinforced plastics 256, 258-9, 262, 428, 432
Silicone rubber ... 425, 441
Synthetic rubber ... 231, 247, 266-7, 438, 441
Urea ... 251
Vinyls ... 257
Vulcanized fibre ... 248, 249, 255


## OTHER NONMETALLICS


Page No.
Asbestos ... 316-7
Carbides, cemented ... 310
Carbon and graphite 307, 309, 318, 320, 322
Ceramics ... 157, 171, 308, 449
Ceramoplastics ... 323-6
Fabrics, coated ... 269, 275, 315, 318
Felts ... 310, 312, 322, 327
Glass ... 309, 319
Glass for reinforcement ... 311, 321
Insulation ... 256, 261
Mica ... 323-6
Mica, glass-bonded ... 323-6, 426
Papers ... 320
Quartz, fused ... 159
Rayon fibers ... 313
Silicones ... 277, 460


## FINISHES AND COATINGS


Page No.
Anodes ... 178, 358
Ceramic coatings ... 348
Chemical conversion coatings ... 358, 360
Electroless nickel coatings ... 355
Flame spray equipment ... 361, 360
Flock coatings ... 363
High temperature ... 263
Inspection, ultrasonic ... 263
Metallic coatings ... 355
Metallized coatings ... 359
Organic coatings ... 350, 353, 357, 358, 363
Plating processes, solutions ... 159, 352, 356
Precoated and preplated metals ... 84-5
Sodium nitrite coatings ... 349
Vacuum deposited coatings ... 358


## FORMS, SHAPES AND COMPOSITES


Page No.
Bearing materials ... 87
Castings
  Centrifugal ... 410, 417, 422, 427
  Ceramic mold ... 451
  Continuous ... 433
  Die ... 418, 452-3
  Meehanite ... 461
  Permanent mold ... 408-9, 420, 459
  Plaster mold ... 438
  Sand ... 408-9, 417, 455, 467
  Shell mold ... 417, 459, 467
Clad metals ... 465
Cold headed parts ... 501
Diaphragms ... 416
Die cut parts ... 276
Drawn, pressed parts ... 457
Encapsulating ... 499
Extrusions
  Metallic ... 176, 408-9, 437, 442, 458, 462
  Nonmetallic 276, 447, 455, 460, 464, 466




THIS CARD NOT GOOD AFTER SEPTEMBER 1961 — 115/60

Name _____ Title _____

Firm _____

Street _____ City _____ Zone _____

State _____

Students and foreign subscribers (other than Canadian), please request literature directly from manufacturers.

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 26 | 51 | 76 | 101 | 126 | 151 | 176 | 201 | 226 | 251 | 276 | 301 | 326 | 351 | 376 | 401 | 426 | 451 | 476 | 501 | 526 | 551 | 576 | 601 | 626 | 651 | 676 |
| 2 | 27 | 52 | 77 | 102 | 127 | 152 | 177 | 202 | 227 | 252 | 277 | 302 | 327 | 352 | 377 | 402 | 427 | 452 | 477 | 502 | 527 | 552 | 577 | 602 | 627 | 652 | 677 |
| 3 | 28 | 53 | 78 | 103 | 128 | 153 | 178 | 203 | 228 | 253 | 278 | 303 | 328 | 353 | 378 | 403 | 428 | 453 | 478 | 503 | 528 | 553 | 578 | 603 | 628 | 653 | 678 |
| 4 | 29 | 54 | 79 | 104 | 129 | 154 | 179 | 204 | 229 | 254 | 279 | 304 | 329 | 354 | 379 | 404 | 429 | 454 | 479 | 504 | 529 | 554 | 579 | 604 | 629 | 654 | 679 |
| 5 | 30 | 55 | 80 | 105 | 130 | 155 | 180 | 205 | 230 | 255 | 280 | 305 | 330 | 355 | 380 | 405 | 430 | 455 | 480 | 505 | 530 | 555 | 580 | 605 | 630 | 655 | 680 |
| 6 | 31 | 56 | 81 | 106 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 | 531 | 556 | 581 | 606 | 631 | 656 | 681 |
| 7 | 32 | 57 | 82 | 107 | 132 | 157 | 182 | 207 | 232 | 257 | 282 | 307 | 332 | 357 | 382 | 407 | 432 | 457 | 482 | 507 | 532 | 557 | 582 | 607 | 632 | 657 | 682 |
| 8 | 33 | 58 | 83 | 108 | 133 | 158 | 183 | 208 | 233 | 258 | 283 | 308 | 333 | 358 | 383 | 408 | 433 | 458 | 483 | 508 | 533 | 558 | 583 | 608 | 633 | 658 | 683 |
| 9 | 34 | 59 | 84 | 109 | 134 | 159 | 184 | 209 | 234 | 259 | 284 | 309 | 334 | 359 | 384 | 409 | 434 | 459 | 484 | 509 | 534 | 559 | 584 | 609 | 634 | 659 | 684 |
| 10 | 35 | 60 | 85 | 110 | 135 | 160 | 185 | 210 | 235 | 260 | 285 | 310 | 335 | 360 | 385 | 410 | 435 | 460 | 485 | 510 | 535 | 560 | 585 | 610 | 635 | 660 | 685 |
| 11 | 36 | 61 | 86 | 111 | 136 | 161 | 186 | 211 | 236 | 261 | 286 | 311 | 336 | 361 | 386 | 411 | 436 | 461 | 486 | 511 | 536 | 561 | 586 | 611 | 636 | 661 | 686 |
| 12 | 37 | 62 | 87 | 112 | 137 | 162 | 187 | 212 | 237 | 262 | 287 | 312 | 337 | 362 | 387 | 412 | 437 | 462 | 487 | 512 | 537 | 562 | 587 | 612 | 637 | 662 | 687 |
| 13 | 38 | 63 | 88 | 113 | 138 | 163 | 188 | 213 | 238 | 263 | 288 | 313 | 338 | 363 | 388 | 413 | 438 | 463 | 488 | 513 | 538 | 563 | 588 | 613 | 638 | 663 | 688 |
| 14 | 39 | 64 | 89 | 114 | 139 | 164 | 189 | 214 | 239 | 264 | 289 | 314 | 339 | 364 | 389 | 414 | 439 | 464 | 489 | 514 | 539 | 564 | 589 | 614 | 639 | 664 | 689 |
| 15 | 40 | 65 | 90 | 115 | 140 | 165 | 190 | 215 | 240 | 265 | 290 | 315 | 340 | 365 | 390 | 415 | 440 | 465 | 490 | 515 | 540 | 565 | 590 | 615 | 640 | 665 | 690 |
| 16 | 41 | 66 | 91 | 116 | 141 | 166 | 191 | 216 | 241 | 266 | 291 | 316 | 341 | 366 | 391 | 416 | 441 | 466 | 491 | 516 | 541 | 566 | 591 | 616 | 641 | 666 | 691 |
| 17 | 42 | 67 | 92 | 117 | 142 | 167 | 192 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 | 617 | 642 | 667 | 692 |
| 18 | 43 | 68 | 93 | 118 | 143 | 168 | 193 | 218 | 243 | 268 | 293 | 318 | 343 | 368 | 393 | 418 | 443 | 468 | 493 | 518 | 543 | 568 | 593 | 618 | 643 | 668 | 693 |
| 19 | 44 | 69 | 94 | 119 | 144 | 169 | 194 | 219 | 244 | 269 | 294 | 319 | 344 | 369 | 394 | 419 | 444 | 469 | 494 | 519 | 544 | 569 | 594 | 619 | 644 | 669 | 694 |
| 20 | 45 | 70 | 95 | 120 | 145 | 170 | 195 | 220 | 245 | 270 | 295 | 320 | 345 | 370 | 395 | 420 | 445 | 470 | 495 | 520 | 545 | 570 | 595 | 620 | 645 | 670 | 695 |
| 21 | 46 | 71 | 96 | 121 | 146 | 171 | 196 | 221 | 246 | 271 | 296 | 321 | 346 | 371 | 396 | 421 | 446 | 471 | 496 | 521 | 546 | 571 | 596 | 621 | 646 | 671 | 696 |
| 22 | 47 | 72 | 97 | 122 | 147 | 172 | 197 | 222 | 247 | 272 | 297 | 322 | 347 | 372 | 397 | 422 | 447 | 472 | 497 | 522 | 547 | 572 | 597 | 622 | 647 | 672 | 697 |
| 23 | 48 | 73 | 98 | 123 | 148 | 173 | 198 | 223 | 248 | 273 | 298 | 323 | 348 | 373 | 398 | 423 | 448 | 473 | 498 | 523 | 548 | 573 | 598 | 623 | 648 | 673 | 698 |
| 24 | 49 | 74 | 99 | 124 | 149 | 174 | 199 | 224 | 249 | 274 | 299 | 324 | 349 | 374 | 399 | 424 | 449 | 474 | 499 | 524 | 549 | 574 | 599 | 624 | 649 | 674 | 699 |
| 25 | 50 | 75 | 100 | 125 | 150 | 175 | 200 | 225 | 250 | 275 | 300 | 325 | 350 | 375 | 400 | 425 | 450 | 475 | 500 | 525 | 550 | 575 | 600 | 625 | 650 | 675 | 700 |

I would like to subscribe to Materials in Design Engineering for ☐ 1 year $3.00 ☐ 2 years $5.00

FIRST CLASS
PERMIT NO. 1538
NEW YORK, N. Y.

**BUSINESS REPLY CARD**
No postage stamp necessary if mailed in the U. S.

POSTAGE WILL BE PAID BY —

MANAGER, READER SERVICE DEPARTMENT 11560

MATERIALS IN DESIGN ENGINEERING
430 PARK AVENUE
NEW YORK 22, N. Y.

# Reader Service

## Subscribe now to get your own copy of the Materials Selector Issue

If you do not have your own copy of the Materials Selector Issue you probably wish you did. You can make sure of getting next year's reference issue by subscribing now to Materials in Design Engineering. That is the only way to be certain of seeing every copy of the one magazine in the world edited solely for those who need to know the latest about engineering materials, forms and finishes. Cost: only $3.00 per year (in U.S.); $5.00 for two years. To start your regular monthly issues coming, simply check one of the two boxes at the bottom of the postage-free card.

## Information on Advertised Products CONTINUED


| | Page No. |
|---|---|
| Forgings | 176, 419, 423, 439, 450, 455 |
| Gaskets | 450 |
| Impact extrusions | 424, 455 |
| Laminates, metal-plastic | 413 |
| Lathe-cut parts | 412 |
| Magnet materials | 420 |
| Metal powder parts | 455, 456, 464 |
| Packings | 416, 450 |
| Perforated materials | 421, 440, 450 |
| Plastics laminates | 444 |
| Plastics moldings | 411, 425, 455, 458, 460 |
| Porous metal components | 466 |
| Potting and impregnating | 499 |
| Pressure vessel accessories | 462 |
| Punched parts | 276 |
| Rings, nonmetallic "O" | 450 |
| Rubber moldings | 276, 438, 441, 448, 460 |
| Screw machine parts | 455 |
| Seals | 412, 416, 450 |
| Shims | 450 |
| Springs | 83, 421, 440, 463 |
| Stampings and punchings | 436, 458, 464 |
| Strip, precision rolled | 89, 90-1, 162 |
| Tubing and pipe | |
| Metallic | 176, 180, 410, 414-5, 435, 446, 455 |
| Nonmetallic | 442 |
| Wire | 421, 446 |
| Wire cloth | 421, 454 |
| Wire forms | 437 |


## JOINING AND FASTENING


| | Page No. |
|---|---|
| Adhesives | 492, 494, 496 |
| Bonding | 499 |
| Brazing alloys | 495, 498 |
| Brazing | 493, 498 |
| Fasteners, mechanical | 494, 496, 497, 498, 501 |
| Tapes, adhesive | 460 |
| Welding electrodes, rods | 82, 176 |
| Weldments | 457, 458 |




FIRST CLASS
PERMIT NO. 1538
NEW YORK, N. Y.

**BUSINESS REPLY CARD**
No postage stamp necessary if mailed in the U. S.

POSTAGE WILL BE PAID BY —

MANAGER, READER SERVICE DEPARTMENT 11560

MATERIALS IN DESIGN ENGINEERING
430 PARK AVENUE
NEW YORK 22, N. Y.

THIS CARD NOT GOOD AFTER SEPTEMBER 1961 115/60

Name _____ Title _____

Firm _____

Street _____ City _____ Zone _____

State _____

Students and foreign subscribers (other than Canadian), please request literature directly from manufacturers.

| | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 26 | 51 | 76 | 101 | 126 | 151 | 176 | 201 | 226 | 251 | 276 | 301 | 326 | 351 | 376 | 401 | 426 | 451 | 476 | 501 | 526 | 551 | 576 | 601 | 626 | 651 | 676 |
| 2 | 27 | 52 | 77 | 102 | 127 | 152 | 177 | 202 | 227 | 252 | 277 | 302 | 327 | 352 | 377 | 402 | 427 | 452 | 477 | 502 | 527 | 552 | 577 | 602 | 627 | 652 | 677 |
| 3 | 28 | 53 | 78 | 103 | 128 | 153 | 178 | 203 | 228 | 253 | 278 | 303 | 328 | 353 | 378 | 403 | 428 | 453 | 478 | 503 | 528 | 553 | 578 | 603 | 628 | 653 | 678 |
| 4 | 29 | 54 | 79 | 104 | 129 | 154 | 179 | 204 | 229 | 254 | 279 | 304 | 329 | 354 | 379 | 404 | 429 | 454 | 479 | 504 | 529 | 554 | 579 | 604 | 629 | 654 | 679 |
| 5 | 30 | 55 | 80 | 105 | 130 | 155 | 180 | 205 | 230 | 255 | 280 | 305 | 330 | 355 | 380 | 405 | 430 | 455 | 480 | 505 | 530 | 555 | 580 | 605 | 630 | 655 | 680 |
| 6 | 31 | 56 | 81 | 106 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 | 531 | 556 | 581 | 606 | 631 | 656 | 681 |
| 7 | 32 | 57 | 82 | 107 | 132 | 157 | 182 | 207 | 232 | 257 | 282 | 307 | 332 | 357 | 382 | 407 | 432 | 457 | 482 | 507 | 532 | 557 | 582 | 607 | 632 | 657 | 682 |
| 8 | 33 | 58 | 83 | 108 | 133 | 158 | 183 | 208 | 233 | 258 | 283 | 308 | 333 | 358 | 383 | 408 | 433 | 458 | 483 | 508 | 533 | 558 | 583 | 608 | 633 | 658 | 683 |
| 9 | 34 | 59 | 84 | 109 | 134 | 159 | 184 | 209 | 234 | 259 | 284 | 309 | 334 | 359 | 384 | 409 | 434 | 459 | 484 | 509 | 534 | 559 | 584 | 609 | 634 | 659 | 684 |
| 10 | 35 | 60 | 85 | 110 | 135 | 160 | 185 | 210 | 235 | 260 | 285 | 310 | 335 | 360 | 385 | 410 | 435 | 460 | 485 | 510 | 535 | 560 | 585 | 610 | 635 | 660 | 685 |
| 11 | 36 | 61 | 86 | 111 | 136 | 161 | 186 | 211 | 236 | 261 | 286 | 311 | 336 | 361 | 386 | 411 | 436 | 461 | 486 | 511 | 536 | 561 | 586 | 611 | 636 | 661 | 686 |
| 12 | 37 | 62 | 87 | 112 | 137 | 162 | 187 | 212 | 237 | 262 | 287 | 312 | 337 | 362 | 387 | 412 | 437 | 462 | 487 | 512 | 537 | 562 | 587 | 612 | 637 | 662 | 687 |
| 13 | 38 | 63 | 88 | 113 | 138 | 163 | 188 | 213 | 238 | 263 | 288 | 313 | 338 | 363 | 388 | 413 | 438 | 463 | 488 | 513 | 538 | 563 | 588 | 613 | 638 | 663 | 688 |
| 14 | 39 | 64 | 89 | 114 | 139 | 164 | 189 | 214 | 239 | 264 | 289 | 314 | 339 | 364 | 389 | 414 | 439 | 464 | 489 | 514 | 539 | 564 | 589 | 614 | 639 | 664 | 689 |
| 15 | 40 | 65 | 90 | 115 | 140 | 165 | 190 | 215 | 240 | 265 | 290 | 315 | 340 | 365 | 390 | 415 | 440 | 465 | 490 | 515 | 540 | 565 | 590 | 615 | 640 | 665 | 690 |
| 16 | 41 | 66 | 91 | 116 | 141 | 166 | 191 | 216 | 241 | 266 | 291 | 316 | 341 | 366 | 391 | 416 | 441 | 466 | 491 | 516 | 541 | 566 | 591 | 616 | 641 | 666 | 691 |
| 17 | 42 | 67 | 92 | 117 | 142 | 167 | 192 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 | 617 | 642 | 667 | 692 |
| 18 | 43 | 68 | 93 | 118 | 143 | 168 | 193 | 218 | 243 | 268 | 293 | 318 | 343 | 368 | 393 | 418 | 443 | 468 | 493 | 518 | 543 | 568 | 593 | 618 | 643 | 668 | 693 |
| 19 | 44 | 69 | 94 | 119 | 144 | 169 | 194 | 219 | 244 | 269 | 294 | 319 | 344 | 369 | 394 | 419 | 444 | 469 | 494 | 519 | 544 | 569 | 594 | 619 | 644 | 669 | 694 |
| 20 | 45 | 70 | 95 | 120 | 145 | 170 | 195 | 220 | 245 | 270 | 295 | 320 | 345 | 370 | 395 | 420 | 445 | 470 | 495 | 520 | 545 | 570 | 595 | 620 | 645 | 670 | 695 |
| 21 | 46 | 71 | 96 | 121 | 146 | 171 | 196 | 221 | 246 | 271 | 296 | 321 | 346 | 371 | 396 | 421 | 446 | 471 | 496 | 521 | 546 | 571 | 596 | 621 | 646 | 671 | 696 |
| 22 | 47 | 72 | 97 | 122 | 147 | 172 | 197 | 222 | 247 | 272 | 297 | 322 | 347 | 372 | 397 | 422 | 447 | 472 | 497 | 522 | 547 | 572 | 597 | 622 | 647 | 672 | 697 |
| 23 | 48 | 73 | 98 | 123 | 148 | 173 | 198 | 223 | 248 | 273 | 298 | 323 | 348 | 373 | 398 | 423 | 448 | 473 | 498 | 523 | 548 | 573 | 598 | 623 | 648 | 673 | 698 |
| 24 | 49 | 74 | 99 | 124 | 149 | 174 | 199 | 224 | 249 | 274 | 299 | 324 | 349 | 374 | 399 | 424 | 449 | 474 | 499 | 524 | 549 | 574 | 599 | 624 | 649 | 674 | 699 |
| 25 | 50 | 75 | 100 | 125 | 150 | 175 | 200 | 225 | 250 | 275 | 300 | 325 | 350 | 375 | 400 | 425 | 450 | 475 | 500 | 525 | 550 | 575 | 600 | 625 | 650 | 675 | 700 |

I would like to subscribe to Materials in Design Engineering for ☐ 1 year $3.00 ☐ 2 years $5.00

# Reader Service

## Reprints of M/DE Manuals and Special Reports

Here is a convenient way to supplement the standard engineering data in the Materials Selector Issue with objective and more detailed information on the specific materials, forms, finishes, processes or problems in which you are most interested. At the right is a list of the Manuals and Special Reports published by Materials in Design Engineering in recent years for which reprints are still available. To order reprints, simply circle the appropriate key numbers on the card. You will be billed later—35¢ for each reprint unless otherwise indicated.*

* If you prefer to send cash, stamps or check with your order, just put the card in an envelope and mail with remittance.

**THIS CARD NOT GOOD AFTER SEPTEMBER 1961** 115/60

Name _____ Title _____

Firm _____

Street _____ City _____ Zone _____

State _____

Students and foreign subscribers (other than Canadian), please request literature directly from manufacturers.

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 26 | 51 | 76 | 101 | 126 | 151 | 176 | 201 | 226 | 251 | 276 | 301 | 326 | 351 | 376 | 401 | 426 | 451 | 476 | 501 | 526 | 551 | 576 | 601 | 626 | 651 | 676 |
| 2 | 27 | 52 | 77 | 102 | 127 | 152 | 177 | 202 | 227 | 252 | 277 | 302 | 327 | 352 | 377 | 402 | 427 | 452 | 477 | 502 | 527 | 552 | 577 | 602 | 627 | 652 | 677 |
| 3 | 28 | 53 | 78 | 103 | 128 | 153 | 178 | 203 | 228 | 253 | 278 | 303 | 328 | 353 | 378 | 403 | 428 | 453 | 478 | 503 | 528 | 553 | 578 | 603 | 628 | 653 | 678 |
| 4 | 29 | 54 | 79 | 104 | 129 | 154 | 179 | 204 | 229 | 254 | 279 | 304 | 329 | 354 | 379 | 404 | 429 | 454 | 479 | 504 | 529 | 554 | 579 | 604 | 629 | 654 | 679 |
| 5 | 30 | 55 | 80 | 105 | 130 | 155 | 180 | 205 | 230 | 255 | 280 | 305 | 330 | 355 | 380 | 405 | 430 | 455 | 480 | 505 | 530 | 555 | 580 | 605 | 630 | 655 | 680 |
| 6 | 31 | 56 | 81 | 106 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 | 531 | 556 | 581 | 606 | 631 | 656 | 681 |
| 7 | 32 | 57 | 82 | 107 | 132 | 157 | 182 | 207 | 232 | 257 | 282 | 307 | 332 | 357 | 382 | 407 | 432 | 457 | 482 | 507 | 532 | 557 | 582 | 607 | 632 | 657 | 682 |
| 8 | 33 | 58 | 83 | 108 | 133 | 158 | 183 | 208 | 233 | 258 | 283 | 308 | 333 | 358 | 383 | 408 | 433 | 458 | 483 | 508 | 533 | 558 | 583 | 608 | 633 | 658 | 683 |
| 9 | 34 | 59 | 84 | 109 | 134 | 159 | 184 | 209 | 234 | 259 | 284 | 309 | 334 | 359 | 384 | 409 | 434 | 459 | 484 | 509 | 534 | 559 | 584 | 609 | 634 | 659 | 684 |
| 10 | 35 | 60 | 85 | 110 | 135 | 160 | 185 | 210 | 235 | 260 | 285 | 310 | 335 | 360 | 385 | 410 | 435 | 460 | 485 | 510 | 535 | 560 | 585 | 610 | 635 | 660 | 685 |
| 11 | 36 | 61 | 86 | 111 | 136 | 161 | 186 | 211 | 236 | 261 | 286 | 311 | 336 | 361 | 386 | 411 | 436 | 461 | 486 | 511 | 536 | 561 | 586 | 611 | 636 | 661 | 686 |
| 12 | 37 | 62 | 87 | 112 | 137 | 162 | 187 | 212 | 237 | 262 | 287 | 312 | 337 | 362 | 387 | 412 | 437 | 462 | 487 | 512 | 537 | 562 | 587 | 612 | 637 | 662 | 687 |
| 13 | 38 | 63 | 88 | 113 | 138 | 163 | 188 | 213 | 238 | 263 | 288 | 313 | 338 | 363 | 388 | 413 | 438 | 463 | 488 | 513 | 538 | 563 | 588 | 613 | 638 | 663 | 688 |
| 14 | 39 | 64 | 89 | 114 | 139 | 164 | 189 | 214 | 239 | 264 | 289 | 314 | 339 | 364 | 389 | 414 | 439 | 464 | 489 | 514 | 539 | 564 | 589 | 614 | 639 | 664 | 689 |
| 15 | 40 | 65 | 90 | 115 | 140 | 165 | 190 | 215 | 240 | 265 | 290 | 315 | 340 | 365 | 390 | 415 | 440 | 465 | 490 | 515 | 540 | 565 | 590 | 615 | 640 | 665 | 690 |
| 16 | 41 | 66 | 91 | 116 | 141 | 166 | 191 | 216 | 241 | 266 | 291 | 316 | 341 | 366 | 391 | 416 | 441 | 466 | 491 | 516 | 541 | 566 | 591 | 616 | 641 | 666 | 691 |
| 17 | 42 | 67 | 92 | 117 | 142 | 167 | 192 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 | 617 | 642 | 667 | 692 |
| 18 | 43 | 68 | 93 | 118 | 143 | 168 | 193 | 218 | 243 | 268 | 293 | 318 | 343 | 368 | 393 | 418 | 443 | 468 | 493 | 518 | 543 | 568 | 593 | 618 | 643 | 668 | 693 |
| 19 | 44 | 69 | 94 | 119 | 144 | 169 | 194 | 219 | 244 | 269 | 294 | 319 | 344 | 369 | 394 | 419 | 444 | 469 | 494 | 519 | 544 | 569 | 594 | 619 | 644 | 669 | 694 |
| 20 | 45 | 70 | 95 | 120 | 145 | 170 | 195 | 220 | 245 | 270 | 295 | 320 | 345 | 370 | 395 | 420 | 445 | 470 | 495 | 520 | 545 | 570 | 595 | 620 | 645 | 670 | 695 |
| 21 | 46 | 71 | 96 | 121 | 146 | 171 | 196 | 221 | 246 | 271 | 296 | 321 | 346 | 371 | 396 | 421 | 446 | 471 | 496 | 521 | 546 | 571 | 596 | 621 | 646 | 671 | 696 |
| 22 | 47 | 72 | 97 | 122 | 147 | 172 | 197 | 222 | 247 | 272 | 297 | 322 | 347 | 372 | 397 | 422 | 447 | 472 | 497 | 522 | 547 | 572 | 597 | 622 | 647 | 672 | 697 |
| 23 | 48 | 73 | 98 | 123 | 148 | 173 | 198 | 223 | 248 | 273 | 298 | 323 | 348 | 373 | 398 | 423 | 448 | 473 | 498 | 523 | 548 | 573 | 598 | 623 | 648 | 673 | 698 |
| 24 | 49 | 74 | 99 | 124 | 149 | 174 | 199 | 224 | 249 | 274 | 299 | 324 | 349 | 374 | 399 | 424 | 449 | 474 | 499 | 524 | 549 | 574 | 599 | 624 | 649 | 674 | 699 |
| 25 | 50 | 75 | 100 | 125 | 150 | 175 | 200 | 225 | 250 | 275 | 300 | 325 | 350 | 375 | 400 | 425 | 450 | 475 | 500 | 525 | 550 | 575 | 600 | 625 | 650 | 675 | 700 |

I would like to subscribe to Materials in Design Engineering for ☐ 1 year $3.00 ☐ 2 years $5.00

FIRST CLASS
PERMIT NO. 1538
NEW YORK, N. Y.


**BUSINESS REPLY CARD**
**No postage stamp necessary if mailed in the U. S.**

POSTAGE WILL BE PAID BY—

MANAGER, READER SERVICE DEPARTMENT 11560

MATERIALS IN DESIGN ENGINEERING
430 PARK AVENUE
NEW YORK 22, N. Y.

| | Circle Key No. |
|---|---|
| Autos: What Materials Are Next? | 700 |
| Guide to Ferrous Castings | 699 |
| The Challenge of the Materials Age (Price $1.00) | 698 |
| Filament Wound Reinforced Plastics | 697 |
| How Radiation Affects Engrg. Mtls. | 696 |
| Appliances: What Materials Are Next? | 695 |
| Introd. to High Temperature Metals | 694 |
| Why Metals Break | 693 |
| Low Cost Coatings for Metal Products | 692 |
| Low Pressure Reinforced Plastics | 691 |
| The New Welding Processes | 690 |
| Materials for Gaskets, Packings, Seals | 689 |
| Impact Thermoplastics | 688 |
| Die Castings | 687 |
| Adhesive Bonding | 686 |
| Guide to Spring Materials | 685 |
| Guide to Industrial Textiles | 684 |
| Physical Properties and Tests | 683 |
| Designing with Metal Powder Parts | 682 |
| Organic Coatings for Metal Products | 681 |
| Guide to Plastics Selection | 680 |
| How to Select a Stainless Steel | 679 |
| Sheet Formed Plastics Parts | 678 |
| Sleeve Bearing Materials | 677 |
| Designing Metal Stampings | 676 |
| Paper as an Engineering Material | 675 |
| Porcelain Enamels, Ceramic Coatings | 674 |
| Designing with Heat Treated Steels | 673 |
| New Developments in Ceramics | 672 |
| Thermal Insulation Materials | 671 |
| Aluminum Alloy Castings | 670 |
| Joining, Fastening of Plastics | 669 |
| Mechanical Tubing | 668 |
| Materials for Gears | 667 |
| Titanium | 666 |
| Conversion Coatings for Metals | 665 |
| Magnesium and Its Alloys | 664 |
| Fluorocarbon Plastics | 663 |
| Electrical Insulation Materials | 662 |
| Hot Forged Parts | 661 |
| Plastics Laminates for Industrial Use | 660 |
| Hard Coatings, Surfaces for Metals | 659 |
| Nickel Silvers | 658 |
| Gray Iron Castings | 657 |
| Materials for Electrical Contacts | 656 |
| Electroplated Coatings | 655 |
| New Stainless Steels | 654 |
| Wrought Aluminum Alloys | 653 |
| Industrial Textile Fibers | 652 |
| Corrosion | 651 |
| Nodular or Ductile Cast Irons | 650 |
| Finishes for Metal Products | 649 |
| Impact (Cold) Extruded Parts | 648 |
| How to Select a Wrought Steel | 647 |
| Finishes for Plastics | 646 |
| Short Run Press Formed Parts | 645 |
| Wrought Non-Leaded Brasses | 644 |
| Clad and Precoated Metals | 643 |
| Engineering Coppers | 642 |
| Surface Hardening of Irons, Steels | 641 |
| Wood and Wood-Base Materials | 640 |
| Carbon and Low Alloy Castings | 639 |




# EDITORIAL SCOPE

Here are the five basic groups of engineering materials, forms, and finishes used in product design and manufacture. They are specified by M/DE subscribers and readers. The editorial content of M/DE is devoted exclusively to the selection and use of these materials:

## 1 IRONS & STEELS

*for example –*

Carbon steels
Alloy steels
Stainless steels
Tool steels
Heat resistant alloys
Gray, malleable, nodular irons

**Editorial coverage in '59 — 214 pages**

## 2 NONFERROUS METALS

*for example –*

Aluminum
Copper, brass, bronze
Magnesium
Zinc, lead, tin
Nickel
Titanium
Zirconium
Low melting alloys
Noble metals
Rare metals
Cemented carbides

**Editorial coverage in '59 — 282 pages**

## 3 NONMETALLIC MATERIALS

*for example –*

Plastics
Rubbers
Silicones
Vulcanized fibres
Impregnated materials
Wood-base materials
Ceramics
Refractories
Glasses and fiberglass
Carbon and graphite
Industrial felts, fabrics and fibers
Leather
Paper-base materials

**Editorial coverage in '59 — 479 pages**

## 4 FORMS & SHAPES

*for example –*

Sand castings
Die castings
Permanent mold castings
Precision castings
Centrifugal castings
Shell mold castings
Drop and press forgings
Stampings
Headed products
Weldments
Brazed assemblies
Metal powder parts
Extrusions
Spinnings
Wire and wire parts
Screw machine products
Drawn and roll formed parts
Tubing and tubular parts
Molded nonmetallics
Formed nonmetallics

**Editorial coverage in '59 — 368 pages**

## 5 FINISHES & COATINGS

*for example –*

Plated coatings
Clad surfaces
Galvanized, tinned metals
Hard facings
Paints, synthetics, enamels
Anodized finishes
Phosphate coatings
Rustproofing
Chemical coloring
Sprayed metal coatings
Porcelain enamels
Ceramic coatings
Plastic and rubber coatings
Mechanical finishes

**Editorial coverage in '59 — 121 pages**

M/DE brings materials specifiers more information on how and where to use engineering materials than any other engineering or design magazine.

MATERIALS SELECTOR ISSUE




A REINHOLD PUBLICATION

